



# Script syntax and chart functions

Qlik Sense®

May 2024

Copyright © 1993-2025 QlikTech International AB. All rights reserved.



---

<b>1 What is Qlik Sense?</b>	<b>16</b>
1.1 What can you do in Qlik Sense?	16
1.2 How does Qlik Sense work?	16
The app model	16
The associative experience	16
Collaboration and mobility	16
1.3 How can you deploy Qlik Sense?	16
Qlik Sense Desktop	17
Qlik Sense Enterprise	17
1.4 How to administer and manage a Qlik Sense site	17
1.5 Extend Qlik Sense and adapt it for your own purposes	17
Building extensions and mashups	17
Building clients	17
Building server tools	17
Connecting to other data sources	17
<b>2 Script syntax overview</b>	<b>18</b>
2.1 Introduction to script syntax	18
2.2 What is Backus-Naur formalism?	18
<b>3 Script statements and keywords</b>	<b>20</b>
3.1 Script control statements	20
Script control statements overview	20
Call	22
Do..loop	23
End	24
Exit	24
Exit script	24
For..next	25
For each..next	26
If..then..elseif..else..end if	29
Next	30
Sub..end sub	30
Switch..case..default..end switch	32
To	32
3.2 Script prefixes	32
Script prefixes overview	33
Add	37
Buffer	38
Concatenate	40
Crosstable	45
First	55
Generic	57
Hierarchy	63
HierarchyBelongsTo	65
Inner	67
IntervalMatch	68
Join	71
Keep	81

---

Left .....	82
Mapping .....	83
Merge .....	84
NoConcatenate .....	89
Only .....	98
Outer .....	98
Partial reload .....	99
Replace .....	102
Right .....	104
Sample .....	105
Semantic .....	108
Unless .....	112
When .....	118
3.3 Script regular statements .....	124
Script regular statements overview .....	124
Alias .....	130
AutoNumber .....	131
Binary .....	134
Comment field .....	136
Comment table .....	136
Connect .....	137
Declare .....	139
Derive .....	141
Direct Query .....	142
Directory .....	147
Disconnect .....	148
Drop .....	149
Drop table .....	150
Execute .....	151
Field/Fields .....	152
FlushLog .....	152
Force .....	152
From .....	154
Load .....	154
Let .....	174
Loosen Table .....	175
Map .....	175
NullAsNull .....	176
NullAsValue .....	177
Qualify .....	177
Rem .....	178
Rename .....	179
Search .....	181
Section .....	181
Select .....	182
Set .....	184
Sleep .....	185
SQL .....	185

---

SQLColumns .....	186
SQLTables .....	187
SQLTypes .....	187
Star .....	188
Store .....	190
Table/Tables .....	196
Tag .....	196
Trace .....	197
Unmap .....	198
Unqualify .....	198
Untag .....	199
3.4 Working directory .....	200
Qlik Sense Desktop working directory .....	200
Qlik Sense working directory .....	200
<b>4 Working with variables in the data load editor .....</b>	<b>201</b>
4.1 Overview .....	201
4.2 Defining a variable .....	201
4.3 Deleting a variable .....	202
4.4 Loading a variable value as a field value .....	202
4.5 Variable calculation .....	202
4.6 System variables .....	203
System variables overview .....	203
CreateSearchIndexOnReload .....	206
HidePrefix .....	206
HideSuffix .....	207
Include .....	207
OpenUrlTimeout .....	208
StripComments .....	208
Verbatim .....	209
4.7 Value handling variables .....	209
Value handling variables overview .....	209
NullDisplay .....	210
NullInterpret .....	210
NullValue .....	210
OtherSymbol .....	211
4.8 Number interpretation variables .....	211
Currency formatting .....	211
Number formatting .....	212
Time formatting .....	212
BrokenWeeks .....	213
DateFormat .....	215
DayNames .....	221
DecimalSep .....	225
FirstWeekDay .....	228
LongDayNames .....	232
LongMonthNames .....	235
MoneyDecimalSep .....	239

---

MoneyFormat .....	243
MoneyThousandSep .....	247
MonthNames .....	251
NumericalAbbreviation .....	256
ReferenceDay .....	257
ThousandSep .....	261
TimeFormat .....	267
TimestampFormat .....	268
4.9 Direct Discovery variables .....	271
Direct Discovery system variables .....	271
Teradata query banding variables .....	272
Direct Discovery character variables .....	273
Direct Discovery number interpretation variables .....	274
4.10 Error variables .....	275
Error variables overview .....	275
ErrorMode .....	275
ScriptError .....	276
ScriptErrorCount .....	277
ScriptErrorList .....	277
<b>5 Script expressions .....</b>	<b>278</b>
<b>6 Chart expressions .....</b>	<b>279</b>
6.1 Defining the aggregation scope .....	279
6.2 Set analysis .....	282
Set expressions .....	282
Examples .....	283
Natural sets .....	283
Set identifiers .....	286
Set operators .....	287
Set modifiers .....	288
Inner and outer set expressions .....	311
Tutorial - Creating a set expression .....	313
Syntax for set expressions .....	322
6.3 General syntax for chart expressions .....	322
6.4 General syntax for aggregations .....	323
<b>7 Operators .....</b>	<b>324</b>
7.1 Bit operators .....	324
7.2 Logical operators .....	325
7.3 Numeric operators .....	325
7.4 Relational operators .....	326
7.5 String operators .....	328
& .....	328
like .....	328
<b>8 Script and chart functions .....</b>	<b>329</b>
8.1 Analytic connections for server-side extensions (SSE) .....	329
8.2 Aggregation functions .....	329
Using aggregation functions in a data load script .....	330

---

Using aggregation functions in chart expressions .....	330
How aggregations are calculated .....	330
Aggregation of key fields .....	330
Basic aggregation functions .....	331
Counter aggregation functions .....	354
Financial aggregation functions .....	371
Statistical aggregation functions .....	400
Statistical test functions .....	467
String aggregation functions .....	533
Synthetic dimension functions .....	546
Nested aggregations .....	549
8.3 Aggr - chart function .....	549
Examples: Chart expressions using Aggr .....	552
8.4 Color functions .....	555
Pre-defined color functions .....	558
ARGB .....	559
RGB .....	559
HSL .....	561
8.5 Conditional functions .....	562
Conditional functions overview .....	562
alt .....	563
class .....	564
coalesce .....	566
if .....	567
match .....	570
mixmatch .....	574
pick .....	577
wildmatch .....	578
8.6 Counter functions .....	581
Counter functions overview .....	581
autonumber .....	582
autonumberhash128 .....	585
autonumberhash256 .....	587
IterNo .....	589
RecNo .....	590
RowNo .....	591
RowNo - chart function .....	592
8.7 Date and time functions .....	594
Date and time functions overview .....	595
addmonths .....	603
addyears .....	613
age .....	620
converttolocaltime .....	622
day .....	626
dayend .....	632
daylightsaving .....	640
dayname .....	641
daynumberofquarter .....	643

## Contents

---

daynumberofyear .....	649
daystart .....	655
firstworkdate .....	663
GMT .....	664
hour .....	668
inday .....	672
indaytotime .....	680
inlunarweek .....	690
inlunarweektodate .....	702
inmonth .....	713
inmonths .....	721
inmonthstodate .....	735
inmonthtodate .....	748
inquarter .....	758
inquartertodate .....	771
inweek .....	784
inweektodate .....	800
inyear .....	814
inyeartodate .....	827
lastworkdate .....	839
localtime .....	849
lunarweekend .....	853
lunarweekname .....	865
lunarweekstart .....	877
makedate .....	889
maketime .....	896
makeweekdate .....	903
minute .....	911
month .....	917
monthend .....	923
monthname .....	932
monthsend .....	940
monthsname .....	953
monthsstart .....	966
monthstart .....	979
networkdays .....	989
now .....	999
quarterend .....	1006
quartername .....	1019
quarterstart .....	1031
second .....	1043
setdateyear .....	1048
setdateyearmonth .....	1050
timezone .....	1052
today .....	1052
UTC .....	1058
week .....	1058
weekday .....	1074



## Contents

---

weekend .....	1083
weekname .....	1095
weekstart .....	1110
weekyear .....	1122
year .....	1132
yearend .....	1138
yearname .....	1150
yearstart .....	1163
yeartodate .....	1175
8.8 Exponential and logarithmic functions .....	1190
8.9 Field functions .....	1191
Count functions .....	1192
Field and selection functions .....	1192
GetAlternativeCount - chart function .....	1193
GetCurrentSelections - chart function .....	1194
GetExcludedCount - chart function .....	1196
GetFieldSelections - chart function .....	1197
GetNotSelectedCount - chart function .....	1199
GetObjectDimension - chart function .....	1200
GetObjectField - chart function .....	1200
GetObjectMeasure - chart function .....	1201
GetPossibleCount - chart function .....	1202
GetSelectedCount - chart function .....	1203
8.10 File functions .....	1205
File functions overview .....	1205
Attribute .....	1207
ConnectString .....	1215
FileName .....	1215
FileDir .....	1215
FileExtension .....	1216
FilePath .....	1216
FileSize .....	1217
FileTime .....	1218
GetFolderPath .....	1218
QvdCreateTime .....	1219
QvdFieldName .....	1220
QvdNoOfFields .....	1221
QvdNoOfRecords .....	1222
QvdTableName .....	1223
8.11 Financial functions .....	1224
Financial functions overview .....	1225
BlackAndSchole .....	1225
FV .....	1226
nPer .....	1227
Pmt .....	1228
PV .....	1229
Rate .....	1230

---

8.12 Formatting functions .....	1231
Formatting functions overview .....	1231
ApplyCodepage .....	1232
Date .....	1233
Dual .....	1235
Interval .....	1236
Money .....	1237
Num .....	1239
Time .....	1241
Timestamp .....	1243
8.13 General numeric functions .....	1244
General numeric functions overview .....	1244
Combination and permutation functions .....	1245
Modulo functions .....	1245
Parity functions .....	1245
Rounding functions .....	1246
BitCount .....	1246
Ceil .....	1246
Combin .....	1248
Div .....	1248
Even .....	1249
Fabs .....	1249
Fact .....	1249
Floor .....	1250
Fmod .....	1251
Frac .....	1252
Mod .....	1253
Odd .....	1253
Permut .....	1254
Round .....	1254
Sign .....	1256
8.14 Geospatial functions .....	1256
Geospatial functions overview .....	1257
GeoAggrGeometry .....	1258
GeoBoundingBox .....	1259
GeoCountVertex .....	1260
GeoGetBoundingBox .....	1260
GeoGetPolygonCenter .....	1261
GeoInvProjectGeometry .....	1261
GeoMakePoint .....	1262
GeoProject .....	1263
GeoProjectGeometry .....	1263
GeoReduceGeometry .....	1264
8.15 Interpretation functions .....	1265
Interpretation functions overview .....	1266
Date# .....	1267
Interval# .....	1268
Money# .....	1269

---

Num# .....	1270
Text .....	1271
Time# .....	1271
Timestamp# .....	1272
8.16 Inter-record functions .....	1273
Row functions .....	1274
Column functions .....	1275
Field functions .....	1275
Pivot table functions .....	1275
Inter-record functions in the data load script .....	1276
Above - chart function .....	1277
Below - chart function .....	1282
Bottom - chart function .....	1285
Column - chart function .....	1290
Dimensionality - chart function .....	1292
Exists .....	1293
FieldIndex .....	1297
FieldValue .....	1299
FieldValueCount .....	1300
LookUp .....	1302
NoOfRows - chart function .....	1304
Peek .....	1306
Previous .....	1313
Top - chart function .....	1315
SecondaryDimensionality - chart function .....	1319
After - chart function .....	1319
Before - chart function .....	1320
First - chart function .....	1322
Last - chart function .....	1323
ColumnNo - chart function .....	1324
NoOfColumns - chart function .....	1324
8.17 Logical functions .....	1325
8.18 Mapping functions .....	1326
Mapping functions overview .....	1326
ApplyMap .....	1326
MapSubstring .....	1328
8.19 Mathematical functions .....	1330
8.20 NULL functions .....	1331
NULL functions overview .....	1331
EmptyIsNull .....	1331
IsNull .....	1332
NULL .....	1333
8.21 Range functions .....	1334
Basic range functions .....	1334
Counter range functions .....	1335
Statistical range functions .....	1335
Financial range functions .....	1336
RangeAvg .....	1337

---

---

RangeCorrel	1339
RangeCount	1341
RangeFractile	1343
RangeIRR	1345
RangeKurtosis	1346
RangeMax	1347
RangeMaxString	1349
RangeMin	1351
RangeMinString	1353
RangeMissingCount	1354
RangeMode	1356
RangeNPV	1358
RangeNullCount	1359
RangeNumericCount	1360
RangeOnly	1362
RangeSkew	1363
RangeStdev	1364
RangeSum	1365
RangeTextCount	1368
RangeXIRR	1369
RangeXNPV	1371
8.22 Relational functions	1373
Ranking functions	1373
Clustering functions	1374
Time series decomposition functions	1375
Rank - chart function	1376
HRank - chart function	1380
Optimizing with k-means: A real-world example	1382
KMeans2D - chart function	1391
KMeansND - chart function	1406
KMeansCentroid2D - chart function	1421
KMeansCentroidND - chart function	1422
STL_Trend - chart function	1423
STL_Seasonal - chart function	1425
STL_Residual - chart function	1427
Tutorial - Time series decomposition in Qlik Sense	1429
8.23 Statistical distribution functions	1434
Statistical distribution functions overview	1434
BetaDensity	1437
BetaDist	1437
BetaInv	1437
BinomDist	1438
BinomFrequency	1438
BinomInv	1439
ChiDensity	1439
ChiDist	1440
ChiInv	1440
FDensity	1441

---

FDist .....	1441
FInv .....	1442
GammaDensity .....	1443
GammaDist .....	1443
Gammalnv .....	1444
NormDist .....	1444
Normlnv .....	1445
PoissonDist .....	1446
PoissonFrequency .....	1446
Poissonlnv .....	1447
TDensity .....	1447
TDist .....	1447
Tlnv .....	1448
8.24 String functions .....	1449
String functions overview .....	1449
Capitalize .....	1452
Chr .....	1453
Evaluate .....	1454
FindOneOf .....	1454
Hash128 .....	1456
Hash160 .....	1456
Hash256 .....	1457
Index .....	1458
IsJson .....	1460
JsonGet .....	1461
JsonSet .....	1462
KeepChar .....	1462
Left .....	1464
Len .....	1464
LevenshteinDist .....	1465
Lower .....	1467
LTrim .....	1468
Mid .....	1469
Ord .....	1470
PurgeChar .....	1471
Repeat .....	1472
Replace .....	1473
Right .....	1473
RTrim .....	1474
SubField .....	1475
SubStringCount .....	1479
TextBetween .....	1480
Trim .....	1481
Upper .....	1482
8.25 System functions .....	1482
System functions overview .....	1482
EngineVersion .....	1485
GetSysAttr .....	1486

---

InObject - chart function .....	1486
IsPartialReload .....	1490
ObjectId - chart function .....	1490
ProductVersion .....	1493
StateName - chart function .....	1494
8.26 Table functions .....	1494
Table functions overview .....	1494
FieldName .....	1496
FieldNumber .....	1497
NoOfFields .....	1497
NoOfRows .....	1498
8.27 Trigonometric and hyperbolic functions .....	1498
8.28 Window functions .....	1500
Window - script function .....	1501
WRank - script function .....	1509
<b>9 File system access restriction .....</b>	<b>1516</b>
9.1 Security aspects when connecting to file based ODBC and OLE DB data connections .....	1516
9.2 Limitations in standard mode .....	1516
System variables .....	1516
Regular script statements .....	1518
Script control statements .....	1519
File functions .....	1520
System functions .....	1522
9.3 Disabling standard mode .....	1522
Qlik Sense .....	1522
Qlik Sense Desktop .....	1522
<b>10 Chart level scripting .....</b>	<b>1524</b>
10.1 Control statements .....	1524
Chart modifier control statements overview .....	1524
Call .....	1526
Do..loop .....	1527
End .....	1527
Exit .....	1528
Exit script .....	1528
For..next .....	1528
For each..next .....	1529
If..then..elseif..else..end if .....	1532
Next .....	1533
Sub..end sub .....	1533
Switch..case..default..end switch .....	1535
To .....	1535
10.2 Prefixes .....	1535
Chart modifier prefixes overview .....	1536
Add .....	1536
Replace .....	1536
10.3 Regular statements .....	1537

---

Chart modifier regular statements overview .....	1537
Load .....	1538
Let .....	1542
Set .....	1543
Put .....	1543
HCValue .....	1544
<b>11 QlikView functions and statements not supported in Qlik Sense .....</b>	<b>1546</b>
11.1 Script statements not supported in Qlik Sense .....	1546
11.2 Functions not supported in Qlik Sense .....	1546
11.3 Prefixes not supported in Qlik Sense .....	1546
<b>12 Functions and statements not recommended in Qlik Sense .....</b>	<b>1547</b>
12.1 Script statements not recommended in Qlik Sense .....	1547
12.2 Script statement parameters not recommended in Qlik Sense .....	1547
12.3 Functions not recommended in Qlik Sense .....	1548
ALL qualifier .....	1549

# 1 What is Qlik Sense?

Qlik Sense is a platform for data analysis. With Qlik Sense you can analyze data and make data discoveries on your own. You can share knowledge and analyze data in groups and across organizations. Qlik Sense lets you ask and answer your own questions and follow your own paths to insight. Qlik Sense enables you and your colleagues to reach decisions collaboratively.

## 1.1 What can you do in Qlik Sense?

Most Business Intelligence (BI) products can help you answer questions that are understood in advance. But what about your follow-up questions? The ones that come after someone reads your report or sees your visualization? With the Qlik Sense associative experience, you can answer question after question after question, moving along your own path to insight. With Qlik Sense you can explore your data freely, with just clicks, learning at each step along the way and coming up with next steps based on earlier findings.

## 1.2 How does Qlik Sense work?

Qlik Sense generates views of information on the fly for you. Qlik Sense does not require predefined and static reports or you being dependent on other users – you just click and learn. Every time you click, Qlik Sense instantly responds, updating every Qlik Sense visualization and view in the app with a newly calculated set of data and visualizations specific to your selections.

### The app model

Instead of deploying and managing huge business applications, you can create your own Qlik Sense apps that you can reuse, modify and share with others. The app model helps you ask and answer the next question on your own, without having to go back to an expert for a new report or visualization.

### The associative experience

Qlik Sense automatically manages all the relationships in the data and presents information to you using a **green/white/gray** metaphor. Selections are highlighted in green, associated data is represented in white, and excluded (unassociated) data appears in gray. This instant feedback enables you to think of new questions and continue to explore and discover.

### Collaboration and mobility

Qlik Sense further enables you to collaborate with colleagues no matter when and where they are located. All Qlik Sense capabilities, including the associative experience and collaboration, are available on mobile devices. With Qlik Sense, you can ask and answer your questions and follow-up questions, with your colleagues, wherever you are.

## 1.3 How can you deploy Qlik Sense?

There are two versions of Qlik Sense to deploy, Qlik Sense Desktop and Qlik Sense Enterprise.



## Qlik Sense Desktop

This is an easy-to-install single user version that is typically installed on a local computer.

## Qlik Sense Enterprise

This version is used to deploy Qlik Sense sites. A site is a collection of one or more server machines connected to a common logical repository or central node.

## 1.4 How to administer and manage a Qlik Sense site

With the Qlik Management Console you can configure, manage and monitor Qlik Sense sites in an easy and intuitive way. You can manage licenses, access and security rules, configure nodes and data source connections and synchronize content and users among many other activities and resources.

## 1.5 Extend Qlik Sense and adapt it for your own purposes

Qlik Sense provides you with flexible APIs and SDKs to develop your own extensions and adapt and integrate Qlik Sense for different purposes, such as:

### Building extensions and mashups

Here you can do web development using JavaScript to build extensions that are custom visualization in Qlik Sense apps, or you use a mashups APIs to build websites with Qlik Sense content.

### Building clients

You can build clients in .NET and embed Qlik Sense objects in your own applications. You can also build native clients in any programming language that can handle WebSocket communication by using the Qlik Sense client protocol.

### Building server tools

With service and user directory APIs you can build your own tool to administer and manage Qlik Sense sites.

### Connecting to other data sources

Create Qlik Sense connectors to retrieve data from custom data sources.

## 2 Script syntax overview

### 2.1 Introduction to script syntax

In a script, the name of the data source, the names of the tables, and the names of the fields included in the logic are defined. Furthermore, the fields in the access rights definition are defined in the script. A script consists of a number of statements that are executed consecutively.

The Qlik Sense command line syntax and script syntax are described in a notation called Backus-Naur Formalism, or BNF code.

The first lines of code are already generated when a new Qlik Sense file is created. The default values of these number interpretation variables are derived from the regional settings of the OS.

The script consists of a number of script statements and keywords that are executed consecutively. All script statements must end with a semicolon, ";".

You can use expressions and functions in the **LOAD**-statements to transform the data that has been loaded.

For a table file with commas, tabs or semicolons as delimiters, a **LOAD**-statement may be used. By default a **LOAD**-statement will load all fields of the file.

General databases can be accessed through ODBC or OLE DBdatabase connectors. Here standard SQL statements are used. The SQL syntax accepted differs between different ODBC drivers.

Additionally, you can access other data sources using custom connectors.

### 2.2 What is Backus-Naur formalism?

The Qlik Sense command line syntax and script syntax are described in a notation called Backus-Naur formalism, also known as BNF code.

The following table provides a list of symbols used in BNF code, with a description of how they are interpreted:

Symbols

Symbol	Description
	Logical OR: the symbol on either side can be used.
()	Parentheses defining precedence: used for structuring the BNF syntax.
[]	Square brackets: enclosed items are optional.
{ }	Braces: enclosed items may be repeated zero or more times.

Symbol	Description
Symbol	A non-terminal syntactic category, that: can be divided further into other symbols. For example, compounds of the above, other non-terminal symbols, text strings, and so on.
::=	Marks the beginning of a block that defines a symbol.
<b>LOAD</b>	A terminal symbol consisting of a text string. Should be written as it is into the script.

All terminal symbols are printed in a **bold face** font. For example, "(" should be interpreted as a parenthesis defining precedence, whereas "((" should be interpreted as a character to be printed in the script.

### Example:

The description of the alias statement is:

```
alias fieldname as aliasname { , fieldname as aliasname }
```

This should be interpreted as the text string "alias", followed by an arbitrary field name, followed by the text string "as", followed by an arbitrary alias name. Any number of additional combinations of "fieldname as alias" may be given, separated by commas.

The following statements are correct:

```
alias a as first;  
alias a as first, b as second;  
alias a as first, b as second, c as third;
```

The following statements are not correct:

```
alias a as first b as second;  
alias a as first { , b as second };
```

### 3 Script statements and keywords

The Qlik Sense script consists of a number of statements. A statement can be either a regular script statement or a script control statement. Certain statements can be preceded by prefixes.

Regular statements are typically used for manipulating data in one way or another. These statements may be written over any number of lines in the script and must always be terminated by a semicolon, ";".

Control statements are typically used for controlling the flow of the script execution. Each clause of a control statement must be kept inside one script line and may be terminated by a semicolon or the end-of-line.

Prefixes may be applied to applicable regular statements but never to control statements. The **when** and **unless** prefixes can however be used as suffixes to a few specific control statement clauses.

In the next subchapter, an alphabetical listing of all script statements, control statements and prefixes, are found.

All script keywords can be typed with any combination of lower case and upper case characters. Field and variable names used in the statements are however case sensitive.

#### 3.1 Script control statements

The Qlik Sense script consists of a number of statements. A statement can be either a regular script statement or a script control statement.

Control statements are typically used for controlling the flow of the script execution. Each clause of a control statement must be kept inside one script line and may be terminated by semicolon or end-of-line.

Prefixes are never applied to control statements, with the exceptions of the prefixes **when** and **unless** which may be used with a few specific control statements.

All script keywords can be typed with any combination of lower case and upper case characters.

#### Script control statements overview

Each function is described further after the overview. You can also click the function name in the syntax to immediately access the details for that specific function.

##### Call

The **call** control statement calls a subroutine which must be defined by a previous **sub** statement.

```
Call name ( [ paramlist ])
```

## 3 Script statements and keywords

---

### Do..loop

The **do..loop** control statement is a script iteration construct which executes one or several statements until a logical condition is met.

```
Do..loop [ ( while | until ) condition ] [statements]
[exit do [ ( when | unless ) condition ] [statements]
loop [ ( while | until ) condition ]
```

### Exit script

This control statement stops script execution. It may be inserted anywhere in the script.

```
Exit script [ (when | unless) condition ]
```

### For each ..next

The **for each..next** control statement is a script iteration construct which executes one or several statements for each value in a comma separated list. The statements inside the loop enclosed by **for** and **next** will be executed for each value of the list.

```
For each..next var in list
[statements]
[exit for [ ( when | unless ) condition ]
[statements]
next [var]
```

### For..next

The **for..next** control statement is a script iteration construct with a counter. The statements inside the loop enclosed by **for** and **next** will be executed for each value of the counter variable between specified low and high limits.

```
For..next counter = expr1 to expr2 [ stepexpr3 ]
[statements]
[exit for [ ( when | unless ) condition ]
[statements]
Next [counter]
```

### If..then

The **if..then** control statement is a script selection construct forcing the script execution to follow different paths depending on one or several logical conditions.



*Since the **if..then** statement is a control statement and as such is ended with either a semicolon or end-of-line, each of its four possible clauses (**if..then**, **elseif..then**, **else** and **end if**) must not cross a line boundary.*

```
If..then..elseif..else..end if condition then
[ statements ]
{ elseif condition then
[ statements ] }
[ else
[ statements ] ]
```

```
end if
```

### Sub

The **sub..end sub** control statement defines a subroutine which can be called upon from a **call** statement.

```
Sub..end sub name [ ( paramlist ) ] statements end sub
```

### Switch

The **switch** control statement is a script selection construct forcing the script execution to follow different paths, depending on the value of an expression.

```
Switch..case..default..end switch expression {case valuelist [ statements ]}  
[default statements] end switch
```

## Call

The **call** control statement calls a subroutine which must be defined by a previous **sub** statement.

### Syntax:

```
Call name ( [ paramlist ] )
```

### Arguments:

Arguments

Argument	Description
name	The name of the subroutine.
paramlist	A comma separated list of the actual parameters to be sent to the subroutine. Each item in the list may be a field name, a variable, or an arbitrary expression.

The subroutine called by a **call** statement must be defined by a **sub** encountered earlier during script execution.

Parameters are copied into the subroutine and, if the parameter in the **call** statement is a variable and not an expression, copied back out again upon exiting the subroutine.

### Limitations:

- Since the **call** statement is a control statement and as such is ended with either a semicolon or end-of-line, it must not cross a line boundary.
- When you define a subroutine with `sub..end sub` inside a control statement, for example `if..then`, you can only call the subroutine from within the same control statement.

### Example:

This example lists all Qlik related files in a folder and its subfolders, and stores file information in a table. It is assumed that you have created a data connection named Apps to the folder .

The DoDir subroutine is called with the reference to the folder, 'lib://Apps', as parameter. Inside the subroutine, there is a recursive call, call DoDir (Dir), that makes the function look for files recursively in subfolders.

```
sub DoDir (Root)
  For Each Ext in 'qvw', 'qvo', 'qvs', 'qvt', 'qvd', 'qvc', 'qvf'
    For Each File in filelist (Root&'\'*' &Ext)
      LOAD
        '$(File)' as Name,
        FileSize( '$(File)' ) as Size,
        FileTime( '$(File)' ) as FileTime
      autogenerate 1;
    Next File
  Next Ext
  For Each Dir in dirlist (Root&'\'*' )
    call DoDir (Dir)
  Next Dir
End Sub

call DoDir ('lib://Apps')
```

### Do..loop

The **do..loop** control statement is a script iteration construct which executes one or several statements until a logical condition is met.

#### Syntax:

```
Do [ ( while | until ) condition ] [statements]
[exit do [ ( when | unless ) condition ] [statements]
loop[ ( while | until ) condition ]
```



Since the **do..loop** statement is a control statement and as such is ended with either a semicolon or end-of-line, each of its three possible clauses (**do**, **exit do** and **loop**) must not cross a line boundary.

#### Arguments:

##### Arguments

Argument	Description
condition	A logical expression evaluating to True or False.
statements	Any group of one or more Qlik Sense script statements.

## 3 Script statements and keywords

Argument	Description
while / until	The <b>while</b> or <b>until</b> conditional clause must only appear once in any <b>do..loop</b> statement, i.e. either after <b>do</b> or after <b>loop</b> . Each condition is interpreted only the first time it is encountered but is evaluated for every time it encountered in the loop.
exit do	If an <b>exit do</b> clause is encountered inside the loop, the execution of the script will be transferred to the first statement after the <b>loop</b> clause denoting the end of the loop. An <b>exit do</b> clause can be made conditional by the optional use of a <b>when</b> or <b>unless</b> suffix.

### Example:

```
// LOAD files file1.csv..file9.csv
Set a=1;
Do while a<10
LOAD * from file$(a).csv;
Let a=a+1;
Loop
```

## End

The **End** script keyword is used to close **If**, **Sub** and **Switch** clauses.

## Exit

The **Exit** script keyword is part of the **Exit Script** statement, but can also be used to exit **Do**, **For** or **Sub** clauses.

## Exit script

This control statement stops script execution. It may be inserted anywhere in the script.

### Syntax:

```
Exit Script [ (when | unless) condition ]
```

Since the **exit script** statement is a control statement and as such is ended with either a semicolon or end-of-line, it must not cross a line boundary.

### Arguments:

#### Arguments

Argument	Description
condition	A logical expression evaluating to True or False.
when / unless	An <b>exit script</b> statement can be made conditional by the optional use of <b>when</b> or <b>unless</b> clause.



### Examples:

```
//Exit script
Exit Script;

//Exit script when a condition is fulfilled
Exit Script when a=1
```

### For..next

The **for..next** control statement is a script iteration construct with a counter. The statements inside the loop enclosed by **for** and **next** will be executed for each value of the counter variable between specified low and high limits.

#### Syntax:

```
For counter = expr1 to expr2 [ step expr3 ]
[statements]
[exit for [ ( when | unless ) condition ]
[statements]
Next [counter]
```

The expressions *expr1*, *expr2* and *expr3* are only evaluated the first time the loop is entered. The value of the counter variable may be changed by statements inside the loop, but this is not good programming practice.

If an **exit for** clause is encountered inside the loop, the execution of the script will be transferred to the first statement after the **next** clause denoting the end of the loop. An **exit for** clause can be made conditional by the optional use of a **when** or **unless** suffix.



Since the **for..next** statement is a control statement and as such is ended with either a semicolon or end-of-line, each of its three possible clauses (**for..to..step**, **exit for** and **next**) must not cross a line boundary.

#### Arguments:

##### Arguments

Argument	Description
counter	A variable name. If <i>counter</i> is specified after <b>next</b> it must be the same variable name as the one found after the corresponding <b>for</b> .
expr1	An expression which determines the first value of the <i>counter</i> variable for which the loop should be executed.

## 3 Script statements and keywords

---

Argument	Description
expr2	An expression which determines the last value of the <i>counter</i> variable for which the loop should be executed.
expr3	An expression which determines the value indicating the increment of the <i>counter</i> variable each time the loop has been executed.
condition	a logical expression evaluating to True or False.
statements	Any group of one or more Qlik Sense script statements.

### Example 1: Loading a sequence of files

```
// LOAD files file1.csv..file9.csv
for a=1 to 9
    LOAD * from file$(a).csv;
next
```

### Example 2: Loading a random number of files

In this example, we assume there are data files *x1.csv*, *x3.csv*, *x5.csv*, *x7.csv* and *x9.csv*. Loading is stopped at a random point using the `if rand( )<0.5 then` condition.

```
for counter=1 to 9 step 2
    set filename=x$(counter).csv;
    if rand( )<0.5 then
        exit for unless counter=1
    end if
    LOAD a,b from $(filename);
next
```

## For each..next

The **for each..next** control statement is a script iteration construct which executes one or several statements for each value in a comma separated list. The statements inside the loop enclosed by **for** and **next** will be executed for each value of the list.

### Syntax:

Special syntax makes it possible to generate lists with file and directory names in the current directory.

```
for each var in list
[statements]
exit for [ ( when | unless ) condition ]
[statements]
next [var]
```

## 3 Script statements and keywords

### Arguments:

#### Arguments

Argument	Description
var	A script variable sname which will acquire a new value from list for each loop execution. If <b>var</b> is specified after <b>next</b> it must be the same variable name as the one found after the corresponding <b>for each</b> .

The value of the **var** variable may be changed by statements inside the loop, but this is not good programming practice.

If an **exit for** clause is encountered inside the loop, the execution of the script will be transferred to the first statement after the **next** clause denoting the end of the loop. An **exit for** clause can be made conditional by the optional use of a **when** or **unless** suffix.



*Since the **for each..next** statement is a control statement and as such is ended with either a semicolon or end-of-line, each of its three possible clauses (**for each**, **exit for** and **next**) must not cross a line boundary.*



### Syntax:

```
list := item { , item }  
item := constant | (expression) | filelist mask | dirlist mask |  
fieldvaluelist mask
```

#### Arguments

Argument	Description
constant	Any number or string. Note that a string written directly in the script must be enclosed by single quotes. A string without single quotes will be interpreted as a variable, and the value of the variable will be used. Numbers do not need to be enclosed by single quotes.
expression	An arbitrary expression.
mask	A filename or folder name mask which may include any valid filename characters as well as the standard wildcard characters, * and ?.  You can use absolute file paths or lib:// paths.
condition	A logical expression evaluating to True or False.
statements	Any group of one or more Qlik Sense script statements.

## 3 Script statements and keywords

Argument	Description
filelist mask	This syntax produces a comma separated list of all files in the current directory matching the filename mask. <div style="border: 1px solid #ccc; padding: 5px; margin-top: 10px;"> <i>This argument supports only library connections in standard mode.</i></div>
dirlist mask	This syntax produces a comma separated list of all folders in the current folder matching the folder name mask. <div style="border: 1px solid #ccc; padding: 5px; margin-top: 10px;"> <i>This argument supports only library connections in standard mode.</i></div>
fieldvaluelist mask	This syntax iterates through the values of a field already loaded into Qlik Sense.



*The Qlik Web Storage Provider Connectors and other DataFiles connections do not support filter masks that use wildcard (\* and ?) characters.*

### Example 1: Loading a list of files

```
// LOAD the files 1.csv, 3.csv, 7.csv and xyz.csv
for each a in 1,3,7,'xyz'
  LOAD * from file$(a).csv;
next
```

### Example 2: Creating a list of files on disk

This example loads a list of all Qlik Sense related files in a folder.

```
sub DoDir (Root)
  for each Ext in 'qvw', 'qva', 'qvo', 'qvs', 'qvc', 'qvf', 'qvd'

    for each File in filelist (Root&'/*.' &Ext)

      LOAD
        '$(File)' as Name,
        FileSize( '$(File)' ) as Size,
        FileTime( '$(File)' ) as FileTime
      autogenerate 1;

    next File

  next Ext
  for each Dir in dirlist (Root&'/*' )

    call DoDir (Dir)

  next Dir
```

```
end sub
```

```
call DoDir ('lib://DataFiles')
```

### Example 3: Iterating through a the values of a field

This example iterates through the list of loaded values of FIELD and generates a new field, NEWFIELD. For each value of FIELD, two NEWFIELD records will be created.

```
Load * inline [  
FIELD  
one  
two  
three  
];
```

```
FOR Each a in FieldValueList('FIELD')  
LOAD '$(a)' &'-'&RecNo() as NEWFIELD AutoGenerate 2;  
NEXT a
```

The resulting table looks like this:

Example table

NEWFIELD
one-1
one-2
two-1
two-2
three-1
three-2

### If..then..elseif..else..end if

The **if..then** control statement is a script selection construct forcing the script execution to follow different paths depending on one or several logical conditions.

Control statements are typically used to control the flow of the script execution. In a chart expression, use the **if** conditional function instead.

#### Syntax:

```
If condition then  
  [ statements ]  
{ elseif condition then  
  [ statements ] }  
[ else  
  [ statements ] ]  
end if
```

## 3 Script statements and keywords

---

Since the **if..then** statement is a control statement and as such is ended with either a semicolon or end-of-line, each of its four possible clauses (**if..then**, **elseif..then**, **else** and **end if**) must not cross a line boundary.

### Arguments:

#### Arguments

Argument	Description
condition	A logical expression which can be evaluated as True or False.
statements	Any group of one or more Qlik Sense script statements.

### Example 1:

```
if a=1 then
    LOAD * from abc.csv;
    SQL SELECT e, f, g from tab1;
end if
```

### Example 2:

```
if a=1 then; drop table xyz; end if;
```

### Example 3:

```
if x>0 then
    LOAD * from pos.csv;
elseif x<0 then
    LOAD * from neg.csv;
else
    LOAD * from zero.txt;
end if
```

## Next

The **Next** script keyword is used to close **For** loops.

## Sub..end sub

The **sub..end sub** control statement defines a subroutine which can be called upon from a **call** statement.

### Syntax:

```
Sub name [ ( paramlist ) ] statements end sub
```

---

## 3 Script statements and keywords

---

Arguments are copied into the subroutine and, if the corresponding actual parameter in the **call** statement is a variable name, copied back out again upon exiting the subroutine.

If a subroutine has more formal parameters than actual parameters passed by a **call** statement, the extra parameters will be initialized to NULL and can be used as local variables within the subroutine.

### Arguments:

Arguments

Argument	Description
name	The name of the subroutine.
paramlist	A comma separated list of variable names for the formal parameters of the subroutine. These can be used as any variable inside the subroutine.
statements	Any group of one or more Qlik Sense script statements.

### Limitations:

- Since the **sub** statement is a control statement and as such is ended with either a semicolon or end-of-line, each of its two clauses (**sub** and **end sub**) must not cross a line boundary.
- When you define a subroutine with `sub..end sub` inside a control statement, for example `if..then`, you can only call the subroutine from within the same control statement.

### Example 1:

```
Sub INCR (I,J)
I = I + 1
Exit Sub when I < 10
J = J + 1
End Sub
Call INCR (X,Y)
```

### Example 2: - parameter transfer

```
Sub ParTrans (A,B,C)
A=A+1
B=B+1
C=C+1
End Sub
A=1
X=1
C=1
Call ParTrans (A, (X+1)*2)
```

The result of the above will be that locally, inside the subroutine, A will be initialized to 1, B will be initialized to 4 and C will be initialized to NULL.

When exiting the subroutine, the global variable A will get 2 as value (copied back from subroutine). The second actual parameter "(X+1)\*2" will not be copied back since it is not a variable. Finally, the global variable C will not be affected by the subroutine call.

### Switch..case..default..end switch

The **switch** control statement is a script selection construct forcing the script execution to follow different paths, depending on the value of an expression.

#### Syntax:

```
Switch expression {case valuelist [ statements ]} [default statements] end switch
```



Since the **switch** statement is a control statement and as such is ended with either a semicolon or end-of-line, each of its four possible clauses (**switch**, **case**, **default** and **end switch**) must not cross a line boundary.

#### Arguments:

##### Arguments

Argument	Description
expression	An arbitrary expression.
valuelist	A comma separated list of values with which the value of expression will be compared. Execution of the script will continue with the statements in the first group encountered with a value in valuelist equal to the value in expression. Each value in valuelist may be an arbitrary expression. If no match is found in any <b>case</b> clause, the statements under the <b>default</b> clause, if specified, will be executed.
statements	Any group of one or more Qlik Sense script statements.

#### Example:

```
Switch I  
Case 1  
LOAD '$(I): CASE 1' as case autogenerate 1;  
Case 2  
LOAD '$(I): CASE 2' as case autogenerate 1;  
Default  
LOAD '$(I): DEFAULT' as case autogenerate 1;  
End Switch
```

### To

The **To** script keyword is used in several script statements.

## 3.2 Script prefixes

Prefixes may be applied to applicable regular statements but never to control statements. The **when** and **unless** prefixes can however be used as suffixes to a few specific control statement clauses.



---

## 3 Script statements and keywords

All script keywords can be typed with any combination of lower case and upper case characters. Field and variable names used in the statements are however case sensitive.

### Script prefixes overview

Each function is described further after the overview. You can also click the function name in the syntax to immediately access the details for that specific function.

#### Add

The **Add** prefix can be added to any **LOAD** or **SELECT** statement in the script to specify that it should add records to another table. It also specifies that this statement should be run in a partial reload. The **Add** prefix can also be used in a **Map** statement.

```
Add [only] [Concatenate[(tablename )]] (loadstatement | selectstatement)
Add [ Only ] mapstatement
```

#### Buffer

QVD files can be created and maintained automatically via the **buffer** prefix. This prefix can be used on most **LOAD** and **SELECT** statements in script. It indicates that QVD files are used to cache/buffer the result of the statement.

```
Buffer[(option [ , option])] ( loadstatement | selectstatement )
option::= incremental | stale [after] amount [(days | hours)]
```

#### Concatenate

If two tables that are to be concatenated have different sets of fields, concatenation of two tables can still be forced with the **Concatenate** prefix.

```
Concatenate [ (tablename ) ] ( loadstatement | selectstatement )
```

#### Crosstable

The **crosstable** load prefix is used to transpose “cross table” or “pivot table” structured data. Data structured this way is commonly encountered when working with spreadsheet sources. The output and aim of the **crosstable** load prefix is to transpose such structures into a regular column-oriented table equivalent, as this structure is generally better suited for analysis in Qlik Sense.

```
Crosstable (attribute field name, data field name [ , n ] ) ( loadstatement |
selectstatement )
```

#### First

The **First** prefix to a **LOAD** or **SELECT (SQL)** statement is used for loading a set maximum number of records from a data source table.

```
First n( loadstatement | selectstatement )
```

#### Generic

The **Generic** load prefix allows for conversion of entity–attribute–value modeled data (EAV) into a traditional, normalized relational table structure. EAV modeling is alternatively referred to as "generic data modeling" or "open schema".

---

## 3 Script statements and keywords

---

```
Generic ( loadstatement | selectstatement )
```

### Hierarchy

The **hierarchy** prefix is used to transform a parent-child hierarchy table to a table that is useful in a Qlik Sense data model. It can be put in front of a **LOAD** or a **SELECT** statement and will use the result of the loading statement as input for a table transformation.

```
Hierarchy (NodeID, ParentID, NodeName, [ParentName], [PathSource],  
[PathName], [PathDelimiter], [Depth])(loadstatement | selectstatement)
```

### HierarchBelongsTo

This prefix is used to transform a parent-child hierarchy table to a table that is useful in a Qlik Sense data model. It can be put in front of a **LOAD** or a **SELECT** statement and will use the result of the loading statement as input for a table transformation.

```
HierarchyBelongsTo (NodeID, ParentID, NodeName, AncestorID, AncestorName,  
[DepthDiff])(loadstatement | selectstatement)
```

### Inner

The **join** and **keep** prefixes can be preceded by the prefix **inner**.

If used before **join** it specifies that an inner join should be used. The resulting table will thus only contain combinations of field values from the raw data tables where the linking field values are represented in both tables. If used before **keep**, it specifies that both raw data tables should be reduced to their common intersection before being stored in Qlik Sense.

```
Inner ( Join | Keep) [ (tablename) ](loadstatement |selectstatement )
```

### IntervalMatch

The **IntervalMatch** prefix is used to create a table matching discrete numeric values to one or more numeric intervals, and optionally matching the values of one or several additional keys.

```
IntervalMatch (matchfield)(loadstatement | selectstatement )  
IntervalMatch (matchfield,keyfield1 [ , keyfield2, ... keyfield5 ] )  
(loadstatement | selectstatement )
```

### Join

The **join** prefix joins the loaded table with an existing named table or the last previously created data table.

```
[Inner | Outer | Left | Right ] Join [ (tablename) ]( loadstatement |  
selectstatement )
```

### Keep

The **keep** prefix is similar to the **join** prefix. Just as the **join** prefix, it compares the loaded table with an existing named table or the last previously created data table, but instead of joining the loaded table with an existing table, it has the effect of reducing one or both of the two tables before they are stored in Qlik Sense, based on the intersection of table data. The comparison made is equivalent to a natural join made over all the common fields, i.e. the same way as in a corresponding

---

## 3 Script statements and keywords

join. However, the two tables are not joined and will be kept in Qlik Sense as two separately named tables.

```
(Inner | Left | Right) Keep [(tablename) ]( loadstatement | selectstatement )
```

### Left

The **Join** and **Keep** prefixes can be preceded by the prefix **left**.

If used before **join** it specifies that a left join should be used. The resulting table will only contain combinations of field values from the raw data tables where the linking field values are represented in the first table. If used before **keep**, it specifies that the second raw data table should be reduced to its common intersection with the first table, before being stored in Qlik Sense.

```
Left ( Join | Keep) [ (tablename) ](loadstatement |selectstatement )
```

### Mapping

The **mapping** prefix is used to create a mapping table that can be used to, for example, replacing field values and field names during script execution.

```
Mapping ( loadstatement | selectstatement )
```

### Merge

The **Merge** prefix can be added to any **LOAD** or **SELECT** statement in the script to specify that the loaded table should be merged into another table. It also specifies that this statement should be run in a partial reload.

```
Merge [only] [(SequenceNoField [, SequenceNoVar])] On ListOfKeys [Concatenate [(TableName)]] (loadstatement | selectstatement)
```

### NoConcatenate

The **NoConcatenate** prefix forces two loaded tables with identical field sets to be treated as two separate internal tables, when they would otherwise be automatically concatenated.

```
NoConcatenate( loadstatement | selectstatement )
```

### Outer

The explicit **Join** prefix can be preceded by the prefix **Outer** to specify an outer join. In an outer join, all combinations between the two tables are generated. The resulting table will thus contain combinations of field values from the raw data tables where the linking field values are represented in one or both tables. The **Outer** keyword is optional and is the default join type used when a join prefix is not specified.

```
Outer Join [ (tablename) ](loadstatement |selectstatement )
```

### Partial reload

A full reload always starts by deleting all tables in the existing data model, and then runs the load script.

## 3 Script statements and keywords

---

A *Partial reload* (page 99) will not do this. Instead it keeps all tables in the data model and then executes only **Load** and **Select** statements preceded by an **Add**, **Merge**, or **Replace** prefix. Other data tables are not affected by the command. The **only** argument denotes that the statement should be executed only during partial reloads, and should be disregarded during full reloads. The following table summarizes statement execution for partial and full reloads.

### Replace

The **Replace** prefix can be added to any **LOAD** or **SELECT** statement in the script to specify that the loaded table should replace another table. It also specifies that this statement should be run in a partial reload. The **Replace** prefix can also be used in a **Map** statement.

```
Replace [only] [Concatenate[(tablename) ]] (loadstatement | selectstatement)
Replace [only] mapstatement
```

### Right

The **Join** and **Keep** prefixes can be preceded by the prefix **right**.

If used before **join** it specifies that a right join should be used. The resulting table will only contain combinations of field values from the raw data tables where the linking field values are represented in the second table. If used before **keep**, it specifies that the first raw data table should be reduced to its common intersection with the second table, before being stored in Qlik Sense.

```
Right (Join | Keep) [(tablename)](loadstatement |selectstatement )
```

### Sample

The **sample** prefix to a **LOAD** or **SELECT** statement is used for loading a random sample of records from the data source.

```
Sample p ( loadstatement | selectstatement )
```

### Semantic

Tables containing relations between records can be loaded through a **semantic** prefix. This can for example be self-references within a table, where one record points to another, such as parent, belongs to, or predecessor.

```
Semantic ( loadstatement | selectstatement)
```

### Unless

The **unless** prefix and suffix is used for creating a conditional clause which determines whether a statement or exit clause should be evaluated or not. It may be seen as a compact alternative to the full **if..end if** statement.

```
(Unless condition statement | exitstatement Unless condition )
```

### When

The **when** prefix and suffix is used for creating a conditional clause which determines whether a statement or exit clause should be executed or not. It may be seen as a compact alternative to the full **if..end if** statement.

```
( When condition statement | exitstatement when condition )
```

### Add

The **Add** prefix can be added to any **LOAD** or **SELECT** statement in the script to specify that it should add records to another table. It also specifies that this statement should be run in a partial reload. The **Add** prefix can also be used in a **Map** statement.



*For partial reload to work properly, the app must be opened with data before a partial reload is triggered.*

Perform a partial reload using the **Reload** button. You can also use the Qlik Engine JSON API.

#### Syntax:

```
Add [only] [Concatenate [(tablename)]] (loadstatement | selectstatement)
```

```
Add [only] mapstatement
```

During a normal (non-partial) reload, the **Add LOAD** construction will work as a normal **LOAD** statement. Records will be generated and stored in a table.

If the **Concatenate** prefix is used, or if there exists a table with the same set of fields, the records will be appended to the relevant existing table. Otherwise, the **Add LOAD** construction will create a new table.

A partial reload will do the same. The only difference is that the **Add LOAD** construction will never create a new table. There always exists a relevant table from the previous script execution to which the records should be appended.

No check for duplicates is performed. Therefore, a statement using the **Add** prefix will often include either a distinct qualifier or a where clause guarding duplicates.

The **Add Map...Using** statement causes mapping to take place also during partial script execution.

#### Arguments:

##### Arguments

Argument	Description
only	An optional qualifier denoting that the statement should be executed only during partial reloads. It should be disregarded during normal (non-partial) reloads.

## 3 Script statements and keywords

Examples and results:

Example	Result
Tab1: LOAD Name, Number FROM Persons.csv; Add LOAD Name, Number FROM newPersons.csv;	<p>During normal reload, data is loaded from <i>Persons.csv</i> and stored in the Qlik Sense table Tab1. Data from <i>NewPersons.csv</i> is then concatenated to the same Qlik Sense table.</p> <p>During partial reload, data is loaded from <i>NewPersons.csv</i> and appended to the Qlik Sense table Tab1. No check for duplicates is made.</p>
Tab1: SQL SELECT Name, Number FROM Persons.csv; Add LOAD Name, Number FROM NewPersons.csv where not exists (Name);	<p>A check for duplicates is made by means of looking if Name exists in the previously loaded table data.</p> <p>During normal reload, data is loaded from <i>Persons.csv</i> and stored in the Qlik Sense table Tab1. Data from <i>NewPersons.csv</i> is then concatenated to the same Qlik Sense table.</p> <p>During partial reload, data is loaded from <i>NewPersons.csv</i> which is appended to the Qlik Sense table Tab1. A check for duplicates is made by means of seeing if Name exists in the previously loaded table data.</p>
Tab1: LOAD Name, Number FROM Persons.csv; Add Only LOAD Name, Number FROM NewPersons.csv where not exists(Name);	<p>During normal reload, data is loaded from <i>Persons.csv</i> and stored in the Qlik Sense table Tab1. The statement loading <i>NewPersons.csv</i> is disregarded.</p> <p>During partial reload, data is loaded from <i>NewPersons.csv</i> which is appended to the Qlik Sense table Tab1. A check for duplicates is made by means of seeing if Name exists in the previously loaded table data.</p>

### Buffer

QVD files can be created and maintained automatically via the **buffer** prefix. This prefix can be used on most **LOAD** and **SELECT** statements in script. It indicates that QVD files are used to cache/buffer the result of the statement.

#### Syntax:

```
Buffer [(option [ , option])] ( loadstatement | selectstatement )  
option ::= incremental | stale [after] amount [(days | hours)]
```

If no option is used, the QVD buffer created by the first execution of the script will be used indefinitely.

The buffer file is stored in the *Buffers* sub-folder, typically *C:\ProgramData\Qlik\Sense\Engine\Buffers* (server installation) or *C:\Users\{user}\Documents\Qlik\Sense\Buffers* (Qlik Sense Desktop).

The name of the QVD file is a calculated name, a 160-bit hexadecimal hash of the entire following **LOAD** or **SELECT** statement and other discriminating info. This means that the QVD buffer will be rendered invalid by any change in the following **LOAD** or **SELECT** statement.

---

## 3 Script statements and keywords

QVD buffers will normally be removed when no longer referenced anywhere throughout a complete script execution in the app that created it or when the app that created it no longer exists.

### Arguments:

Arguments

Argument	Description
incremental	<p>The incremental option enables the ability to read only part of an underlying file. Previous size of the file is stored in the XML header in the QVD file. This is particularly useful with log files. All records loaded at a previous occasion are read from the QVD file whereas the following new records are read from the original source and finally an updated QVD-file is created.</p> <p>The incremental option can only be used with <b>LOAD</b> statements and text files. Incremental load cannot be used where old data is changed or deleted.</p>
stale [after] amount [(days   hours)]	<p>amount is a number specifying the time period. Decimals may be used. The unit is assumed to be days if omitted.</p> <p>The stale after option is typically used with DB sources where there is no simple timestamp on the original data. Instead you specify how old the QVD snapshot can be to be used. A stale after clause simply states a time period from the creation time of the QVD buffer after which it will no longer be considered valid. Before that time the QVD buffer will be used as source for data and after that the original data source will be used. The QVD buffer file will then automatically be updated and a new period starts.</p>

### Limitations:

Numerous limitations exist, most notable is that there must be either a file **LOAD** or a **SELECT** statement at the core of any complex statement.

#### Example 1:

```
Buffer SELECT * from MyTable;
```

#### Example 2:

```
Buffer (stale after 7 days) SELECT * from MyTable;
```

#### Example 3:

```
Buffer (incremental) LOAD * from MyLog.log;
```

### Concatenate

`concatenate` is a script load prefix that enables a dataset to be appended to an already existing in-memory table. It is often used to append different sets of transactional data to a single central fact table, or to build up common reference datasets of a specific type that originate from multiple sources. It is similar in functionality to a SQL UNION operator.

The resulting table from a `concatenate` operation will contain the original dataset with the new rows of data appended to the bottom of that table. The source and target tables may have different fields present. Where fields are different, the resulting table will be widened to represent the combined result of all fields present in both the source table and the target table.

#### Syntax:

```
Concatenate [ (tablename ) ] ( loadstatement | selectstatement )
```

#### Arguments

Argument	Description
tablename	The name of an existing table. The named table will be the target of the <code>concatenate</code> operation and any records of data loaded will be appended to that table. If the <code>tablename</code> parameter isn't used, the target table will be the last loaded table before this statement.
loadstatement/selectstatement	The <code>loadstatement/selectstatement</code> argument that follows the <code>tablename</code> argument will be concatenated to the specified table.

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.



## 3 Script statements and keywords

---

### Function example

Example	Result
Concatenate (Transactions) Load .... ;	The data loaded in the load statement below the concatenate prefix will be appended to the existing in-memory table named <code>Transactions</code> (assuming that a table named <code>Transactions</code> has been loaded prior to this point in the load script).

### Example 1 – Appending multiple sets of data to a target table with Concatenate load prefix

Load script and results

#### Overview

In this example you will load two scripts in sequential order.

- The first load script contains an initial dataset with dates and amounts that is sent to a table named `Transactions`.
- The second load script contains:
  - A second dataset that is appended to the initial dataset by using the `concatenate` prefix. This dataset has an additional field, `type`, that is not in the initial dataset.
  - The `concatenate` prefix.

Open the data load editor and add the load script below to a new tab.

#### First load script

```
Transactions:  
Load * Inline [
```

```
id, date, amount  
3750, 08/30/2018, 23.56  
3751, 09/07/2018, 556.31  
3752, 09/16/2018, 5.75  
3753, 09/22/2018, 125.00  
3754, 09/22/2018, 484.21  
3756, 09/22/2018, 59.18  
3757, 09/23/2018, 177.42  
];
```

#### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- `id`
- `date`
- `amount`

## 3 Script statements and keywords

---

First load script results table

id	date	amount
3750	08/30/2018	23.56
3751	09/07/2018	556.31
3752	09/16/2018	5.75
3753	09/22/2018	125.00
3754	09/22/2018	484.21
3756	09/22/2018	59.18
3757	09/23/2018	177.42

The table shows the initial dataset.

### Second load script

Open the data load editor and add the load script below .

```
Concatenate(Transactions)
Load * Inline [
id, date, amount, type
3758, 10/01/2018, 164.27, Internal
3759, 10/03/2018, 384.00, External
3760, 10/06/2018, 25.82, Internal
3761, 10/09/2018, 312.00, Internal
3762, 10/15/2018, 4.56, Internal
3763, 10/16/2018, 90.24, Internal
3764, 10/18/2018, 19.32, External
];
```

### Results

Load the data and go to the sheet. Create this field as a dimension.

- type

Second load script results table

id	date	amount	type
3750	08/30/2018	23.56	-
3751	09/07/2018	556.31	-
3752	09/16/2018	5.75	-
3753	09/22/2018	125.00	-
3754	09/22/2018	484.21	-
3756	09/22/2018	59.18	-

id	date	amount	type
3757	09/23/2018	177.42	-
3758	10/01/2018	164.27	Internal
3759	10/03/2018	384.00	External
3760	10/06/2018	25.82	Internal
3761	10/09/2018	312.00	Internal
3762	10/15/2018	4.56	Internal
3763	10/16/2018	90.24	Internal
3764	10/18/2018	19.32	External

Note the null values in the `type` field for the first seven records loaded where `type` had not been defined.

### Example 2 – Appending multiple sets of data to a target table using implicit concatenation

Load script and results

#### Overview

A typical use case for implicitly appending data is when you load several files of identically structured data and want to append them all to a target table.

For example, by using wildcards in file names with syntax such as:

```
myTable:
Load * from [myFile_*.qvd] (qvd);
```

or in loops using constructs such as:

```
for each file in filelist('myFile_*.qvd')
myTable:
Load * from [$(file)] (qvd);
next file
```



*Implicit concatenation will take place between any two tables that are loaded with identically named fields, even if they aren't defined after one another in the script. This can lead to data being unintentionally appended to tables. If you don't want a secondary table with identical fields to be appended in this way, use the `noconcatenate` load prefix. Renaming the table with an alternate table name tag is not sufficient to prevent implicit concatenation to occur. For more information, see [NoConcatenate](#) (page 89).*

In this example you will load two scripts in sequential order.

## 3 Script statements and keywords

---

- The first load script contains an initial dataset with four fields that is sent to a table named Transactions.
- The second load script contains a dataset with the same fields as the first dataset.

Open the data load editor and add the load script below to a new tab.

### First load script

```
Transactions:
Load * Inline [
id, date, amount, type
3758, 10/01/2018, 164.27, Internal
3759, 10/03/2018, 384.00, External
3760, 10/06/2018, 25.82, Internal
3761, 10/09/2018, 312.00, Internal
3762, 10/15/2018, 4.56, Internal
3763, 10/16/2018, 90.24, Internal
3764, 10/18/2018, 19.32, External
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- id
- date
- amount
- type

First load script results table

id	date	type	amount
3758	10/01/2018	Internal	164.27
3759	10/03/2018	External	384.00
3760	10/06/2018	Internal	25.82
3761	10/09/2018	Internal	312.00
3762	10/15/2018	Internal	4.56
3763	10/16/2018	Internal	90.24
3764	10/18/2018	External	19.32

The table shows the initial dataset.

### Second load script

Open the data load editor and add the load script below .

```
Load * Inline [
id, date, amount, type
```

---

## 3 Script statements and keywords

---

```
3765, 11/03/2018, 129.40, Internal  
3766, 11/05/2018, 638.50, External  
];
```

### Results

Load the data and go to the sheet.

Second load script results table

id	date	type	amount
3758	10/01/2018	Internal	164.27
3759	10/03/2018	External	384.00
3760	10/06/2018	Internal	25.82
3761	10/09/2018	Internal	312.00
3762	10/15/2018	Internal	4.56
3763	10/16/2018	Internal	90.24
3764	10/18/2018	External	19.32
3765	11/03/2018	Internal	129.40
3766	11/05/2018	External	638.50


The second dataset was implicitly concatenated onto the initial dataset because they had identical fields.

### Crosstable

The **crosstable** load prefix is used to transpose “cross table” or “pivot table” structured data. Data structured this way is commonly encountered when working with spreadsheet sources. The output and aim of the **crosstable** load prefix is to transpose such structures into a regular column-oriented table equivalent, as this structure is generally better suited for analysis in Qlik Sense.

### 3 Script statements and keywords

Example of data structured as a crosstable and its equivalent structure after a crosstable transformation



#### Syntax:

```
crosstable (attribute field name, data field name [ , n ] ) ( loadstatement | selectstatement )
```

#### Arguments

Argument	Description
attribute field name	The desired output field name describing the horizontally oriented dimension that is to be transposed (the header row).
data field name	The desired output field name which describes the horizontally oriented data of the dimension that is to be transposed (the matrix of data values beneath the header row).
n	The number of qualifier fields, or unchanged dimensions preceding the table to be transformed to generic form. The default value is 1.

This scripting function is related to the following functions:

#### Related functions

Function	Interaction
<i>Generic</i> (page 57)	A transformation load prefix which takes an entity-attribute-value structured data set and transforms it into a regular relational table structure, separating each attribute encountered into a new field or column of data.

### Example 1 – Transforming pivoted sales data (simple)

Load scripts and results

#### Overview

Open the Data load editor and add the first load script below to a new tab.

The first load script contains a dataset to which the `crosstable` script prefix will be applied later, with the section applying `crosstable` commented out. This means that comment syntax was used to disable this section in the load script.

The second load script is the same as the first, but with the application of `crosstable` uncommented (enabled by removing the comment syntax). The scripts are shown this way to highlight the value of this scripting function in transforming data.

#### First load script (function not applied)

```
tmpData:
//Crosstable (MonthText, Sales)
Load * inline [
Product, Jan 2021, Feb 2021, Mar 2021, Apr 2021, May 2021, Jun 2021
A, 100, 98, 103, 63, 108, 82
B, 284, 279, 297, 305, 294, 292
C, 50, 53, 50, 54, 49, 51];

//Final:
//Load Product,
//Date(Date#(MonthText,'MMM YYYY'),'MMM YYYY') as Month,
//Sales

//Resident tmpData;

//Drop Table tmpData;
```

#### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- Product
- Jan 2021
- Feb 2021
- Mar 2021
- Apr 2021
- May 2021
- Jun 2021

## 3 Script statements and keywords

---

Results table

Product	Jan 2021	Feb 2021	Mar 2021	Apr 2021	May 2021	Jun 2021
A	100	98	103	63	108	82
B	284	279	297	305	294	292
C	50	53	50	54	49	51

This script allows the creation of a crosstable with one column for each month and one row per product. In its current format, this data is not easy to analyze. It would be much better to have all numbers in one field and all months in another, in a three-column table. The next section explains how to do this transformation to the crosstable.

### Second load script (function applied)

Uncomment the script by removing the //. The load script should look like this:

```
tmpData:
Crosstable (MonthText, Sales)
Load * inline [
Product, Jan 2021, Feb 2021, Mar 2021, Apr 2021, May 2021, Jun 2021
A, 100, 98, 103, 63, 108, 82
B, 284, 279, 297, 305, 294, 292
C, 50, 53, 50, 54, 49, 51];

Final:
Load Product,
Date(Date#(MonthText, 'MMM YYYY'), 'MMM YYYY') as Month,
Sales

Resident tmpData;

Drop Table tmpData;
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- Product
- Month
- Sales

Results table

Product	Month	Sales
A	Jan 2021	100
A	Feb 2021	98
A	Mar 2021	103



## 3 Script statements and keywords

---

Product	Month	Sales
A	Apr 2021	63
A	May 2021	108
A	Jun 2021	82
B	Jan 2021	284
B	Feb 2021	279
B	Mar 2021	297
B	Apr 2021	305
B	May 2021	294
B	Jun 2021	292
C	Jan 2021	50
C	Feb 2021	53
C	Mar 2021	50
C	Apr 2021	54
C	May 2021	49
C	Jun 2021	51

Once the script prefix has been applied, the crosstable is transformed into a straight table with one column for month and another for sales. This improves the readability of the data.

### Example 2 – Transforming pivoted sales target data into a vertical table structure (intermediate)

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset which is loaded into a table named Targets.
- The `crosstable` load prefix, which transposes the pivoted sales person names into a field of its own, labeled `sales Person`.
- The associated sales target data, which is structured into a field called `target`.

#### Load script

```
salesTargets:  
CROSTABLE([Sales Person],Target,1)
```

## 3 Script statements and keywords

---

```
LOAD
*
INLINE [
Area, Lisa, James, Sharon
APAC, 1500, 1750, 1850
EMEA, 1350, 950, 2050
NA, 1800, 1200, 1350
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- Area
- Sales Person

Add this measure:

```
=Sum(Target)
```

Results table

Area	Sales Person	=Sum(Target)
APAC	James	1750
APAC	Lisa	1500
APAC	Sharon	1850
EMEA	James	950
EMEA	Lisa	1350
EMEA	Sharon	2050
NA	James	1200
NA	Lisa	1800
NA	Sharon	1350

If you want to replicate the display of data as the pivoted input table, you can create an equivalent pivot table in a sheet.

### Do the following:

1. Copy and paste the table you have just created into the sheet.
2. Drag the **Pivot table** chart object on top of the newly created table copy. Select **Convert**.
3. Click **Done editing**.
4. Drag the sales person field from the vertical column shelf to the horizontal column shelf.

The following table shows the data in its initial table form, as it is displayed in Qlik Sense:

### 3 Script statements and keywords

Original results table, as shown in Qlik Sense

Area	Sales Person	=Sum(Target)
Totals	-	13800
APAC	James	1750
APAC	Lisa	1500
APAC	Sharon	1850
EMEA	James	950
EMEA	Lisa	1350
EMEA	Sharon	2050
NA	James	1200
NA	Lisa	1800
NA	Sharon	1350

The equivalent pivot table looks similar to the following, with the column for each sales person's name being contained within the larger row for sales Person:

Equivalent pivot table with the sales Person field pivoted horizontally

Area	James	Lisa	Sharon
APAC	1750	1500	1850
EMEA	950	1350	2050
NA	1350	1350	1350

Example of data displayed as a table and an equivalent pivot table with the sales Person field pivoted horizontally

The screenshot shows two views of the same data. On the left is a standard table with columns 'Area', 'Sales Person', and 'Sum(Target)'. On the right is a pivot table with 'Area' as the row field and 'Sales Person' as the column field. The pivot table has a header row with columns for 'James', 'Lisa', and 'Sharon'. The data rows correspond to the 'Area' field: APAC, EMEA, and NA. The values in the pivot table match the 'Sum(Target)' values from the original table.

Table			
Area	Sales Person	Sum(Target)	
Totals		13800	
APAC	James	1750	
APAC	Lisa	1500	
APAC	Sharon	1850	
EMEA	James	950	
EMEA	Lisa	1350	
EMEA	Sharon	2050	
NA	James	1200	
NA	Lisa	1800	
NA	Sharon	1350	

Pivot table			
Area	Sales Person		
	James	Lisa	Sharon
APAC	1750	1500	1850
EMEA	950	1350	2050
NA	1200	1800	1350

### Example 3 – Transforming pivoted sales and target data into a vertical table structure (advanced)

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset representing sales and targets data, organized by area and month of the year. This is loaded into a table called `salesAndTargets`.
- The `crosstable` load prefix. This is used to unpivot the `month year` dimension into a dedicated field, as well as to transpose the matrix of sales and target amounts into a dedicated field called `Amount`.
- A conversion of the `month year` field from text to a proper date, using the text-to-date conversion function `date#`. This date-converted `month year` field is joined back onto the `salesAndTarget` table via a `join` load prefix.

#### Load script

`SalesAndTargets:`

```
CROSTABLE(MonthYearAsText,Amount,2)
```

```
LOAD
```

```
*
```

```
INLINE [
```

Area	Type	Jan-22	Feb-22	Mar-22	Apr-22	May-22	Jun-22	Jul-22	Aug-22	Sep-22	Oct-22	Nov-22	Dec-22
APAC	Target	425	425	425	425	425	425	425	425	425	425	425	425
APAC	Actual	435	434	397	404	458	447	413	458	385	421	448	397
EMEA	Target	362.5	362.5	362.5	362.5	362.5	362.5	362.5	362.5	362.5	362.5	362.5	362.5
EMEA	Actual	363.5	359.5	337.5	361.5	341.5	337.5	379.5	352.5	327.5	337.5	360.5	334.5
NA	Target	375	375	375	375	375	375	375	375	375	375	375	375
NA	Actual	378	415	363	356	403	343	401	365	393	340	360	405

```
] (delimiter is '\t');
```

```
tmp:
```

```
LOAD DISTINCT MonthYearAsText,date#(MonthYearAsText,'MMM-YY') AS [Month Year]
```

```
RESIDENT SalesAndTargets;
```

```
JOIN (SalesAndTargets)
```

```
LOAD * RESIDENT tmp;
```

```
DROP TABLE tmp;
```

```
DROP FIELD MonthYearAsText;
```

#### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

## 3 Script statements and keywords

---

- Area
- Month Year

Create the following measure, with the label `Actual`:

```
=Sum({<Type={'Actual'}>} Amount)
```

Also create this measure, with the label `Target`:

```
=Sum({<Type={'Target'}>} Amount)
```

Results table (cropped)

Area	Month Year	Actual	Target
APAC	Jan-22	435	425
APAC	Feb-22	434	425
APAC	Mar-22	397	425
APAC	Apr-22	404	425
APAC	May-22	458	425
APAC	Jun-22	447	425
APAC	Jul-22	413	425
APAC	Aug-22	458	425
APAC	Sep-22	385	425
APAC	Oct-22	421	425
APAC	Nov-22	448	425
APAC	Dec-22	397	425
EMEA	Jan-22	363.5	362.5
EMEA	Feb-22	359.5	362.5

If you wish to replicate the display of data as the pivoted input table, you can create an equivalent pivot table in a sheet.

### Do the following:

1. Copy and paste the table you have just created into the sheet.
2. Drag the **Pivot table** chart object on top of the newly created table copy. Select **Convert**.
3. Click **Done editing**.
4. Drag the `Month Year` field from the vertical column shelf to the horizontal column shelf.
5. Drag the `values` item from the horizontal column shelf to the vertical column shelf.

The following table shows the data in its initial table form, as it is displayed in Qlik Sense:

### 3 Script statements and keywords

Original results table (cropped), as shown in Qlik Sense

Area	Month Year	Actual	Target
Totals	-	13812	13950
APAC	Jan-22	435	425
APAC	Feb-22	434	425
APAC	Mar-22	397	425
APAC	Apr-22	404	425
APAC	May-22	458	425
APAC	Jun-22	447	425
APAC	Jul-22	413	425
APAC	Aug-22	458	425
APAC	Sep-22	385	425
APAC	Oct-22	421	425
APAC	Nov-22	448	425
APAC	Dec-22	397	425
EMEA	Jan-22	363.5	362.5
EMEA	Feb-22	359.5	362.5

The equivalent pivot table looks similar to the following, with the column for each individual month of the year being contained within the larger row for Month Year:

Equivalent pivot table (cropped) with the Month Year field pivoted horizontally

Area (Values)	Jan-22	Feb-22	Mar-22	Apr-22	May-22	Jun-22	Jul-22	Aug-22	Sep-22	Oct-22	Nov-22	Dec-22
APAC - Actual	435	434	397	404	458	447	413	458	385	421	448	397
APAC - Target	425	425	425	425	425	425	425	425	425	425	425	425
EMEA - Actual	363.5	359.5	337.5	361.5	341.5	337.5	379.5	352.5	327.5	337.5	360.5	334.5

### 3 Script statements and keywords

Area (Values)	Jan-22	Feb-22	Mar-22	Apr-22	May-22	Jun-22	Jul-22	Aug-22	Sep-22	Oct-22	Nov-22	Dec-22
EMEA - Target	362.5	362.5	362.5	362.5	362.5	362.5	362.5	362.5	362.5	362.5	362.5	362.5
NA - Actual	378	415	363	356	403	343	401	365	393	340	360	405
NA - Target	375	375	375	375	375	375	375	375	375	375	375	375

Example of data displayed as a table and an equivalent pivot table with the Month Year field pivoted horizontally

Area	Month Year	Actual	Target
Totals		13812	13950
APAC	Jan-22	435	425
APAC	Feb-22	434	425
APAC	Mar-22	397	425
APAC	Apr-22	404	425
APAC	May-22	458	425
APAC	Jun-22	447	425
APAC	Jul-22	413	425
APAC	Aug-22	458	425
APAC	Sep-22	385	425
APAC	Oct-22	421	425
APAC	Nov-22	448	425

Area	Jan-22	Feb-22	Mar-22	Apr-22	May-22	Jun-22	Jul-22	Aug-22	Sep-22	Oct-22	Nov-22	Dec-22
APAC - Actual	435	434	397	404	458	447	413	458	385	421	448	397
APAC - Target	425	425	425	425	425	425	425	425	425	425	425	425
EMEA - Actual	362.5	362.5	362.5	362.5	362.5	362.5	362.5	362.5	362.5	362.5	362.5	362.5
EMEA - Target	362.5	362.5	362.5	362.5	362.5	362.5	362.5	362.5	362.5	362.5	362.5	362.5
NA - Actual	378	415	363	356	403	343	401	365	393	340	360	405
NA - Target	375	375	375	375	375	375	375	375	375	375	375	375

## First

The `First` prefix to a `LOAD` or `SELECT` (SQL) statement is used for loading a set maximum number of records from a data source table. A typical use case for using the `First` prefix is when you want to retrieve a small subset of records from a large and/or slow data load step. As soon as the defined “n” number of records has been loaded, the load step terminates prematurely, and the rest of the script execution continues as normal.

### Syntax:

```
First n ( loadstatement | selectstatement )
```

### Arguments

Argument	Description
n	An arbitrary expression that evaluates to an integer indicating the maximum number of records to be read. n can also be enclosed in parentheses: (n).
loadstatement   selectstatement	The load statement/select statement that follows the n argument will define the specified table that must be loaded with the set maximum number of records.

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET dateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

#### Function examples

Example	Result
<code>FIRST 10 LOAD * from abc.csv;</code>	This example will retrieve the first ten lines from an excel file.
<code>FIRST (1) SQL SELECT * from orders;</code>	This example will retrieve the first selected line from the orders dataset.

### Example – Load the first five rows

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset of dates from the first two weeks of 2020.
- The `FIRST` variable that instructs the application to only load the first five records.

#### Load script

```
Sales:
FIRST 5
LOAD
*
Inline [
date,sales
01/01/2020,6000
01/02/2020,3000
01/03/2020,6000
01/04/2020,8000
01/05/2020,5000
01/06/2020,7000
01/07/2020,3000
01/08/2020,5000
01/09/2020,9000
```



## 3 Script statements and keywords

---

```
01/10/2020, 5000
01/11/2020, 7000
01/12/2020, 7000
01/13/2020, 7000
01/14/2020, 7000
];
```

### Results

Load the data and open a sheet. Create a new table and add `date` as a field and `sum(sales)` as a measure:

Results table

Date	sum(sales)
01/01/2020	6000
01/02/2020	3000
01/03/2020	6000
01/04/2020	8000
01/05/2020	5000


The script only loads the first five records of the `sales` table.

### Generic

The **Generic** load prefix allows for conversion of entity–attribute–value modeled data (EAV) into a traditional, normalized relational table structure. EAV modeling is alternatively referred to as "generic data modeling" or "open schema".

*Example of EAV modeled data and an equivalent denormalized relational table*


Product ID	Attribute	Value
13	Status	Discontinued
13	Colour	Brown
20	Colour	White
13	Size	13-15
20	Size	16-18



Product ID	Status	Colour	Size
13	Discontinued	Brown	13-15
20		White	16-18

### 3 Script statements and keywords

Example of EAV modeled data and an equivalent set of normalized relational tables



While it is technically possible to load and analyze EAV modeled data in Qlik, it is often easier to work with an equivalent traditional relational data structure.

#### Syntax:

```
Generic( loadstatement | selectstatement )
```

These topics may help you work with this function:

#### Related topics

Topic	Description
<a href="#">Crosstable</a> (page 45)	The <code>crosstable</code> load prefix transforms data that is horizontally-oriented into vertically-oriented data. From a purely functional perspective, it performs the opposite transformation to the <code>generic</code> load prefix, although the prefixes typically serve entirely different use cases.
<b>Generic databases</b> in <a href="#">Manage data</a>	EAV structured data models are further described here.

#### Example 1 – Transforming EAV structured data with the Generic load prefix

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

---

## 3 Script statements and keywords

The load script contains a dataset which is loaded into a table named `Transactions`. The dataset includes a date field. The default `MonthNames` definition is used.

### Load script

```
Products:
Generic
Load * inline [
Product ID, Attribute, Value
13, Status, Discontinued
13, Color, Brown
20, Color, White
13, Size, 13-15
20, Size, 16-18
2, Status, Discontinued
5, Color, Brown
2, Color, White
44, Color, Brown
45, Size, 16-18
45, Color, Brown
];
```

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension: `color`.

Add this measure:

```
=Count([Product ID])
```

Now you can inspect the number of products by color.

Results table


Color	=Count([Product ID])
Brown	4
White	2

Note the shape of the data model, where each attribute has been broken out into a separate table named according to the original target table tag `Product`. Each table has the attribute as a suffix. One example of this is `Product.Color`. The resulting Product Attribute output records are associated by the `Product ID`.

### 3 Script statements and keywords

---

Data model viewer representation of the results



Resulting table of records: Products.Status

Product ID	Status
13	Discontinued
2	Discontinued

Resulting table of records: Products.Size

Product ID	Size
13	13-15
20	16-18
45	16-18

Resulting table of records: Products.Color

Product ID	Color
13	Brown
5	Brown
44	Brown
45	Brown
20	White
2	White

### Example 2 – Analyzing EAV structured data without the Generic load prefix

Load script and chart expression

#### Overview

This example shows how to analyze EAV structured data in its original form.

Open the Data load editor and add the load script below to a new tab.

The load script contains a dataset which is loaded into a table named `Products` in an EAV structure.

In this example, we are still counting products by color attribute. In order to analyze data structured in this way, you will need to apply expression-level filtering of products carrying the Attribute value `color`.

Furthermore, individual attributes are not available to select as dimensions or fields, making it harder to determine how to build effective visualizations.

#### Load script

```
Products:
Load * Inline
[
Product ID, Attribute, Value
13, Status, Discontinued
13, Color, Brown
20, Color, White
13, Size, 13-15
20, Size, 16-18
2, Status, Discontinued
5, Color, Brown
2, Color, White
44, Color, Brown
45, Size, 16-18
45, Color, Brown
];
```

#### Results

Load the data and open a sheet. Create a new table and add this field as a dimension: `value`.

Create the following measure:

```
=Count({<Attribute={'color'}>} [Product ID])
```

Now you can inspect the number of products by color.

Resulting table of records: Products.Status

Value	=Count({<Attribute={'Color'}>} [Product ID])
Brown	4
White	2

### Example 3 – Denormalizing the resulting output tables from a Generic load (advanced)

Load script and chart expression

#### Overview

In this example, we show how the normalised data structure produced by the generic load prefix can be denormalised back into a consolidated product dimension table. This is an advanced modeling technique which can be employed as part of data model performance tuning.

Open the Data load editor and add the load script below to a new tab.

#### Load script

Products:

Generic

```
Load * inline [  
Product ID, Attribute, Value  
13, Status, Discontinued  
13, Color, Brown  
20, Color, White  
13, Size, 13-15  
20, Size, 16-18  
2, Status, Discontinued  
5, Color, Brown  
2, Color, White  
44, Color, Brown  
45, Size, 16-18  
45, Color, Brown  
];
```

```
RENAME TABLE Products.Color TO Products;
```

```
OUTER JOIN (Products)  
LOAD * RESIDENT Products.Size;
```

```
OUTER JOIN (Products)  
LOAD * RESIDENT Products.Status;  
DROP TABLES Products.Size,Products.Status;
```

### Results

Open the Data model viewer and note the shape of the resulting data model. Only one denormalized table is present. It is a combination of the three intermediary output tables: `Products.Size`, `Products.Status`, and `Products.Color`.

Resulting  
internal data  
model

<b>Products</b>
Product ID
Status
Color
Size

Resulting table of records: Products

<b>Product ID</b>	<b>Status</b>	<b>Color</b>	<b>Size</b>
13	Discontinued	Brown	13-15
20	-	White	16-18
2	Discontinued	White	-
5	-	Brown	-
44	-	Brown	-
45	-	Brown	16-18

Load the data and open a sheet. Create a new table and add this field as a dimension: `color`.

Add this measure:

```
=Count([Product ID])
```

Results table

<b>Color</b>	<b>=Count([Product ID])</b>
Brown	4
White	2

### Hierarchy

The **hierarchy** prefix is used to transform a parent-child hierarchy table to a table that is useful in a Qlik Sense data model. It can be put in front of a **LOAD** or a **SELECT** statement and will use the result of the loading statement as input for a table

## 3 Script statements and keywords

---

transformation.

The prefix creates an expanded nodes table, which normally has the same number of records as the input table, but in addition each level in the hierarchy is stored in a separate field. The path field can be used in a tree structure.

### Syntax:

```
Hierarchy (NodeID, ParentID, NodeName, [ParentName, [PathSource, [PathName, [PathDelimiter, Depth]]]]) (loadstatement | selectstatement)
```

The input table must be an adjacent nodes table. Adjacent nodes tables are tables where each record corresponds to a node and has a field that contains a reference to the parent node. In such a table the node is stored on one record only but the node can still have any number of children. The table may of course contain additional fields describing attributes for the nodes.

The prefix creates an expanded nodes table, which normally has the same number of records as the input table, but in addition each level in the hierarchy is stored in a separate field. The path field can be used in a tree structure.

Usually the input table has exactly one record per node and in such a case the output table will contain the same number of records. However, sometimes there are nodes with multiple parents, i.e. one node is represented by several records in the input table. If so, the output table may have more records than the input table.

All nodes with a parent id not found in the node id column (including nodes with missing parent id) will be considered as roots. Also, only nodes with a connection to a root node - direct or indirect - will be loaded, thus avoiding circular references.

Additional fields containing the name of the parent node, the path of the node and the depth of the node can be created.

### Arguments:

Arguments

Argument	Description
NodeID	The name of the field that contains the node id. This field must exist in the input table.
ParentID	The name of the field that contains the node id of the parent node. This field must exist in the input table.
NodeName	The name of the field that contains the name of the node. This field must exist in the input table.
ParentName	A string used to name the new <b>ParentName</b> field. If omitted, this field will not be created.



## 3 Script statements and keywords

Argument	Description
ParentSource	The name of the field that contains the name of the node used to build the node path. Optional parameter. If omitted, <b>NodeName</b> will be used.
PathName	A string used to name the new <b>Path</b> field, which contains the path from the root to the node. Optional parameter. If omitted, this field will not be created.
PathDelimiter	A string used as delimiter in the new <b>Path</b> field. Optional parameter. If omitted, '/' will be used.
Depth	A string used to name the new <b>Depth</b> field, which contains the depth of the node in the hierarchy. Optional parameter. If omitted, this field will not be created.

### Example:

```
Hierarchy(NodeID, ParentID, NodeName, ParentName, NodeName, PathName, '\', Depth) LOAD *
inline [
NodeID, ParentID, NodeName
1, 4, London
2, 3, Munich
3, 5, Germany
4, 5, UK
5, , Europe
];
```

Nod eID	Paren tID	NodeN ame	NodeNa me1	NodeNa me2	NodeNa me3	ParentN ame	PathName	Dep th
1	4	London	Europe	UK	London	UK	Europe\UK\Lon don	3
2	3	Munich	Europe	German y	Munich	German y	Europe\German y\Munich	3
3	5	Germa ny	Europe	German y	-	Europe	Europe\German y	2
4	5	UK	Europe	UK	-	Europe	Europe\UK	2
5		Europe	Europe	-	-	-	Europe	1

### HierarchyBelongsTo

This prefix is used to transform a parent-child hierarchy table to a table that is useful in a Qlik Sense data model. It can be put in front of a **LOAD** or a **SELECT** statement and will use the result of the loading statement as input for a table transformation.

The prefix creates a table containing all ancestor-child relations of the hierarchy. The ancestor fields can then be used to select entire trees in the hierarchy. The output table in most cases contains several records per node.

## 3 Script statements and keywords

---

### Syntax:

```
HierarchyBelongsTo (NodeID, ParentID, NodeName, AncestorID, AncestorName, [DepthDiff]) (loadstatement | selectstatement)
```

The input table must be an adjacent nodes table. Adjacent nodes tables are tables where each record corresponds to a node and has a field that contains a reference to the parent node. In such a table the node is stored on one record only but the node can still have any number of children. The table may of course contain additional fields describing attributes for the nodes.

The prefix creates a table containing all ancestor-child relations of the hierarchy. The ancestor fields can then be used to select entire trees in the hierarchy. The output table in most cases contains several records per node.

An additional field containing the depth difference of the nodes can be created.

### Arguments:

#### Arguments

Argument	Description
NodeID	The name of the field that contains the node id. This field must exist in the input table.
ParentID	The name of the field that contains the node id of the parent node. This field must exist in the input table.
NodeName	The name of the field that contains the name of the node. This field must exist in the input table.
AncestorID	A string used to name the new ancestor id field, which contains the id of the ancestor node.
AncestorName	A string used to name the new ancestor field, which contains the name of the ancestor node.
DepthDiff	A string used to name the new <b>DepthDiff</b> field, which contains the depth of the node in the hierarchy relative the ancestor node. Optional parameter. If omitted, this field will not be created.

### Example:

```
HierarchyBelongsTo (NodeID, AncestorID, NodeName, AncestorID, AncestorName, DepthDiff) LOAD *  
inline [  
NodeID, AncestorID, NodeName  
1, 4, London  
2, 3, Munich  
3, 5, Germany  
4, 5, UK  
5, , Europe  
];
```

## 3 Script statements and keywords

Results

NodeID	AncestorID	NodeName	AncestorName	DepthDiff
1	1	London	London	0
1	4	London	UK	1
1	5	London	Europe	2
2	2	Munich	Munich	0
2	3	Munich	Germany	1
2	5	Munich	Europe	2
3	3	Germany	Germany	0
3	5	Germany	Europe	1
4	4	UK	UK	0
4	5	UK	Europe	1
5	5	Europe	Europe	0

### Inner

The **join** and **keep** prefixes can be preceded by the prefix **inner**. If used before **join** it specifies that an inner join should be used. The resulting table will thus only contain combinations of field values from the raw data tables where the linking field values are represented in both tables. If used before **keep**, it specifies that both raw data tables should be reduced to their common intersection before being stored in Qlik Sense.

#### Syntax:

```
Inner ( Join | Keep ) [ (tablename) ] (loadstatement |selectstatement )
```

#### Arguments:

Arguments

Argument	Description
tablename	The named table to be compared to the loaded table.
loadstatement or selectstatement	The <b>LOAD</b> or <b>SELECT</b> statement for the loaded table.

#### Example

##### Load script

Add the example script to your app and run it. To see the result, add the fields listed in the results column to a sheet in your app.

```
Table1:  
Load * inline [  
column1, column2
```

## 3 Script statements and keywords

---

```
A, B  
1, aa  
2, cc  
3, ee ];
```

```
Table2:  
Inner Join Load * inline [  
Column1, Column3  
A, C  
1, xx  
4, yy ];
```

### Result

Resulting table

Column1	Column2	Column3
A	B	C
1	aa	xx

### Explanation

This example demonstrates the Inner Join output where only values present in both the first (left) and the second (right) tables are joined.

## IntervalMatch

The **IntervalMatch** prefix is used to create a table matching discrete numeric values to one or more numeric intervals, and optionally matching the values of one or several additional keys.

### Syntax:

```
IntervalMatch (matchfield) (loadstatement | selectstatement )  
IntervalMatch (matchfield, keyfield1 [ , keyfield2, ... keyfield5 ] )  
(loadstatement | selectstatement )
```

The **IntervalMatch** prefix must be placed before a **LOAD** or a **SELECT** statement that loads the intervals. The field containing the discrete data points (Time in the example below) and additional keys must already have been loaded into Qlik Sense before the statement with the **IntervalMatch** prefix. The prefix does not by itself read this field from the database table. The prefix transforms the loaded table of intervals and keys to a table that contains an additional column: the discrete numeric data points. It also expands the number of records so that the new table has one record per possible combination of discrete data point, interval and value of the key field(s).

The intervals may be overlapping and the discrete values will be linked to all matching intervals.

When the IntervalMatch prefix is extended with key fields, it is used to create a table matching discrete numeric values to one or more numeric intervals, while at the same time matching the values of one or several additional keys.

## 3 Script statements and keywords

---

In order to avoid undefined interval limits being disregarded, it may be necessary to allow NULL values to map to other fields that constitute the lower or upper limits to the interval. This can be handled by the **NullAsValue** statement or by an explicit test that replaces NULL values with a numeric value well before or after any of the discrete numeric data points.

### Arguments:

#### Arguments

Argument	Description
matchfield	The field containing the discrete numeric values to be linked to intervals.
keyfield	Fields that contain the additional attributes that are to be matched in the transformation.
loadstatement orselectstatement	Must result in a table, where the first field contains the lower limit of each interval, the second field contains the upper limit of each interval, and in the case of using key matching, the third and any subsequent fields contain the keyfield(s) present in the <b>IntervalMatch</b> statement. The intervals are always closed, i.e. the end points are included in the interval. Non-numeric limits render the interval to be disregarded (undefined).

### Example 1:

In the two tables below, the first one lists a number of discrete events and the second one defines the start and end times for the production of different orders. By means of the **IntervalMatch** prefix it is possible to logically connect the two tables in order to find out e.g. which orders were affected by disturbances and which orders were processed by which shifts.

EventLog:

```
LOAD * Inline [  
Time, Event, Comment  
00:00, 0, Start of shift 1  
01:18, 1, Line stop  
02:23, 2, Line restart 50%  
04:15, 3, Line speed 100%  
08:00, 4, Start of shift 2  
11:43, 5, End of production  
];
```

OrderLog:

```
LOAD * INLINE [  
Start, End, Order  
01:00, 03:35, A  
02:30, 07:58, B  
03:04, 10:27, C  
07:23, 11:43, D  
];
```

```
//Link the field Time to the time intervals defined by the fields Start and End.  
Inner Join IntervalMatch ( Time )  
LOAD Start, End  
Resident OrderLog;
```

## 3 Script statements and keywords

---

The table **OrderLog** contains now an additional column: *Time*. The number of records is also expanded.

Table with additional column

Time	Start	End	Order
00:00	-	-	-
01:18	01:00	03:35	A
02:23	01:00	03:35	A
04:15	02:30	07:58	B
04:15	03:04	10:27	C
08:00	03:04	10:27	C
08:00	07:23	11:43	D
11:43	07:23	11:43	D

### Example 2: (using keyfield)

Same example than above, adding *ProductionLine* as a key field.

EventLog:

```
LOAD * Inline [  
Time, Event, Comment, ProductionLine  
00:00, 0, Start of shift 1, P1  
01:00, 0, Start of shift 1, P2  
01:18, 1, Line stop, P1  
02:23, 2, Line restart 50%, P1  
04:15, 3, Line speed 100%, P1  
08:00, 4, Start of shift 2, P1  
09:00, 4, Start of shift 2, P2  
11:43, 5, End of production, P1  
11:43, 5, End of production, P2  
];
```

OrderLog:

```
LOAD * INLINE [  
Start, End, Order, ProductionLine  
01:00, 03:35, A, P1  
02:30, 07:58, B, P1  
03:04, 10:27, C, P1  
07:23, 11:43, D, P2  
];
```

```
//Link the field Time to the time intervals defined by the fields Start and End and match the values
```

```
// to the key ProductionLine.
```

```
Inner Join
```

```
IntervalMatch ( Time, ProductionLine )
```

```
LOAD Start, End, ProductionLine
```

```
Resident OrderLog;
```

---

## 3 Script statements and keywords

---

A table box could now be created as below:

Tablebox example

ProductionLine	Time	Event	Comment	Order	Start	End
P1	00:00	0	Start of shift 1	-	-	-
P2	01:00	0	Start of shift 1	-	-	-
P1	01:18	1	Line stop	A	01:00	03:35
P1	02:23	2	Line restart 50%	A	01:00	03:35
P1	04:15	3	Line speed 100%	B	02:30	07:58
P1	04:15	3	Line speed 100%	C	03:04	10:27
P1	08:00	4	Start of shift 2	C	03:04	10:27
P2	09:00	4	Start of shift 2	D	07:23	11:43
P1	11:43	5	End of production	-	-	-
P2	11:43	5	End of production	D	07:23	11:43

### Join

The **join** prefix joins the loaded table with an existing named table or the last previously created data table.

The effect of joining data is to extend the target table by an additional set of fields or attributes, namely ones not already present in the target table. Any common field names between the source data set and the target table are used to work out how to associate the new incoming records. This is commonly referred to as a “natural join”. A Qlik join operation can lead to the resulting target table having more or fewer records than it started with, depending on the uniqueness of the join association and the type of join employed.

There are four types of joins:

#### Left join

Left joins are the most common join type. For example, if you have a transaction data set and would like to combine it with a reference data set, you would typically use a `Left Join`. You would load the transaction table first, then load the reference data set while joining it via a `Left Join` prefix onto the already loaded transaction table. A `Left Join` would keep all transactions as-is and add on the supplementary reference data fields where a match is found.

### Inner join

When you have two data sets where you only care about any results where there is a matching association, consider using an `inner join`. This will eliminate all records from both the source data loaded and the target table if no match is found. As a result, this may leave your target table with fewer records than before the join operation took place.

### Outer join

When you need to keep both the target records and all of the incoming records, use an `outer join`. Where no match is found, each set of records is still kept while the fields from the opposite side of the join will remain unpopulated (null).

If the type keyword is omitted, the default join type is an outer join.

### Right join

This join type keeps all the records about to be loaded, while reducing the records in the table targeted by the join to only those records where there is an association match in the incoming records. This is a niche join type that is sometimes used as a means of trimming down an already pre-loaded table of records to a required subset.

*Example results sets from different types of join operations*

DATASETS	OPERATION	OUTPUT																		
<p>Target Table</p> <table border="1"> <thead> <tr> <th>Trade ID</th> <th>Asset Class</th> </tr> </thead> <tbody> <tr> <td>101533</td> <td>Fixed Income</td> </tr> <tr> <td>606601</td> <td>Commodities</td> </tr> </tbody> </table>	Trade ID	Asset Class	101533	Fixed Income	606601	Commodities	<p>LEFT JOIN</p> <p>➔</p>	<table border="1"> <thead> <tr> <th>Trade ID</th> <th>Asset Class</th> <th></th> </tr> </thead> <tbody> <tr> <td>101533</td> <td>Fixed Income</td> <td>LSE</td> </tr> <tr> <td>606601</td> <td>Commodities</td> <td></td> </tr> </tbody> </table>	Trade ID	Asset Class		101533	Fixed Income	LSE	606601	Commodities				
Trade ID	Asset Class																			
101533	Fixed Income																			
606601	Commodities																			
Trade ID	Asset Class																			
101533	Fixed Income	LSE																		
606601	Commodities																			
	<p>INNER JOIN</p> <p>➔</p>	<table border="1"> <thead> <tr> <th>Trade ID</th> <th>Asset Class</th> <th></th> </tr> </thead> <tbody> <tr> <td>101533</td> <td>Fixed Income</td> <td>LSE</td> </tr> </tbody> </table>	Trade ID	Asset Class		101533	Fixed Income	LSE												
Trade ID	Asset Class																			
101533	Fixed Income	LSE																		
<p>Incoming Dataset</p> <table border="1"> <thead> <tr> <th>Trade ID</th> <th>Exchange</th> </tr> </thead> <tbody> <tr> <td>101533</td> <td>LSE</td> </tr> <tr> <td>79052</td> <td>Hong Kong</td> </tr> </tbody> </table>	Trade ID	Exchange	101533	LSE	79052	Hong Kong	<p>OUTER JOIN</p> <p>➔</p>	<table border="1"> <thead> <tr> <th>Trade ID</th> <th>Asset Class</th> <th></th> </tr> </thead> <tbody> <tr> <td>101533</td> <td>Fixed Income</td> <td>LSE</td> </tr> <tr> <td>606601</td> <td>Commodities</td> <td></td> </tr> <tr> <td>79052</td> <td></td> <td>Hong Kong</td> </tr> </tbody> </table>	Trade ID	Asset Class		101533	Fixed Income	LSE	606601	Commodities		79052		Hong Kong
Trade ID	Exchange																			
101533	LSE																			
79052	Hong Kong																			
Trade ID	Asset Class																			
101533	Fixed Income	LSE																		
606601	Commodities																			
79052		Hong Kong																		
	<p>RIGHT JOIN</p> <p>➔</p>	<table border="1"> <thead> <tr> <th>Trade ID</th> <th>Asset Class</th> <th></th> </tr> </thead> <tbody> <tr> <td>101533</td> <td>Fixed Income</td> <td>LSE</td> </tr> <tr> <td>79052</td> <td></td> <td>Hong Kong</td> </tr> </tbody> </table>	Trade ID	Asset Class		101533	Fixed Income	LSE	79052		Hong Kong									
Trade ID	Asset Class																			
101533	Fixed Income	LSE																		
79052		Hong Kong																		



*If there are no field names in common between the source and target of a join operation, the join will result in a cartesian product of all rows – this is called a “cross join”.*



## 3 Script statements and keywords

Example result set from a "cross join" operation

DATASETS			OPERATION	OUTPUT																											
Target Table			JOIN (any type) →	<table border="1"> <thead> <tr> <th>Trade ID</th> <th>Base Currency</th> <th>Amount</th> <th>Target Currency</th> <th>Rate</th> </tr> </thead> <tbody> <tr> <td>101533</td> <td>EUR</td> <td>1250</td> <td>USD</td> <td>1.08</td> </tr> <tr> <td>101533</td> <td>EUR</td> <td>1250</td> <td>GBP</td> <td>0.84</td> </tr> <tr> <td>606601</td> <td>EUR</td> <td>1650</td> <td>USD</td> <td>1.08</td> </tr> <tr> <td>606601</td> <td>EUR</td> <td>1650</td> <td>GBP</td> <td>0.84</td> </tr> </tbody> </table>			Trade ID	Base Currency	Amount	Target Currency	Rate	101533	EUR	1250	USD	1.08	101533	EUR	1250	GBP	0.84	606601	EUR	1650	USD	1.08	606601	EUR	1650	GBP	0.84
Trade ID	Base Currency	Amount					Target Currency	Rate																							
101533	EUR	1250	USD	1.08																											
101533	EUR	1250	GBP	0.84																											
606601	EUR	1650	USD	1.08																											
606601	EUR	1650	GBP	0.84																											
<table border="1"> <thead> <tr> <th>Trade ID</th> <th>Base Currency</th> <th>Amount</th> </tr> </thead> <tbody> <tr> <td>101533</td> <td>EUR</td> <td>1250</td> </tr> <tr> <td>606601</td> <td>EUR</td> <td>1650</td> </tr> </tbody> </table>			Trade ID	Base Currency	Amount	101533	EUR	1250	606601	EUR	1650																				
Trade ID	Base Currency	Amount																													
101533	EUR	1250																													
606601	EUR	1650																													
Incoming Dataset																															
<table border="1"> <thead> <tr> <th>Target Currency</th> <th>Rate</th> </tr> </thead> <tbody> <tr> <td>USD</td> <td>1.08</td> </tr> <tr> <td>GBP</td> <td>0.84</td> </tr> </tbody> </table>			Target Currency	Rate	USD	1.08	GBP	0.84																							
Target Currency	Rate																														
USD	1.08																														
GBP	0.84																														

### Syntax:

```
[inner | outer | left | right ]Join [ (tablename ) ] ( loadstatement |
selectstatement )
```

#### Arguments

Argument	Description
tablename	The named table to be compared to the loaded table.
loadstatement or selectstatement	The <b>LOAD</b> or <b>SELECT</b> statement for the loaded table.

These topics may help you work with this function:

#### Related topics

Topic	Description
<b>Combining tables with Join and Keep</b> in <i>Manage data</i>	This topic provides further explanation of the concepts of "joining" and "keeping" data sets.
<i>Keep (page 81)</i>	The keep load prefix is similar to the join prefix, but it does not combine the source and target datasets. Instead, it trims each dataset according to the type of operation adopted (inner, outer, left, or right).

### Example 1 - Left join: Enriching a target table with a reference data set

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset representing change records, which is loaded into a table named changes. It includes a Status ID key field.
- A second dataset representing change statuses, which is loaded and combined with the original change records by joining it with a left join load prefix.

This left join ensures that the change records remain intact while adding on status attributes where a match in the incoming status records is found based on a common Status ID.

#### Load script

Changes:

```
Load * inline [
```

Change ID	Status ID	Scheduled Start Date	Scheduled End Date	Business Impact
10030	4	19/01/2022	23/02/2022	None
10015	3	04/01/2022	15/02/2022	Low
10103	1	02/04/2022	29/05/2022	Medium
10185	2	23/06/2022	08/09/2022	None
10323	1	08/11/2022	26/11/2022	High
10326	2	11/11/2022	05/12/2022	None
10138	2	07/05/2022	03/08/2022	None
10031	3	20/01/2022	25/03/2022	Low
10040	1	29/01/2022	22/04/2022	None
10134	1	03/05/2022	08/07/2022	Low
10334	2	19/11/2022	06/02/2023	Low
10220	2	28/07/2022	06/09/2022	None
10264	1	10/09/2022	17/10/2022	Medium
10116	1	15/04/2022	24/04/2022	None
10187	2	25/06/2022	24/08/2022	Low

```
] (delimiter is '\t');
```

Status:

```
Left Join (Changes)
```

```
Load * inline [
```

Status ID	Status	Sub Status
1	Open	Not Started
2	Open	Started
3	Closed	Completed
4	Closed	Cancelled
5	Closed	Obsolete

```
] (delimiter is '\t');
```

## 3 Script statements and keywords

---

### Results

Open the Data model viewer and note the shape of the data model. Only one denormalized table is present. It is a combination of all the original change records, with the matching status attributes joined onto each change record.

Resulting internal data  
model

<b>Changes</b>
Change ID
Status ID
Scheduled Start Date
Scheduled End Date
Business Impact
Status
Sub Status

If you expand the preview window in the Data model viewer, you will see a portion of this full result set organized into a table:

Preview of Changes table in the Data model viewer

<b>Change ID</b>	<b>Status ID</b>	<b>Scheduled Start Date</b>	<b>Scheduled End Date</b>	<b>Business Impact</b>	<b>Status</b>	<b>Sub Status</b>
10030	4	19/01/2022	23/02/2022	None	Closed	Cancelled
10031	3	20/01/2022	25/03/2022	Low	Closed	Completed
10015	3	04/01/2022	15/02/2022	Low	Closed	Completed
10103	1	02/04/2022	29/05/2022	Medium	Open	Not Started
10116	1	15/04/2022	24/04/2022	None	Open	Not Started
10134	1	03/05/2022	08/07/2022	Low	Open	Not Started
10264	1	10/09/2022	17/10/2022	Medium	Open	Not Started
10040	1	29/01/2022	22/04/2022	None	Open	Not Started
10323	1	08/11/2022	26/11/2022	High	Open	Not Started
10187	2	25/06/2022	24/08/2022	Low	Open	Started
10185	2	23/06/2022	08/09/2022	None	Open	Started
10220	2	28/07/2022	06/09/2022	None	Open	Started
10326	2	11/11/2022	05/12/2022	None	Open	Started

## 3 Script statements and keywords

Change ID	Status ID	Scheduled Start Date	Scheduled End Date	Business Impact	Status	Sub Status
10138	2	07/05/2022	03/08/2022	None	Open	Started
10334	2	19/11/2022	06/02/2023	Low	Open	Started

Since the fifth row in the Status table (Status ID: '5', Status: 'Closed', Sub Status: 'Obsolete') does not correspond to any of the records in the Changes table, the information in this row does not appear in the result set above.

Return to the Data load editor. Load the data and open a sheet. Create a new table and add this field as a dimension: `status`.

Add this measure:

```
=Count([Change ID])
```

Now you can inspect the number of Changes by Status.

Results table

Status	=Count([Change ID])
Open	12
Closed	3

### Example 2 – Inner join: Combining matching records only

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset representing change records, which is loaded into a table named `changes`.
- A second dataset representing change records originating from the source system `JIRA`. This is loaded and combined with the original records by joining it with an `Inner Join` load prefix.

This `Inner Join` ensures that only the five change records which are found in both datasets are kept.

#### Load script

Changes:

```
Load * inline [
```

```
Change ID      Status ID      Scheduled Start Date      Scheduled End Date      Business Impact
10030  4      19/01/2022      23/02/2022      None
10015  3      04/01/2022      15/02/2022      Low
10103  1      02/04/2022      29/05/2022      Medium
```

## 3 Script statements and keywords

```
10185 2      23/06/2022      08/09/2022      None
10323 1      08/11/2022      26/11/2022      High
10326 2      11/11/2022      05/12/2022      None
10138 2      07/05/2022      03/08/2022      None
10031 3      20/01/2022      25/03/2022      Low
10040 1      29/01/2022      22/04/2022      None
10134 1      03/05/2022      08/07/2022      Low
10334 2      19/11/2022      06/02/2023      Low
10220 2      28/07/2022      06/09/2022      None
10264 1      10/09/2022      17/10/2022      Medium
10116 1      15/04/2022      24/04/2022      None
10187 2      25/06/2022      24/08/2022      Low
] (delimiter is '\t');
```

```
JIRA_changes:
Inner Join (Changes)
Load
  [Ticket ID] AS [Change ID],
  [Source System]
inline
[
Ticket ID      Source System
10000 JIRA
10030 JIRA
10323 JIRA
10134 JIRA
10334 JIRA
10220 JIRA
20000 TFS
] (delimiter is '\t');
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- Source System
- Change ID
- Business Impact

Now you can inspect the five resulting records. The resultant table from an `Inner Join` will only include records with matching information in both datasets.

Results table

Source System	Change ID	Business Impact
JIRA	10030	None
JIRA	10134	Low
JIRA	10220	None
JIRA	10323	High
JIRA	10334	Low

### Example 3 – Outer join: Combining overlapping record sets

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset representing change records, which is loaded into a table named `changes`.
- A second dataset representing change records originating from the source system `JIRA`, which is loaded and combined with the original records by joining it with an `outer join` load prefix.

This ensures that all the overlapping change records from both datasets are kept.

#### Load script

```
// 8 Change records
```

```
Changes:
```

```
Load * inline [
```

Change ID	Status ID	Scheduled Start Date	Scheduled End Date	Business Impact
10030	4	19/01/2022	23/02/2022	None
10015	3	04/01/2022	15/02/2022	Low
10138	2	07/05/2022	03/08/2022	None
10031	3	20/01/2022	25/03/2022	Low
10040	1	29/01/2022	22/04/2022	None
10134	1	03/05/2022	08/07/2022	Low
10334	2	19/11/2022	06/02/2023	Low
10220	2	28/07/2022	06/09/2022	None

```
] (delimiter is '\t');
```

```
// 6 Change records
```

```
JIRA_changes:
```

```
Outer Join (Changes)
```

```
Load
```

```
  [Ticket ID] AS [Change ID],
```

```
  [Source System]
```

```
inline
```

```
[
```

Ticket ID	Source System
10030	JIRA
10323	JIRA
10134	JIRA
10334	JIRA
10220	JIRA
10597	JIRA

```
] (delimiter is '\t');
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- Source System
- Change ID
- Business Impact

Now you can inspect the 10 resulting records.

Results table

Source System	Change ID	Business Impact
JIRA	10030	None
JIRA	10134	Low
JIRA	10220	None
JIRA	10323	-
JIRA	10334	Low
JIRA	10597	-
-	10015	Low
-	10031	Low
-	10040	None
-	10138	None

### Example 4 – Right join: Trimming down a target table by a secondary master dataset

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset representing change records, which is loaded into a table named `changes`.
- A second dataset representing change records originating from the source system `Teamwork`. This is loaded and combined with the original records by joining it with a `right join` load prefix.

This ensures that only `Teamwork` change records are kept, while not losing any `Teamwork` records if the target table does not have a matching `change ID`.

### Load script

Changes:

```
Load * inline [  
Change ID      Status ID      Scheduled Start Date      Scheduled End Date      Business Impact  
10030 4      19/01/2022      23/02/2022      None  
10015 3      04/01/2022      15/02/2022      Low  
10103 1      02/04/2022      29/05/2022      Medium  
10185 2      23/06/2022      08/09/2022      None  
10323 1      08/11/2022      26/11/2022      High  
10326 2      11/11/2022      05/12/2022      None  
10138 2      07/05/2022      03/08/2022      None  
10031 3      20/01/2022      25/03/2022      Low  
10040 1      29/01/2022      22/04/2022      None  
10134 1      03/05/2022      08/07/2022      Low  
10334 2      19/11/2022      06/02/2023      Low  
10220 2      28/07/2022      06/09/2022      None  
10264 1      10/09/2022      17/10/2022      Medium  
10116 1      15/04/2022      24/04/2022      None  
10187 2      25/06/2022      24/08/2022      Low  
] (delimiter is '\t');
```

Teamwork\_changes:

Right Join (Changes)

Load

```
[Ticket ID] AS [Change ID],  
[Source System]
```

inline

```
[
```

```
Ticket ID      Source System
```

```
10040 Teamwork
```

```
10015 Teamwork
```

```
10103 Teamwork
```

```
10031 Teamwork
```

```
50231 Teamwork
```

```
] (delimiter is '\t');
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- Source System
- Change ID
- Business Impact

Now you can inspect the five resulting records.



Results table

Source System	Change ID	Business Impact
Teamwork	10015	Low
Teamwork	10031	Low
Teamwork	10040	None
Teamwork	10103	Medium
Teamwork	50231	-

### Keep

The **keep** prefix is similar to the **join** prefix. Just as the **join** prefix, it compares the loaded table with an existing named table or the last previously created data table, but instead of joining the loaded table with an existing table, it has the effect of reducing one or both of the two tables before they are stored in Qlik Sense, based on the intersection of table data. The comparison made is equivalent to a natural join made over all the common fields, i.e. the same way as in a corresponding join. However, the two tables are not joined and will be kept in Qlik Sense as two separately named tables.

#### Syntax:

```
(inner | left | right) keep [(tablename) ]( loadstatement | selectstatement )
```

The **keep** prefix must be preceded by one of the prefixes **inner**, **left** or **right**.

The explicit **join** prefix in Qlik Sense script language performs a full join of the two tables. The result is one table. In many cases such joins will result in very large tables. One of the main features of Qlik Sense is its ability to make associations between multiple tables instead of joining them, which greatly reduces memory usage, increases processing speed and offers enormous flexibility. Explicit joins should therefore generally be avoided in Qlik Sense scripts. The **keep** functionality was designed to reduce the number of cases where explicit joins needs to be used.

#### Arguments:

Arguments

Argument	Description
tablename	The named table to be compared to the loaded table.
loadstatement or selectstatement	The <b>LOAD</b> or <b>SELECT</b> statement for the loaded table.

#### Example:

```
Inner Keep LOAD * from abc.csv;  
Left Keep SELECT * from table1;  
tab1:  
LOAD * from file1.csv;  
tab2:
```

```
LOAD * from file2.csv;
... ..
Left Keep (tab1) LOAD * from file3.csv;
```

### Left

The **Join** and **Keep** prefixes can be preceded by the prefix **left**.

If used before **join** it specifies that a left join should be used. The resulting table will only contain combinations of field values from the raw data tables where the linking field values are represented in the first table. If used before **keep**, it specifies that the second raw data table should be reduced to its common intersection with the first table, before being stored in Qlik Sense.



*Were you looking for the string function by the same name? See: [Left \(page 1464\)](#)*

#### Syntax:

```
Left ( Join | Keep ) [ (tablename) ] (loadstatement | selectstatement)
```

#### Arguments:

##### Arguments

Argument	Description
tablename	The named table to be compared to the loaded table.
loadstatement or selectstatement	The <b>LOAD</b> or <b>SELECT</b> statement for the loaded table.

#### Example

##### Load script

Add the example script to your app and run it. To see the result, add the fields listed in the results column to a sheet in your app.

```
Table1:
Load * inline [
Column1, Column2
A, B
1, aa
2, cc
3, ee ];
```

```
Table2:
Left Join Load * inline [
Column1, Column3
A, C
1, xx
4, yy ];
```

### Result

Resulting table

Column1	Column2	Column3
A	B	C
1	aa	xx
2	cc	-
3	ee	-

### Explanation

This example demonstrates the Left Join output where only values present in the first (left) table are joined.

## Mapping

The **mapping** prefix is used to create a mapping table that can be used to, for example, replacing field values and field names during script execution.

### Syntax:

```
Mapping( loadstatement | selectstatement )
```

The **mapping** prefix can be put in front of a **LOAD** or a **SELECT** statement and will store the result of the loading statement as a mapping table. Mapping provides an efficient way to substituting field values during script execution, e.g. replacing US, U.S. or America with USA. A mapping table consists of two columns, the first containing comparison values and the second containing the desired mapping values. Mapping tables are stored temporarily in memory and dropped automatically after script execution.

The content of the mapping table can be accessed using e.g. the **Map ... Using** statement, the **Rename Field** statement, the **Applymap()** function or the **Mapsubstring()** function.

### Example:

In this example we load a list of salespersons with a country code representing their country of residence. We use a table mapping a country code to a country to replace the country code with the country name. Only three countries are defined in the mapping table, other country codes are mapped to 'Rest of the world'.

```
// Load mapping table of country codes:  
map1:  
mapping LOAD *  
inline [  
  CCode, Country  
  Sw, Sweden  
  Dk, Denmark  
  No, Norway  
] ;
```

## 3 Script statements and keywords

```
// Load list of salesmen, mapping country code to country
// If the country code is not in the mapping table, put Rest of the world
Salespersons:
LOAD *,
ApplyMap('map1', CCode,'Rest of the world') As Country
Inline [
CCode, Salesperson
Sw, John
Sw, Mary
Sw, Per
Dk, Preben
Dk, Olle
No, Ole
Sf, Risttu] ;
// we don't need the CCode anymore
Drop Field 'CCode';
```

The resulting table looks like this:

Mapping table

Salesperson	Country
John	Sweden
Mary	Sweden
Per	Sweden
Preben	Denmark
Olle	Denmark
Ole	Norway
Risttu	Rest of the world

### Merge

The **Merge** prefix can be added to any **LOAD** or **SELECT** statement in the script to specify that the loaded table should be merged into another table. It also specifies that this statement should be run in a partial reload.

The typical use case is when you load a change log and want to use this to apply inserts, updates, and deletes to an existing table.



*For partial reload to work properly, the app must be opened with data before a partial reload is triggered.*

Perform a partial reload using the **Reload** button. You can also use the Qlik Engine JSON API.

#### Syntax:

```
Merge [only] [(SequenceNoField [, SequenceNoVar])] On ListOfKeys [Concatenate [(TableName)]] (loadstatement | selectstatement)
```

### Arguments:

Arguments

Argument	Description
only	An optional qualifier denoting that the statement should be executed only during partial reloads. The statement is disregarded during normal (non-partial) reloads.
SequenceNoField	The name of the field containing a timestamp or a sequence number that defines the order of the operations.
SequenceNoVar	The name of the variable that gets assigned the maximum value for SequenceNoField of the table being merged.
ListOfKeys	A comma separated list of field names specifying the primary key.
Operation	The first field of the load statement must contain the operation as a text string: 'Insert', 'Update', or 'Delete'. 'i', 'u' and 'd' are also accepted.

### General functionality

During a normal (non-partial) reload, the **Merge LOAD** construction works as a normal **Load** statement but with the additional functionality of removing older obsolete records and records marked for deletion. The first field of the **Load** statement must hold information about the operation: Insert, Update, or Delete.

For each loaded record, the record identifier is compared with previously loaded records, and only the latest record (according to the sequence number) will be kept. If the latest record is marked with Delete, none will be kept.

### Target table

Which table to modify is determined by the set of fields. If a table with the same set of fields (except the first field; the operation) already exists, this will be the relevant table to modify. Alternatively, a **Concatenate** prefix can be used to specify the table. If the target table is not determined, the result of the **Merge LOAD** construction is stored in a new table.

If the Concatenate prefix is used, the resulting table has a set of fields corresponding to the union of the existing table and the input to the merge. Hence, the target table may get more fields than the change log that is used as input to the merge.

A partial reload does the same as a full reload. One difference is that a partial reload rarely creates a new table. Unless you have used the **Only** clause, a target table with the same set of fields from the previous script execution always exists.

### Sequence number

If the loaded change log is an accumulated log, that is, it contains changes that already have been loaded, the parameter `SequenceNoVar` can be used in a **Where** clause to limit the amount of input data. The **Merge LOAD** could then be made to only load records where the field `SequenceNoField` is greater than `SequenceNoVar`. Upon completion, the **Merge LOAD** assigns a new value to the `SequenceNoVar` with the maximum value seen in the `SequenceNoField` field.

### Operations

The **Merge LOAD** can have fewer fields than the target table. The different operations treat missing fields differently:

**Insert:** Fields missing in the **Merge LOAD**, but existing in the target table, get a NULL in the target table.

**Delete:** Missing fields do not affect the result. The relevant records are deleted anyway.

**Update:** Fields listed in the **Merge LOAD** are updated in the target table. Missing fields are not changed. This means that the two following statements are not identical:

- Merge on Key Concatenate Load 'U' as Operation, Key, F1, Null() as F2 From ...;
- Merge on Key Concatenate Load 'U' as Operation, Key, F1 From ...;

The first statement updates the listed records and changes F2 to NULL. The second does not change F2, but instead, leaves the values in the target table.

### Examples

#### Example 1: Simple merge with specified table

In this example, an inline table named `Persons` is loaded with three rows. **Merge** then changes the table as follows:

- Adds the row, *Mary, 4* .
- Deletes the row, *Steven, 3*.
- Assigns the number *5* to *Jake* .

The `LastChangeDate` variable is set to the maximum value in the `ChangeDate` column after **Merge** is executed.

### Load script

Add the example script to your app and run it. To see the result, add the fields listed in the results column to a sheet in your app.

```
Set DateFormat='D/M/YYYY';
Persons:
load * inline [
Name, Number
Jake, 3
Jill, 2
Steven, 3
```

## 3 Script statements and keywords

---

```
];
```

```
Merge (ChangeDate, LastChangeDate) on Name Concatenate(Persons)
```

```
LOAD * inline [
```

```
Operation, ChangeDate, Name, Number
```

```
Insert, 1/1/2021, Mary, 4
```

```
Delete, 1/1/2021, Steven,
```

```
Update, 2/1/2021, Jake, 5
```

```
];
```

### Result

Prior to the **Merge Load**, the resulting table appears as follows:

Resulting table

Name	Number
Jake	3
Jill	2
Steven	3


Following the **Merge Load**, the table appears as follows:

Resulting table

ChangeDate	Name	Number
2/1/2021	Jake	5
-	Jill	2
1/1/2021	Mary	4

When the data is loaded, the **Data load progress** dialog box shows the operations that are performed:

*Data load progress dialog box*



### Example 2: Data load script with missing fields

In this example, the same data as above is loaded, but now with an ID for each person.

**Merge** changes the table as follows:

- Adds the row, *Mary, 4*.
- Deletes the row, *Steven, 3*.
- Assigns the number *5* to *Jake*.
- Assigns the number *6* to *Jill*.

### Load script

Here we use two **Merge Load** statements, one for 'Insert' and 'Delete', and a second one for the 'Update'.

Add the example script to your app and run it. To see the result, add the fields listed in the results column to a sheet in your app.

```
Set DateFormat='D/M/YYYY';
Persons:
Load * Inline [
PersonID, Name, Number
1, Jake, 3
2, Jill, 2
3, Steven, 3
```



## 3 Script statements and keywords

---

```
];
```

```
Merge (ChangeDate, LastChangeDate) on PersonID Concatenate(Persons)
Load * Inline [
Operation, ChangeDate, PersonID, Name, Number
Insert, 1/1/2021, 4, Mary, 4
Delete, 1/1/2021, 3, Steven,
];
```

```
Merge (ChangeDate, LastChangeDate) on PersonID Concatenate(Persons)
Load * Inline [
Operation, ChangeDate, PersonID, Number
Update, 2/1/2021, 1, 5
Update, 3/1/2021, 2, 6
];
```

### Result

Following the **Merge Load** statements, the table appears as follows:

Resulting table

PersonID	ChangeDate	Name	Number
1	2/1/2021	Jake	5
2	3/1/2021	Jill	6
4	1/1/2021	Mary	4

Note that the second **Merge** statement does not include the field **Name**, and as a consequence, the names have not been changed.

### Example 3: Data load script - Partial reload using a Where-clause with ChangeDate

In the following example, the **Only** argument specifies that the **Merge** command is only executed during a partial reload. Updates are filtered based on the previously captured LastChangeDate. After **Merge** is finished, LastChangeDate variable is assigned the maximum value of the ChangeDate column processed during the merge.

#### Load script

```
Merge Only (ChangeDate, LastChangeDate) on Name Concatenate(Persons)
LOAD Operation, ChangeDate, Name, Number
from [lib://ChangeFilesFolder/BulkChangesInPersonsTable.csv] (txt)
where ChangeDate >='$(LastChangeDate)';
```

### NoConcatenate

The **NoConcatenate** prefix forces two loaded tables with identical field sets to be treated as two separate internal tables, when they would otherwise be automatically concatenated.

#### Syntax:

```
NoConcatenate ( loadstatement | selectstatement )
```

---

## 3 Script statements and keywords

By default, if a table is loaded that contains an identical number of fields and matching field names to a table loaded earlier in the script, Qlik Sense will auto concatenate these two tables. This will happen even if the second table is named differently.

However, if the script prefix `noconcatenate` is included before the load statement or select statement of the second table, then these two tables will be loaded separately.

A typical use case for `noconcatenate` is when you may need to create a temporary copy of a table to perform some temporary transformations on that copy, while retaining a copy of the original data. `noconcatenate` ensures that you can make that copy without implicitly adding it back onto the source table.

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

Function example

Example	Result
Source: LOAD A,B from file1.csv; CopyOfSource: NoConcatenate LOAD A,B resident Source;	A table with A and B as measures is loaded. A second table with the same fields is loaded separately by using the <code>noconcatenate</code> variable.

### Example 1 – Implicit concatenation

Load script and results

#### Overview

In this example, you will add two load scripts in sequential order.

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- An initial dataset with dates and amounts that is sent to a table named `Transactions`.

### First load script

Transactions:

```
LOAD
*
Inline [
id, date, amount
1, 08/30/2018, 23.56
2, 09/07/2018, 556.31
3, 09/16/2018, 5.75
4, 09/22/2018, 125.00
5, 09/22/2018, 484.21
6, 09/22/2018, 59.18
7, 09/23/2018, 177.42
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- id
- date
- amount

First results table

id	date	amount
1	08/30/2018	23.56
2	09/07/2018	556.31
3	09/16/2018	5.75
4	09/22/2018	125.00
5	09/22/2018	484.21
6	09/22/2018	59.18
7	09/23/2018	177.42

### Second load script

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A second dataset with identical fields is sent to a table named sales.

Sales:

```
LOAD
*
Inline [
id, date, amount
8, 10/01/2018, 164.27
```

```
9, 10/03/2018, 384.00
10, 10/06/2018, 25.82
11, 10/09/2018, 312.00
12, 10/15/2018, 4.56
13, 10/16/2018, 90.24
14, 10/18/2018, 19.32
];
```

### Results

Load the data and go to the table.

Second results table


<b>id</b>	<b>date</b>	<b>amount</b>
1	08/30/2018	23.56
2	09/07/2018	556.31
3	09/16/2018	5.75
4	09/22/2018	125.00
5	09/22/2018	484.21
6	09/22/2018	59.18
7	09/23/2018	177.42
8	10/01/2018	164.27
9	10/03/2018	384.00
10	10/06/2018	25.82
11	10/09/2018	312.00
12	10/15/2018	4.56
13	10/16/2018	90.24
14	10/18/2018	19.32

When the script runs, the `sales` table is implicitly concatenated onto the existing `transactions` table due to the two datasets sharing an identical number of fields, with identical field names. This happens despite the second table name tag attempting to name the result set 'sales'.

You can see that the Sales dataset is implicitly concatenated by looking at the **Data load progress** log.

## 3 Script statements and keywords

Data load progress log showing Transactions data being implicitly concatenated.



### Example 2 – Use case scenario

Load script and results

#### Overview

In this use case scenario you have:

- A transactions dataset with:
  - id
  - date
  - amount (in GBP)
- A currency table with:
  - Conversion rates for USD to GBP
- A second transactions dataset with:
  - id

---

## 3 Script statements and keywords

- date
- amount (in USD)

You will load five scripts in sequential order.

- The first load script contains an initial dataset with dates and amounts in GBP that is sent to a table named `Transactions`.
- The second load script contains:
  - A second dataset with dates and amounts in USD that is sent to a table named `Transactions_in_USD`.
  - The `noconcatenate` prefix which is placed before the load statement of the `Transactions_in_USD` dataset to prevent implicit concatenation.
- The third load script contains the `join` prefix which will be used create a currency exchange rate between GBP and USD in the `Transactions_in_USD` table.
- The fourth load script contains the `concatenate` prefix which will add the `Transactions_in_USD` to the initial `Transactions` table.
- The fifth load script contains the `drop table` statement which will remove the `Transactions_in_USD` table its data has been concatenated to the `Transactions` table.

### First load script

`Transactions:`

```
Load * Inline [  
id, date, amount  
1, 12/30/2018, 23.56  
2, 12/07/2018, 556.31  
3, 12/16/2018, 5.75  
4, 12/22/2018, 125.00  
5, 12/22/2018, 484.21  
6, 12/22/2018, 59.18  
7, 12/23/2018, 177.42  
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- id
- date
- amount

First load script results

<b>id</b>	<b>date</b>	<b>amount</b>
1	12/30/2018	23.56
2	12/07/2018	556.31

<b>id</b>	<b>date</b>	<b>amount</b>
3	12/16/2018	5.75
4	12/22/2018	125.00
5	12/22/2018	484.21
6	12/22/2018	59.18
7	12/23/2018	177.42

The table shows the initial dataset with amounts in GBP.

### Second load script

```
Transactions_in_USD:
NoConcatenate
Load * Inline [
id, date, amount
8, 01/01/2019, 164.27
9, 01/03/2019, 384.00
10, 01/06/2019, 25.82
11, 01/09/2019, 312.00
12, 01/15/2019, 4.56
13, 01/16/2019, 90.24
14, 01/18/2019, 19.32
];
```

### Results

Load the data and go to the table.

#### Second load script results

<b>id</b>	<b>date</b>	<b>amount</b>
1	12/30/2018	23.56
2	12/07/2018	556.31
3	12/16/2018	5.75
4	12/22/2018	125.00
5	12/22/2018	484.21
6	12/22/2018	59.18
7	12/23/2018	177.42
8	01/01/2019	164.27
9	01/03/2019	384.00
10	01/06/2019	25.82
11	01/09/2019	312.00

## 3 Script statements and keywords

---

id	date	amount
12	01/15/2019	4.56
13	01/16/2019	90.24
14	01/18/2019	19.32

You will see that the second dataset from the `Transactions_in_USD` table has been added.

### Third load script

This load script joins a currency exchange rate from USD to GBP to the `Transactions_in_USD` table.

```
Join (Transactions_in_USD)
Load * Inline [
rate
0.7
];
```

### Results

Load the data and go to the Data model viewer. Select the `Transactions_in_USD` table and you will see that every existing record has a 'rate' field value of 0.7.

### Fourth load script

Using resident load, this load script will concatenate the `Transactions_in_USD` table to the `Transactions` table after converting the amounts into USD.

```
Concatenate (Transactions)
LOAD
id,
date,
amount * rate as amount
Resident Transactions_in_USD;
```

### Results

Load the data and go to the table. You will see new entries with amounts in GBP from lines eight to fourteen.

#### Fourth load script results

id	date	amount
1	12/30/2018	23.56
2	12/07/2018	556.31
3	12/16/2018	5.75
4	12/22/2018	125.00



<b>id</b>	<b>date</b>	<b>amount</b>
5	12/22/2018	484.21
6	12/22/2018	59.18
7	12/23/2018	177.42
8	01/01/2019	114.989
8	01/01/2019	164.27
9	01/03/2019	268.80
9	01/03/2019	384.00
10	01/06/2019	18.074
10	01/06/2019	25.82
11	01/09/2019	218.40
11	01/09/2019	312.00
12	01/15/2019	3.192
12	01/15/2019	4.56
13	01/16/2019	63.168
13	01/16/2019	90.24
14	01/18/2019	13.524
14	01/18/2019	19.32

### **Fifth load script**

This load script will drop the duplicate entries from the fourth load script results table, leaving only entries with amounts in GBP.

```
drop tables Transactions_in_USD;
```

### **Results**

Load the data and go to the table.

Fifth load script results

<b>id</b>	<b>date</b>	<b>amount</b>
1	12/30/2018	23.56
2	12/07/2018	556.31
3	12/16/2018	5.75
4	12/22/2018	125.00
5	12/22/2018	484.21

## 3 Script statements and keywords

---

id	date	amount
6	12/22/2018	59.18
7	12/23/2018	177.42
8	01/01/2019	114.989
9	01/03/2019	268.80
10	01/06/2019	18.074
11	01/09/2019	218.40
12	01/15/2019	3.192
13	01/16/2019	63.168
14	01/18/2019	13.524

After loading the fifth load script, the results table shows all fourteen transactions that existed in both transaction datasets; however, transactions 8-14 have had their amounts converted to GBP.

If we remove the `noconcatenate` prefix that was used before the `transactions_in_usd` in the second load script, the script will fail with the error: "Table 'transactions\_in\_usd' not found". This is because the `transactions_in_usd` table would have been auto concatenated onto the original `transactions` table.

### Only

The **Only** script keyword is used as an aggregation function, or as part of the syntax in partial reload prefixes **Add**, **Replace**, and **Merge**.

### Outer

The explicit **Join** prefix can be preceded by the prefix **Outer** to specify an outer join. In an outer join, all combinations between the two tables are generated. The resulting table will thus contain combinations of field values from the raw data tables where the linking field values are represented in one or both tables. The **Outer** keyword is optional and is the default join type used when a join prefix is not specified.

#### Syntax:

```
Outer Join [ (tablename) ] (loadstatement |selectstatement )
```

#### Arguments:

##### Arguments

Argument	Description
tablename	The named table to be compared to the loaded table.
loadstatement or selectstatement	The <b>LOAD</b> or <b>SELECT</b> statement for the loaded table.

Example

### Load script

Add the example script to your app and run it. To see the result, add the fields listed in the results column to a sheet in your app.

```
Table1:  
Load * inline [  
column1, column2  
A, B  
1, aa  
2, cc  
3, ee ];
```

```
Table2:  
Outer Join Load * inline [  
column1, column3  
A, C  
1, xx  
4, yy ];
```

Resulting table

Column1	Column2	Column3
A	B	C
1	aa	xx
2	cc	-
3	ee	-
4	-	yy

### Explanation

In this example, the two tables, Table1 and Table2, are merged into a single table labeled Table1. In cases like this, the **outer** prefix is often used to join several tables into a single table to perform aggregations over the values of a single table.

### Partial reload

A full reload always starts by deleting all tables in the existing data model, and then runs the load script.

A partial reload will not do this. Instead it keeps all tables in the data model and then executes only **Load** and **Select** statements preceded by an **Add**, **Merge**, or **Replace** prefix. Other data tables are not affected by the command. The **only** argument denotes that the statement should be executed only during partial reloads, and should be disregarded during full reloads. The following table summarizes statement execution for partial and full reloads.

## 3 Script statements and keywords

---

Statement	Full reload	Partial reload
Load ...	Statement will run	Statement will not run
Add/Replace/Merge Load ...	Statement will run	Statement will run
Add/Replace/Merge Only Load ...	Statement will not run	Statement will run

Partial reloads have several benefits compared to full reloads:

- Faster, because only data recently changed needs to be loaded. With large data sets the difference is significant.
- Less memory is consumed, because less data is loaded.
- More reliable, because queries to source data run faster, reducing the risk of network problems.



*For partial reload to work properly, the app must be opened with data before a partial reload is triggered.*

Perform a partial reload using the **Reload** button. You can also use the Qlik Engine JSON API.

### Limitations

A partial reload will fail if there are commands with references to tables that existed during full reload, but not during partial reload.

### Example

#### Example commands

```
LEFT JOIN(<Table_removed_after_full_reload>)  
CONCATENATE(<Table_removed_after_full_reload>)
```

Where <Table\_removed\_after\_full\_reload> is a table that existed in full reload, but not in partial reload.

### Workaround

As a workaround you can surround the command with following if-statement:

```
IF NOT IsPartialReload() THEN ... ENDIF.
```

A partial reload can remove values from the data. However, this will not be reflected in the list of distinct values, which is a table maintained internally. So, after a partial reload, the list will contain all distinct values that have existed in the field since the last full reload, which may be more than what currently exists after the partial reload. This affects the output of the FieldValueCount() and the FieldValue() functions. The FieldValueCount() could potentially return a number greater than the current number of field values.

---

## 3 Script statements and keywords

Example

### Example 1

#### Load script

Add the example script to your app and do a partial reload. To see the result, add the fields listed in the results column to a sheet in your app.

T1:

```
Add only Load distinct recno()+10 as Num autogenerate 10;
```

#### Result

Resulting table

Num	Count(Num)
11	1
12	1
13	1
14	1
15	1
16	1
17	1
18	1
19	1
20	1

#### Explanation

The statement is only executed during a partial reload. If the "distinct" prefix is omitted, the count of the **Num** field will increase with each subsequent partial reload.

### Example 2

#### Load script

Add the example script to your app. Do a full reload and view the result. Next, do a partial reload and view the result. To see the results, add the fields listed in the results column to a sheet in your app.

T1:

```
Load recno() as ID, recno() as Value autogenerate 10;
```

T1:

```
Replace only Load recno() as ID, repeat(recno(),3) as Value autogenerate 10;
```

## 3 Script statements and keywords

---

### Result

Output table after full reload

ID	Value
1	1
2	2
3	3
4	4
5	5
6	6
7	7
8	8
9	9
10	10

Output table after partial reload

ID	Value
1	111
2	222
3	333
4	444
5	555
6	666
7	777
8	888
9	999
10	101010

### Explanation

The first table is loaded during a full reload and the second table simply replaces the first table during a partial reload.

### Replace

The **Replace** script keyword is used as a string function, or as a prefix in partial reload.

### Replace

The **Replace** prefix can be added to any **LOAD** or **SELECT** statement in the script to specify that the loaded table should replace another table. It also specifies that this statement should be run in a partial reload. The **Replace** prefix can also be used in a **Map** statement.



*For partial reload to work properly, the app must be opened with data before a partial reload is triggered.*

Perform a partial reload using the **Reload** button. You can also use the Qlik Engine JSON API.

#### Syntax:

```
Replace [only] [Concatenate[(tablename)]] (loadstatement | selectstatement)
```

```
Replace [only] mapstatement
```

During a normal (non-partial) reload, the **Replace LOAD** construction will work as a normal **LOAD** statement but be preceded by a **Drop Table**. First the old table will be dropped, then records will be generated and stored as a new table.

If the **Concatenate** prefix is used, or if there exists a table with the same set of fields, this will be the relevant table to drop. Otherwise, there is no table to drop and the **Replace LOAD** construction will be identical to a normal **LOAD**.

A partial reload will do the same. The only difference is that there is always a table from the previous script execution to drop. The **Replace LOAD** construction will always first drop the old table, then create a new one.

The **Replace Map...Using** statement causes mapping to take place also during partial script execution.

#### Arguments:

##### Arguments

Argument	Description
only	An optional qualifier denoting that the statement should be executed only during partial reloads. It should be disregarded during normal (non-partial) reloads.

Examples and results:

Example	Result
Tab1: Replace LOAD * from File1.csv;	During both normal and partial reload, the Qlik Sense table Tab1 is initially dropped. Thereafter new data is loaded from File1.csv and stored in Tab1.

## 3 Script statements and keywords

Example	Result
Tab1: Replace only LOAD * from File1.csv;	During normal reload, this statement is disregarded.  During partial reload, any Qlik Sense table previously named Tab1 is initially dropped. Thereafter new data is loaded from File1.csv and stored in Tab1.
Tab1: LOAD a,b,c from File1.csv; Replace LOAD a,b,c from File2.csv;	During normal reload, the file File1.csv is first read into the Qlik Sense table Tab1, but then immediately dropped and replaced by new data loaded from File2.csv. All data from File1.csv is lost.  During partial reload, the entire Qlik Sense table Tab1 is initially dropped. Thereafter it is replaced by new data loaded from File2.csv.
Tab1: LOAD a,b,c from File1.csv; Replace only LOAD a,b,c from File2.csv;	During normal reload, data is loaded from File1.csv and stored in the Qlik Sense table Tab1. File2.csv is disregarded.  During partial reload, the entire Qlik Sense table Tab1 is initially dropped. Thereafter it is replaced by new data loaded from File2.csv. All data from File1.csv is lost.

### Right

The **Join** and **Keep** prefixes can be preceded by the prefix **right**.

If used before **join** it specifies that a right join should be used. The resulting table will only contain combinations of field values from the raw data tables where the linking field values are represented in the second table. If used before **keep**, it specifies that the first raw data table should be reduced to its common intersection with the second table, before being stored in Qlik Sense.



*Were you looking for the string function by the same name? See: [Right \(page 1473\)](#)*

#### Syntax:

```
Right (Join | Keep) [(tablename)] (loadstatement |selectstatement )
```

#### Arguments:

##### Arguments

Argument	Description
tablename	The named table to be compared to the loaded table.
loadstatement or selectstatement	The <b>LOAD</b> or <b>SELECT</b> statement for the loaded table.



### Example

#### Load script

Add the example script to your app and run it. To see the result, add the fields listed in the results column to a sheet in your app.

```
Table1:  
Load * inline [  
column1, column2  
A, B  
1, aa  
2, cc  
3, ee ];
```

```
Table2:  
Right Join Load * inline [  
column1, column3  
A, C  
1, xx  
4, yy ];
```

#### Result

Resulting table

Column1	Column2	Column3
A	B	C
1	aa	xx
4	-	yy

#### Explanation

This example demonstrates the Right Join output where only values present in the second (right) table are joined.

### Sample

The **sample** prefix to a **LOAD** or **SELECT** statement is used for loading a random sample of records from the data source.

#### Syntax:

```
Sample p ( loadstatement | selectstatement )
```

The expression that is evaluated does not define the percentage of records from the dataset that will be loaded into the Qlik Sense application, but the probability of each record that is read to be loaded into the application. In other words, specifying a value  $p = 0.5$  does not mean that 50% of the total number of records will be loaded, but instead that for each record there will be a 50% chance that it is loaded into the Qlik Sense application.

## 3 Script statements and keywords

---

### Arguments

Argument	Description
p	An arbitrary expression which evaluates to a number larger than 0 and lower or equal to 1. The number indicates the probability for a given record to be read.  All records will be read but only some of them will be loaded into Qlik Sense.

### When to use it

Sample is useful when you would like to sample data coming from a large table, to understand the nature of data, distribution or field contents. As it brings a subset of data, the data loads are faster, allowing faster testing of scripts. Unlike `First`, the `sample` function brings data from the whole table, instead of being limited to the first few rows. This can provide a more accurate representation of the data in some cases.

The following examples show two possible uses of the `sample` script prefix:

```
sample 0.15 SQL SELECT * from Longtable;  
sample(0.15) LOAD * from Longtab.csv;
```

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Example 1 – Sample from an inline table

Load script and results

#### Overview

In this example, the script loads a sample set of data from a dataset containing seven records into a table named `Transactions` from an inline table.

#### Load script

```
Transactions:  
SAMPLE 0.3  
LOAD  
*  
Inline [
```

## 3 Script statements and keywords

---

```
id, date, amount
1, 08/30/2018, 23.56
2, 09/07/2018, 556.31
3, 09/16/2018, 5.75
4, 09/22/2018, 125.00
5, 09/22/2018, 484.21
6, 09/22/2018, 59.18
7, 09/23/2018, 177.42
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- id
- amount

Add the following the measure:

```
=sum(amount)8
```

Results table

id	date	=Sum(amount)
2	09/07/2018	556.31
4	09/22/2018	125
1	08/30/2018	23.56
3	09/16/2018	5.75

In the iteration of the load used in this example, all seven records were read, but only four records were loaded into the data table. Any re-run load could result in a different number, and a different set of records being loaded into the application.

### Example 2 – Sample from an autogenerated table

Load script and results

#### Overview

In this example, using `Autogenerate`, a dataset of 100 records is created with the fields `date`, `id`, and `amount`. However, the `sample` prefix is used, with a value of 0.1.

#### Load script

```
SampleData:
Sample 0.1
LOAD
RecNo() AS id,
MakeDate(2013, Ceil(Rand() * 12), Ceil(Rand() * 29)) as date,
Rand() * 1000 AS amount
```

Autogenerate(100);

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- id
- amount

Add the following the measure:

Results table

id	date	=Sum(amount)
48	9/28/2013	763
20	5/15/2013	752
19	11/8/2013	657
25	3/24/2013	522
27	8/23/2013	389
81	6/1/2013	53
100	8/15/2013	17

In the iteration of the load used in this example, seven records were loaded from the created dataset. Once again, any re-run load could result in a different number, and a different set of records being loaded into the application.

## Semantic

The `semantic` load prefix creates a special type of field that can be used in Qlik Sense to connect and manage relational data, such as tree structures, self-referencing parent-child structured data and/or data that can be described as a graph.

Note that the `semantic` load can function similarly to the *Hierarchy* (page 63) and *HierarchyBelongsTo* (page 65) prefixes. All three prefixes can be used as building blocks in effective front-end solutions for traversing relational data.

### Syntax:

```
Semantic( loadstatement | selectstatement)
```

A semantic load expects an input that is exactly three or four fields wide with a strict definition of what each ordered field represents, as shown in the table below:

## 3 Script statements and keywords

### Semantic load fields

Field name	Field description
1st Field:	This tag is a representation of the first of two objects between which there is a relationship.
2nd Field:	This tag will be used to describe the “forward” relationship between the first and second object. If the first object is a child and the second object is a parent, you can create a relationship tab that states “parent” or “parent of” as if you are following the relationship from child to parent.
3rd Field:	This tag is a representation of the second of two objects between which there is a relationship.
4th Field:	This field is optional. This tag describes the “backward” or “inverse” relationship between the first and second object. If the first object is a child and the second object is a parent, a relationship tab could state “child” or “child of” as if you are following the relationship from parent to child. If you do not add a fourth field, then the second field tag will be used to describe the relationship in either direction. In that case, an arrow symbol is automatically added as part of the tag.

The following code is an example of the `semantic` prefix.

```
Semantic
Load
Object,
'Parent' AS Relationship,
NeighbouringObject AS Object,
'Child' AS Relationship
from graphdata.csv;
```



*It is allowed and typical practice to label the third field the same as the first field. This creates a self-referencing lookup, so that you can follow object(s) to the related object(s) one relationship step away at a time. If the 3rd field does not carry the same name, then the end result will be a simple lookup from an object(s) to its direct relational neighbor(s) one step away only, which is an output of little practical use.*

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the

## 3 Script statements and keywords

---

Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Related functions

#### Functions

*Hierarchy (page 63)*

*HierarchyBelongsTo (page 65)*

#### Interaction

The Hierarchy load prefix is used to divide and organize nodes in parent-child and other graph-like data structures and transform them into tables.

The HierarchyBelongsTo load prefix is used to locate and organize the ancestors of parent-child and other graph-like data structures and transform them into tables.

### Example - Creating a special field for connecting relationships using the semantic prefix

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset representing geography relation records which is loaded into a table named GeographyTree.
  - Each entry has an ID at the beginning of the line and a ParentID at the end of the line.
- The semantic prefix which will add one special behavior field labeled, `relation`.

#### Load script

GeographyTree:

LOAD

```
ID,  
Geography,  
if(ParentID='',null(),ParentID) AS ParentID
```

INLINE [

```
ID,Geography,ParentID
```

```
1,world
```

```
2,Europe,1
```

```
3,Asia,1
```

```
4,North America,1
```

```
5,South America,1
```

```
6,UK,2
```

```
7,Germany,2
```

```
8,Sweden,2
```

```
9,South Korea,3
```

```
10,North Korea,3
```

## 3 Script statements and keywords

---

```
11,China,3
12,London,6
13,Birmingham,6
];
```

```
SemanticTable:
Semantic Load
    ID as ID,
    'Parent' as Relation,
    ParentID as ID,
    'Child' as Relation
resident GeographyTree;
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions.

- Id
- Geography

Then, create a filter pane with `relation` as a dimension. Click **Done editing**.

Results table

<b>Id</b>	<b>Geography</b>
1	World
2	Europe
3	Asia
4	North America
5	South America
6	UK
7	Germany
8	Sweden
9	South Korea
10	North Korea
11	China
12	London
13	Birmingham

Filter pane

### Relation

Child

Parent

## 3 Script statements and keywords

---

Click **Europe** from the geography dimension in the table and click **Child** from the relation dimension in the filter pane. Note the expected result in the table:

Results table showing  
"children" of Europe

<b>Id</b>	<b>Geography</b>
6	UK
7	Germany
8	Sweden

Clicking **Child** again will show places that are "children" of the UK, one step further down.

Results table showing  
"children" of UK

<b>Id</b>	<b>Geography</b>
12	London
13	Birmingham

### Unless

The **unless** prefix and suffix is used for creating a conditional clause which determines whether a statement or exit clause should be evaluated or not. It may be seen as a compact alternative to the full **if..end if** statement.

#### Syntax:

```
(Unless condition statement | exitstatement Unless condition )
```

The **statement** or the **exitstatement** will only be executed if **condition** is evaluated to False.

The **unless** prefix may be used on statements which already have one or several other statements, including additional **when** or **unless** prefixes.

#### Arguments

<b>Argument</b>	<b>Description</b>
condition	A logical expression evaluating to True or False.
statement	Any Qlik Sense script statement except control statements.
exitstatement	An <b>exit for</b> , <b>exit do</b> or <b>exit sub</b> clause or an <b>exit script</b> statement.

### When to use it

The `unless` statement returns a Boolean result. Typically, this type of function will be used as a condition when the user would like to conditionally load or exclude parts of the script.

The following lines show three examples of how the `unless` function may be used:

```
exit script unless A=1;  
unless A=1 LOAD * from myfile.csv;
```



---

## 3 Script statements and keywords

---

```
unless A=1 when B=2 drop table Tab1;
```

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Example 1 – Unless prefix

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The creation of variable A, which is given a value of 1.
- A dataset which is loaded into a table named Transactions, unless the variable A = 2.

#### Load script

```
LET A = 1;

UNLESS A = 2

Transactions:
LOAD
*
Inline [
id, date, amount
1, 08/30/2018, 23.56
2, 09/07/2018, 556.31
3, 09/16/2018, 5.75
4, 09/22/2018, 125.00
5, 09/22/2018, 484.21
6, 09/22/2018, 59.18
7, 09/23/2018, 177.42
];
```

#### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- id
- date
- amount

Results table

id	date	amount
1	08/30/2018	23.56
2	09/07/2018	556.31
3	09/16/2018	5.75
4	09/22/2018	125.00
5	09/22/2018	484.21
6	09/22/2018	59.18
7	09/23/2018	177.42

Because the variable A is assigned the value of 1 at the start of the script, the condition following the `unless` prefix is evaluated, returning a result of `FALSE`. As a result, the script continues to run the `Load` statement. In the results table, all the records from the `Transactions` table can be seen.

If this variable value is set to equal to 2, no data will be loaded into the data model.

### Example 2 – Unless suffix

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script starts by loading an initial dataset into a table named `transactions`. The script is then terminated unless there are less than 10 records in the `Transactions` table.

If this condition does not result in a termination of the script, a further set of transactions is concatenated into the `transactions` table and this process is repeated.

#### Load script

Transactions:

```
LOAD
```

```
*
```

```
Inline [
```

```
id, date, amount
```

```
1, 08/30/2018, 23.56
```

```
2, 09/07/2018, 556.31
```

```
3, 09/16/2018, 5.75
```

```
4, 09/22/2018, 125.00
```

```
5, 09/22/2018, 484.21
```

## 3 Script statements and keywords

---

```
6, 09/22/2018, 59.18
7, 09/23/2018, 177.42
];
```

```
exit script unless NoOfRows('Transactions') < 10 ;
```

```
Concatenate
LOAD
*
Inline [
id, date, amount
8, 10/01/2018, 164.27
9, 10/03/2018, 384.00
10, 10/06/2018, 25.82
11, 10/09/2018, 312.00
12, 10/15/2018, 4.56
13, 10/16/2018, 90.24
14, 10/18/2018, 19.32
];
```

```
exit script unless NoOfRows('Transactions') < 10 ;
```

```
Concatenate
LOAD
*
Inline [
id, date, amount
15, 10/01/2018, 164.27
16, 10/03/2018, 384.00
17, 10/06/2018, 25.82
18, 10/09/2018, 312.00
19, 10/15/2018, 4.56
20, 10/16/2018, 90.24
21, 10/18/2018, 19.32
];
```

```
exit script unless NoOfRows('Transactions') < 10 ;
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- id
- date
- amount

Results table

id	date	amount
1	08/30/2018	23.56

id	date	amount
2	09/07/2018	556.31
3	09/16/2018	5.75
4	09/22/2018	125.00
5	09/22/2018	484.21
6	09/22/2018	59.18
7	09/23/2018	177.42
8	10/01/2018	164.27
9	10/03/2018	384.00
10	10/06/2018	25.82
11	10/09/2018	312.00
12	10/15/2018	4.56
13	10/16/2018	90.24
14	10/18/2018	19.32

There are seven records in each of the three datasets of the load script.

The first dataset (with transaction id 1 through 7) is loaded into the application. The `unless` condition evaluates whether there are less than 10 rows in the `Transactions` table. This evaluates to `TRUE`, and therefore the second dataset (with transaction id 8 through 14) is loaded into the application. The second `unless` condition evaluates if there are less than 10 records in the `Transactions` table. This evaluates to `FALSE`, and so the script terminates.

### Example 3 – Multiple Unless prefixes

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

In this example, a dataset containing one transaction is created as a table called `Transactions`. A 'for' loop is then triggered, in which two nested `unless` statements evaluate:

1. Unless there are more than 100 records in the `Transactions` table
2. Unless the number of records in the `Transactions` table is a multiple of 6

If these conditions are `FALSE`, a further seven records are generated and concatenated onto the existing `Transactions` table. This process is repeated until one of the two transactions returns a value of `TRUE`.

### Load script

```
Transactions:
Load
    0 as id
Autogenerate 1;

For i = 1 to 100
    unless NoOfRows('Transactions') > 100 unless mod(NoOfRows('Transactions'),6) = 0
        Concatenate
            Load
if(isnull(Peek(id)),1,peek(id)+1) as id
                Autogenerate 7;
    next i
```

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension: id.

Results table

id
0
1
2
3
4
5
+30 more rows

The nested unless statements that occur in the 'for' loop evaluate the following:

1. Are there more than 100 rows in the `Transactions` table?
2. Is the total number of records in the `Transactions` table a multiple of 6?

Whenever both unless statements return a value of `FALSE`, a further seven records are generated and concatenated onto the existing `Transactions` table.

These statements return a value of `FALSE` five times, at which point there are a total of 36 rows of data in the `Transactions` table.

After this, the second unless statement returns a value of `TRUE`, and therefore the load statement following this will no longer be executed.

### When

The **when** prefix and suffix is used for creating a conditional clause which determines whether a statement or exit clause should be executed or not. It may be seen as a compact alternative to the full **if..end if** statement.

#### Syntax:

```
(when condition statement | exitstatement when condition )
```

**Return data type:** Boolean

In Qlik Sense, the Boolean true value is represented by -1, and the false value is represented by 0.

The **statement** or the **exitstatement** will only be executed if condition is evaluated to TRUE.

The when prefix may be used on statements which already have one or several other statements, including additional when or unless prefixes.

#### When to use it

The when statement returns a Boolean result. Typically, this type of function will be used as a condition when the user would like to load or exclude parts of a script.

#### Arguments

Argument	Description
condition	A logical expression evaluating to TRUE or FALSE
statement	Any Qlik Sense script statement except control statements.
exitstatement	An <b>exit for</b> , <b>exit do</b> or <b>exit sub</b> clause or an <b>exit script</b> statement.

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the SET DateFormat statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

## 3 Script statements and keywords

---

### Function examples

Example	Result
<code>exit script when A=1;</code>	When the statement <code>A=1</code> is evaluated to be TRUE, the script will stop.
<code>when A=1 LOAD * from myfile.csv;</code>	When the statement <code>A=1</code> is evaluated to be TRUE, the <code>myfile.csv</code> will be loaded.
<code>when A=1 unless B=2 drop table Tab1;</code>	When the statement <code>A=1</code> is evaluated to be TRUE, and if <code>B=2</code> is evaluated to be FALSE, then the <code>Tab1</code> table will be dropped.

### Example 1 – When prefix

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset with dates and amounts that is sent to a table named 'Transactions'.
- The `LET` statement which states that the variable `A` is created and has the value of 1.
- The `when` condition which provides the condition that if `A` equals 1, then the script will continue to load.

#### Load script

```
LET A = 1;

WHEN A = 1

Transactions:
LOAD
*
Inline [
id, date, amount
1, 08/30/2018, 23.56
2, 09/07/2018, 556.31
3, 09/16/2018, 5.75
4, 09/22/2018, 125.00
5, 09/22/2018, 484.21
6, 09/22/2018, 59.18
7, 09/23/2018, 177.42
];
```

#### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- id
- date
- amount

Results table

id	date	amount
1	08/30/2018	23.56
2	09/07/2018	556.31
3	09/16/2018	5.75
4	09/22/2018	125.00
5	09/22/2018	484.21
6	09/22/2018	59.18
7	09/23/2018	177.42

Because the variable `A` is assigned the value of 1 at the start of the script, the condition following the `when` prefix is evaluated and returns a result of `TRUE`. Because it returns a `TRUE` result, the script continues to run the load statement. All the records from the results table can be seen.

If this variable value was set to any value not equal to 1, no data would be loaded into the data model.

### Example 2 – When suffix

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- Three datasets with dates and amounts that are sent to a table named 'Transactions'.
  - The first dataset contains transactions 1-7.
  - The second dataset contains transactions 8-14.
  - The third dataset contains transactions 15-21.
- A `when` condition which determines whether the 'Transactions' table contains more than ten rows. If any of the `when` statements are evaluated to be `TRUE`, the load script will stop. This condition is placed at the end of each of the three datasets.

#### Load script

```
Transactions:
LOAD
*
Inline [
```



## 3 Script statements and keywords

---

```
id, date, amount
1, 08/30/2018, 23.56
2, 09/07/2018, 556.31
3, 09/16/2018, 5.75
4, 09/22/2018, 125.00
5, 09/22/2018, 484.21
6, 09/22/2018, 59.18
7, 09/23/2018, 177.42
];
```

```
exit script when NoOfRows('Transactions') > 10 ;
```

Concatenate

```
LOAD
```

```
*
```

```
Inline [
```

```
id, date, amount
8, 10/01/2018, 164.27
9, 10/03/2018, 384.00
10, 10/06/2018, 25.82
11, 10/09/2018, 312.00
12, 10/15/2018, 4.56
13, 10/16/2018, 90.24
14, 10/18/2018, 19.32
];
```

```
exit script when NoOfRows('Transactions') > 10 ;
```

Concatenate

```
LOAD
```

```
*
```

```
Inline [
```

```
id, date, amount
15, 10/01/2018, 164.27
16, 10/03/2018, 384.00
17, 10/06/2018, 25.82
18, 10/09/2018, 312.00
19, 10/15/2018, 4.56
20, 10/16/2018, 90.24
21, 10/18/2018, 19.32
];
```

```
exit script when NoOfRows('Transactions') > 10 ;
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- id
- date
- amount

Results table

id	date	amount
1	08/30/2018	23.56
2	09/07/2018	556.31
3	09/16/2018	5.75
4	09/22/2018	125.00
5	09/22/2018	484.21
6	09/22/2018	59.18
7	09/23/2018	177.42
8	10/01/2018	164.27
9	10/03/2018	384.00
10	10/06/2018	25.82
11	10/09/2018	312.00
12	10/15/2018	4.56
13	10/16/2018	90.24
14	10/18/2018	19.32

There are seven transactions in each of the three datasets. The first dataset contains transaction 1-7 and is loaded into the application. The `when` condition following this load statement is evaluated as `FALSE` because there are less than ten rows in the 'Transactions' table. The load script continues to the next dataset.

The second dataset contains transaction 8-14 and is loaded into the application. The second `when` condition evaluates as `TRUE` because there are more than ten rows in the 'Transactions' table. Therefore, the script terminates.

### Example 3 – Multiple When prefixes

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a single transaction is created as a table called 'Transactions'.
- A `For` loop which is triggered contains two nested `when` conditions which evaluate whether:
  1. There are less than 100 records in the 'Transactions' table.
  2. The number of records in the 'Transactions' table is not a multiple of 6.

### Load script

```
RowsCheck = NoOfRows('Transactions') < 100 or mod(NoOfRows('Transactions'),6) <> 0;
Transactions:
Load
    0 as id
Autogenerate 1;
For i = 1 to 100
    when(RowsCheck)
        Concatenate
        Load
            if(isnull(peek(id)),1,peek(id)+1) as id
        Autogenerate 7;
next i
```

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension:

- id

The results table only shows the first five transaction IDs but the load script creates 36 rows and then terminates once the when condition is fulfilled.

Results table

id
0
1
2
3
4
5
+30 more rows

The nested when conditions in the For loop evaluate the following questions:

- Are there less than 100 rows in the 'Transactions' table?
- Is the total number of records in the 'Transactions' table not a multiple of six?

Whenever both when conditions return a value of TRUE, a further seven records are generated and concatenated onto the existing 'Transactions' table.

The when conditions return a TRUE value five times. At that point there are a total of 36 rows of data in the 'Transactions' table.

When 36 rows of data are created in the 'Transactions' table, the second when statement returns a value of FALSE and therefore the load statement following this will no longer be executed.

### 3.3 Script regular statements

Regular statements are typically used for manipulating data in one way or another. These statements may be written over any number of lines in the script and must always be terminated by a semicolon, ";".

All script keywords can be typed with any combination of lower case and upper case characters. Field and variable names used in the statements are however case sensitive.

#### Script regular statements overview

Each function is described further after the overview. You can also click the function name in the syntax to immediately access the details for that specific function.

##### Alias

The **alias** statement is used for setting an alias according to which a field will be renamed whenever it occurs in the script that follows.

```
Alias fieldname as aliasname {,fieldname as aliasname}
```

##### Autonumber

This statement creates a unique integer value for each distinct evaluated value in a field encountered during the script execution.

```
AutoNumber fields [Using namespace] ]
```

##### Binary

The **binary** statement is used for loading the data from another QlikView document, including section access data.

```
Binary [path] filename
```

##### comment

Provides a way of displaying the field comments (metadata) from databases and spreadsheets. Field names not present in the app will be ignored. If multiple occurrences of a field name are found, the last value is used.

```
Comment field *fieldlist using mapname  
Comment field fieldname with comment
```

##### comment table

Provides a way of displaying the table comments (metadata) from databases or spreadsheets.

```
Comment table tablelist using mapname  
Comment table tablename with comment
```

### Connect



*This functionality is not available in Qlik Sense SaaS.*

The **CONNECT** statement is used to define Qlik Sense access to a general database through the OLE DB/ODBC interface. For ODBC, the data source first needs to be specified using the ODBC administrator.

```
ODBC Connect TO connect-string [ ( access_info ) ]
OLEDB CONNECT TO connect-string [ ( access_info ) ]
CUSTOM CONNECT TO connect-string [ ( access_info ) ]
LIB CONNECT TO connection
```

### Declare

The **Declare** statement is used to create field definitions, where you can define relations between fields or functions. A set of field definitions can be used to automatically generate derived fields, which can be used as dimensions. For example, you can create a calendar definition, and use that to generate related dimensions, such as year, month, week and day, from a date field.

```
definition_name:
Declare [Field[s]] Definition [Tagged tag_list ]
[Parameters parameter_list ]
Fields field_list
[Groups group_list ]

<definition name>:
Declare [Field] [s] Definition
Using <existing_definition>
[With <parameter_assignment> ]
```

### Derive

The **Derive** statement is used to generate derived fields based on a field definition created with a **Declare** statement. You can either specify which data fields to derive fields for, or derive them explicitly or implicitly based on field tags.

```
Derive [Field[s]] From [Field[s]] field_list Using definition
Derive [Field[s]] From Explicit [Tag[s]] (tag_list) Using definition
Derive [Field[s]] From Implicit [Tag[s]] Using definition
```

### Direct Query

The **DIRECT QUERY** statement allows you to access tables through an ODBC or OLE DB connection using the Direct Discovery function.

```
Direct Query [path]
```

### Directory

The **Directory** statement defines which directory to look in for data files in subsequent **LOAD** statements, until a new **Directory** statement is made.

## 3 Script statements and keywords

**Directory** [path]

### Disconnect

The **Disconnect** statement terminates the current ODBC/OLE DB/Custom connection. This statement is optional.

**Disconnect**

### drop field

One or several Qlik Sense fields can be dropped from the data model, and thus from memory, at any time during script execution, by means of a **drop field** statement. The "distinct" property of a table is removed after a **drop field** statement.



Both **drop field** and **drop fields** are allowed forms with no difference in effect. If no table is specified, the field will be dropped from all tables where it occurs.

```
Drop field fieldname [ , fieldname2 ...] [from tablename1 [ , tablename2 ...]]  
drop fields fieldname [ , fieldname2 ...] [from tablename1 [ , tablename2 ...]]
```

### drop table

One or several Qlik Sense internal tables can be dropped from the data model, and thus from memory, at any time during script execution, by means of a **drop table** statement.



The forms **drop table** and **drop tables** are both accepted.

```
Drop table tablename [ , tablename2 ...]  
drop tables[ tablename [ , tablename2 ...]]
```

### Execute

The **Execute** statement is used to run other programs while Qlik Sense is loading data. For example, to make conversions that are necessary.

**Execute** commandline

### FlushLog

The **FlushLog** statement forces Qlik Sense to write the content of the script buffer to the script log file.

**FlushLog**

### Force

The **force** statement forces Qlik Sense to interpret field values of subsequent **LOAD** and **SELECT** statements as written with only upper case letters, with only lower case letters, as always capitalized or as they appear (mixed). This statement makes it possible to associate field values from tables made according to different conventions.

## 3 Script statements and keywords

---

```
Force ( capitalization | case upper | case lower | case mixed )
```

### LOAD

The **LOAD** statement loads fields from a file, from data defined in the script, from a previously loaded table, from a web page, from the result of a subsequent **SELECT** statement or by generating data automatically. It is also possible to load data from analytic connections.

```
Load [ distinct ] *fieldlist  
[ ( from file [ format-spec ] |  
from_field fieldsource [ format-spec ]  
inline data [ format-spec ] |  
resident table-label |  
autogenerate size ) ]  
[ where criterion | while criterion ]  
[ group_by groupbyfieldlist ]  
[ order_by orderbyfieldlist ]  
[ extension pluginname.functionname (tabledescription) ]
```

### Let

The **let** statement is a complement to the **set** statement, used for defining script variables. The **let** statement, in opposition to the **set** statement, evaluates the expression on the right side of the '=' at script run time before it is assigned to the variable.

```
Let variablename=expression
```

### Loosen Table

One or more Qlik Sense internal data tables can be explicitly declared loosely coupled during script execution by using a **Loosen Table** statement. When a table is loosely coupled, all associations between field values in the table are removed. A similar effect could be achieved by loading each field of the loosely coupled table as independent, unconnected tables. Loosely coupled can be useful during testing to temporarily isolate different parts of the data structure. A loosely coupled table can be identified in the table viewer by the dotted lines. The use of one or more **Loosen Table** statements in the script will make Qlik Sense disregard any setting of tables as loosely coupled made before the script execution.

```
tablename [ , tablename2 ... ]  
Loosen Tables tablename [ , tablename2 ... ]
```

### Map ... using

The **map ... using** statement is used for mapping a certain field value or expression to the values of a specific mapping table. The mapping table is created through the **Mapping** statement.

```
Map *fieldlist Using mapname
```

### NullAsNull

The **NullAsNull** statement turns off the conversion of NULL values to string values previously set by a **NullAsValue** statement.

```
NullAsNull *fieldlist
```

## 3 Script statements and keywords

---

### NullAsValue

The **NullAsValue** statement specifies for which fields that NULL should be converted to a value.

```
NullAsValue *fieldlist
```

### Qualify

The **Qualify** statement is used for switching on the qualification of field names, i.e. field names will get the table name as a prefix.

```
Qualify *fieldlist
```

### Rem

The **rem** statement is used for inserting remarks, or comments, into the script, or to temporarily deactivate script statements without removing them.

```
Rem string
```

### Rename Field

This script function renames one or more existing Qlik Sense field(s) after they have been loaded.

```
Rename field (using mapname | oldname to newname{ , oldname to newname })
```

```
Rename Fields (using mapname | oldname to newname{ , oldname to newname })
```

### Rename Table

This script function renames one or more existing Qlik Sense internal table(s) after they have been loaded.

```
Rename table (using mapname | oldname to newname{ , oldname to newname })
```

```
Rename Tables (using mapname | oldname to newname{ , oldname to newname })
```

### Section

With the **section** statement, it is possible to define whether the subsequent **LOAD** and **SELECT** statements should be considered as data or as a definition of the access rights.

```
Section (access | application)
```

### Select

The selection of fields from an ODBC data source or OLE DB provider is made through standard SQL **SELECT** statements. However, whether the **SELECT** statements are accepted depends on the ODBC driver or OLE DB provider used.

```
Select [all | distinct | distinctrow | top n [percent] ] *fieldlist
```

```
From tablelist
```

```
[Where criterion ]
```

```
[Group by fieldlist [having criterion ] ]
```

```
[Order by fieldlist [asc | desc] ]
```

```
[ (Inner | Left | Right | Full)Join tablename on fieldref = fieldref ]
```



## 3 Script statements and keywords

---

### Set

The **set** statement is used for defining script variables. These can be used for substituting strings, paths, drives, and so on.

```
Set variablename=string
```

### Sleep

The **sleep** statement pauses script execution for a specified time.

```
Sleep n
```

### SQL

The **SQL** statement allows you to send an arbitrary SQL command through an ODBC or OLE DB connection.

```
SQL sql_command
```

### SQLColumns

The **sqlcolumns** statement returns a set of fields describing the columns of an ODBC or OLE DB data source, to which a **connect** has been made.

```
SQLColumns
```

### SQLTables

The **sqltables** statement returns a set of fields describing the tables of an ODBC or OLE DB data source, to which a **connect** has been made.

```
SQLTables
```

### SQLTypes

The **sqltypes** statement returns a set of fields describing the types of an ODBC or OLE DB data source, to which a **connect** has been made.

```
SQLTypes
```

### Star

The string used for representing the set of all the values of a field in the database can be set through the **star** statement. It affects the subsequent **LOAD** and **SELECT** statements.

```
Star is [ string ]
```

### Store

The **Store** statement creates a QVD, Parquet, CSV, or TXT file.

```
Store [ *fieldlist from] table into filename [ format-spec ];
```

### Tag

This script statement provides a way to assign tags to one or more fields or tables. If an attempt to tag a field or table not present in the app is made, the tagging will be ignored. If conflicting occurrences of a field or tag name are found, the last value is used.

```
Tag[field|fields] fieldlist with tagname
```

## 3 Script statements and keywords

---

```
Tag [field|fields] fieldlist using mapname
Tag table tablelist with tagname
```

### Trace

The **trace** statement writes a string to the **Script Execution Progress** window and to the script log file, when used. It is very useful for debugging purposes. Using **\$**-expansions of variables that are calculated prior to the **trace** statement, you can customize the message.

```
Trace string
```

### Unmap

The **Unmap** statement disables field value mapping specified by a previous **Map ... Using** statement for subsequently loaded fields.

```
Unmap *fieldlist
```

### Unqualify

The **Unqualify** statement is used for switching off the qualification of field names that has been previously switched on by the **Qualify** statement.

```
Unqualify *fieldlist
```

### Untag

This script statement provides a way to remove tags from fields or tables. If an attempt to untag a field or table not present in the app is made, the untagging will be ignored.

```
Untag[field|fields] fieldlist with tagname
Tag [field|fields] fieldlist using mapname
Tag table tablelist with tagname
```

## Alias

The **alias** statement is used for setting an alias according to which a field will be renamed whenever it occurs in the script that follows.

### Syntax:

```
alias fieldname as aliasname {,fieldname as aliasname}
```

### Arguments:

Arguments

Argument	Description
fieldname	The name of the field in your source data
aliasname	An alias name you want to use instead

## 3 Script statements and keywords

---

Examples and results:

Example	Result
Alias ID_N as NameID;	
Alias A as Name, B as Number, C as Date;	The name changes defined through this statement are used on all subsequent <b>SELECT</b> and <b>LOAD</b> statements. A new alias can be defined for a field name by a new <b>alias</b> statement at any subsequent position in the script.

### AutoNumber

This statement creates a unique integer value for each distinct evaluated value in a field encountered during the script execution.

You can also use the *autonumber* (page 582) function inside a **LOAD** statement, but this has some limitations when you want to use an optimized load. You can create an optimized load by loading the data from a **QVD** file first, and then using the **AutoNumber** statement to convert values to symbol keys.

#### Syntax:

```
AutoNumber *fieldlist [Using namespace] ]
```

#### Arguments:

##### Arguments

Argument	Description
*fieldlist	A comma-separated list of the fields where the values should be replaced by a unique integer value.  You can use wildcard characters ? and * in the field names to include all fields with matching names. You can also use * to include all fields. You need to quote field names when wildcards are used.
namespace	<b>Using namespace</b> is optional. You can use this option if you want to create a namespace, where identical values in different fields share the same key.  If you do not use this option, all fields will have a separate key index.

#### Limitations:

When you have several **LOAD** statements in the script, you need to place the **AutoNumber** statement after the final **LOAD** statement.

## 3 Script statements and keywords

---

Example - script with AutoNumber

### Script example

In this example, the data is first loaded without the **AutoNumber** statement. The **AutoNumber** statement is then added to show the effect.

### Data used in the example

Load the following data as an inline load in the data load editor to create the script example below. Leave the **AutoNumber** statement commented out for now.

```
RegionSales:
LOAD *,
Region &' '|& Year &' '|& Month as KeyToOtherTable
INLINE
[ Region, Year, Month, Sales
North, 2014, May, 245
North, 2014, May, 347
North, 2014, June, 127
South, 2014, June, 645
South, 2013, May, 367
South, 2013, May, 221
];
```

```
Budget:
LOAD Budget,
Region &' '|& Year &' '|& Month as KeyToOtherTable
INLINE
[Region, Year, Month, Budget
North, 2014, May, 200
North, 2014, May, 350
North, 2014, June, 150
South, 2014, June, 500
South, 2013, May, 300
South, 2013, May, 200
];
```

```
//AutoNumber KeyToOtherTable;
```

### Create visualizations

Create two table visualizations in a Qlik Sense sheet. Add **KeyToOtherTable**, **Region**, **Year**, **Month**, and **Sales** as dimensions to the first table. Add **KeyToOtherTable**, **Region**, **Year**, **Month**, and **Budget** as dimensions to the second table.

### Result

RegionSales table

KeyToOtherTable	Region	Year	Month	Sales
North 2014 June	North	2014	June	127

### 3 Script statements and keywords

---

<b>KeyToOtherTable</b>	<b>Region</b>	<b>Year</b>	<b>Month</b>	<b>Sales</b>
North 2014 May	North	2014	May	245
North 2014 May	North	2014	May	347
South 2013 May	South	2013	May	221
South 2013 May	South	2013	May	367
South 2014 June	South	2014	June	645

Budget table

<b>KeyToOtherTable</b>	<b>Region</b>	<b>Year</b>	<b>Month</b>	<b>Budget</b>
North 2014 June	North	2014	June	150
North 2014 May	North	2014	May	200
North 2014 May	North	2014	May	350
South 2013 May	South	2013	May	200
South 2013 May	South	2013	May	300
South 2014 June	South	2014	June	500

#### Explanation

The example shows a composite field **KeyToOtherTable** that links the two tables. **AutoNumber** is not used. Note the length of the **KeyToOtherTable** values.

#### Add AutoNumber statement

Uncomment the **AutoNumber** statement in the load script:

```
AutoNumber KeyToOtherTable;
```

#### Result

RegionSales table

<b>KeyToOtherTable</b>	<b>Region</b>	<b>Year</b>	<b>Month</b>	<b>Sales</b>
1	North	2014	June	127
1	North	2014	May	245
2	North	2014	May	347
3	South	2013	May	221
4	South	2013	May	367
4	South	2014	June	645

## 3 Script statements and keywords

---

Budget table

KeyToOtherTable	Region	Year	Month	Budget
1	North	2014	June	150
1	North	2014	May	200
2	North	2014	May	350
3	South	2013	May	200
4	South	2013	May	300
4	South	2014	June	500

### Explanation

The **KeyToOtherTable** field values have been replaced with unique integer values and, as a result, the length of the field values has been reduced, thus conserving memory. The key fields in both tables are affected by **AutoNumber** and the tables remain linked. The example is brief for demonstration purposes, but would be meaningful with a table containing a large number of rows.

### Binary

The **binary** statement is used for loading the data from another Qlik Sense app or QlikView document, including section access data. Other elements of the app are not included, for example, sheets, stories, visualizations, master items or variables.

Only one **binary** statement is allowed in the script. The **binary** statement must be the first statement of the script, even before the SET statements usually located at the beginning of the script.

#### Syntax:

```
binary [path] filename
```

### Arguments:

#### Arguments

Argument	Description
path	<p>The path to the file which should be a reference to a folder data connection. This is required if the file is not located in the Qlik Sense working directory.</p> <p><b>Example: 'lib://Table Files/'</b></p> <p>In legacy scripting mode, the following path formats are also supported:</p> <ul style="list-style-type: none"> <li>absolute</li> </ul> <p><b>Example: c:\data\</b></p> <ul style="list-style-type: none"> <li>relative to the app containing this script line.</li> </ul> <p><b>Example: data\</b></p>
filename	The name of the file, including the file extension .qvw or .qvf.

### Limitations:

You cannot use **binary** to load data from an app on the same Qlik Sense Enterprise deployment by referring to the app ID. You can only load from a .qvf file.

### Examples

String	Description
Binary lib://DataFolder/customer.qvw;	In this example, the file must be in located in the <b>Folder</b> data connection. This may be, for example, a folder that your administrator creates on the Qlik Sense server. Click <b>Create new connection</b> in the data load editor and then select <b>Folder</b> under <b>File locations</b> .
Binary customer.qvf;	In this example, the file must be in located in the Qlik Sense working directory.
Binary c:\qv\customer.qvw;	This example using an absolute file path will only work in legacy scripting mode.

### Comment field

Provides a way of displaying the field comments (metadata) from databases and spreadsheets. Field names not present in the app will be ignored. If multiple occurrences of a field name are found, the last value is used.

#### Syntax:

```
comment [fields] *fieldlist using mapname  
comment [field] fieldname with comment
```

The map table used should have two columns, the first containing field names and the second the comments.

#### Arguments:

##### Arguments

Argument	Description
<i>*fieldlist</i>	A comma separated list of the fields to be commented. Using * as field list indicates all fields. The wildcard characters * and ? are allowed in field names. Quoting of field names may be necessary when wildcards are used.
<i>mapname</i>	The name of a mapping table previously read in a mapping <b>LOAD</b> or mapping <b>SELECT</b> statement.
<i>fieldname</i>	The name of the field that should be commented.
<i>comment</i>	The comment that should be added to the field.

#### Example 1:

```
commentmap:  
mapping LOAD * inline [  
a,b  
Alpha,This field contains text values  
Num,This field contains numeric values  
];  
comment fields using commentmap;
```

#### Example 2:

```
comment field Alpha with AFieldContainingCharacters;  
comment field Num with '*A field containing numbers';  
comment Gamma with 'Mickey Mouse field';
```

### Comment table

Provides a way of displaying the table comments (metadata) from databases or spreadsheets.



## 3 Script statements and keywords

Table names not present in the app are ignored. If multiple occurrences of a table name are found, the last value is used. The keyword can be used to read comments from a data source.

### Syntax:

```
comment [tables] tablelist using mapname
comment [table] tablename with comment
```

### Arguments:

#### Arguments

Argument	Description
<i>tablelist</i>	(table{,table})
<i>mapname</i>	The name of a mapping table previously read in a mapping <b>LOAD</b> or mapping <b>SELECT</b> statement.
<i>tablename</i>	The name of the table that should be commented.
<i>comment</i>	The comment that should be added to the table.

### Example 1:

```
Commentmap:
mapping LOAD * inline [
a,b
Main,This is the fact table
Currencies, Currency helper table
];
comment tables using Commentmap;
```

### Example 2:

```
comment table Main with 'Main fact table';
```

## Connect

The **CONNECT** statement is used to define Qlik Sense access to a general database through the OLE DB/ODBC interface. For ODBC, the data source first needs to be specified using the ODBC administrator.



*This functionality is not available in Qlik Sense SaaS.*



*This statement supports only folder data connections in standard mode.*

### Syntax:

```
ODBC CONNECT TO connect-string
OLEDB CONNECT TO connect-string
CUSTOM CONNECT TO connect-string
```

## 3 Script statements and keywords

**LIB CONNECT TO** connection

### Arguments:

Arguments	
Argument	Description
connect-string	<p>connect-string ::= datasourcename { ; conn-spec-item }</p> <p>The connection string is the data source name and an optional list of one or more connection specification items. If the data source name contains blanks, or if any connection specification items are listed, the connection string must be enclosed by quotation marks.</p> <p><b>datasourcename</b> must be a defined ODBC data source or a string that defines an OLE DB provider.</p> <p>conn-spec-item ::= <b>DBQ</b>=database_specifier   <b>DriverID</b>=driver_specifier   <b>UID</b>=userid   <b>PWD</b>=password</p> <p>The possible connection specification items may differ between different databases. For some databases, also other items than the above are possible. For OLE DB, some of the connection specific items are mandatory and not optional.</p>
connection	The name of a data connection stored in the data load editor.

If the **ODBC** is placed before **CONNECT**, the ODBC interface will be used; else, OLE DB will be used.

Using **LIB CONNECT TO** connects to a database using a stored data connection that was created in the data load editor.

### Example 1:

```
ODBC CONNECT TO 'Sales
```

```
DBQ=C:\Program Files\Access\Samples\Sales.mdb';
```

The data source defined through this statement is used by subsequent **Select (SQL)** statements, until a new **CONNECT** statement is made.

### Example 2:

```
LIB CONNECT TO 'DataConnection';
```

### Connect32

This statement is used the same way as the **CONNECT** statement, but forces a 64-bit system to use a 32-bit ODBC/OLE DB provider. Not applicable for custom connect.

### Connect64

This statement is used the same way as the as the **CONNECT** statement, but forces use of a 64-bit provider. Not applicable for custom connect.

### Declare

The **Declare** statement is used to create field definitions, where you can define relations between fields or functions. A set of field definitions can be used to automatically generate derived fields, which can be used as dimensions. For example, you can create a calendar definition, and use that to generate related dimensions, such as year, month, week and day, from a date field.


You can use **Declare** to either set up a new field definition, or to create a field definition based on an already existing definition.

### Setting up a new field definition

#### Syntax:

```
definition_name:  
Declare [Field[s]] Definition [Tagged tag_list ]  
[Parameters parameter_list ]  
Fields field_list
```

#### Arguments:

Argument	Description
definition_name	<p>Name of the field definition, ended with a colon.</p> <div data-bbox="403 1084 1390 1218" style="border: 1px solid #ccc; padding: 5px;"> <i>Do not use autoCalendar as name for field definitions, as this name is reserved for auto-generated calendar templates.</i></div> <p><b>Example:</b></p> <pre>calendar:</pre>
tag_list	<p>A comma separated list of tags to apply to fields derived from the field definition. Applying tags is optional, but if you do not apply tags that are used to specify sort order, such as \$date, \$numeric or \$text, the derived field will be sorted by load order as default.</p> <p><b>Example:</b></p> <pre>'\$date'Thank you for bringing this to our attention, and apologies for the inconvenience.</pre>

## 3 Script statements and keywords

Argument	Description
parameter_list	<p>A comma separated list of parameters. A parameter is defined in the form <code>name=value</code> and is assigned a start value, which can be overridden when a field definition is re-used. Optional.</p> <p><b>Example:</b></p> <pre>first_month_of_year = 1</pre>
field_list	<p>A comma separated list of fields to generate when the field definition is used. A field is defined in the form <code>&lt;expression&gt; As field_name tagged tag</code>. Use <code>\$1</code> to reference the data field from which the derived fields should be generated.</p> <p><b>Example:</b></p> <pre>Year(\$1) As Year tagged ('\$numeric')</pre>

### Example:

Calendar:

```
DECLARE FIELD DEFINITION TAGGED '$date'
  Parameters
    first_month_of_year = 1
  Fields
    Year($1) As Year Tagged ('$numeric'),
    Month($1) as Month Tagged ('$numeric'),
    Date($1) as Date Tagged ('$date'),
    Week($1) as week Tagged ('$numeric'),
    Weekday($1) as weekday Tagged ('$numeric'),
    DayNumberOfYear($1, first_month_of_year) as DayNumberOfYear Tagged ('$numeric')
;
```

The calendar is now defined, and you can apply it to the date fields that have been loaded, in this case `OrderDate` and `ShippingDate`, using a **Derive** clause.

### Re-using an existing field definition

#### Syntax:

```
<definition name>:
Declare [Field][s] Definition
Using <existing_definition>
[With <parameter_assignment> ]
```

### Arguments:

Argument	Description
definition_name	Name of the field definition, ended with a colon.  <b>Example:</b>  MyCalendar:
existing_definition	The field definition to re-use when creating the new field definition. The new field definition will function the same way as the definition it is based on, with the exception if you use parameter_assignment to change a value used in the field expressions.  <b>Example:</b>  using Calendar
parameter_assignment	A comma separated list of parameter assignments. A parameter assignment is defined in the form name=value and overrides the parameter value that is set in the base field definition. Optional.  <b>Example:</b>  first_month_of_year = 4

### Example:

In this example we re-use the calendar definition that was created in the previous example. In this case we want to use a fiscal year that starts in April. This is achieved by assigning the value 4 to the first\_month\_of\_year parameter, which will affect the DayNumberOfYear field that is defined.

The example assumes that you use the sample data and field definition from the previous example.

```
MyCalendar:
DECLARE FIELD DEFINITION USING Calendar WITH first_month_of_year=4;

DERIVE FIELDS FROM FIELDS OrderDate,ShippingDate USING MyCalendar;
```

When you have reloaded the data script, the generated fields are available in the sheet editor, with names OrderDate.MyCalendar.\* and ShippingDate.MyCalendar.\*.

## Derive

The **Derive** statement is used to generate derived fields based on a field definition created with a **Declare** statement. You can either specify which data fields to derive fields for, or derive them explicitly or implicitly based on field tags.

### Syntax:

```
Derive [fields] From [Field[s]] field_list Using definition
```

## 3 Script statements and keywords

```
Derive [Field[s]] From Explicit [Tag[s]] tag_list Using definition
Derive [Field[s]] From Implicit [Tag[s]] Using definition
```

### Arguments:

#### Arguments

Argument	Description
definition	Name of the field definition to use when deriving fields.  <b>Example: calendar</b>
field_list	A comma separated list of data fields from which the derived fields should be generated, based on the field definition. The data fields should be fields you have already loaded in the script.  <b>Example: orderDate, shippingDate</b>
tag_list	A comma separated list of tags. Derived fields will be generated for all data fields with any of the listed tags. The list of tags should be enclosed by round brackets.  <b>Example: ('\$date', '\$timestamp')</b>

### Examples:

- Derive fields for specific data fields.  
In this case we specify the OrderDate and ShippingDate fields.  
`DERIVE FIELDS FROM FIELDS OrderDate,ShippingDate USING Calendar;`
- Derive fields for all fields with a specific tag.  
In this case we derive fields based on Calendar for all fields with a \$date tag.  
`DERIVE FIELDS FROM EXPLICIT TAGS ('$date') USING Calendar;`
- Derive fields for all fields with the field definition tag.  
In this case we derive fields for all data fields with the same tag as the Calendar field definition, which in this case is \$date.  
`DERIVE FIELDS FROM IMPLICIT TAG USING Calendar;`

## Direct Query

The **DIRECT QUERY** statement allows you to access tables through an ODBC or OLE DB connection using the Direct Discovery function.

### Syntax:

```
DIRECT QUERY DIMENSION fieldlist [MEASURE fieldlist] [DETAIL fieldlist] FROM
tablelist
[WHERE where_clause]
```

The **DIMENSION**, **MEASURE**, and **DETAIL** keywords can be used in any order.

The **DIMENSION** and **FROM** keyword clauses are required on all **DIRECT QUERY** statements. The **FROM** keyword must appear after the **DIMENSION** keyword.

## 3 Script statements and keywords

The fields specified directly after the **DIMENSION** keyword are loaded in memory and can be used to create associations between in-memory and Direct Discovery data.



The **DIRECT QUERY** statement cannot contain **DISTINCT** or **GROUP BY** clauses.

Using the **MEASURE** keyword you can define fields that Qlik Sense is aware of on a “meta level”. The actual data of a measure field resides only in the database during the data load process, and is retrieved on an ad hoc basis driven by the chart expressions that are used in a visualization.

Typically, fields with discrete values that will be used as dimensions should be loaded with the **DIMENSION** keyword, whereas numbers that will be used in aggregations only should be selected with the **MEASURE** keyword.

**DETAIL** fields provide information or details, like comment fields, that a user may want to display in a drill-to-details table box. **DETAIL** fields cannot be used in chart expressions.

By design, the **DIRECT QUERY** statement is data-source neutral for data sources that support SQL. For that reason, the same **DIRECT QUERY** statement can be used for different SQL databases without change. Direct Discovery generates database-appropriate queries as needed.

Native data-source syntax can be used when the user knows the database to be queried and wants to exploit database-specific extensions to SQL. Native data-source syntax is supported:

- As field expressions in **DIMENSION** and **MEASURE** clauses
- As the content of the **WHERE** clause

Examples:

**DIRECT QUERY**

```
DIMENSION Dim1, Dim2
MEASURE
    NATIVE ('X % Y') AS X_MOD_Y
```

**FROM** TableName

**DIRECT QUERY**

```
DIMENSION Dim1, Dim2
MEASURE X, Y
FROM TableName
WHERE NATIVE ('EMAIL MATCHES "*"*.EDU"')
```



The following terms are used as keywords and so cannot be used as column or field names without being quoted: *and, as, detach, detail, dimension, distinct, from, in, is, like, measure, native, not, or, where*

## 3 Script statements and keywords

---

### Arguments:

Argument	Description
fieldlist	A comma-separated list of field specifications, <i>fieldname {, fieldname}</i> . A field specification can be a field name, in which case the same name is used for the database column name and the Qlik Sense field name. Or a field specification can be a "field alias," in which case a database expression or column name is given a Qlik Sense field name.
tablelist	A list of the names of tables or views in the database from which data will be loaded. Typically, it will be views that contain a JOIN performed on the database.
where_ clause	<p>The full syntax of database <b>WHERE</b> clauses is not defined here, but most SQL "relational expressions" are allowed, including the use of function calls, the <b>LIKE</b> operator for strings, <b>IS NULL</b> and <b>IS NOT NULL</b>, and <b>IN</b>. <b>BETWEEN</b> is not included.</p> <p><b>NOT</b> is a unary operator, as opposed to a modifier on certain keywords.</p> <p>Examples:</p> <pre>WHERE x &gt; 100 AND "Region Code" IN ('south', 'west') WHERE Code IS NOT NULL and Code LIKE '%prospect' WHERE NOT X in (1,2,3)</pre> <p>The last example can not be written as:</p> <pre>WHERE X NOT in (1,2,3)</pre>

### Example:

In this example, a database table called TableName, containing fields Dim1, Dim2, Num1, Num2 and Num3, is used. Dim1 and Dim2 will be loaded into the Qlik Sense dataset.

```
DIRECT QUERY DIMENSION Dim1, Dim2 MEASURE Num1, Num2, Num3 FROM TableName ;
```

Dim1 and Dim2 will be available for use as dimensions. Num1, Num2 and Num3 will be available for aggregations. Dim1 and Dim2 are also available for aggregations. The type of aggregations for which Dim1 and Dim2 can be used depends on their data types. For example, in many cases **DIMENSION** fields contain string data such as names or account numbers. Those fields cannot be summed, but they can be counted: `count(Dim1)`.





**DIRECT QUERY** statements are written directly in the script editor. To simplify construction of **DIRECT QUERY** statements, you can generate a **SELECT** statement from a data connection, and then edit the generated script to change it into a **DIRECT QUERY** statement.

For example, the **SELECT** statement:

```
SQL SELECT
  SalesOrderID,
  RevisionNumber,
  OrderDate,
  SubTotal,
  TaxAmt
FROM MyDB.Sales.SalesOrderHeader;
```

could be changed to the following **DIRECT QUERY** statement:

```
DIRECT QUERY
DIMENSION
  SalesOrderID,
  RevisionNumber

MEASURE
  SubTotal,
  TaxAmt

DETAIL
  OrderDate

FROM MyDB.Sales.SalesOrderHeader;
```

### Direct Discovery field lists

A field list is a comma-separated list of field specifications, *fieldname {, fieldname}*. A field specification can be a field name, in which case the same name is used for the database column name and the field name. Or a field specification can be a field alias, in which case a database expression or column name is given a Qlik Sense field name.

Field names can be either simple names or quoted names. A simple name begins with an alphabetic Unicode character and is followed by any combination of alphabetic or numeric characters or underscores. Quoted names begin with a double quotation mark and contain any sequence of characters. If a quoted name contains double quotation marks, those quotation marks are represented using two adjacent double quotation marks.

---

## 3 Script statements and keywords

Qlik Sense field names are case-sensitive. Database field names may or may not be case-sensitive, depending on the database. A Direct Discovery query preserves the case of all field identifiers and aliases. In the following example, the alias "MyState" is used internally to store the data from the database column "STATEID".

```
DIRECT QUERY Dimension STATEID as MyState Measure AMOUNT from SALES_TABLE;
```

This differs from the result of an **SQL Select** statement with an alias. If the alias is not explicitly quoted, the result contains the default case of column returned by the target database. In the following example, the **SQL Select** statement to an Oracle database creates "MYSTATE," with all upper case letters, as the internal Qlik Sense alias even though the alias is specified as mixed case. The **SQL Select** statement uses the column name returned by the database, which in the case of Oracle is all upper case.

```
SQL Select STATEID as MyState, STATENAME from STATE_TABLE;
```

To avoid this behavior, use the LOAD statement to specify the alias.

```
Load STATEID as MyState, STATENAME;  
SQL Select STATEID, STATEMENT from STATE_TABLE;
```

In this example, the "STATEID" column is stored internally by Qlik Sense as "MyState".

Most database scalar expressions are allowed as field specifications. Function calls can also be used in field specifications. Expressions can contain constants that are boolean, numeric, or strings contained in single quotation marks (embedded single quotation marks are represented by adjacent single quotation marks).

### Examples:

```
DIRECT QUERY  
  
    DIMENSION  
  
        SalesOrderID, RevisionNumber  
  
    MEASURE  
  
        SubTotal AS "Sub Total"  
  
FROM Adventureworks.Sales.SalesOrderHeader;  
  
DIRECT QUERY  
  
    DIMENSION  
  
        "SalesOrderID" AS "Sales Order ID"  
  
    MEASURE  
  
        SubTotal, TaxAmt, (SubTotal-TaxAmt) AS "Net Total"  
  
FROM Adventureworks.Sales.SalesOrderHeader;
```

```
DIRECT QUERY

DIMENSION

    (2*Radius*3.14159) AS Circumference,

    Moles/6.02e23 AS Moles

MEASURE

    Num1 AS numA

FROM TableName;
```

```
DIRECT QUERY
  DIMENSION
    concat(region, 'code') AS region_code
  MEASURE
    Num1 AS NumA
FROM TableName;
```

Direct Discovery does not support using aggregations in **LOAD** statements. If aggregations are used, the results are unpredictable. A **LOAD** statement such as the following should not be used:

```
DIRECT QUERY DIMENSION stateid, SUM(amount*7) AS MultiFirst MEASURE amount FROM sales_table;
The SUM should not be in the LOAD statement.
```

Direct Discovery also does not support Qlik Sense functions in **Direct Query** statements. For example, the following specification for a **DIMENSION** field results in a failure when the "Mth" field is used as a dimension in a visualization:

```
month(ModifiedDate) as Mth
```

## Directory

The **Directory** statement defines which directory to look in for data files in subsequent **LOAD** statements, until a new **Directory** statement is made.

### Syntax:

```
Directory [path]
```

If the **Directory** statement is issued without a **path** or left out, Qlik Sense will look in the Qlik Sense working directory.

### Arguments:

#### Arguments

Argument	Description
<b>path</b>	<p>A text that can be interpreted as the path to the data file.</p> <p>The path is the path to the file, either:</p> <ul style="list-style-type: none"><li>• absolute <b>Example: <code>c:\data</code></b></li><li>• relative to the Qlik Sense app working directory. <b>Example: <code>data</code></b></li><li>• URL address (HTTP or FTP), pointing to a location on the Internet or an intranet. <b>Example: <code>http://www.qlik.com</code></b></li></ul>

### Examples:

```
DIRECTORY C:\userfiles\data; // OR -> DIRECTORY data\
```

```
LOAD * FROM  
[data1.csv] // ONLY THE FILE NAME CAN BE SPECIFIED HERE (WITHOUT THE FULL PATH)  
(ansi, txt, delimiter is ',', embedded labels);
```

```
LOAD * FROM  
[data2.txt] // ONLY THE FILE NAME CAN BE SPECIFIED HERE UNTIL A NEW DIRECTORY STATEMENT IS  
MADE  
(ansi, txt, delimiter is '\t', embedded labels);
```

## Disconnect

The **Disconnect** statement terminates the current ODBC/OLE DB/Custom connection. This statement is optional.

### Syntax:

```
Disconnect
```

The connection will be automatically terminated when a new **connect** statement is executed or when the script execution is finished.

### Example:

```
Disconnect;
```

### Drop

The **Drop** script keyword can be used to drop tables or fields from the database.

#### Drop field

One or several Qlik Sense fields can be dropped from the data model, and thus from memory, at any time during script execution, by means of a **drop field** statement. The "distinct" property of a table is removed after a **drop field** statement.



Both **drop field** and **drop fields** are allowed forms with no difference in effect. If no table is specified, the field will be dropped from all tables where it occurs.

#### Syntax:

```
Drop field fieldname { , fieldname2 ...} [from tablename1 { , tablename2 ...}]  
Drop fields fieldname { , fieldname2 ...} [from tablename1 { , tablename2 ...}]
```

#### Examples:

```
Drop field A;  
Drop fields A,B;  
Drop field A from X;  
Drop fields A,B from X,Y;
```

#### Drop table

One or several Qlik Sense internal tables can be dropped from the data model, and thus from memory, at any time during script execution, by means of a **drop table** statement.

#### Syntax:

```
drop table tablename {, tablename2 ...}  
drop tables tablename {, tablename2 ...}
```



The forms **drop table** and **drop tables** are both accepted.

The following items will be lost as a result of this:

- The actual table(s).
- All fields which are not part of remaining tables.
- Field values in remaining fields, which came exclusively from the dropped table(s).

## 3 Script statements and keywords

Examples and results:

Example	Result
<pre>drop table Orders, Salesmen, T456a;</pre>	This line results in three tables being dropped from memory.
<pre>Tab1: Load * Inline [ Customer, Items, UnitPrice Bob, 5, 1.50 ];  Tab2: LOAD Customer, Sum( Items * UnitPrice ) as Sales resident Tab1 group by Customer;  drop table Tab1;</pre>	Once the table <i>Tab2</i> is created, the table <i>Tab1</i> is dropped.

### Drop table

One or several Qlik Sense internal tables can be dropped from the data model, and thus from memory, at any time during script execution, by means of a **drop table** statement.

#### Syntax:

```
drop table tablename {, tablename2 ...}
drop tables tablename {, tablename2 ...}
```



The forms **drop table** and **drop tables** are both accepted.

The following items will be lost as a result of this:

- The actual table(s).
- All fields which are not part of remaining tables.
- Field values in remaining fields, which came exclusively from the dropped table(s).

Examples and results:

Example	Result
<pre>drop table Orders, Salesmen, T456a;</pre>	This line results in three tables being dropped from memory.

## 3 Script statements and keywords

Example	Result
<pre>Tab1: Load * Inline [ Customer, Items, UnitPrice Bob, 5, 1.50 ];  Tab2: LOAD Customer, Sum( Items * UnitPrice ) as Sales resident Tab1 group by Customer;  drop table Tab1;</pre>	Once the table <i>Tab2</i> is created, the table <i>Tab1</i> is dropped.

### Execute

The **Execute** statement is used to run other programs while Qlik Sense is loading data. For example, to make conversions that are necessary.



*This functionality is not available in Qlik Sense SaaS.*



*This statement is not supported in standard mode.*

#### Syntax:

```
execute commandline
```

#### Arguments:

##### Arguments

Argument	Description
<i>commandline</i>	A text that can be interpreted by the operating system as a command line. You can refer to an absolute file path or a lib:// folder path.

If you want to use **Execute** the following conditions need to be met:

- You must run in legacy mode (applicable for Qlik Sense and Qlik Sense Desktop).
- You need to set `OverrideScriptSecurity` to 1 in *Settings.ini* (applicable for Qlik Sense). *Settings.ini* is located in `C:\ProgramData\Qlik\Sense\Engine\` and is generally an empty file.



*If you set `OverrideScriptSecurity` to enable **Execute**, any user can execute files on the server. For example, a user can attach an executable file to an app, and then execute the file in the data load script.*

### Do the following:

1. Make a copy of *Settings.ini* and open it in a text editor.
2. Check that the file includes *[Settings 7]* in the first line.
3. Insert a new line and type *OverrideScriptSecurity=1*.
4. Insert an empty line at the end of the file.
5. Save the file.
6. Substitute *Settings.ini* with your edited file.
7. Restart Qlik Sense Engine Service (QES).



*If Qlik Sense is running as a service, some commands may not behave as expected.*

### Example:

```
Execute C:\Program Files\Office12\Excel.exe;  
Execute lib://win\notepad.exe // win is a folder connection referring to c:\windows
```

## Field/Fields

The **Field** and **Fields** script keywords are used in **Declare**, **Derive**, **Drop**, **Comment**, **Rename** and **Tag/Untag** statements.

## FlushLog

The **FlushLog** statement forces Qlik Sense to write the content of the script buffer to the script log file.

### Syntax:

```
FlushLog
```

The content of the buffer is written to the log file. This command can be useful for debugging purposes, as you will receive data that otherwise may have been lost in a failed script execution.

### Example:

```
FlushLog;
```

## Force

The **force** statement forces Qlik Sense to interpret field values of subsequent **LOAD** and **SELECT** statements as written with only upper case letters, with only lower case letters, as always capitalized or as they appear (mixed). This statement makes it possible to associate field values from tables made according to different conventions.



## 3 Script statements and keywords

---

The **force** statement can also change field names during a load or select with the following data sources:

- QVD
- CSV (text files)
- XLS
- QVX (files and ODBC connections)

The **force** statement only changes field names if the data is loaded in compact mode (loaded with \*).

The field names of the following data sources are not affected by the **force** statement:

- JSON
- Parquet
- XML
- XLSX

### Syntax:

```
Force ( capitalization | case upper | case lower | case mixed )
```

If nothing is specified, force case mixed is assumed. The force statement is valid until a new force statement is made.

The **force** statement has no effect in the access section: all field values loaded are case insensitive.

### Examples and results

Example	Result
<p>This example shows how to force capitalization.</p> <pre>FORCE Capitalization; Capitalization: LOAD * Inline [ ab Cd eF GH ];</pre>	<p>The <b>Capitalization</b> table contains the following values:</p> <pre>Ab Cd Ef Gh</pre> <p>All values are capitalized.</p>

## 3 Script statements and keywords

Example	Result
<p>This example shows how to force case upper.</p> <pre>FORCE Case Upper; CaseUpper: LOAD * Inline [ ab Cd eF GH ];</pre>	<p>The <b>CaseUpper</b> table contains the following values:</p> <p>AB CD EF GH</p> <p>All values are upper case.</p>
<p>This example shows how to force case lower.</p> <pre>FORCE Case Lower; CaseLower: LOAD * Inline [ ab Cd eF GH ];</pre>	<p>The <b>CaseLower</b> table contains the following values:</p> <p>ab cd ef gh</p> <p>All values are lower case.</p>
<p>This example shows how to force case mixed.</p> <pre>FORCE Case Mixed; CaseMixed: LOAD * Inline [ ab Cd eF GH ];</pre>	<p>The <b>CaseMixed</b> table contains the following values:</p> <p>ab Cd eF GH</p> <p>All values are as they appear in the script.</p>

### See also:

## From

The **From** script keyword is used in **Load** statements to refer to a file, and in **Select** statements to refer to a database table or view.

## Load

The **LOAD** statement loads fields from a file, from data defined in the script, from a previously loaded table, from a web page, from the result of a subsequent **SELECT** statement or by generating data automatically. It is also possible to load data from analytic connections.

### Syntax:

```
LOAD [ distinct ] fieldlist
```

## 3 Script statements and keywords

---


```
[ ( from file [ format-spec ] |  
from_field fieldsource [format-spec]|  
inline data [ format-spec ] |  
resident table-label |  
autogenerate size ) | extension pluginname.functionname([script]  
tabledescription)]  
[ where criterion | while criterion ]  
[ group by groupbyfieldlist ]  
[ order by orderbyfieldlist ]
```

### Arguments


Argument	Description
distinct	<p>You can use <b>distinct</b> as a predicate if you only want to load unique records. If there are duplicate records, the first instance will be loaded.</p> <p>If you are using preceding loads, you need to place <b>distinct</b> in the first load statement, as <b>distinct</b> only affects the destination table.</p>

### 3 Script statements and keywords

Argument	Description
fieldlist	<p><i>fieldlist</i> ::= ( *   <i>field</i>{, *   <i>field</i> } )</p> <p>A list of the fields to be loaded. Using * as a field list indicates all fields in the table.</p> <p><i>field</i> ::= ( <i>fieldref</i>   <i>expression</i> ) [<b>as</b> <i>aliasname</i> ]</p> <p>The field definition must always contain a literal, a reference to an existing field, or an expression.</p> <p><i>fieldref</i> ::= ( <i>fieldname</i>   @<i>fieldnumber</i>   @<i>startpos:endpos</i> [<b>I</b>   <b>U</b>   <b>R</b>   <b>B</b>   <b>T</b>] )</p> <p><i>fieldname</i> is a text that is identical to a field name in the table. Note that the field name must be enclosed by straight double quotation marks or square brackets if it contains e.g. spaces. Sometimes field names are not explicitly available. Then a different notation is used:</p> <p>@<i>fieldnumber</i> represents the field number in a delimited table file. It must be a positive integer preceded by "@". The numbering is always made from 1 and up to the number of fields.</p> <p>@<i>startpos:endpos</i> represents the start and end positions of a field in a file with fixed length records. The positions must both be positive integers. The two numbers must be preceded by "@" and separated by a colon. The numbering is always made from 1 and up to the number of positions. In the last field, <b>n</b> is used as end position.</p> <ul style="list-style-type: none"> <li>• If @<i>startpos:endpos</i> is immediately followed by the characters <b>I</b> or <b>U</b>, the bytes read will be interpreted as a binary signed (<b>I</b>) or unsigned (<b>U</b>) integer (Intel byte order). The number of positions read must be 1, 2 or 4.</li> <li>• If @<i>startpos:endpos</i> is immediately followed by the character <b>R</b>, the bytes read will be interpreted as a binary real number (IEEE 32-bit or 64 bit floating point). The number of positions read must be 4 or 8.</li> <li>• If @<i>startpos:endpos</i> is immediately followed by the character <b>B</b>, the bytes read will be interpreted as a BCD (Binary Coded Decimal) numbers according to the COMP-3 standard. Any number of bytes may be specified.</li> </ul> <p><i>expression</i> can be a numeric function or a string function based on one or several other fields in the same table. For further information, see the syntax of expressions.</p> <p><b>as</b> is used for assigning a new name to the field.</p>

Argument	Description
from	<p><b>from</b> is used if data should be loaded from a file using a folder or a web file data connection</p> <p><i>file ::= [ path ] filename</i></p> <p><b>Example: 'lib://Table Files/'</b></p> <p>If the path is omitted, Qlik Sense searches for the file in the directory specified by the <b>Directory</b> statement. If there is no <b>Directory</b> statement, Qlik Sense searches in the working directory, <i>C:\Users\{user}\Documents\Qlik\Sense\Apps</i>.</p> <div style="border: 1px solid gray; padding: 5px; margin: 10px 0;"> <p> <i>In a Qlik Sense server installation, the working directory is specified in Qlik Sense Repository Service, by default it is C:\ProgramData\Qlik\Sense\Apps.</i></p> </div> <p>The <i>filename</i> may contain the standard DOS wildcard characters ( * and ? ). This will cause all the matching files in the specified directory to be loaded.</p> <p><i>format-spec ::= ( fspec-item { , fspec-item } )</i></p> <p>The format specification consists of a list of several format specification items, within brackets.</p> <p><b>Legacy scripting mode</b></p> <p>In legacy scripting mode, the following path formats are also supported:</p> <ul style="list-style-type: none"> <li>• absolute           <p style="margin-left: 20px;"><b>Example: c:\data\</b></p> </li> <li>• relative to the Qlik Sense app working directory.           <p style="margin-left: 20px;"><b>Example: data\</b></p> </li> <li>• URL address (HTTP or FTP), pointing to a location on the Internet or an intranet.           <p style="margin-left: 20px;"><b>Example: http://www.qlik.com</b></p> </li> </ul>

### 3 Script statements and keywords

Argument	Description
from_field	<p><b>from_field</b> is used if data should be loaded from a previously loaded field.  <i>fieldsource::=(tablename, fieldname)</i></p> <p>The field is the name of the previously loaded <i>tablename</i> and <i>fieldname</i>.  <i>format-spec ::= ( fspec-item {, fspec-item } )</i></p> <p>The format specification consists of a list of several format specification items, within brackets. For more information, see <i>Format specification items (page 165)</i>.</p> <div style="border: 1px solid #ccc; padding: 5px; margin-top: 10px;">  <b>from_field</b> only supports commas as the list delimiter in when separating fields in tables.         </div>
inline	<p><b>inline</b> is used if data should be typed within the script, and not loaded from a file.  <i>data ::= [ text ]</i></p> <p>Data entered through an <b>inline</b> clause must be enclosed by specific characters – square brackets, quotation marks, or back ticks. The text between these is interpreted in the same way as the content of a file. Hence, where you would insert a new line in a text file, you should also do it in the text of an <b>inline</b> clause: by pressing the Enter key when typing the script.</p> <p>In a simple inline load, the number of columns are defined by the first line.  <i>format-spec ::= ( fspec-item {, fspec-item } )</i></p> <p>You can customize the inline load with many of the same format specification items that are available for other loaded tables. These items are listed in brackets. For more information, see <i>Format specification items (page 165)</i>.</p> <p>For more information about inline loads, see <a href="#">Using inline loads to load data</a>.</p>
resident	<p><b>resident</b> is used if data should be loaded from a previously loaded table. <i>table label</i> is a label preceding the <b>LOAD</b> or <b>SELECT</b> statement(s) that created the original table. The label should be given with a colon at the end.</p>

## 3 Script statements and keywords

Argument	Description
autogenerate	<p><b>autogenerate</b> is used if data should be automatically generated by Qlik Sense.</p> <p><i>size ::= number</i></p> <p><i>Number</i> is an integer indicating the number of records to be generated.</p> <p>The field list must not contain expressions which require data from an external data source or a previously loaded table, unless you refer to a single field value in a previously loaded table with the <b>Peek</b> function.</p>
extension	<p>You can load data from analytic connections. You need to use the <b>extension</b> clause to call a function defined in the server-side extension (SSE) plugin, or evaluate a script.</p> <p>You can send a single table to the SSE plugin, and a single data table is returned. If the plugin does not specify the names of the fields that are returned, the fields will be named Field1, Field2, and so on.</p> <pre>Extension pluginname.functionname( tabledescription );</pre> <ul style="list-style-type: none"><li>• Loading data using a function in an SSE plugin <i>tabledescription ::= (table { ,tablefield} )</i> If you do not state table fields, the fields will be used in load order.</li><li>• Loading data by evaluating a script in an SSE plugin <i>tabledescription ::= ( script, table { ,tablefield} )</i></li></ul> <p><b>Data type handling in the table field definition</b></p> <p>Data types are automatically detected in analytic connections. If the data has no numeric values and at least one non-NULL text string, the field is considered as text. In any other case it is considered as numeric.</p> <p>You can force the data type by wrapping a field name with <b>String()</b> or <b>Mixed()</b>.</p> <ul style="list-style-type: none"><li>• <b>String()</b> forces the field to be text. If the field is numeric, the text part of the dual value is extracted, there is no conversion performed.</li><li>• <b>Mixed()</b> forces the field to be dual.</li></ul> <p><b>String()</b> or <b>Mixed()</b> cannot be used outside <b>extension</b> table field definitions, and you cannot use other Qlik Sense functions in a table field definition.</p> <p><b>More about analytic connections</b></p> <p>You need to configure analytic connections before you can use them.</p>

## 3 Script statements and keywords

Argument	Description
where	<b>where</b> is a clause used for stating whether a record should be included in the selection or not. The selection is included if <i>criteria</i> is True. <i>criteria</i> is a logical expression.
while	<b>while</b> is a clause used for stating whether a record should be repeatedly read. The same record is read as long as <i>criteria</i> is True. In order to be useful, a <b>while</b> clause must typically include the <b>IterNo( )</b> function. <i>criteria</i> is a logical expression.
group by	<b>group by</b> is a clause used for defining over which fields the data should be aggregated (grouped). The aggregation fields should be included in some way in the expressions loaded. No other fields than the aggregation fields may be used outside aggregation functions in the loaded expressions.  <i>groupbyfieldlist ::= (fieldname { ,fieldname } )</i>
order by	<b>order by</b> is a clause used for sorting the records of a resident table before they are processed by the <b>load</b> statement. The resident table can be sorted by one or more fields in ascending or descending order. The sorting is made primarily by numeric value and secondarily by national collation order. This clause may only be used when the data source is a resident table. The ordering fields specify which field the resident table is sorted by. The field can be specified by its name or by its number in the resident table (the first field is number 1).  <i>orderbyfieldlist ::= fieldname [ sortorder ] { , fieldname [ sortorder ] }</i>  <i>sortorder</i> is either <i>asc</i> for ascending or <i>desc</i> for descending. If no <i>sortorder</i> is specified, <i>asc</i> is assumed.  <i>fieldname, path, filename</i> and <i>aliasname</i> are text strings representing what the respective names imply. Any field in the source table can be used as <i>fieldname</i> . However, fields created through the <i>as</i> clause ( <i>aliasname</i> ) are out of scope and cannot be used inside the same <b>load</b> statement.

If no source of data is given by means of a **from, inline, resident, from\_field, extension** or **autogenerate** clause, data will be loaded from the result of the immediately succeeding **SELECT** or **LOAD** statement. The succeeding statement should not have a prefix.

### Examples:

Loading different file formats

Load a delimited data file with default options:

```
LOAD * from data1.csv;
```

Load a delimited data file from a library connection (DataFiles):



---

## 3 Script statements and keywords

---

```
LOAD * from 'lib://DataFiles/data1.csv';
```

Load all delimited data files from a library connection (DataFiles):

```
LOAD * from 'lib://DataFiles/*.csv';
```

Load a delimited file, specifying comma as delimiter and with embedded labels:

```
LOAD * from 'c:\userfiles\data1.csv' (ansi, txt, delimiter is ',', embedded labels);
```

Load a delimited file specifying tab as delimiter and with embedded labels:

```
LOAD * from 'c:\userfiles\data2.txt' (ansi, txt, delimiter is '\t', embedded labels);
```

Load a dif file with embedded headers:

```
LOAD * from file2.dif (ansi, dif, embedded labels);
```

Load three fields from a fixed record file without headers:

```
LOAD @1:2 as ID, @3:25 as Name, @57:80 as City from data4.fix (ansi, fix, no labels, header is 0, record is 80);
```

Load a QVX file, specifying an absolute path:

```
LOAD * from C:\qdssamples\xyz.qvx (qvx);
```

Loading web files

Load from the default URL set in the web file data connection:

```
LOAD * from [lib://MywebFile];
```

Load from a specific URL, and override the URL set in the web file data connection:

```
LOAD * from [lib://MywebFile] (URL is 'http://localhost:8000/foo.bar');
```

Load from a specific URL set in a variable using dollar-sign expansion:

```
SET dynamicURL = 'http://localhost/foo.bar';  
LOAD * from [lib://MywebFile] (URL is '$(dynamicURL)');
```

Selecting certain fields, renaming and calculating fields

Load only three specific fields from a delimited file:

```
LOAD FirstName, LastName, Number from data1.csv;
```

Rename first field as A and second field as B when loading a file without labels:

```
LOAD @1 as A, @2 as B from data3.txt (ansi, txt, delimiter is '\t', no labels);
```

Load Name as a concatenation of FirstName, a space character, and LastName:

```
LOAD FirstName&' '&LastName as Name from data1.csv;
```

Load Quantity, Price and Value (the product of Quantity and Price):

```
LOAD quantity, Price, quantity*Price as value from data1.csv;
```

## 3 Script statements and keywords

---

Selecting certain records

Load only unique records, duplicate records will be discarded:

```
LOAD distinct FirstName, LastName, Number from data1.csv;
```

Load only records where the field Litres has a value above zero:

```
LOAD * from Consumption.csv where Litres>0;
```

Loading data not on file and auto-generated data

Load a table with inline data, two fields named CatID and Category:

```
LOAD * Inline  
[CatID, Category  
0,Regular  
1,Occasional  
2,Permanent];
```

Load a table with inline data, three fields named UserID, Password and Access:

```
LOAD * Inline [UserID, Password, Access  
A, ABC456, User  
B, VIP789, Admin];
```

Load a table with 10 000 rows. Field A will contain the number of the read record (1,2,3,4,5...) and field B will contain a random number between 0 and 1:

```
LOAD RecNo( ) as A, rand( ) as B autogenerate(10000);
```



*The parenthesis after autogenerate is allowed but not required.*

Loading data from a previously loaded table

First we load a delimited table file and name it tab1:

```
tab1:  
SELECT A,B,C,D from 'lib://DataFiles/data1.csv';
```

Load fields from the already loaded tab1 table as tab2:

```
tab2:  
LOAD A,B,month(C),A*B+D as E resident tab1;
```

Load fields from already loaded table tab1 but only records where A is larger than B:

```
tab3:  
LOAD A,A+B+C resident tab1 where A>B;
```

Load fields from already loaded table tab1 ordered by A:

```
LOAD A,B*C as E resident tab1 order by A;
```

Load fields from already loaded table tab1, ordered by the first field, then the second field:

```
LOAD A,B*C as E resident tab1 order by 1,2;
```

---

## 3 Script statements and keywords

Load fields from already loaded table tab1 ordered by C descending, then B in ascending order, and then the first field in descending order:

```
LOAD A,B*C as E resident tab1 order by C desc, B asc, 1 desc;
```

Loading data from previously loaded fields

Load field Types from previously loaded table Characters as A:

```
LOAD A from_field (Characters, Types);
```

Loading data from a succeeding table (preceding load)

Load A, B and calculated fields X and Y from Table1 that is loaded in succeeding **SELECT** statement:

```
LOAD A, B, if(C>0,'positive','negative') as X, weekday(D) as Y;  
SELECT A,B,C,D from Table1;
```

Grouping data

Load fields grouped (aggregated) by ArtNo:

```
LOAD ArtNo, round(Sum(TransAmount),0.05) as ArtNoTotal from table.csv group by ArtNo;
```

Load fields grouped (aggregated) by Week and ArtNo:

```
LOAD Week, ArtNo, round(Avg(TransAmount),0.05) as weekArtNoAverages from table.csv group by  
Week, ArtNo;
```

Reading one record repeatedly

In this example we have a input file Grades.csv containing the grades for each student condensed in one field:

```
Student,Grades  
Mike,5234  
John,3345  
Pete,1234  
Paul,3352
```

The grades, in a 1-5 scale, represent subjects Math, English, Science and History. We can separate the grades into separate values by reading each record several times with a **while** clause, using the **IterNo( )** function as a counter. In each read, the grade is extracted with the **Mid** function and stored in Grade, and the subject is selected using the **pick** function and stored in Subject. The final **while** clause contains the test to check if all grades have been read (four per student in this case), which means next student record should be read.

MyTab:

```
LOAD Student,  
mid(Grades,IterNo( ),1) as Grade,  
pick(IterNo( ), 'Math', 'English', 'Science', 'History') as Subject from Grades.csv  
while IsNum(mid(Grades,IterNo(),1));
```

The result is a table containing this data:

## 3 Script statements and keywords

---

Student	Subject	Grade
John	English	3
John	History	5
John	Math	3
John	Science	4
Mike	English	2
Mike	History	4
Mike	Math	5
Mike	Science	3
Paul	English	3
Paul	History	2
Paul	Math	3
Paul	Science	5
Pete	English	2
Pete	History	4
Pete	Math	1
Pete	Science	3

Loading from analytic connections

The following sample data is used.

Values:

Load

    Rand() as A,

    Rand() as B,

    Rand() as C

AutoGenerate(50);

### Loading data using a function

In these examples, we assume that we have an analytic connection plugin named *P* that contains a custom function *Calculate(Parameter1, Parameter2)*. The function returns the table *Results* that contains the fields *Field1* and *Field2*.

```
Load * Extension P.Calculate( values{A, C} );
```

Load all fields that are returned when sending the fields A and C to the function.

```
Load Field1 Extension P.Calculate( values{A, C} );
```

Load only the Field1 field when sending the fields A and C to the function.

```
Load * Extension P.Calculate( values );
```

Load all fields that are returned when sending the fields A and B to the function. As fields are not specified, A and B are used as they are the first in order in the table.

```
Load * Extension P.Calculate( values {C, C});
```

Load all fields that are returned when sending the field C to both parameters of the function.

```
Load * Extension P.Calculate( values {String(A), Mixed(B)});
```

Load all fields that are returned when sending the field A forced as a string and B forced as a numeric to the function.

### Loading data by evaluating a script

Load A as A\_echo, B as B\_echo Extension R.ScriptEval( 'q;', Values{A, B} );  
Load the table returned by the script q when sending the values of A and B.

Load \* Extension R.ScriptEval( '\$(My\_R\_Script)', Values{A, B} );  
Load the table returned by the script stored in the My\_R\_Script variable when sending the values of A and B.

Load \* Extension R.ScriptEval( '\$(My\_R\_Script)', Values{B as D, \*} );  
Load the table returned by the script stored in the My\_R\_Script variable when sending the values of B renamed to D, A and C. Using \* sends the remaining unreferenced fields.



The file extension of DataFiles connections is case sensitive. For example: .qvd.

### Format specification items

Each format specification item defines a certain property of the table file:

**fspec-item** ::= [ansi | oem | mac | UTF-8 | Unicode | txt | fix | dif | biff | ooxml | html | xml | kml | qvd | qvx | parquet | delimiter is char | no eof | embedded labels | explicit labels | no labels | table is [tablename] | header is n | header is line | header is n lines | comment is string | record is n | record is line | record is n lines | no quotes | msq | URL is string | userAgent is string]

#### Character set

Character set is a file specifier for the **LOAD** statement that defines the character set used in the file.

The **ansi**, **oem** and **mac** specifiers were used in QlikView and will still work. However, they will not be generated when creating the **LOAD** statement with Qlik Sense.

#### Syntax:

```
utf8 | unicode | ansi | oem | mac | codepage is
```

#### Arguments:

##### Arguments

Argument	Description
<b>utf8</b>	UTF-8 character set
<b>unicode</b>	Unicode character set
<b>ansi</b>	Windows, codepage 1252
<b>oem</b>	DOS, OS/2, AS400 and others
<b>mac</b>	Codepage 10000
<b>codepage is</b>	With the <b>codepage</b> specifier, it is possible to use any Windows codepage as <i>N</i> .

### Limitations:


Conversion from the **oem** character set is not implemented for macOS. If nothing is specified, codepage 1252 is assumed under Windows.

### Example:

```
LOAD * from a.txt (utf8, txt, delimiter is ',' , embedded labels)
LOAD * from a.txt (unicode, txt, delimiter is ',' , embedded labels)
LOAD * from a.txt (codepage is 10000, txt, delimiter is ',' , no labels)
```

---


### See also:

 [Load \(page 154\)](#)

### Table format

The table format is a file specifier for the **LOAD** statement that defines the file type. If nothing is specified, a *.txt* file is assumed.

Table format types

Type	Description
txt	In a delimited text file the columns in the table are separated by a delimiter character.
fix	<p>In a fixed record file, each field is exactly a certain number of characters.</p> <p>Typically, many fixed record length files contains records separated by a linefeed, but there are more advanced options to specify record size in bytes or to span over more than one line with <b>Record is</b>.</p> <div data-bbox="359 1332 1284 1512" style="border: 1px solid #ccc; padding: 10px;"><p> <i>If the data contains multi-byte characters, field breaks can become misaligned as the format is based on a fixed length in bytes.</i></p></div>
dif	In a <i>.dif</i> file, (Data Interchange Format) a special format for defining the table is used.
biff	Qlik Sense can also interpret data in standard Excel files by means of the <i>biff</i> format (Binary Interchange File Format).
ooxml	<p>Excel 2007 and later versions use the ooxml <i>.xlsx</i> format.</p> <p>The <b>Table is</b> specifier can be used to define the sheet name to be loaded as a table.</p> <p><i>Table is (page 170)</i></p>

### 3 Script statements and keywords

Type	Description
html	If the table is part of an html page or file, html should be used.
xml	xml (Extensible Markup Language) is a common markup language that is used to represent data structures in a textual format.  The <b>Table is</b> specifier can be used to define the path of the XML to be loaded as a table.  <i>Table is (page 170)</i>
qvd	The format <i>qvd</i> is the proprietary QVD files format, exported from a Qlik Sense app.
qvx	<i>qvx</i> is a file/stream format for high performance output to Qlik Sense.
parquet	Apache Parquet is a columnar storage format, highly efficient for storing and querying large datasets.  With Parquet files containing nested data, you can specify the table from the Parquet file to load using <b>Table is</b> specifier. For example: <code>LOAD * FROM [lib://DataFiles/company.parquet] (parquet, table is [company:salesrep.salesrep]);</code>  <i>Table is (page 170)</i>

#### Delimiter is

For delimited table files, an arbitrary delimiter can be specified through the **delimiter is** specifier. This specifier is relevant only for delimited .txt files.

#### Syntax:

```
delimiter is char
```

#### Arguments:

##### Arguments

Argument	Description
char	Specifies a single character from the 127 ASCII characters.

Additionally, the following values can be used:

##### Optional values

Value	Description
'\t'	representing a tab sign, with or without quotation marks.
'\''	representing a backslash ( \ ) character.

## 3 Script statements and keywords

---

Value	Description
'spaces'	representing all combinations of one or more spaces. Non-printable characters with an ASCII-value below 32, with the exception of CR and LF, will be interpreted as spaces.


If nothing is specified, **delimiter is ','** is assumed.

### Example:

```
LOAD * from a.txt (utf8, txt, delimiter is ',' , embedded labels);
```

---

### See also:

 [Load \(page 154\)](#)

### No eof

The **no eof** specifier is used to disregard end-of-file character when loading delimited **.txt** files.

### Syntax:

```
no eof
```

If the **no eof** specifier is used, characters with code point 26, which otherwise denotes end-of-file, are disregarded and can be part of a field value.


It is relevant only for delimited text files.

### Example:

```
LOAD * from a.txt (txt, utf8, embedded labels, delimiter is ' ', no eof);
```

---

### See also:

 [Load \(page 154\)](#)

### Labels

**Labels** is a file specifier for the **LOAD** statement that defines where in a file the field names can be found.

### Syntax:

```
embedded labels|explicit labels|no labels
```

The field names can be found in different places of the file. If the first record contains the field names, **embedded labels** should be used. If there are no field names to be found, **no labels** should be used. In *dif* files, a separate header section with explicit field names is sometimes used. In such a case, **explicit labels** should be used. If nothing is specified, **embedded labels** is assumed, also for *dif* files.



### Example 1:


```
LOAD * from a.txt (unicode, txt, delimiter is ',', embedded labels)
```

### Example 2:

```
LOAD * from a.txt (codePage is 1252, txt, delimiter is ',', no labels)
```

---

### See also:

 [Load \(page 154\)](#)

### Header is

Specifies the header size in table files. An arbitrary header length can be specified through the **header is** specifier. A header is a text section not used by Qlik Sense.

### Syntax:

```
header is n  
header is line  
header is n lines
```

The header length can be given in bytes (**header is n**), or in lines (**header is line** or **header is n lines**). **n** must be a positive integer, representing the header length. If not specified, **header is 0** is assumed. The **header is** specifier is only relevant for table files.

### Example:

This is an example of a data source table containing a header text line that should not be interpreted as data by Qlik Sense.

```
*Header line  
col1,col2  
a,B  
c,D
```


Using the **header is 1 lines** specifier, the first line will not be loaded as data. In the example, the **embedded labels** specifier tells Qlik Sense to interpret the first non-excluded line as containing field labels.

```
LOAD col1, col2  
FROM 'lib://files/header.txt'  
(txt, embedded labels, delimiter is ',', msq, header is 1 lines);
```

The result is a table with two fields, Col1 and Col2.

---

### See also:

 [Load \(page 154\)](#)

---

Record is

For fixed record length files, the record length must be specified through the **record is** specifier.

**Syntax:**

```
Record is n
Record is line
Record is n lines
```

**Arguments:**

Arguments

Argument	Description
n	Specifies the record length in bytes.
line	Specifies the record length as one line.
n lines	Specifies the record length in lines where n is a positive integer representing the record length.

**Limitations:**

The **record is** specifier is only relevant for **fix** files.

---

**See also:**


 [Load \(page 154\)](#)

Table is

For Excel, XML, or Parquet files, you can specify the table you are loading data from in the table format specifier.

**Syntax:**

```
Table is table name
```

### Arguments:

#### Arguments

Argument	Description
table name	<p>Specifies the name of the table. The value depends on the table format:</p> <ul style="list-style-type: none"> <li>• Excel: The sheet name.</li> <li>• XML: The path that specifies the part of the XML to be loaded.</li> <li>• Parquet: The path that specifies the table, with the format <code>&lt;node&gt;.&lt;node&gt;.&lt;node&gt;</code>.</li> </ul> <p>Use <b>Table is</b> when specifying a table within a nested structure. For example, you have Parquet data in the following schema: Schema:</p> <pre>Field(name: "Name", datatype: String), Field(name: "Age", datatype: Float), Field(name: "Phone", datatype: List(     Field(name: "Item", datatype: Struct[         Field(name: "Number", datatype: String)</pre> <p>You could load Phone and its nested fields as a table with the argument <code>Table is [Schema:Phone.Item]</code>. This will generate the key field <code>%Key_Phone</code> with the table.</p>

### Example: Excel

```
LOAD
    "Item Number",
    "Product Group",
    "Product Line",
    "Product Sub Group",
    "Product Type"
FROM [lib://AttachedFiles/Item master.xlsx]
(ooxml, embedded labels, table is [Item master]);
```

### Example: XML

```
LOAD
    city%Table,
    %Key_row_7FAC1F878EC01ECB
FROM [lib://AttachedFiles/cities.xml]
(XmlSimple, table is [root/row/country/city]);
```

### Example: Parquet

The file `company.parquet` contains the following schema:

```
company (String)
contact (String)
company:salesrep (List)
    salesrep (Group)
        salesrep (String)
```

## 3 Script statements and keywords

---

```
company:headquarter (List)
  headquarter (Group)
    country (String)
    city (String)
    city:region (List)
    region (Group)
      region (String)
```

The following would load the contents from the file into tables. The first load statement loads the root group. The second load statement loads the contents of the *salesrep* group as a table. The third loads the *headquarter* group as a table. The fourth loads the *region* group in as a table.

```
LOAD * FROM [...] (parquet);
LOAD * FROM [...] (parquet, table is [company:salesrep.salesrep]);
LOAD * FROM [...] (parquet, table is [company:headquarter.headquarter]
LOAD * FROM [...] (parquet, table is [company:headquarter.headquarter.city:region.region]
```

### Limitations:

The **Table is** specifier is only relevant for Excel, XML, or Parquet files.

### Quotes

**Quotes** is a file specifier for the **LOAD** statement that defines whether quotes can be used and the precedence between quotes and separators. For text files only.

### Syntax:

```
no quotes
msq
```

If the specifier is omitted, standard quoting is used, that is, the quotes " " or ' ' can be used, but only if they are the first and last non blank character of a field value.

### Arguments:

Arguments

Argument	Description
no quotes	Used if quotation marks are not to be accepted in a text file.
msq	Used to specify modern style quoting, allowing multi-line content in fields. Fields containing end-of-line characters must be enclosed within double quotes.  One limitation of the msq option is that single double-quote (") characters appearing as first or last character in field content will be interpreted as start or end of multi-line content, which may lead to unpredicted results in the data set loaded. In this case you should use standard quoting instead, omitting the specifier.

### XML

This script specifier is used when loading xml files. Valid options for the **XML** specifier are listed in syntax.



You cannot load DTD files in Qlik Sense.

### Syntax:

```
xmlsimple
```

### See also:

[Load \(page 154\)](#)

### KML

This script specifier is used when loading KML files to use in a map visualization.

### Syntax:

```
kml
```

The KML file can represent either area data (for example, countries or regions) represented by polygons, line data (for example tracks or roads), or point data (for example, cities or places) represented by points in the form [long, lat].

### URL is

This script specifier is used to set the URL of a web file data connection when loading a web file.

### Syntax:

```
URL is string
```

### Arguments:

#### Arguments

Argument	Description
string	Specifies the URL of the file to load. This will override the URL set in the web file connection that is used.

### Limitations:

The **URL is** specifier is only relevant for web files. You need to use an existing web file data connection.

### See also:

[Load \(page 154\)](#)

userAgent is

This script specifier is used to set the browser user agent when loading a web file.

**Syntax:**

```
userAgent is string
```

**Arguments:**

Arguments


Argument	Description
string	Specifies the browser user agent string. This will override the default browser user agent "Mozilla/5.0".

**Limitations:**

The **userAgent is** specifier is only relevant for web files.

---

**See also:**

 [Load \(page 154\)](#)

## Let

The **let** statement is a complement to the **set** statement, used for defining script variables. The **let** statement, in opposition to the **set** statement, evaluates the expression on the right side of the '=' at script run time before it is assigned to the variable.

**Syntax:**

```
Let variablename=expression
```

Examples and results:

Example	Result
Set x=3+4; Let y=3+4; z=\$(y)+1;	\$(x) will be evaluated as ' 3+4 '  \$(y) will be evaluated as ' 7 '  \$(z) will be evaluated as ' 8 '  Note the difference between the <b>Set</b> and <b>Let</b> statements. The <b>Set</b> statement assigns the string '3+4' to the variable whereas the <b>Let</b> statement evaluates the string and assigns 7 to the variable.
Let T=now( );	\$(T) will be given the value of the current time.

### Loosen Table

One or more Qlik Sense internal data tables can be explicitly declared loosely coupled during script execution by using a **Loosen Table** statement. When a table is loosely coupled, all associations between field values in the table are removed. A similar effect could be achieved by loading each field of the loosely coupled table as independent, unconnected tables. Loosely coupled can be useful during testing to temporarily isolate different parts of the data structure. A loosely coupled table can be identified in the table viewer by the dotted lines. The use of one or more **Loosen Table** statements in the script will make Qlik Sense disregard any setting of tables as loosely coupled made before the script execution.

#### Syntax:

```
Loosen Tabletablename [ , tablename2 ...]  
Loosen Tablestablename [ , tablename2 ...]
```

Either syntax: **Loosen Table** or **Loosen Tables** can be used.



*Should Qlik Sense find circular references in the data structure which cannot be broken by tables declared loosely coupled interactively or explicitly in the script, one or more additional tables will be forced loosely coupled until no circular references remain. When this happens, the **Loop Warning** dialog, gives a warning.*

#### Example:

```
Tab1:  
SELECT * from Trans;  
Loosen Table Tab1;
```

### Map

The **map ... using** statement is used for mapping a certain field value or expression to the values of a specific mapping table. The mapping table is created through the **Mapping** statement.

#### Syntax:

```
Map fieldlist Using mapname
```

The automatic mapping is done for fields loaded after the **Map ... Using** statement until the end of the script or until an **Unmap** statement is encountered.

The mapping is done last in the chain of events leading up to the field being stored in the internal table in Qlik Sense. This means that mapping is not done every time a field name is encountered as part of an expression, but rather when the value is stored under the field name in the internal table. If mapping on the expression level is required, the **Applymap()** function has to be used instead.

### Arguments:

#### Arguments

Argument	Description
<i>fieldlist</i>	A comma separated list of the fields that should be mapped from this point in the script. Using * as field list indicates all fields. The wildcard characters * and ? are allowed in field names. Quoting of field names may be necessary when wildcards are used.
<i>mapname</i>	The name of a mapping table previously read in a <b>mapping load</b> or <b>mapping select</b> statement.

#### Examples and results:

Example	Result
Map Country Using Cmap;	Enables mapping of the field Country using the map Cmap.
Map A, B, C Using X;	Enables mapping of the fields A, B and C using the map X.
Map * Using GenMap;	Enables mapping of all fields using GenMap.

## NullAsNull

The **NullAsNull** statement turns off the conversion of NULL values to string values previously set by a **NullAsValue** statement.

### Syntax:

```
NullAsNull *fieldlist
```

The **NullAsValue** statement operates as a switch and can be turned on or off several times in the script, using either a **NullAsValue** or a **NullAsNull** statement.

### Arguments:

#### Arguments

Argument	Description
*fieldlist	A comma separated list of the fields for which <b>NullAsNull</b> should be turned on. Using * as field list indicates all fields. The wildcard characters * and ? are allowed in field names. Quoting of field names may be necessary when wildcards are used.

### Example:

```
NullAsNull A,B;
```



```
LOAD A,B from x.csv;
```

### NullAsValue

The **NullAsValue** statement specifies for which fields that NULL should be converted to a value.

#### Syntax:

```
NullAsValue *fieldlist
```

By default, Qlik Sense considers NULL values to be missing or undefined entities. However, certain database contexts imply that NULL values are to be considered as special values rather than simply missing values. The fact that NULL values are normally not allowed to link to other NULL values can be suspended by means of the **NullAsValue** statement.

The **NullAsValue** statement operates as a switch and will operate on subsequent loading statements. It can be switched off again by means of the **NullAsNull** statement.

#### Arguments:

##### Arguments

Argument	Description
*fieldlist	A comma separated list of the fields for which <b>NullAsValue</b> should be turned on. Using * as field list indicates all fields. The wildcard characters * and ? are allowed in field names. Quoting of field names may be necessary when wildcards are used.

#### Example:

```
NullAsValue A,B;  
Set NullValue = 'NULL';  
LOAD A,B from x.csv;
```

### Qualify

The **Qualify** statement is used for switching on the qualification of field names, i.e. field names will get the table name as a prefix.

#### Syntax:

```
Qualify *fieldlist
```

The automatic join between fields with the same name in different tables can be suspended by means of the **qualify** statement, which qualifies the field name with its table name. If qualified, the field name(s) will be renamed when found in a table. The new name will be in the form of *tablename.fieldname*. *Tablename* is equivalent to the label of the current table, or, if no label exists, to the name appearing after **from** in **LOAD** and **SELECT** statements.

The qualification will be made for all fields loaded after the **qualify** statement.

## 3 Script statements and keywords

Qualification is always turned off by default at the beginning of script execution. Qualification of a field name can be activated at any time using a **qualify** statement. Qualification can be turned off at any time using an **Unqualify** statement.



The **qualify** statement should not be used in conjunction with partial reload.

### Arguments:

#### Arguments

Argument	Description
*fieldlist	A comma separated list of the fields for which qualification should be turned on. Using * as field list indicates all fields. The wildcard characters * and ? are allowed in field names. Quoting of field names may be necessary when wildcards are used.

### Example 1:

```
Qualify B;  
LOAD A,B from x.csv;  
LOAD A,B from y.csv;
```

The two tables **x.csv** and **y.csv** are associated only through **A**. Three fields will result: A, x.B, y.B.

### Example 2:

In an unfamiliar database, it is often useful to start out by making sure that only one or a few fields are associated, as illustrated in this example:

```
qualify *;  
unqualify TransID;  
SQL SELECT * from tab1;  
SQL SELECT * from tab2;  
SQL SELECT * from tab3;
```

Only **TransID** will be used for associations between the tables *tab1*, *tab2* and *tab3*.

## Rem

The **rem** statement is used for inserting remarks, or comments, into the script, or to temporarily deactivate script statements without removing them.

### Syntax:

```
Rem string
```

Everything between the **rem** and the next semicolon ; is considered to be a comment.

There are two alternative methods available for making comments in the script:

## 3 Script statements and keywords

1. It is possible to create a comment anywhere in the script - except between two quotes - by placing the section in question between `/*` and `*/`.
2. When typing `//` in the script, all text that follows to the right on the same row becomes a comment. (Note the exception `//:` that may be used as part of an Internet address.)

### Arguments:

Arguments

Argument	Description
string	An arbitrary text.

### Example:

```
Rem ** This is a comment **;  
/* This is also a comment */  
// This is a comment as well
```

## Rename

The **Rename** script keyword can be used to rename tables or fields that are already loaded.

### Rename field

This script function renames one or more existing Qlik Sense field(s) after they have been loaded.



*It is not recommended to name a variable identically to a field or a function in Qlik Sense.*

Either syntax: **rename field** or **rename fields** can be used.

### Syntax:

```
Rename Field (using mapname | oldname to newname{ , oldname to newname })  
Rename Fields (using mapname | oldname to newname{ , oldname to newname })
```

### Arguments:

Argument	Description
mapname	The name of a previously loaded mapping table containing one or more pairs of old and new field names.
oldname	The old field name.
newname	The new field name.

### Limitations:

You cannot rename two fields to having the same name.

### Example 1:

```
Rename Field XAZ0007 to Sales;
```

### Example 2:

```
FieldMap:  
Mapping SQL SELECT oldnames, newnames from datadictionary;  
Rename Fields using FieldMap;
```

## Rename table

This script function renames one or more existing Qlik Sense internal table(s) after they have been loaded.

Either syntax: **rename table** or **rename tables** can be used.

### Syntax:

```
Rename Table (using mapname | oldname to newname{ , oldname to newname })  
Rename Tables (using mapname | oldname to newname{ , oldname to newname })
```

### Arguments:

Arguments

Argument	Description
mapname	The name of a previously loaded mapping table containing one or more pairs of old and new table names.
oldname	The old table name.
newname	The new table name.

### Limitations:

Two differently named tables cannot be renamed to having the same name. The script will generate an error if you try to rename a table to the same name as an existing table.

### Example 1:

```
Tab1:  
SELECT * from Trans;  
Rename Table Tab1 to Xyz;
```

### Example 2:

```
TabMap:  
Mapping LOAD oldnames, newnames from tabnames.csv;  
Rename Tables using TabMap;
```

### Search

The **Search** statement is used for including or excluding fields in smart search.

**Syntax:**

```
Search Include *fieldlist
```

```
Search Exclude *fieldlist
```

You can use several Search statements to refine your selection of fields to include. The statements are evaluated from top to bottom.

**Arguments:**

Arguments

Argument	Description
*fieldlist	A comma separated list of the fields to include or exclude from searches in smart search. Using * as field list indicates all fields. The wildcard characters * and ? are allowed in field names. Quoting of field names may be necessary when wildcards are used.

**Example:**

Search examples

Statement	Description
Search Include *;	Include all fields in searches in smart search.
Search Exclude [*ID];	Exclude all fields ending with ID from searches in smart search.
Search Exclude '*ID';	Exclude all fields ending with ID from searches in smart search.
Search Include ProductID;	Include the field ProductID in searches in smart search.

The combined result of these three statements, in this sequence, is that all fields ending with ID except ProductID are excluded from searches in smart search.

### Section

With the **section** statement, it is possible to define whether the subsequent **LOAD** and **SELECT** statements should be considered as data or as a definition of the access rights.

**Syntax:**

```
Section (access | application)
```

If nothing is specified, **section application** is assumed. The **section** definition is valid until a new **section** statement is made.

### Example:

```
Section access;  
Section application;
```

### Select

The selection of fields from an ODBC data source or OLE DB provider is made through standard SQL **SELECT** statements. However, whether the **SELECT** statements are accepted depends on the ODBC driver or OLE DB provider used. Use of the **SELECT** statement requires an open data connection to the source.

### Syntax:

```
Select [all | distinct | distinctrow | top n [percent] ] fieldlist  
  
From tablelist  
  
[where criterion ]  
  
[group by fieldlist [having criterion ] ]  
  
[order by fieldlist [asc | desc] ]  
  
[ (Inner | Left | Right | Full) join tablename on fieldref = fieldref ]
```

Furthermore, several **SELECT** statements can sometimes be concatenated into one through the use of a **union** operator:

```
selectstatement Union selectstatement
```

The **SELECT** statement is interpreted by the ODBC driver or OLE DB provider, so deviations from the general SQL syntax might occur depending on the capabilities of the ODBC drivers or OLE DB provider, for example:

- **as** is sometimes not allowed, i.e. *aliasname* must follow immediately after *fieldname*.
- **as** is sometimes compulsory if an *aliasname* is used.
- **distinct**, **as**, **where**, **group by**, **order by**, or **union** is sometimes not supported.
- The ODBC driver sometimes does not accept all the different quotation marks listed above.



*This is not a complete description of the SQL **SELECT** statement! E.g. **SELECT** statements can be nested, several joins can be made in one **SELECT** statement, the number of functions allowed in expressions is sometimes very large, etc.*

## 3 Script statements and keywords

### Arguments:

#### Arguments

Argument	Description
distinct	<b>distinct</b> is a predicate used if duplicate combinations of values in the selected fields only should be loaded once.
distinctrow	<b>distinctrow</b> is a predicate used if duplicate records in the source table only should be loaded once.
fieldlist	<p><b>fieldlist ::= (*  field ) {, field }</b> A list of the fields to be selected. Using * as field list indicates all fields in the table.</p> <p><b>fieldlist ::= field {, field }</b> A list of one or more fields, separated by commas.</p> <p><b>field ::= ( fieldref   expression ) [as aliasname ]</b> The expression can e.g. be a numeric or string function based on one or several other fields. Some of the operators and functions usually accepted are: +, -, *, /, &amp; (string concatenation), sum(fieldname), count(fieldname), avg(fieldname) (average), month(fieldname), etc. See the documentation of the ODBC driver for more information.</p> <p><b>fieldref ::= [ tablename. ] fieldname</b> The <b>tablename</b> and the <b>fieldname</b> are text strings identical to what they imply. They must be enclosed by straight double quotation marks if they contain e.g. spaces. The <b>as</b> clause is used for assigning a new name to the field.</p>
from	<p><b>tablelist ::= table {, table }</b> The list of tables that the fields are to be selected from.</p> <p><b>table ::= tablename [ [as ] aliasname ]</b> The <b>tablename</b> may or may not be put within quotes.</p>
where	<p><b>where</b> is a clause used for stating whether a record should be included in the selection or not.</p> <p><b>criterion</b> is a logical expression that can sometimes be very complex. Some of the operators accepted are: numeric operators and functions, =, &lt;&gt; or #(not equal), &gt;, &gt;=, &lt;, &lt;=, <b>and</b>, <b>or</b>, <b>not</b>, <b>exists</b>, <b>some</b>, <b>all</b>, <b>in</b> and also new <b>SELECT</b> statements. See the documentation of the ODBC driver or OLE DB provider for more information.</p>
group by	<b>group by</b> is a clause used for aggregating (group) several records into one. Within one group, for a certain field, all the records must either have the same value, or the field can only be used from within an expression, e.g. as a sum or an average. The expression based on one or several fields is defined in the expression of the field symbol.

## 3 Script statements and keywords

---

Argument	Description
having	<b>having</b> is a clause used for qualifying groups in a similar manner to how the <b>where</b> clause is used for qualifying records.
order by	<b>order by</b> is a clause used for stating the sort order of the resulting table of the <b>SELECT</b> statement.
join	<b>join</b> is a qualifier stating if several tables are to be joined together into one. Field names and table names must be put within quotes if they contain blank spaces or letters from the national character sets. When the script is automatically generated by Qlik Sense, the quotation mark used is the one preferred by the ODBC driver or OLE DB provider specified in the data source definition of the data source in the <b>Connect</b> statement.

### Example 1:

```
SELECT * FROM `Categories`;
```

### Example 2:

```
SELECT `Category ID`, `Category Name` FROM `Categories`;
```

### Example 3:

```
SELECT `Order ID`, `Product ID`,  
`Unit Price` * Quantity * (1-Discount) as NetSales  
FROM `Order Details`;
```

### Example 4:

```
SELECT `Order Details`.`Order ID`,  
Sum(`Order Details`.`Unit Price` * `Order Details`.Quantity) as `Result`  
FROM `Order Details`, Orders  
where Orders.`Order ID` = `Order Details`.`Order ID`  
group by `Order Details`.`Order ID`;
```

## Set

The **set** statement is used for defining script variables. These can be used for substituting strings, paths, drives, and so on.

### Syntax:

```
Set variablename=string
```

### Example 1:

```
Set FileToUse=Data1.csv;
```

### Example 2:

```
Set Constant="My string";
```



### Example 3:

```
Set BudgetYear=2012;
```

## Sleep

The **sleep** statement pauses script execution for a specified time.

### Syntax:

```
Sleep n
```

### Arguments:

Argument	Description
n	Stated in milliseconds, where <i>n</i> is a positive integer no larger than 3600000 (i.e. 1 hour). The value may be an expression.

### Example 1:

```
sleep 10000;
```

### Example 2:

```
sleep t*1000;
```

## SQL

The **SQL** statement allows you to send an arbitrary SQL command through an ODBC or OLE DB connection.

### Syntax:

```
SQL sql_command
```

Sending SQL statements which update the database will return an error if Qlik Sense has opened the ODBC connection in read-only mode.

The syntax:

```
SQL SELECT * from tab1;
```

is allowed, and is the preferred syntax for **SELECT**, for reasons of consistency. The SQL prefix will, however, remain optional for **SELECT** statements.

### Arguments:

Argument	Description
<i>sql_command</i>	A valid SQL command.

### Example 1:

```
SQL Leave;
```

### Example 2:

```
SQL Execute <storedProc>;
```

## SQLColumns

The **sqlcolumns** statement returns a set of fields describing the columns of an ODBC or OLE DB data source, to which a **connect** has been made.

### Syntax:

```
SQLcolumns
```

The fields can be combined with the fields generated by the **sqltables** and **sqltypes** commands in order to give a good overview of a given database. The twelve standard fields are:

TABLE\_QUALIFIER

TABLE\_OWNER

TABLE\_NAME

COLUMN\_NAME

DATA\_TYPE

TYPE\_NAME

PRECISION

LENGTH

SCALE

RADIX

NULLABLE

REMARKS

For a detailed description of these fields, see an ODBC reference handbook.

### Example:

```
Connect to 'MS Access 7.0 Database; DBQ=C:\Course3\DataSrc\QWT.mbd';  
SQLcolumns;
```



*Some ODBC drivers may not support this command. Some ODBC drivers may produce additional fields.*

### SQLTables

The **sqltables** statement returns a set of fields describing the tables of an ODBC or OLE DB data source, to which a **connect** has been made.

#### Syntax:

```
SQLTables
```

The fields can be combined with the fields generated by the **sqlcolumns** and **sqltypes** commands in order to give a good overview of a given database. The five standard fields are:

TABLE\_QUALIFIER

TABLE\_OWNER

TABLE\_NAME

TABLE\_TYPE

REMARKS

For a detailed description of these fields, see an ODBC reference handbook.

#### Example:

```
Connect to 'MS Access 7.0 Database; DBQ=C:\Course3\DataSrc\QWT.mbd';  
SQLTables;
```



*Some ODBC drivers may not support this command. Some ODBC drivers may produce additional fields.*

### SQLTypes

The **sqltypes** statement returns a set of fields describing the types of an ODBC or OLE DB data source, to which a **connect** has been made.

#### Syntax:

```
SQLTypes
```

The fields can be combined with the fields generated by the **sqlcolumns** and **sqltables** commands in order to give a good overview of a given database. The fifteen standard fields are:

TYPE\_NAME

DATA\_TYPE

PRECISION  
LITERAL\_PREFIX  
LITERAL\_SUFFIX  
CREATE\_PARAMS  
NULLABLE  
CASE\_SENSITIVE  
SEARCHABLE  
UNSIGNED\_ATTRIBUTE  
MONEY  
AUTO\_INCREMENT  
LOCAL\_TYPE\_NAME  
MINIMUM\_SCALE  
MAXIMUM\_SCALE

For a detailed description of these fields, see an ODBC reference handbook.

**Example:**

```
Connect to 'MS Access 7.0 Database; DBQ=C:\Course3\DataSrc\QWT.mbd';  
SQLTypes;
```



*Some ODBC drivers may not support this command. Some ODBC drivers may produce additional fields.*

## Star

The string used for representing the set of all the values of a field in the database can be set through the **star** statement. It affects the subsequent **LOAD** and **SELECT** statements.

**Syntax:**

```
Star is [ string ]
```

### Arguments:

#### Arguments

Argument	Description
string	<p>An arbitrary text. Note that the string must be enclosed by quotation marks if it contains blanks.</p> <p>If nothing is specified, <b>star is</b>; is assumed, i.e. there is no star symbol available unless explicitly specified. This definition is valid until a new <b>star</b> statement is made.</p>

The **Star is** statement is not recommended for use in the data part of the script (under **Section Application**) if section access is used. The star character is however fully supported for the protected fields in the **Section Access** part of the script. In this case you do not need to use the explicit **Star is** statement since this is always implicit in section access.

### Limitations

- You cannot use the star character with key fields; that is, fields that link tables.
- You cannot use the star character with any fields affected by the **Unqualify** statement as this can affect fields that link tables.
- You cannot use the star character with non-logical tables, for example, info-load tables or mapping-load tables.
- When the star character is used in a reducing field (a field that links to the data) in section access, it represents the values listed in this field in section access. It does not represent other values that may exist in the data but are not listed in section access.
- You cannot use the star character with fields affected by any form of data reduction outside the **Section Access** area.

### Example

The example below is an extract of a data load script featuring section access.

```
star is *;

Section Access;
LOAD * INLINE [
ACCESS, USERID, OMIT
ADMIN, ADMIN,
USER, USER1, SALES
USER, USER2, WAREHOUSE
USER, USER3, EMPLOYEES
USER, USER4, SALES
USER, USER4, WAREHOUSE
USER, USER5, *
];

Section Application;
LOAD * INLINE [
SALES, WAREHOUSE, EMPLOYEES, ORDERS
1, 2, 3, 4
```

];

The following applies:

- The *Star* sign is `*`.
- The user `ADMIN` sees all fields. Nothing is omitted.
- The user `USER1` is not able to see the field `SALES`.
- The user `USER2` is not able to see the field `WAREHOUSE`.
- The user `USER3` cannot see the field `EMPLOYEES`.
- The user `USER4` is added twice to the solution to OMIT two fields for this user, `SALES` and `WAREHOUSE`.
- The `USER5` has a `"*"` added which means that all listed fields in OMIT are unavailable, that is, user `USER5` cannot see the fields `SALES`, `WAREHOUSE` and `EMPLOYEES` but this user can see the field `ORDERS`.

### Store

The **Store** statement creates a QVD, Parquet, CSV, or TXT file.

#### Syntax:

```
Store [ fieldlist from] table into filename [ format-spec ];
```

The statement will create an explicitly named QVD, Parquet, or text file.

The statement can only export fields from one data table, unless you are storing to Parquet. If fields from several tables are to be exported into a QVD, CSV, or TXT file, an explicit join must be made previously in the script to create the data table that should be exported. You can store multiple tables in a single Parquet by nesting the data in the Parquet files.

The text values are exported to the CSV file in UTF-8 with BOM format. A delimiter can be specified, see **LOAD**. The **store** statement to a CSV file does not support BIFF export.



*In some cases with data that is not well-formed, fields will be surrounded by double quotes to ensure that the data is interpreted correctly. This can happen, for example, when the field contains characters such as quotes, comma, space or line breaks.*

## 3 Script statements and keywords

### Arguments:

Store command arguments

Argument	Description
<i>fieldlist</i> ::= ( *   <i>field</i> ) { , <i>field</i> }	<p>A list of the fields to be selected. Using * as field list indicates all fields.</p> <p><i>field</i>::= <i>fieldname</i> [<b>as</b> <i>aliasname</i> ]</p> <p><i>fieldname</i> is a text that is identical to a field name in <i>table</i>. (Note that the field name must be enclosed by straight double quotation marks or square brackets if it contains spaces or other non-standard characters.)</p> <p><i>aliasname</i> is an alternate name for the field to be used in the resulting QVD or CSV file.</p>
<i>table</i>	<p>A script label representing an already loaded table to be used as source for data.</p>
<i>filename</i>	<p>The name of the target file including a valid path to an existing folder data connection.</p> <p><b>Example: 'lib://Table Files/target.qvd'</b></p> <p>In legacy scripting mode, the following path formats are also supported:</p> <ul style="list-style-type: none"><li>absolute</li></ul> <p><b>Example: c:\data\sales.qvd</b></p> <ul style="list-style-type: none"><li>relative to the Qlik Sense app working directory.</li></ul> <p><b>Example: data\sales.qvd</b></p> <p>If the path is omitted, Qlik Sense stores the file in the directory specified by the <b>Directory</b> statement. If there is no <b>Directory</b> statement, Qlik Sense stores the file in the working directory, <i>C:\Users\{user}\Documents\Qlik\Sense\Apps</i>.</p>

## 3 Script statements and keywords

Argument	Description
<code>format-spec ::= ( <b>txt</b>   <b>qvd</b>   <b>parquet</b> ), <b>compression is</b> <i>codec</i></code>	<p>You can set the format specification to either of these file formats. If the format specification is omitted, <b>qvd</b> is assumed.</p> <ul style="list-style-type: none"><li>• <b>txt</b> for CSV and TXT files.</li><li>• <b>qvd</b> for QVD files.</li><li>• <b>parquet</b> for Parquet files.</li></ul> <p>If you use <b>parquet</b>, you can also set which compression codec to use with <b>compression is</b>. If you do not specify the compression codec with <b>compression is</b>, snappy is used. The following compression settings are available:</p> <ul style="list-style-type: none"><li>• uncompressed</li><li>• snappy</li><li>• gzip</li><li>• lz4</li><li>• brotli</li><li>• zstd</li><li>• lz4_hadoop</li></ul> <p>Example:</p> <pre>Store mytable into [lib://AttachedFiles/myfile.parquet] (parquet, compression is lz4);</pre>

### Examples:

```
Store mytable into xyz.qvd (qvd);
Store * from mytable into 'lib://FolderConnection/myfile.qvd';
Store Name, RegNo from mytable into xyz.qvd;
Store Name as a, RegNo as b from mytable into 'lib://FolderConnection/myfile.qvd';
Store mytable into myfile.txt (txt);
Store mytable into [lib://FolderConnection/myfile.csv] (txt);
Store mytable into myfile.parquet (parquet);
Store * from mytable into 'lib://FolderConnection/myfile.qvd';
```

### Storing in Parquet files

Parquet is a strongly typed file format, where each field contains a single specific type of data (such as in32, double, timestamp, or text). Qlik Sense stores internal data as a loosely typed dual, where data from different sources can be mixed into the same fields. As only one part of the dual can be stored in each field in Parquet, it is important to know what each field contains. By default, Qlik Sense uses the field type to determine how the field should be stored. When storing data in Parquet files in a specific format, you must specify what type of data your fields are when loading them. If you try to store data into incompatible fields in a Parquet file, such as numbers in a text field or text in a timestamp field, you will end up with null values.



## 3 Script statements and keywords

---

When loading data you intend to store in Parquet, it is possible to change the default behavior. You can either format it to change your data type or tag it to force specific column types in Parquet.

### Formatting data for storage in Parquet

You can use Qlik Sense formatting functions to classify your data. For example, **Text()**, **Num()**, **Interval()**, or **Timestamp()** can enforce data formats when storing data in Parquet. Qlik Sense can store data into almost 20 data types depending on field attributes and automatic field tags. For more information, see *Interpretation functions (page 1265)*

#### Example: Formatting data with Num() and Text()

The following example demonstrates preparing data for storage in Parquet. **Num()** is applied to the num field. **Text()** is applied to both text and mixed. In the case of mixed, **Text()** prevents it from being treated like a number field in Parquet and having the text values changed to null values.

Data:

```
LOAD * INLINE [  
num, text, mixed  
123.321, abc, 123  
456.654, def, xyz  
789.987, ghi, 321  
];
```

Format:

```
NoConcatenate  
LOAD num, text, Text(mixed) as mixed RESIDENT Data;  
STORE Format INTO [lib://AttachedFiles/Tmp.parquet] (parquet);
```

### Tagging data for storage in Parquet

You tag your data with \$parquet tags to force specific column types when storing data in Parquet. Each data type can be enforced by adding the corresponding control tag. For example, to store a field as INT32 in Parquet, tag it with \$parquet-int32 in the load script. Depending on the data type, either the string or the numerical representation of the dual data will be stored.

The following Parquet control tags can be used to tag fields for storing in Parquet files.

Parquet control tags				
Control tag	Dual	Physical type	Logical type	Converted type
\$parquet-boolean	Number	BOOLEAN	NONE	NONE
\$parquet-int32	Number	INT32	NONE	NONE
\$parquet-int64	Number	INT64	NONE	NONE
\$parquet-float	Number	FLOAT	NONE	NONE
\$parquet-double	Number	DOUBLE	NONE	NONE
\$parquet-bytearray	String	BYTE_ARRAY	NONE	UTF8
\$parquet-bytearrayfix	Number	FIXED_LEN_BYTE_	NONE	DECIMAL

## 3 Script statements and keywords

---

Control tag	Dual	Physical type	Logical type	Converted type
		ARRAY		
\$parquet-decimal	Number	INT64	DECIMAL	DECIMAL
\$parquet-date	Number	INT32	DATE	DATE
\$parquet-time	Number	INT64	TIME	TIME_MICROS
\$parquet-timestamp	Number	INT64	TIMESTAMP	TIMESTAMP_ MICROS
\$parquet-string	String	BYTE_ARRAY	STRING	UTF8
\$parquet-enum	String	BYTE_ARRAY	ENUM	ENUM
\$parquet-interval	Number	FIXED_LEN_BYTE_ ARRAY	INTERVAL	INTERVAL
\$parquet-json	String	BYTE_ARRAY	JSON	JSON
\$parquet-bson	String	BYTE_ARRAY	BSON	BSON
\$parquet-uuid	String	FIXED_LEN_BYTE_ ARRAY	UUID	NONE

### Example: Tagging data for storage in Parquet

In this example, two tags are used to define the data for Parquet. The field *num* is tagged with `$parquet-int32` to define it as a number field that will be set as INT32 in Parquet.

```
Data:
LOAD * INLINE [
num, text,
123.321, abc
456.654, def
789.987, ghi
];
TAG num WITH '$parquet-int32';
STORE Format INTO [lib://AttachedFiles/Tmp.parquet] (parquet);
```

### Storing nested data in Parquet files

You can store multiple tables in a Parquet files by nesting them into structured data. **Store** supports structured nodes and list nodes in a star schema. Single tables can also be stored in nested mode by using the **Delimiter is** specifier.

When storing tables, specify the tables you want to include separated by commas. For example: `STORE Table1, Table2, Table3 INTO [lib://<file location>/<file name>.parquet] (parquet);`. You can control which fields are stored by using a field list in the **Store** statement. For example `STORE Field1, Field2, FROM Table1, Table2 INTO [lib://<file location>/<file name>.parquet] (parquet);`. All fields in the field list must be in one or more of the listed tables. The first table in the **Store** statement will be used as the fact table in the star schema.

## 3 Script statements and keywords

---

Field names are used to control how groups will be created and nested. By default, field names are split into nodes with a period (.). The delimiter can be changed by setting the system variable *FieldNameDelimiter* or by using the specifier **Delimiter is**. The specifier will override the system variable..

Field names are split by the delimiter and the parts are used to create the schema with nested groups. For example, `STORE Field1, Field1.Field2, Field1.Field3, Field1.Field4 FROM Table1 INTO [nested.parquet] (parquet, delimiter is '.');` will create two groups (*Group1* and *Group2*) with *Fields1*, *Field2* and *Field3*, *Field4*.



*Groups and fields may not have the same name in a node in the schema. For example, `STORE Address, Address.Street INTO [nested.parquet] (parquet, delimiter is '.');` will fail because *Address* is ambiguous and is both a data field and a group.*

When storing nested data in Parquet, keys between tables are transformed into link nodes in the schema. Tables are transformed into structured nodes in the schema. You can override the default transformation using field names.

### Example: Storing nested data in a Parquet file

company:

```
LOAD * INLINE [  
company, contact  
A&G, Amanda Honda  
Cabro, Cary Frank  
Fenwick, Dennis Fisher  
Camros, Molly McKenzie  
];
```

salesrep:

```
LOAD * INLINE [  
company, salesrep  
A&G, Bob Park  
Cabro, Cezar Sandu  
Fenwick, Ken Roberts  
Camros, Max Smith  
];
```

headquarter:

```
LOAD * INLINE [  
company, country, city  
A&G, USA, Los Angeles  
Cabro, USA, Albuquerque  
Fenwick, USA, Baltimore  
Camros, USA, Omaha  
];
```

region:

```
LOAD * INLINE [  
region, city  
west, Los Angeles  
Southwest, Albuquerque
```

```
East, Baltimore
Central, Omaha
];
```

```
STORE company, salesrep, headquarter, region INTO [lib://AttachedFiles/company.parquet]
(parquet)
```

```
DROP TABLES company, salesrep, headquarter, region;
```

The resulting Parquet file has the following schema:

```
company (String)
contact (String)
company:salesrep (List)
    salesrep (Group)
        salesrep (String)
company:headquarter (List)
    headquarter (Group)
        country (String)
        city (String)
        city:region (List)
            region (Group)
                region (String)
```

### Limitations

Storing nested data in Parquet has the following limitations:

- Store does not support map nodes.
- Storing does not include key fields generated from loading nested parquet files.
- You cannot store data from tables together that are not linked with key fields.
- The nested file denormalizes the data model. Non-referenced values will not be saved and values referenced multiple times will be copied.

### Table/Tables

The **Table** and **Tables** script keywords are used in **Drop**, **Comment** and **Rename** statements, as well as a format specifier in **Load** statements.

### Tag

This script statement provides a way to assign tags to one or more fields or tables. If an attempt to tag a field or table not present in the app is made, the tagging will be ignored. If conflicting occurrences of a field or tag name are found, the last value is used.

#### Syntax:

```
Tag [field|fields] fieldlist with tagname
```

```
Tag [field|fields] fieldlist using mapname
```

```
Tag table tablelist with tagname
```

## 3 Script statements and keywords

---

### Arguments

Argument	Description
fieldlist	One or several fields that should be tagged, in a comma separated list.
mapname	The name of a mapping table previously loaded in a <b>mapping Load</b> or <b>mapping Select</b> statement.
tablelist	A comma separated list of the tables that should be tagged.
tagname	The name of the tag that should be applied to the field.

#### Example 1:

```
tagmap:
mapping LOAD * inline [
a,b
Alpha,MyTag
Num,MyTag
];
tag fields using tagmap;
```

#### Example 2:

```
tag field Alpha with 'MyTag2';
```

## Trace

The **trace** statement writes a string to the **Script Execution Progress** window and to the script log file, when used. It is very useful for debugging purposes. Using **\$**-expansions of variables that are calculated prior to the **trace** statement, you can customize the message.

#### Syntax:

```
Trace string
```

#### Example 1:

The following statement can be used right after the Load statement that loads the 'Main' table.

```
Trace Main table loaded;
```

This will display the text 'Main table loaded' in the script execution dialog and in the log file.

#### Example 2:

The following statements can be used right after the Load statement that loads the 'Main' table.

```
Let MyMessage = NoOfRows('Main') & ' rows in Main table';
Trace $(MyMessage);
```

This will display a text showing the number of rows in the script execution dialog and in the log file, for example, '265,391 rows in Main table'.

### Unmap

The **Unmap** statement disables field value mapping specified by a previous **Map ... Using** statement for subsequently loaded fields.

**Syntax:**

```
Unmap *fieldlist
```

**Arguments:**

Arguments

Argument	Description
*fieldlist	a comma separated list of the fields that should no longer be mapped from this point in the script. Using * as field list indicates all fields. The wildcard characters * and ? are allowed in field names. Quoting of field names may be necessary when wildcards are used.

Examples and results:

Example	Result
Unmap Country;	Disables mapping of field Country.
Unmap A, B, C;	Disables mapping of fields A, B and C.
Unmap * ;	Disables mapping of all fields.

### Unqualify

The **Unqualify** statement is used for switching off the qualification of field names that has been previously switched on by the **Qualify** statement.

**Syntax:**

```
Unqualify *fieldlist
```

**Arguments:**

Arguments

Argument	Description
*fieldlist	A comma separated list of the fields for which qualification should be turned on. Using * as field list indicates all fields. The wildcard characters * and ? are allowed in field names. Quoting of field names may be necessary when wildcards are used.  Refer to the documentation for the <b>Qualify</b> statement for further information.

### Example 1:

In an unfamiliar database, it is often useful to start out by making sure that only one or a few fields are associated, as illustrated in this example:

```
qualify *;  
unqualify TransID;  
SQL SELECT * from tab1;  
SQL SELECT * from tab2;  
SQL SELECT * from tab3;
```

First, qualification is turned on for all fields.

Then qualification is turned off for **TransID**.

Only **TransID** will be used for associations between the tables *tab1*, *tab2* and *tab3*. All other fields will be qualified with the table name.

## Untag

This script statement provides a way to remove tags from fields or tables. If an attempt to untag a field or table not present in the app is made, the untagging will be ignored.

### Syntax:

```
Untag [field|fields] fieldlist with tagname
```

```
Untag [field|fields] fieldlist using mapname
```

```
Untag table tablelist with tagname
```

### Arguments:

#### Arguments

Argument	Description
fieldlist	One or several fields which tags should be removed, in a comma separated list.
mapname	The name of a mapping table previously loaded in a mapping <b>LOAD</b> or mapping <b>SELECT</b> statement.
tablelist	A comma separated list of the tables that should be untagged.
tagname	The name of the tag that should be removed from the field.

### Example 1:

```
tagmap:  
mapping LOAD * inline [  
a,b  
Alpha,MyTag  
Num,MyTag  
];  
Untag fields using tagmap;
```

### Example 2:

```
Untag field Alpha with MyTag2;
```

## 3.4 Working directory

If you are referencing a file in a script statement and the path is omitted, Qlik Sense searches for the file in the following order:

1. The directory specified by a **Directory** statement (only supported in legacy scripting mode).
2. If there is no **Directory** statement, Qlik Sense searches in the working directory.

### Qlik Sense Desktop working directory

In Qlik Sense Desktop, the working directory is *C:\Users\{user}\Documents\Qlik\Sense\Apps*.

### Qlik Sense working directory

In a Qlik Sense server installation, the working directory is specified in Qlik Sense Repository Service, by default it is *C:\ProgramData\Qlik\Sense\Apps*. See the Qlik Management Console help for more information.



# 4 Working with variables in the data load editor

A variable in Qlik Sense is a container storing a static value or a calculation, for example a numeric or alphanumeric value. When you use the variable in the app, any change made to the variable is applied everywhere the variable is used. You can define variables in the variables overview, or in the script using the Data load editor. You set the value of a variable using **Let** or **Set** statements in the data load script.



*You can also work with the Qlik Sense variables from the variables overview when editing a sheet.*

## 4.1 Overview

If the first character of a variable value is an equals sign '=' Qlik Sense will try to evaluate the value as a formula (Qlik Sense expression) and then display or return the result rather than the actual formula text.

When used, the variable is substituted by its value. Variables can be used in the script for dollar sign expansion and in various control statements. This is very useful if the same string is repeated many times in the script, for example, a path.

Some special system variables will be set by Qlik Sense at the start of the script execution regardless of their previous values.

## 4.2 Defining a variable

Variables provide the ability to store static values or the result of a calculation. When defining a variable, use the following syntax:

```
set variablename = string
```

or

```
let variable = expression
```

The **Set** statement is used for string assignment. It assigns the text to the right of the equal sign to the variable. The **Let** statement evaluates an expression to the right of the equal sign at script run time and assigns the result of the expression to the variable.

Variables are case sensitive.



*It is not recommended to name a variable identically to a field or a function in Qlik Sense.*

### Examples:

```
set x = 3 + 4; // the variable will get the string '3 + 4' as the value.
```

```
let x = 3 + 4; // returns 7 as the value.
```

```
set x = Today(); // returns 'Today()' as the value.
```

```
let x = Today(); // returns today's date as the value, for example, '9/27/2021'.
```

### 4.3 Deleting a variable

If you remove a variable from the script and reload the data, the variable stays in the app. If you want to fully remove the variable from the app, you must also delete the variable from the variables dialog.

### 4.4 Loading a variable value as a field value

If you want to load a variable value as a field value in a **LOAD** statement and the result of the dollar expansion is text rather than numeric or an expression then you need to enclose the expanded variable in single quotes.

#### Example:

This example loads the system variable containing the list of script errors to a table. You can note that the expansion of `ScriptErrorCount` in the **If** clause does not require quotes, while the expansion of `ScriptErrorList` requires quotes.

```
IF $(ScriptErrorCount) >= 1 THEN
    LOAD '$(ScriptErrorList)' AS Error AutoGenerate 1;
END IF
```

### 4.5 Variable calculation

There are several ways to use variables with calculated values in Qlik Sense, and the result depends on how you define it and how you call it in an expression.

In this example, we load some inline data:

```
LOAD * INLINE [
    Dim, Sales
    A, 150
    A, 200
    B, 240
    B, 230
    C, 410
    C, 330
];
```

Let's define two variables:

```
Let vsales = 'Sum(Sales)' ;
```

## 4 Working with variables in the data load editor

---

Let `vSales2 = '=Sum(Sales)'` ;

In the second variable, we add an equal sign before the expression. This will cause the variable to be calculated before it is expanded and the expression is evaluated.

If you use the `vSales` variable as it is, for example in a measure, the result will be the string `Sum (Sales)`, that is, no calculation is performed.

If you add a dollar-sign expansion and call `$(vSales)` in the expression, the variable is expanded, and the sum of `Sales` is displayed.

Finally, if you call `$(vSales2)`, the variable will be calculated before it is expanded. This means that the result displayed is the total sum of `Sales`. The difference between using `=$(vSales)` and `=$(vSales2)` as measure expressions is seen in this chart showing the results:

Results

Dim	\$(vSales)	\$(vSales2)
A	350	1560
B	470	1560
C	740	1560

As you can see, `$(vSales)` results in the partial sum for a dimension value, while `$(vSales2)` results in the total sum.

The following script variables are available:

- *Error variables (page 275)*
- *Number interpretation variables (page 211)*
- *System variables (page 203)*
- *Value handling variables (page 209)*

### 4.6 System variables

System variables, some of which are system-defined, provide information about the system and the Qlik Sense app.

#### System variables overview

Some of the functions are described further after the overview. For those functions, you can click the function name in the syntax to immediately access the details for that specific function.

##### **CreateSearchIndexOnReload**

This variable defines if search index files should be created during data reload.

##### **CreateSearchIndexOnReload**

##### **Floppy**

Returns the drive letter of the first floppy drive found, normally `a:`. This is a system-defined variable.

## 4 Working with variables in the data load editor

---

### Floppy



*This variable is not supported in standard mode.*

### CD

Returns the drive letter of the first CD-ROM drive found. If no CD-ROM is found, then *c:* is returned. This is a system-defined variable.

### CD



*This variable is not supported in standard mode.*

### HidePrefix

All field names beginning with this text string will be hidden in the same manner as the system fields. This is a user-defined variable.

### HidePrefix

### HideSuffix

All field names ending with this text string will be hidden in the same manner as the system fields. This is a user-defined variable.

### HideSuffix

### Include

The **Include/Must\_Include** variable specifies a file that contains text that should be included in the script and evaluated as script code. It is not used to add data. You can store parts of your script code in a separate text file and reuse it in several apps. This is a user-defined variable.

```
$(Include=filename)
```

```
$(Must_Include=filename)
```

### OpenUrlTimeout

This variable defines the timeout in seconds that Qlik Sense should respect when getting data from URL sources (e.g. HTML pages). If omitted, the timeout is about 20 minutes.

### OpenUrlTimeout

### QvPath

Returns the browse string to the Qlik Sense executable. This is a system-defined variable.

### QvPath



*This variable is not supported in standard mode.*

### QvRoot

Returns the root directory of the Qlik Sense executable. This is a system-defined variable.

## 4 Working with variables in the data load editor

---

### QvRoot



*This variable is not supported in standard mode.*

### QvWorkPath

Returns the browse string to the current Qlik Sense app. This is a system-defined variable.

### QvWorkPath



*This variable is not supported in standard mode.*

### QvWorkRoot

Returns the root directory of the current Qlik Sense app. This is a system-defined variable.

### QvWorkRoot



*This variable is not supported in standard mode.*

### StripComments

If this variable is set to 0, stripping of /\*..\*/ and // comments in the script will be inhibited. If this variable is not defined, stripping of comments will always be performed.

### StripComments

### Verbatim

Normally all field values are automatically stripped of leading and trailing blanks (ASCII 32) before being loaded into the Qlik Sense database. Setting this variable to 1 suspends the stripping of blanks. Tab (ASCII 9) and hard space (ANSI 160) characters are never stripped.

### Verbatim

### WinPath

Returns the browse string to Windows. This is a system-defined variable.

### WinPath



*This variable is not supported in standard mode.*

### WinRoot

Returns the root directory of Windows. This is a system-defined variable.

### WinRoot



*This variable is not supported in standard mode.*

---

## 4 Working with variables in the data load editor

---

### CollationLocale

Specifies which locale to use for sort order and search matching. The value is the culture name of a locale, for example 'en-US'. This is a system-defined variable.

### CollationLocale

## CreateSearchIndexOnReload

This variable defines if search index files should be created during data reload.

### Syntax:

#### CreateSearchIndexOnReload

You can define if search index files should be created during data reload, or if they should be created after the first search request of the user. The benefit of creating search index files during data reload is that you avoid the waiting time experienced by the first user making a search. This needs to be weighed against the longer data reload time required by search index creation.

If this variable is omitted, search index files will not be created during data reload.



*For session apps, search index files will not be created during data reload, regardless of the setting of this variable.*

### Example 1: Create search index fields during data reload

```
set CreateSearchIndexOnReload=1;
```

### Example 2: Create search index fields after first search request

```
set CreateSearchIndexOnReload=0;
```

## HidePrefix

All field names beginning with this text string will be hidden in the same manner as the system fields. This is a user-defined variable.

### Syntax:

#### HidePrefix

### Example:

```
set HidePrefix='_' ;
```

If this statement is used, the field names beginning with an underscore will not be shown in the field name lists when the system fields are hidden.

### HideSuffix

All field names ending with this text string will be hidden in the same manner as the system fields. This is a user-defined variable.

#### Syntax:

```
HideSuffix
```

#### Example:

```
set HideSuffix='%';
```

If this statement is used, the field names ending with a percentage sign will not be shown in the field name lists when the system fields are hidden.

### Include

The **Include/Must\_Include** variable specifies a file that contains text that should be included in the script and evaluated as script code. It is not used to add data. You can store parts of your script code in a separate text file and reuse it in several apps. This is a user-defined variable.



*This variable supports only folder data connections in standard mode.*

#### Syntax:

```
$(Include=filename)
```

```
$(Must_Include=filename)
```

There are two versions of the variable:

- **Include** does not generate an error if the file cannot be found, it will fail silently.
- **Must\_Include** generates an error if the file cannot be found.

If you don't specify a path, the filename will be relative to the Qlik Sense app working directory. You can also specify an absolute file path, or a path to a lib:// folder connection. Do not put a space character before or after the equal sign.



*The construction **set Include =filename** is not applicable.*

#### Examples:

```
$(Include=abc.txt);
```

```
$(Must_Include=lib://DataFiles/abc.txt);
```

### Limitations

Limited cross-compatibility between UTF-8 encoded files under Windows versus Linux.

It is optional to use UTF-8 with BOM (Byte Order Mark). BOM can interfere with the use of UTF-8 in software that does not expect non-ASCII bytes at the start of a file, but that could otherwise handle the text stream.

- Windows systems use BOM in UTF-8 to identify that a file is UTF-8 encoded, despite the fact that there is no ambiguity in the byte storage.
- Unix/Linux use UTF-8 for Unicode, but does not use the BOM as this interferes with the syntax for command files.

This has some implications for Qlik Sense.

- In Windows any file that begins with an UTF-8 BOM is considered a UTF-8 script file. Otherwise ANSI encoding is assumed.
- In Linux, the system default 8 bit code page is UTF-8. This is why the UTF-8 works although it does not contain a BOM.

As a result, portability cannot be guaranteed. It is not always possible to create a file on Windows that can be interpreted by Linux and vice versa. There is no cross compatibility between the two systems regarding UTF-8 encoded files due to different handling of the BOM.

### OpenUrlTimeout

This variable defines the timeout in seconds that Qlik Sense should respect when getting data from URL sources (e.g. HTML pages). If omitted, the timeout is about 20 minutes.

#### Syntax:

```
OpenUrlTimeout
```

#### Example:

```
set openUrlTimeout=10;
```

### StripComments

If this variable is set to 0, stripping of /\*..\*/ and // comments in the script will be inhibited. If this variable is not defined, stripping of comments will always be performed.

#### Syntax:

```
StripComments
```



## 4 Working with variables in the data load editor

---

Certain database drivers use `/*..*/` as optimization hints in **SELECT** statements. If this is the case, the comments should not be stripped before sending the **SELECT** statement to the database driver.



*It is recommended that this variable be reset to 1 immediately after the statement(s) where it is needed.*

### Example:

```
set StripComments=0;
SQL SELECT * /* <optimization directive> */ FROM Table ;
set StripComments=1;
```

## Verbatim

Normally all field values are automatically stripped of leading and trailing blanks (ASCII 32) before being loaded into the Qlik Sense database. Setting this variable to 1 suspends the stripping of blanks. Tab (ASCII 9) and hard space (ANSI 160) characters are never stripped.

### Syntax:

**Verbatim**

### Example:

```
set verbatim = 1;
```

## 4.7 Value handling variables

This section describes variables that are used for handling NULL and other values.

### Value handling variables overview

Each function is described further after the overview. You can also click the function name in the syntax to immediately access the details for that specific function.

#### **NullDisplay**

The defined symbol will substitute all NULL values from ODBC, and connectors, on the lowest level of data. This is a user-defined variable.

**NullDisplay**

#### **NullInterpret**

The defined symbol will be interpreted as NULL when it occurs in a text file, Excel file or an inline statement. This is a user-defined variable.

**NullInterpret**

### NullValue

If the **NullAsValue** statement is used, the defined symbol will substitute all NULL values in the **NullAsValue** specified fields with the specified string.

```
NullValue
```

### OtherSymbol

Defines a symbol to be treated as 'all other values' before a **LOAD/SELECT** statement. This is a user-defined variable.

```
OtherSymbol
```

### NullDisplay

The defined symbol will substitute all NULL values from ODBC, and connectors, on the lowest level of data. This is a user-defined variable.

#### Syntax:

```
NullDisplay
```

#### Example:

```
set NullDisplay='<NULL>';
```

### NullInterpret

The defined symbol will be interpreted as NULL when it occurs in a text file, Excel file or an inline statement. This is a user-defined variable.

#### Syntax:

```
NullInterpret
```

#### Examples:

```
set NullInterpret=' ';  
set NullInterpret =;
```

will not return NULL values for blank values in Excel, but it will for a CSV text file.

```
set NullInterpret ='';
```

will return NULL values for blank values in Excel.

### NullValue

If the **NullAsValue** statement is used, the defined symbol will substitute all NULL values in the **NullAsValue** specified fields with the specified string.

#### Syntax:

```
NullValue
```

### Example:

```
NullAsValue Field1, Field2;  
set NullValue='<NULL>';
```

### OtherSymbol

Defines a symbol to be treated as 'all other values' before a **LOAD/SELECT** statement. This is a user-defined variable.

### Syntax:

```
OtherSymbol
```

### Example:

```
set otherSymbol='+';  
LOAD * inline  
[X, Y  
a, a  
b, b];  
LOAD * inline  
[X, Z  
a, a  
+, c];
```

The field value Y='b' will now link to Z='c' through the other symbol.

## 4.8 Number interpretation variables

Number interpretation variables are system defined. The variables are included at the top of the load script and apply number formatting settings at the time of the script execution. They can be deleted, edited, or duplicated.

Number interpretation variables are automatically generated according to the current regional settings of the operating system when a new app is created. In Qlik Sense Desktop, this is according to the settings of the computer operating system. In Qlik Sense, it is according to the operating system of the server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Currency formatting

#### MoneyDecimalSep

The decimal separator defined replaces the decimal symbol for currency set by your regional settings.

```
MoneyDecimalSep
```

---

## 4 Working with variables in the data load editor

---

### **MoneyFormat**

The symbol defined replaces the currency symbol set by your regional settings.

```
MoneyFormat
```

### **MoneyThousandSep**

The thousands separator defined replaces the digit grouping symbol for currency set by your regional settings.

```
MoneyThousandSep
```

## Number formatting

### **DecimalSep**

The decimal separator defined replaces the decimal symbol set by your regional settings.

```
DecimalSep
```

### **ThousandSep**

The thousands separator defined replaces the digit grouping symbol of the operating system (regional settings).

```
ThousandSep
```

### **NumericalAbbreviation**

The numerical abbreviation sets which abbreviation to use for scale prefixes of numerals, for example M for mega or a million ( $10^6$ ), and  $\mu$  for micro ( $10^{-6}$ ).

```
NumericalAbbreviation
```

## Time formatting

### **DateFormat**

This environment variable defines the date format used as the default in the app. The format is used both to interpret and format dates. If the variable is not defined, the date format of the regional settings of the operating system will be fetched when the script runs.

```
DateFormat
```

### **TimeFormat**

The format defined replaces the time format of the operating system (regional settings).

```
TimeFormat
```

### **TimestampFormat**

The format defined replaces the date and time formats of the operating system (regional settings).

```
TimestampFormat
```

### **MonthNames**

The format defined replaces the month names convention of the regional settings.

## 4 Working with variables in the data load editor

---

### **MonthNames**

#### **LongMonthNames**

The format defined replaces the long month names convention in the regional settings.

### **LongMonthNames**

#### **DayNames**

The format defined replaces the weekday names convention set by your regional settings.

### **DayNames**

#### **LongDayNames**

The format defined replaces the long weekday names convention in the regional settings.

### **LongDayNames**

#### **FirstWeekDay**

Integer that defines which day to use as the first day of the week.

### **FirstWeekDay**

#### **BrokenWeeks**

This setting defines if weeks are broken or not.

### **BrokenWeeks**

#### **ReferenceDay**

The setting defines which day in January to set as reference day to define week 1.

### **ReferenceDay**

#### **FirstMonthOfYear**

The setting defines which month to use as first month of the year, which can be used to define financial years that use a monthly offset, for example starting April 1.



*This setting is currently unused but reserved for future use.*

Valid settings are 1 (January) to 12 (December). Default setting is 1.

#### **Syntax:**

### **FirstMonthOfYear**

#### **Example:**

```
set FirstMonthOfYear=4; //Sets the year to start in April
```

## BrokenWeeks

This setting defines if weeks are broken or not.

## 4 Working with variables in the data load editor

---

### Syntax:

#### BrokenWeeks

In Qlik Sense, the regional settings are fetched when the app is created, and the corresponding settings are stored in the script as environment variables.

A North American app developer often gets set `brokenweeks=1`; in the script, corresponding to broken weeks. A European app developer often gets set `brokenweeks=0`; in the script, corresponding to unbroken weeks.

Unbroken weeks means that:

- In some years, week 1 starts in December, and in other years, the last week of previous year continues into January.
- According to ISO 8601, week 1 always has at least 4 days in January. In Qlik Sense, this can be configured using the `referenceDay` variable.

Broken weeks means that:

- The last week of the year never continues into January.
- Week 1 starts on January 1 and is, in most cases, not a full week.

The following values can be used:

- 0 (=use unbroken weeks)
- 1 (= use broken weeks)

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Examples:

If you want ISO settings for weeks and week numbers, make sure to have the following in the script:

```
Set FirstWeekDay=0;
Set BrokenWeeks=0;    //(use unbroken weeks)
Set ReferenceDay=4;
```

If you want US settings, make sure to have the following in the script:

## 4 Working with variables in the data load editor

---

```
Set FirstWeekDay=6;
Set BrokenWeeks=1; // (use broken weeks)
Set ReferenceDay=1;
```

### DateFormat

This environment variable defines the date format used as the default in the app and by date returning functions like `date()` and `date#()`. The format is used to interpret and format dates. If the variable is not defined, the date format set by your regional settings is fetched when the script runs.

#### Syntax:

##### DateFormat

##### DateFormat Function examples

Example	Result
<pre>Set DateFormat='M/D/YY'; //(US format)</pre>	This use of the <code>DateFormat</code> function defines the date as the US format, month/day/year.
<pre>Set DateFormat='DD/MM/YY'; //(UK date format)</pre>	This use of the <code>DateFormat</code> function defines the date as the UK format, day/month/year.
<pre>Set DateFormat='YYYY/MM/DD'; //( ISO date format)</pre>	This use of the <code>DateFormat</code> function defines the date as the ISO format, year/month/day.

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Example 1 – System variables default

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

## 4 Working with variables in the data load editor

---

- A dataset of dates.
- The `DateFormat` function, which will use the US date format.

In this example, a dataset is loaded into a table named 'Transactions'. It includes a date field. The US `DateFormat` definition is used. This pattern will be used for implicit text to date conversion when the text dates are loaded.

### Load script

```
Set DateFormat='MM/DD/YYYY';
```

```
Transactions:
LOAD
date,
month(date) as month,
id,
amount
INLINE
[
date,id,amount
01/01/2022,1,1000
02/01/2022,2,2123
03/01/2022,3,4124
04/01/2022,4,2431
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- month

Create this measure:

```
=sum(amount)
```

Results table		
date	month	=sum(amount)
01/01/2022	Jan	1000
02/01/2022	Feb	2123
03/01/2022	Mar	4124
04/01/2022	Apr	2431

The `DateFormat` definition `MM/DD/YYYY` is used for implicit conversion of text to dates, which is why the date field is properly interpreted as a date. The same format is used to display the date, as shown in the results table.



### Example 2 – Change system variable

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same dataset from the previous example.
- The `DateFormat` function, which will use the 'DD/MM/YYYY' format.

#### Load script

```
SET DateFormat='DD/MM/YYYY';
Transactions:
LOAD
date,
month(date) as month,
id,
amount
INLINE
[
date,id,amount
01/01/2022,1,1000
02/01/2022,2,2123
03/01/2022,3,4124
04/01/2022,4,2431
];
```

#### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- month

Create this measure:

```
=sum(amount)
```

Results table		
date	month	=sum(amount)
01/01/2022	Jan	1000
02/01/2022	Jan	2123
03/01/2022	Jan	4124
04/01/2022	Jan	2431

---

## 4 Working with variables in the data load editor

---

Because the `dateFormat` definition was set to 'DD/MM/YYYY', you can see that the two digits after the first "/" symbol have been interpreted as the month, resulting in all records being from the month of January.

### Example 3 – Date interpretation

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset with dates in numerical format.
- The `dateFormat` variable, which will use the 'DD/MM/YYYY' format.
- The `date()` variable.

#### Load script

```
SET dateFormat='MM/DD/YYYY';
```

Transactions:

```
Load
date(numerical_date),
month(date(numerical_date)) as month,
id,
amount
Inline
[
numerical_date,id,amount
43254,1,1000
43255,2,2123
43256,3,4124
43258,4,2431
];
```

#### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- month

Create this measure:

```
=sum(amount)
```

## 4 Working with variables in the data load editor

---

Results table		
<b>date</b>	<b>month</b>	<b>=sum(amount)</b>
06/03/2022	Jun	1000
06/04/2022	Jun	2123
06/05/2022	Jun	4124
06/07/2022	Jun	2431

In the load script, you use the `date()` function to convert the numerical date into a date format. Because you do not provide a specified format as a second argument in the function, the `DateFormat` is used. This results in the date field using the format 'MM/DD/YYYY'.

### Example 4 – Foreign date formatting

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset of dates.
- The `DateFormat` variable, which uses the 'DD/MM/YYYY' format but is uncommented by forward slashes.

#### Load script

```
// SET DateFormat='DD/MM/YYYY';
```

Transactions:

```
Load
date,
month(date) as month,
id,
amount
inline
[
date,id,amount
22-05-2022,1,1000
23-05-2022,2,2123
24-05-2022,3,4124
25-05-2022,4,2431
];
```

#### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

## 4 Working with variables in the data load editor

- date
- month

Create this measure:

```
=sum(amount)
```

Results table

date	month	=sum(amount)
22-05-2022	-	1000
23-05-2022	-	2123
24-05-2022	-	4124
25-05-2022	-	2431

In the initial load script, the `dateFormat` being used is the default 'MM/DD/YYYY'. Because the `date` field in the `transactions` dataset is not in this format, the field is not interpreted as a date. This is shown in the results table where the `month` field values are null.

You can verify the interpreted data types in the Data model viewer by inspecting the `date` field's "Tags" properties.

*Preview of the Transactions table. Note the "Tags" for the date field indicating that the textual input data has not been implicitly converted to a date/timestamp.*

date	Transactions				
Density	100%	date	month	id	amount
Subset ratio	100%	22-05-2022	-	1	1000
Has duplicates	false	23-05-2022	-	2	2123
Total distinct values	4	24-05-2022	-	3	4124
Present distinct values	4	25-05-2022	-	4	2431
Non-null values	4				
Tags	Sascii Stext				

This can be solved by enabling the `dateFormat` system variable:

```
// SET dateFormat='DD/MM/YYYY';
```

Remove the double forward slashes and reload the data.

## 4 Working with variables in the data load editor

Preview of the `Transactions` table. Note the "Tags" for the date field indicating that the textual input data has been implicitly converted to a date/timestamp.

date		Transactions			
Density	100%	date	month	id	amount
Subset ratio	100%	22-05-2022	May	1	1000
Has duplicates	false	23-05-2022	May	2	2123
Total distinct values	4	24-05-2022	May	3	4124
Present distinct values	4	25-05-2022	May	4	2431
Non-null values	4				
Tags	Snumeric Sinteger Stimestamp Sdate				

### DayNames

The format defined replaces the weekday names convention set by your regional settings.

#### Syntax:

##### DayNames

When modifying the variable, a semicolon ; is required to separate the individual values.

#### DayName Function examples

##### Function example

```
Set  
DayNames='Mon;Tue;Wed;Thu;Fri;Sat;Sun';  
  
Set DayNames='M;Tu;W;Th;F;Sa;Su';
```

##### Result definition

This use of the DayNames function defines day names in their abbreviated form.

This use of the DayNames function defines day names by their first letters.

The DayNames function is often used in combination with the following functions:

#### Related functions

##### Function

*weekday* (page 1074)

*Date* (page 1233)

*LongDayNames* (page 232)

##### Interaction

Script function to return DayNames as field values .

Script function to return DayNames as field values.

Long form values of DayNames.

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default

---

## 4 Working with variables in the data load editor

---

date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Example 1 - System variables default

Load script and results

#### Overview

In this example, the dates in the dataset are set in the MM/DD/YYYY format.

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset with dates, which will be loaded into a table named, `Transactions`.
- A date field.
- The default `DayNames` definition.

#### Load script

```
SET DayNames='Mon;Tue;Wed;Thu;Fri;Sat;Sun';
```

```
Transactions:
LOAD
date,
weekDay(date) as dayname,
id,
amount
INLINE
[
date,id,amount
01/01/2022,1,1000
02/01/2022,2,2123
03/01/2022,3,4124
04/01/2022,4,2431
];
```

#### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- `date`
- `dayname`

## 4 Working with variables in the data load editor

---

Create this measure:

```
sum(amount)
```

Results table		
date	dayname	sum(amount)
01/01/2022	Sat	1000
02/01/2022	Tue	2123
03/01/2022	Tue	4124
04/01/2022	Fri	2431

In the load script, the `weekDay` function is used with the `date` field as the provided argument. In the results table, the output of this `weekDay` function displays the days of the week in the format of the `DayNames` definition.

### Example 2 - Change system variable

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab. The same dataset and scenario from the first example are used.

However, at the start of the script, the `DayNames` definition is modified to use the abbreviated days of the week in Afrikaans.

#### Load script

```
SET DayNames='Ma;Di;Wo;Do;Vr;Sa;So';
```

```
Transactions:
```

```
Load
date,
weekDay(date) as dayname,
id,
amount
InLine
[
date,id,amount
01/01/2022,1,1000
02/01/2022,2,2123
03/01/2022,3,4124
04/01/2022,4,2431
];
```

#### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

## 4 Working with variables in the data load editor

---

- date
- dayname

Create this measure:

```
sum(amount)
```

Results table		
date	dayname	sum(amount)
01/01/2022	Sa	1000
02/01/2022	Di	2123
03/01/2022	Di	4124
04/01/2022	Vr	2431

In the results table, the output of this weekday function displays the days of the week in the format of the `DayNames` definition.

It is important to remember that if the language for the `DayNames` is modified like it has been in this example, the `LongDayNames` would still contain the days of the week in English. This would need to be modified as well if both variables are used in the application.

### Example 3 – Date function

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset with dates, which will be loaded into a table named, `Transactions`.
- A date field.
- The default `DayNames` definition.

#### Load script

```
SET DayNames='Mon;Tue;Wed;Thu;Fri;Sat;Sun';
```

```
Transactions:
```

```
Load
```

```
date,
```

```
Date(date,'www') as dayname,
```

```
id,
```

```
amount
```

```
Inline
```

```
[
```

```
date,id,amount
```

```
01/01/2022,1,1000
```



---

## 4 Working with variables in the data load editor

---

```
02/01/2022,2,2123
03/01/2022,3,4124
04/01/2022,4,2431
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- dayname

Create this measure:

```
sum(amount)
```

Results table		
date	dayname	sum(amount)
01/01/2022	Sat	1000
02/01/2022	Tue	2123
03/01/2022	Tue	4124
04/01/2022	Fri	2431

The default `dayNames` definition is used. In the load script, the `date` function is used with the `date` field as the first argument. The second argument is `www`. This formatting converts the result into the values stored in the `dayNames` definition. This is displayed in the output of the results table.

### DecimalSep

The decimal separator defined replaces the decimal symbol set by your regional settings.

Qlik Sense automatically interprets text as numbers whenever a recognizable number pattern is encountered. The `thousandSep` and `decimalSep` system variables determine the makeup of the patterns applied when parsing text as numbers. The `thousandSep` and `decimalSep` variables set the default number format pattern when visualizing numeric content in front-end charts and tables. That is, it directly impacts the **Number formatting** options for any front end expression.

Assuming a thousand separator of comma ',' and a decimal separator of '.', these are examples of patterns that would be implicitly converted to numeric equivalent values:

```
0,000.00
```

```
0000.00
```

```
0,000
```

These are examples of patterns that would remain unchanged as text; that is, not converted to numeric:

```
0.000,00
```

0,00

### Syntax:

#### DecimalSep

Function examples

Example	Result
<code>set DecimalSep='.';</code>	Sets '.' as the decimal separator.
<code>set DecimalSep=',';</code>	Sets ',' as the decimal separator.

## Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

## Example – Effect of setting number separator variables on different input data

Load script and results

### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset of sums and dates with the sums set in different format patterns.
- A table named `Transactions`.
- The `DecimalSep` variable which is set to '.'.
- The `ThousandSep` variable which is set to ','.
- The `delimiter` variable that is set as the '|' character to separate the different fields in a line.

### Load script

```
set ThousandSep=',';
set DecimalSep='.';
```

`Transactions:`

## 4 Working with variables in the data load editor

---

```
Load date,
id,
amount as amount
Inline
[
date|id|amount
01/01/2022|1|1.000-45
01/02/2022|2|23.344
01/03/2022|3|4124,35
01/04/2022|4|2431.36
01/05/2022|5|4,787
01/06/2022|6|2431.84
01/07/2022|7|4132.5246
01/08/2022|8|3554.284
01/09/2022|9|3.756,178
01/10/2022|10|3,454.356
] (delimiter is '|');
```

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension amount.

Create this measure:

```
=sum(amount)
```

Amount	Results table	
	=Sum(amount)	
Totals		20814.7086
1.000-45		
3.756,178		
4124,35		
	23.344	23.344
	2431.36	2431.36
	2431.84	2431.84
	3,454.356	3454.356
	3554.284	3554.284
	4132.5246	4132.5246
	4,787	4787

Any value not interpreted as number remains as text and is aligned to the left by default. Any successfully converted values are aligned to the right, retaining the original input format.

The expression column shows the numeric equivalent, which is by default formatted with only a decimal separator '.'. This can be overridden with the **Number formatting** drop down setting in the expression configuration.

### FirstWeekDay

Integer that defines which day to use as the first day of the week.

#### Syntax:

##### **FirstWeekDay**

Monday is the first day of the week according to ISO 8601, the international standard for the representation of dates and times. Monday is also used as the first day of the week in a number of countries, for example on the UK, France, Germany and Sweden.

But in other countries, like in the United States and Canada, Sunday is considered to be the start of the week.

In Qlik Sense, the regional settings are fetched when the app is created, and the corresponding settings are stored in the script as environment variables.

A North American app developer often gets `set FirstWeekDay=6;` in the script, corresponding to Sunday. A European app developer often gets `set FirstWeekDay=0;` in the script, corresponding to Monday.

Values that can be set for  
FirstWeekDay

Value	Day
0	Monday
1	Tuesday
2	Wednesday
3	Thursday
4	Friday
5	Saturday
6	Sunday

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

## 4 Working with variables in the data load editor

---

### Examples:

If you want ISO settings for weeks and week numbers, make sure to have the following in the script:

```
Set FirstWeekDay=0; // Monday as first week day
Set BrokenWeeks=0;
Set ReferenceDay=4;
```

If you want US settings, make sure to have the following in the script:

```
Set FirstWeekDay=6; // Sunday as first week day
Set BrokenWeeks=1;
Set ReferenceDay=1;
```

### Example 1 – Using default value (script)

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

In this example, the load script uses the default Qlik Sense system variable value, `FirstWeekDay=6`. This data contains data for the first 14 days in 2020.

#### Load script

```
// Example 1: Load Script using the default value of FirstWeekDay=6, i.e. Sunday
```

```
SET FirstWeekDay = 6;
```

```
Sales:
```

```
LOAD
    date,
    sales,
    week(date) as week,
    weekday(date) as weekday
```

```
Inline [
date,sales
01/01/2021,6000
01/02/2021,3000
01/03/2021,6000
01/04/2021,8000
01/05/2021,5000
01/06/2020,7000
01/07/2020,3000
01/08/2020,5000
01/09/2020,9000
01/10/2020,5000
01/11/2020,7000
01/12/2020,7000
01/13/2020,7000
01/14/2020,7000
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- week
- weekday

Results table

Date	week	weekday
01/01/2021	1	Wed
01/02/2021	1	Thu
01/03/2021	1	Fri
01/04/2021	1	Sat
01/05/2021	2	Sun
01/06/2020	2	Mon
01/07/2020	2	Tue
01/08/2020	2	Wed
01/09/2020	2	Thu
01/10/2020	2	Fri
01/11/2020	2	Sat
01/12/2020	3	Sun
01/13/2020	3	Mon
01/14/2020	3	Tue

Because the default settings are being used, the `FirstWeekDay` system variable is set to 6. In the results table, each new week can be seen beginning on Sunday (the 5th and 12th of January).

### Example 2 – Changing the FirstWeekDay variable (script)

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

In this example, the data contains the first 14 days in 2020. At the start of the script, we set the `FirstWeekDay` variable to 3.

## 4 Working with variables in the data load editor

---

### Load script

// Example 2: Load Script setting the value of FirstWeekDay=3, i.e. Thursday

```
SET FirstWeekDay = 3;
```

```
Sales:
```

```
LOAD
```

```
    date,  
    sales,  
    week(date) as week,  
    weekday(date) as weekday
```

```
Inline [
```

```
date,sales
```

```
01/01/2021,6000
```

```
01/02/2021,3000
```

```
01/03/2021,6000
```

```
01/04/2021,8000
```

```
01/05/2021,5000
```

```
01/06/2020,7000
```

```
01/07/2020,3000
```

```
01/08/2020,5000
```

```
01/09/2020,9000
```

```
01/10/2020,5000
```

```
01/11/2020,7000
```

```
01/12/2020,7000
```

```
01/13/2020,7000
```

```
01/14/2020,7000
```

```
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- week
- weekday

Results table

Date	week	weekday
01/01/2021	52	Wed
01/02/2021	1	Thu
01/03/2021	1	Fri
01/04/2021	1	Sat
01/05/2021	1	Sun
01/06/2020	1	Mon

## 4 Working with variables in the data load editor

---

Date	week	weekday
01/07/2020	1	Tue
01/08/2020	1	Wed
01/09/2020	2	Thu
01/10/2020	2	Fri
01/11/2020	2	Sat
01/12/2020	2	Sun
01/13/2020	2	Mon
01/14/2020	2	Tue

Because the `FirstWeekDay` system variable is set to 3, the first day of each week will be a Thursday. In the results table, each new week can be seen beginning on Thursday (the 2nd and 9th of January).

### LongDayNames

The format defined replaces the long weekday names convention in the regional settings.

#### Syntax:

##### LongDayNames

The following example of the `LongDayNames` function defines day names in full:

```
set LongDayNames='Monday;Tuesday;Wednesday;Thursday;Friday;Saturday;Sunday';
```

When modifying the variable, a semicolon ; is required to separate the individual values.

The `LongDayNames` function can be used in combination with the `Date (page 1233)` function which returns `DayNames` as field values.

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Example 1 - System variable default

Load script and results



## 4 Working with variables in the data load editor

---

### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset with dates, which will be loaded into a table named, `Transactions`.
- A date field.
- The default `LongDayNames` definition.

### Load script

```
SET LongDayNames='Monday;Tuesday;Wednesday;Thursday;Friday;Saturday;Sunday';
```

```
Transactions:
LOAD
date,
Date(date,'www') as dayname,
id,
amount
INLINE
[
date,id,amount
01/01/2022,1,1000
02/01/2022,2,2123
03/01/2022,3,4124
04/01/2022,4,2431
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- `date`
- `dayname`

Create this measure:

```
=sum(amount)
```

Results table		
<b>date</b>	<b>dayname</b>	<b>=sum(amount)</b>
01/01/2022	Saturday	1000
02/01/2022	Tuesday	2123
03/01/2022	Tuesday	4124
04/01/2022	Friday	2431

In the load script, to create a field called, `dayname`, the `date` function is used with the `date` field as the first argument. The second argument in the function is the formatting `www`.

## 4 Working with variables in the data load editor

---

Using this formatting converts the values from the first argument into the corresponding full day name that is set in the variable `LongDayNames`. In the results table, the field values of our created field `dayname` display this.

### Example 2 – Change system variable

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The same dataset and scenario from the first example are used. However, at the start of the script, the `LongDayNames` definition is modified to use the days of the week in Spanish.

#### Load Script

```
SET LongDayNames='Lunes;Martes;Miércoles;Jueves;Viernes;Sábado;Domingo';
```

Transactions:

```
LOAD
date,
Date(date,'www') as dayname,
id,
amount
INLINE
[
date,id,amount
01/01/2022,1,1000
02/01/2022,2,2123
03/01/2022,3,4124
04/01/2022,4,2431
];
```

#### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- dayname

Create this measure:

```
=sum(amount)
```

Results table		
date	dayname	=sum(amount)
01/01/2022	Sábado	1000
02/01/2022	Martes	2123

## 4 Working with variables in the data load editor

---

<b>date</b>	<b>dayname</b>	<b>=sum(amount)</b>
03/01/2022	Martes	4124
04/01/2022	Viernes	2431

In the load script, the `LongDayNames` variable is modified to list the days of the week in Spanish.

Then, you create a field called, `dayname`, which is the `date` function used with the `date` field as the first argument.

The second argument in the function is the formatting `www`. By using this formatting Qlik Sense converts the values from the first argument into the corresponding full day name set in the variable `LongDayNames`.

In the results table, the field values of our created field `dayname` displays the days of the week written in Spanish and in full.

### LongMonthNames

The format defined replaces the long month names convention in the regional settings.

#### Syntax:

##### **LongMonthNames**

When modifying the variable, the `;` needs to be used to separate the individual values.

The following example of the `LongMonthNames` function defines month names in full:

Set

```
LongMonthNames='January;February;March;April;May;June;July;August;September;October;November;December';
```

The `LongMonthNames` function is often used in combination with the following functions:

<b>Function</b>	<b>Related functions</b>
<i>Date (page 1233)</i>	<b>Interaction</b> Script function to return <code>DayNames</code> as field values.
<i>LongDayNames (page 232)</i>	Long form values of <code>DayNames</code> .

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: `MM/DD/YYYY`. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the

---

## 4 Working with variables in the data load editor

---

Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Example 1 - System variables default

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset of dates that is loaded into a table named `Transactions`.
- A date field.
- The default `LongMonthNames` definition.

#### Load script

```
SET  
LongMonthNames='January;February;March;April;May;June;July;August;September;October;November;December';
```

Transactions:

```
Load  
date,  
Date(date,'MMMM') as monthname,  
id,  
amount  
Inline  
[  
date,id,amount  
01/01/2022,1,1000.45  
01/02/2022,2,2123.34  
01/03/2022,3,4124.35  
01/04/2022,4,2431.36  
01/05/2022,5,4787.78  
01/06/2022,6,2431.84  
01/07/2022,7,2854.83  
01/08/2022,8,3554.28  
01/09/2022,9,3756.17  
01/10/2022,10,3454.35  
];
```

#### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions.

- date
- monthname

Create this measure

## 4 Working with variables in the data load editor

---

```
=sum(amount)
```

Results table		
date	monthname	sum(amount)
01/01/2022	January	1000.45
01/02/2022	January	2123.34
01/03/2022	January	4124.35
01/04/2022	January	2431.36
01/05/2022	January	4787.78
01/06/2022	January	2431.84
01/07/2022	January	2854.83
01/08/2022	January	3554.28
01/09/2022	January	3756.17
01/10/2022	January	3454.35

The default `LongMonthNames` definition is used. In the load script, to create a field called, `month`, the `date` function is used with the `date` field as the first argument. The second argument in the function is the formatting `MMMM`.

Using this formatting Qlik Sense converts the values from the first argument into the corresponding full month name set in the variable `LongMonthNames`. In the results table, the field values of our created field `month` display this.

### Example 2 - Change system variable

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset of dates that is loaded into a table named `Transactions`.
- A date field.
- The `LongMonthNames` variable that is modified to use the abbreviated days of the week in Spanish.

#### Load script

```
SET  
LongMonthNames='Enero;Febrero;Marzo;Abril;Mayo;Junio;Julio;Agosto;Septiembre;OctubreNoviembre;  
Diciembre';
```

```
Transactions:  
LOAD
```

## 4 Working with variables in the data load editor

---

```
date,
Date(date, 'MMMM') as monthname,
id,
amount
INLINE
[
date, id, amount
01/01/2022, 1, 1000
02/01/2022, 2, 2123
03/01/2022, 3, 4124
04/01/2022, 4, 2431
];
```

### Results

Load the data and open a sheet. Create a new table and add `sum(amount)` as a measure and these fields as dimensions:

- date
- monthname

Create this measure:

```
=sum(amount)
```

Results table		
date	monthname	sum(amount)
01/01/2022	Enero	1000.45
01/02/2022	Enero	2123.34
01/03/2022	Enero	4124.35
01/04/2022	Enero	2431.36
01/05/2022	Enero	4787.78
01/06/2022	Enero	2431.84
01/07/2022	Enero	2854.83
01/08/2022	Enero	3554.28
01/09/2022	Enero	3756.17
01/10/2022	Enero	3454.35

In the load script, the `LongMonthNames` variable is modified to list the months of the year in Spanish. Then, to create a field called, `monthname`, the `Date` function is used with the `date` field as the first argument. The second argument in the function is the formatting `MMMM`.

Using this formatting Qlik Sense converts the values from the first argument into the corresponding full month name set in the variable `LongMonthNames`. In the results table, the field values of our created field `monthname` display the month name written in Spanish.

### MoneyDecimalSep

The decimal separator defined replaces the decimal symbol for currency set by your regional settings.



*By default, Qlik Sense displays numbers and text differently in table charts. Numbers are right-aligned, and text is left-aligned. This makes it easy to find text-to-number conversion issues. Any tables on this page that show Qlik Sense results will use this formatting.*

#### Syntax:

##### **MoneyDecimalSep**

Qlik Sense applications will interpret text fields that conform to this formatting as monetary values. The text field must contain the currency symbol that is defined in the `MoneyFormat` system variable. `MoneyDecimalSep` is particularly helpful when handling data sources received from multiple different regional settings.

The following example shows a possible use of the `MoneyDecimalSep` system variable:

```
Set MoneyDecimalSep='.';
```

This function is often used together with the following functions:

#### Related functions

Function	Interaction
<code>MoneyFormat</code>	In instances of text field interpretation, the <code>MoneyFormat</code> symbol will be used as part of the interpretation. For Number Formatting, the <code>MoneyFormat</code> formatting will be used by Qlik Sense in Chart Objects.
<code>MoneyThousandSep</code>	In instances of text field interpretation, the <code>MoneyThousandSep</code> function must also be adhered to.

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Example 1 - MoneyDecimalSep dot (.) notation

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset that is loaded into a table named `transactions`.
- Provided data that has its monetary field in text format with a dot '.' used as the decimal separator. Each record is also prefixed by a '\$' symbol, except for the last record, which is prefixed by a '£' symbol.

Keep in mind that the `MoneyFormat` system variable defines dollar '\$' as the default currency.

#### Load script

```
SET MoneyThousandSep=',';
SET MoneyDecimalSep='.';
SET MoneyFormat='$###0.00;-###0.00';
```

Transactions:

```
Load
date,
id,
amount
Inline
[
date,id,amount
01/01/2022,1,'$14.41'
01/02/2022,2,'$2,814.32'
01/03/2022,3,'$249.36'
01/04/2022,4,'$24.37'
01/05/2022,5,'$7.54'
01/06/2022,6,'$243.63'
01/07/2022,7,'$545.36'
01/08/2022,8,'$3.55'
01/09/2022,9,'$3.436'
01/10/2022,10,'£345.66'
];
```

#### Results

Load the data and open a sheet. Create a new table and add this field as a dimension:`amount`.

Add the following measures:

- `isNum(amount)`
- `sum(amount)`



## 4 Working with variables in the data load editor

---

Review the results below, demonstrating the correct interpretation of all dollar '\$' values only.

Results table

amount	=isNum(amount)	=Sum(amount)
Totals	0	\$3905.98
£345.66	0	\$0.00
\$3.436	-1	\$3.44
\$3.55	-1	\$3.55
\$7.54	-1	\$7.54
\$14.41	-1	\$14.41
\$24.37	-1	\$24.37
243.63	-1	\$243.63
\$249.36	-1	\$249.36
\$545.36	-1	\$545.36
\$2,814.32	-1	\$2814.32

The results table above shows how the amount field has been interpreted correctly for all dollar (\$) prefixed values, whilst the pound (£) prefixed amount has not been converted to a monetary value.

### Example 2 - MoneyDecimalSep comma (,) notation

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset which is loaded into a table named Transactions.
- Provided data that has its monetary field in text format with a comma ',' used as the decimal separator. Each record is also prefixed by a '\$' symbol, except for the last record, which erroneously uses the dot decimal separator '.'.

Keep in mind that the MoneyFormat system variable defines dollar '\$' as the default currency.

#### Load script

```
SET MoneyThousandSep='.';
SET MoneyDecimalSep=',';
SET MoneyFormat='$###0.00;-###0.00';
```

Transactions:

Load

## 4 Working with variables in the data load editor

---

```
date,
id,
amount
Inline
[
date,id,amount
01/01/2022,1,'$14,41'
01/02/2022,2,'$2.814,32'
01/03/2022,3,'$249,36'
01/04/2022,4,'$24,37'
01/05/2022,5,'$7,54'
01/06/2022,6,'$243,63'
01/07/2022,7,'$545,36'
01/08/2022,8,'$3,55'
01/09/2022,9,'$3,436'
01/10/2022,10,'$345.66'
];
```

### Results

Paragraph text for Results.

Load the data and open a sheet. Create a new table and add this field as a dimension:amount.

Add the following measures:

- isNum(amount)
- sum(amount)

Review the results below, demonstrating the correct interpretation of all values, except for the amount in which the decimal separator uses dot '.' notation. In that case, a comma should have been used instead.

Results table

amount	=isNum(amount)	=Sum(amount)
Totals	0	\$3905.98
\$345.66	0	\$0.00
\$3,436	-1	\$3.44
\$3,55	-1	\$3.55
\$7,54	-1	\$7.54
\$14,41	-1	\$14.41
\$24,37	-1	\$24.37
\$243,63	-1	\$243.63
\$249,36	-1	\$249.36
\$545,36	-1	\$545.36
\$2.814,32	-1	\$2814.32

### MoneyFormat

This system variable defines the format pattern used by Qlik for automatic translation of text to number where the number is prefixed by a monetary symbol. It also defines how measures whose Number Formatting properties are set to 'Money' will be displayed in chart objects.

The symbol defined as part of the format pattern in the `MoneyFormat` system variable replaces the currency symbol set by your regional settings.



*By default, Qlik Sense displays numbers and text differently in table charts. Numbers are right-aligned, and text is left-aligned. This makes it easy to find text-to-number conversion issues. Any tables on this page that show Qlik Sense results will use this formatting.*

#### Syntax:

##### **MoneyFormat**

```
Set MoneyFormat='$ #,##0.00; ($ #,##0.00)';
```

This formatting will be displayed in chart objects when a numerical field's `Number Formatting` property is set to `money`. Further, when numerical text fields are interpreted by Qlik Sense, if the currency symbol of the text field matches that of the symbol defined in the `MoneyFormat` variable, Qlik Sense will interpret this field as a monetary value.

This function is often used together with the following functions:

#### Related functions

Function	Interaction
<i>MoneyDecimalSep (page 239)</i>	For Number Formatting, <code>moneyDecimalSep</code> will be used in field formatting of objects.
<i>MoneyThousandSep (page 247)</i>	For Number Formatting, <code>moneyThousandSep</code> will be used in field formatting of objects.

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

## 4 Working with variables in the data load editor

---

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Example 1 - MoneyFormat

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains a dataset which is loaded into a table named `transactions`. The default `MoneyFormat` variable definition is used.

#### Load script

```
SET MoneyThousandSep=',';
SET MoneyDecimalSep='.';
SET MoneyFormat='$###0.00;-$$$0.00';
```

Transactions:

```
Load
date,
id,
amount
Inline
[
date,id,amount
01/01/2022,1,$10000000441
01/02/2022,2,$21237492432
01/03/2022,3,$249475336
01/04/2022,4,$24313369837
01/05/2022,5,$7873578754
01/06/2022,6,$24313884663
01/07/2022,7,$545883436
01/08/2022,8,$35545828255
01/09/2022,9,$37565817436
01/10/2022,10,$3454343566
];
```

#### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- amount

Add this measure:

```
=Sum(amount)
```

## 4 Working with variables in the data load editor

---

Under **Number formatting**, select **Money** to configure `sum(amount)` as a monetary value.

Results table

date	Amount	=Sum(amount)
Totals		\$165099674156.00
01/01/2022	\$10000000441	\$10000000441.00
01/02/2022	\$21237492432	\$21237492432.00
01/03/2022	\$249475336	\$249475336.00
01/04/2022	\$24313369837	\$24313369837.00
01/05/2022	\$7873578754	\$7873578754.00
01/06/2022	\$24313884663	\$24313884663.00
01/07/2022	\$545883436	\$545883436.00
01/08/2022	\$35545828255	\$35545828255.00
01/09/2022	\$37565817436	\$37565817436.00
01/10/2022	\$3454343566	\$3454343566.00

The default `MoneyFormat` definition is used. This looks as follows: `###0.00;-###0.00`. In the results table, the format of the `amount` field displays the currency symbol and the decimal point and decimal places have been included.

### Example 2 - MoneyFormat with thousands separator and mixed input formats

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A mixed-input format dataset, which is loaded into a table named `Transactions` with thousands separators and decimal separators interspersed.
- A modification of the `MoneyFormat` definition is modified to include a comma as the thousands separator.
- One of the rows of data erroneously delimited with thousands separator commas in the wrong places. Note how this amount is left as text and not interpretable as a number.

#### Load script

```
SET MoneyThousandSep=',';  
SET MoneyDecimalSep='.';  
SET MoneyFormat = '$#,##0.00;-#,##0.00';
```

## 4 Working with variables in the data load editor

---

Transactions:

```
Load
date,
id,
amount
Inline
[
date, id, amount
01/01/2022, 1, '$10,000,000,441.45'
01/02/2022, 2, '$212,3749,24,32.23'
01/03/2022, 3, $249475336.45
01/04/2022, 4, $24,313,369,837
01/05/2022, 5, $7873578754
01/06/2022, 6, $24313884663
01/07/2022, 7, $545883436
01/08/2022, 8, $35545828255
01/09/2022, 9, $37565817436
01/10/2022, 10, $3454343566
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- amount

Add this measure:

```
=Sum(amount)
```

Under **Number formatting**, select **Money** to configure sum(amount) as a monetary value.

Results table

date	Amount	=Sum(amount)
Totals		\$119,548,811,911.90
01/01/2022	\$10,000,000,441.45	\$10,000,000,441.45
01/02/2022	\$212,3749,24,32.23	\$0.00
01/03/2022	\$249475336.45	\$249,475,336.45
01/04/2022	\$24	\$24.00
01/05/2022	\$7873578754	\$7,873,578,754.00
01/06/2022	\$24313884663	\$24,313,884,663.00
01/07/2022	\$545883436	\$545,883,436.00
01/08/2022	\$35545828255	\$35,545,828,255.00

## 4 Working with variables in the data load editor

date	Amount	=Sum(amount)
01/09/2022	\$37565817436	\$37,565,817,436.00
01/10/2022	\$3454343566	\$3,454,343,566.00

At the start of the script, the `MoneyFormat` system variable is modified to include a comma as a thousands separator. In the Qlik Sense table, the formatting can be seen to include this separator. Furthermore, the row with the erroneous separator has not been interpreted correctly and remains as text. This is why it does not contribute towards the summation of the amount.

### MoneyThousandSep

The thousands separator defined replaces the digit grouping symbol for currency set by your regional settings.



*By default, Qlik Sense displays numbers and text differently in table charts. Numbers are right-aligned, and text is left-aligned. This makes it easy to find text-to-number conversion issues. Any tables on this page that show Qlik Sense results will use this formatting.*

#### Syntax:

##### MoneyThousandSep

Qlik Sense applications will interpret text fields that conform to this formatting as monetary values. The text field must contain the currency symbol that is defined in the `MoneyFormat` system variable. `MoneyThousandSep` is particularly helpful when handling data sources received from multiple different regional settings.

The following example shows a possible use of the `MoneyThousandSep` system variable:

```
set MoneyDecimalSep=',';
```

This function is often used together with the following functions:

#### Related functions

Function	Interaction
<code>MoneyFormat</code>	In instances of text field interpretation, the <code>MoneyFormat</code> symbol will be used as part of the interpretation. For Number Formatting, the <code>MoneyFormat</code> formatting will be used by Qlik Sense in chart objects.
<code>MoneyDecimalSep</code>	In instances of text field interpretation, the <code>MoneyDecimalSep</code> function must also be adhered to.

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors.

---

## 4 Working with variables in the data load editor

---

You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Example 1 - MoneyThousandSep comma (,) notation

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset which is loaded into a table named `Transactions`.
- Provided data that has its monetary field in text format with a comma used as the thousands separator. Each record is also prefixed by a '\$' symbol.

Keep in mind that the `MoneyFormat` system variable defines dollar '\$' as the default currency.

#### Load script

```
SET MoneyThousandSep=',';
SET MoneyDecimalSep='.';
SET MoneyFormat='$###0.00;-###0.00';
```

`Transactions:`

```
Load
date,
id,
amount
Inline
[
date,id,amount
01/01/2022,1,'$10,000,000,441'
01/02/2022,2,'$21,237,492,432'
01/03/2022,3,'$249,475,336'
01/04/2022,4,'$24,313,369,837'
01/05/2022,5,'$7,873,578,754'
01/06/2022,6,'$24,313,884,663'
01/07/2022,7,'$545,883,436'
01/08/2022,8,'$35,545,828,255'
01/09/2022,9,'$37,565,817,436'
01/10/2022,10,'$3.454.343.566'
];
```



## 4 Working with variables in the data load editor

---

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension:amount.

Add the following measures:

- `isNum(amount)`
- `sum(amount)`

Review the results below. The table demonstrates the correct interpretation of all values using comma ',' notation as the thousands separator.

The amount field has been interpreted correctly for all values, with the exception of one value which used a dot '.' as the thousands separator.

Results table

amount	=isNum(amount)	=Sum(amount)
Totals	0	\$161645330590.00
\$3.454.343.566	0	\$0.00
\$249,475,336	-1	\$249475336.00
\$545,883,436	-1	\$545883436.00
\$7,873,578,754	-1	\$7873578754.00
\$10,000,000,441	-1	\$10000000441.00
\$21,237,492,432	-1	\$21237492432.00
\$24,313,369,837	-1	\$24313369837.00
\$24,33,884,663	-1	\$24313884663.00
\$35,545,828,255	-1	\$35545828255.00
\$37,565,817,436	-1	\$37565817436.00

### Example 2 - MoneyThousandSep dot (.) notation

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset which is loaded into a table named `Transactions`.
- Provided data that has its monetary field in text format with a dot '.' used as the thousands separator. Each record is also prefixed by a '\$' symbol.

## 4 Working with variables in the data load editor

---

Keep in mind that the `MoneyFormat` system variable defines dollar '\$' as the default currency.

### Load script

```
SET MoneyThousandSep='.';
SET MoneyDecimalSep='';
SET MoneyFormat='$###0.00;-$###0.00';
```

Transactions:

```
Load
date,
id,
amount
Inline
[
date,id,amount
01/01/2022,1,'$10.000.000.441'
01/02/2022,2,'$21.237.492.432'
01/03/2022,3,'$249.475.336'
01/04/2022,4,'$24.313.369.837'
01/05/2022,5,'$7.873.578.754'
01/06/2022,6,'$24.313.884.663'
01/07/2022,7,'$545.883.436'
01/08/2022,8,'$35.545.828.255'
01/09/2022,9,'$37.565.817.436'
01/10/2022,10,'$3,454,343,566'
];
```

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension: `amount`.

Add the following measures:

- `isNum(amount)`
- `sum(amount)`

Review the results below, demonstrating the correct interpretation of all values using dot '.' notation as the thousand separator.

The `amount` field has been interpreted correctly for all values, with the exception of one value which used a comma ',' as the thousands separator.

Results table

<b>amount</b>	<b>=isNum(amount)</b>	<b>=Sum(amount)</b>
Totals	0	\$161645330590.00
\$3,545,343,566	0	\$0.00
\$249.475.336	-1	\$249475336.00

## 4 Working with variables in the data load editor

---

amount	=isNum(amount)	=Sum(amount)
\$545.883.436	-1	545883436.00
\$7.873.578.754	-1	\$7873578754.00
\$10.000.000.441	-1	\$10000000441.00
\$21.237.492.432	-1	\$21237492432.00
\$24.313.884.663	-1	\$24313884663.00
\$24.313.884.663	-1	\$24313884663.00
\$35.545.828.255	-1	\$35545828255.00
\$37.565.817.436	-1	\$37565817436.00

### MonthNames

The format defined replaces the month names convention of the regional settings.

#### Syntax:

##### MonthNames

When modifying the variable, the ; needs to be used to separate the individual values.

#### Function examples

##### Example

```
Set MonthNames='Jan;Feb;Mar;Apr;May;Jun;Jul;Aug;Sep;Oct;Nov;Dec';
```

```
Set
```

```
MonthNames='Enero;Feb;Marzo;Abr;Mayo;Jun;Jul;Agosto;Set;Oct;Nov;Dic';
```

##### Results

This use of the MonthNames function defines month names in English and their abbreviated form.

This use of the MonthNames function defines month names in Spanish and their abbreviated form.

The MonthNames function can be used in combination with the following functions:

#### Related functions

##### Function

*month* (page 917)

*Date* (page 1233)

*LongMonthNames*  
(page 235)

##### Interaction

Script function to return values defined in MonthNames as field values

Script function to return values defined in MonthNames as field values based on a formatting argument provided

Long form values of MonthNames

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Example 1 – System variables default

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset of dates that is loaded into a table named `Transactions`.
- A date field.
- The default `MonthNames` definition.

#### Load script

```
SET MonthNames='Jan;Feb;Mar;Apr;May;Jun;Jul;Aug;Sep;Oct;Nov;Dec';
```

```
Transactions:
LOAD
date,
Month(date) as monthname,
id,
amount
INLINE
[
date,id,amount
01/01/2022,1,1000.45
01/02/2022,2,2123.34
01/03/2022,3,4124.35
01/04/2022,4,2431.36
01/05/2022,5,4787.78
01/06/2022,6,2431.84
01/07/2022,7,2854.83
01/08/2022,8,3554.28
01/09/2022,9,3756.17
01/10/2022,10,3454.35
];
```

---

## 4 Working with variables in the data load editor

---

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- monthname

Create this measure:

```
=sum(amount)
```

Results table		
date	monthname	sum(amount)
01/01/2022	Jan	1000.45
01/02/2022	Jan	2123.34
01/03/2022	Jan	4124.35
01/04/2022	Jan	2431.36
01/05/2022	Jan	4787.78
01/06/2022	Jan	2431.84
01/07/2022	Jan	2854.83
01/08/2022	Jan	3554.28
01/09/2022	Jan	3756.17
01/10/2022	Jan	3454.35

The default `monthNames` definition is used. In the load script, the `month` function is used with the `date` field as the provided argument.

In the results table, the output of this `month` function displays the months of the year in the format of the `monthNames` definition.

### Example 2 - Change system variable

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset of dates that is loaded into a table named `transactions`.
- A date field.
- The `monthNames` variable that is modified to use the abbreviated months in Spanish.

## 4 Working with variables in the data load editor

---

### Load script

```
Set MonthNames='Enero;Feb;Marzo;Abr;Mayo;Jun;Jul;Agosto;Set;Oct;Nov;Dic';
```

```
Transactions:
LOAD
date,
month(date) as month,
id,
amount
INLINE
[
date,id,amount
01/01/2022,1,1000
02/01/2022,2,2123
03/01/2022,3,4124
04/01/2022,4,2431
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- monthname

Create this measure:

```
=sum(amount)
```

Results table		
date	monthname	sum(amount)
01/01/2022	Enero	1000.45
01/02/2022	Enero	2123.34
01/03/2022	Enero	4124.35
01/04/2022	Enero	2431.36
01/05/2022	Enero	4787.78
01/06/2022	Enero	2431.84
01/07/2022	Enero	2854.83
01/08/2022	Enero	3554.28
01/09/2022	Enero	3756.17
01/10/2022	Enero	3454.35

In the load script, first the `MonthNames` variable is modified to list the months of the year abbreviated in Spanish. The `Month` function is used with the `date` field as the provided argument.

---

## 4 Working with variables in the data load editor

---

In the results table, the output of this `Month` function displays the months of the year in the format of the `MonthNames` definition.

It is important to remember that if the language for the `MonthNames` variable is modified like it has been in this example, the `LongMonthNames` variable would still contain the months of the year in English. The `LongMonthNames` variable would have to be modified if both variables are used in the application.

### Example 3 – Date function

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset of dates that is loaded into a table named `Transactions`.
- A date field.
- The default `MonthNames` definition.

#### Load script

```
SET MonthNames='Jan;Feb;Mar;Apr;May;Jun;Jul;Aug;Sep;Oct;Nov;Dec';
```

Transactions:

```
LOAD
date,
Month(date, 'MMM') as monthname,
id,
amount
INLINE
[
date,id,amount
01/01/2022,1,1000.45
01/02/2022,2,2123.34
01/03/2022,3,4124.35
01/04/2022,4,2431.36
01/05/2022,5,4787.78
01/06/2022,6,2431.84
01/07/2022,7,2854.83
01/08/2022,8,3554.28
01/09/2022,9,3756.17
01/10/2022,10,3454.35
];
```

#### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

---

## 4 Working with variables in the data load editor

---

- date
- monthname

Create this measure:

```
=sum(amount)
```

Results table		
date	monthname	sum(amount)
01/01/2022	Jan	1000.45
01/02/2022	Jan	2123.34
01/03/2022	Jan	4124.35
01/04/2022	Jan	2431.36
01/05/2022	Jan	4787.78
01/06/2022	Jan	2431.84
01/07/2022	Jan	2854.83
01/08/2022	Jan	3554.28
01/09/2022	Jan	3756.17
01/10/2022	Jan	3454.35

The default `monthNames` definition is used. In the load script, the `date` function is used with the `date` field as the first argument. The second argument is `MMM`.

Using this formatting Qlik Sense converts the values from the first argument into the corresponding month name set in the variable `monthNames`. In the results table, the field values of our created field `month` display this.

### NumericalAbbreviation

The numerical abbreviation sets which abbreviation to use for scale prefixes of numerals, for example M for mega or a million ( $10^6$ ), and  $\mu$  for micro ( $10^{-6}$ ).

#### Syntax:

##### **NumericalAbbreviation**

You set the `NumericalAbbreviation` variable to a string containing a list of abbreviation definition pairs, delimited by semi colon. Each abbreviation definition pair should contain the scale (the exponent in decimal base) and the abbreviation separated by a colon, for example, `6:M` for a million.

The default setting is `'3:k;6:M;9:G;12:T;15:P;18:E;21:Z;24:Y;-3:m;-6:μ;-9:n;-12:p;-15:f;-18:a;-21:z;-24:y'`.

#### Examples:

This setting will change the prefix for a thousand to `t` and the prefix for a billion to `B`. This would be useful for financial applications where you would expect abbreviations like `t$`, `M$`, and `B$`.



---

## 4 Working with variables in the data load editor

---

```
Set NumericalAbbreviation='3:t;6:M;9:B;12:T;15:P;18:E;21:Z;24:Y;-3:m;-6:μ;-9:n;-12:p;-15:f;-18:a;-21:z;-24:y';
```

### ReferenceDay

The setting defines which day in January to set as reference day to define week 1. In other words, this setting prescribes how many days in week 1 must be dates within January.

#### Syntax:

##### ReferenceDay

ReferenceDay sets how many days are included in the first week of the year. ReferenceDay can be set to any value between 1 and 7. Any value outside of the 1-7 range is interpreted as the midpoint of the week (4), which is equivalent to ReferenceDay being set to 4.

If you do not select a value for the ReferenceDay setting, then the default value will show ReferenceDay=0 which will be interpreted as the midpoint of the week (4), as seen in the ReferenceDay values table below.

The ReferenceDay function is often used in combination with the following functions:

#### Related functions

Variable	Interaction
<i>BrokenWeeks</i> (page 213)	If the Qlik Sense app is operating with unbroken weeks, the ReferenceDay variable setting will be enforced. However, if broken weeks are being used, week 1 will begin on January 1 and terminate in conjunction with the FirstWeekDay variable setting and ignore the ReferenceDay flag.
<i>FirstWeekDay</i> (page 228)	Integer that defines which day to use as the first day of the week.

Qlik Sense allows the following values to be set for ReferenceDay:

#### ReferenceDay values

Value	Reference day
0 (default)	January 4
1	January 1
2	January 2
3	January 3
4	January 4
5	January 5
6	January 6
7	January 7

In the following example the ReferenceDay = 3 defines January 3 as the reference day:

---

## 4 Working with variables in the data load editor

---

```
SET ReferenceDay=3; //(set January 3 as the reference day)
```

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Examples:

If you want ISO settings for weeks and week numbers, make sure to have the following in the script:

```
Set FirstWeekDay=0;
Set BrokenWeeks=0;
Set ReferenceDay=4; // Jan 4th is always in week 1
```

If you want US settings, make sure to have the following in the script:

```
Set FirstWeekDay=6;
Set BrokenWeeks=1;
Set ReferenceDay=1; // Jan 1st is always in week 1
```

### Example 1 - Load script using the default value; ReferenceDay=0

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The `ReferenceDay` variable that is set to 0.
- The `BrokenWeeks` variable that is set to 0 which forces the app to use unbroken weeks.
- A dataset of dates from the end of 2019 to the start of 2020.

#### Load script

```
SET BrokenWeeks = 0;
SET ReferenceDay = 0;
```

```
Sales:
LOAD
date,
sales,
week(date) as week,
```

## 4 Working with variables in the data load editor

---

```
weekday(date) as weekday
Inline [
date,sales
12/27/2019,5000
12/28/2019,6000
12/29/2019,7000
12/30/2019,4000
12/31/2019,3000
01/01/2020,6000
01/02/2020,3000
01/03/2020,6000
01/04/2020,8000
01/05/2020,5000
01/06/2020,7000
01/07/2020,3000
01/08/2020,5000
01/09/2020,9000
01/10/2020,5000
01/11/2020,7000
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- week
- weekday

Results table		
<b>date</b>	<b>week</b>	<b>weekday</b>
12/27/2019	52	Fri
12/28/2019	52	Sat
12/29/2019	1	Sun
12/30/2019	1	Mon
12/31/2019	1	Tue
01/01/2020	1	Wed
01/02/2020	1	Thu
01/03/2020	1	Fri
01/04/2020	1	Sat
01/05/2020	2	Sun
01/06/2020	2	Mon
01/07/2020	2	Tue
01/08/2020	2	Wed

## 4 Working with variables in the data load editor

---

<b>date</b>	<b>week</b>	<b>weekday</b>
01/09/2020	2	Thu
01/10/2020	2	Fri
01/11/2020	2	Sat

Week 52 concludes on Saturday, December 28. Because `referenceDay` requires January 4 to be included in week 1, week 1 therefore begins on December 29 and concludes on Saturday, January 4.

### Example - ReferenceDay variable set to 5

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The `referenceDay` variable that is set to 5.
- The `brokenWeeks` variable that is set to 0 which forces the app to use unbroken weeks.
- A dataset of dates from the end of 2019 to the start of 2020.

#### Load script

```
SET BrokenWeeks = 0;  
SET ReferenceDay = 5;
```

```
sales:  
LOAD  
date,  
sales,  
week(date) as week,  
weekday(date) as weekday  
Inline [  
date,sales  
12/27/2019,5000  
12/28/2019,6000  
12/29/2019,7000  
12/30/2019,4000  
12/31/2019,3000  
01/01/2020,6000  
01/02/2020,3000  
01/03/2020,6000  
01/04/2020,8000  
01/05/2020,5000  
01/06/2020,7000  
01/07/2020,3000  
01/08/2020,5000  
01/09/2020,9000
```

## 4 Working with variables in the data load editor

---

```
01/10/2020,5000  
01/11/2020,7000  
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- week
- weekday

Results table

<b>date</b>	<b>week</b>	<b>weekday</b>
12/27/2019	52	Fri
12/28/2019	52	Sat
12/29/2019	53	Sun
12/30/2019	53	Mon
12/31/2019	53	Tue
01/01/2020	53	Wed
01/02/2020	53	Thu
01/03/2020	53	Fri
01/04/2020	53	Sat
01/05/2020	1	Sun
01/06/2020	1	Mon
01/07/2020	1	Tue
01/08/2020	1	Wed
01/09/2020	1	Thu
01/10/2020	1	Fri
01/11/2020	1	Sat

Week 52 concludes on Saturday, December 28. The `brokenweeks` variable forces the app to use unbroken weeks. The reference day value of 5 requires January 5 to be included in week 1.

However, this is eight days after the conclusion of week 52 of the previous year. Therefore, week 53 begins on December 29 and concludes on January 4. Week 1 begins on Sunday, January 5.

### ThousandSep


The thousands separator defined replaces the digit grouping symbol of the operating system (regional settings).

## 4 Working with variables in the data load editor

### Syntax:

#### ThousandSep

Qlik Sense object using the ThousandSep variable (with thousands separator)



Qlik Sense apps interpret text fields that conform to this formatting as numbers. This formatting will be displayed in chart objects when a numerical field's **Number formatting** property is set to **Number**.

Thousandsep is helpful when handling data sources received from multiple regional settings.



*If the ThousandSep variable is modified after objects have already been created and formatted in the application, the user will need to re-format each relevant field by de-selecting and then re-selecting the **Number formatting** property **Number**.*

The following examples show possible uses of the ThousandSep system variable:

```
set ThousandSep=','; //(for example, seven billion will be displayed as: 7,000,000,000)
```

```
set ThousandSep=' '; //(for example, seven billion will be displayed as: 7 000 000 000)
```

These topics may help you work with this function:

#### Related topics

Topic	Description
<i>DecimalSep</i> (page 225)	In instances of text field interpretation, the decimal separator settings, as provided by this function, must also be respected. For number formatting, <b>DecimalSep</b> will be used by Qlik Sense where necessary.

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

## 4 Working with variables in the data load editor

---

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Example 1 - Default system variables

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset which is loaded into a table named Transactions.
- Use of the default Thousandsep variable definition.

#### Load script

Transactions:

```
Load
date,
id,
amount
Inline
[
date,id,amount
01/01/2022,1,10000000441
01/02/2022,2,21237492432
01/03/2022,3,41249475336
01/04/2022,4,24313369837
01/05/2022,5,47873578754
01/06/2022,6,24313884663
01/07/2022,7,28545883436
01/08/2022,8,35545828255
01/09/2022,9,37565817436
01/10/2022,10,3454343566
];
```


#### Results

##### Do the following:

1. Load the data and open a sheet. Create a new table and add this field as a dimension:date.
2. Add the following measure:  
=sum(amount)
3. In the properties panel, under **Data**, select the measure.
4. Under **Number formatting**, select **Number**.

## 4 Working with variables in the data load editor

Adjusting number formatting for a chart measure



Results table

<b>date</b>	<b>=sum(amount)</b>
01/01/2022	10,000,000,441.00
01/02/2022	21,237,492,432.00
01/03/2022	41,249,475,336.00
01/04/2022	24,313,369,837.00
01/05/2022	47,873,578,754.00
01/06/2022	24,313,884,663.00
01/07/2022	28,545,883,436.00
01/08/2022	35,545,828,255.00
01/09/2022	37,565,817,436.00
01/10/2022	3,454,343,566.00

In this example, the default `ThousandSep` definition, which is set to comma format (','), is used. In the results table, the format of the amount field displays a comma between thousand groupings.

### Example 2 - Changing system variable

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.



## 4 Working with variables in the data load editor

---

The load script contains:

- The same dataset from the first example, which is loaded into a table named `Transactions`.
- Modification of the `ThousandSep` definition, at the start of the script, to display a '\*' character as the thousands separator. This is an extreme example, and is used solely to demonstrate the functionality of the variable.

The modification used in this example is extreme and not commonly used, but is shown here to demonstrate the functionality of the variable.

### Load script

```
SET ThousandSep='*';
```

```
Transactions:
```

```
Load
```

```
date,
```

```
id,
```

```
amount
```

```
Inline
```

```
[
```

```
date,id,amount
```

```
01/01/2022,1,10000000441
```

```
01/02/2022,2,21237492432
```

```
01/03/2022,3,41249475336
```

```
01/04/2022,4,24313369837
```

```
01/05/2022,5,47873578754
```

```
01/06/2022,6,24313884663
```

```
01/07/2022,7,28545883436
```

```
01/08/2022,8,35545828255
```

```
01/09/2022,9,37565817436
```

```
01/10/2022,10,3454343566
```

```
];
```

### Results

#### Do the following:

1. Load the data and open a sheet. Create a new table and add this field as a dimension: `date`.
2. Add the following measure:  
`=sum(amount)`
3. In the properties panel, under **Data**, select the measure.
4. Under **Number formatting**, select **Custom**.

Results table

date	=sum(amount)
01/01/2022	10*000*000*441.00
01/02/2022	21*237*492*432.00

## 4 Working with variables in the data load editor

---

date	=sum(amount)
01/03/2022	41*249*475*336.00
01/04/2022	24*313*369*837.00
01/05/2022	47*873*578*754.00
01/06/2022	24*313*884*663.00
01/07/2022	28*545*883*436.00
01/08/2022	35*545*828*255.00
01/09/2022	37*565*817*436.00
01/10/2022	3*454*343*566.00

At the start of the script, the `Thousandsep` system variable is modified to a `'*`'. In the results table, the format of the amount field can be seen to display a `'*`' between thousand grouping.

### Example 3 - Text interpretation

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset which is loaded into a table named `transactions`.
- Data which has its numerical field in text format, with a comma used as the thousands separator.
- Use of the default `Thousandsep` system variable.

#### Load script

```
Transactions:
Load
date,
id,
amount
Inline
[
date,id,amount
01/01/2022,1,'10,000,000,441'
01/02/2022,2,'21,492,432'
01/03/2022,3,'4,249,475,336'
01/04/2022,4,'24,313,369,837'
01/05/2022,5,'4,873,578,754'
01/06/2022,6,'313,884,663'
01/07/2022,7,'2,545,883,436'
01/08/2022,8,'545,828,255'
```

## 4 Working with variables in the data load editor

```
01/09/2022,9,'37,565,817,436'  
01/10/2022,10,'3,454,343,566'  
];
```

### Results

#### Do the following:

1. Load the data and open a sheet. Create a new table and add this field as a dimension:date.
2. Add the following measure:  
`=sum(amount)`
3. In the properties panel, under **Data**, select the measure.
4. Under **Number formatting**, select **Number**.
5. Add the following measure to evaluate whether or not the amount field is a numerical value:  
`=isnum(amount)`

Results table

date	=sum(amount)	=isnum(amount)
01/01/2022	10,000,000,441.00	-1
01/02/2022	21,492,432.00	-1
01/03/2022	4,249,475,336.00	-1
01/04/2022	24,313,369,837.00	-1
01/05/2022	4,873,578,754.00	-1
01/06/2022	313,884,663.00	-1
01/07/2022	2,545,883,436.00	-1
01/08/2022	545,828,255.00	-1
01/09/2022	37,565,817,436.00	-1
01/10/2022	3*454*343*566.00	-1

Once the data is loaded, we can see that Qlik Sense has interpreted the amount field as a numerical value, due to the data conforming to the `thousandsep` variable. This is demonstrated by the `isnum()` function, which evaluates each entry to -1, or `TRUE`.



*In Qlik Sense, the Boolean true value is represented by -1, and the false value is represented by 0.*

## TimeFormat

The format defined replaces the time format of the operating system (regional settings).

### Syntax:

```
TimeFormat
```

### Example:

```
Set TimeFormat='hh:mm:ss';
```

## TimestampFormat

The format defined replaces the date and time formats of the operating system (regional settings).

### Syntax:

```
TimestampFormat
```

### Example:

The following examples use *1983-12-14T13:15:30Z* as timestamp data to show the results of different **SET TimestampFormat** statements. The date format used is **YYYYMMDD** and the time format is **h:mm:ss TT**. The date format is specified in the **SET DateFormat** statement and the time format is specified in the **SET TimeFormat** statement, at the top of the data load script.

#### Results

Example	Result
SET TimestampFormat='YYYYMMDD';	19831214
SET TimestampFormat='M/D/YY hh:mm:ss[.fff]';	12/14/83 13:15:30
SET TimestampFormat='DD/MM/YYYY hh:mm:ss[.fff]';	14/12/1983 13:15:30
SET TimestampFormat='DD/MM/YYYY hh:mm:ss[.fff] TT';	14/12/1983 1:15:30 PM
SET TimestampFormat='YYYY-MM-DD hh:mm:ss[.fff] TT';	1983-12-14 01:15:30

## Examples: Load script

### Example: Load script

In the first load script *SET TimestampFormat='DD/MM/YYYY h:mm:ss[.fff] TT'* is used. In the second load script the timestamp format is changed to *SET TimestampFormat='MM/DD/YYYY hh:mm:ss[.fff]'*. The different results show how the **SET TimeFormat** statement works with different time data formats.

The table below shows the data set that is used in the load scripts that follow. The second column of the table shows the format of each timestamp in the data set. The first five timestamps follow ISO 8601 rules but the sixth does not.

## 4 Working with variables in the data load editor

---

### Data set

Table showing the time data used and the format for each timestamp in the data set.

transaction_timestamp	time data format
2018-08-30	YYYY-MM-DD
20180830T193614.857	YYYYMMDDhhmmss.sss
20180830T193614.857+0200	YYYYMMDDhhmmss.sss±hhmm
2018-09-16T12:30-02:00	YYYY-MM-DDhh:mm±hh:mm
2018-09-16T13:15:30Z	YYYY-MM-DDhh:mmZ
9/30/18 19:36:14	M/D/YY hh:mm:ss

In the **Data load editor**, create a new section, and then add the example script and run it. Then add, at least, the fields listed in the results column to a sheet in your app to see the result.

### Load script

```
SET FirstWeekDay=0;
SET BrokenWeeks=1;
SET ReferenceDay=0;
SET DayNames='Mon;Tue;Wed;Thu;Fri;Sat;Sun';
SET LongDayNames='Monday;Tuesday;Wednesday;Thursday;Friday;Saturday;Sunday';
SET DateFormat='YYYYMMDD';
SET TimestampFormat='DD/MM/YYYY h:mm:ss[.fff] TT';

Transactions:
Load
*,
Timestamp(transaction_timestamp, 'YYYY-MM-DD hh:mm:ss[.fff]') as LogTimestamp
;

Load * Inline [
transaction_id, transaction_timestamp, transaction_amount, transaction_quantity, discount,
customer_id, size, color_code
3750, 2018-08-30, 12423.56, 23, 0, 2038593, L, Red
3751, 20180830T193614.857, 5356.31, 6, 0.1, 203521, m, orange
3752, 20180830T193614.857+0200, 15.75, 1, 0.22, 5646471, S, blue
3753, 2018-09-16T12:30-02:00, 1251, 7, 0, 3036491, l, Black
3754, 2018-09-16T13:15:30Z, 21484.21, 1356, 75, 049681, xs, Red
3755, 9/30/18 19:36:14, -59.18, 2, 0.3333333333333333, 2038593, M, Blue
];
```

## 4 Working with variables in the data load editor

---

### Results

*Qlik Sense table showing results of the TimestampFormat interpretation variable being used in the load script. The last timestamp in the data set does not return a correct date.*

transaction_id	transaction_timestamp	LogTimeStamp
3750	2018-08-30	2018-08-30 00:00:00
3751	20180830T193614.857	2018-08-30 19:36:14
3752	20180830T193614.857+0200	2018-08-30 17:36:14
3753	2018-09-16T12:30-02:00	2018-09-16 14:30:00
3754	2018-09-16T13:15:30Z	2018-09-16 13:15:30
3755	9/30/18 19:36:14	-

The next load script uses the same data set. However, it uses *SET TimestampFormat='MM/DD/YYYY hh:mm:ss[.fff]'* to match the non-ISO 8601 format of the sixth timestamp.

In the **Data load editor**, replace the previous example script with the one below and run it. Then add, at least, the fields listed in the results column to a sheet in your app to see the result.

### Load script

```
SET FirstWeekDay=0;
SET BrokenWeeks=1;
SET ReferenceDay=0;
SET DayNames='Mon;Tue;Wed;Thu;Fri;Sat;Sun';
SET LongDayNames='Monday;Tuesday;Wednesday;Thursday;Friday;Saturday;Sunday';
SET DateFormat='YYYYMMDD';
SET TimestampFormat='MM/DD/YYYY hh:mm:ss[.fff]';

Transactions:
Load
*,
Timestamp(transaction_timestamp, 'YYYY-MM-DD hh:mm:ss[.fff]') as LogTimeStamp
;

Load * Inline [
transaction_id, transaction_timestamp, transaction_amount, transaction_quantity, discount,
customer_id, size, color_code
3750, 2018-08-30, 12423.56, 23, 0, 2038593, L, Red
3751, 20180830T193614.857, 5356.31, 6, 0.1, 203521, m, orange
3752, 20180830T193614.857+0200, 15.75, 1, 0.22, 5646471, s, blue
3753, 2018-09-16T12:30-02:00, 1251, 7, 0, 3036491, l, black
3754, 2018-09-16T13:15:30Z, 21484.21, 1356, 75, 049681, xs, Red
3755, 9/30/18 19:36:14, -59.18, 2, 0.3333333333333333, 2038593, M, Blue
];
```

### Results

*Qlik Sense table showing results of the TimestampFormat interpretation variable being used in the load script.*

transaction_id	transaction_timestamp	LogTimeStamp
3750	2018-08-30	2018-08-30 00:00:00
3751	20180830T193614.857	2018-08-30 19:36:14
3752	20180830T193614.857+0200	2018-08-30 17:36:14
3753	2018-09-16T12:30-02:00	2018-09-16 14:30:00
3754	2018-09-16T13:15:30Z	2018-09-16 13:15:30
3755	9/30/18 19:36:14	2018-09-16 19:36:14

## 4.9 Direct Discovery variables

### Direct Discovery system variables

#### DirectCacheSeconds

You can set a caching limit to the Direct Discovery query results for visualizations. Once this time limit is reached, Qlik Sense clears the cache when new Direct Discovery queries are made. Qlik Sense queries the source data for the selections and creates the cache again for the designated time limit. The result for each combination of selections is cached independently. That is, the cache is refreshed for each selection independently, so one selection refreshes the cache only for the fields selected, and a second selection refreshes cache for its relevant fields. If the second selection includes fields that were refreshed in the first selection, they are not updated in cache again if the caching limit has not been reached.

The Direct Discovery cache does not apply to **Table** visualizations. Table selections query the data source every time.

The limit value must be set in seconds. The default cache limit is 1800 seconds (30 minutes).

The value used for **DirectCacheSeconds** is the value set at the time the **DIRECT QUERY** statement is executed. The value cannot be changed at runtime.

#### Example:

```
SET DirectCacheSeconds=1800;
```

#### DirectConnectionMax

You can do asynchronous, parallel calls to the database by using the connection pooling capability. The load script syntax to set up the pooling capability is as follows:

```
SET DirectConnectionMax=10;
```

## 4 Working with variables in the data load editor

---

The numeric setting specifies the maximum number of database connections the Direct Discovery code should use while updating a sheet. The default setting is 1.



*This variable should be used with caution. Setting it to greater than 1 is known to cause problems when connecting to Microsoft SQL Server.*

### DirectUnicodeStrings

Direct Discovery can support the selection of extended Unicode data by using the SQL standard format for extended character string literals (N'<extended string>') as required by some databases (notably SQL Server). The use of this syntax can be enabled for Direct Discovery with the script variable **DirectUnicodeStrings**.

Setting this variable to 'true' will enable the use of the ANSI standard wide character marker "N" in front of the string literals. Not all databases support this standard. The default setting is 'false'.

### DirectDistinctSupport

When a **DIMENSION** field value is selected in a Qlik Sense object, a query is generated for the source database. When the query requires grouping, Direct Discovery uses the **DISTINCT** keyword to select only unique values. Some databases, however, require the **GROUP BY** keyword. Set **DirectDistinctSupport** to 'false' to generate **GROUP BY** instead of **DISTINCT** in queries for unique values.

```
SET DirectDistinctSupport='false';
```

If **DirectDistinctSupport** is set to true, then **DISTINCT** is used. If it is not set, the default behavior is to use **DISTINCT**.

### DirectEnableSubquery

In high cardinality multi-table scenarios, it is possible to generate sub queries in the SQL query instead of generating a large IN clause. This is activated by setting **DirectEnableSubquery** to 'true'. The default value is 'false'.



*When **DirectEnableSubquery** is enabled, you cannot load tables that are not in Direct Discovery mode.*

```
SET DirectEnableSubquery='true';
```

## Teradata query banding variables

Teradata query banding is a function that enables enterprise applications to collaborate with the underlying Teradata database in order to provide for better accounting, prioritization, and workload management. Using query banding you can wrap metadata, such as user credentials, around a query.

Two variables are available, both are strings that are evaluated and sent to the database.

SQLSessionPrefix

This string is sent when a connection to the database is created.



---

## 4 Working with variables in the data load editor

---

```
SET SQLSessionPrefix = 'SET QUERY_BAND = ' & Chr(39) & 'who=' & OSuser() & ';' & Chr(39) & '
FOR SESSION;';
```

If **OSuser()** for example returns *WA\sbt*, this will be evaluated to `SET QUERY_BAND = 'who=WA\sbt;'` FOR SESSION; , which is sent to the database when the connection is created.

SQLQueryPrefix

This string is sent for each single query.

```
SET SQLSessionPrefix = 'SET QUERY_BAND = ' & Chr(39) & 'who=' & OSuser() & ';' & Chr(39) & '
FOR TRANSACTION;';
```

### Direct Discovery character variables

#### DirectFieldColumnDelimiter

You can set the character used as the field delimiter in **Direct Query** statements for databases that require a character other than comma as the field delimiter. The specified character must be surrounded by single quotation marks in the **SET** statement.

```
SET DirectFieldColumnDelimiter= '|'
```

#### DirectStringQuoteChar

You can specify a character to use to quote strings in a generated query. The default is a single quotation mark. The specified character must be surrounded by single quotation marks in the **SET** statement.

```
SET DirectStringQuoteChar= '''';
```

#### DirectIdentifierQuoteStyle

You can specify that non-ANSI quoting of identifiers be used in generated queries. At this time, the only non-ANSI quoting available is GoogleBQ. The default is ANSI. Uppercase, lowercase, and mixed case can be used (ANSI, ansi, Ansi).

```
SET DirectIdentifierQuoteStyle="GoogleBQ";
```

For example, ANSI quoting is used in the following **SELECT** statement:

```
SELECT [Quarter] FROM [qvTest].[sales] GROUP BY [Quarter]
```

When **DirectIdentifierQuoteStyle** is set to "GoogleBQ", the **SELECT** statement would use quoting as follows:

```
SELECT [Quarter] FROM [qvTest.sales] GROUP BY [Quarter]
```

#### DirectIdentifierQuoteChar

You can specify a character to control the quoting of identifiers in a generated query. This can be set to either one character (such as a double quotation mark) or two (such as a pair of square brackets). The default is a double quotation mark.

```
SET DirectIdentifierQuoteChar='[]';
SET DirectIdentifierQuoteChar='``';
SET DirectIdentifierQuoteChar=' ' ;
SET DirectIdentifierQuoteChar='''''';
```

### **DirectTableBoxListThreshold**

When Direct Discovery fields are used in a **Table** visualization, a threshold is set to limit the number of rows displayed. The default threshold is 1000 records. The default threshold setting can be changed by setting the **DirectTableBoxListThreshold** variable in the load script. For example:

```
SET DirectTableBoxListThreshold=5000;
```

The threshold setting applies only to **Table** visualizations that contain Direct Discovery fields. **Table** visualizations that contain only in-memory fields are not limited by the **DirectTableBoxListThreshold** setting.

No fields are displayed in the **Table** visualization until the selection has fewer records than the threshold limit.

## Direct Discovery number interpretation variables

### **DirectMoneyDecimalSep**

The decimal separator defined replaces the decimal symbol for currency in the SQL statement generated to load data using Direct Discovery. This character must match the character used in **DirectMoneyFormat**.

Default value is '.'

#### **Example:**

```
Set DirectMoneyDecimalSep='.';
```

### **DirectMoneyFormat**

The symbol defined replaces the currency format in the SQL statement generated to load data using Direct Discovery. The currency symbol for the thousands separator should not be included.

Default value is '#.0000'

#### **Example:**

```
Set DirectMoneyFormat='#.0000';
```

### **DirectTimeFormat**

The time format defined replaces the time format in the SQL statement generated to load data using Direct Discovery.

#### **Example:**

```
Set DirectTimeFormat='hh:mm:ss';
```

### **DirectDateFormat**

The date format defined replaces the date format in the SQL statement generated to load data using Direct Discovery.

#### **Example:**

```
Set DirectDateFormat='MM/DD/YYYY';
```

### **DirectTimeStampFormat**

The format defined replaces the date and time format in the SQL statement generated in the SQL statement generated to load data using Direct Discovery.

#### **Example:**

```
Set DirectTimeStampFormat='M/D/YY hh:mm:ss[.fff]';
```

## 4.10 Error variables

The values of all error variables will exist after the script execution. The first variable, `ErrorMode`, is input from the user, and the last three are output from Qlik Sense with information on errors in the script.

### Error variables overview

Each variable is described further after the overview. You can also click the variable name in the syntax to immediately access the details for that specific variable.

Refer to the Qlik Sense online help for further details about the variable.

#### **ErrorMode**

This error variable determines what action is to be taken by Qlik Sense when an error is encountered during script execution.

**ErrorMode**

#### **ScriptError**

This error variable returns the error code of the last executed script statement.

**ScriptError**

#### **ScriptErrorCount**

This error variable returns the total number of statements that have caused errors during the current script execution. This variable is always reset to 0 at the start of script execution.

**ScriptErrorCount**

#### **ScriptErrorList**

This error variable will contain a concatenated list of all script errors that have occurred during the last script execution. Each error is separated by a line feed.

**ScriptErrorList**

## ErrorMode

This error variable determines what action is to be taken by Qlik Sense when an error is encountered during script execution.

#### **Syntax:**

**ErrorMode**

## 4 Working with variables in the data load editor

---

### Arguments:

Arguments

Argument	Description
<b>ErrorMode=1</b>	The default setting. The script execution will halt and the user will be prompted for action (non-batch mode).
<b>ErrorMode =0</b>	Qlik Sense will simply ignore the failure and continue script execution at the next script statement.
<b>ErrorMode =2</b>	Qlik Sense will trigger an "Execution of script failed..." error message immediately on failure, without prompting the user for action beforehand.

### Example:

```
set ErrorMode=0;
```

## ScriptError

This error variable returns the error code of the last executed script statement.

### Syntax:

```
ScriptError
```

This variable will be reset to 0 after each successfully executed script statement. If an error occurs it will be set to an internal Qlik Sense error code. Error codes are dual values with a numeric and a text component. The following error codes exist:

Script error codes

Error code	Description
0	No error. Dual value text is empty.
1	General error.
2	Syntax error.
3	General ODBC error.
4	General OLE DB error.
5	General custom database error.
6	General XML error.
7	General HTML error.
8	File not found.

Error code	Description
9	Database not found.
10	Table not found.
11	Field not found.
12	File has wrong format.
16	Semantic error.

### Example:

```
set ErrorMode=0;
LOAD * from abc.qvf;
if ScriptError=8 then
exit script;
//no file;
end if
```

### ScriptErrorCount

This error variable returns the total number of statements that have caused errors during the current script execution. This variable is always reset to 0 at the start of script execution.

#### Syntax:

```
ScriptErrorCount
```

### ScriptErrorList

This error variable will contain a concatenated list of all script errors that have occurred during the last script execution. Each error is separated by a line feed.

#### Syntax:

```
ScriptErrorList
```

## 5 Script expressions

Expressions can be used in both **LOAD** statements and **SELECT** statements. The syntax and functions described here apply to the **LOAD** statement, and not to the **SELECT** statement, since the latter is interpreted by the ODBC driver and not by Qlik Sense. However, most ODBC drivers are often capable of interpreting a number of the functions described below.

Expressions consist of functions, fields and operators, combined in a syntax.

All expressions in a Qlik Sense script return a number and/or a string, whichever is appropriate. Logical functions and operators return 0 for False and -1 for True. Number to string conversions and vice versa are implicit. Logical operators and functions interpret 0 as False and all else as True.

The general syntax for an expression is:

General syntax

Expression	Fields	Operator
expression ::= (constant	constant	
expression ::= (constant	fieldref	
expression ::= (constant	operator1 expression	
expression ::= (constant	expression operator2 expression	
expression ::= (constant	function	
expression ::= (constant	( expression )	)

where:

- **constant** is a string (a text, a date or a time) enclosed by single straight quotation marks, or a number. Constants are written with no thousands separator and with a decimal point as the decimal separator.
- **fieldref** is a field name of the loaded table.
- **operator1** is a unary operator (working on one expression, the one to the right).
- **operator2** is a binary operator (working on two expressions, one on each side).
- **function ::= functionname( parameters)**
- **parameters ::= expression { , expression }**

The number and types of parameters are not arbitrary. They depend on the function used.

Expressions and functions can thus be nested freely, and as long as the expression returns an interpretable value, Qlik Sense will not give any error messages.

## 6 Chart expressions

A chart (visualization) expression is a combination of functions, fields, and mathematical operators (+ \* / =), and other measures. Expressions are used to process data in the app in order to produce a result that can be seen in a visualization. They are not limited to use in measures. You can build visualizations that are more dynamic and powerful, with expressions for titles, subtitles, footnotes, and even dimensions.

This means, for example, that instead of the title of a visualization being static text, it can be made from an expression whose result changes depending on the selections made.



*For detailed reference regarding script functions and chart functions, see the Script syntax and chart functions.*

### 6.1 Defining the aggregation scope

There are usually two factors that together determine which records are used to define the value of aggregation in an expression. When working in visualizations these factors are:

- Dimensional value (of the aggregation in a chart expression)
- Selections

Together, these factors define the scope of the aggregation. You may come across situations where you want your calculation to disregard the selection, the dimension or both. In chart functions, you can achieve this by using the TOTAL qualifier, set analysis or a combination of the two.

## Aggregation: Method and description

Method	Description
TOTAL qualifier	<p>Using the total qualifier inside your aggregation function disregards the dimensional value.</p> <p>The aggregation will be performed on all possible field values.</p> <p>The <b>TOTAL</b> qualifier may be followed by a list of one or more field names within angle brackets. These field names should be a subset of the chart dimension variables. In this case, the calculation is made disregarding all chart dimension variables except those listed, that is, one value is returned for each combination of field values in the listed dimension fields. Also, fields that are not currently a dimension in a chart may be included in the list. This may be useful in the case of group dimensions, where the dimension fields are not fixed. Listing all of the variables in the group causes the function to work when the drill-down level changes.</p>
Set analysis	Using set analysis inside your aggregation overrides the selection. The aggregation will be performed on all values split across the dimensions.
TOTAL qualifier and set analysis	Using the <b>TOTAL</b> qualifier and set analysis inside your aggregation overrides the selection and disregards the dimensions.
ALL qualifier	<p>Using the <b>ALL</b> qualifier inside your aggregation disregards the selection and the dimensions. The equivalent can be achieved with the {1} set analysis statement and the <b>TOTAL</b> qualifier:</p> <p>=sum(All Sales)</p> <p>=sum({1} Total Sales)</p>

**Example: TOTAL qualifier**

The following example shows how TOTAL can be used to calculate a relative share. Assuming that Q2 has been selected, using TOTAL calculates the sum of all values disregarding the dimensions.

Example: Total qualifier

Year	Quarter	Sum (Amount)	Sum(TOTAL Amount)	Sum(Amount)/Sum(TOTAL Amount)
		3000	3000	100%
2012	Q2	1700	3000	56,7%
2013	Q2	1300	3000	43,3%





To show the numbers as a percentage, in the properties panel, for the measure you want to show as a percentage value, under **Number formatting**, select **Number**, and from **Formatting**, choose **Simple** and one of the % formats.

### Example: Set analysis

The following example shows how set analysis can be used to make a comparison between data sets before any selection was made. Assuming that Q2 has been selected, using set analysis with the set definition {1} calculates the sum of all values disregarding any selections but split by the dimensions.

Example: Set analysis

Year	Quarter	Sum(Amount)	Sum({1} Amount)	Sum(Amount)/Sum({1} Amount)
		3000	10800	27,8%
2012	Q1	0	1100	0%
2012	Q3	0	1400	0%
2012	Q4	0	1800	0%
2012	Q2	1700	1700	100%
2013	Q1	0	1000	0%
2013	Q3	0	1100	0%
2013	Q4	0	1400	0%
2013	Q2	1300	1300	100%

### Example: TOTAL qualifier and set analysis

The following example shows how set analysis and the TOTAL qualifier can be combined to make a comparison between data sets before any selection was made and across all dimensions. Assuming that Q2 has been selected, using set analysis with the set definition {1} and the TOTAL qualifier calculates the sum of all values disregarding any selections and disregarding the dimensions.

Example: TOTAL qualifier and set analysis

Year	Quarter	Sum (Amount)	Sum({1} TOTAL Amount)	Sum(Amount)/Sum({1} TOTAL Amount)
		3000	10800	27,8%
2012	Q2	1700	10800	15,7%
2013	Q2	1300	10800	12%

Data used in examples:

```
AggregationScope:
LOAD * inline [
```

```
Year Quarter Amount
2012 Q1 1100
2012 Q2 1700
2012 Q3 1400
2012 Q4 1800
2013 Q1 1000
2013 Q2 1300
2013 Q3 1100
2013 Q4 1400] (delimiter is ' ');
```

### 6.2 Set analysis

When you make a selection in an app, you define a subset of records in the data. Aggregation functions, such as `sum()`, `max()`, `min()`, `avg()`, and `count()` are calculated based on this subset.

In other words, your selection defines the scope of the aggregation, it defines the set of records on which calculations are made.

Set analysis offers a way of defining a scope that is different from the set of records defined by the current selection. This new scope can also be regarded as an alternative selection.

This can be useful if you want to compare the current selection with a particular value, for example last year's value or the global market share.

### Set expressions

Set expressions can be used inside and outside aggregation functions, and are enclosed in curly brackets.

#### Example: Inner set expression

```
sum( {<Year={2021}>} Sales )
```

#### Example: Outer set expression

```
{<Year={2021}>} sum(Sales) / count(distinct Customer)
```

A set expression consists of a combination of the following elements:


- **Identifiers.** A set identifier represents a selection, defined elsewhere. It also represents a specific set of records in the data. It could be the current selection, a selection from a bookmark, or a selection from an alternate state. A simple set expression consists of a single identifier, such as the dollar sign, `{$}`, which means all records in the current selection. Examples: `$`, `1`, `BookMark1`, `State2`
- **Operators.** A set operator can be used to create unions, differences or intersections between different set identifiers. This way, you can create a subset or a superset of the selections defined by the set identifiers. Examples: `+`, `-`, `*`, `/`

- **Modifiers.** A set modifier can be added to the set identifier to change its selection. A modifier can also be used on its own and will then modify the default identifier. A modifier must be enclosed in angle brackets <...>.

Examples: <Year={2020}>, <Supplier={ACME}>

The elements are combined to form set expressions.

*Elements in a set expression*



The set expression above, for example, is built from the aggregation `sum(Sales)`.

The first operand returns sales for the year 2021 for the current selection, which is indicated by the `$` set identifier and the modifier containing the selection of year 2021. The second operand returns sales for Sweden, and ignores the current selection, which is indicated by the `1` set identifier.

Finally, the expression returns a set consisting of the records that belongs to any of the two set operands, as indicated by the `+` set operator.

## Examples

Examples that combine the set expression elements above are available in the following topics:

### Natural sets

Usually, a set expression represents both a set of records in the data model, and a selection that defines this subset of data. In this case, the set is called a natural set.

Set identifiers, with or without set modifiers, always represent natural sets.

However, a set expression using set operators also represents a subset of the records, but can generally still not be described using a selection of field values. Such an expression is a non-natural set.

For example, the set given by `{1-$}` cannot always be defined by a selection. It is therefore not a natural set. This can be shown by loading the following data, adding it to a table, and then making selections using filter panes.

```
Load * Inline
[Dim1, Dim2, Number
A, X, 1
A, Y, 1
B, X, 1
```

B, Y, 1];

By making selections for `Dim1` and `Dim2`, you get the view shown in the following table.

Table with natural and non-natural sets

Dim1	Dim2	Sum({\$} Number)	Sum({1-\$} Number)
Totals		1	3
A	X	1	0
A	Y	0	1
B	X	0	1
B	Y	0	1

The set expression in the first measure uses a natural set: it corresponds to the selection that is made `{$}`.

The second measure is different. It uses `{1-$}`. It is not possible to make a selection that corresponds to this set, so it is a non-natural set.

This distinction has a number of consequences:

- Set modifiers can only be applied to set identifiers. They cannot be applied to an arbitrary set expression. For example, it is not possible to use a set expression such as:  
`{ (BM01 * BM02) <Field={x,y}> }`  
 Here, the normal (round) brackets imply that the intersection between `BM01` and `BM02` should be evaluated before the set modifier is applied. The reason is that there is no element set that can be modified.
- You cannot use non-natural sets inside the `P()` and `E()` element functions. These functions return an element set, but it is not possible to deduce the element set from a non-natural set.
- A measure using a non-natural set cannot always be attributed to the right dimensional value if the data model has many tables. For example, in the following chart, some excluded sales numbers are attributed to the correct Country, whereas others have NULL as Country.

### Chart with non-natural set

ProductCategory	Country	Sum({\$} Sales)	Sum({1-\$} Sales)
Baby Clothes		127791.28	0
Children's Clothes		0	81681.54
Men's Clothes		0	140987.45
Men's Footwear		0	232747.44
Sportswear		0	270272.76
Swimwear		0	29548.6
Women's Clothes		0	649348.5
Women's Footwear		0	140654.44
-		0	131935.86
Belgium		0	1005.02
Germany		0	773.3
Portugal		0	1279.74

Whether or not the assignment is made correctly depends on the data model. In this case, the number cannot be assigned if it pertains to a country that is excluded by the selection.

Identifier	Description
1	Represents the full set of all the records in the application, irrespective of any selections made.
\$	Represents the records of the current selection. The set expression <b>{}</b> is thus the equivalent to not stating a set expression.
\$1	Represents the previous selection. \$2 represents the previous selection-but-one, and so on.
\$_1	Represents the next (forward) selection. \$_2 represents the next selection-but-one, and so on.
BM01	You can use any bookmark ID or bookmark name.
MyAltState	You can reference the selections made in an alternate state by its state name.

Example	Result
sum ({1} Sales)	Returns total sales for the app, disregarding selections but not the dimension.
sum ({\$} Sales)	Returns the sales for the current selection, that is, the same as sum(Sales).
sum ({\$1} Sales)	Returns the sales for the previous selection.
sum ({BM01} Sales)	Returns the sales for the bookmark named <i>BM01</i> .

Example	Result
sum({\$<OrderDate = DeliveryDate>} Sales)	Returns the sales for the current selection where OrderDate = DeliveryDate.
sum({1<Region = {US}>} Sales)	Returns the sales for region US, disregarding the current selection.
sum({\$<Region = >} Sales)	Returns the sales for the selection, but with the selection in <i>Region</i> removed.
sum({<Region = >} Sales)	Returns the same as the example above. When the set to modify is omitted, \$ is assumed.
sum({\$<Year={2000}, Region="{U*}">} Sales)	Returns the sales for the current selection, but with new selections both in <i>Year</i> and in <i>Region</i> .

## Set identifiers

A set identifier represents a set of records in the data; either all the data or a subset of the data. It is the set of records defined by a selection. It could be the current selection, all data (no selection), a selection from a bookmark, or a selection from an alternate state.

In the example `sum( {$<Year = {2009}>} sales )`, the identifier is the dollar sign: \$. This represents the current selection. It also represents all the possible records. This set can then be altered by the modifier part of the set expression: the selection 2009 in year is added.

The \$ set identifier is the same as not stating a set identifier. For instance, with the example above, the expression `sum( {$<Year = {2009}>} sales )` is equivalent to `sum( <Year = {2009}> sales )`.

In a more complex set expression, two identifiers can be used together with an operator to form a union, a difference, or an intersection of the two record sets.

The following table shows some common identifiers.

Examples with common identifiers

Identifier	Description
1	Represents the full set of all the records in the application, irrespective of any selections made.
\$ (or no set identifier)	Represents the records of the current selection in the default state. The set expression {\$} is thus usually the equivalent to not stating a set expression.
\$1	Represents the previous selection in the default state. \$2 represents the previous selection-but-one, and so on.
\$_1	Represents the next (forward) selection. \$_2 represents the next selection-but-one, and so on.

Identifier	Description
BM01	You can use any bookmark ID or bookmark name.
AltState	You can reference an alternate state by its state name.
AltState::BM01	A bookmark contains the selections of all states, and you can reference a specific bookmark by qualifying the bookmark name.

The following table shows examples with different identifiers.

Examples with different identifiers

Example	Result
Sum ({1} sales)	Returns total sales for the app disregarding selections but not the dimension.
Sum ({\$} sales)	Returns the sales for the current selection, that is, the same as sum(sales).
Sum ({\$1} sales)	Returns the sales for the previous selection.
Sum ({BM01} sales)	Returns the sales for the bookmark named BM01.

## Set operators

Set operators are used to include, exclude, or intersect data sets. All operators use sets as operands and return a set as result.

You can use set operators in two different situations:

- To perform a set operation on set identifiers, representing sets of records in data.
- To perform a set operation on the element sets, on the field values, or inside a set modifier.

The following table shows the operators that can be used in set expressions.

Operators

Operator	Description
+	Union. This binary operation returns a set consisting of the records or elements that belong to any of the two set operands.
-	Exclusion. This binary operation returns a set consisting of the records or elements that belong to the first but not the other of the two set operands. Also, when used as a unary operator, it returns the complement set.
*	Intersection. This binary operation returns a set consisting of the records or elements that belong to both set operands.
/	Symmetric difference (XOR). This binary operation returns a set consisting of the records or elements that belong to either, but not both set operands.

The following table shows examples with operators.

## Examples with operators

Example	Result
<code>sum ({1-\$} sales)</code>	Returns sales for everything excluded by current selection.
<code>sum ({*\$BM01} sales)</code>	Returns sales for the intersection between the selection and bookmark #160;BM01.
<code>sum ({-(\$+BM01)} sales)</code>	Returns sales excluded by the selection and bookmark BM01.
<code>sum ({&lt;Year={2009}&gt;+1&lt;Country={'Sweden'}&gt;} sales)</code>	Returns sales for the year 2009 associated with the current selections and add the full set of data associated with the country sweden across all years.
<code>sum ({&lt;Country={'S*'}+{"*land"}&gt;} sales)</code>	Returns the sales for countries that begin with s or end with land.

## Set modifiers

Set expressions are used to define the scope of a calculation. The central part of the set expression is the set modifier that specifies a selection. This is used to modify the user selection, or the selection in the set identifier, and the result defines a new scope for the calculation.

The set modifier consists of one or more field names, each followed by a selection that should be made on the field. The modifier is enclosed by angled brackets: < >

For example:

- `sum ( {<Year = {2015}>} sales )`
- `count ( {1<Country = {Germany}>} distinct OrderID )`
- `sum ( {<Year = {2015}, Country = {Germany}>} sales )`

## Element sets

An element set can be defined using the following:

- A list of values
- A search
- A reference to another field
- A set function

If the element set definition is omitted, the set modifier will clear any selection in this field. For example:

```
sum( {<Year = >} sales )
```



## Examples: Chart expressions for set modifiers based on element sets

Examples - chart expressions

**Load script**

Load the following data as an inline load in the data load editor to create the chart expression examples below.

```
MyTable:
Load * Inline [
Country, Year, Sales
Argentina, 2014, 66295.03
Argentina, 2015, 140037.89
Austria, 2014, 54166.09
Austria, 2015, 182739.87
Belgium, 2014, 182766.87
Belgium, 2015, 178042.33
Brazil, 2014, 174492.67
Brazil, 2015, 2104.22
Canada, 2014, 101801.33
Canada, 2015, 40288.25
Denmark, 2014, 45273.25
Denmark, 2015, 106938.41
Finland, 2014, 107565.55
Finland, 2015, 30583.44
France, 2014, 115644.26
France, 2015, 30696.98
Germany, 2014, 8775.18
Germany, 2015, 77185.68
];
```

**Chart expressions**

Create a table in a Qlik Sense sheet with the following chart expressions.

Table - Set modifiers based on element sets

Country	Sum(Sales)	Sum ({1<Country= {Belgium}>} Sales)	Sum ({1<Country= {"*A*"}>} Sales)	Sum ({1<Country= {"A*"}>} Sales)	Sum ({1<Year= {\$(=Max (Year))}>} Sales)
Totals	1645397.3	360809.2	1284588.1	443238.88	788617.07
Argentina	206332.92	0	206332.92	206332.92	140037.89
Austria	236905.96	0	236905.96	236905.96	182739.87
Belgium	360809.2	360809.2	0	0	178042.33

Country	Sum(Sales)	Sum ({1<Country={Belgium}>} Sales)	Sum ({1<Country={ "*A*"}>} Sales)	Sum ({1<Country={ "A*"}>} Sales)	Sum ({1<Year={ \$(=Max (Year))>} Sales)
Brazil	176596.89	0	176596.89	0	2104.22
Canada	142089.58	0	142089.58	0	40288.25
Denmark	152211.66	0	152211.66	0	106938.41
Finland	138148.99	0	138148.99	0	30583.44
France	146341.24	0	146341.24	0	30696.98
Germany	85960.86	0	85960.86	0	77185.68

### Explanation

- Dimensions:
  - Country
- Measures:
  - sum(Sales)  
Sum sales with no set expression.
  - sum({1<Country={Belgium}>}Sales)  
Select Belgium, and then sum corresponding sales.
  - sum({1<Country={"\*A\*"}>}Sales)  
Select all countries that have an A, and then sum corresponding sales.
  - sum({1<Country={"A\*"}>}Sales)  
Select all countries that begin with an A, and then sum corresponding sales.
  - sum({1<Year={\$(=Max(Year))>}Sales)  
Calculate the Max(Year), which is 2015, and then sum corresponding sales.

Set modifiers based on element sets

My new sheet

Country	Sum (Sales)	Sum( {1<Country = {Belgium}>} Sales )	Sum( {1<Country = {"*A*"}>} Sales )	Sum( {1<Country = {"A*"}>} Sales )	Sum( {1<Year = {\$(=Max(Year))}>} Sales )
<b>Totals</b>	<b>1645397.3</b>	<b>360809.2</b>	<b>1284588.1</b>	<b>443238.88</b>	<b>788617.07</b>
Argentina	206332.92	0	206332.92	206332.92	140037.89
Austria	236905.96	0	236905.96	236905.96	182739.87
Belgium	360809.2	360809.2	0	0	178042.33
Brazil	176596.89	0	176596.89	0	2104.22
Canada	142089.58	0	142089.58	0	40288.25
Denmark	152211.66	0	152211.66	0	106938.41
Finland	138148.99	0	138148.99	0	30583.44
France	146341.24	0	146341.24	0	30696.98
Germany	85960.86	0	85960.86	0	77185.68

## Listed values

The most common example of an element set is one that is based on a list of field values enclosed in curly brackets. For example:

- `{<Country = {Canada, Germany, Singapore}>}`
- `{<Year = {2015, 2016}>}`

The inner curly brackets define the element set. The individual values are separated by commas.

## Quotes and case sensitivity

If the values contain blanks or special characters, the values need to be quoted. Single quotes will be a literal, case-sensitive match with a single field value. Double quotes imply a case-insensitive match with one or several field values. For example:

- `<Country = {'New Zealand'}>`  
Matches new zealand only.
- `<Country = {"New Zealand"}>`  
Matches New Zealand, NEW ZEALAND, and new zealand.

Dates must be enclosed in quotes and use the date format of the field in question. For example:

- `<ISO_Date = {'2021-12-31'}>`
- `<US_Date = {'12/31/2021'}>`
- `<UK_Date = {'31/12/2021'}>`

Double quotes can be substituted by square brackets or by grave accents.

## Searches

Element sets can also be created through searches. For example:

- `<Country = {"C*"}>`
- `<Ingredient = {"*garlic*"}>`
- `<Year = {">2015"}>`
- `<Date = {">12/31/2015"}>`

Wildcards can be used in text searches: An asterisk (\*) represents any number of characters, and a question mark (?) represents a single character. Relational operators can be used to define numeric searches.

You should always use double quotes for searches. Searches are case-insensitive.

### Dollar expansions

Dollar expansions are needed if you want to use a calculation inside your element set. For example, if you want to look at the last possible year only, you can use:

```
<Year = {$ (=Max(Year))}>
```

### Selected values in other fields

Modifiers can be based on the selected values of another field. For example:

```
<OrderDate = DeliveryDate>
```

This modifier will take the selected values from `DeliveryDate` and apply those as a selection on `OrderDate`. If there are many distinct values – more than a couple of hundred – then this operation is CPU intensive and should be avoided.

### Element set functions

The element set can also be based on the set functions `P()` (possible values) and `E()` (excluded values).

For example, if you want to select countries where the product cap has been sold, you can use:

```
<Country = P({1<Product={Cap}>} Country)>
```

Similarly, if you want to pick out the countries where the product cap has not been sold, you can use:

```
<Country = E({1<Product={Cap}>} Country)>
```

### Set modifiers with searches

You can create element sets through searches with set modifiers.

For example:

- `<Country = {"C*"}>`
- `<Year = {">2015"}>`
- `<Ingredient = {"*garlic*"}>`

Searches should always be enclosed in double quotes, square brackets or grave accents. You can use a list with a mixture of literal strings (single quotes) and searches (double quotes). For example:

```
<Product = {'Nut', '*Bolt', Washer}>
```

### Text searches

Wildcards and other symbols can be used in text searches:

- An asterisk (\*) will represent any number of characters.
- A question mark (?) will represent a single character.
- A circumflex accent (^) will mark the beginning of a word.

For example:

- `<Country = {"c*", "*land"}>`  
Match all countries beginning with a c or ending with land.
- `<Country = {"^z*"}>`  
This will match all countries that have a word beginning with z, such as New Zealand.

### Numeric searches

You can make numeric searches using these relational operators: >, >=, <, <=

A numeric search always begins with one of these operators. For example:

- `<Year = {">2015"}>`  
Match 2016 and subsequent years.
- `<Date = {">=1/1/2015<1/1/2016"}>`  
Match all dates during 2015. Note the syntax for describing a time range between two dates. The date format needs to match the date format of the field in question.

### Expression searches

You can use expression searches to make more advanced searches. An aggregation is then evaluated for each field value in the search field. All values for which the search expression returns true are selected.

An expression search always begins with an equals sign: =

For example:

```
<Customer = {"=Sum(Sales)>1000"}>
```

This will return all customers with a sales value greater than 1000. `sum(sales)` is calculated on the current selection. This means that if you have a selection in another field, such as the `Product` field, you will get the customers that fulfilled the sales condition for the selected products only.

If you want the condition to be independent of the selection, you need to use set analysis inside the search string. For example:

```
<Customer = {"=Sum({1} Sales)>1000"}>
```

The expressions after the equals sign will be interpreted as a boolean value. This means that if it evaluates to something else, any non-zero number will be interpreted as true, while zero and strings are interpreted as false.

### Quotes

Use quotation marks when the search strings contain blanks or special characters. Single quotes imply a literal, case-sensitive match with a single field value. Double quotes imply a case insensitive search that potentially matches multiple field values.

For example:

- `<Country = {'New Zealand'}>`  
Match New Zealand only.
- `<Country = {"New Zealand"}>`  
Match New Zealand, NEW ZEALAND, and new Zealand

Double quotes can be substituted by square brackets or by grave accents.



*In previous versions of Qlik Sense, there was no distinction between single quotes and double quotes, and all quoted strings were treated as searches. To maintain backward compatibility, apps created with older versions of Qlik Sense will continue to work as they did in previous versions. Apps created with Qlik Sense November 2017 or later will respect the difference between the two types of quotes.*

### Examples: Chart expressions for set modifiers with searches

Examples - chart expressions

#### Load script

Load the following data as an inline load in the data load editor to create the chart expression examples below.

```
MyTable:
Load
Year(Date) as Year,
Date#(Date,'YYYY-MM-DD') as ISO_Date,
Date(Date#(Date,'YYYY-MM-DD'),'M/D/YYYY') as US_Date,
Country, Product, Amount
Inline
[Date, Country, Product, Amount
2018-02-20, Canada, washer, 6
2018-07-08, Germany, Anchor bolt, 10
2018-07-14, Germany, Anchor bolt, 3
2018-08-31, France, Nut, 2
2018-09-02, Czech Republic, Bolt, 1
2019-02-11, Czech Republic, Bolt, 3
2019-07-31, Czech Republic, washer, 6
```

2020-03-13, France, Anchor bolt, 1  
 2020-07-12, Canada, Anchor bolt, 8  
 2020-09-16, France, washer, 1];

### Example 1: Chart expressions with text searches

Create a table in a Qlik Sense sheet with the following chart expressions.

Table - Set modifiers with text searches

Country	Sum (Amount)	Sum({<Country= {"C*"}>} Amount)	Sum({<Country= {"*^R*"}>} Amount)	Sum({<Product= {"*bolt*"}>} Amount)
<b>Totals</b>	<b>41</b>	<b>24</b>	<b>10</b>	<b>26</b>
Canada	14	14	0	8
Czech Republic	10	10	10	4
France	4	0	0	1
Germany	13	0	0	13

### Explanation

- Dimensions:
  - Country
- Measures:
  - Sum(Amount)  
Sum Amount with no set expression.
  - Sum({<Country={"C\*"}>}Amount)  
Sum Amount for all countries that start with c, such as canada and czech republic.
  - Sum({<Country={"\*^R\*"}>}Amount)  
Sum Amount for all countries that have a word that starts with r, such as czech republic.
  - Sum({<Product={"\*bolt\*"}>}Amount)  
Sum Amount for all products that contain the string bolt, such as bolt and Anchor bolt.

Set modifiers with text searches

My new sheet

Country	Sum (Amount)	Sum({<Country={"C*"}>} Amount)	Sum({<Country={"**R*"}>} Amount)	Sum({<Product={"*bolt*"}>} Amount)
<b>Totals</b>	<b>41</b>	<b>24</b>	<b>10</b>	<b>26</b>
Canada	14	14	0	8
Czech Republic	10	10	10	4
France	4	0	0	1
Germany	13	0	0	13

### Example 2: Chart expressions with numeric searches

Create a table in a Qlik Sense sheet with the following chart expressions.

Table - Set modifiers with numeric searches

Country	Sum (Amount)	Sum({<Year={"}>2019"}>} Amount)	Sum({<ISO_Date={"}>=2019-07-01"}>} Amount)	Sum({<US_Date={"}>=4/1/2018<=12/31/2018"}>} Amount)
<b>Totals</b>	<b>41</b>	<b>10</b>	<b>16</b>	<b>16</b>
Canada	14	8	8	0
Czech Republic	10	0	6	1
France	4	2	2	2
Germany	13	0	0	13

### Explanation

- Dimensions:
  - Country
- Measures:
  - Sum(Amount)  
Sum Amount with no set expression.
  - Sum({<Year={"}>2019"}>}Amount)  
Sum Amount for all years after 2019.
  - Sum({<ISO\_Date={"}>=2019-07-01"}>}Amount)  
Sum Amount for all dates on or after 2019-07-01. The format of the date in the search must match the format of the field.
  - Sum({<US\_Date={"}>=4/1/2018<=12/31/2018"}>}Amount)



Sum Amount for all dates from 4/1/2018 to 12/31/2018, including the start and end dates. The format of the dates in the search must match the format of the field.

*Set modifiers with numeric searches*

My new sheet

Country	Sum (Amount)	Sum({<Year=[">2019"]>} Amount)	Sum({<ISO_Date=[">2019-07-01"]>} Amount)	Sum({<US_Date=[">=4/1/2018<=12/31/2018"]>} Amount)
Totals	41	10	16	16
Canada	14	8	8	0
Czech Republic	10	0	6	1
France	4	2	2	2
Germany	13	0	0	13

### Example 3: Chart expressions with expression searches

Create a table in a Qlik Sense sheet with the following chart expressions.

Table - Set modifiers with expression searches

Country	Sum (Amount)	Sum({<Country={"=Sum (Amount)>10"}>} Amount)	Sum({<Country={"=Count(distinct Product)=1"}>} Amount)	Sum({<Product={"=Count (Amount)>3"}>} Amount)
Totals	41	27	13	22
Canada	14	14	0	8
Czech Republic	10	0	0	0
France	4	0	0	1
Germany	13	13	13	13

### Explanation

- Dimensions:
  - Country
- Measures:
  - Sum(Amount)  
Sum Amount with no set expression.
  - Sum({<Country={"=Sum(Amount)>10"}>} Amount)  
Sum Amount for all countries that have an aggregated sum of Amount greater than 10.
  - Sum({<Country={"=Count(distinct Product)=1"}>} Amount)  
Sum Amount for all countries that are associated with exactly one distinct product.

- `Sum({<Product={"=Count(Amount)>3"}>}Amount)`  
Sum Amount for all countries that have more than three transactions in the data.

Set modifiers with expression searches

My new sheet				
Country	Sum (Amount)	Sum({<Country={"=Sum(Amount)>10"}>} Amount)	Sum({<Country={"=Count(distinct Product)=1"}>} Amount)	Sum({<Product={"=Count(Amount)>3"}>} Amount)
Totals	41	27	13	22
Canada	14	14	0	8
Czech Republic	10	0	0	0
France	4	0	0	1
Germany	13	13	13	13


Examples	Results
<code>sum( {\$-1&lt;Product = {"*Internal*", "*Domestic*"}&gt;} Sales )</code>	Returns the sales for current selection, excluding transactions pertaining to products with the string 'Internal' or 'Domestic' in the product name.
<code>sum( {\$&lt;Customer = {"=Sum ({1&lt;Year = {2007}&gt;} Sales ) &gt; 1000000"}&gt;} Sales )</code>	Returns the sales for current selection, but with a new selection in the 'Customer' field: only customers who during 2007 had a total sales of more than 1000000.

### Set modifiers with dollar-sign expansions

Dollar-sign expansions are constructs that are calculated before the expression is parsed and evaluated. The result is then injected into the expression instead of the `$(...)`. The calculation of the expression is then made using the result of the dollar expansion.

The expression editor shows a dollar expansion preview so that you can verify what your dollar-sign expansion evaluates to.

*Dollar-sign expansion preview in expression editor*



Use dollar-sign expansions when you want to use a calculation inside your element set.

For example, if you want to look at the last possible year only, you can use the following construction:

```
<Year = {$(=Max(Year))}>
```

`Max(Year)` is calculated first, and the result would be injected in the expression instead of the `$(...)`.

The result after the dollar expansion will be an expression such as the following:

```
<Year = {2021}>
```

The expression inside the dollar expansion is calculated based on the current selection. This means that if you have a selection in another field, the result of the expression will be affected.

If you want the calculation to be independent of the selection, use set analysis inside the dollar expansion. For example:

```
<Year = {$(=Max({1} Year))}>
```

### Strings

When you want the dollar expansion to result in a string, normal quoting rules apply. For example:

```
<Country = {'$(=FirstSortedValue(Country,Date))'}>
```

The result after the dollar expansion will be an expression such as the following:

```
<Country = {'New Zealand'}>
```

You will get a syntax error if you do not use the quotation marks.

### Numbers

When you want the dollar expansion to result in a number, ensure that the expansion gets the same formatting as the field. This means that you sometimes need to wrap the expression in a formatting function.

For example:

```
<Amount = {$(=Num(Max(Amount), '###0.00'))}>
```

The result after the dollar expansion will be an expression such as the following:

```
<Amount = {12362.00}>
```

Use a hash to force the expansion to always use decimal point and no thousand separator . For example:

```
<Amount = {$(#=Max(Amount))}>
```

### Dates

When you want the dollar expansion to result in a date, ensure that the expansion has the correct formatting. This means that you sometimes need to wrap the expression in a formatting function.

For example:

```
<Date = {'$ (=Date(Max(Date)))'}>
```

The result after the dollar expansion will be an expression such as the following:

```
<Date = {'12/31/2015'}>
```

Just as with strings, you need to use the correct quotes.

A common use case is that you want your calculation to be limited to the last month (or year). Then you can use a numeric search in combination with the `AddMonths()` function.

For example:

```
<Date = {">=$ (=AddMonths(Today(), -1))"}>
```

The result after the dollar expansion will be an expression such as the following:

```
<Date = {">=9/31/2021"}>
```

This will pick out all events that have occurred the last month.

### Example: Chart expressions for set modifiers with dollar-sign expansions

Example - chart expressions

#### Load script

Load the following data as an inline load in the data load editor to create the chart expression examples below.

```
Let vToday = Today();
MyTable:
Load
Year(Date) as Year,
Date#(Date, 'YYYY-MM-DD') as ISO_Date,
Date(Date#(Date, 'YYYY-MM-DD'), 'M/D/YYYY') as US_Date,
Country, Product, Amount
Inline
[Date, Country, Product, Amount
2018-02-20, Canada, washer, 6
```

2018-07-08, Germany, Anchor bolt, 10  
 2018-07-14, Germany, Anchor bolt, 3  
 2018-08-31, France, Nut, 2  
 2018-09-02, Czech Republic, Bolt, 1  
 2019-02-11, Czech Republic, Bolt, 3  
 2019-07-31, Czech Republic, Washer, 6  
 2020-03-13, France, Anchor bolt, 1  
 2020-07-12, Canada, Anchor bolt, 8  
 2021-10-15, France, washer, 1];

### Chart expressions with dollar-sign expansions

Create a table in a Qlik Sense sheet with the following chart expressions.

Table - Set modifiers with dollar-sign expansions

Country	Sum (Amount)	Sum({<US_Date= '\$(vToday)'}>} Amount)	Sum({<ISO_Date= '\$(=Date(Min(ISO_ Date), 'YYYY-MM- DD'))'>} Amount)	Sum({<US_Date= '>=\$(=AddYears (Max(US_Date), - 1))'>} Amount)
<b>Totals</b>	<b>41</b>	<b>1</b>	<b>6</b>	<b>1</b>
Canada	14	0	6	0
Czech Republic	10	0	0	0
France	4	1	0	1
Germany	13	0	0	0

### Explanation

- Dimensions:
  - Country
- Measures:
  - Sum(Amount)  
Sum Amount with no set expression.
  - Sum({<US\_Date={'\$(vToday)'}>}Amount)  
Sum Amount for all records where the us\_date is the same as in the variable vToday.
  - Sum({<ISO\_Date={'\$(=Date(Min(ISO\_Date), 'YYYY-MM-DD'))'>}Amount)  
Sum Amount for all records where the iso\_date is the same as the first (smallest) possible iso\_date. The date() function is needed to ensure that the format of the date matches that of the field.
  - Sum({<US\_Date={'>=\$(=AddYears(Max(US\_Date), -1))'>}Amount)  
Sum Amount for all records that have a us\_date after or on the date a year before the latest (largest) possible us\_date. The Addyears() function will return a date in the format specified by the variable dateFormat, and this needs to match the format of the field us\_date.

Set modifiers with dollar-sign expansions

My new sheet

Country	Sum (Amount)	Sum( {<US_Date=[S(vToday)]>} Amount )	Sum( {<ISO_Date=[S(=Date(Min(ISO_Date),YYYY-MM-DD))]>} Amount )	Sum( {<US_Date=[S(=AddYears(Max(US_Date),-1))]>} Amount )
Totals	41	1	6	1
Canada	14	0	6	0
Czech Republic	10	0	0	0
France	4	1	0	1
Germany	13	0	0	0

Examples	Results
sum( {<Year = {\$(#vLastYear)}>} Sales )	Returns the sales for the previous year in relation to current selection. Here, a variable vLastYear containing the relevant year is used in a dollar-sign expansion.
sum( {<Year = {\$(#=Only(Year)-1)}>} Sales )	Returns the sales for the previous year in relation to current selection. Here, a dollar-sign expansion is used to calculate previous year.

### Set modifiers with set operators

Set operators are used to include, exclude, or intersect different element sets. They combine the different methods to define element sets.

The operators are the same as those used for set identifiers.

#### Operators

Operator	Description
+	Union. This binary operation returns a set consisting of the records or elements that belong to any of the two set operands.
-	Exclusion. This binary operation returns a set consisting of the records or elements that belong to the first but not the other of the two set operands. Also, when used as a unary operator, it returns the complement set.
*	Intersection. This binary operation returns a set consisting of the records or elements that belong to both set operands.
/	Symmetric difference (XOR). This binary operation returns a set consisting of the records or elements that belong to either, but not both set operands.

For example, the following two modifiers define the same set of field values:

- <Year = {1997, "20\*"}>
- <Year = {1997} + {"20\*"}>

Both expressions select 1997 and the years that begin with 20. In other words, this is the union of the two conditions.

Set operators also allow for more complex definitions. For example:

```
<Year = {1997, "20*"} - {2000}>
```

This expression will select the same years as those above, but in addition exclude year 2000.

.

Examples: Chart expressions for set modifiers with set operators

Examples - chart expressions

### Load script

Load the following data as an inline load in the data load editor to create the chart expression examples below.

```
MyTable:
Load
Year(Date) as Year,
Date#(Date,'YYYY-MM-DD') as ISO_Date,
Date(Date#(Date,'YYYY-MM-DD'),'M/D/YYYY') as US_Date,
Country, Product, Amount
Inline
[Date, Country, Product, Amount
2018-02-20, Canada, washer, 6
2018-07-08, Germany, Anchor bolt, 10
2018-07-14, Germany, Anchor bolt, 3
2018-08-31, France, Nut, 2
2018-09-02, Czech Republic, Bolt, 1
2019-02-11, Czech Republic, Bolt, 3
2019-07-31, Czech Republic, washer, 6
2020-03-13, France, Anchor bolt, 1
2020-07-12, Canada, Anchor bolt, 8
2020-09-16, France, washer, 1];
```

### Chart expressions

Create a table in a Qlik Sense sheet with the following chart expressions.

Table - Set modifiers with set operators

Country	Sum (Amount)	Sum({<Year= {">2018"}- {2020}>} Amount)	Sum ({<Country=- {Germany}>} Amount)	Sum({<Country= {Germany}+P({<Product= {Nut}>}Country)>} Amount)
<b>Totals</b>	<b>41</b>	<b>9</b>	<b>28</b>	<b>17</b>
Canada	14	0	14	0
Czech Republic	10	9	10	0
France	4	0	4	4
Germany	13	0	0	13

### Explanation

- Dimensions:
  - Country
- Measures:
  - Sum(Amount)  
Sum Amount with no set expression.
  - Sum({<Year={">2018"}-{2020}>}Amount)  
Sum Amount for all years after 2018, except 2020.
  - Sum({<Country=- {Germany}>}Amount)  
Sum Amount for all countries except germany. Note the unary exclusion operator.
  - Sum({<Country={Germany}+P({<Product={Nut}>}Country)>}Amount)  
Sum Amount for germany and all countries associated with the product nut.

Set modifiers with set operators

My new sheet

Country	Sum (Amount)	Sum({<Year={">2018"}- {2020}>} Amount)	Sum({<Country=- {Germany}>} Amount)	Sum({<Country={Germany}+P({<Product= {Nut}>}Country)>} Amount)
<b>Totals</b>	<b>41</b>	<b>9</b>	<b>28</b>	<b>17</b>
Canada	14	0	14	0
Czech Republic	10	9	10	0
France	4	0	4	4
Germany	13	0	0	13



Examples	Results
<pre>sum( {\$&lt;Product = Product + {OurProduct1} - {OurProduct2} &gt;} Sales )</pre>	Returns the sales for the current selection, but with the product "OurProduct1" added to the list of selected products and "OurProduct2" removed from the list of selected products.
<pre>sum( {\$&lt;Year = Year + {"20*",1997} - {2000} &gt;} Sales )</pre>	<p>Returns the sales for the current selection but with additional selections in the field "Year": 1997 and all that begin with "20" – however, not 2000.</p> <p>Note that if 2000 is included in the current selection, it will still be included after the modification.</p>
<pre>sum( {\$&lt;Year = (Year + {"20*",1997}) - {2000} &gt;} Sales )</pre>	Returns almost the same as above, but here 2000 will be excluded, also if it initially is included in the current selection. The example shows the importance of sometimes using brackets to define an order of precedence.
<pre>sum( {\$&lt;Year = {"*"} - {2000}, Product = {"*bearing*"} &gt;} Sales )</pre>	Returns the sales for the current selection but with a new selection in "Year": all years except 2000; and only for products containing the string 'bearing'.

### Set modifiers with implicit set operators

The standard way to write selections in a set modifier is to use an equals sign. For example:

```
Year = {">2015"}
```

The expression to the right of the equals sign in the set modifier is called an element set. It defines a set of distinct field values, in other words a selection.

This notation defines a new selection, disregarding the current selection in the field. So, if the set identifier contains a selection in this field, the old selection will be replaced by the one in the element set.

When you want to base your selection on the current selection in the field, you need to use a different expression

For example, if you want to respect the old selection, and add the requirement that the year is after 2015, you can write the following:

```
Year = Year * {">2015"}
```

The asterisk is a set operator defining an intersection, so you will get the intersection between the current selection in `Year`, and the additional requirement that the year be after 2015. An alternative way to write this is the following:

```
Year *= {">2015"}
```

That is, the assignment operator (`*=`) implicitly defines an intersection.

Similarly, implicit unions, exclusions and symmetric differences can be defined using the following:  
+=, -=, /=

Examples: Chart expressions for set modifiers with implicit set operators

Examples - chart expressions

### Load script

Load the following data as an inline load in the data load editor to create the chart expression examples below.

```
MyTable:
Load
Year(Date) as Year,
Date#(Date,'YYYY-MM-DD') as ISO_Date,
Date(Date#(Date,'YYYY-MM-DD'),'M/D/YYYY') as US_Date,
Country, Product, Amount
Inline
[Date, Country, Product, Amount
2018-02-20, Canada, Washer, 6
2018-07-08, Germany, Anchor bolt, 10
2018-07-14, Germany, Anchor bolt, 3
2018-08-31, France, Nut, 2
2018-09-02, Czech Republic, Bolt, 1
2019-02-11, Czech Republic, Bolt, 3
2019-07-31, Czech Republic, Washer, 6
2020-03-13, France, Anchor bolt, 1
2020-07-12, Canada, Anchor bolt, 8
2020-09-16, France, Washer, 1];
```

### Chart expressions with implicit set operators

Create a table in a Qlik Sense sheet with the following chart expressions.

Select canada and czech republic from a list of countries.

Table - Chart expressions with implicit set operators

Country	Sum (Amount)	Sum({<Country*= {Canada}>>} Amount)	Sum({<Country-= {Canada}>>} Amount)	Sum({<Country+= {France}>>} Amount)
<b>Totals</b>	<b>24</b>	<b>14</b>	<b>10</b>	<b>28</b>
Canada	14	14	0	14
Czech Republic	10	0	10	10
France	0	0	0	4

### Explanation

- Dimensions:
  - Country
- Measures:
  - Sum(Amount)  
Sum Amount for the current selection. Note that only Canada and Czech Republic have non-zero values.
  - Sum({<Country\*={Canada}>}Amount)  
Sum Amount for the current selection, intersected with the requirement that the country be Canada. If Canada is not part of the user selection, the set expression returns an empty set, and the column will have 0 on all rows.
  - Sum({<Country-={Canada}>}Amount)  
Sum Amount for the current selection, but first exclude Canada from the country selection. If Canada is not part of the user selection, the set expression will not change any numbers.
  - Sum({<Country+={France}>}Amount)  
Sum Amount for the current selection, but first add France to the country selection. If France is already part of the user selection, the set expression will not change any numbers.

Set modifiers with implicit set operators

Country		2 of 4																								
My new sheet																										
<div style="border: 1px solid #ccc; padding: 5px;"> <div style="border-bottom: 1px solid #ccc; padding: 2px 5px;"> <span style="font-size: 1.2em;">Q</span> Country           </div> <div style="padding: 2px 5px;"> <span style="background-color: #008000; color: white; padding: 2px 5px;">Canada</span> ✓           </div> <div style="padding: 2px 5px;"> <span style="background-color: #008000; color: white; padding: 2px 5px;">Czech Republic</span> ✓           </div> <div style="padding: 2px 5px;"> <span style="background-color: #f0f0f0; padding: 2px 5px;">France</span> </div> <div style="padding: 2px 5px;"> <span style="background-color: #f0f0f0; padding: 2px 5px;">Germany</span> </div> </div>	<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 15%;">Country</th> <th style="width: 15%;">Sum (Amount)</th> <th style="width: 20%;">Sum({&lt;Country*={Canada}&gt;} Amount)</th> <th style="width: 20%;">Sum({&lt;Country-={Canada}&gt;} Amount)</th> <th style="width: 20%;">Sum({&lt;Country+={France}&gt;} Amount)</th> </tr> </thead> <tbody> <tr> <td><b>Totals</b></td> <td><b>24</b></td> <td><b>14</b></td> <td><b>10</b></td> <td><b>28</b></td> </tr> <tr> <td>Canada</td> <td>14</td> <td>14</td> <td>0</td> <td>14</td> </tr> <tr> <td>Czech Republic</td> <td>10</td> <td>0</td> <td>10</td> <td>10</td> </tr> <tr> <td>France</td> <td>0</td> <td>0</td> <td>0</td> <td>4</td> </tr> </tbody> </table>	Country	Sum (Amount)	Sum({<Country*={Canada}>} Amount)	Sum({<Country-={Canada}>} Amount)	Sum({<Country+={France}>} Amount)	<b>Totals</b>	<b>24</b>	<b>14</b>	<b>10</b>	<b>28</b>	Canada	14	14	0	14	Czech Republic	10	0	10	10	France	0	0	0	4
Country	Sum (Amount)	Sum({<Country*={Canada}>} Amount)	Sum({<Country-={Canada}>} Amount)	Sum({<Country+={France}>} Amount)																						
<b>Totals</b>	<b>24</b>	<b>14</b>	<b>10</b>	<b>28</b>																						
Canada	14	14	0	14																						
Czech Republic	10	0	10	10																						
France	0	0	0	4																						

Examples	Results
<code>sum( {\$&lt;Product += {OurProduct1, OurProduct2} &gt;} Sales )</code>	Returns the sales for the current selection, but using an implicit union to add the products 'OurProduct1' and 'OurProduct2' to the list of selected products.

Examples	Results
<code>sum( {\$&lt;Year += {"20*",1997} - {2000} &gt;} Sales )</code>	<p>Returns the sales for the current selection but using an implicit union to add a number of years in the selection: 1997 and all that begin with "20" – however, not 2000.</p> <p>Note that if 2000 is included in the current selection, it will still be included after the modification. Same as <code>&lt;Year=Year + ({"20*",1997} - {2000})&gt;</code>.</p>
<code>sum( {\$&lt;Product *= {OurProduct1} &gt;} Sales )</code>	<p>Returns the sales for the current selection, but only for the intersection of currently selected products and the product OurProduct1.</p>

### Set modifiers using set functions

Sometimes you need to define a set of field values using a nested set definition. For example, you may want to select all customers that have bought a specific product, without selecting the product.

In such cases, use the element set functions `P()` and `E()`. These return the element sets of possible values and excluded values of a field, respectively. Inside the brackets, you can specify the field in question, and a set expression that defines the scope. For example:

```
P({1<Year = {2021}>} Customer)
```

This will return the set of customers that had transactions in 2021. You can then use this in a set modifier. For example:

```
Sum({<Customer = P({1<Year = {2021}>} Customer)>} Amount)
```

This set expression will select these customers, but it will not restrict the selection to 2021.

These functions cannot be used in other expressions.

Additionally, only natural sets can be used inside the element set functions. That is, a set of records that can be defined by a simple selection.

For example, the set given by `{1-$}` cannot always be defined through a selection, and is therefore not a natural set. Using these functions on non-natural sets will return unexpected results.

### Examples: Chart expressions for set modifiers using set functions

Examples - chart expressions

#### Load script

Load the following data as an inline load in the data load editor to create the chart expression examples below.

```

MyTable:
Load
Year(Date) as Year,
Date#(Date,'YYYY-MM-DD') as ISO_Date,
Date(Date#(Date,'YYYY-MM-DD'),'M/D/YYYY') as US_Date,
Country, Product, Amount
Inline
[Date, Country, Product, Amount
2018-02-20, Canada, washer, 6
2018-07-08, Germany, Anchor bolt, 10
2018-07-14, Germany, Anchor bolt, 3
2018-08-31, France, Nut, 2
2018-09-02, Czech Republic, Bolt, 1
2019-02-11, Czech Republic, Bolt, 3
2019-07-31, Czech Republic, Washer, 6
2020-03-13, France, Anchor bolt, 1
2020-07-12, Canada, Anchor bolt, 8
2020-09-16, France, washer, 1];

```

### Chart expressions

Create a table in a Qlik Sense sheet with the following chart expressions.

Table - Set modifiers using set functions

Country	Sum (Amount)	Sum({<Country=P {<Year={2019}>}Country>} Amount)	Sum({<Product=P {<Year={2019}>}Product>} Amount)	Sum({<Country=E {<Product=Washer>}Country>} Amount)
<b>Totals</b>	<b>41</b>	<b>10</b>	<b>17</b>	<b>13</b>
Canada	14	0	6	0
Czech Republic	10	10	10	0
France	4	0	1	0
Germany	13	0	0	13

### Explanation

- Dimensions:
  - Country
- Measures:
  - Sum(Amount)  
Sum Amount with no set expression.
  - Sum({<Country=P({<Year={2019}>} Country)>} Amount)  
Sum Amount for the countries that are associated with year 2019. It will however not limit the calculation to 2019.

## 6 Chart expressions

- `Sum({<Product=P({<Year={2019}>} Product)>} Amount)`  
Sum Amount for the products that are associated with year 2019. It will however not limit the calculation to 2019.
- `Sum({<Country=E({<Product={Washer}>} Country)>} Amount)`  
Sum Amount for the countries that are not associated with the product washer.

Set modifiers using set functions

My new sheet

Country	Sum (Amount)	Sum({<Country=P({<Year={2019}>} Country)>} Amount)	Sum({<Product=P({<Year={2019}>} Product)>} Amount)	Sum({<Country=E({<Product={Washer}>} Country)>} Amount)
<b>Totals</b>	<b>41</b>	<b>10</b>	<b>17</b>	<b>13</b>
Canada	14	0	6	0
Czech Republic	10	10	10	0
France	4	0	1	0
Germany	13	0	0	13

Examples	Results
<code>sum({&lt;Customer = P({1&lt;Product={ 'Shoe'&gt;} Customer)&gt;} Sales )</code>	Returns the sales for current selection, but only those customers that ever have bought the product 'Shoe'. The element function P ( ) here returns a list of possible customers; those that are implied by the selection 'Shoe' in the field Product.
<code>sum({&lt;Customer = P({1&lt;Product={ 'Shoe'&gt;}&gt;} Sales )</code>	Same as above. If the field in the element function is omitted, the function will return the possible values of the field specified in the outer assignment.
<code>sum({&lt;Customer = P({1&lt;Product={ 'Shoe'&gt;} Supplier)&gt;} Sales )</code>	Returns the sales for current selection, but only those customers that ever have supplied the product 'Shoe', that is, the customer is also a supplier. The element function P ( ) here returns a list of possible suppliers; those that are implied by the selection 'Shoe' in the field Product. The list of suppliers is then used as a selection in the field Customer.
<code>sum({&lt;Customer = E({1&lt;Product={ 'Shoe'&gt;}&gt;} Sales )</code>	Returns the sales for current selection, but only those customers that never bought the product 'Shoe'. The element function E ( ) here returns the list of excluded customers; those that are excluded by the selection 'Shoe' in the field Product.

### Inner and outer set expressions

Set expressions can be used inside and outside aggregation functions, and are enclosed in curly brackets.

When you use a set expression inside an aggregation function, it can look like this:

#### Example: Inner set expression

```
sum( {<Year={2021}>} Sales )
```

Use a set expression outside the aggregation function if you have expressions with multiple aggregations and want to avoid writing the same set expression in every aggregation function.

If you use an outer set expression, it must be placed at the beginning of the scope.

#### Example: Outer set expression

```
{<Year={2021}>} sum(Sales) / count(distinct Customer)
```

If you use a set expression outside the aggregation function, you can also apply it on existing master measures.

#### Example: Outer set expression applied to master measure

```
{<Year={2021}>} [Master Measure]
```

A set expression used outside aggregation functions affects the entire expression, unless it is enclosed in brackets then the brackets define the scope. In the lexical scoping example below, the set expression is only applied to the aggregation inside the brackets.

#### Example: Lexical scoping

```
( {<Year={2021}>} sum(Amount) / count(distinct Customer) ) - Avg(CustomerSales)
```

### Rules

#### Lexical scope

The set expression affects the entire expression, unless it is enclosed in brackets. If so, the brackets define the lexical scope.

#### Position

The set expression must be placed in the beginning of the lexical scope.

#### Context

The context is the selection that is relevant for the expression. Traditionally, the context has always been the default state of current selection. But if an object is set to an alternate state, the context is the alternate state of the current selection.

You can also define a context in the form of an outer set expression.

### Inheritance

Inner set expressions have precedence over outer set expressions. If the inner set expression contains a set identifier, it replaces the context. Otherwise, the context and the set expression will be merged.

- `{<SetExpression>}` - overrides the outer set expression
- `{<SetExpression>}` - is merged with the outer set expression

### Element set assignment

The element set assignment determines how the two selections are merged. If a normal equals sign is used, the selection in the inner set expression has precedence. Otherwise, the implicit set operator will be used.

- `{<Field={value}>}` - this inner selection replaces any outer selection in "Field".
- `{<Field+={value}>}` - this inner selection is merged with the outer selection in "Field", using the union operator.
- `{<Field*={value}>}` - this inner selection is merged with the outer selection in "Field", using the intersection operator.

### Inheritance in multiple steps

The inheritance can occur in multiple steps. Examples:

- Current Selection → `Sum(Amount)`  
The aggregation function will use the context, which here is the current selection.
- Current Selection → `{<Set1>} Sum(Amount)`  
`set1` will inherit from current selection, and the result will be the context for the aggregation function.
- Current Selection → `{<set1>} ({<Set2>} Sum(Amount))`  
`set2` will inherit from `set1`, which in turn inherits from current selection, and the result will be the context for the aggregation function.

### The Aggr() function

The `Aggr()` function creates a nested aggregation that has two independent aggregations. In the example below, a `count()` is calculated for each value of `Dim`, and the resulting array is aggregated using the `sum()` function.

#### Example:

```
Sum(Aggr(Count(X),Dim))
```

`count()` is the inner aggregation and `sum()` is the outer aggregation.

- The inner aggregation does not inherit any context from the outer aggregation.
- The inner aggregation inherits the context from the `Aggr()` function, which may contain a set expression.
- Both the `Aggr()` function and the outer aggregation function inherit the context from an outer set expression.



## Tutorial - Creating a set expression

You can build set expressions in Qlik Sense to support data analysis. In this context, the analysis is often referred to as set analysis. Set analysis offers a way of defining a scope that is different from the set of records defined by the current selection in an app.

### What you will learn

This tutorial provides the data and chart expressions to build set expressions using set modifiers, identifiers and operators.

### Who should complete this tutorial

This tutorial is for app developers who are comfortable working with the script editor and chart expressions.

### What you need to do before you start


A Qlik Sense Enterprise professional access allocation, which allows you to load data and create apps.

- [Set Analysis Part 1: Beginners' Introduction](#)
- [Set Analysis Part 2](#)

### Elements in a set expression

Set expressions are enclosed in an aggregation function, such as `sum()`, `max()`, `min()`, `avg()`, or `count()`. Set expressions are constructed from building blocks known as elements. These elements are set modifiers, identifiers, and operators.

*Elements in a set expression*



The set expression above, for example, is built from the aggregation `sum(sales)`. The set expression is enclosed in the outer curly brackets: `{ }`

The first operand in the expression is: `$<year={2021}>`

This operand returns sales for the year 2021 for the current selection. The modifier, `<Year={2021}>`, contains the selection of the year 2021. The `$` set identifier indicates that the set expression is based on current selection.

The second operand in the expression is: `1<Country={'Sweden'}>`

This operand returns Sales for Sweden. The modifier, `<Country={'Sweden'}>`, contains the selection of the country Sweden. The `1` set identifier indicates that selections made in the app will be ignored.

Finally, the `+` set operator indicates that the expression returns a set consisting of the records that belongs to any of the two set operands.

### Creating a set expression tutorial

Complete the following procedures to create the set expressions shown in this tutorial.

Create a new app and load data

#### Do the following:

1. Create a new app.
2. Click **Script editor**. Alternatively, click **Prepare > Data load editor** in the navigation bar.
3. Create a new section in the **Data load editor**.
4. Copy the following data and paste it into the new section: *Set expression tutorial data (page 321)*
5. Click **Load data**. The data is loaded as an inline load.

#### Create set expressions with modifiers

The set modifier consists of one or more field names, each followed by a selection that should be made on the field. The modifier is enclosed by angled brackets. For example, in this set expression:

```
sum ( {<Year = {2015}>} sales )
```


The modifier is:

```
<Year = {2015}>
```


This modifier specifies that data from the year 2015 will be selected. The curly brackets in which the modifier is enclosed indicate a set expression.

### Do the following:


1. In a sheet, open the **Assets** panel from the navigation bar, and then click **Charts**.




2. Drag a **KPI** onto the sheet, and then click **Add measure**.




3. Click `sa1es`, and then select `sum(sa1es)` for the aggregation.



The KPI shows the sum of sales for all years.




4. Copy and paste the KPI to create a new KPI.
5. Click the new KPI, click **Sales** under **Measures**, and then click **Open Expression editor**.




The expression editor opens with the aggregation `sum(sales)`.



6. In the expression editor, create an expression to sum Sales for 2015 only:
  - i. Add curly brackets to indicate a set expression: `sum({}sales)`
  - i. Add angle brackets to indicate a set modifier: `sum({<>}sales)`
  - ii. In the angle brackets, add the field to be selected, in this case the field is year, followed by an equal sign. Next, enclose 2015 in another set of curly brackets. The resulting set modifier is: `{<Year={2015}>}`.  
The entire expression is:  
`sum({<Year={2015}>}sales)`



- iii. Click **Apply** to save the expression and to close the expression editor. The sum of Sales for 2015 is shown in the KPI.



7. Create two more KPIs with the following expressions:

`Sum({<Year={2015,2016}>}Sales)`

The modifier in the above is `<Year={2015,2016}>`. The expression will return the sum of Sales for 2015 and 2016.

`Sum({<Year={2015},Country={'Germany'}>}Sales)`

The modifier in the above is `<Year={2015}, country={'Germany'}>`. The expression will return the sum of Sales for 2015, where 2015 intersects with Germany.

KPIs using set modifiers

The image shows a grid of four KPI cards and a configuration panel on the right. The KPI cards are:

- Sum(Sales) = 1.65M
- Sum({<Year={2015}>}Sales) = 788.6k
- Sum({<Year={2015,2016}>}Sales) = 1.65M (highlighted with a green border)
- Sum({<Year={2015},Country={USA}>}Sales) = 77.19k

The configuration panel on the right shows the settings for the 'First KPI':

- Data:** (empty)
- Measures:** First KPI
- Sum:** {<Year={2015,2016...}
- Expression:** Sum({<Year={2015,2016}>}Sales) *fx*
- Label:** Sum({<Year={2015,2016}>}Sales) *fx*
- Number formatting:** Auto
- Master item:** Add new, Delete
- Second KPI:** Add

### Add set identifiers

The set expressions above will use current selections as base, because an identifier was not used. Next, add identifiers to specify the behavior when selections are made.

### Do the following:

On your sheet, build or copy the following set expressions:


```
sum({$<Year={"2015"}>}Sales)
```

The \$ identifier will base the set expression on the current selections made in the data. This is also the default behavior when an identifier is not used.

```
sum({1<Year={"2015"}>}Sales)
```

The 1 identifier will cause the aggregation of `sum(sales)` on 2015 to ignore the current selection. The value of the aggregation will not change when the user makes other selections. For example, when Germany is selected below, the value for the aggregate sum of 2015 does not change.

*KPIs using set modifiers and identifiers*



### Add operators

Set operators are used to include, exclude, or intersect data sets. All operators use sets as operands and return a set as result.

You can use set operators in two different situations:

- To perform a set operation on set identifiers, representing sets of records in data.
- To perform a set operation on the element sets, on the field values, or inside a set modifier.

### Do the following:

On your sheet, build or copy the following set expression:

```
sum({$<Year={2015}>+1<Country={'Germany'}>}Sales)
```

The plus sign (+) operator produces a union of the data sets for 2015 and Germany. As explained with set identifiers above, the dollar sign (\$) identifier means current selections will be used for the first operand, `<Year={2015}>`, will be respected. The 1 identifier means selection will be ignored for the second operand, `<Country={'Germany'}>`.



KPI using plus sign (+) operator




Alternatively, use a minus sign (-) to return a data set that consists of the records that belong to 2015 but not Germany. Or, use an asterisk (\*) to return a set consisting of the records that belong to both sets.

```
Sum({$<Year={2015}>-1<Country={'Germany'}>}Sales)
```

```
Sum({$<Year={2015}>*1<Country={'Germany'}>}Sales)
```

KPIs using operators



## Set expression tutorial data

Load script

Load the following data as an inline load and then create the chart expressions in the tutorial.

```
//Create table salesByCountry
SalesByCountry:
Load * Inline [
Country, Year, Sales
Argentina, 2016, 66295.03
Argentina, 2015, 140037.89
```

```

Austria, 2016, 54166.09
Austria, 2015, 182739.87
Belgium, 2016, 182766.87
Belgium, 2015, 178042.33
Brazil, 2016, 174492.67
Brazil, 2015, 2104.22
Canada, 2016, 101801.33
Canada, 2015, 40288.25
Denmark, 2016, 45273.25
Denmark, 2015, 106938.41
Finland, 2016, 107565.55
Finland, 2015, 30583.44
France, 2016, 115644.26
France, 2015, 30696.98
Germany, 2016, 8775.18
Germany, 2015, 77185.68
];

```

## Syntax for set expressions

The full syntax (not including the optional use of standard brackets to define precedence) is described using Backus-Naur Formalism:

```

set_expression ::= { set_entity { set_operator set_entity } }
set_entity ::= set_identifier [ set_modifier ] | set_modifier
set_identifier ::= 1 | $ | $N | $_N | bookmark_id | bookmark_name
set_operator ::= + | - | * | /
set_modifier ::= < field_selection {, field_selection } >
field_selection ::= field_name [ = | += | -= | *= | /= ] element_set_
expression
element_set_expression ::= [ - ] element_set { set_operator element_set }
element_set ::= [ field_name ] | { element_list } | element_function
element_list ::= element { , element }
element_function ::= ( P | E ) ( [set_expression] [field_name] )
element ::= field_value | " search_mask "

```

## 6.3 General syntax for chart expressions

The following general syntax structure can be used for chart expressions, with many optional parameters:

```

expression ::= ( constant | expressionname | operator1 expression | expression operator2
expression | function | aggregation function | (expression) )

```

where:

**constant** is a string (a text, a date or a time) enclosed by single straight quotation marks, or a number. Constants are written without thousands separator and with a decimal point as decimal separator.

**expressionname** is the name (label) of another expression in the same chart.

**operator1** is a unary operator (working on one expression, the one to the right).

**operator2** is a binary operator (working on two expressions, one on each side).

```
function ::= functionname ( parameters )  
parameters ::= expression { , expression }
```

The number and types of parameters are not arbitrary. They depend on the function used.

```
aggregationfunction ::= aggregationfunctionname ( parameters2 )  
parameters2 ::= aggexpression { , aggexpression }
```

The number and types of parameters are not arbitrary. They depend on the function used.

### 6.4 General syntax for aggregations

The following general syntax structure can be used for aggregations, with many optional parameters:

```
aggexpression ::= ( fieldref | operator1 aggexpression | aggexpression operator2  
aggexpression | functioninaggr | ( aggexpression ) )
```

**fieldref** is a field name.

```
functionaggr ::= functionname ( parameters2 )
```

Expressions and functions can thus be nested freely, as long as **fieldref** is always enclosed by exactly one aggregation function and provided the expression returns an interpretable value, Qlik Sense does not give any error messages.

## 7 Operators

This section describes the operators that can be used in Qlik Sense. There are two types of operators:

- Unary operators (take only one operand)
- Binary operators (take two operands)

Most operators are binary.

The following operators can be defined:

- Bit operators
- Logical operators
- Numeric operators
- Relational operators
- String operators

### 7.1 Bit operators

All bit operators convert (truncate) the operands to signed integers (32 bit) and return the result in the same way. All operations are performed bit by bit. If an operand cannot be interpreted as a number, the operation will return NULL.

Bit operators

Operator	Full name	Description
bitnot	Bit inverse.	Unary operator. The operation returns the logical inverse of the operand performed bit by bit.  <b>Example:</b>  <code>bitnot 17</code> returns -18
bitand	Bit and.	The operation returns the logical AND of the operands performed bit by bit.  <b>Example:</b>  <code>17 bitand 7</code> returns 1
bitor	Bit or.	The operation returns the logical OR of the operands performed bit by bit.  <b>Example:</b>  <code>17 bitor 7</code> returns 23

Operator	Full name	Description
bitxor	Bit exclusive or.	The operation returns the logical exclusive or of the operands performed bit by bit.  <b>Example:</b>  17 bitxor 7 returns 22
>>	Bit right shift.	The operation returns the first operand shifted to the right. The number of steps is defined in the second operand.  <b>Example:</b>  8 >> 2 returns 2
<<	Bit left shift.	The operation returns the first operand shifted to the left. The number of steps is defined in the second operand.  <b>Example:</b>  8 << 2 returns 32

## 7.2 Logical operators

All logical operators interpret the operands logically and return True (-1) or False (0) as result.

Logical operators

Operator	Description
not	Logical inverse. One of the few unary operators. The operation returns the logical inverse of the operand.
and	Logical and. The operation returns the logical and of the operands.
or	Logical or. The operation returns the logical or of the operands.
Xor	Logical exclusive or. The operation returns the logical exclusive or of the operands. I.e. like logical or, but with the difference that the result is False if both operands are True.

## 7.3 Numeric operators

All numeric operators use the numeric values of the operands and return a numeric value as result.

## Numeric operators

Operator	Description
+	Sign for positive number (unary operator) or arithmetic addition. The binary operation returns the sum of the two operands.
-	Sign for negative number (unary operator) or arithmetic subtraction. The unary operation returns the operand multiplied by -1, and the binary the difference between the two operands.
*	Arithmetic multiplication. The operation returns the product of the two operands.
/	Arithmetic division. The operation returns the ratio between the two operands.

## 7.4 Relational operators

All relational operators compare the values of the operands and return True (-1) or False (0) as the result. All relational operators are binary.

## Relational operators

Operator	Description
<	Less than. A numeric comparison is made if both operands can be interpreted numerically. The operation returns the logical value of the evaluation of the comparison.
<=	Less than or equal. A numeric comparison is made if both operands can be interpreted numerically. The operation returns the logical value of the evaluation of the comparison.
>	Greater than. A numeric comparison is made if both operands can be interpreted numerically. The operation returns the logical value of the evaluation of the comparison.
>=	Greater than or equal. A numeric comparison is made if both operands can be interpreted numerically. The operation returns the logical value of the evaluation of the comparison.
=	Equals. A numeric comparison is made if both operands can be interpreted numerically. The operation returns the logical value of the evaluation of the comparison.
<>	Not equivalent to. A numeric comparison is made if both operands can be interpreted numerically. The operation returns the logical value of the evaluation of the comparison.

Operator	Description
<b>precedes</b>	<p>Unlike the &lt; operator no attempt is made to make a numeric interpretation of the argument values before the comparison. The operation returns true if the value to the left of the operator has a text representation which, in string comparison, comes before the text representation of the value on the right.</p> <p><b>Example:</b></p> <p>'1 ' precedes ' 2' returns FALSE</p> <p>' 1' precedes ' 2' returns TRUE</p> <p>as the ASCII value of a space ( ' ') is of less value than the ASCII value of a number.</p> <p>Compare this to:</p> <p>'1 ' &lt; ' 2' returns TRUE</p> <p>' 1' &lt; ' 2' returns TRUE</p>
<b>follows</b>	<p>Unlike the &gt; operator no attempt is made to make a numeric interpretation of the argument values before the comparison. The operation returns true if the value to the left of the operator has a text representation which, in string comparison, comes after the text representation of the value on the right.</p> <p><b>Example:</b></p> <p>' 2' follows '1' returns FALSE</p> <p>'2' follows '1' returns TRUE</p> <p>as the ASCII value of a space ( ' ') is of less value than the ASCII value of a number.</p> <p>Compare this to:</p> <p>' 2' &gt; ' 1' returns TRUE</p> <p>' 2' &gt; '1 ' returns TRUE</p>

## 7.5 String operators

There are two string operators. One uses the string values of the operands and return a string as result. The other one compares the operands and returns a boolean value to indicate match.

### &

String concatenation. The operation returns a text string, that consists of the two operand strings, one after another.

**Example:**

'abc' & 'xyz' returns 'abcxyz'

### like

String comparison with wildcard characters. The operation returns a boolean True (-1) if the string before the operator is matched by the string after the operator. The second string may contain the wildcard characters \* (any number of arbitrary characters) or ? (one arbitrary character).

**Example:**

'abc' like 'a\*' returns True (-1)

'abcd' like 'a?c\*' returns True (-1)

'abc' like 'a??bc' returns False (0)



# 8 Script and chart functions

Transform and aggregate data using functions in data load scripts and chart expressions.

Many functions can be used in the same way in both data load scripts and chart expressions, but there are a number of exceptions:

- Some functions can only be used in data load scripts, denoted by - script function.
- Some functions can only be used in chart expressions, denoted by - chart function.
- Some functions can be used in both data load scripts and chart expressions, but with differences in parameters and application. These are described in separate topics denoted by - script function or - chart function.

## 8.1 Analytic connections for server-side extensions (SSE)

Functions enabled by analytic connections will only be visible if you have configured the analytic connections and Qlik Sense has started.

You configure the analytic connections in the QMC, see the topic "Creating an analytic connection" in the guide *Manage Qlik Sense sites*.

In Qlik Sense Desktop, you configure the analytic connections by editing the *Settings.ini* file, see the topic "Configuring analytic connections in Qlik Sense Desktop" in the guide *Qlik Sense Desktop*.

## 8.2 Aggregation functions

The family of functions known as aggregation functions consists of functions that take multiple field values as their input and return a single result per group, where the grouping is defined by a chart dimension or a **group by** clause in the script statement.

Aggregation functions include **Sum()**, **Count()**, **Min()**, **Max()**, and many more.

Most aggregation functions can be used in both the data load script and chart expressions, but the syntax differs.

### Limitations:

The parameter of the aggregation function must not contain other aggregation functions, unless these inner aggregations contain the **TOTAL** qualifier. For more advanced nested aggregations, use the advanced function **Aggr**, in combination with a specified dimension.

When naming an entity, avoid assigning the same name to more than one field, variable, or measure. There is a strict order of precedence for resolving conflicts between entities with identical names. This order is reflected in any objects or contexts in which these entities are used. This order of precedence is as follows:

- Inside an aggregation, a field has precedence over a variable. Measure labels are not relevant in aggregations and are not prioritized.
- Outside an aggregation, a measure label has precedence over a variable, which in turn has precedence over a field name.
- Additionally, outside an aggregation, a measure can be re-used by referencing its label, unless the label is in fact a calculated one. In that situation, the measure drops in significance in order to reduce risk of self-reference, and in this case the name will always be interpreted first as a measure label, second as a field name, and third as a variable name.

### Using aggregation functions in a data load script

Aggregation functions can only be used inside **LOAD** and **SELECT** statements.

### Using aggregation functions in chart expressions

The parameter of the aggregation function must not contain other aggregation functions, unless these inner aggregations contain the **TOTAL** qualifier. For more advanced nested aggregations, use the advanced function **Aggr**, in combination with a specified dimension.

An aggregation function aggregates over the set of possible records defined by the selection. However, an alternative set of records can be defined by using a set expression in set analysis.

### How aggregations are calculated

An aggregation loops over the records of a specific table, aggregating the records in it. For example, **Count**(<Field>) will count the number of records in the table where <Field> resides. Should you want to aggregate just the distinct field values, you need to use the **distinct** clause, such as **Count(distinct <Field>)**.

If the aggregation function contains fields from different tables, the aggregation function will loop over the records of the cross product of the tables of the constituent fields. This has a performance penalty, and for this reason such aggregations should be avoided, particularly when you have large amounts of data.

### Aggregation of key fields


The way aggregations are calculated means that you cannot aggregate key fields because it is not clear which table should be used for the aggregation. For example, if the field <Key> links two tables, it is not clear whether **Count**(<Key>) should return the number of records from the first or the second table.

However, if you use the **distinct** clause, the aggregation is well-defined and can be calculated for a key field linked across two tables.

If you use a key field inside an aggregation function without the **distinct** clause, Qlik Sense will return a number which may be meaningless. The solution is to either use the **distinct** clause, or use a copy of the key – a copy that resides in one table only.

For example, in the following tables, *ProductId* is the key between the tables.

*ProductId* key between *Products* and *Details* tables



*Count(ProductId)* can be counted either in the *Products* table (which has only one record per product – *ProductId* is the primary key) or it can be counted in the *Details* table (which most likely has several records per product). If you want to count the number of distinct products, you should use *Count(distinct ProductId)*. If you want to count the number of rows in a specific table, you should not use the key.

### Aggregations of key fields contained in three or more tables

The **distinct** prefix only works with key fields linking up to two tables. When grouping an aggregation over a key field that exists in three or more tables, any operation that requires frequency information for a field will return NULL. In the case of a key field linking three or more tables, a non-key copy of the field must be used instead.

## Basic aggregation functions

### Basic aggregation functions overview

Basic aggregation functions are a group of the most common aggregation functions.

Each function is described further after the overview. You can also click the function name in the syntax to immediately access the details for that specific function.

### Basic aggregation functions in the data load script

#### FirstSortedValue

**FirstSortedValue()** returns the value from the expression specified in **value** that corresponds to the result of sorting the **sort\_weight** argument, for example, the name of the product with the lowest unit price. The nth value in the sort order, can be specified in **rank**. If more than one resulting value shares the same **sort\_weight** for the specified **rank**, the function returns NULL. The sorted values are iterated over a number of records, as defined by a **group by** clause, or aggregated across the full data set if no **group by** clause is defined.

```
FirstSortedValue ([ distinct ] expression, sort_weight [, rank ])
```

#### Max

**Max()** finds the highest numeric value of the aggregated data in the expression, as defined by a **group by** clause. By specifying a **rank** n, the nth highest value can be found.

```
Max ( expression[, rank])
```

#### Min

**Min()** returns the lowest numeric value of the aggregated data in the expression, as defined by a **group by** clause. By specifying a **rank** n, the nth lowest value can be found.

```
Min ( expression[, rank])
```

#### Mode

**Mode()** returns the most commonly-occurring value, the mode value, of the aggregated data in the expression, as defined by a **group by** clause. The **Mode()** function can return numeric values as well as text values.

```
Mode (expression )
```

#### Only

**Only()** returns a value if there is one and only one possible result from the aggregated data. If records contain only one value then that value is returned, otherwise NULL is returned. Use the **group by** clause to evaluate over multiple records. The **Only()** function can return numeric and text values.

```
Only (expression )
```

#### Sum

**Sum()** calculates the total of the values aggregated in the expression, as defined by a **group by** clause.

```
Sum ([distinct]expression)
```

### Basic aggregation functions in chart expressions

Chart aggregation functions can only be used on fields in chart expressions. The argument expression of one aggregation function must not contain another aggregation function.

FirstSortedValue

**FirstSortedValue()** returns the value from the expression specified in **value** that corresponds to the result of sorting the **sort\_weight** argument, for example, the name of the product with the lowest unit price. The nth value in the sort order, can be specified in **rank**. If more than one resulting value shares the same **sort\_weight** for the specified **rank**, the function returns NULL.

```
FirstSortedValue - chart function([SetExpression] [DISTINCT] [TOTAL [<fld {,fld}>]] value, sort_weight [,rank])
```

Max

**Max()** finds the highest value of the aggregated data. By specifying a **rank** n, the nth highest value can be found.

```
Max - chart functionMax() finds the highest value of the aggregated data. By specifying a rank n, the nth highest value can be found. You might also want to look at FirstSortedValue and rangemax, which have similar functionality to the Max function. Max([SetExpression] [TOTAL [<fld {,fld}>]] expr [,rank])
```

numeric Arguments	Argument	Description	expr	The expression or field containing the data to be measured.	rank	The default value of rank is 1, which corresponds to the highest value. By specifying rank as 2, the second highest value is returned. If rank is 3, the third highest value is returned, and so on.
SetExpression	By default, the aggregation function will aggregate over the set of possible records defined by the selection. An alternative set of records can be defined by a set analysis expression.	TOTAL	If the word TOTAL occurs before the function arguments, the calculation is made over all possible values given the current selections, and not just those that pertain to the current dimensional value, that is, it disregards the chart dimensions. By using TOTAL [<fld {,fld}>], where the TOTAL qualifier is followed by a list of one or more field names as a subset of the chart dimension variables, you create a subset of the total possible values.	DataCustomerProductUnitSalesUnitPrice	AstridaAA416AstridaAA1015AstridaBB99BetacabBB510BetacabCC220BetacabDD-25CanutilityAA815CanutilityCC-19	Examples and results
Examples	Results	Max (UnitSales)	10, because this is the highest value in UnitSales.	The value of an order is calculated from the number of units sold in (UnitSales) multiplied by the unit price.	Max (UnitSales*UnitPrice)	150, because this is the highest value of the result of calculating all possible values of (UnitSales)* (UnitPrice).
Max (UnitSales, 2)	9, which is the second highest value.	Max (TOTAL UnitSales)	10, because the TOTAL qualifier means the highest possible value is found, disregarding the chart dimensions. For a chart with Customer as dimension, the TOTAL qualifier will ensure the maximum value across the full dataset is returned, instead of the maximum UnitSales for each customer.	Make the selection Customer B.	Max({1} TOTAL UnitSales)	10, independent of the selection made, because the Set Analysis expression {1} defines the set of records to be evaluated as ALL, no matter what selection is made.

```
Data used in examples:ProductData:LOAD * inline
[Customer|Product|UnitSales|UnitPriceAstrida|AA|4|16Astrida|AA|10|15Astrida|B
```

```
B|9|9Betacab|BB|5|10Betacab|CC|2|20Betacab|DD||25Canutility|AA|8|15Canutility|CC||19] (delimiter is '|'); FirstSortedValue RangeMax ([{SetExpression}] [DISTINCT] [TOTAL [<fld {,fld}>]] expr [,rank])
```

Min

**Min()** finds the lowest value of the aggregated data. By specifying a **rank** n, the nth lowest value can be found.

```
Min - chart function([{SetExpression}] [DISTINCT] [TOTAL [<fld {,fld}>]] expr [,rank])
```

Mode

**Mode()** finds the most commonly-occurring value, the mode value, in the aggregated data. The **Mode()** function can process text values as well as numeric values.

```
Mode - chart function ([{SetExpression}] [TOTAL [<fld {,fld}>]] expr)
```

Only

**Only()** returns a value if there is one and only one possible result from the aggregated data. For example, searching for the only product where the unit price =9 will return NULL if more than one product has a unit price of 9.

```
Only - chart function([{SetExpression}] [DISTINCT] [TOTAL [<fld {,fld}>]] expr)
```

Sum

**Sum()** calculates the total of the values given by the expression or field across the aggregated data.

```
Sum - chart function([{SetExpression}] [DISTINCT] [TOTAL [<fld {,fld}>]] expr)
```

### FirstSortedValue

**FirstSortedValue()** returns the value from the expression specified in **value** that corresponds to the result of sorting the **sort\_weight** argument, for example, the name of the product with the lowest unit price. The nth value in the sort order, can be specified in **rank**. If more than one resulting value shares the same **sort\_weight** for the specified **rank**, the function returns NULL. The sorted values are iterated over a number of records, as defined by a **group by** clause, or aggregated across the full data set if no **group by** clause is defined.

**Syntax:**

```
FirstSortedValue ([ distinct ] value, sort-weight [, rank ])
```

**Return data type:** dual

**Arguments:**

Arguments

Argument	Description
value Expression	The function finds the value of the expression <b>value</b> that corresponds to the result of sorting <b>sort_weight</b> .
sort-weight Expression	The expression containing the data to be sorted. The first (lowest) value of <b>sort_weight</b> is found, from which the corresponding value of the <b>value</b> expression is determined. If you place a minus sign in front of <b>sort_weight</b> , the function returns the last (highest) sorted value instead.
rank Expression	By stating a <b>rank</b> "n" larger than 1, you get the nth sorted value.
distinct	If the word <b>DISTINCT</b> occurs before the function arguments, duplicates resulting from the evaluation of the function arguments are disregarded.

**Examples and results:**

Add the example script to your app and run it. Then add, at least, the fields listed in the results column to a sheet in our app to see the result.

To get the same look as in the result column below, in the properties panel, under Sorting, switch from Auto to Custom, then deselect numerical and alphabetical sorting.

### Scripting examples

Example	Result
<pre>Temp: LOAD * inline [ Customer Product OrderNumber UnitSales CustomerID Astrida AA 1 10 1 Astrida AA 7 18 1 Astrida BB 4 9 1 Astrida CC 6 2 1 Betacab AA 5 4 2 Betacab BB 2 5 2 Betacab DD 12 25 2 Canutility AA 3 8 3 Canutility CC 13 19 3 Divadip AA 9 16 4 Divadip AA 10 16 4 Divadip DD 11 10 4 ] (delimiter is ' ');  FirstSortedValue: LOAD Customer,FirstSortedValue(Product, UnitSales) as MyProductWithSmallestOrderByCustomer Resident Temp Group By Customer;</pre>	<pre>Customer MyProductWithSmallestOrderByCustomer Astrida CC Betacab AA Canutility AA Divadip DD</pre> <p>The function sorts UnitSales from smallest to largest, looking for the value of Customer with the smallest value of UnitSales, the smallest order.</p> <p>Because CC corresponds to the smallest order (value of UnitSales=2) for customer Astrida. AA corresponds to the smallest order (4) for customer Betacab, AA corresponds to the smallest order (8) for customer Canutility, and DD corresponds to the smallest order (10) for customer Divadip..</p>
<p>Given that the <b>Temp</b> table is loaded as in the previous example:</p> <pre>LOAD Customer,FirstSortedValue(Product, -UnitSales) as MyProductWithLargestOrderByCustomer Resident Temp Group By Customer;</pre>	<pre>Customer MyProductWithLargestOrderByCustomer Astrida AA Betacab DD Canutility CC Divadip -</pre> <p>A minus sign precedes the sort_weight argument, so the function sorts the largest first.</p> <p>Because AA corresponds to the largest order (value of UnitSales:18) for customer Astrida, DD corresponds to the largest order (12) for customer Betacab, and CC corresponds to the largest order (13) for customer Canutility. There are two identical values for the largest order (16) for customer Divadip, therefore this produces a null result.</p>



Example	Result
<p>Given that the <b>Temp</b> table is loaded as in the previous example:</p> <pre>LOAD Customer,FirstSortedValue(distinct Product, - Unitsales) as MyProductWithSmallestOrderByCustomer Resident Temp Group By Customer;</pre>	<pre>Customer MyProductWithLargestOrderByCustomer Astrida AA Betacab DD Canutility CC Divadip AA</pre> <p>This is the same as the previous example, except the distinct qualifier is used. This causes the duplicate result for Divadip to be disregarded, allowing a non-null value to be returned.</p>

### FirstSortedValue - chart function

**FirstSortedValue()** returns the value from the expression specified in **value** that corresponds to the result of sorting the **sort\_weight** argument, for example, the name of the product with the lowest unit price. The nth value in the sort order, can be specified in **rank**. If more than one resulting value shares the same **sort\_weight** for the specified **rank**, the function returns NULL.

#### Syntax:

```
FirstSortedValue([SetExpression] [DISTINCT] [TOTAL [<fld {,fld}>]] value,
sort_weight [,rank])
```

**Return data type:** dual

#### Arguments:

##### Arguments

Argument	Description
value	Output field. The function finds the value of the expression <b>value</b> that corresponds to the result of sorting <b>sort_weight</b> .
sort_weight	Input field. The expression containing the data to be sorted. The first (lowest) value of <b>sort_weight</b> is found, from which the corresponding value of the <b>value</b> expression is determined. If you place a minus sign in front of <b>sort_weight</b> , the function returns the last (highest) sorted value instead.
rank	By stating a <b>rank</b> "n" larger than 1, you get the nth sorted value.
SetExpression	By default, the aggregation function will aggregate over the set of possible records defined by the selection. An alternative set of records can be defined by a set analysis expression.
DISTINCT	If the word <b>DISTINCT</b> occurs before the function arguments, duplicates resulting from the evaluation of the function arguments are disregarded.

Argument	Description
TOTAL	<p>If the word <b>TOTAL</b> occurs before the function arguments, the calculation is made over all possible values given the current selections, and not just those that pertain to the current dimensional value, that is, it disregards the chart dimensions.</p> <p>By using <b>TOTAL [&lt;fld {fld}&gt;]</b>, where the <b>TOTAL</b> qualifier is followed by a list of one or more field names as a subset of the chart dimension variables, you create a subset of the total possible values.</p>

### Examples and results:

Data			
Customer	Product	UnitSales	UnitPrice
Astrida	AA	4	16
Astrida	AA	10	15
Astrida	BB	9	9
Betacab	BB	5	10
Betacab	CC	2	20
Betacab	DD	-	25
Canutility	AA	8	15
Canutility	CC	-	19

### Examples and results

Example	Result
firstsortedvalue (Product, UnitPrice)	BB, which is the Product with the lowest unitPrice(9).
firstsortedvalue (Product, UnitPrice, 2)	BB, which is the Product with the second-lowest unitPrice(10).
firstsortedvalue (Customer, -UnitPrice, 2)	Betacab, which is the customer with the Product that has second-highest unitPrice(20).
firstsortedvalue (Customer, UnitPrice, 3)	<p>NULL, because there are two values of customer (Astrida and Canutility) with the same rank (third-lowest) unitPrice(15).</p> <p>Use the distinct qualifier to make sure unexpected null results do not occur.</p>
firstsortedvalue (Customer, -UnitPrice*UnitSales, 2)	Canutility, which is the customer with the second-highest sales order value unitPrice multiplied by unitSales (120).

Data used in examples:

```
ProductData:
LOAD * inline [
Customer|Product|UnitsSales|UnitPrice
Astrida|AA|4|16
Astrida|AA|10|15
Astrida|BB|9|9
Betacab|BB|5|10
Betacab|CC|2|20
Betacab|DD||25
Canutility|AA|8|15
Canutility|CC||19
] (delimiter is '|');
```

### Max

**Max()** finds the highest numeric value of the aggregated data in the expression, as defined by a **group by** clause. By specifying a **rank** n, the nth highest value can be found.

#### Syntax:

```
Max ( expr [, rank] )
```

**Return data type:** numeric

#### Arguments:

##### Arguments

Argument	Description
expr Expression	The expression or field containing the data to be measured.
rank Expression	The default value of <b>rank</b> is 1, which corresponds to the highest value. By specifying <b>rank</b> as 2, the second highest value is returned. If <b>rank</b> is 3, the third highest value is returned, and so on.

#### Examples and results:

Add the example script to your app and run it. Then add, at least, the fields listed in the results column to a sheet in our app to see the result.

To get the same look as in the result column below, in the properties panel, under Sorting, switch from Auto to Custom, then deselect numerical and alphabetical sorting.

#### Example:

```
Temp:
LOAD * inline [
Customer|Product|OrderNumber|UnitSales|CustomerID
Astrida|AA|1|10|1
Astrida|AA|7|18|1
Astrida|BB|4|9|1
Astrida|CC|6|2|1
```

```
Betacab|AA|5|4|2  
Betacab|BB|2|5|2  
Betacab|DD  
Canutility|DD|3|8  
Canutility|CC  
] (delimiter is '|');
```

Max:

```
LOAD Customer, Max(UnitSales) as MyMax Resident Temp Group By Customer;
```

Resulting table

Customer	MyMax
Astrida	18
Betacab	5
Canutility	8

### Example:

Given that the **Temp** table is loaded as in the previous example:

```
LOAD Customer, Max(UnitSales,2) as MyMaxRank2 Resident Temp Group By Customer;
```

Resulting table

Customer	MyMaxRank2
Astrida	10
Betacab	4
Canutility	-

### Max - chart function

**Max()** finds the highest value of the aggregated data. By specifying a **rank** n, the nth highest value can be found.



You might also want to look at **FirstSortedValue** and **rangemax**, which have similar functionality to the **Max** function.

### Syntax:

```
Max ([{SetExpression}] [TOTAL [<fld {,fld}>]] expr [,rank])
```

**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
expr	The expression or field containing the data to be measured.
rank	The default value of <b>rank</b> is 1, which corresponds to the highest value. By specifying <b>rank</b> as 2, the second highest value is returned. If <b>rank</b> is 3, the third highest value is returned, and so on.
SetExpression	By default, the aggregation function will aggregate over the set of possible records defined by the selection. An alternative set of records can be defined by a set analysis expression.
TOTAL	<p>If the word <b>TOTAL</b> occurs before the function arguments, the calculation is made over all possible values given the current selections, and not just those that pertain to the current dimensional value, that is, it disregards the chart dimensions.</p> <p>By using <b>TOTAL [&lt;fld {fld}&gt;]</b>, where the <b>TOTAL</b> qualifier is followed by a list of one or more field names as a subset of the chart dimension variables, you create a subset of the total possible values.</p>

**Examples and results:**

Data

Customer	Product	UnitSales	UnitPrice
Astrida	AA	4	16
Astrida	AA	10	15
Astrida	BB	9	9
Betacab	BB	5	10
Betacab	CC	2	20
Betacab	DD	-	25
Canutility	AA	8	15
Canutility	CC	-	19



## Examples and results

Examples	Results
<code>Max(Unitsales)</code>	10, because this is the highest value in <code>unitsales</code> .
The value of an order is calculated from the number of units sold in ( <code>unitsales</code> ) multiplied by the unit price.  <code>Max (Unitsales*UnitPrice)</code>	150, because this is the highest value of the result of calculating all possible values of <code>(unitsales)*(unitPrice)</code> .
<code>Max(Unitsales, 2)</code>	9, which is the second highest value.
<code>Max(TOTAL Unitsales)</code>	10, because the TOTAL qualifier means the highest possible value is found, disregarding the chart dimensions. For a chart with Customer as dimension, the TOTAL qualifier will ensure the maximum value across the full dataset is returned, instead of the maximum UnitSales for each customer.
Make the selection Customer B.  <code>Max({1} TOTAL Unitsales)</code>	10, independent of the selection made, because the Set Analysis expression <code>{1}</code> defines the set of records to be evaluated as ALL, no matter what selection is made.

Data used in examples:

```
ProductData:
LOAD * inline [
Customer|Product|Unitsales|UnitPrice
Astrida|AA|4|16
Astrida|AA|10|15
Astrida|BB|9|9
Betacab|BB|5|10
Betacab|CC|2|20
Betacab|DD||25
Canutility|AA|8|15
Canutility|CC||19
] (delimiter is '|');
```

**See also:**

-  [FirstSortedValue - chart function \(page 337\)](#)
-  [RangeMax \(page 1347\)](#)

**Min**

**Min()** returns the lowest numeric value of the aggregated data in the expression, as defined by a **group by** clause. By specifying a **rank** *n*, the *n*th lowest value can be found.

### Syntax:

```
Min ( expr [, rank] )
```

**Return data type:** numeric

### Arguments:

Arguments

Argument	Description
expr Expression	The expression or field containing the data to be measured.
rank Expression	The default value of <b>rank</b> is 1, which corresponds to the lowest value. By specifying <b>rank</b> as 2, the second lowest value is returned. If <b>rank</b> is 3, the third lowest value is returned, and so on.

### Examples and results:

Add the example script to your app and run it. Then add, at least, the fields listed in the results column to a sheet in our app to see the result.

To get the same look as in the result column below, in the properties panel, under Sorting, switch from Auto to Custom, then deselect numerical and alphabetical sorting.

### Example:

Temp:

```
LOAD * inline [
Customer|Product|OrderNumber|UnitSales|CustomerID
Astrida|AA|1|10|1
Astrida|AA|7|18|1
Astrida|BB|4|9|1
Astrida|CC|6|2|1
Betacab|AA|5|4|2
Betacab|BB|2|5|2
Betacab|DD
Canutility|DD|3|8
Canutility|CC
] (delimiter is '|');
```

Min:

```
LOAD Customer, Min(UnitSales) as MyMin Resident Temp Group By Customer;
```

Resulting table

Customer	MyMin
Astrida	2
Betacab	4
Canutility	8

**Example:**

Given that the **Temp** table is loaded as in the previous example:

```
LOAD Customer, Min(UnitsSales,2) as MyMinRank2 Resident Temp Group By Customer;
```

Resulting table

Customer	MyMinRank2
Astrida	9
Betacab	5
Canutility	-

**Min - chart function**

**Min()** finds the lowest value of the aggregated data. By specifying a **rank** n, the nth lowest value can be found.



You might also want to look at **FirstSortedValue** and **rangemin**, which have similar functionality to the **Min** function.

**Syntax:**

```
Min ([SetExpression] [TOTAL [<fld {,fld}>]]) expr [,rank])
```

**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
expr	The expression or field containing the data to be measured.
rank	The default value of <b>rank</b> is 1, which corresponds to the lowest value. By specifying <b>rank</b> as 2, the second lowest value is returned. If <b>rank</b> is 3, the third lowest value is returned, and so on.
SetExpression	By default, the aggregation function will aggregate over the set of possible records defined by the selection. An alternative set of records can be defined by a set analysis expression.
TOTAL	<p>If the word <b>TOTAL</b> occurs before the function arguments, the calculation is made over all possible values given the current selections, and not just those that pertain to the current dimensional value, that is, it disregards the chart dimensions.</p> <p>By using <b>TOTAL [&lt;fld {,fld}&gt;]</b>, where the <b>TOTAL</b> qualifier is followed by a list of one or more field names as a subset of the chart dimension variables, you create a subset of the total possible values.</p>



**Examples and results:**

Data			
Customer	Product	UnitSales	UnitPrice
Astrida	AA	4	16
Astrida	AA	10	15
Astrida	BB	9	9
Betacab	BB	5	10
Betacab	CC	2	20
Betacab	DD	-	25
Canutility	AA	8	15
Canutility	CC	-	19



*The Min() function must return a non-NULL value from the array of values given by the expression, if there is one. So in the examples, because there are NULL values in the data, the function returns the first non-NULL value evaluated from the expression.*

**Examples and results**

Examples	Results
Min(UnitSales)	2, because this is the lowest non-NULL value in unitSales.
The value of an order is calculated from the number of units sold in (unitSales) multiplied by the unit price.  Min (UnitSales*UnitPrice)	40, because this is the lowest non-NULL value result of calculating all possible values of (unitSales)*(unitPrice).
Min(UnitSales, 2)	4, which is the second lowest value (after the NULL values).
Min(TOTAL UnitSales)	2, because the TOTAL qualifier means the lowest possible value is found, disregarding the chart dimensions. For a chart with Customer as dimension, the TOTAL qualifier will ensure the minimum value across the full dataset is returned, instead of the minimum UnitSales for each customer.



Examples	Results
Make the selection Customer B.  Min({1} TOTAL unitsales)	2, which is independent of the selection of Customer B.  The Set Analysis expression {1} defines the set of records to be evaluated as ALL, no matter what selection is made.

Data used in examples:

```

ProductData:
LOAD * inline [
Customer|Product|UnitsSales|UnitPrice
Astrida|AA|4|16
Astrida|AA|10|15
Astrida|BB|9|9
Betacab|BB|5|10
Betacab|CC|2|20
Betacab|DD||25
Canutility|AA|8|15
Canutility|CC||19
] (delimiter is '|');
  
```

### See also:

-  [FirstSortedValue - chart function \(page 337\)](#)
-  [RangeMin \(page 1351\)](#)

## Mode

**Mode()** returns the most commonly-occurring value, the mode value, of the aggregated data in the expression, as defined by a **group by** clause. The **Mode()** function can return numeric values as well as text values.

### Syntax:

```
Mode ( expr )
```

**Return data type:** dual

### Arguments

Argument	Description
expr Expression	The expression or field containing the data to be measured.

### Limitations:

If more than one value is equally commonly occurring, NULL is returned.

### Examples and results:

Add the example script to your app and run it. Then add, at least, the fields listed in the results column to a sheet in our app to see the result.

To get the same look as in the result column below, in the properties panel, under Sorting, switch from Auto to Custom, then deselect numerical and alphabetical sorting.

Scripting examples

Example	Result
<pre>Temp: LOAD * inline [ Customer Product OrderNumber UnitSales CustomerID Astrida AA 1 10 1 Astrida AA 7 18 1 Astrida BB 4 9 1 Astrida CC 6 2 1 Betacab AA 5 4 2 Betacab BB 2 5 2 Betacab DD Canutility DD 3 8 Canutility CC ] (delimiter is ' ');  Mode: LOAD Customer, Mode(Product) as MyMostOftenSoldProduct Resident Temp Group By Customer;</pre>	<p>MyMostOftenSoldProduct</p> <p>AA</p> <p>because AA is the only product sold more than once.</p>

### Mode - chart function

**Mode()** finds the most commonly-occurring value, the mode value, in the aggregated data. The **Mode()** function can process text values as well as numeric values.

#### Syntax:

```
Mode ({[SetExpression] [TOTAL [<fld {,fld}>]]) expr)
```

**Return data type:** dual

#### Arguments:

Arguments

Argument	Description
expr	The expression or field containing the data to be measured.
SetExpression	By default, the aggregation function will aggregate over the set of possible records defined by the selection. An alternative set of records can be defined by a set analysis expression.

Argument	Description
TOTAL	<p>If the word <b>TOTAL</b> occurs before the function arguments, the calculation is made over all possible values given the current selections, and not just those that pertain to the current dimensional value, that is, it disregards the chart dimensions.</p> <p>By using <b>TOTAL [&lt;fld {fld}&gt;]</b>, where the <b>TOTAL</b> qualifier is followed by a list of one or more field names as a subset of the chart dimension variables, you create a subset of the total possible values.</p>

### Examples and results:

Data			
Customer	Product	UnitSales	UnitPrice
Astrida	AA	4	16
Astrida	AA	10	15
Astrida	BB	9	9
Betacab	BB	5	10
Betacab	CC	2	20
Betacab	DD	-	25
Canutility	AA	8	15
Canutility	CC	-	19



### Examples and results

Examples	Results
Mode(UnitPrice) Make the selection Customer A.	15, because this is the most commonly-occurring value in unitSales.  Returns NULL (-). No single value occurs more often than another.
Mode(Product) Make the selection Customer A	AA, because this is the most commonly occurring value in Product.  Returns NULL (-). No single value occurs more often than another.
Mode (TOTAL UnitPrice)	15, because the TOTAL qualifier means the most commonly occurring value is still 15, even disregarding the chart dimensions.
Make the selection Customer B.  Mode({1} TOTAL UnitPrice)	15, independent of the selection made, because the Set Analysis expression {1} defines the set of records to be evaluated as ALL, no matter what selection is made.

Data used in examples:

```
ProductData:
LOAD * inline [
Customer|Product|UnitsSales|UnitPrice
Astrida|AA|4|16
Astrida|AA|10|15
Astrida|BB|9|9
Betacab|BB|5|10
Betacab|CC|2|20
Betacab|DD||25
Canutility|AA|8|15
Canutility|CC||19
] (delimiter is '|');
```

### See also:

-  [Avg - chart function \(page 407\)](#)
-  [Median - chart function \(page 446\)](#)

### Only

**Only()** returns a value if there is one and only one possible result from the aggregated data. If records contain only one value then that value is returned, otherwise NULL is returned. Use the **group by** clause to evaluate over multiple records. The **Only()** function can return numeric and text values.

### Syntax:

```
Only ( expr )
```

**Return data type:** dual

### Arguments

Argument	Description
expr Expression	The expression or field containing the data to be measured.

### Examples and results:

Add the example script to your app and run it. Then add, at least, the fields listed in the results column to a sheet in our app to see the result.

To get the same look as in the result column below, in the properties panel, under Sorting, switch from Auto to Custom, then deselect numerical and alphabetical sorting.

```
Temp:
LOAD * inline [
Customer|Product|OrderNumber|UnitsSales|CustomerID
Astrida|AA|1|10|1
Astrida|AA|7|18|1
Astrida|BB|4|9|1
Astrida|CC|6|2|1
Betacab|AA|5|4|2
Betacab|BB|2|5|2
Betacab|DD
```

```
Canutility|DD|3|8
Canutility|CC
] (delimiter is '|');
Only:
LOAD Customer, Only(CustomerID) as MyUniqIDCheck Resident Temp Group By Customer;
```

Resulting table

Customer	MyUniqIDCheck
Astrida	1

because only customer Astrida has complete records that include CustomerID.

### Only - chart function

**Only()** returns a value if there is one and only one possible result from the aggregated data. For example, searching for the only product where the unit price =9 will return NULL if more than one product has a unit price of 9.

#### Syntax:

```
Only ([{SetExpression}] [TOTAL [<fld {,fld}>]] expr)
```

**Return data type:** dual

#### Arguments:

Arguments

Argument	Description
expr	The expression or field containing the data to be measured.
SetExpression	By default, the aggregation function will aggregate over the set of possible records defined by the selection. An alternative set of records can be defined by a set analysis expression.
TOTAL	<p>If the word <b>TOTAL</b> occurs before the function arguments, the calculation is made over all possible values given the current selections, and not just those that pertain to the current dimensional value, that is, it disregards the chart dimensions.</p> <p>By using <b>TOTAL [&lt;fld {,fld}&gt;]</b>, where the <b>TOTAL</b> qualifier is followed by a list of one or more field names as a subset of the chart dimension variables, you create a subset of the total possible values.</p>



*Use Only() when you want a NULL result if there are multiple possible values in the sample data.*

**Examples and results:**

Data			
Customer	Product	UnitSales	UnitPrice
Astrida	AA	4	16
Astrida	AA	10	15
Astrida	BB	9	9
Betacab	BB	5	10
Betacab	CC	2	20
Betacab	DD	-	25
Canutility	AA	8	15
Canutility	CC	-	19

## Examples and results

Examples	Results
<code>only({&lt;UnitPrice={9}&gt;} Product)</code>	BB, because this is the only Product that has a unitPrice of '9'.
<code>only({&lt;Product={DD}&gt;} Customer)</code>	Betacab, because it is the only customer selling a Product called 'DD'.
<code>only({&lt;UnitPrice={20}&gt;} unitsales)</code>	The number of unitsales where unitPrice is 20 is 2, because there is only one value of unitsales where the unitPrice =20.
<code>only({&lt;UnitPrice={15}&gt;} unitsales)</code>	NULL, because there are two values of unitsales where the unitPrice =15.

## Data used in examples:

```
ProductData:
LOAD * inline [
Customer|Product|unitsales|unitPrice
Astrida|AA|4|16
Astrida|AA|10|15
Astrida|BB|9|9
Betacab|BB|5|10
Betacab|CC|2|20
Betacab|DD||25
Canutility|AA|8|15
Canutility|CC||19
] (delimiter is '|');
```

### Sum

**Sum()** calculates the total of the values aggregated in the expression, as defined by a **group by** clause.

#### Syntax:

```
sum ( [ distinct] expr)
```

**Return data type:** numeric

#### Arguments:

Arguments

Argument	Description
distinct	If the word <b>distinct</b> occurs before the expression, all duplicates will be disregarded.
expr Expression	The expression or field containing the data to be measured.

#### Examples and results:

Add the example script to your app and run it. Then add, at least, the fields listed in the results column to a sheet in our app to see the result.

To get the same look as in the result column below, in the properties panel, under Sorting, switch from Auto to Custom, then deselect numerical and alphabetical sorting.

Temp:

```
LOAD * inline [
Customer|Product|OrderNumber|UnitSales|CustomerID
Astrida|AA|1|10|1
Astrida|AA|7|18|1
Astrida|BB|4|9|1
Astrida|CC|6|2|1
Betacab|AA|5|4|2
Betacab|BB|2|5|2
Betacab|DD
Canutility|DD|3|8
Canutility|CC
] (delimiter is '|');
```

Sum:

```
LOAD Customer, Sum(UnitSales) as MySum Resident Temp Group By Customer;
```

Resulting table

Customer	MySum
Astrida	39
Betacab	9
Canutility	8



## Sum - chart function

**Sum()** calculates the total of the values given by the expression or field across the aggregated data.


### Syntax:

```
Sum ([{SetExpression}] [DISTINCT] [TOTAL [<fld {,fld}>]] expr)
```

**Return data type:** numeric

### Arguments:

#### Arguments

Argument	Description
expr	The expression or field containing the data to be measured.
SetExpression	By default, the aggregation function will aggregate over the set of possible records defined by the selection. An alternative set of records can be defined by a set analysis expression.
DISTINCT	If the word <b>DISTINCT</b> occurs before the function arguments, duplicates resulting from the evaluation of the function arguments are disregarded. <div style="border: 1px solid gray; padding: 5px; margin-top: 10px;">  <i>Although the DISTINCT qualifier is supported, use it only with extreme caution because it may mislead the reader into thinking a total value is shown when some data has been omitted.</i> </div>
TOTAL	If the word <b>TOTAL</b> occurs before the function arguments, the calculation is made over all possible values given the current selections, and not just those that pertain to the current dimensional value, that is, it disregards the chart dimensions. <p>By using <b>TOTAL [&lt;fld {,fld}&gt;]</b>, where the <b>TOTAL</b> qualifier is followed by a list of one or more field names as a subset of the chart dimension variables, you create a subset of the total possible values.</p>

### Examples and results:

#### Data

Customer	Product	UnitSales	UnitPrice
Astrida	AA	4	16
Astrida	AA	10	15
Astrida	BB	9	9

Customer	Product	UnitSales	UnitPrice
Betacab	BB	5	10
Betacab	CC	2	20
Betacab	DD	-	25
Canutility	AA	8	15
Canutility	CC	-	19

### Examples and results

Examples	Results
Sum(UnitSales)	38. The total of the values in unitSales.
Sum(UnitSales*UnitPrice)	505. The total of unitPrice multiplied by unitSales aggregated.
Sum (TOTAL UnitSales*UnitPrice)	505 for all rows in the table as well as the total, because the TOTAL qualifier means the sum is still 505, disregarding the chart dimensions.
Make the selection customer B.  Sum({1} TOTAL UnitSales*UnitPrice)	505, independent of the selection made, because the Set Analysis expression {1} defines the set of records to be evaluated as ALL, no matter what selection is made.

Data used in examples:

```
ProductData:
LOAD * inline [
Customer|Product|UnitSales|UnitPrice
Astrida|AA|4|16
Astrida|AA|10|15
Astrida|BB|9|9
Betacab|BB|5|10
Betacab|CC|2|20
Betacab|DD||25
Canutility|AA|8|15
canutility|CC||19
] (delimiter is '|');
```

## Counter aggregation functions

Counter aggregation functions return various types of counts of an expression over a number of records in a data load script or a number of values in a chart dimension.

Each function is described further after the overview. You can also click the function name in the syntax to immediately access the details for that specific function.

### Counter aggregation functions in the data load script

#### Count

**Count()** returns the number of values aggregated in expression, as defined by a **group by** clause.

```
Count ([distinct ] expression | * )
```

#### MissingCount

**MissingCount()** returns the number of missing values aggregated in the expression, as defined by a **group by** clause.

```
MissingCount ([ distinct ] expression)
```

#### NullCount

**NullCount()** returns the number of NULL values aggregated in the expression, as defined by a **group by** clause.

```
NullCount ([ distinct ] expression)
```

#### NumericCount

**NumericCount()** returns the number of numeric values found in the expression, as defined by a **group by** clause.

```
NumericCount ([ distinct ] expression)
```

#### TextCount

**TextCount()** returns the number of field values that are non-numeric aggregated in the expression, as defined by a **group by** clause.

```
TextCount ([ distinct ] expression)
```

### Counter aggregation functions in chart expressions

The following counter aggregation functions can be used in charts.

#### Count

**Count()** is used to aggregate the number of values, text and numeric, in each chart dimension.

```
Count - chart function({[SetExpression] [DISTINCT] [TOTAL [<fld {,fld}>]]}  
expr)
```

#### MissingCount

**MissingCount()** is used to aggregate the number of missing values in each chart dimension. Missing values are all non-numeric values.

```
MissingCount - chart function({[SetExpression] [DISTINCT] [TOTAL [<fld  
{,fld}>]] expr)
```

#### NullCount

**NullCount()** is used to aggregate the number of NULL values in each chart dimension.

```
NullCount - chart function ({ [SetExpression] [DISTINCT] [TOTAL [<fld {,fld}>]] }  
expr)
```

NumericCount

**NumericCount()** aggregates the number of numeric values in each chart dimension.

```
NumericCount - chart function ({ [SetExpression] [DISTINCT] [TOTAL [<fld  
{,fld}>]] } expr)
```

TextCount

**TextCount()** is used to aggregate the number of field values that are non-numeric in each chart dimension.

```
TextCount - chart function ({ [SetExpression] [DISTINCT] [TOTAL [<fld  
{,fld}>]] } expr)
```

Count

**Count()** returns the number of values aggregated in expression, as defined by a **group by** clause.

**Syntax:**

```
Count( [distinct ] expr)
```

**Return data type:** integer

**Arguments:**

Arguments

Argument	Description
expr	The expression or field containing the data to be measured.
distinct	If the word <b>distinct</b> occurs before the expression, all duplicates are disregarded.

**Examples and results:**

Add the example script to your app and run it. Then add, at least, the fields listed in the results column to a sheet in our app to see the result.

To get the same look as in the result column below, in the properties panel, under Sorting, switch from Auto to Custom, then deselect numerical and alphabetical sorting.

### Scripting examples

Example	Result
<pre>Temp: LOAD * inline [ Customer Product OrderNumber UnitSales UnitPrice Astrida AA 1 4 16 Astrida AA 7 10 15 Astrida BB 4 9 9 Betacab CC 6 5 10 Betacab AA 5 2 20 Betacab BB 1 25  25 Canutility AA 3 8 15 Canutility CC   19 Divadip CC 2 4 16 Divadip DD 3 1 25 ] (delimiter is ' ');  Count1: LOAD Customer,Count(OrderNumber) as OrdersByCustomer Resident Temp Group By Customer;</pre>	<pre>Customer OrdersByCustomer Astrida 3 Betacab 3 Canutility 2 Divadip 2</pre> <p>As long as the dimension Customer is included in the table on the sheet otherwise the result for OrdersByCustomer is 3, 2.</p>
<p>Given that the <b>Temp</b> table is loaded as in the previous example:</p> <pre>LOAD Count(OrderNumber) as TotalOrderNumber Resident Temp;</pre>	<pre>TotalOrderNumber 10</pre>
<p>Given that the <b>Temp</b> table is loaded as in the first example:</p> <pre>LOAD Count(distinct OrderNumber) as TotalOrderNumber Resident Temp;</pre>	<pre>TotalOrderNumber 8</pre> <p>Because there are two values of OrderNumber with the same value, 1, and one null value.</p>

### Count - chart function

**Count()** is used to aggregate the number of values, text and numeric, in each chart dimension.

#### Syntax:

```
Count ({[SetExpression] [DISTINCT] [TOTAL [<fld {,fld}>]]} expr)
```

**Return data type:** integer

#### Arguments:

##### Arguments

Argument	Description
expr	The expression or field containing the data to be measured.


Argument	Description
SetExpression	By default, the aggregation function will aggregate over the set of possible records defined by the selection. An alternative set of records can be defined by a set analysis expression.
DISTINCT	If the word <b>DISTINCT</b> occurs before the function arguments, duplicates resulting from the evaluation of the function arguments are disregarded.
TOTAL	<p>If the word <b>TOTAL</b> occurs before the function arguments, the calculation is made over all possible values given the current selections, and not just those that pertain to the current dimensional value, that is, it disregards the chart dimensions.</p> <p>By using <b>TOTAL [&lt;fld {fld}&gt;]</b>, where the <b>TOTAL</b> qualifier is followed by a list of one or more field names as a subset of the chart dimension variables, you create a subset of the total possible values.</p>

### Examples and results:

Data				
Customer	Product	OrderNumber	UnitSales	Unit Price
Astrida	AA	1	4	16
Astrida	AA	7	10	15
Astrida	BB	4	9	9
Betacab	BB	6	5	10
Betacab	CC	5	2	20
Betacab	DD	1	25	25
Canutility	AA	3	8	15
Canutility	CC			19
Divadip	AA	2	4	16
Divadip	DD	3		25

The following examples assume that all customers are selected, except where stated.

### Examples and results

Example	Result
Count(OrderNumber)	10, because there are 10 fields that could have a value for OrderNumber, and all records, even empty ones, are counted.  <div style="border: 1px solid gray; padding: 5px; margin-top: 10px;">  "0" counts as a value and not an empty cell. However, if a measure aggregates to 0 for a dimension, that dimension will not be included in charts. </div>
Count(Customer)	10, because Count evaluates the number of occurrences in all fields.
Count(DISTINCT [Customer])	4, because using the Distinct qualifier, Count only evaluates unique occurrences.
Given that customer Canutility is selected  Count (OrderNumber)/Count({1} TOTAL OrderNumber)	0.2, because the expression returns the number of orders from the selected customer as a percentage of orders from all customers. In this case 2 / 10.
Given that customers Astrida and Canutility are selected  Count(TOTAL <Product> OrderNumber)	5, because that is the number of orders placed on products for the selected customers only and empty cells are counted.

Data used in examples:

```
Temp:
LOAD * inline [
Customer|Product|OrderNumber|UnitSales|UnitPrice
Astrida|AA|1|4|16
Astrida|AA|7|10|15
Astrida|BB|4|9|9
Betacab|CC|6|5|10
Betacab|AA|5|2|20
Betacab|BB|1|25| 25
Canutility|AA|3|8|15
Canutility|CC|||19
Divadip|CC|2|4|16
Divadip|DD|3|1|25
] (delimiter is '|');
```

### MissingCount

**MissingCount()** returns the number of missing values aggregated in the expression, as defined by a **group by** clause.

### Syntax:

```
MissingCount ( [ distinct ] expr)
```

**Return data type:** integer

### Arguments:

#### Arguments

Argument	Description
expr Expression	The expression or field containing the data to be measured.
distinct	If the word <b>distinct</b> occurs before the expression, all duplicates are disregarded.

### Examples and results:

Add the example script to your app and run it. Then add, at least, the fields listed in the results column to a sheet in our app to see the result.

To get the same look as in the result column below, in the properties panel, under Sorting, switch from Auto to Custom, then deselect numerical and alphabetical sorting.

#### Scripting examples

Example	Result
<pre>Temp: LOAD * inline [ Customer Product OrderNumber UnitSales UnitPrice Astrida AA 1 4 16 Astrida AA 7 10 15 Astrida BB 4 9 9 Betacab CC 6 5 10 Betacab AA 5 2 20 Betacab BB    25 Canutility AA   15 Canutility CC   19 Divadip CC 2 4 16 Divadip DD 3 1 25 ] (delimiter is ' '); MissCount1: LOAD Customer,MissingCount(OrderNumber) as MissingOrdersByCustomer Resident Temp Group By Customer;  Load MissingCount(OrderNumber) as TotalMissingCount Resident Temp;</pre>	<pre>Customer MissingOrdersByCustomer Astrida 0 Betacab 1 Canutility 2 Divadip 0  The second statement gives:  TotalMissingCount 3  in a table with that dimension.</pre>
<p>Given that the <b>Temp</b> table is loaded as in the previous example:</p> <pre>LOAD MissingCount(distinct OrderNumber) as TotalMissingCountDistinct Resident Temp;</pre>	<pre>TotalMissingCountDistinct 1  Because there is only oneOrderNumber one missing value.</pre>



### MissingCount - chart function

**MissingCount()** is used to aggregate the number of missing values in each chart dimension. Missing values are all non-numeric values.

**Syntax:**

```
MissingCount(([SetExpression] [DISTINCT] [TOTAL [<fld {,fld}>]]) expr)
```

**Return data type:** integer

**Arguments:**

Arguments

Argument	Description
expr	The expression or field containing the data to be measured.
SetExpression	By default, the aggregation function will aggregate over the set of possible records defined by the selection. An alternative set of records can be defined by a set analysis expression.
DISTINCT	If the word <b>DISTINCT</b> occurs before the function arguments, duplicates resulting from the evaluation of the function arguments are disregarded.
TOTAL	<p>If the word <b>TOTAL</b> occurs before the function arguments, the calculation is made over all possible values given the current selections, and not just those that pertain to the current dimensional value, that is, it disregards the chart dimensions.</p> <p>By using <b>TOTAL [&lt;fld {,fld}&gt;]</b>, where the <b>TOTAL</b> qualifier is followed by a list of one or more field names as a subset of the chart dimension variables, you create a subset of the total possible values.</p>


**Examples and results:**

Data

Customer	Product	OrderNumber	UnitSales	Unit Price
Astrida	AA	1	4	16
Astrida	AA	7	10	15
Astrida	BB	4	9	9
Betacab	BB	6	5	10
Betacab	CC	5	2	20
Betacab	DD			25

Customer	Product	OrderNumber	UnitSales	Unit Price
Canutility	AA			15
Canutility	CC			19
Divadip	AA	2	4	16
Divadip	DD	3		25

## Examples and results

Example	Result
MissingCount([OrderNumber])	3 because 3 of the 10 OrderNumber fields are empty  <div style="border: 1px solid gray; padding: 5px; margin: 5px 0;">  "0" counts as a value and not an empty cell. However, if a measure aggregates to 0 for a dimension, that dimension will not be included in charts. </div>
MissingCount([OrderNumber])/MissingCount({1} Total [OrderNumber])	The expression returns the number of incomplete orders from the selected customer as a fraction of incomplete orders from all customers. There is a total of 3 missing values for OrderNumber for all customers. So, for each Customer that has a missing value for Product the result is 1/3.

Data used in example:

```
Temp:
LOAD * inline [
Customer|Product|OrderNumber|UnitSales|UnitPrice
Astrida|AA|1|4|16
Astrida|AA|7|10|15
Astrida|BB|4|9|9
Betacab|CC|6|5|10
Betacab|AA|5|2|20
Betacab|BB||| 25
Canutility|AA|||15
Canutility|CC| |19
Divadip|CC|2|4|16
Divadip|DD|3|1|25
] (delimiter is '|');
```

## NullCount

**NullCount()** returns the number of NULL values aggregated in the expression, as defined by a **group by** clause.

### Syntax:

```
NullCount ( [ distinct ] expr)
```

**Return data type:** integer

**Arguments:**

Arguments

Argument	Description
expr Expression	The expression or field containing the data to be measured.
distinct	If the word <b>distinct</b> occurs before the expression, all duplicates are disregarded.

**Examples and results:**

Add the example script to your app and run it. Then add, at least, the fields listed in the results column to a sheet in our app to see the result.

To get the same look as in the result column below, in the properties panel, under Sorting, switch from Auto to Custom, then deselect numerical and alphabetical sorting.

Scripting examples

Example	Result
<pre>Set NULLINTERPRET = NULL; Temp: LOAD * inline [ Customer Product OrderNumber UnitSales CustomerID Astrida AA 1 10 1 Astrida AA 7 18 1 Astrida BB 4 9 1 Astrida CC 6 2 1 Betacab AA 5 4 2 Betacab BB 2 5 2 Betacab DD    Canutility AA 3 8  Canutility CC NULL   ] (delimiter is ' '); Set NULLINTERPRET=; NullCount1: LOAD Customer,NullCount(OrderNumber) as NullOrdersByCustomer Resident Temp Group By Customer;  LOAD NullCount(OrderNumber) as TotalNullCount Resident Temp;</pre>	<p>Customer NullOrdersByCustomer Astrida 0 Betacab 0 Canutility 1</p> <p>The second statement gives:</p> <p>TotalNullCount 1 in a table with that dimension, because only one record contains a null value.</p>

### NullCount - chart function

**NullCount()** is used to aggregate the number of NULL values in each chart dimension.

**Syntax:**

```
NullCount ({ [SetExpression] [DISTINCT] [TOTAL [<fld {,fld}>]] } expr)
```

**Return data type:** integer

**Arguments:**

Arguments

Argument	Description
expr	The expression or field containing the data to be measured.
set_expression	By default, the aggregation function will aggregate over the set of possible records defined by the selection. An alternative set of records can be defined by a set analysis expression.
DISTINCT	If the word <b>DISTINCT</b> occurs before the function arguments, duplicates resulting from the evaluation of the function arguments are disregarded.
TOTAL	<p>If the word <b>TOTAL</b> occurs before the function arguments, the calculation is made over all possible values given the current selections, and not just those that pertain to the current dimensional value, that is, it disregards the chart dimensions.</p> <p>By using <b>TOTAL [&lt;fld {fld}&gt;]</b>, where the <b>TOTAL</b> qualifier is followed by a list of one or more field names as a subset of the chart dimension variables, you create a subset of the total possible values.</p>

**Examples and results:**

Examples and results

Example	Result
NullCount ([OrderNumber])	1 because we have introduced a null value using NullInterpret in the inline <b>LOAD</b> statement.

Data used in example:

```
Set NULLINTERPRET = NULL;
Temp:
LOAD * inline [
Customer|Product|OrderNumber|UnitSales|CustomerID
Astrida|AA|1|10|1
Astrida|AA|7|18|1
Astrida|BB|4|9|1
Astrida|CC|6|2|1
Betacab|AA|5|4|2
Betacab|BB|2|5|2
Betacab|DD|||
Canutility|AA|3|8|
Canutility|CC|NULL||
] (delimiter is '|');
Set NULLINTERPRET=;
```

## NumericCount

**NumericCount()** returns the number of numeric values found in the expression, as defined by a **group by** clause.

### Syntax:

```
NumericCount ( [ distinct ] expr)
```

**Return data type:** integer

### Arguments:

#### Arguments

Argument	Description
expr Expression	The expression or field containing the data to be measured.
distinct	If the word <b>distinct</b> occurs before the expression, all duplicates are disregarded.

### Examples and results:

Add the example script to your app and run it. Then add, at least, the fields listed in the results column to a sheet in our app to see the result.

To get the same look as in the result column below, in the properties panel, under Sorting, switch from Auto to Custom, then deselect numerical and alphabetical sorting.

#### Scripting example

Example	Result
<pre>LOAD NumericCount(OrderNumber) as TotalNumericCount Resident Temp;</pre>	<p>The second statement gives:</p> <p>TotalNumericCount 7 in a table with that dimension.</p>
<p>Given that the <b>Temp</b> table is loaded as in the previous example:</p> <pre>LOAD NumericCount(distinct OrderNumber) as TotalNumericCountDistinct Resident Temp;</pre>	<p>TotalNumericCountDistinct 6 Because there is one OrderNumber that duplicates another, so the result is 6 that are not duplicates..</p>

### Example:

```
Temp:
LOAD * inline [
Customer|Product|OrderNumber|UnitSales|UnitPrice
Astrida|AA|1|4|16
Astrida|AA|7|10|15
```

```

Astrida|BB|4|9|9
Betacab|CC|6|5|10
Betacab|AA|5|2|20
Betacab|BB||| 25
Canutility|AA|||15
Canutility|CC| ||19
Divadip|CC|2|4|16
Divadip|DD|7|1|25
] (delimiter is '|');
NumCount1:
LOAD Customer, NumericCount(OrderNumber) as NumericCountByCustomer Resident Temp Group By
Customer;

```

Resulting table

Customer	NumericCountByCustomer
Astrida	3
Betacab	2
Canutility	0
Divadip	2

### NumericCount - chart function

**NumericCount()** aggregates the number of numeric values in each chart dimension.

#### Syntax:

```
NumericCount ({ [SetExpression] [DISTINCT] [TOTAL [<fld {,fld}>]] } expr)
```

**Return data type:** integer

#### Arguments:

Arguments


Argument	Description
expr	The expression or field containing the data to be measured.
set_ expression	By default, the aggregation function will aggregate over the set of possible records defined by the selection. An alternative set of records can be defined by a set analysis expression.
DISTINCT	If the word <b>DISTINCT</b> occurs before the function arguments, duplicates resulting from the evaluation of the function arguments are disregarded.

Argument	Description
TOTAL	<p>If the word <b>TOTAL</b> occurs before the function arguments, the calculation is made over all possible values given the current selections, and not just those that pertain to the current dimensional value, that is, it disregards the chart dimensions.</p> <p>By using <b>TOTAL [&lt;fld {fld}&gt;]</b>, where the <b>TOTAL</b> qualifier is followed by a list of one or more field names as a subset of the chart dimension variables, you create a subset of the total possible values.</p>

### Examples and results:

Data				
Customer	Product	OrderNumber	UnitSales	Unit Price
Astrida	AA	1	4	16
Astrida	AA	7	10	15
Astrida	BB	4	9	1
Betacab	BB	6	5	10
Betacab	CC	5	2	20
Betacab	DD			25
Canutility	AA			15
Canutility	CC			19
Divadip	AA	2	4	16
Divadip	DD	3		25

The following examples assume that all customers are selected, except where stated.

Examples and results	
Example	Result
NumericCount ([OrderNumber])	<p>7 because three of the 10 fields in OrderNumber are empty.</p> <div style="border: 1px solid gray; padding: 5px; margin-top: 10px;"> <p> "0" counts as a value and not an empty cell. However, if a measure aggregates to 0 for a dimension, that dimension will not be included in charts.</p> </div>

Example	Result
NumericCount ([Product])	0 because all product names are in text. Typically you could use this to check that no text fields have been given numeric content.
NumericCount (DISTINCT [OrderNumber])/Count (DISTINCT [OrderNumber])	Counts all the number of distinct numeric order numbers and divides it by the number of order numbers numeric and non-numeric. This will be 1 if all field values are numeric. Typically you could use this to check that all field values are numeric. In the example, there are 7 distinct numeric values for OrderNumber of 8 distinct numeric and non-numeric, so the expression returns 0.875.

Data used in example:

```
Temp:
LOAD * inline [
Customer|Product|OrderNumber|UnitSales|UnitPrice
Astrida|AA|1|4|16
Astrida|AA|7|10|15
Astrida|BB|4|9|9
Betacab|CC|6|5|10
Betacab|AA|5|2|20
Betacab|BB||| 25
Canutility|AA|||15
Canutility|CC| |19
Divadip|CC|2|4|16
Divadip|DD|3|1|25
] (delimiter is '|');
```

### TextCount

**TextCount()** returns the number of field values that are non-numeric aggregated in the expression, as defined by a **group by** clause.

#### Syntax:

```
TextCount ( [ distinct ] expr)
```

**Return data type:** integer

#### Arguments:

##### Arguments

Argument	Description
expr Expression	The expression or field containing the data to be measured.
distinct	If the word <b>distinct</b> occurs before the expression, all duplicates are disregarded.



### Examples and results:

Add the example script to your app and run it. Then add, at least, the fields listed in the results column to a sheet in our app to see the result.

To get the same look as in the result column below, in the properties panel, under Sorting, switch from Auto to Custom, then deselect numerical and alphabetical sorting.

### Example:

```
Temp:
LOAD * inline [
Customer|Product|OrderNumber|UnitSales|UnitPrice
Astrida|AA|1|4|16
Astrida|AA|7|10|15
Astrida|BB|4|9|9
Betacab|CC|6|5|10
Betacab|AA|5|2|20
Betacab|BB||| 25
Canutility|AA|||15
Canutility|CC| |19
Divadip|CC|2|4|16
Divadip|DD|3|1|25
] (delimiter is '|');
TextCount1:
LOAD Customer,TextCount(Product) as ProductTextCount Resident Temp Group By Customer;
```

Resulting table

Customer	ProductTextCount
Astrida	3
Betacab	3
Canutility	2
Divadip	2

### Example:

```
LOAD Customer,TextCount(OrderNumber) as OrderNumberTextCount Resident Temp Group By Customer;
```

Resulting table

Customer	OrderNumberTextCount
Astrida	0
Betacab	1
Canutility	2
Divadip	0

## TextCount - chart function

**TextCount()** is used to aggregate the number of field values that are non-numeric in each chart dimension.

### Syntax:

```
TextCount ({ [SetExpression] [DISTINCT] [TOTAL [<fld {,fld}>]] } expr)
```

**Return data type:** integer

### Arguments:

#### Arguments

Argument	Description
expr	The expression or field containing the data to be measured.
SetExpression	By default, the aggregation function will aggregate over the set of possible records defined by the selection. An alternative set of records can be defined by a set analysis expression.
DISTINCT	If the word <b>DISTINCT</b> occurs before the function arguments, duplicates resulting from the evaluation of the function arguments are disregarded.
TOTAL	<p>If the word <b>TOTAL</b> occurs before the function arguments, the calculation is made over all possible values given the current selections, and not just those that pertain to the current dimensional value, that is, it disregards the chart dimensions.</p> <p>By using <b>TOTAL [&lt;fld {,fld}&gt;]</b>, where the <b>TOTAL</b> qualifier is followed by a list of one or more field names as a subset of the chart dimension variables, you create a subset of the total possible values.</p>


### Examples and results:

#### Data

Customer	Product	OrderNumber	UnitSales	Unit Price
Astrida	AA	1	4	16
Astrida	AA	7	10	15
Astrida	BB	4	9	1
Betacab	BB	6	5	10
Betacab	CC	5	2	20
Betacab	DD			25

Customer	Product	OrderNumber	UnitSales	Unit Price
Canutility	AA			15
Canutility	CC			19
Divadip	AA	2	4	16
Divadip	DD	3		25

### Examples and results

Example	Result
TextCount ([Product])	10 because all of the 10 fields in Product are text.  <div style="border: 1px solid gray; padding: 5px;">  <i>"0" counts as a value and not an empty cell. However, if a measure aggregates to 0 for a dimension, that dimension will not be included in charts. Empty cells are evaluated as being non text and are not counted by TextCount.</i> </div>
TextCount ([OrderNumber])	3, because empty cells are counted. Typically, you would use this to check that no numeric fields have been given text values or are non-zero.
TextCount (DISTINCT [Product])/Count ([Product])	Counts all the number of distinct text values of Product (4), and divides it by the total number of values in Product (10). The result is 0.4.

Data used in example:

```
Temp:
LOAD * inline [
Customer|Product|OrderNumber|UnitSales|UnitPrice
Astrida|AA|1|4|16
Astrida|AA|7|1|15
Astrida|BB|4|9|9
Betacab|CC|6|5|10
Betacab|AA|5|2|20
Betacab|BB|||| 25
Canutility|AA|||15
Canutility|CC|||19
Divadip|CC|2|4|16
Divadip|DD|3|1|25
] (delimiter is '|');
```

## Financial aggregation functions

This section describes aggregation functions for financial operations regarding payments and cash flow.

Each function is described further after the overview. You can also click the function name in the syntax to immediately access the details for that specific function.

### Financial aggregation functions in the data load script

#### IRR

**IRR()** returns the aggregated internal rate of return for a series of cash flows represented by the numbers in the expression iterated over a number of records as defined by a group by clause.

```
IRR (expression)
```

#### XIRR

**XIRR()** returns the aggregated internal rate of return (yearly) for a schedule of cash flows (that is not necessarily periodic) represented by paired numbers in **pmt** and **date** iterated over a number of records as defined by a group by clause. All payments are discounted based on a 365-day year.

```
XIRR (valueexpression, dateexpression )
```

#### NPV

The **NPV()** script function takes a discount rate and multiple values ordered by period. Inflows (incomes) are positive, and outflows (future payments) are assumed to be negative values for these calculations. These occur at the end of each period.

```
NPV (rate, expression)
```

#### XNPV

**XNPV()** returns the aggregated net present value for a schedule of cashflows (not necessarily periodic) represented by paired numbers in **pmt** and **date**. All payments are discounted based on a 365-day year.

```
XNPV (rate, valueexpression, dateexpression)
```

### Financial aggregation functions in chart expressions

These financial aggregation functions can be used in charts

#### IRR

**IRR()** returns the aggregated internal rate of return for a series of cash flows represented by the numbers in the expression given by **value** iterated over the chart dimensions.

```
IRR - chart function([TOTAL [<fld {,fld}>]] value)
```

#### NPV

**NPV()** returns the aggregated net present value of an investment based on a **discount\_rate** per period and a series of future payments (negative values) and incomes (positive values,) represented by the numbers in **value**, iterated over the chart dimensions. The payments and incomes are assumed to occur at the end of each period.

```
NPV - chart function([TOTAL [<fld {,fld}>]] discount_rate, value)
```

### XIRR

**XIRR()** returns the aggregated internal rate of return (yearly) for a schedule of cash flows (that is not necessarily periodic) represented by paired numbers in the expressions given by **pmt** and **date** iterated over the chart dimensions. All payments are discounted based on a 365-day year.

```
XIRR - chart function([TOTAL [<fld {,fld}>]] pmt, date)
```

### XNPV

**XNPV()** returns the aggregated net present value for a schedule of cash flows (not necessarily periodic) represented by paired numbers in the expressions given by **pmt** and **date**, iterated over the chart dimensions. All payments are discounted based on a 365-day year.

```
XNPV - chart function([TOTAL [<fld {,fld}>]] discount_rate, pmt, date)
```

### IRR

**IRR()** returns the aggregated internal rate of return for a series of cash flows represented by the numbers in the expression iterated over a number of records as defined by a group by clause.

These cash flows do not have to be even, as they would be for an annuity. However, the cash flows must occur at regular intervals, such as monthly or annually. The internal rate of return is the interest rate received for an investment consisting of payments (negative values) and income (positive values) that occur at regular periods. The function needs at least one positive and one negative value to calculate.

This function uses a simplified version of the Newton method for calculating the internal rate of return (IRR).

#### Syntax:

```
IRR(value)
```

**Return data type:** numeric

#### Arguments:

##### Arguments

Argument	Description
value	The expression or field containing the data to be measured.

#### Limitations:

Text values, NULL values and missing values are disregarded.

#### Examples and results:

Add the example script to your app and run it. To see the result, add the fields listed in the results column to a sheet in your app.

**Examples and results:**

## Examples and results

Example	Year	IRR2013
<pre>Cashflow: LOAD 2013 as Year, * inline [ Date Discount Payments 2013-01-01 0.1 -10000 2013-03-01 0.1 3000 2013-10-30 0.1 4200 2014-02-01 0.2 6800 ] (delimiter is ' ');  Cashflow1: LOAD Year,IRR(Payments) as IRR2013 Resident Cashflow Group By Year;</pre>	2013	0.1634

**IRR - chart function**

**IRR()** returns the aggregated internal rate of return for a series of cash flows represented by the numbers in the expression given by **value** iterated over the chart dimensions.

These cash flows do not have to be even, as they would be for an annuity. However, the cash flows must occur at regular intervals, such as monthly or annually. The internal rate of return is the interest rate received for an investment consisting of payments (negative values) and income (positive values) that occur at regular periods. The function needs at least one positive and one negative value to calculate.

This function uses a simplified version of the Newton method for calculating the internal rate of return (IRR).

**Syntax:**

```
IRR ([TOTAL [<fld {,fld}>]] value)
```

**Return data type:** numeric

**Arguments:**

## Arguments

Argument	Description
value	The expression or field containing the data to be measured.
TOTAL	<p>If the word <b>TOTAL</b> occurs before the function arguments, the calculation is made over all possible values given the current selections, and not just those that pertain to the current dimensional value, that is, it disregards the chart dimensions.</p> <p>By using <b>TOTAL [&lt;fld {,fld}&gt;]</b>, where the <b>TOTAL</b> qualifier is followed by a list of one or more field names as a subset of the chart dimension variables, you create a subset of the total possible values.</p>


### Limitations:

The parameter of the aggregation function must not contain other aggregation functions, unless these inner aggregations contain the **TOTAL** qualifier. For more advanced nested aggregations, use the advanced function **Aggr**, in combination with a specified dimension.

Text values, NULL values and missing values are disregarded.

### Examples and results:

#### Examples and results



Example	Result
IRR (Payments)	0.1634  The payments are assumed to be periodic in nature, for example monthly.  <div style="border: 1px solid #ccc; padding: 5px; margin-top: 10px;">  <i>The Date field is used in the XIRR example where payments can be non-periodical as long as you provide the dates on which payments were made.</i> </div>

### Data used in examples:

Cashflow:

```
LOAD 2013 as Year, * inline [
Date|Discount|Payments
2013-01-01|0.1|-10000
2013-03-01|0.1|3000
2013-10-30|0.1|4200
2014-02-01|0.2|6800
] (delimiter is '|');
```

### See also:

-  [XIRR - chart function \(page 387\)](#)
-  [Aggr - chart function \(page 549\)](#)

## NPV

The **NPV()** script function takes a discount rate and multiple values ordered by period. Inflows (incomes) are positive, and outflows (future payments) are assumed to be negative values for these calculations. These occur at the end of each period.

Net Present Value, or NPV, is used to calculate the current total value of a future stream of cash flows. To calculate NPV, we need to estimate future cash flows for each period and determine the correct discount rate. The **NPV()** script function takes a discount rate and multiple values ordered by period. Inflows (incomes) are positive, and outflows (future payments) are assumed to be negative values for these calculations. These occur at the end of each period.

### Syntax:

**NPV**(discount\_rate, value)

**Return data type:** numeric. By default, the result will be formatted as currency.

The formula to calculate net present value is:

$$NPV = \sum_{t=1}^n \frac{R_t}{(1+i)^t}$$

where:

- $R_t$  = Net cash inflow-outflows during a single period  $t$
- $i$  = Discount rate or return that could be earned in alternative investments
- $t$  = Number of timer periods

### Arguments

Argument	Description
discount_rate	<b>discount_rate</b> is the percentage rate of discount applied. A value of 0.1 would indicate a 10% discount rate.
value	This field holds values for multiple periods ordered by period. The first value is assumed to be the cashflow at the end of period 1, and so on.

### Limitations:

The `NPV()` function has the following limitations:

- Text values, NULL values and missing values are disregarded.
- Cashflow values must be in order of ascending period.

### When to use it

`NPV()` is a financial function used to check project profitability and to derive other measures. This function is useful when cashflows are available as raw data.

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.



Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Example 1 – Single payment (script)

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset of one project and its cashflow for one period, which is loaded into a table named `CashFlow`.
- A resident load from the `cashFlow` table, which is used to calculate the NPV field for the project in a table named `NPV`.
- A hard-coded discount rate of 10% , which is used in the NPV calculation.
- A `Group By` statement, which is used to group all the payments for the project.

#### Load script

```
CashFlow:
Load
*
Inline
[
PrjId,PeriodId,values
1,1,1000
];

NPV:
Load
    PrjId,
    NPV(0.1,values) as NPV //Discount Rate of 10%
Resident CashFlow
Group By PrjId;
```

#### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- `PrjId`
- `NPV`

Results table

PrjId	NPV
1	\$909.09

For a single payment of \$1000 to be received at the end of one period, at a discount rate of 10% per period, the NPV is equal to \$1000 divided by (1 + discount rate). The effective NPV is equal to \$909.09

### Example 2 – Multiple payments (script)

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset of one project and its cashflow for multiple periods, which is loaded into a table named `CashFlow`.
- A resident load from the `CashFlow` table, which is used to calculate the NPV field for the project in a table named `NPV`.
- A hard-coded discount rate of 10% (0.1) is used in the NPV calculation.
- A `Group By` statement, which is used to group all the payments for the project.

#### Load script

```
CashFlow:
Load
*
Inline
[
PrjId,PeriodId,Values
1,1,1000
1,2,1000
];

NPV:
Load
    PrjId,
    NPV(0.1,Values) as NPV //Discount Rate of 10%
Resident CashFlow
Group By PrjId;
```

#### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- PrjId
- NPV

Results table

PrjId	NPV
1	\$1735.54

For payments of \$1000 to be received at the end of two periods, at a discount rate of 10% per period, the effective NPV is equal to \$1735.54.

### Example 3 – Multiple payments (script)

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- Discount rates for two projects, which is loaded into a table named `Project`.
- Cashflows for multiple periods for each project by project ID and period ID. This period ID could be used to order the records in case the data is not ordered.
- The combination of `noconcatenate`, Resident loads, and the `Left Join` function to create a temporary table, `tmpNPV`. The table combines the records of `Project` and `CashFlow` tables into one flat table. This table will have discount rates repeated for each period.
- A resident load from the `tmpNPV` table, which is used to calculate the NPV field for each project in a table named `NPV`.
- The single value discount rate associated to each project. This is retrieved using the `only()` function and is used in the NPV calculation for each project.
- A `Group By` statement, which is used to group all the payments for each project by project ID.

To avoid any synthetic or redundant data being loaded into the data model, the `tmpNPV` table is dropped at the end of the script.

#### Load script

```
Project:
Load * inline [
PrjId,Discount_Rate
1,0.1
2,0.15
];
```

```
CashFlow:
Load
*
inline
```

```
[
PrjId,PeriodId,Values
1,1,1000
1,2,1000
1,3,1000
2,1,500
2,2,500
2,3,1000
2,4,1000
];

tmpNPV:
NoConcatenate Load *
Resident Project;
Left Join
Load *
Resident CashFlow;

NPV:
Load
    PrjId,
    NPV(Only(Discount_Rate),Values) as NPV //Discount Rate will be 10% for Project 1 and 15% for
Project 2
Resident tmpNPV
Group By PrjId;

Drop table tmpNPV;
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- PrjId
- NPV

Results table

PrjId	NPV
1	\$2486.85
2	\$2042.12

Project ID 1 expects for payments of \$1000 to be received at the end of three periods, at a discount rate of 10% per period. Therefore, the effective NPV is equal to \$2486.85.

Project ID 2 expects two payments of \$500 and two further payments of \$1000 across four periods at a discount rate of 15%. Therefore, the effective NPV is equal to \$2042.12.

### Example 4 – Project profitability example (script)

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- Discount rates and initial investments (period 0) for two projects, loaded into a table named `Project`.
- Cashflows for multiple periods for each project by project ID and period ID. This period ID could be used to order the records in case the data is not ordered.
- The combination of `NoConcatenate`, `Resident` loads, and the `Left Join` function to create a temporary table, `tmpNPV`. The table combines the records of `Project` and `CashFlow` tables into one flat table. This table will have discount rates repeated for each period.
- The single value discount rate associated to each project, which is retrieved using the `only()` function and is used in the NPV calculation for each project.
- A resident load from the `tmpNPV` table is used to calculate the NPV field for each project in a table named `NPV`.
- An additional field that divides the NPV by the initial investment of each project is created to calculate the project profitability index.
- A group by statement, grouping by project ID, is used to group all the payments for each project.

To avoid any synthetic or redundant data being loaded into the data model, the `tmpNPV` table is dropped at the end of the script.

#### Load script

```
Project:
Load * inline [
PrjId,Discount_Rate, Initial_Investment
1,0.1,100000
2,0.15,100000
];
```

```
CashFlow:
Load
*
Inline
[
PrjId,PeriodId,values,
1,1,35000
1,2,35000
1,3,35000
2,1,30000
2,2,40000
2,3,50000
```

```
2,4,60000
];
```

```
tmpNPV:
NoConcatenate Load *
Resident Project;
Left Join
Load *
Resident CashFlow;
```

```
NPV:
Load
    PrjId,
    NPV(Only(Discount_Rate),Values) as NPV, //Discount Rate will be 10% for Project 1 and
15% for Project 2
    NPV(Only(Discount_Rate),values)/ Only(Initial_Investment) as Profitability_Index
Resident tmpNPV
Group By PrjId;
```

```
Drop table tmpNPV;
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- PrjId
- NPV

Create the following measure:

```
=only(Profitability_Index)
```

Results table

PrjId	NPV	=only(Profitability_Index)
1	\$87039.82	0.87
2	\$123513.71	1.24

Project ID 1 has an effective NPV of \$87039.82 and an initial investment of \$100000. Therefore, the profitability index is equal to 0.87. Because it is less than 1, the project is not profitable.

Project ID 2 has an effective NPV of \$123513.71 and an initial investment of \$100000. Therefore, the profitability index is equal to 1.24. Because it is greater than 1, the project is profitable.

### NPV - chart function

**NPV()** returns the aggregated net present value of an investment based on a **discount\_rate** per period and a series of future payments (negative values) and incomes (positive values,) represented by the numbers in **value**, iterated over the chart dimensions. The payments and incomes are assumed to occur at the end of each period.

#### Syntax:

```
NPV([TOTAL [<fld {,fld}>]] discount_rate, value)
```

**Return data type:** numeric By default, the result will be formatted as currency.

**Arguments:**

Arguments

Argument	Description
discount_rate	<b>discount_rate</b> is the percentage rate of discount applied.
value	The expression or field containing the data to be measured.
TOTAL	<p>If the word <b>TOTAL</b> occurs before the function arguments, the calculation is made over all possible values given the current selections, and not just those that pertain to the current dimensional value, that is, it disregards the chart dimensions.</p> <p>By using <b>TOTAL [&lt;fld {fld}&gt;]</b>, where the <b>TOTAL</b> qualifier is followed by a list of one or more field names as a subset of the chart dimension variables, you create a subset of the total possible values.</p> <p>The <b>TOTAL</b> qualifier may be followed by a list of one or more field names within angle brackets. These field names should be a subset of the chart dimension variables. In this case, the calculation is made disregarding all chart dimension variables except those listed, that is, one value is returned for each combination of field values in the listed dimension fields. Also, fields that are not currently a dimension in a chart may be included in the list. This may be useful in the case of group dimensions, where the dimension fields are not fixed. Listing all of the variables in the group causes the function to work when the drill-down level changes.</p>

**Limitations:**

**discount\_rate** and **value** must not contain aggregation functions, unless these inner aggregations contain the **TOTAL** qualifier. For more advanced nested aggregations, use the advanced function **Aggr**, in combination with a specified dimension.

Text values, NULL values and missing values are disregarded.

**Examples and results:**

Examples and results



Example	Result
NPV(Discount, Payments)	-\$540.12

Data used in examples:

Cashflow:  
LOAD 2013 as Year, \* inline [

```
Date|Discount|Payments
2013-01-01|0.1|-10000
2013-03-01|0.1|3000
2013-10-30|0.1|4200
2014-02-01|0.2|6800
] (delimiter is '|');
```

### See also:

-  [XNPV - chart function \(page 397\)](#)
-  [Aggr - chart function \(page 549\)](#)

## XIRR

**XIRR()** returns the aggregated internal rate of return (yearly) for a schedule of cash flows (that is not necessarily periodic) represented by paired numbers in **pmt** and **date** iterated over a number of records as defined by a group by clause. All payments are discounted based on a 365-day year.

Qlik's XIRR functionality (**XIRR()** and **RangeXIRR()** functions) uses the following equation, solving for the rate value, to determine the correct XIRR value:

$$\text{XNPV}(\text{Rate}, \text{pmt}, \text{date}) = 0$$

The equation is solved using a simplified version of the Newton method.

### Syntax:

```
XIRR (pmt, date )
```

**Return data type:** numeric

### Arguments

Argument	Description
pmt	Payments. The expression or field containing the cash flows corresponding to the payment schedule given in <b>date</b> .
date	The expression or field containing the schedule of dates corresponding to the cash flow payments given in <b>pmt</b> .

When working with this function, the following limitations apply:

- Text values, NULL values and missing values in any or both pieces of a data-pair will result in the entire data-pair to be disregarded.
- This function requires at least one valid negative and at least one valid positive payment (with corresponding valid dates). If these payments are not provided, a NULL value is returned.

These topics might help you work with this function:



- *XNPV* (page 390): Use this function to calculate aggregated net present value for a schedule of cash flows.
- *RangeXIRR* (page 1369): **RangeXIRR()** is the equivalent range function for the **XIRR()** function.



Across different versions of Qlik Sense Client-Managed, there are variations in the underlying algorithm used by this function. For more information about recent updates to the algorithm, see support article [XIRR function Fix and Update](#).

### Example

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- Transaction data for a series of cashflows.
- The use of the **XIRR()** function to compute internal yearly rate of return for these cashflows.

#### Load script

Cashflow:

```
LOAD 2013 as Year, * inline [
Date|Payments
2013-01-01|-10000
2013-03-01|3000
2013-10-30|4200
2014-02-01|6800
] (delimiter is '|');
```

Cashflow1:

```
LOAD Year,XIRR(Payments, Date) as XIRR2013 Resident Cashflow Group By Year;
```

#### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- Year
- XIRR2013

Results table

Year	XIRR2013
2013	0.5385

### Interpreting the XIRR return value

The XIRR functionality is usually used to analyze an investment, where there is an outgoing (negative) payment in the beginning, and then a series of smaller income (positive) payments later on. Here is a simplified example with only one negative and one positive payment:

```
Cashflow:
LOAD * inline [
Date|Payments
2023-01-01|-100
2024-01-01|110
] (delimiter is '|');
```

We make an initial payment of 100 and get 110 back after exactly one year. This represents a rate of return of 10% per year. `XIRR(Payments, Date)` returns a value of 0.1.

The return value of the XIRR functionality can be positive or negative. In the case of an investment, a negative result indicates that the investment is a loss. The amount of gain or loss can be calculated simply by making a sum aggregation over the payments field.

In the example above, we are lending out our money for one year. The rate of return can be thought of as interest. It is also possible to use XIRR's functionality when you are on the other side of the transaction (for example, if you are the borrower instead of the lender).

Consider this example:

```
Cashflow:
LOAD * inline [
Date|Payments
2023-01-01|100
2024-01-01|-110
] (delimiter is '|');
```

This is the same as the first example but inverted. Here, we are borrowing 100 for one year and we repay it with a 10% interest. In this example, the XIRR calculation returns 0.1 (10%), the same value as the first example.

Note that in the first example, we received a profit of 10, and in the second example, we experienced a loss of 10, but the return value of the XIRR functionality is positive for both these examples. This is because the XIRR functionality calculates the hidden interest in the transaction, regardless of which side you are on in the transaction.

### Limitations with multiple solutions

Qlik's XIRR functionality is defined by the following equation, in which the rate value is solved:

$$\text{XNPV}(\text{Rate}, \text{pmt}, \text{date}) = 0$$

It is sometimes possible for this equation to have more than one solution. This is known as the "multiple-IRR problem", and is caused by a non-normal cash flow stream (also called an unconventional cash flow). The following load script shows an example of this:

```
Cashflow:
LOAD * inline [
Date|Payments
```




```
2021-01-01|-200
2022-01-01|500
2023-01-01|-250
] (delimiter is '|');
```

In this example, there is one negative solution and one positive solution (`rate = -0.3` and `rate = 0.8`). **XIRR()** will return 0.8.

When Qlik's XIRR functionality searches for a solution, it starts at `rate = 0` and increases the rate in steps until it finds a solution. If there is more than one positive solution, it will return the first one that it encounters. If it cannot find a positive solution, it will reset the `rate` back to zero and start searching for a solution in the negative direction.

Note that a "normal" cash flow stream is guaranteed to have only one solution. "Normal" cash flow stream means that all payments with the same sign (positive or negative) are in a continuous group.

### See also:

-  [XNPV \(page 390\)](#)
-  [RangeXIRR \(page 1369\)](#)
-  [XIRR function Fix and Update](#)

### XIRR - chart function

**XIRR()** returns the aggregated internal rate of return (yearly) for a schedule of cash flows (that is not necessarily periodic) represented by paired numbers in the expressions given by **pmt** and **date** iterated over the chart dimensions. All payments are discounted based on a 365-day year.

Qlik's XIRR functionality (**XIRR()** and **RangeXIRR()** functions) uses the following equation, solving for the `rate` value, to determine the correct XIRR value:

$$\text{XNPV}(\text{Rate}, \text{pmt}, \text{date}) = 0$$

The equation is solved using a simplified version of the Newton method.

### Syntax:

```
XIRR ([TOTAL [<fld {,fld}>]] pmt, date)
```

**Return data type:** numeric

#### Arguments

Argument	Description
pmt	Payments. The expression or field containing the cash flows corresponding to the payment schedule given in <b>date</b> .
date	The expression or field containing the schedule of dates corresponding to the cash flow payments given in <b>pmt</b> .

Argument	Description
TOTAL	<p>If the word <b>TOTAL</b> occurs before the function arguments, the calculation is made over all possible values given the current selections, and not just those that pertain to the current dimensional value, that is, it disregards the chart dimensions.</p> <p>By using <b>TOTAL [&lt;fld {fld}&gt;]</b>, where the <b>TOTAL</b> qualifier is followed by a list of one or more field names as a subset of the chart dimension variables, you create a subset of the total possible values.</p>

When working with this function, the following limitations apply:

- **pmt** and **date** must not contain aggregation functions, unless these inner aggregations contain the **TOTAL** qualifier. For more advanced nested aggregations, use the advanced function **Aggr**, in combination with a specified dimension.
- Text values, NULL values and missing values in any or both pieces of a data-pair result in the entire data-pair being disregarded.
- This function requires at least one valid negative and at least one valid positive payment (with corresponding valid dates). If these payments are not provided, a NULL value is returned.

These topics might help you work with this function:

- *XNPV - chart function (page 397)*: Use this function to calculate aggregated net present value for a schedule of cash flows.
- *RangeXIRR (page 1369)*: **RangeXIRR()** is the equivalent range function for the **XIRR()** function.



*Across different versions of Qlik Sense Client-Managed, there are variations in the underlying algorithm used by this function. For more information about recent updates to the algorithm, see support article [XIRR function Fix and Update](#).*

### Example

Load script and chart expression

### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing cashflow transactions.
- Information stored in a table called `cashflow`.

### Load script

```
Cashflow:
LOAD 2013 as Year, * inline [
Date|Payments
2013-01-01|-10000
2013-03-01|3000
2013-10-30|4200
2014-02-01|6800
] (delimiter is '|');
```

### Results

#### Do the following:

Load the data and open a sheet. Create a new table and add the following calculation as a measure:

```
=XIRR(Payments, Date)
```

Results table

<b>=XIRR(Payments, Date)</b>
0.5385

### Interpreting the XIRR return value

The XIRR functionality is usually used to analyze an investment, where there is an outgoing (negative) payment in the beginning, and then a series of smaller income (positive) payments later on. Here is a simplified example with only one negative and one positive payment:

```
Cashflow:
LOAD * inline [
Date|Payments
2023-01-01|-100
2024-01-01|110
] (delimiter is '|');
```

We make an initial payment of 100 and get 110 back after exactly one year. This represents a rate of return of 10% per year. `XIRR(Payments, Date)` returns a value of 0.1.

The return value of the XIRR functionality can be positive or negative. In the case of an investment, a negative result indicates that the investment is a loss. The amount of gain or loss can be calculated simply by making a sum aggregation over the payments field.

In the example above, we are lending out our money for one year. The rate of return can be thought of as interest. It is also possible to use XIRR's functionality when you are on the other side of the transaction (for example, if you are the borrower instead of the lender).

Consider this example:

```
Cashflow:
LOAD * inline [
Date|Payments
```

```
2023-01-01|100
2024-01-01|-110
] (delimiter is '|');
```

This is the same as the first example but inverted. Here, we are borrowing 100 for one year and we repay it with a 10% interest. In this example, the XIRR calculation returns 0.1 (10%), the same value as the first example.

Note that in the first example, we received a profit of 10, and in the second example, we experienced a loss of 10, but the return value of the XIRR functionality is positive for both these examples. This is because the XIRR functionality calculates the hidden interest in the transaction, regardless of which side you are on in the transaction.

### Limitations with multiple solutions

Qlik's XIRR functionality is defined by the following equation, in which the `rate` value is solved:

```
XNPV(Rate, pmt, date) = 0
```

It is sometimes possible for this equation to have more than one solution. This is known as the “multiple-IRR problem”, and is caused by a non-normal cash flow stream (also called an unconventional cash flow). The following load script shows an example of this:

```
Cashflow:
LOAD * inline [
Date|Payments
2021-01-01|-200
2022-01-01|500
2023-01-01|-250
] (delimiter is '|');
```




In this example, there is one negative solution and one positive solution (`rate = -0.3` and `rate = 0.8`). **XIRR()** will return 0.8.

When Qlik's XIRR functionality searches for a solution, it starts at `rate = 0` and increases the rate in steps until it finds a solution. If there is more than one positive solution, it will return the first one that it encounters. If it cannot find a positive solution, it will reset the `rate` back to zero and start searching for a solution in the negative direction.

Note that a “normal” cash flow stream is guaranteed to have only one solution. “Normal” cash flow stream means that all payments with the same sign (positive or negative) are in a continuous group.

---

### See also:

-  [IRR - chart function \(page 374\)](#)
-  [Aggr - chart function \(page 549\)](#)
-  [XIRR function Fix and Update](#)

### XNPV

**XNPV()** returns the aggregated net present value for a schedule of cashflows (not necessarily periodic) represented by paired numbers in **pmt** and **date**. All payments are discounted based on a 365-day year.

### Syntax:

**XNPV**(discount\_rate, pmt, date)

**Return data type:** numeric



By default, the result will be formatted as currency.

The formula to calculate XNPV is shown below:

*XNPV aggregation formula*

$$XNPV = \sum_{i=1}^n \frac{P_i}{(1+rate)^{(d_i-d_1)/365}}$$

where:


- $P_i$  = Net cash inflow-outflows during a single period  $i$
- $d_1$  = the first payment date
- $d_i$  = the  $i^{\text{th}}$  payment date
- $rate$  = discount rate

Net present value, or NPV, is used to calculate the current total value of a future stream of cash flows given a discount rate. To calculate XNPV, we need to estimate future cash flows with corresponding dates. After this, for each payment, we apply the compounded discount rate based on the date of the payment.

Performing the XNPV aggregation over a series of payments is similar to performing a Sum aggregation over those payments. The difference is that each amount is modified (or “discounted”) according to the chosen discount rate (similar to interest rate) and how far into the future the payment is. Performing XNPV with the **discount\_rate** parameter set to zero will make XNPV equivalent to a Sum operation (the payments will not be modified before being summed). In general, the closer the **discount\_rate** is set to zero, the more similar the XNPV result will be to that of a Sum aggregation.

### Arguments

Argument	Description
discount_rate	<b>discount_rate</b> is the yearly rate that the payments should be discounted by. A value of 0.1 would indicate a 10% discount rate.

Argument	Description
pmt	<p>Payments. The expression or field containing the cash flows corresponding to the payment schedule given in <b>date</b>. Positive values are assumed to be inflows, and negative values are assumed to be outflows.</p> <div style="border: 1px solid #ccc; padding: 10px; margin-top: 10px;"> <p> <b>XNPV()</b> does not discount the initial cash flow since it will always happen on the start date. Subsequent payments are discounted based on a 365-day year. This is different from <b>NPV()</b>, where also the first payment is discounted.</p> </div>
date	<p>The expression or field containing the schedule of dates corresponding to the cash flow payments given in <b>pmt</b>. The first value is used as the start date for calculating the time offsets for future cashflows.</p>

When working with this function, the following limitations apply:

- Text values, NULL values and missing values in any or both pieces of a data-pair result in the entire data-pair being disregarded.

When to use it

- `XNPV()` is used in financial modeling for calculating the net present value (NPV) of an investment opportunity.
- Due to its higher precision, XNPV is preferred over NPV, for all types of financial models.

Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET dateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

Example 1 – Single payment (script)

Load script and results

### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:



- A dataset of one project and its cashflow for one year, in a table named `CashFlow`. The initial date for calculation is set to July 1, 2022, with a net cashflow of 0. After one year, a cashflow of \$1000 occurs.
- A resident load from the `CashFlow` table, which is used to calculate the `XNPV` field for the project in a table named `XNPV`.
- A hard-coded discount rate of 10% (0.1) is used in the `XNPV` calculation.
- A `Group By` statement is used to group all the payments for the project.

### Load script

```
CashFlow:
Load
*
Inline
[
PrjId, Dates, Values
1, '07/01/2022', 0
1, '07/01/2023', 1000
];

XNPV:
Load
    PrjId,
    XNPV(0.1, Values, Dates) as XNPV //Discount Rate of 10%
Resident CashFlow
Group By PrjId;
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- `PrjId`
- `XNPV`

Results table

<b>PrjId</b>	<b>XNPV</b>
1	\$909.09

As per the formula, the `XNPV` value for the first record is 0, and for the second record, the `XNPV` value is \$909.09. Thus, the total `XNPV` is \$909.09.

### Example 2 – Multiple payments (script)

Load script and results

### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset of one project and its cashflow for one year, in a table named `CashFlow`.
- A resident load from the `CashFlow` table, which is used to calculate the `XNPV` field for the project in a table named `XNPV`.
- A hard-coded discount rate of 10% (0.1) is used in the XNPV calculation.
- A `Group By` statement is used to group all the payments for the project.

### Load script

```
CashFlow:
Load
*
Inline
[
PrjId,Dates,Values
1, '07/01/2022',0
1, '07/01/2024',500
1, '07/01/2023',1000
];

XNPV:
Load
    PrjId,
    XNPV(0.1,Values,Dates) as XNPV //Discount Rate of 10%
Resident CashFlow
Group By PrjId;
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- `PrjId`
- `XNPV`

Results table

PrjId	XNPV
1	\$1322.21

In this example, a payment of \$1000 is received at the end of first year, and a payment of \$500 is received at the end of second year. With a discount rate of 10% per period, the effective XNPV is equal to \$1322.21.

Note that only the first row of data should refer to the base date for calculations. For rest of the rows, order is not important, since the date parameter is used to calculate the elapsed period.

### Example 3 – Multiple payments and irregular cashflows (script)

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- Discount rates for two projects in a table named `Project`.
- Cashflows for multiple periods for each project by project ID and Dates. The `Dates` field is used to calculate the duration for which discount rate is applied to the cash flow. Apart from the first record (initial cashflow and date), order of records is not important, and changing it should not impact the calculations.
- Using a combination of `NoConcatenate`, Resident loads, and the `Left Join` function, a temporary table, `tmpNPV`, is created that combines the records of the `Project` and `CashFlow` tables in one flat table. This table will have discount rates repeated for each cashflow.
- A resident load from the `tmpNPV` table, which is used to calculate the `xNPV` field for each project in a table named `xNPV`.
- The single value discount rate associated to each project is fetched using the `only()` function and is used in the `xNPV` calculation for each project.
- A `Group By` statement, grouping by project ID, is used to group all the payments and corresponding dates for each project.
- To avoid any synthetic or redundant data being loaded into the data model, the `tmpxNPV` table is dropped at the end of the script.

#### Load script

```
Project:
Load * inline [
PrjId,Discount_Rate
1,0.1
2,0.15
];
```

```
CashFlow:
Load
*
inline
[
PrjId,Dates,Values
1,'07/01/2021',0
1,'07/01/2022',1000
1,'07/01/2023',1000
2,'07/01/2020',0
2,'07/01/2023',500
2,'07/01/2024',1000
2,'07/01/2022',500
];
```

```
tmpXNPV:
NoConcatenate Load *
Resident Project;
Left Join
Load *
Resident CashFlow;

XNPV:
Load
    PrjId,
    XNPV(Only(Discount_Rate),Values,Dates) as XNPV //Discount Rate will be 10% for Project 1 and
15% for Project 2
Resident tmpXNPV
Group By PrjId;

Drop table tmpXNPV;
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- PrjId
- XNPV

Results table








PrjId	XNPV
1	\$1735.54
2	\$278.36

Project ID 1 has an initial cashflow of \$0 on July 1, 2021. There are two payments of \$1000 to be received at the end of two subsequent years, at a discount rate of 10% per period. Therefore, the effective XNPV is equal to \$1735.54.

Project ID 2 has an initial outflow of \$1000 (thus the negative sign) on July 1, 2020. After two years, a payment of \$500 is expected. After 3 years, another \$500 payment is expected. Finally, on July 1, 2024, a payment of \$1000 is expected. With the discount rate of 15%, the effective XNPV is equal to \$278.36.

---

### See also:

-  [Drop table \(page 150\)](#)
-  [group by \(page 160\)](#)
-  [Join \(page 71\)](#)
-  [Max \(page 339\)](#)
-  [NoConcatenate \(page 89\)](#)
-  [NPV - chart function \(page 382\)](#)
-  [Only \(page 349\)](#)

### XNPV - chart function

**XNPV()** returns the aggregated net present value for a schedule of cash flows (not necessarily periodic) represented by paired numbers in the expressions given by **pmt** and **date**, iterated over the chart dimensions. All payments are discounted based on a 365-day year.

#### Syntax:

```
XNPV ([TOTAL [<fld{,fld}>]] discount_rate, pmt, date)
```

**Return data type:** numeric



*By default, the result will be formatted as currency.*

The formula to calculate XNPV is shown below:

*XNPV aggregation formula*

$$XNPV = \sum_{i=1}^n \frac{P_i}{(1+rate)^{(d_i-d_1)/365}}$$


where:

- $P_i$  = Net cash inflow-outflows during a single period  $i$
- $d_1$  = the first payment date
- $d_i$  = the  $i^{\text{th}}$  payment date
- $rate$  = discount rate

Net present value, or NPV, is used to calculate the current total value of a future stream of cash flows given a discount rate. To calculate XNPV, we need to estimate future cash flows with corresponding dates. After this, for each payment, we apply the compounded discount rate based on the date of the payment.

Performing the XNPV aggregation over a series of payments is similar to performing a Sum aggregation over those payments. The difference is that each amount is modified (or “discounted”) according to the chosen discount rate (similar to interest rate) and how far into the future the payment is. Performing XNPV with the **discount\_rate** parameter set to zero will make XNPV equivalent to a Sum operation (the payments will not be modified before being summed). In general, the closer the **discount\_rate** is set to zero, the more similar the XNPV result will be to that of a Sum aggregation.

### Arguments

Argument	Description
discount_rate	<b>discount_rate</b> is the yearly rate that the payments should be discounted by. A value of 0.1 would indicate a 10% discount rate.
pmt	Payments. The expression or field containing the cash flows corresponding to the payment schedule given in <b>date</b> . Positive values are assumed to be inflows, and negative values are assumed to be outflows.  <div style="border: 1px solid #ccc; padding: 5px; margin-top: 10px;">  <b>XNPV()</b> does not discount the initial cash flow since it will always happen on the start date. Subsequent payments are discounted based on a 365-day year. This is different from <b>NPV()</b>, where also the first payment is discounted.         </div>
date	The expression or field containing the schedule of dates corresponding to the cash flow payments given in <b>pmt</b> . The first value is used as the start date for calculating the time offsets for future cash flows.
TOTAL	If the word <b>TOTAL</b> occurs before the function arguments, the calculation is made over all possible values given the current selections, and not just those that pertain to the current dimensional value, that is, it disregards the chart dimensions.  By using <b>TOTAL [&lt;fld {fld}&gt;]</b> , where the <b>TOTAL</b> qualifier is followed by a list of one or more field names as a subset of the chart dimension variables, you create a subset of the total possible values.

When working with this function, the following limitations apply:

- **discount\_rate**, **pmt** and **date** must not contain aggregation functions, unless these inner aggregations contain the **TOTAL** or **ALL** qualifiers. For more advanced nested aggregations, use the advanced function **Aggr**, in combination with a specified dimension.
- Text values, NULL values and missing values in any or both pieces of a data-pair result in the entire data-pair being disregarded.

When to use it

- **XNPV()** is used in financial modeling for calculating the net present value (NPV) of an investment opportunity.
- Due to its higher precision, **XNPV** is preferred over **NPV**, for all types of financial models.

Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

## 8 Script and chart functions

---

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Example

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing cashflow transactions.
- Information stored in a table called `cashflow`.

#### Load script

```
Cashflow:
LOAD 2013 as Year, * inline [
Date|Payments
2013-01-01|-10000
2013-03-01|3000
2013-10-30|4200
2014-02-01|6800
] (delimiter is '|');
```

#### Results

##### Do the following:



Load the data and open a sheet. Create a new table and add the following calculation as a measure:

```
=XNPV(0.09, Payments, Date)
```

Results table

<b>=XNPV(0.09, Payments, Date)</b>
\$3062.49

#### See also:

-  [NPV - chart function \(page 382\)](#)
-  [Aggr - chart function \(page 549\)](#)

### Statistical aggregation functions

Each function is described further after the overview. You can also click the function name in the syntax to immediately access the details for that specific function.

#### Statistical aggregation functions in the data load script

The following statistical aggregation functions can be used in scripts.

##### **Avg**

**Avg()** finds the average value of the aggregated data in the expression over a number of records as defined by a **group by** clause.

```
Avg ([distinct] expression)
```

##### **Correl**

**Correl()** returns the aggregated correlation coefficient for a series of coordinates represented by paired numbers in x-expression and y-expression iterated over a number of records as defined by a **group by** clause.

```
Correl (x-expression, y-expression)
```

##### **Fractile**

**Fractile()** finds the value that corresponds to the inclusive fractile (quantile) of the aggregated data in the expression over a number of records as defined by a **group by** clause.

```
Fractile (expression, fractile)
```

##### **FractileExc**

**FractileExc()** finds the value that corresponds to the exclusive fractile (quantile) of the aggregated data in the expression over a number of records as defined by a **group by** clause.

```
FractileExc (expression, fractile)
```

##### **Kurtosis**

**Kurtosis()** returns the kurtosis of the data in the expression over a number of records as defined by a **group by** clause.

```
Kurtosis ([distinct ] expression )
```

##### **LINEST\_B**

**LINEST\_B()** returns the aggregated b value (y-intercept) of a linear regression defined by the equation  $y=mx+b$  for a series of coordinates represented by paired numbers in x-expression and y-expression iterated over a number of records as defined by a **group by** clause.

```
LINEST_B (y-expression, x-expression [, y0 [, x0 ]])
```



### **LINEST\_df**

**LINEST\_DF()** returns the aggregated degrees of freedom of a linear regression defined by the equation  $y=mx+b$  for a series of coordinates represented by paired numbers in x-expression and y-expression iterated over a number of records as defined by a **group by** clause.

```
LINEST_DF (y-expression, x-expression [, y0 [, x0 ]])
```

### **LINEST\_f**

This script function returns the aggregated F statistic ( $r^2/(1-r^2)$ ) of a linear regression defined by the equation  $y=mx+b$  for a series of coordinates represented by paired numbers in x-expression and y-expression iterated over a number of records as defined by a **group by** clause.

```
LINEST_F (y-expression, x-expression [, y0 [, x0 ]])
```

### **LINEST\_m**

**LINEST\_M()** returns the aggregated m value (slope) of a linear regression defined by the equation  $y=mx+b$  for a series of coordinates represented by paired numbers in x-expression and y-expression iterated over a number of records as defined by a **group by** clause.

```
LINEST_M (y-expression, x-expression [, y0 [, x0 ]])
```

### **LINEST\_r2**

**LINEST\_R2()** returns the aggregated  $r^2$  value (coefficient of determination) of a linear regression defined by the equation  $y=mx+b$  for a series of coordinates represented by paired numbers in x-expression and y-expression iterated over a number of records as defined by a **group by** clause.

```
LINEST_R2 (y-expression, x-expression [, y0 [, x0 ]])
```

### **LINEST\_seb**

**LINEST\_SEB()** returns the aggregated standard error of the b value of a linear regression defined by the equation  $y=mx+b$  for a series of coordinates represented by paired numbers in x-expression and y-expression iterated over a number of records as defined by a **group by** clause.

```
LINEST_SEB (y-expression, x-expression [, y0 [, x0 ]])
```

### **LINEST\_sem**

**LINEST\_SEM()** returns the aggregated standard error of the m value of a linear regression defined by the equation  $y=mx+b$  for a series of coordinates represented by paired numbers in x-expression and y-expression iterated over a number of records as defined by a **group by** clause.

```
LINEST_SEM (y-expression, x-expression [, y0 [, x0 ]])
```

### **LINEST\_sey**

**LINEST\_SEY()** returns the aggregated standard error of the y estimate of a linear regression defined by the equation  $y=mx+b$  for a series of coordinates represented by paired numbers in x-expression and y-expression iterated over a number of records as defined by a **group by** clause.

```
LINEST_SEY (y-expression, x-expression [, y0 [, x0 ]])
```

### **LINEST\_ssreg**

**LINEST\_SSREG()** returns the aggregated regression sum of squares of a linear regression defined by the equation  $y=mx+b$  for a series of coordinates represented by paired numbers in x-expression and y-expression iterated over a number of records as defined by a **group by** clause.

```
LINEST_SSREG (y-expression, x-expression [, y0 [, x0 ]])
```

### **Linest\_ssresid**

**LINEST\_SSRESID()** returns the aggregated residual sum of squares of a linear regression defined by the equation  $y=mx+b$  for a series of coordinates represented by paired numbers in x-expression and y-expression iterated over a number of records as defined by a **group by** clause.

```
LINEST_SSRESID (y-expression, x-expression [, y0 [, x0 ]])
```

### **Median**

**Median()** returns the aggregated median of the values in the expression over a number of records as defined by a **group by** clause.

```
Median (expression)
```

### **Skew**

**Skew()** returns the skewness of expression over a number of records as defined by a **group by** clause.

```
Skew ([ distinct] expression)
```

### **Stdev**

**Stdev()** returns the standard deviation of the values given by the expression over a number of records as defined by a **group by** clause.

```
Stdev ([distinct] expression)
```

### **Sterr**

**Sterr()** returns the aggregated standard error (stdev/sqrt(n)) for a series of values represented by the expression iterated over a number of records as defined by a **group by** clause.

```
Sterr ([distinct] expression)
```

### **STEYX**

**STEYX()** returns the aggregated standard error of the predicted y-value for each x-value in the regression for a series of coordinates represented by paired numbers in x-expression and y-expression iterated over a number of records as defined by a **group by** clause.

```
STEYX (y-expression, x-expression)
```

## Statistical aggregation functions in chart expressions

The following statistical aggregation functions can be used in charts:

### **Avg**

**Avg()** returns the aggregated average of the expression or field iterated over the chart dimensions.

```
Avg - chart function([[SetExpression] [DISTINCT] [TOTAL [<fld{, fld}>]])  
expr)
```

Correl

**Correl()** returns the aggregated correlation coefficient for two data sets. The correlation function is a measure of the relationship between the data sets and is aggregated for (x,y) value pairs iterated over the chart dimensions.

```
Correl - chart function([[SetExpression] [TOTAL [<fld {, fld}>]]) value1,  
value2 )
```

Fractile

**Fractile()** finds the value that corresponds to the inclusive fractile (quantile) of the aggregated data in the range given by the expression iterated over the chart dimensions.

```
Fractile - chart function([[SetExpression] [TOTAL [<fld {, fld}>]]) expr,  
fraction)
```

FractileExc

**FractileExc()** finds the value that corresponds to the exclusive fractile (quantile) of the aggregated data in the range given by the expression iterated over the chart dimensions.

```
FractileExc - chart function([[SetExpression] [TOTAL [<fld {, fld}>]]) expr,  
fraction)
```

Kurtosis

**Kurtosis()** finds the kurtosis of the range of data aggregated in the expression or field iterated over the chart dimensions.

```
Kurtosis - chart function([[SetExpression] [DISTINCT] [TOTAL [<fld{, fld}>]])  
expr)
```

LINEST\_b

**LINEST\_B()** returns the aggregated b value (y-intercept) of a linear regression defined by the equation  $y=mx+b$  for a series of coordinates represented by paired numbers in the expressions given by the expressions **x\_value** and **y\_value**, iterated over the chart dimensions.

```
LINEST_R2 - chart function([[SetExpression] [TOTAL [<fld{ ,fld}>]]) y_value,  
x_value[, y0_const[, x0_const]])
```

LINEST\_df

**LINEST\_DF()** returns the aggregated degrees of freedom of a linear regression defined by the equation  $y=mx+b$  for a series of coordinates represented by paired numbers in the expressions given by **x\_value** and **y\_value**, iterated over the chart dimensions.

```
LINEST_DF - chart function([[SetExpression] [TOTAL [<fld{, fld}>]]) y_value,  
x_value [, y0_const [, x0_const]])
```

### LINEST\_f

**LINEST\_F()** returns the aggregated F statistic ( $r^2/(1-r^2)$ ) of a linear regression defined by the equation  $y=mx+b$  for a series of coordinates represented by paired numbers in the expressions given by **x\_value** and the **y\_value**, iterated over the chart dimensions.

```
LINEST_F - chart function({[SetExpression] [TOTAL [<fld{, fld}>]] } y_value, x_value [, y0_const [, x0_const]])
```

### LINEST\_m

**LINEST\_M()** returns the aggregated m value (slope) of a linear regression defined by the equation  $y=mx+b$  for a series of coordinates represented by paired numbers given by the expressions **x\_value** and **y\_value**, iterated over the chart dimensions.

```
LINEST_M - chart function({[SetExpression] [TOTAL [<fld{, fld}>]] } y_value, x_value [, y0_const [, x0_const]])
```

### LINEST\_r2

**LINEST\_R2()** returns the aggregated r2 value (coefficient of determination) of a linear regression defined by the equation  $y=mx+b$  for a series of coordinates represented by paired numbers given by the expressions **x\_value** and **y\_value**, iterated over the chart dimensions.

```
LINEST_R2 - chart function({[SetExpression] [TOTAL [<fld{, fld}>]] } y_value, x_value[, y0_const[, x0_const]])
```

### LINEST\_seb

**LINEST\_SEB()** returns the aggregated standard error of the b value of a linear regression defined by the equation  $y=mx+b$  for a series of coordinates represented by paired numbers given by the expressions **x\_value** and **y\_value**, iterated over the chart dimensions.

```
LINEST_SEB - chart function({[SetExpression] [TOTAL [<fld{, fld}>]] } y_value, x_value[, y0_const[, x0_const]])
```

### LINEST\_sem

**LINEST\_SEM()** returns the aggregated standard error of the m value of a linear regression defined by the equation  $y=mx+b$  for a series of coordinates represented by paired numbers given by the expressions **x\_value** and **y\_value**, iterated over the chart dimensions.

```
LINEST_SEM - chart function({[set_expression]} [distinct ] [total [<fld{, fld}>]] y-expression, x-expression [, y0 [, x0 ] ] )
```

### LINEST\_sey

**LINEST\_SEY()** returns the aggregated standard error of the y estimate of a linear regression defined by the equation  $y=mx+b$  for a series of coordinates represented by paired numbers given by the expressions **x\_value** and **y\_value**, iterated over the chart dimensions.

```
LINEST_SEY - chart function({[SetExpression] [TOTAL [<fld{, fld}>]] } y_value, x_value[, y0_const[, x0_const]])
```

LINEST\_ssreg

**LINEST\_SSREG()** returns the aggregated regression sum of squares of a linear regression defined by the equation  $y=mx+b$  for a series of coordinates represented by paired numbers given by the expressions **x\_value** and **y\_value**, iterated over the chart dimensions.

```
LINEST_SSREG - chart function([SetExpression] [TOTAL [<fld{ ,fld}>]] y_value, x_value[, y0_const[, x0_const]])
```

LINEST\_ssresid

**LINEST\_SSRESID()** returns the aggregated residual sum of squares of a linear regression defined by the equation  $y=mx+b$  for a series of coordinates represented by paired numbers in the expressions given by **x\_value** and **y\_value**, iterated over the chart dimensions.

```
LINEST_SSRESID - chart functionLINEST_SSRESID() returns the aggregated residual sum of squares of a linear regression defined by the equation  $y=mx+b$  for a series of coordinates represented by paired numbers in the expressions given by x_value and y_value, iterated over the chart dimensions. LINEST_SSRESID([SetExpression] [DISTINCT] [TOTAL [<fld{ ,fld}>]] y_value, x_value [, y0_const[, x0_const]]) numeric ArgumentsArgumentDescriptiony_valueThe expression or field containing the range of y-values to be measured.x_valueThe expression or field containing the range of x-values to be measured.y0, x0An optional value y0 may be stated forcing the regression line to pass through the y-axis at a given point. By stating both y0 and x0 it is possible to force the regression line to pass through a single fixed coordinate. Unless both y0 and x0 are stated, the function requires at least two valid data-pairs to calculate. If y0 and x0 are stated, a single data pair will do. SetExpressionBy default, the aggregation function will aggregate over the set of possible records defined by the selection. An alternative set of records can be defined by a set analysis expression. DISTINCTIf the word DISTINCT occurs before the function arguments, duplicates resulting from the evaluation of the function arguments are disregarded. TOTALIf the word TOTAL occurs before the function arguments, the calculation is made over all possible values given the current selections, and not just those that pertain to the current dimensional value, that is, it disregards the chart dimensions. By using TOTAL [<fld { .fld}>], where the TOTAL qualifier is followed by a list of one or more field names as a subset of the chart dimension variables, you create a subset of the total possible values.An optional value y0 may be stated forcing the regression line to pass through the y-axis at a given point. By stating both y0 and x0 it is possible to force the regression line to pass through a single fixed coordinate. The parameter of the aggregation function must not contain other aggregation functions, unless these inner aggregations contain the TOTAL qualifier. For more advanced nested aggregations, use the advanced function Aggr, in combination with a specified dimension. Text values, NULL values and missing values in any or both pieces of a data-pair result in the entire data-pair
```

being disregarded. An example of how to use `linest` functions is `avg`  
(`{[SetExpression] [TOTAL [<fld{ ,fld}>]] }y_value, x_value[, y0_const[, x0_`  
`const]]`)

Median

**Median()** returns the median value of the range of values aggregated in the expression iterated over the chart dimensions.

```
Median - chart function({[SetExpression] [TOTAL [<fld{, fld}>]]} expr)
```

**MutualInfo**

**MutualInfo** calculates the mutual information (MI) between two fields or between aggregated values in **Aggr()**.

```
MutualInfo - chart function({[SetExpression] [DISTINCT] [TOTAL target, driver
```

```
[, datatype [, breakdownbyvalue [, sample size ]]])
```

Skew

**Skew()** returns the aggregated skewness of the expression or field iterated over the chart dimensions.

```
Skew - chart function({[SetExpression] [DISTINCT] [TOTAL [<fld{ ,fld}>]]} expr)
```

Stdev

**Stdev()** finds the standard deviation of the range of data aggregated in the expression or field iterated over the chart dimensions.

```
Stdev - chart function({[SetExpression] [DISTINCT] [TOTAL [<fld{, fld}>]]} expr)
```

Sterr

**Sterr()** finds the value of the standard error of the mean, ( $stdev/\sqrt{n}$ ), for the series of values aggregated in the expression iterated over the chart dimensions.

```
Sterr - chart function({[SetExpression] [DISTINCT] [TOTAL [<fld{, fld}>]]} expr)
```

STEYX

**STEYX()** returns the aggregated standard error when predicting y-values for each x-value in a linear regression given by a series of coordinates represented by paired numbers in the expressions given by **y\_value** and **x\_value**.

```
STEYX - chart function({[SetExpression] [TOTAL [<fld{, fld}>]]} y_value, x_
```

```
value)
```

Avg

**Avg()** finds the average value of the aggregated data in the expression over a number of records as defined by a **group by** clause.

### Syntax:

```
Avg ([DISTINCT] expr)
```

**Return data type:** numeric

### Arguments:

#### Arguments

Argument	Description
expr	The expression or field containing the data to be measured.
DISTINCT	If the word <b>distinct</b> occurs before the expression, all duplicates will be disregarded.

### Examples and results:

Add the example script to your app and run it. To see the result, add the fields listed in the results column to a sheet in your app.

#### Resulting data

Example	Result
<pre>Temp: crosstable (Month, Sales) load * inline [ Customer Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Astrida 46 60 70 13 78 20 45 65 78 12 78 22 Betacab 65 56 22 79 12 56 45 24 32 78 55 15 Canutility 77 68 34 91 24 68 57 36 44 90 67 27 Divadip 36 44 90 67 27 57 68 47 90 80 94 ] (delimiter is ' ');  Avg1: LOAD Customer, Avg(Sales) as MyAverageSalesByCustomer Resident Temp Group By Customer;</pre>	<pre>Customer MyAverageSalesByCustomer Astrida 48.916667 Betacab 44.916667 Canutility 56.916667 Divadip 63.083333</pre> <p>This can be checked in the sheet by creating a table including the measure . Sum(Sales)/12</p>
<p>Given that the <b>Temp</b> table is loaded as in the previous example:</p> <pre>LOAD Customer, Avg(DISTINCT Sales) as MyAvgSalesDistinct Resident Temp Group By Customer;</pre>	<pre>Customer MyAverageSalesByCustomer Astrida 43.1 Betacab 43.909091 Canutility 55.909091 Divadip 61</pre> <p>Only the distinct values are counted. Divide the total by the number of non-duplicate values.</p>

### Avg - chart function

**Avg()** returns the aggregated average of the expression or field iterated over the chart dimensions.

### Syntax:

```
Avg ([{SetExpression}] [DISTINCT] [TOTAL [<fld{, fld}>]] expr)
```

**Return data type:** numeric

### Arguments:

#### Arguments

Argument	Description
expr	The expression or field containing the data to be measured.
SetExpression	By default, the aggregation function will aggregate over the set of possible records defined by the selection. An alternative set of records can be defined by a set analysis expression.
DISTINCT	If the word <b>DISTINCT</b> occurs before the function arguments, duplicates resulting from the evaluation of the function arguments are disregarded.
TOTAL	<p>If the word <b>TOTAL</b> occurs before the function arguments, the calculation is made over all possible values given the current selections, and not just those that pertain to the current dimensional value, that is, it disregards the chart dimensions.</p> <p>By using <b>TOTAL [&lt;fld {, fld}&gt;]</b>, where the <b>TOTAL</b> qualifier is followed by a list of one or more field names as a subset of the chart dimension variables, you create a subset of the total possible values.</p>

### Limitations:

The parameter of the aggregation function must not contain other aggregation functions, unless these inner aggregations contain the **TOTAL** qualifier. For more advanced nested aggregations, use the advanced function **Aggr**, in combination with a specified dimension.

### Examples and results:

Example table

Customer	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
Astrida	46	60	70	13	78	20	45	65	78	12	78	22
Betacab	65	56	22	79	12	56	45	24	32	78	55	15
Canutility	77	68	34	91	24	68	57	36	44	90	67	27
Divadip	57	36	44	90	67	27	57	68	47	90	80	94



### Function examples

Example	Result
Avg(Sales)	For a table including the dimension customer and the measure Avg([Sales]), if <b>Totals</b> are shown, the result is 2566.
Avg([TOTAL (Sales)])	53.458333 for all values of customer, because the TOTAL qualifier means that dimensions are disregarded.
Avg(DISTINCT (Sales))	51.862069 for the total, because using the Distinct qualifier means only unique values in sales for each customer are evaluated.

Data used in examples:


Monthnames:

```
LOAD *, Dual(MonthText,MonthNumber) as Month INLINE [
MonthText, MonthNumber
Jan, 1
Feb, 2
Mar, 3
Apr, 4
May, 5
Jun, 6
Jul, 7
Aug, 8
Sep, 9
Oct, 10
Nov, 11
Dec, 12
];
```

sales2013:

```
Crosstable (MonthText, Sales) LOAD * inline [
Customer|Jan|Feb|Mar|Apr|May|Jun|Jul|Aug|Sep|Oct|Nov|Dec
Astrida|46|60|70|13|78|20|45|65|78|12|78|22
Betacab|65|56|22|79|12|56|45|24|32|78|55|15
Canutility|77|68|34|91|24|68|57|36|44|90|67|27
Divadip|57|36|44|90|67|27|57|68|47|90|80|94
] (delimiter is '|');
```

**See also:**

 [Aggr - chart function \(page 549\)](#)

### Correl

**Correl()** returns the aggregated correlation coefficient for a series of coordinates represented by paired numbers in x-expression and y-expression iterated over a number of records as defined by a **group by** clause.

**Syntax:**

```
Correl (value1, value2)
```

**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
value1, value2	The expressions or fields containing the two sample sets for which the correlation coefficient is to be measured.

**Limitations:**

Text values, NULL values and missing values in any or both pieces of a data-pair result in the entire data-pair being disregarded.

**Examples and results:**

Add the example script to your app and run it. To see the result, add the fields listed in the results column to a sheet in your app.

Resulting data

Example	Result
<pre> salary: Load *, 1 as Grp; LOAD * inline [ "Employee name" Gender Age Salary Aiden Charles Male 20 25000 Brenda Davies Male 25 32000 Charlotte Edberg Female 45 56000 Daroush Ferrara Male 31 29000 Eunice Goldblum Female 31 32000 Freddy Halvorsen Male 25 26000 Gauri Indu Female 36 46000 Harry Jones Male 38 40000 Ian Underwood Male 40 45000 Jackie Kingsley Female 23 28000 ] (delimiter is ' ');  Correl1: LOAD Grp, Correl(Age,Salary) as Correl_ Salary Resident Salary Group By Grp; </pre>	<p>In a table with the dimension <code>correl_salary</code>, the result of the <code>Correl()</code> calculation in the data load script will be shown: 0.9270611</p>

### Correl - chart function

**Correl()** returns the aggregated correlation coefficient for two data sets. The correlation function is a measure of the relationship between the data sets and is aggregated for (x,y) value pairs iterated over the chart dimensions.

#### Syntax:

```
Correl ([{SetExpression}] [DISTINCT] [TOTAL [<fld{, fld}>]] value1, value2 )
```

**Return data type:** numeric

#### Arguments:

##### Arguments

Argument	Description
value1, value2	The expressions or fields containing the two sample sets for which the correlation coefficient is to be measured.
SetExpression	By default, the aggregation function will aggregate over the set of possible records defined by the selection. An alternative set of records can be defined by a set analysis expression.
DISTINCT	If the word <b>DISTINCT</b> occurs before the function arguments, duplicates resulting from the evaluation of the function arguments are disregarded.
TOTAL	<p>If the word <b>TOTAL</b> occurs before the function arguments, the calculation is made over all possible values given the current selections, and not just those that pertain to the current dimensional value, that is, it disregards the chart dimensions.</p> <p>By using <b>TOTAL [&lt;fld {,fld}&gt;]</b>, where the <b>TOTAL</b> qualifier is followed by a list of one or more field names as a subset of the chart dimension variables, you create a subset of the total possible values.</p>

#### Limitations:

The parameter of the aggregation function must not contain other aggregation functions, unless these inner aggregations contain the **TOTAL** qualifier. For more advanced nested aggregations, use the advanced function **Aggr**, in combination with a specified dimension.

Text values, NULL values and missing values in any or both pieces of a data-pair result in the entire data-pair being disregarded.

### Examples and results:




#### Function examples

Example	Result
<code>Correl (Age, salary)</code>	For a table including the dimension <code>Employee name</code> and the measure <code>Correl (Age, salary)</code> , the result is 0.9270611. The result is only displayed for the totals cell.
<code>Correl (TOTAL Age, salary))</code>	0.927. This and the following results are shown to three decimal places for readability.  If you create a filter pane with the dimension <code>Gender</code> , and make selections from it, you see the result 0.951 when <code>Female</code> is selected and 0.939 if <code>Male</code> is selected. This is because the selection excludes all results that do not belong to the other value of <code>Gender</code> .
<code>Correl({1} TOTAL Age, salary))</code>	0.927. Independent of selections. This is because the set expression <code>{1}</code> disregards all selections and dimensions.
<code>Correl (TOTAL &lt;Gender&gt; Age, salary))</code>	0.927 in the total cell, 0.939 for all values of <code>Male</code> , and 0.951 for all values of <code>Female</code> . This corresponds to the results from making the selections in a filter pane based on <code>Gender</code> .

#### Data used in examples:

```
salary:
LOAD * inline [
"Employee name"|Gender|Age|Salary
Aiden Charles|Male|20|25000
Brenda Davies|Male|25|32000
Charlotte Edberg|Female|45|56000
Daroush Ferrara|Male|31|29000
Eunice Goldblum|Female|31|32000
Freddy Halvorsen|Male|25|26000
Gauri Indu|Female|36|46000
Harry Jones|Male|38|40000
Ian Underwood|Male|40|45000
Jackie Kingsley|Female|23|28000
] (delimiter is '|');
```

#### See also:

-  [Aggr - chart function \(page 549\)](#)
-  [Avg - chart function \(page 407\)](#)
-  [RangeCorrel \(page 1339\)](#)

### Fractile

**Fractile()** finds the value that corresponds to the inclusive fractile (quantile) of the aggregated data in the expression over a number of records as defined by a **group by** clause.



You can use *FractileExc* (page 417) to calculate the exclusive fractile.

#### Syntax:

```
Fractile(expr, fraction)
```

**Return data type:** numeric

The function returns the value corresponding to the rank as defined by  $\text{rank} = \text{fraction} * (N-1) + 1$  where  $N$  is the number of values in *expr*. If rank is a non-integer number, an interpolation is made between the two closest values.

#### Arguments:

##### Arguments

Argument	Description
expr	The expression or field containing the data to use when calculating the fractile.
fraction	A number between 0 and 1 corresponding to the fractile (quantile expressed as a fraction) to be calculated.

#### Examples and results:

Add the example script to your app and run it. To see the result, add the fields listed in the results column to a sheet in your app.

Resulting data	
Example	Result
<pre>Table1: Crosstable (Type, Value) Load recno() as ID, * inline [ Observation Comparison 35 2 40 27 12 38 15 31 21 1 14 19 46 1 10 34 28 3 48 1 16 2 30 3 32 2 48 1 31 2 22 1 12 3 39 29 19 37 25 2 ] (delimiter is ' ');  Fractile1: LOAD Type, Fractile(Value,0.75) as MyFractile Resident Table1 Group By Type;</pre>	<p>In a table with the dimensions Type and MyFractile, the results of the Fractile() calculations in the data load script are:</p> <pre>Type MyFractile Comparison 27.5 Observation 36</pre>

## Fractile - chart function

**Fractile()** finds the value that corresponds to the inclusive fractile (quantile) of the aggregated data in the range given by the expression iterated over the chart dimensions.



*You can use FractileExc - chart function (page 418) to calculate the exclusive fractile.*

### Syntax:

```
Fractile([SetExpression] [DISTINCT] [TOTAL [<fld{, fld}>]] expr, fraction)
```

**Return data type:** numeric

The function returns the value corresponding to the rank as defined by  $\text{rank} = \text{fraction} * (N-1) + 1$  where  $N$  is the number of values in `expr`. If rank is a non-integer number, an interpolation is made between the two closest values.

### Arguments:

Arguments

Argument	Description
expr	The expression or field containing the data to use when calculating the fractile.
fraction	A number between 0 and 1 corresponding to the fractile (quantile expressed as a fraction) to be calculated.
SetExpression	By default, the aggregation function will aggregate over the set of possible records defined by the selection. An alternative set of records can be defined by a set analysis expression.
DISTINCT	If the word <b>DISTINCT</b> occurs before the function arguments, duplicates resulting from the evaluation of the function arguments are disregarded.
TOTAL	<p>If the word <b>TOTAL</b> occurs before the function arguments, the calculation is made over all possible values given the current selections, and not just those that pertain to the current dimensional value, that is, it disregards the chart dimensions.</p> <p>By using <b>TOTAL [&lt;fld {fld}&gt;]</b>, where the <b>TOTAL</b> qualifier is followed by a list of one or more field names as a subset of the chart dimension variables, you create a subset of the total possible values.</p>

### Limitations:

The parameter of the aggregation function must not contain other aggregation functions, unless these inner aggregations contain the **TOTAL** qualifier. For more advanced nested aggregations, use the advanced function **Aggr**, in combination with a specified dimension.

### Examples and results:

Example table

Customer	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
Astrida	46	60	70	13	78	20	45	65	78	12	78	22
Betacab	65	56	22	79	12	56	45	24	32	78	55	15
Canutility	77	68	34	91	24	68	57	36	44	90	67	27
Divadip	57	36	44	90	67	27	57	68	47	90	80	94

### Function examples

Example	Result
Fractile (Sales, 0.75)	For a table including the dimension customer and the measure Fractile([Sales]), if <b>Totals</b> are shown, the result is 71.75. This is the point in the distribution of values of sales that 75% of the values fall beneath.
Fractile (TOTAL Sales, 0.75))	71.75 for all values of customer, because the TOTAL qualifier means that dimensions are disregarded.
Fractile (DISTINCT Sales, 0.75)	70 for the total, because using the DISTINCT qualifier means only unique values in sales for each customer are evaluated.

### Data used in examples:

#### Monthnames:

```
LOAD *, Dual(MonthText,MonthNumber) as Month INLINE [
MonthText, MonthNumber
Jan, 1
Feb, 2
Mar, 3
Apr, 4
May, 5
Jun, 6
Jul, 7
Aug, 8
Sep, 9
Oct, 10
Nov, 11
Dec, 12
];
```

#### Sales2013:

```
Crosstable (MonthText, Sales) LOAD * inline [
Customer|Jan|Feb|Mar|Apr|May|Jun|Jul|Aug|Sep|Oct|Nov|Dec
Astrida|46|60|70|13|78|20|45|65|78|12|78|22
Betacab|65|56|22|79|12|56|45|24|32|78|55|15
Canutility|77|68|34|91|24|68|57|36|44|90|67|27
Divadip|57|36|44|90|67|27|57|68|47|90|80|94
] (delimiter is '|');
```

### See also:

 [Aggr - chart function \(page 549\)](#)



### FractileExc

**FractileExc()** finds the value that corresponds to the exclusive fractile (quantile) of the aggregated data in the expression over a number of records as defined by a **group by** clause.



You can use *Fractile* (page 413) to calculate the inclusive fractile.

#### Syntax:

```
FractileExc(expr, fraction)
```

**Return data type:** numeric

The function returns the value corresponding to the rank as defined by  $\text{rank} = \text{fraction} * (N+1)$  where  $N$  is the number of values in *expr*. If rank is a non-integer number, an interpolation is made between the two closest values.

#### Arguments:

##### Arguments

Argument	Description
expr	The expression or field containing the data to use when calculating the fractile.
fraction	A number between 0 and 1 corresponding to the fractile (quantile expressed as a fraction) to be calculated.

#### Examples and results:

Add the example script to your app and run it. To see the result, add the fields listed in the results column to a sheet in your app.

Resulting data	
Example	Result
<pre>Table1: Crosstable (Type, Value) Load recno() as ID, * inline [ Observation Comparison 35 2 40 27 12 38 15 31 21 1 14 19 46 1 10 34 28 3 48 1 16 2 30 3 32 2 48 1 31 2 22 1 12 3 39 29 19 37 25 2 ] (delimiter is ' ');  Fractile1: LOAD Type, FractileExc(Value,0.75) as MyFractile Resident Table1 Group By Type;</pre>	<p>In a table with the dimensions Type and MyFractile, the results of the FractileExc() calculations in the data load script are:</p> <pre>Type MyFractile Comparison 28.5 Observation 38</pre>

## FractileExc - chart function

**FractileExc()** finds the value that corresponds to the exclusive fractile (quantile) of the aggregated data in the range given by the expression iterated over the chart dimensions.



*You can use Fractile - chart function (page 414) to calculate the inclusive fractile.*

### Syntax:

```
FractileExc([{SetExpression}] [DISTINCT] [TOTAL [<fld{, fld}>]] expr,
fraction)
```

**Return data type:** numeric

The function returns the value corresponding to the rank as defined by  $\text{rank} = \text{fraction} * (N+1)$  where  $N$  is the number of values in `expr`. If rank is a non-integer number, an interpolation is made between the two closest values.

### Arguments:

Arguments

Argument	Description
expr	The expression or field containing the data to use when calculating the fractile.
fraction	A number between 0 and 1 corresponding to the fractile (quantile expressed as a fraction) to be calculated.
SetExpression	By default, the aggregation function will aggregate over the set of possible records defined by the selection. An alternative set of records can be defined by a set analysis expression.
DISTINCT	If the word <b>DISTINCT</b> occurs before the function arguments, duplicates resulting from the evaluation of the function arguments are disregarded.
TOTAL	<p>If the word <b>TOTAL</b> occurs before the function arguments, the calculation is made over all possible values given the current selections, and not just those that pertain to the current dimensional value, that is, it disregards the chart dimensions.</p> <p>By using <b>TOTAL [&lt;fld {fld}&gt;]</b>, where the <b>TOTAL</b> qualifier is followed by a list of one or more field names as a subset of the chart dimension variables, you create a subset of the total possible values.</p>

### Limitations:

The parameter of the aggregation function must not contain other aggregation functions, unless these inner aggregations contain the **TOTAL** qualifier. For more advanced nested aggregations, use the advanced function **Aggr**, in combination with a specified dimension.

### Examples and results:

Example table

Customer	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
Astrida	46	60	70	13	78	20	45	65	78	12	78	22
Betacab	65	56	22	79	12	56	45	24	32	78	55	15
Canutility	77	68	34	91	24	68	57	36	44	90	67	27
Divadip	57	36	44	90	67	27	57	68	47	90	80	94

### Function examples

Example	Result
FractileExc (Sales, 0.75)	For a table including the dimension customer and the measure FractileExc ([Sales]), if <b>Totals</b> are shown, the result is 75.25. This is the point in the distribution of values of sales that 75% of the values fall beneath.
FractileExc (TOTAL Sales, 0.75))	75.25 for all values of customer, because the TOTAL qualifier means that dimensions are disregarded.
FractileExc (DISTINCT sales, 0.75)	73.50 for the total, because using the DISTINCT qualifier means only unique values in sales for each customer are evaluated.

Data used in examples:

Monthnames:

```
LOAD *, Dual(MonthText,MonthNumber) as Month INLINE [
MonthText, MonthNumber
Jan, 1
Feb, 2
Mar, 3
Apr, 4
May, 5
Jun, 6
Jul, 7
Aug, 8
Sep, 9
Oct, 10
Nov, 11
Dec, 12
];
```

Sales2013:

```
Crosstable (MonthText, Sales) LOAD * inline [
Customer|Jan|Feb|Mar|Apr|May|Jun|Jul|Aug|Sep|Oct|Nov|Dec
Astrida|46|60|70|13|78|20|45|65|78|12|78|22
Betacab|65|56|22|79|12|56|45|24|32|78|55|15
Canutility|77|68|34|91|24|68|57|36|44|90|67|27
Divadip|57|36|44|90|67|27|57|68|47|90|80|94
] (delimiter is '|');
```

**See also:**

 [Aggr - chart function \(page 549\)](#)

### Kurtosis

**Kurtosis()** returns the kurtosis of the data in the expression over a number of records as defined by a **group by** clause.

**Syntax:**

```
Kurtosis([distinct ] expr )
```

**Return data type:** numeric**Arguments:**

## Arguments

Argument	Description
expr	The expression or field containing the data to be measured.
distinct	If the word <b>distinct</b> occurs before the expression, all duplicates will be disregarded.

**Examples and results:**

Add the example script to your app and run it. To see the result, add the fields listed in the results column to a sheet in your app.

### Resulting data

Example	Result
<pre>Table1: Crosstable (Type, Value) Load recno() as ID, * inline [ Observation Comparison 35 2 40 27 12 38 15 31 21 1 14 19 46 1 10 34 28 3 48 1 16 2 30 3 32 2 48 1 31 2 22 1 12 3 39 29 19 37 25 2 ] (delimiter is ' ');  Kurtosis1: LOAD Type, Kurtosis(Value) as MyKurtosis1, Kurtosis(DISTINCT Value) as MyKurtosis2 Resident Table1 Group By Type;</pre>	<p>In a table with the dimensions Type, MyKurtosis1, and MyKurtosis2, the results of the Kurtosis() calculations in the data load script are:</p> <pre>Type MyKurtosis1 MyKurtosis2 Comparison -1.1612957 -1.4982366 Observation -1.1148768 -0.93540144</pre>

### Kurtosis - chart function

**Kurtosis()** finds the kurtosis of the range of data aggregated in the expression or field iterated over the chart dimensions.

#### Syntax:

```
Kurtosis ([{SetExpression}] [DISTINCT] [TOTAL [<fld{, fld}>]] expr)
```

**Return data type:** numeric

#### Arguments:

#### Arguments

Argument	Description
expr	The expression or field containing the data to be measured.

Argument	Description
SetExpression	By default, the aggregation function will aggregate over the set of possible records defined by the selection. An alternative set of records can be defined by a set analysis expression.
DISTINCT	If the word <b>DISTINCT</b> occurs before the function arguments, duplicates resulting from the evaluation of the function arguments are disregarded.
TOTAL	<p>If the word <b>TOTAL</b> occurs before the function arguments, the calculation is made over all possible values given the current selections, and not just those that pertain to the current dimensional value, that is, it disregards the chart dimensions.</p> <p>By using <b>TOTAL [&lt;fld {fld}&gt;]</b>, where the <b>TOTAL</b> qualifier is followed by a list of one or more field names as a subset of the chart dimension variables, you create a subset of the total possible values.</p>

### Limitations:

The parameter of the aggregation function must not contain other aggregation functions, unless these inner aggregations contain the **TOTAL** qualifier. For more advanced nested aggregations, use the advanced function **Aggr**, in combination with a specified dimension.

### Examples and results:

Example table

Type	Value																			
Comparison	2	2	3	3	1	1	1	3	3	1	2	3	2	1	2	1	3	2	3	2
Observation	35	4	1	1	2	1	4	1	2	4	1	3	3	4	3	2	1	3	1	2
		0	2	5	1	4	6	0	8	8	6	0	2	8	1	2	2	9	9	5

Function examples

Example	Result
kurtosis (value)	For a table including the dimension type and the measure kurtosis(value), if <b>Totals</b> are shown for the table, and number formatting is set to 3 significant figures, the result is 1.252. For comparison it is 1.161 and for observation it is 1.115.
kurtosis (TOTAL value)	1.252 for all values of type, because the TOTAL qualifier means that dimensions are disregarded.


Data used in examples:

Table1:  
Crosstable (Type, value)

```
Load recno() as ID, * inline [
Observation|Comparison
35|2
40|27
12|38
15|31
21|1
14|19
46|1
10|34
28|3
48|1
16|2
30|3
32|2
48|1
31|2
22|1
12|3
39|29
19|37
25|2 ] (delimiter is '|');
```

---

**See also:**

 [Avg - chart function \(page 407\)](#)

### LINEST\_B

**LINEST\_B()** returns the aggregated b value (y-intercept) of a linear regression defined by the equation  $y=mx+b$  for a series of coordinates represented by paired numbers in x-expression and y-expression iterated over a number of records as defined by a **group by** clause.

**Syntax:**

```
LINEST_B (y_value, x_value[, y0 [, x0 ]])
```

**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
y_value	The expression or field containing the range of y-values to be measured.
x_value	The expression or field containing the range of x-values to be measured.




Argument	Description
y(0), x(0)	<p>An optional value y0 may be stated forcing the regression line to pass through the y-axis at a given point. By stating both y0 and x0 it is possible to force the regression line to pass through a single fixed coordinate.</p> <p>Unless both y0 and x0 are stated, the function requires at least two valid data-pairs to calculate. If y0 and x0 are stated, a single data pair will do.</p>

### Limitations:

Text values, NULL values and missing values in any or both pieces of a data-pair result in the entire data-pair being disregarded.

### See also:

 [Examples of how to use linest functions \(page 464\)](#)

## LINEST\_B - chart function

**LINEST\_B()** returns the aggregated b value (y-intercept) of a linear regression defined by the equation  $y=mx+b$  for a series of coordinates represented by paired numbers in the expressions given by the expressions **x\_value** and **y\_value**, iterated over the chart dimensions.


### Syntax:

```
LINEST_B ([{SetExpression}] [DISTINCT] [TOTAL [<fld{, fld}>]] y_value, x_value [, y0_const [ , x0_const]])
```

**Return data type:** numeric

### Arguments:

#### Arguments

Argument	Description
y_value	The expression or field containing the range of y-values to be measured.
x_value	The expression or field containing the range of x-values to be measured.
y0_const, x0_const	<p>An optional value y0 may be stated forcing the regression line to pass through the y-axis at a given point. By stating both y0 and x0 it is possible to force the regression line to pass through a single fixed coordinate.</p> <div style="border: 1px solid #ccc; padding: 10px; margin-top: 10px;"> <p> <i>Unless both y0 and x0 are stated, the function requires at least two valid data-pairs to calculate. If y0 and x0 are stated, a single data pair will do.</i></p> </div>



Argument	Description
SetExpression	By default, the aggregation function will aggregate over the set of possible records defined by the selection. An alternative set of records can be defined by a set analysis expression.
DISTINCT	If the word <b>DISTINCT</b> occurs before the function arguments, duplicates resulting from the evaluation of the function arguments are disregarded.
TOTAL	<p>If the word <b>TOTAL</b> occurs before the function arguments, the calculation is made over all possible values given the current selections, and not just those that pertain to the current dimensional value, that is, it disregards the chart dimensions.</p> <p>By using <b>TOTAL [&lt;fld {fld}&gt;]</b>, where the <b>TOTAL</b> qualifier is followed by a list of one or more field names as a subset of the chart dimension variables, you create a subset of the total possible values.</p>

### Limitations:

The parameter of the aggregation function must not contain other aggregation functions, unless these inner aggregations contain the **TOTAL** qualifier. For more advanced nested aggregations, use the advanced function **Aggr**, in combination with a specified dimension.

Text values, NULL values and missing values in any or both pieces of a data-pair result in the entire data-pair being disregarded.

### See also:

-  [Examples of how to use linest functions \(page 464\)](#)
-  [Avg - chart function \(page 407\)](#)

## LINEST\_DF

**LINEST\_DF()** returns the aggregated degrees of freedom of a linear regression defined by the equation  $y=mx+b$  for a series of coordinates represented by paired numbers in x-expression and y-expression iterated over a number of records as defined by a **group by** clause.

### Syntax:

```
LINEST_DF (y_value, x_value[, y0 [, x0 ]])
```

**Return data type:** numeric

**Arguments:**


Arguments

Argument	Description
y_value	The expression or field containing the range of y-values to be measured.
x_value	The expression or field containing the range of x-values to be measured.
y(0), x(0)	<p>An optional value y0 may be stated forcing the regression line to pass through the y-axis at a given point. By stating both y0 and x0 it is possible to force the regression line to pass through a single fixed coordinate.</p> <p>Unless both y0 and x0 are stated, the function requires at least two valid data-pairs to calculate. If y0 and x0 are stated, a single data pair will do.</p>

**Limitations:**

Text values, NULL values and missing values in any or both pieces of a data-pair result in the entire data-pair being disregarded.

**See also:**

 [Examples of how to use linest functions \(page 464\)](#)

### LINEST\_DF - chart function

**LINEST\_DF()** returns the aggregated degrees of freedom of a linear regression defined by the equation  $y=mx+b$  for a series of coordinates represented by paired numbers in the expressions given by **x\_value** and **y\_value**, iterated over the chart dimensions.

**Syntax:**


```
LINEST_DF ([{SetExpression}] [DISTINCT] [TOTAL [<fld{, fld}>]] y_value, x_value [, y0_const [, x0_const]])
```

**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
y_value	The expression or field containing the range of y-values to be measured.
x_value	The expression or field containing the range of x-values to be measured.



Argument	Description
y0, x0	<p>An optional value y0 may be stated forcing the regression line to pass through the y-axis at a given point. By stating both y0 and x0 it is possible to force the regression line to pass through a single fixed coordinate.</p> <div style="border: 1px solid #ccc; padding: 10px; margin-top: 10px;"> <p> Unless both y0 and x0 are stated, the function requires at least two valid data-pairs to calculate. If y0 and x0 are stated, a single data pair will do.</p> </div>
SetExpression	By default, the aggregation function will aggregate over the set of possible records defined by the selection. An alternative set of records can be defined by a set analysis expression.
DISTINCT	If the word <b>DISTINCT</b> occurs before the function arguments, duplicates resulting from the evaluation of the function arguments are disregarded.
TOTAL	<p>If the word <b>TOTAL</b> occurs before the function arguments, the calculation is made over all possible values given the current selections, and not just those that pertain to the current dimensional value, that is, it disregards the chart dimensions.</p> <p>By using <b>TOTAL [&lt;fld {fld}&gt;]</b>, where the <b>TOTAL</b> qualifier is followed by a list of one or more field names as a subset of the chart dimension variables, you create a subset of the total possible values.</p>

### Limitations:

The parameter of the aggregation function must not contain other aggregation functions, unless these inner aggregations contain the **TOTAL** qualifier. For more advanced nested aggregations, use the advanced function **Aggr**, in combination with a specified dimension.

Text values, NULL values and missing values in any or both pieces of a data-pair result in the entire data-pair being disregarded.

### See also:

-  [Examples of how to use linest functions \(page 464\)](#)
-  [Avg - chart function \(page 407\)](#)

### LINEST\_F

This script function returns the aggregated F statistic ( $r^2/(1-r^2)$ ) of a linear regression defined by the equation  $y=mx+b$  for a series of coordinates represented by paired numbers in x-expression and y-expression iterated over a number of records as defined by a **group by** clause.

### Syntax:

```
LINEST_F (y_value, x_value[, y0 [, x0 ]])
```

**Return data type:** numeric

### Arguments:


#### Arguments

Argument	Description
y_value	The expression or field containing the range of y-values to be measured.
x_value	The expression or field containing the range of x-values to be measured.
y(0), x(0)	An optional value y0 may be stated forcing the regression line to pass through the y-axis at a given point. By stating both y0 and x0 it is possible to force the regression line to pass through a single fixed coordinate.  Unless both y0 and x0 are stated, the function requires at least two valid data-pairs to calculate. If y0 and x0 are stated, a single data pair will do.

### Limitations:

Text values, NULL values and missing values in any or both pieces of a data-pair result in the entire data-pair being disregarded.

### See also:

 [Examples of how to use linest functions \(page 464\)](#)

### LINEST\_F - chart function

**LINEST\_F()** returns the aggregated F statistic ( $r^2/(1-r^2)$ ) of a linear regression defined by the equation  $y=mx+b$  for a series of coordinates represented by paired numbers in the expressions given by **x\_value** and the **y\_value**, iterated over the chart dimensions.

### Syntax:


```
LINEST_F ([{SetExpression}] [DISTINCT] [TOTAL [<fld{, fld}>]] y_value, x_value  
[, y0_const [, x0_const]])
```

**Return data type:** numeric

### Arguments:

#### Arguments

Argument	Description
y_value	The expression or field containing the range of y-values to be measured.



Argument	Description
x_value	The expression or field containing the range of x-values to be measured.
y0, x0	<p>An optional value y0 may be stated forcing the regression line to pass through the y-axis at a given point. By stating both y0 and x0 it is possible to force the regression line to pass through a single fixed coordinate.</p> <div style="border: 1px solid #ccc; padding: 10px; margin-top: 10px;">  <i>Unless both y0 and x0 are stated, the function requires at least two valid data-pairs to calculate. If y0 and x0 are stated, a single data pair will do.</i> </div>
SetExpression	By default, the aggregation function will aggregate over the set of possible records defined by the selection. An alternative set of records can be defined by a set analysis expression.
DISTINCT	If the word <b>DISTINCT</b> occurs before the function arguments, duplicates resulting from the evaluation of the function arguments are disregarded.
TOTAL	<p>If the word <b>TOTAL</b> occurs before the function arguments, the calculation is made over all possible values given the current selections, and not just those that pertain to the current dimensional value, that is, it disregards the chart dimensions.</p> <p>By using <b>TOTAL [&lt;fld {fld}&gt;]</b>, where the <b>TOTAL</b> qualifier is followed by a list of one or more field names as a subset of the chart dimension variables, you create a subset of the total possible values.</p>

**Limitations:**

The parameter of the aggregation function must not contain other aggregation functions, unless these inner aggregations contain the **TOTAL** qualifier. For more advanced nested aggregations, use the advanced function **Aggr**, in combination with a specified dimension.

Text values, NULL values and missing values in any or both pieces of a data-pair result in the entire data-pair being disregarded.

**See also:**

-  [Examples of how to use linest functions \(page 464\)](#)
-  [Avg - chart function \(page 407\)](#)

**LINEST\_M**

**LINEST\_M()** returns the aggregated m value (slope) of a linear regression defined by the equation  $y=mx+b$  for a series of coordinates represented by paired numbers in x-expression and y-expression iterated over a number of records as defined by a **group by** clause.

### Syntax:

```
LINEST_M (y_value, x_value[, y0 [, x0 ]])
```

**Return data type:** numeric

### Arguments:


#### Arguments

Argument	Description
y_value	The expression or field containing the range of y-values to be measured.
x_value	The expression or field containing the range of x-values to be measured.
y(0), x(0)	An optional value y0 may be stated forcing the regression line to pass through the y-axis at a given point. By stating both y0 and x0 it is possible to force the regression line to pass through a single fixed coordinate.  Unless both y0 and x0 are stated, the function requires at least two valid data-pairs to calculate. If y0 and x0 are stated, a single data pair will do.

### Limitations:

Text values, NULL values and missing values in any or both pieces of a data-pair result in the entire data-pair being disregarded.

### See also:

 [Examples of how to use linest functions \(page 464\)](#)

## LINEST\_M - chart function

**LINEST\_M()** returns the aggregated m value (slope) of a linear regression defined by the equation  $y=mx+b$  for a series of coordinates represented by paired numbers given by the expressions **x\_value** and **y\_value**, iterated over the chart dimensions.

### Syntax:


```
LINEST_M ([{SetExpression}] [DISTINCT] [TOTAL [<fld{, fld}>]] y_value, x_value  
[, y0_const [, x0_const]])
```

**Return data type:** numeric

### Arguments:

#### Arguments

Argument	Description
y_value	The expression or field containing the range of y-values to be measured.



Argument	Description
x_value	The expression or field containing the range of x-values to be measured.
y0, x0	<p>An optional value y0 may be stated forcing the regression line to pass through the y-axis at a given point. By stating both y0 and x0 it is possible to force the regression line to pass through a single fixed coordinate.</p> <div style="border: 1px solid #ccc; padding: 10px; margin-top: 10px;">  <i>Unless both y0 and x0 are stated, the function requires at least two valid data-pairs to calculate. If y0 and x0 are stated, a single data pair will do.</i> </div>
SetExpression	By default, the aggregation function will aggregate over the set of possible records defined by the selection. An alternative set of records can be defined by a set analysis expression.
DISTINCT	If the word <b>DISTINCT</b> occurs before the function arguments, duplicates resulting from the evaluation of the function arguments are disregarded.
TOTAL	<p>If the word <b>TOTAL</b> occurs before the function arguments, the calculation is made over all possible values given the current selections, and not just those that pertain to the current dimensional value, that is, it disregards the chart dimensions.</p> <p>By using <b>TOTAL [&lt;fld {fld}&gt;]</b>, where the <b>TOTAL</b> qualifier is followed by a list of one or more field names as a subset of the chart dimension variables, you create a subset of the total possible values.</p>

**Limitations:**

The parameter of the aggregation function must not contain other aggregation functions, unless these inner aggregations contain the **TOTAL** qualifier. For more advanced nested aggregations, use the advanced function **Aggr**, in combination with a specified dimension.

Text values, NULL values and missing values in any or both pieces of a data-pair result in the entire data-pair being disregarded.

**See also:**

-  [Examples of how to use linest functions \(page 464\)](#)
-  [Avg - chart function \(page 407\)](#)

**LINEST\_R2**

**LINEST\_R2()** returns the aggregated  $r^2$  value (coefficient of determination) of a linear regression defined by the equation  $y=mx+b$  for a series of coordinates represented by paired numbers in x-expression and y-expression iterated over a number of records as defined by a **group by** clause.



### Syntax:

```
LINEST_R2 (y_value, x_value[, y0 [, x0 ]])
```

**Return data type:** numeric

### Arguments:


#### Arguments

Argument	Description
y_value	The expression or field containing the range of y-values to be measured.
x_value	The expression or field containing the range of x-values to be measured.
y(0), x(0)	An optional value y0 may be stated forcing the regression line to pass through the y-axis at a given point. By stating both y0 and x0 it is possible to force the regression line to pass through a single fixed coordinate.  Unless both y0 and x0 are stated, the function requires at least two valid data-pairs to calculate. If y0 and x0 are stated, a single data pair will do.

### Limitations:

Text values, NULL values and missing values in any or both pieces of a data-pair result in the entire data-pair being disregarded.

### See also:

 [Examples of how to use linest functions \(page 464\)](#)

### LINEST\_R2 - chart function

**LINEST\_R2()** returns the aggregated r2 value (coefficient of determination) of a linear regression defined by the equation  $y=mx+b$  for a series of coordinates represented by paired numbers given by the expressions **x\_value** and **y\_value**, iterated over the chart dimensions.

### Syntax:


```
LINEST_R2 ([[SetExpression]] [DISTINCT] [TOTAL [<fld{, fld}>]] y_value, x_value[, y0_const[, x0_const]])
```

**Return data type:** numeric

### Arguments:

#### Arguments

Argument	Description
y_value	The expression or field containing the range of y-values to be measured.



Argument	Description
x_value	The expression or field containing the range of x-values to be measured.
y0, x0	<p>An optional value y0 may be stated forcing the regression line to pass through the y-axis at a given point. By stating both y0 and x0 it is possible to force the regression line to pass through a single fixed coordinate.</p> <div style="border: 1px solid gray; padding: 10px; margin-top: 10px;">  <i>Unless both y0 and x0 are stated, the function requires at least two valid data-pairs to calculate. If y0 and x0 are stated, a single data pair will do.</i> </div>
SetExpression	By default, the aggregation function will aggregate over the set of possible records defined by the selection. An alternative set of records can be defined by a set analysis expression.
DISTINCT	If the word <b>DISTINCT</b> occurs before the function arguments, duplicates resulting from the evaluation of the function arguments are disregarded.
TOTAL	<p>If the word <b>TOTAL</b> occurs before the function arguments, the calculation is made over all possible values given the current selections, and not just those that pertain to the current dimensional value, that is, it disregards the chart dimensions.</p> <p>By using <b>TOTAL [&lt;fld {fld}&gt;]</b>, where the <b>TOTAL</b> qualifier is followed by a list of one or more field names as a subset of the chart dimension variables, you create a subset of the total possible values.</p>

### Limitations:

The parameter of the aggregation function must not contain other aggregation functions, unless these inner aggregations contain the **TOTAL** qualifier. For more advanced nested aggregations, use the advanced function **Aggr**, in combination with a specified dimension.

Text values, NULL values and missing values in any or both pieces of a data-pair result in the entire data-pair being disregarded.

### See also:

-  [Examples of how to use linest functions \(page 464\)](#)
-  [Avg - chart function \(page 407\)](#)

## LINEST\_SEB

**LINEST\_SEB()** returns the aggregated standard error of the b value of a linear regression defined by the equation  $y=mx+b$  for a series of coordinates represented by paired numbers in x-expression and y-expression iterated over a number of records as defined by a **group by** clause.

### Syntax:

```
LINEST_SEB (y_value, x_value[, y0 [, x0 ]])
```

**Return data type:** numeric

### Arguments:


#### Arguments

Argument	Description
y_value	The expression or field containing the range of y-values to be measured.
x_value	The expression or field containing the range of x-values to be measured.
y(0), x(0)	An optional value y0 may be stated forcing the regression line to pass through the y-axis at a given point. By stating both y0 and x0 it is possible to force the regression line to pass through a single fixed coordinate.  Unless both y0 and x0 are stated, the function requires at least two valid data-pairs to calculate. If y0 and x0 are stated, a single data pair will do.

### Limitations:

Text values, NULL values and missing values in any or both pieces of a data-pair result in the entire data-pair being disregarded.

### See also:

 [Examples of how to use linest functions \(page 464\)](#)

## LINEST\_SEB - chart function

**LINEST\_SEB()** returns the aggregated standard error of the b value of a linear regression defined by the equation  $y=mx+b$  for a series of coordinates represented by paired numbers given by the expressions **x\_value** and **y\_value**, iterated over the chart dimensions.

### Syntax:


```
LINEST_SEB ([{SetExpression}] [DISTINCT] [TOTAL [<fld{, fld}>]] y_value, x_value[, y0_const[, x0_const])
```

**Return data type:** numeric

### Arguments:

#### Arguments

Argument	Description
y_value	The expression or field containing the range of y-values to be measured.



Argument	Description
x_value	The expression or field containing the range of x-values to be measured.
y0, x0	<p>An optional value y0 may be stated forcing the regression line to pass through the y-axis at a given point. By stating both y0 and x0 it is possible to force the regression line to pass through a single fixed coordinate.</p> <div style="border: 1px solid #ccc; padding: 10px; margin-top: 10px;">  <i>Unless both y0 and x0 are stated, the function requires at least two valid data-pairs to calculate. If y0 and x0 are stated, a single data pair will do.</i> </div>
SetExpression	By default, the aggregation function will aggregate over the set of possible records defined by the selection. An alternative set of records can be defined by a set analysis expression.
DISTINCT	If the word <b>DISTINCT</b> occurs before the function arguments, duplicates resulting from the evaluation of the function arguments are disregarded.
TOTAL	<p>If the word <b>TOTAL</b> occurs before the function arguments, the calculation is made over all possible values given the current selections, and not just those that pertain to the current dimensional value, that is, it disregards the chart dimensions.</p> <p>By using <b>TOTAL [&lt;fld {fld}&gt;]</b>, where the <b>TOTAL</b> qualifier is followed by a list of one or more field names as a subset of the chart dimension variables, you create a subset of the total possible values.</p>

**Limitations:**

The parameter of the aggregation function must not contain other aggregation functions, unless these inner aggregations contain the **TOTAL** qualifier. For more advanced nested aggregations, use the advanced function **Aggr**, in combination with a specified dimension.

Text values, NULL values and missing values in any or both pieces of a data-pair result in the entire data-pair being disregarded.

**See also:**

-  [Examples of how to use linest functions \(page 464\)](#)
-  [Avg - chart function \(page 407\)](#)

**LINEST\_SEM**

**LINEST\_SEM()** returns the aggregated standard error of the m value of a linear regression defined by the equation  $y=mx+b$  for a series of coordinates represented by paired numbers in x-expression and y-expression iterated over a number of records as defined by a **group by** clause.

### Syntax:

```
LINEST_SEM (y_value, x_value[, y0 [, x0 ]])
```

**Return data type:** numeric


### Arguments:

Argument	Description
y_value	The expression or field containing the range of y-values to be measured.
x_value	The expression or field containing the range of x-values to be measured.
y(0), x(0)	An optional value y0 may be stated forcing the regression line to pass through the y-axis at a given point. By stating both y0 and x0 it is possible to force the regression line to pass through a single fixed coordinate.  Unless both y0 and x0 are stated, the function requires at least two valid data-pairs to calculate. If y0 and x0 are stated, a single data pair will do.

### Limitations:

Text values, NULL values and missing values in any or both pieces of a data-pair result in the entire data-pair being disregarded.

### See also:

 [Examples of how to use linest functions \(page 464\)](#)

### LINEST\_SEM - chart function

**LINEST\_SEM()** returns the aggregated standard error of the m value of a linear regression defined by the equation  $y=mx+b$  for a series of coordinates represented by paired numbers given by the expressions **x\_value** and **y\_value**, iterated over the chart dimensions.

### Syntax:


```
LINEST_SEM([{SetExpression}] [DISTINCT] [TOTAL [<fld{, fld}>]] y_value, x_value[, y0_const[, x0_const])
```

**Return data type:** numeric

### Arguments:

#### Arguments

Argument	Description
y_value	The expression or field containing the range of y-values to be measured.



Argument	Description
x_value	The expression or field containing the range of x-values to be measured.
y0, x0	<p>An optional value y0 may be stated forcing the regression line to pass through the y-axis at a given point. By stating both y0 and x0 it is possible to force the regression line to pass through a single fixed coordinate.</p> <div style="border: 1px solid #ccc; padding: 10px; margin-top: 10px;">  <i>Unless both y0 and x0 are stated, the function requires at least two valid data-pairs to calculate. If y0 and x0 are stated, a single data pair will do.</i> </div>
SetExpression	By default, the aggregation function will aggregate over the set of possible records defined by the selection. An alternative set of records can be defined by a set analysis expression.
DISTINCT	If the word <b>DISTINCT</b> occurs before the function arguments, duplicates resulting from the evaluation of the function arguments are disregarded.
TOTAL	<p>If the word <b>TOTAL</b> occurs before the function arguments, the calculation is made over all possible values given the current selections, and not just those that pertain to the current dimensional value, that is, it disregards the chart dimensions.</p> <p>By using <b>TOTAL [&lt;fld {fld}&gt;]</b>, where the <b>TOTAL</b> qualifier is followed by a list of one or more field names as a subset of the chart dimension variables, you create a subset of the total possible values.</p>

**Limitations:**

The parameter of the aggregation function must not contain other aggregation functions, unless these inner aggregations contain the **TOTAL** qualifier. For more advanced nested aggregations, use the advanced function **Aggr**, in combination with a specified dimension.

Text values, NULL values and missing values in any or both pieces of a data-pair result in the entire data-pair being disregarded.

**See also:**

-  [Examples of how to use linest functions \(page 464\)](#)
-  [Avg - chart function \(page 407\)](#)

**LINEST\_SEY**

**LINEST\_SEY()** returns the aggregated standard error of the y estimate of a linear regression defined by the equation  $y=mx+b$  for a series of coordinates represented by paired numbers in x-expression and y-expression iterated over a number of records as defined by a **group by** clause.

### Syntax:

```
LINEST_SEY (y_value, x_value[, y0 [, x0 ]])
```

**Return data type:** numeric


### Arguments:

Argument	Description
y_value	The expression or field containing the range of y-values to be measured.
x_value	The expression or field containing the range of x-values to be measured.
y(0), x(0)	An optional value y0 may be stated forcing the regression line to pass through the y-axis at a given point. By stating both y0 and x0 it is possible to force the regression line to pass through a single fixed coordinate.  Unless both y0 and x0 are stated, the function requires at least two valid data-pairs to calculate. If y0 and x0 are stated, a single data pair will do.

### Limitations:

Text values, NULL values and missing values in any or both pieces of a data-pair result in the entire data-pair being disregarded.

### See also:

 [Examples of how to use linest functions \(page 464\)](#)

## LINEST\_SEY - chart function

**LINEST\_SEY()** returns the aggregated standard error of the y estimate of a linear regression defined by the equation  $y=mx+b$  for a series of coordinates represented by paired numbers given by the expressions **x\_value** and **y\_value**, iterated over the chart dimensions.

### Syntax:


```
LINEST_SEY ([{SetExpression}] [DISTINCT] [TOTAL [<fld{, fld}>]] y_value, x_value[, y0_const[, x0_const])
```

**Return data type:** numeric

### Arguments:

#### Arguments

Argument	Description
y_value	The expression or field containing the range of y-values to be measured.



Argument	Description
x_value	The expression or field containing the range of x-values to be measured.
y0, x0	<p>An optional value y0 may be stated forcing the regression line to pass through the y-axis at a given point. By stating both y0 and x0 it is possible to force the regression line to pass through a single fixed coordinate.</p> <div style="border: 1px solid #ccc; padding: 10px; margin-top: 10px;"> <p> <i>Unless both y0 and x0 are stated, the function requires at least two valid data-pairs to calculate. If y0 and x0 are stated, a single data pair will do.</i></p> </div>
SetExpression	By default, the aggregation function will aggregate over the set of possible records defined by the selection. An alternative set of records can be defined by a set analysis expression.
DISTINCT	If the word <b>DISTINCT</b> occurs before the function arguments, duplicates resulting from the evaluation of the function arguments are disregarded.
TOTAL	<p>If the word <b>TOTAL</b> occurs before the function arguments, the calculation is made over all possible values given the current selections, and not just those that pertain to the current dimensional value, that is, it disregards the chart dimensions.</p> <p>By using <b>TOTAL [&lt;fld {fld}&gt;]</b>, where the <b>TOTAL</b> qualifier is followed by a list of one or more field names as a subset of the chart dimension variables, you create a subset of the total possible values.</p>

### Limitations:

The parameter of the aggregation function must not contain other aggregation functions, unless these inner aggregations contain the **TOTAL** qualifier. For more advanced nested aggregations, use the advanced function **Aggr**, in combination with a specified dimension.

Text values, NULL values and missing values in any or both pieces of a data-pair result in the entire data-pair being disregarded.

### See also:

-  [Examples of how to use linest functions \(page 464\)](#)
-  [Avg - chart function \(page 407\)](#)

## LINEST\_SSREG

**LINEST\_SSREG()** returns the aggregated regression sum of squares of a linear regression defined by the equation  $y=mx+b$  for a series of coordinates represented by paired numbers in x-expression and y-expression iterated over a number of records as defined by a **group by** clause.



### Syntax:

```
LINEST_SSREG (y_value, x_value[, y0 [, x0 ]])
```

**Return data type:** numeric

### Arguments:


#### Arguments

Argument	Description
y_value	The expression or field containing the range of y-values to be measured.
x_value	The expression or field containing the range of x-values to be measured.
y(0), x(0)	An optional value y0 may be stated forcing the regression line to pass through the y-axis at a given point. By stating both y0 and x0 it is possible to force the regression line to pass through a single fixed coordinate.  Unless both y0 and x0 are stated, the function requires at least two valid data-pairs to calculate. If y0 and x0 are stated, a single data pair will do.

### Limitations:

Text values, NULL values and missing values in any or both pieces of a data-pair result in the entire data-pair being disregarded.

### See also:

 [Examples of how to use linest functions \(page 464\)](#)

### LINEST\_SSREG - chart function

**LINEST\_SSREG()** returns the aggregated regression sum of squares of a linear regression defined by the equation  $y=mx+b$  for a series of coordinates represented by paired numbers given by the expressions **x\_value** and **y\_value**, iterated over the chart dimensions.

### Syntax:


```
LINEST_SSREG ([{SetExpression}] [DISTINCT] [TOTAL [<fld{, fld}>]] y_value, x_value[, y0_const[, x0_const]])
```

**Return data type:** numeric

### Arguments:

#### Arguments

Argument	Description
y_value	The expression or field containing the range of y-values to be measured.



Argument	Description
x_value	The expression or field containing the range of x-values to be measured.
y0, x0	<p>An optional value y0 may be stated forcing the regression line to pass through the y-axis at a given point. By stating both y0 and x0 it is possible to force the regression line to pass through a single fixed coordinate.</p> <div style="border: 1px solid #ccc; padding: 10px; margin-top: 10px;">  <i>Unless both y0 and x0 are stated, the function requires at least two valid data-pairs to calculate. If y0 and x0 are stated, a single data pair will do.</i> </div>
SetExpression	By default, the aggregation function will aggregate over the set of possible records defined by the selection. An alternative set of records can be defined by a set analysis expression.
DISTINCT	If the word <b>DISTINCT</b> occurs before the function arguments, duplicates resulting from the evaluation of the function arguments are disregarded.
TOTAL	<p>If the word <b>TOTAL</b> occurs before the function arguments, the calculation is made over all possible values given the current selections, and not just those that pertain to the current dimensional value, that is, it disregards the chart dimensions.</p> <p>By using <b>TOTAL [&lt;fld {fld}&gt;]</b>, where the <b>TOTAL</b> qualifier is followed by a list of one or more field names as a subset of the chart dimension variables, you create a subset of the total possible values.</p>

**Limitations:**

The parameter of the aggregation function must not contain other aggregation functions, unless these inner aggregations contain the **TOTAL** qualifier. For more advanced nested aggregations, use the advanced function **Aggr**, in combination with a specified dimension.

Text values, NULL values and missing values in any or both pieces of a data-pair result in the entire data-pair being disregarded.

**See also:**

-  [Examples of how to use linest functions \(page 464\)](#)
-  [Avg - chart function \(page 407\)](#)

**LINEST\_SSRESID**

**LINEST\_SSRESID()** returns the aggregated residual sum of squares of a linear regression defined by the equation  $y=mx+b$  for a series of coordinates represented by paired numbers in x-expression and y-expression iterated over a number of records as defined by a **group by** clause.

### Syntax:

```
LINEST_SSRESID (y_value, x_value[, y0 [, x0 ]])
```

**Return data type:** numeric

### Arguments:


#### Arguments

Argument	Description
y_value	The expression or field containing the range of y-values to be measured.
x_value	The expression or field containing the range of x-values to be measured.
y(0), x(0)	An optional value y0 may be stated forcing the regression line to pass through the y-axis at a given point. By stating both y0 and x0 it is possible to force the regression line to pass through a single fixed coordinate.  Unless both y0 and x0 are stated, the function requires at least two valid data-pairs to calculate. If y0 and x0 are stated, a single data pair will do.

### Limitations:

Text values, NULL values and missing values in any or both pieces of a data-pair result in the entire data-pair being disregarded.

### See also:

 [Examples of how to use linest functions \(page 464\)](#)

## LINEST\_SSRESID - chart function

**LINEST\_SSRESID()** returns the aggregated residual sum of squares of a linear regression defined by the equation  $y=mx+b$  for a series of coordinates represented by paired numbers in the expressions given by **x\_value** and **y\_value**, iterated over the chart dimensions.

### Syntax:


```
LINEST_SSRESID ([{SetExpression}] [DISTINCT] [TOTAL [<fld{, fld}>]] y_value, x_value[, y0_const[, x0_const]])
```

**Return data type:** numeric

### Arguments:

#### Arguments

Argument	Description
y_value	The expression or field containing the range of y-values to be measured.

Argument	Description
x_value	The expression or field containing the range of x-values to be measured.
y0, x0	<p>An optional value y0 may be stated forcing the regression line to pass through the y-axis at a given point. By stating both y0 and x0 it is possible to force the regression line to pass through a single fixed coordinate.</p> <div style="border: 1px solid #ccc; padding: 10px; margin-top: 10px;"> <p> <i>Unless both y0 and x0 are stated, the function requires at least two valid data-pairs to calculate. If y0 and x0 are stated, a single data pair will do.</i></p> </div>
SetExpression	By default, the aggregation function will aggregate over the set of possible records defined by the selection. An alternative set of records can be defined by a set analysis expression.
DISTINCT	If the word <b>DISTINCT</b> occurs before the function arguments, duplicates resulting from the evaluation of the function arguments are disregarded.
TOTAL	<p>If the word <b>TOTAL</b> occurs before the function arguments, the calculation is made over all possible values given the current selections, and not just those that pertain to the current dimensional value, that is, it disregards the chart dimensions.</p> <p>By using <b>TOTAL [&lt;fld {fld}&gt;]</b>, where the <b>TOTAL</b> qualifier is followed by a list of one or more field names as a subset of the chart dimension variables, you create a subset of the total possible values.</p>



An optional value y0 may be stated forcing the regression line to pass through the y-axis at a given point. By stating both y0 and x0 it is possible to force the regression line to pass through a single fixed coordinate.

### Limitations:

The parameter of the aggregation function must not contain other aggregation functions, unless these inner aggregations contain the **TOTAL** qualifier. For more advanced nested aggregations, use the advanced function **Aggr**, in combination with a specified dimension.

Text values, NULL values and missing values in any or both pieces of a data-pair result in the entire data-pair being disregarded.

### See also:

-  [Examples of how to use linest functions \(page 464\)](#)
-  [Avg - chart function \(page 407\)](#)

## Median

**Median()** returns the aggregated median of the values in the expression over a number of records as defined by a **group by** clause.

### Syntax:

**Median** (expr)

**Return data type:** numeric

### Arguments:

#### Arguments

Argument	Description
expr	The expression or field containing the data to be measured.

### Example: Script expression using Median

Example - script expression

#### Load script

Load the following inline data and script expression in the data load editor for this example.

Table 1:

```
Load RecNo() as RowNo, Letter, Number Inline
```

```
[Letter, Number
```

```
A,1
```

```
A,3
```

```
A,4
```

```
A,9
```

```
B,2
```

```
B,8
```

```
B,9];
```

```
Median:
```

```
LOAD Letter,
```

```
Median(Number) as MyMedian
```

```
Resident Table1 Group By Letter;
```

#### Create a visualization

Create a table visualization in a Qlik Sense sheet with **Letter** and **MyMedian** as dimensions.

#### Result

Letter	MyMedian
A	3.5
B	8

#### Explanation

The median is considered the "middle" number when the numbers have been sorted in order from smallest to greatest. If the data set has an even number of values, the function returns the average of the two middle values. In this example, the median is calculated for each set of values of **A** and **B**,

which is 3.5 and 8, respectively.

### Median - chart function

**Median()** returns the median value of the range of values aggregated in the expression iterated over the chart dimensions.

#### Syntax:

```
Median([{SetExpression}] [DISTINCT] [TOTAL [<fld{, fld}>]] expr)
```

**Return data type:** numeric

#### Arguments:

Arguments

Argument	Description
expr	The expression or field containing the data to be measured.
SetExpression	By default, the aggregation function will aggregate over the set of possible records defined by the selection. An alternative set of records can be defined by a set analysis expression.
DISTINCT	If the word <b>DISTINCT</b> occurs before the function arguments, duplicates resulting from the evaluation of the function arguments are disregarded.
TOTAL	<p>If the word <b>TOTAL</b> occurs before the function arguments, the calculation is made over all possible values given the current selections, and not just those that pertain to the current dimensional value, that is, it disregards the chart dimensions.</p> <p>By using <b>TOTAL [&lt;fld {, fld}&gt;]</b>, where the <b>TOTAL</b> qualifier is followed by a list of one or more field names as a subset of the chart dimension variables, you create a subset of the total possible values.</p>

#### Limitations:

The parameter of the aggregation function must not contain other aggregation functions, unless these inner aggregations contain the **TOTAL** qualifier. For more advanced nested aggregations, use the advanced function **Aggr**, in combination with a specified dimension.

#### Example: Chart expression using Median

Example - chart expression

#### Load script

Load the following data as an inline load in the data load editor to create the chart expression example below.

```
Load RecNo() as RowNo, Letter, Number Inline
[Letter, Number
A,1
```

A, 3  
A, 4  
A, 9  
B, 2  
B, 8  
B, 9];

### Create a visualization

Create a table visualization in a Qlik Sense sheet with **Letter** as a dimension.

### Chart expression

Add the following expression to the table, as a measure:

```
Median(Number)
```

### Result

Letter	Median(Number)
Totals	4
A	3.5
B	8

### Explanation

The median is considered the "middle" number when the numbers have been sorted in order from smallest to greatest. If the data set has an even number of values, the function returns the average of the two middle values. In this example, the median is calculated for each set of values of **A** and **B**, which is 3.5 and 8, respectively.

The median for **Totals** is calculated from all values, which equals 4.

---

### See also:

[Avg - chart function \(page 407\)](#)

### MutualInfo - chart function

**MutualInfo** calculates the mutual information (MI) between two fields or between aggregated values in **Aggr()**.

**MutualInfo** returns the aggregated mutual information for two datasets. This allows key driver analysis between a field and a potential driver. Mutual information measures the relationship between the datasets and is aggregated for (x,y) pair values iterated over the chart dimensions. Mutual information is measured between 0 and 1 and can be formatted as a percentile value.

**MutualInfo** is defined by either selections or by a set expression.

**MutualInfo** allows different kinds of MI analysis:

- Pair-wise MI: Calculate the MI between a driver field and a target field.
- Driver breakdown by value: The MI is calculated between individual field values in the driver and target fields.
- Feature selection: Use **MutualInfo** in a grid chart to create a matrix where all fields are compared to each other based on MI.

**MutualInfo** does not necessarily indicate causality between fields sharing mutual information. Two fields may share mutual information, but may not be equal drivers for each other. For example, when comparing ice cream sales and outdoor temperature, **MutualInfo** will show mutual information between the two. It will not indicate if it is outdoor temperature driving ice cream sales, which is likely, or if it is ice cream sales that drives outdoor temperature, which is unlikely.

When calculating mutual information, associations affect the correspondence between and the frequency of values from fields that are from different tables.

Returned values for the same fields or selections may vary slightly. This is due to each **MutualInfo** call operating on a randomly selected sample and the inherent randomness of the **MutualInfo** algorithm.

**MutualInfo** can be applied to the **Aggr()** function.

### Syntax:

```
MutualInfo ({SetExpression} [DISTINCT] [TOTAL] field1, field2 , datatype [, breakdownbyvalue [, sample size ]])
```

**Return data type:** numeric

### Arguments:

#### Arguments

Argument	Description
field1, field2	The expressions or fields containing the two sample sets for which the mutual information to be measured.
datatype	The data types contained in the target and driver, 1 or 'dd' for discrete:discrete 2 or 'cc' for continuous:continuous 3 or 'cd' for continuous:discrete 4 or 'dc' for discrete:continuous Data types are not case sensitive.



Argument	Description
breakdownbyvalue	<p>A static value corresponding to a value in the driver. If supplied, the calculation will calculate the MI contribution for that value. You can use <b>ValueList()</b> or <b>ValueLoop()</b>. If <b>Null()</b> is added, the calculation will calculate the overall MI for all values in the driver.</p> <p>Breaking down by value requires the driver contain discrete data.</p>
samplesize	<p>The number of values to sample from the target and driver. Sampling is random. <b>MutualInfo</b> requires a minimum sample size of 80. By default, <b>MutualInfo</b> only samples up to 10,000 data-pairs as <b>MutualInfo</b> can be resource intensive. You can specify greater numbers of data-pairs in the sample size. If <b>MutualInfo</b> times out, reduce the sample size.</p>
SetExpression	<p>By default, the aggregation function will aggregate over the set of possible records defined by the selection. An alternative set of records can be defined by a set analysis expression.</p>
DISTINCT	<p>If the word <b>DISTINCT</b> occurs before the function arguments, duplicates resulting from the evaluation of the function arguments are disregarded.</p>
TOTAL	<p>If the word <b>TOTAL</b> occurs before the function arguments, the calculation is made over all possible values given the current selections, and not just those that pertain to the current dimensional value, that is, it disregards the chart dimensions.</p> <p>By using <b>TOTAL [&lt;fld {fld}&gt;]</b>, where the <b>TOTAL</b> qualifier is followed by a list of one or more field names as a subset of the chart dimension variables, you create a subset of the total possible values.</p>

### Limitations:

Text values, NULL values and missing values in any or both pieces of a data-pair result in the entire data-pair being disregarded.

### Examples and results:

Add the example script to your app and run it. To see the result, add the fields listed in the results column to a sheet in your app.

#### Function examples

Example	Result
mutualinfo (Age, salary, 1)	For a table including the dimension Employee name and the measure mutualinfo (Age, salary, 1), the result is 0.99820986. The result is only displayed for the totals cell.

Example	Result
mutualinfo (TOTAL Age, Salary, 1, null(), 81)	If you create a filter pane with the dimension Gender, and make selections from it, you see the result 0.99805677 when Female is selected and 0.99847373 if Male is selected. This is because the selection excludes all results that do not belong to the other value of Gender.
mutualinfo (TOTAL Age, Gender, 1, ValueLoop (25,35))	0.68196996. Selecting any value from Gender will change this to 0.
mutualinfo {1} TOTAL Age, Salary, 1, null()	0.99820986. This is independent of selections. The set expression {1} disregards all selections and dimensions.

Data used in examples:

```
Salary:
LOAD * inline [
"Employee name"|Age|Gender|Salary
Aiden Charles|20|Male|25000
Ann Lindquist|69|Female|58000
Anna Johansen|37|Female|36000
Anna Karlsson|42|Female|23000
Antonio Garcia|20|Male|61000
Benjamin Smith|42|Male|27000
Bill Yang|49|Male|50000
Binh Protzmann|69|Male|21000
Bob Park|51|Male|54000
Brenda Davies|25|Male|32000
Celine Gagnon|48|Female|38000
Cezar Sandu|50|Male|46000
Charles Ingvar Jönsson|27|Male|58000
Charlotte Edberg|45|Female|56000
Cindy Lynn|69|Female|28000
Clark Wayne|63|Male|31000
Daroush Ferrara|31|Male|29000
David Cooper|37|Male|64000
David Leg|58|Male|57000
Eunice Goldblum|31|Female|32000
Freddy Halvorsen|25|Male|26000
Gauri Indu|36|Female|46000
George van Zaant|59|Male|47000
Glenn Brown|58|Male|40000
Harry Jones|38|Male|40000
Helen Brolin|52|Female|66000
Hiroshi Ito|24|Male|42000
Ian Underwood|40|Male|45000
Ingrid Hendrix|63|Female|27000
Ira Baume|39|Female|39000
Jackie Kingsley|23|Female|28000
Jennica Williams|36|Female|48000
Jerry Tessel|31|Male|57000
Jim Bond|50|Male|58000
```

```
Joan Callins|60|Female|65000
Joan Cleaves|25|Female|61000
Joe Cheng|61|Male|41000
John Doe|36|Male|59000
John Lemon|43|Male|21000
Karen Helmkey|54|Female|25000
Karl Berger|38|Male|68000
Karl Straubaum|30|Male|40000
Kaya Alpan|32|Female|60000
Kenneth Finley|21|Male|25000
Leif Shine|63|Male|70000
Lennart Skoglund|63|Male|24000
Leona Korhonen|46|Female|50000
Lina André|50|Female|65000
Louis Presley|29|Male|36000
Luke Langston|50|Male|63000
Marcus Salvatori|31|Male|46000
Marie Simon|57|Female|23000
Mario Rossi|39|Male|62000
Markus Danzig|26|Male|48000
Michael Carlen|21|Male|45000
Michelle Tyson|44|Female|69000
Mike Ashkenaz|45|Male|68000
Miro Ito|40|Male|39000
Nina Mihn|62|Female|57000
Olivia Nguyen|35|Female|51000
Olivier Simenon|44|Male|31000
Östen Ärlig|68|Male|57000
Pamala Garcia|69|Female|29000
Paolo Romano|34|Male|45000
Pat Taylor|67|Female|69000
Paul Dupont|34|Male|38000
Peter Smith|56|Male|53000
Pierre Clouseau|21|Male|37000
Preben Jørgensen|35|Male|38000
Rey Jones|65|Female|20000
Ricardo Gucci|55|Male|65000
Richard Ranieri|30|Male|64000
Rob Carsson|46|Male|54000
Rolf Wesenlund|25|Male|51000
Ronaldo Costa|64|Male|39000
Sabrina Richards|57|Female|40000
Sato Hiromu|35|Male|21000
Sehoon Daw|57|Male|24000
Stefan Lind|67|Male|35000
Steve Cioazzi|58|Male|23000
Sunil Gupta|45|Male|40000
Sven Svensson|45|Male|55000
Tom Lindwall|46|Male|24000
Tomas Nilsson|27|Male|22000
Trinity Rizzo|52|Female|48000
Vanessa Lambert|54|Female|27000
] (delimiter is '|');
```

### Skew

**Skew()** returns the skewness of expression over a number of records as defined by a **group by** clause.

**Syntax:**

```
Skew([ distinct] expr)
```

**Return data type:** numeric

**Arguments:**

## Arguments

Argument	Description
expr	The expression or field containing the data to be measured.
DISTINCT	If the word <b>distinct</b> occurs before the expression, all duplicates will be disregarded.

**Examples and results:**

Add the example script to your app and run it. Then build a straight table with `type` and `MySkew` as dimensions.

### Resulting data

Example	Result
<pre>Table1: Crosstable (Type, value) Load recno() as ID, * inline [ Observation Comparison 35 2 40 27 12 38 15 31 21 1 14 19 46 1 10 34 28 3 48 1 16 2 30 3 32 2 48 1 31 2 22 1 12 3 39 29 19 37 25 2 ] (delimiter is ' ');  Skew1: LOAD Type, Skew(Value) as MySkew Resident Table1 Group By Type;</pre>	<p>The results of the Skew() calculation are:</p> <ul style="list-style-type: none"> <li>• Type is MySkew</li> <li>• Comparison is 0.86414768</li> <li>• Observation is 0.32625351</li> </ul>

### Skew - chart function

**Skew()** returns the aggregated skewness of the expression or field iterated over the chart dimensions.

#### Syntax:

```
Skew ([{SetExpression}] [DISTINCT] [TOTAL [<fld{, fld}>]] expr)
```

**Return data type:** numeric

#### Arguments:

#### Arguments

Argument	Description
expr	The expression or field containing the data to be measured.

Argument	Description
SetExpression	By default, the aggregation function will aggregate over the set of possible records defined by the selection. An alternative set of records can be defined by a set analysis expression.
DISTINCT	If the word <b>DISTINCT</b> occurs before the function arguments, duplicates resulting from the evaluation of the function arguments are disregarded.
TOTAL	<p>If the word <b>TOTAL</b> occurs before the function arguments, the calculation is made over all possible values given the current selections, and not just those that pertain to the current dimensional value, that is, it disregards the chart dimensions.</p> <p>By using <b>TOTAL [&lt;fld {fld}&gt;]</b>, where the <b>TOTAL</b> qualifier is followed by a list of one or more field names as a subset of the chart dimension variables, you create a subset of the total possible values.</p>

### Limitations:

The parameter of the aggregation function must not contain other aggregation functions, unless these inner aggregations contain the **TOTAL** qualifier. For more advanced nested aggregations, use the advanced function **Aggr**, in combination with a specified dimension.


### Examples and results:

Add the example script to your app and run it. Then build a straight table with `type` as dimension and `skew(value)` as measure.

`total`s should be enabled in the properties of the table.

Example	Result
<pre>Table1: Crosstable (Type, value) Load recno() as ID, * inline [ Observation Comparison 35 2 40 27 12 38 15 31 21 1 14 19 46 1 10 34 28 3 48 1 16 2 30 3 32 2 48 1 31 2 22 1 12 3 39 29 19 37 25 2 ] (delimiter is ' ');</pre>	<p>The results of the Skew(Value) calculation are:</p> <ul style="list-style-type: none"> <li>• Total is 0.23522195</li> <li>• Comparison is 0.86414768</li> <li>• Observation is 0.32625351</li> </ul>

**See also:**

 [Avg - chart function \(page 407\)](#)

### Stdev

**Stdev()** returns the standard deviation of the values given by the expression over a number of records as defined by a **group by** clause.

**Syntax:**

```
Stdev([distinct] expr)
```

**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
expr	The expression or field containing the data to be measured.
distinct	If the word <b>distinct</b> occurs before the expression, all duplicates will be disregarded.

### Examples and results:

Add the example script to your app and run it. Then build a straight table with `Type` and `MyStdev` as dimensions.

Resulting data

Example	Result
<pre>Table1: Crosstable (Type, value) Load recno() as ID, * inline [ Observation Comparison 35 2 40 27 12 38 15 31 21 1 14 19 46 1 10 34 28 3 48 1 16 2 30 3 32 2 48 1 31 2 22 1 12 3 39 29 19 37 25 2 ] (delimiter is ' ');  Stdev1: LOAD Type, Stdev(Value) as MyStdev Resident Table1 Group By Type;</pre>	<p>The results of the Stdev() calculation are:</p> <ul style="list-style-type: none"> <li>• <code>Type</code> is <code>MyStdev</code></li> <li>• <code>Comparison</code> is 14.61245</li> <li>• <code>observation</code> is 12.507997</li> </ul>

### Stdev - chart function

**Stdev()** finds the standard deviation of the range of data aggregated in the expression or field iterated over the chart dimensions.

#### Syntax:

```
Stdev([SetExpression] [DISTINCT] [TOTAL [<fld{, fld}>]] expr)
```



**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
expr	The expression or field containing the data to be measured.
SetExpression	By default, the aggregation function will aggregate over the set of possible records defined by the selection. An alternative set of records can be defined by a set analysis expression.
DISTINCT	If the word <b>DISTINCT</b> occurs before the function arguments, duplicates resulting from the evaluation of the function arguments are disregarded.
TOTAL	<p>If the word <b>TOTAL</b> occurs before the function arguments, the calculation is made over all possible values given the current selections, and not just those that pertain to the current dimensional value, that is, it disregards the chart dimensions.</p> <p>By using <b>TOTAL [&lt;fld {fld}&gt;]</b>, where the <b>TOTAL</b> qualifier is followed by a list of one or more field names as a subset of the chart dimension variables, you create a subset of the total possible values.</p>

**Limitations:**

The parameter of the aggregation function must not contain other aggregation functions, unless these inner aggregations contain the **TOTAL** qualifier. For more advanced nested aggregations, use the advanced function **Aggr**, in combination with a specified dimension.



**Examples and results:**

Add the example script to your app and run it. Then build a straight table with `type` as dimension and `stdev(value)` as measure.

`totals` should be enabled in the properties of the table.

Example	Result
<pre>stdev(value) Table1: Crosstable (Type, value) Load recno() as ID, * inline [ Observation Comparison 35 2 40 27 12 38 15 31 21 1 14 19 46 1 10 34 28 3 48 1 16 2 30 3 32 2 48 1 31 2 22 1 12 3 39 29 19 37 25 2 ] (delimiter is ' ');</pre>	<p>The results of the Stdev(Value) calculation are:</p> <ul style="list-style-type: none"> <li>• Total is 15.47529</li> <li>• Comparison is 14.61245</li> <li>• Observation is 12.507997</li> </ul>

**See also:**

-  [Avg - chart function \(page 407\)](#)
-  [STEYX - chart function \(page 462\)](#)

**Sterr**

**Sterr()** returns the aggregated standard error (stdev/sqrt(n)) for a series of values represented by the expression iterated over a number of records as defined by a **group by** clause.

**Syntax:**

```
Sterr ([distinct] expr)
```

**Return data type:** numeric

**Arguments:**

## Arguments

Argument	Description
expr	The expression or field containing the data to be measured.
distinct	If the word <b>distinct</b> occurs before the expression, all duplicates will be disregarded.

### Limitations:

Text values, NULL values and missing values are disregarded.

### Examples and results:

Add the example script to your app and run it. To see the result, add the fields listed in the results column to a sheet in your app.

Resulting data	
Example	Result
<pre>Table1: Crosstable (Type, value) Load recno() as ID, * inline [ Observation Comparison 35 2 40 27 12 38 15 31 21 1 14 19 46 1 10 34 28 3 48 1 16 2 30 3 32 2 48 1 31 2 22 1 12 3 39 29 19 37 25 2 ] (delimiter is ' ');  Sterr1: LOAD Type, Sterr(Value) as MySterr Resident Table1 Group By Type;</pre>	<p>In a table with the dimensions <code>Type</code> and <code>MySterr</code>, the results of the <code>Sterr()</code> calculation in the data load script are:</p> <pre>Type MySterr Comparison 3.2674431 Observation 2.7968733</pre>

### Sterr - chart function

**Sterr()** finds the value of the standard error of the mean, ( $\text{stdev}/\sqrt{n}$ ), for the series of values aggregated in the expression iterated over the chart dimensions.

### Syntax:

```
Sterr ([{SetExpression}] [DISTINCT] [TOTAL [<fld{, fld}>]] expr)
```

**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
expr	The expression or field containing the data to be measured.
SetExpression	By default, the aggregation function will aggregate over the set of possible records defined by the selection. An alternative set of records can be defined by a set analysis expression.
DISTINCT	If the word <b>DISTINCT</b> occurs before the function arguments, duplicates resulting from the evaluation of the function arguments are disregarded.
TOTAL	<p>If the word <b>TOTAL</b> occurs before the function arguments, the calculation is made over all possible values given the current selections, and not just those that pertain to the current dimensional value, that is, it disregards the chart dimensions.</p> <p>By using <b>TOTAL [&lt;fld {fld}&gt;]</b>, where the <b>TOTAL</b> qualifier is followed by a list of one or more field names as a subset of the chart dimension variables, you create a subset of the total possible values.</p>

**Limitations:**

The parameter of the aggregation function must not contain other aggregation functions, unless these inner aggregations contain the **TOTAL** qualifier. For more advanced nested aggregations, use the advanced function **Aggr**, in combination with a specified dimension.

Text values, NULL values and missing values are disregarded.

**Examples and results:**

Add the example script to your app and run it. Then build a straight table with `type` as dimension and `sterr(value)` as measure.

`totals` should be enabled in the properties of the table.

Example	Result
<pre>Table1: Crosstable (Type, value) Load recno() as ID, * inline [ Observation Comparison 35 2 40 27 12 38 15 31 21 1 14 19 46 1 10 34 28 3 48 1 16 2 30 3 32 2 48 1 31 2 22 1 12 3 39 29 19 37 25 2 ] (delimiter is ' ');</pre>	<p>The results of the Sterr(Value) calculation are:</p> <ul style="list-style-type: none"> <li>• Total is 2.4468583</li> <li>• Comparison is 3.2674431</li> <li>• Observation is 2.7968733</li> </ul>

### See also:

- [Avg - chart function \(page 407\)](#)
- [STEYX - chart function \(page 462\)](#)

### STEYX

**STEYX()** returns the aggregated standard error of the predicted y-value for each x-value in the regression for a series of coordinates represented by paired numbers in x-expression and y-expression iterated over a number of records as defined by a **group by** clause.

### Syntax:

```
STEYX (y_value, x_value)
```

**Return data type:** numeric

### Arguments:

#### Arguments

Argument	Description
y_value	The expression or field containing the range of y-values to be measured.
x_value	The expression or field containing the range of x-values to be measured.

### Limitations:

Text values, NULL values and missing values in any or both pieces of a data-pair result in the entire data-pair being disregarded.

### Examples and results:

Add the example script to your app and run it. To see the result, add the fields listed in the results column to a sheet in your app.

Resulting data

Example	Result
<pre>Trend: Load *, 1 as Grp; LOAD * inline [ Month KnownY KnownX Jan 2 6 Feb 3 5 Mar 9 11 Apr 6 7 May 8 5 Jun 7 4 Jul 5 5 Aug 10 8 Sep 9 10 Oct 12 14 Nov 15 17 Dec 14 16 ] (delimiter is ' ');  STEYX1: LOAD Grp, STEYX(KnownY, KnownX) as MySTEYX Resident Trend Group By Grp;</pre>	<p>In a table with the dimension <code>MySTEYX</code>, the result of the <code>STEYX()</code> calculation in the data load script is 2.0714764.</p>

### STEYX - chart function

**STEYX()** returns the aggregated standard error when predicting y-values for each x-value in a linear regression given by a series of coordinates represented by paired numbers in the expressions given by **y\_value** and **x\_value**.

### Syntax:

```
STEYX([{SetExpression}] [DISTINCT] [TOTAL [<fld{, fld}>]] y_value, x_value)
```

**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
y_value	The expression or field containing the range of known y-values to be measured.
x_value	The expression or field containing the range of known x-values to be measured.
SetExpression	By default, the aggregation function will aggregate over the set of possible records defined by the selection. An alternative set of records can be defined by a set analysis expression.
DISTINCT	If the word <b>DISTINCT</b> occurs before the function arguments, duplicates resulting from the evaluation of the function arguments are disregarded.
TOTAL	<p>If the word <b>TOTAL</b> occurs before the function arguments, the calculation is made over all possible values given the current selections, and not just those that pertain to the current dimensional value, that is, it disregards the chart dimensions.</p> <p>By using <b>TOTAL [&lt;fld {fld}&gt;]</b>, where the <b>TOTAL</b> qualifier is followed by a list of one or more field names as a subset of the chart dimension variables, you create a subset of the total possible values.</p>

**Limitations:**

The parameter of the aggregation function must not contain other aggregation functions, unless these inner aggregations contain the **TOTAL** qualifier. For more advanced nested aggregations, use the advanced function **Aggr**, in combination with a specified dimension.

Text values, NULL values and missing values in any or both pieces of a data-pair result in the entire data-pair being disregarded.



**Examples and results:**

Add the example script to your app and run it. Then build a straight table with `knownY` and `knownX` as dimension and `Steyx(knownY, knownX)` as measure

`total`s should be enabled in the properties of the table.

Example	Result
<pre>Trend: LOAD * inline [ Month KnownY KnownX Jan 2 6 Feb 3 5 Mar 9 11 Apr 6 7 May 8 5 Jun 7 4 Jul 5 5 Aug 10 8 Sep 9 10 Oct 12 14 Nov 15 17 Dec 14 16 ] (delimiter is ' ');</pre>	<p>The result of the STEYX(KnownY,KnownX) calculation is 2.071 (If number formatting is set to 3 decimal places.)</p>

### See also:

-  [Avg - chart function \(page 407\)](#)
-  [Sterr - chart function \(page 459\)](#)

### Examples of how to use linest functions

The linest functions are used to find values associated with linear regression analysis. This section describes how to build visualizations using sample data to find the values of the linest functions available in Qlik Sense. The linest functions can be used in the data load script and in chart expressions.

Refer to the individual linest chart function and script function topics for descriptions of syntax and arguments.

### Data and script expressions used in the examples

Load the following inline data and script expressions in the data load editor for the linest() examples below.

```
T1:
LOAD *, 1 as Grp;
LOAD * inline [
X|Y
1|0
2|1
3|3
4|8
5|14
6|20
7|0
8|50
9|25
10|60
11|38
12|19
13|26
```



```
14|143
15|98
16|27
17|59
18|78
19|158
20|279 ] (delimiter is '|');
```

```
R1:
LOAD
Grp,
linest_B(Y,X) as Linest_B,
linest_DF(Y,X) as Linest_DF,
linest_F(Y,X) as Linest_F,
linest_M(Y,X) as Linest_M,
linest_R2(Y,X) as Linest_R2,
linest_SEB(Y,X,1,1) as Linest_SEB,
linest_SEM(Y,X) as Linest_SEM,
linest_SEY(Y,X) as Linest_SEY,
linest_SSREG(Y,X) as Linest_SSREG,
linest_SSRESID(Y,X) as Linest_SSRESID
resident T1 group by Grp;
```

### Example 1: Script expressions using linest

Example: Script expressions

#### Create a visualization from the data load script calculations

Create a table visualization in a Qlik Sense sheet with the following fields as columns:

- Linest\_B
- Linest\_DF
- Linest\_F
- Linest\_M
- Linest\_R2
- Linest\_SEB
- Linest\_SEM
- Linest\_SEY
- Linest\_SSREG
- Linest\_SSRESID

#### Result

The table containing the results of the linest calculations made in the data load script should look like this:

Results table

Linest_B	Linest_DF	Linest_F	Linest_M	Linest_R2	Linest_SEB
-35.047	18	20.788	8.605	0.536	22.607

Results table

Linest_SEM	Linest_SEY	Linest_SSREG	Linest_SSRESID
1.887	48.666	49235.014	42631.186

### Example 2: Chart expressions using linest

Example: Chart expressions

Create a table visualization in a Qlik Sense sheet with the following fields as dimensions:

```
valueList('Linest_b', 'Linest_df', 'Linest_f', 'Linest_m', 'Linest_r2', 'Linest_SEB', 'Linest_SEM', 'Linest_SEY', 'Linest_SSREG', 'Linest_SSRESID')
```

This expression uses the synthetic dimensions function to create labels for the dimensions with the names of the linest functions. You can change the label to **Linest functions** to save space.

Add the following expression to the table as a measure:

```
Pick(Match(ValueList('Linest_b', 'Linest_df', 'Linest_f', 'Linest_m', 'Linest_r2', 'Linest_SEB', 'Linest_SEM', 'Linest_SEY', 'Linest_SSREG', 'Linest_SSRESID'), 'Linest_b', 'Linest_df', 'Linest_f', 'Linest_m', 'Linest_r2', 'Linest_SEB', 'Linest_SEM', 'Linest_SEY', 'Linest_SSREG', 'Linest_SSRESID'), Linest_b(Y,X), Linest_df(Y,X), Linest_f(Y,X), Linest_m(Y,X), Linest_r2(Y,X), Linest_SEB(Y,X,1,1), Linest_SEM(Y,X), Linest_SEY(Y,X), Linest_SSREG(Y,X), Linest_SSRESID(Y,X) )
```

This expression displays the value of the result of each linest function against the corresponding name in the synthetic dimension. The result of `Linest_b(Y,X)` is displayed next to **linest\_b**, and so on.

### Result

Results table


Linest functions	Linest function results
Linest_b	-35.047
Linest_df	18
Linest_f	20.788
Linest_m	8.605
Linest_r2	0.536
Linest_SEB	22.607
Linest_SEM	1.887
Linest_SEY	48.666
Linest_SSREG	49235.014
Linest_SSRESID	42631.186

### Example 3: Chart expressions using linest

Example: Chart expressions

1. Create a barchart visualization in a Qlik Sense sheet with **X** as a dimension and **Y** as a measure.
2. Add a linear trend line to the Y measure.
3. Add a KPI visualization to the sheet.
  1. Add *slope* as a label for the KPI.
  2. Add `sum(Linest_M)` as an expression for the KPI.
4. Add a second KPI visualization to the sheet.
  1. Add *intercept* as a label for the KPI.
  2. Add `sum(Linest_B)` as an expression for the KPI.
5. Add a third KPI visualization to the sheet.
  1. Add *coefficient of determination* as a label for the KPI.
  2. Add `sum(Linest_R2)` as an expression for the KPI.

### Result



### Explanation

The barchart shows the plotting of the X and Y data. Relevant `linest()` functions provide values for the linear regression equation that the trend line is based on, namely  $y = m * x + b$ . The equation uses the "least squares" method to calculate a straight line (trend line) by returning an array that describes a line that best fits the data.

The KPIs display the results of the `linest()` functions **`sum(Linest_M)`** for slope and **`sum(Linest_B)`** for the Y intercept, which are variables in the linear regression equation, and the corresponding aggregated R2 value for coefficient of determination.

### Statistical test functions

Statistical test functions can be used in both the data load script and chart expressions, but the syntax differs.

### Chi-2 test functions

Generally used in the study of qualitative variables. One can compare observed frequencies in a one-way frequency table with expected frequencies, or study the connection between two variables in a contingency table.

### T-test functions

T-test functions are used for statistical examination of two population means. A two-sample t-test examines whether two samples are different and is commonly used when two normal distributions have unknown variances and when an experiment uses a small sample size.

### Z-test functions

A statistical examination of two population means. A two sample z-test examines whether two samples are different and is commonly used when two normal distributions have known variances and when an experiment uses a large sample size.

### Chi2-test functions

Generally used in the study of qualitative variables. One can compare observed frequencies in a one-way frequency table with expected frequencies, or study the connection between two variables in a contingency table. Chi-squared test functions are used to determine whether there is a statistically significant difference between the expected frequencies and the observed frequencies in one or more groups. Often a histogram is used, and the different bins are compared to an expected distribution.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

Chi2Test\_chi2

**Chi2Test\_chi2()** returns the aggregated chi<sup>2</sup>-test value for one or two series of values.

```
Chi2Test_chi2() returns the aggregated chi2-test value for one or two series of values. (col, row, actual_value[, expected_value])
```

Chi2Test\_df

**Chi2Test\_df()** returns the aggregated chi<sup>2</sup>-test df value (degrees of freedom) for one or two series of values.

```
Chi2Test_df() returns the aggregated chi2-test df value (degrees of freedom) for one or two series of values. (col, row, actual_value[, expected_value])
```

Chi2Test\_p

**Chi2Test\_p()** returns the aggregated chi<sup>2</sup>-test p value (significance) for one or two series of values.

```
Chi2Test_p - chart function(col, row, actual_value[, expected_value])
```

### See also:

- [T-test functions \(page 471\)](#)
- [Z-test functions \(page 506\)](#)

Chi2Test\_chi2

**Chi2Test\_chi2()** returns the aggregated chi<sup>2</sup>-test value for one or two series of values.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.



All Qlik Sense chi<sup>2</sup> -test functions have the same arguments.

### Syntax:

```
Chi2Test_chi2(col, row, actual_value[, expected_value])
```

**Return data type:** numeric

### Arguments:

#### Arguments

Argument	Description
col, row	The specified column and row in the matrix of values being tested.
actual_value	The observed value of the data at the specified <b>col</b> and <b>row</b> .
expected_value	The expected value for the distribution at the specified <b>col</b> and <b>row</b> .

### Limitations:

Text values, NULL values and missing values in the expression value will result in the function returning NULL.

### Examples:

```
Chi2Test_chi2( Grp, Grade, Count )  
Chi2Test_chi2( Gender, Description, Observed, Expected )
```

### See also:

- [Examples of how to use chi2-test functions in charts \(page 522\)](#)
- [Examples of how to use chi2-test functions in the data load script \(page 525\)](#)

## Chi2Test\_df

**Chi2Test\_df()** returns the aggregated chi<sup>2</sup>-test df value (degrees of freedom) for one or two series of values.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.



All Qlik Sense chi<sup>2</sup>-test functions have the same arguments.

**Syntax:**

```
Chi2Test_df(col, row, actual_value[, expected_value])
```

**Return data type:** numeric

**Arguments:**

## Arguments

Argument	Description
col, row	The specified column and row in the matrix of values being tested.
actual_value	The observed value of the data at the specified <b>col</b> and <b>row</b> .
expected_value	The expected value for the distribution at the specified <b>col</b> and <b>row</b> .

**Limitations:**

Text values, NULL values and missing values in the expression value will result in the function returning NULL.

**Examples:**

```
Chi2Test_df( Grp, Grade, Count )
```

```
Chi2Test_df( Gender, Description, Observed, Expected )
```

**See also:**

- [Examples of how to use chi2-test functions in charts \(page 522\)](#)
- [Examples of how to use chi2-test functions in the data load script \(page 525\)](#)

## Chi2Test\_p - chart function

**Chi2Test\_p()** returns the aggregated chi<sup>2</sup>-test p value (significance) for one or two series of values. The test can be done either on the values in **actual\_value**, testing for variations within the specified **col** and **row** matrix, or by comparing values in **actual\_**

**value** with corresponding values in **expected\_value**, if specified.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.



*All Qlik Sense  $\chi^2$  -test functions have the same arguments.*

### Syntax:

```
Chi2Test_p(col, row, actual_value[, expected_value])
```

**Return data type:** numeric

### Arguments:

#### Arguments

Argument	Description
col, row	The specified column and row in the matrix of values being tested.
actual_value	The observed value of the data at the specified <b>col</b> and <b>row</b> .
expected_value	The expected value for the distribution at the specified <b>col</b> and <b>row</b> .

### Limitations:

Text values, NULL values and missing values in the expression value will result in the function returning NULL.

### Examples:

```
Chi2Test_p( Grp, Grade, Count )  
Chi2Test_p( Gender, Description, Observed, Expected )
```

### See also:

- [Examples of how to use chi2-test functions in charts \(page 522\)](#)
- [Examples of how to use chi2-test functions in the data load script \(page 525\)](#)

## T-test functions

T-test functions are used for statistical examination of two population means. A two-sample t-test examines whether two samples are different and is commonly used when two normal distributions have unknown variances and when an experiment uses a small sample size.

In the following sections, the t-test statistical test functions are grouped according to the sample student test that applies to each type of function.

*Creating a typical t-test report (page 527)*

### Two independent samples t-tests

The following functions apply to two independent samples student's t-tests.

ttest\_conf

**TTest\_conf** returns the aggregated t-test confidence interval value for two independent samples.

```
TTest_conf returns the aggregated t-test confidence interval value for two independent samples. ( grp, value [, sig[, eq_var]])
```

ttest\_df

**TTest\_df()** returns the aggregated student's t-test value (degrees of freedom) for two independent series of values.

```
TTest_df() returns the aggregated student's t-test value (degrees of freedom) for two independent series of values. (grp, value [, eq_var)
```

ttest\_dif

**TTest\_dif()** is a numeric function that returns the aggregated student's t-test mean difference for two independent series of values.

```
TTest_dif() is a numeric function that returns the aggregated student's t-test mean difference for two independent series of values. (grp, value)
```

ttest\_lower

**TTest\_lower()** returns the aggregated value for the lower end of the confidence interval for two independent series of values.

```
TTest_lower() returns the aggregated value for the lower end of the confidence interval for two independent series of values. (grp, value [, sig [, eq_var]])
```

ttest\_sig

**TTest\_sig()** returns the aggregated student's t-test 2-tailed level of significance for two independent series of values.

```
TTest_sig() returns the aggregated student's t-test 2-tailed level of significance for two independent series of values. (grp, value [, eq_var])
```

ttest\_sterr

**TTest\_sterr()** returns the aggregated student's t-test standard error of the mean difference for two independent series of values.

```
TTest_sterr() returns the aggregated student's t-test standard error of the mean difference for two independent series of values. (grp, value [, eq_var])
```



ttest\_t

**TTest\_t()** returns the aggregated t value for two independent series of values.

```
TTest_t() returns the aggregated t value for two independent series of values. (grp, value [, eq_var])
```

ttest\_upper

**TTest\_upper()** returns the aggregated value for the upper end of the confidence interval for two independent series of values.

```
TTest_upper() returns the aggregated value for the upper end of the confidence interval for two independent series of values. (grp, value [, sig [, eq_var]])
```

### Two independent weighted samples t-tests

The following functions apply to two independent samples student's t-tests where the input data series is given in weighted two-column format.

ttestw\_conf

**TTestw\_conf()** returns the aggregated t value for two independent series of values.

```
TTestw_conf() returns the aggregated t value for two independent series of values. (weight, grp, value [, sig[, eq_var]])
```

ttestw\_df

**TTestw\_df()** returns the aggregated student's t-test df value (degrees of freedom) for two independent series of values.

```
TTestw_df() returns the aggregated student's t-test df value (degrees of freedom) for two independent series of values. (weight, grp, value [, eq_var])
```

ttestw\_dif

**TTestw\_dif()** returns the aggregated student's t-test mean difference for two independent series of values.

```
TTestw_dif() returns the aggregated student's t-test mean difference for two independent series of values. ( weight, grp, value)
```

ttestw\_lower

**TTestw\_lower()** returns the aggregated value for the lower end of the confidence interval for two independent series of values.

```
TTestw_lower() returns the aggregated value for the lower end of the confidence interval for two independent series of values. (weight, grp, value [, sig[, eq_var]])
```

ttestw\_sig

**TTestw\_sig()** returns the aggregated student's t-test 2-tailed level of significance for two independent series of values.

**TTestw\_sig()** returns the aggregated student's t-test 2-tailed level of significance for two independent series of values. (weight, grp, value [, eq\_var])

ttestw\_sterr

**TTestw\_sterr()** returns the aggregated student's t-test standard error of the mean difference for two independent series of values.

**TTestw\_sterr()** returns the aggregated student's t-test standard error of the mean difference for two independent series of values. (weight, grp, value [, eq\_var])

ttestw\_t

**TTestw\_t()** returns the aggregated t value for two independent series of values.

**TTestw\_t()** returns the aggregated t value for two independent series of values. (weight, grp, value [, eq\_var])

ttestw\_upper

**TTestw\_upper()** returns the aggregated value for the upper end of the confidence interval for two independent series of values.

**TTestw\_upper()** returns the aggregated value for the upper end of the confidence interval for two independent series of values. (weight, grp, value [, sig [, eq\_var]])

### One sample t-tests

The following functions apply to one-sample student's t-tests.

ttest1\_conf

**TTest1\_conf()** returns the aggregated confidence interval value for a series of values.

**TTest1\_conf()** returns the aggregated confidence interval value for a series of values. (value [, sig])

ttest1\_df

**TTest1\_df()** returns the aggregated student's t-test df value (degrees of freedom) for a series of values.

**TTest1\_df()** returns the aggregated student's t-test df value (degrees of freedom) for a series of values. (value)

ttest1\_dif

**TTest1\_dif()** returns the aggregated student's t-test mean difference for a series of values.

**TTest1\_dif()** returns the aggregated student's t-test mean difference for a series of values. (value)

ttest1\_lower

**TTest1\_lower()** returns the aggregated value for the lower end of the confidence interval for a series of values.

```
TTest1_lower() returns the aggregated value for the lower end of the confidence interval for a series of values. (value [, sig])
```

ttest1\_sig

**TTest1\_sig()** returns the aggregated student's t-test 2-tailed level of significance for a series of values.

```
TTest1_sig() returns the aggregated student's t-test 2-tailed level of significance for a series of values. (value)
```

ttest1\_sterr

**TTest1\_sterr()** returns the aggregated student's t-test standard error of the mean difference for a series of values.

```
TTest1_sterr() returns the aggregated student's t-test standard error of the mean difference for a series of values. (value)
```

ttest1\_t

**TTest1\_t()** returns the aggregated t value for a series of values.

```
TTest1_t() returns the aggregated t value for a series of values. (value)
```

ttest1\_upper

**TTest1\_upper()** returns the aggregated value for the upper end of the confidence interval for a series of values.

```
TTest1_upper() returns the aggregated value for the upper end of the confidence interval for a series of values. (value [, sig])
```

### One weighted sample t-tests

The following functions apply to one-sample student's t-tests where the input data series is given in weighted two-column format.

ttest1w\_conf

**TTest1w\_conf()** is a **numeric** function that returns the aggregated confidence interval value for a series of values.

```
TTest1w_conf() is a numeric function that returns the aggregated confidence interval value for a series of values. (weight, value [, sig])
```

ttest1w\_df

**TTest1w\_df()** returns the aggregated student's t-test df value (degrees of freedom) for a series of values.

```
TTest1w_df() returns the aggregated student's t-test df value (degrees of freedom) for a series of values. (weight, value)
```

ttest1w\_dif

**TTest1w\_dif()** returns the aggregated student's t-test mean difference for a series of values.

```
TTest1w_dif() returns the aggregated student's t-test mean difference for a series of values. (weight, value)
```

ttest1w\_lower

**TTest1w\_lower()** returns the aggregated value for the lower end of the confidence interval for a series of values.

```
TTest1w_lower() returns the aggregated value for the lower end of the confidence interval for a series of values. (weight, value [, sig])
```

ttest1w\_sig

**TTest1w\_sig()** returns the aggregated student's t-test 2-tailed level of significance for a series of values.

```
TTest1w_sig() returns the aggregated student's t-test 2-tailed level of significance for a series of values. (weight, value)
```

ttest1w\_sterr

**TTest1w\_sterr()** returns the aggregated student's t-test standard error of the mean difference for a series of values.

```
TTest1w_sterr() returns the aggregated student's t-test standard error of the mean difference for a series of values. (weight, value)
```

ttest1w\_t

**TTest1w\_t()** returns the aggregated t value for a series of values.

```
TTest1w_t() returns the aggregated t value for a series of values. ( weight, value)
```

ttest1w\_upper

**TTest1w\_upper()** returns the aggregated value for the upper end of the confidence interval for a series of values.

```
TTest1w_upper() returns the aggregated value for the upper end of the confidence interval for a series of values. (weight, value [, sig])
```

TTest\_conf

**TTest\_conf** returns the aggregated t-test confidence interval value for two independent samples.

This function applies to independent samples student's t-tests.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

**Syntax:**

```
TTest_conf ( grp, value [, sig [, eq_var]])
```

**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
value	The sample values to be evaluated. The sample values must be logically grouped as specified by exactly two values in <b>group</b> . If a field name for the sample values is not provided in the load script, the field will automatically be named <b>Value</b> .
grp	The field containing the names of each of the two sample groups. If a field name for the group is not provided in the load script, the field will automatically be given the name <b>Type</b> .
sig	The two-tailed level of significance can be specified in <b>sig</b> . If omitted, <b>sig</b> is set to 0.025, resulting in a 95% confidence interval.
eq_var	If <b>eq_var</b> is specified as False (0), separate variances of the two samples will be assumed. If <b>eq_var</b> is specified as True (1), equal variances between the samples will be assumed.


**Limitations:**

Text values, NULL values and missing values in the expression value will result in the function returning NULL.

**Examples:**

```
TTest_conf( Group, value )
TTest_conf( Group, value, sig, false )
```

**See also:**

 [Creating a typical t-test report \(page 527\)](#)

**TTest\_df**

**TTest\_df()** returns the aggregated student's t-test value (degrees of freedom) for two independent series of values.

This function applies to independent samples student's t-tests.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

**Syntax:**

```
TTest_df (grp, value [, eq_var])
```

**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
value	The sample values to be evaluated. The sample values must be logically grouped as specified by exactly two values in <b>group</b> . If a field name for the sample values is not provided in the load script, the field will automatically be named <b>Value</b> .
grp	The field containing the names of each of the two sample groups. If a field name for the group is not provided in the load script, the field will automatically be given the name <b>Type</b> .
eq_var	If <b>eq_var</b> is specified as False (0), separate variances of the two samples will be assumed. If <b>eq_var</b> is specified as True (1), equal variances between the samples will be assumed.

**Limitations:**


Text values, NULL values and missing values in the expression value will result in the function returning NULL.

**Examples:**

```
TTest_df( Group, value )  
TTest_df( Group, value, false )
```

---

**See also:**

 [Creating a typical t-test report \(page 527\)](#)

TTest\_dif

**TTest\_dif()** is a numeric function that returns the aggregated student's t-test mean difference for two independent series of values.

This function applies to independent samples student's t-tests.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

**Syntax:**

```
TTest_dif (grp, value [, eq_var] )
```

**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
value	The sample values to be evaluated. The sample values must be logically grouped as specified by exactly two values in <b>group</b> . If a field name for the sample values is not provided in the load script, the field will automatically be named <b>Value</b> .
grp	The field containing the names of each of the two sample groups. If a field name for the group is not provided in the load script, the field will automatically be given the name <b>Type</b> .
eq_var	If <b>eq_var</b> is specified as False (0), separate variances of the two samples will be assumed. If <b>eq_var</b> is specified as True (1), equal variances between the samples will be assumed.

**Limitations:**


Text values, NULL values and missing values in the expression value will result in the function returning NULL.

**Examples:**

```
TTest_dif( Group, value )  
TTest_dif( Group, value, false )
```

---

**See also:**

 [Creating a typical t-test report \(page 527\)](#)

TTest\_lower

**TTest\_lower()** returns the aggregated value for the lower end of the confidence interval for two independent series of values.

This function applies to independent samples student's t-tests.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

**Syntax:**

```
TTest_lower (grp, value [, sig [, eq_var]])
```

**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
value	The sample values to be evaluated. The sample values must be logically grouped as specified by exactly two values in <b>group</b> . If a field name for the sample values is not provided in the load script, the field will automatically be named <b>Value</b> .
grp	The field containing the names of each of the two sample groups. If a field name for the group is not provided in the load script, the field will automatically be given the name <b>Type</b> .
sig	The two-tailed level of significance can be specified in <b>sig</b> . If omitted, <b>sig</b> is set to 0.025, resulting in a 95% confidence interval.
eq_var	If <b>eq_var</b> is specified as False (0), separate variances of the two samples will be assumed. If <b>eq_var</b> is specified as True (1), equal variances between the samples will be assumed.


**Limitations:**

Text values, NULL values and missing values in the expression value will result in the function returning NULL.

**Examples:**

```
TTest_lower( Group, value )
TTest_lower( Group, value, sig, false )
```

**See also:**

 [Creating a typical t-test report \(page 527\)](#)

**TTest\_sig**

**TTest\_sig()** returns the aggregated student's t-test 2-tailed level of significance for two independent series of values.

This function applies to independent samples student's t-tests.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

**Syntax:**

```
TTest_sig (grp, value [, eq_var])
```



**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
value	The sample values to be evaluated. The sample values must be logically grouped as specified by exactly two values in <b>group</b> . If a field name for the sample values is not provided in the load script, the field will automatically be named <b>Value</b> .
grp	The field containing the names of each of the two sample groups. If a field name for the group is not provided in the load script, the field will automatically be given the name <b>Type</b> .
eq_var	If <b>eq_var</b> is specified as False (0), separate variances of the two samples will be assumed. If <b>eq_var</b> is specified as True (1), equal variances between the samples will be assumed.

**Limitations:**


Text values, NULL values and missing values in the expression value will result in the function returning NULL.

**Examples:**

```
TTest_sig( Group, value )  
TTest_sig( Group, value, false )
```

---

**See also:**

 [Creating a typical t-test report \(page 527\)](#)

TTest\_sterr

**TTest\_sterr()** returns the aggregated student's t-test standard error of the mean difference for two independent series of values.

This function applies to independent samples student's t-tests.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

**Syntax:**

```
TTest_sterr (grp, value [, eq_var])
```

**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
value	The sample values to be evaluated. The sample values must be logically grouped as specified by exactly two values in <b>group</b> . If a field name for the sample values is not provided in the load script, the field will automatically be named <b>Value</b> .
grp	The field containing the names of each of the two sample groups. If a field name for the group is not provided in the load script, the field will automatically be given the name <b>Type</b> .
eq_var	If <b>eq_var</b> is specified as False (0), separate variances of the two samples will be assumed. If <b>eq_var</b> is specified as True (1), equal variances between the samples will be assumed.

**Limitations:**


Text values, NULL values and missing values in the expression value will result in the function returning NULL.

**Examples:**

```
TTest_sterr( Group, value )  
TTest_sterr( Group, value, false )
```

---

**See also:**

 [Creating a typical t-test report \(page 527\)](#)

TTest\_t

**TTest\_t()** returns the aggregated t value for two independent series of values.

This function applies to independent samples student's t-tests.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

**Syntax:**

```
TTest_t(grp, value[, eq_var])
```

**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
value	The sample values to be evaluated. The sample values must be logically grouped as specified by exactly two values in <b>group</b> . If a field name for the sample values is not provided in the load script, the field will automatically be named <b>Value</b> .
grp	The field containing the names of each of the two sample groups. If a field name for the group is not provided in the load script, the field will automatically be given the name <b>Type</b> .
eq_var	If <b>eq_var</b> is specified as False (0), separate variances of the two samples will be assumed. If <b>eq_var</b> is specified as True (1), equal variances between the samples will be assumed.


**Limitations:**

Text values, NULL values and missing values in the expression value will result in the function returning NULL.

**Example:**

```
TTest_t( Group, value, false )
```

**See also:**

 [Creating a typical t-test report \(page 527\)](#)

TTest\_upper

**TTest\_upper()** returns the aggregated value for the upper end of the confidence interval for two independent series of values.

This function applies to independent samples student's t-tests.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

**Syntax:**

```
TTest_upper (grp, value [, sig [, eq_var]])
```

**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
value	The sample values to be evaluated. The sample values must be logically grouped as specified by exactly two values in <b>group</b> . If a field name for the sample values is not provided in the load script, the field will automatically be named <b>Value</b> .
grp	The field containing the names of each of the two sample groups. If a field name for the group is not provided in the load script, the field will automatically be given the name <b>Type</b> .
sig	The two-tailed level of significance can be specified in <b>sig</b> . If omitted, <b>sig</b> is set to 0.025, resulting in a 95% confidence interval.
eq_var	If <b>eq_var</b> is specified as False (0), separate variances of the two samples will be assumed. If <b>eq_var</b> is specified as True (1), equal variances between the samples will be assumed.


**Limitations:**

Text values, NULL values and missing values in the expression value will result in the function returning NULL.

**Examples:**

```
TTest_upper( Group, value )
TTest_upper( Group, value, sig, false )
```

**See also:**

 [Creating a typical t-test report \(page 527\)](#)

**TTestw\_conf**

**TTestw\_conf()** returns the aggregated t value for two independent series of values.

This function applies to two independent samples student's t-tests where the input data series is given in weighted two-column format.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

**Syntax:**

```
TTestw_conf (weight, grp, value [, sig [, eq_var]])
```

**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
value	The sample values to be evaluated. The sample values must be logically grouped as specified by exactly two values in <b>group</b> . If a field name for the sample values is not provided in the load script, the field will automatically be named <b>Value</b> .
weight	Each value in <b>value</b> can be counted one or more times according to a corresponding weight value in <b>weight</b> .
grp	The field containing the names of each of the two sample groups. If a field name for the group is not provided in the load script, the field will automatically be given the name <b>Type</b> .
sig	The two-tailed level of significance can be specified in <b>sig</b> . If omitted, <b>sig</b> is set to 0.025, resulting in a 95% confidence interval.
eq_var	If <b>eq_var</b> is specified as False (0), separate variances of the two samples will be assumed. If <b>eq_var</b> is specified as True (1), equal variances between the samples will be assumed.


**Limitations:**

Text values, NULL values and missing values in the expression value will result in the function returning NULL.

**Examples:**

```
TTestw_conf( weight, Group, value )
TTestw_conf( weight, Group, value, sig, false )
```

**See also:**

 [Creating a typical t-test report \(page 527\)](#)

**TTestw\_df**

**TTestw\_df()** returns the aggregated student's t-test df value (degrees of freedom) for two independent series of values.

This function applies to two independent samples student's t-tests where the input data series is given in weighted two-column format.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

### Syntax:

```
TTestw_df (weight, grp, value [, eq_var])
```

**Return data type:** numeric

### Arguments:

#### Arguments

Argument	Description
weight	Each value in <b>value</b> can be counted one or more times according to a corresponding weight value in <b>weight</b> .
grp	The field containing the names of each of the two sample groups. If a field name for the group is not provided in the load script, the field will automatically be given the name <b>Type</b> .
value	The sample values to be evaluated. The sample values must be logically grouped as specified by exactly two values in <b>group</b> . If a field name for the sample values is not provided in the load script, the field will automatically be named <b>Value</b> .
eq_var	If <b>eq_var</b> is specified as False (0), separate variances of the two samples will be assumed. If <b>eq_var</b> is specified as True (1), equal variances between the samples will be assumed.


### Limitations:

Text values, NULL values and missing values in the expression value will result in the function returning NULL.

### Examples:

```
TTestw_df( weight, Group, Value )
TTestw_df( weight, Group, Value, false )
```

### See also:

 [Creating a typical t-test report \(page 527\)](#)

### TTestw\_dif

**TTestw\_dif()** returns the aggregated student's t-test mean difference for two independent series of values.

This function applies to two independent samples student's t-tests where the input data series is given in weighted two-column format.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

**Syntax:**

```
TTestw_dif (weight, grp, value)
```

**Return data type:** numeric

**Arguments:**

## Arguments

Argument	Description
weight	Each value in <b>value</b> can be counted one or more times according to a corresponding weight value in <b>weight</b> .
grp	The field containing the names of each of the two sample groups. If a field name for the group is not provided in the load script, the field will automatically be given the name <b>Type</b> .
value	The sample values to be evaluated. The sample values must be logically grouped as specified by exactly two values in <b>group</b> . If a field name for the sample values is not provided in the load script, the field will automatically be named <b>Value</b> .


**Limitations:**

Text values, NULL values and missing values in the expression value will result in the function returning NULL.

**Examples:**

```
TTestw_dif( weight, Group, value )  
TTestw_dif( weight, Group, value, false )
```

**See also:**

 [Creating a typical t-test report \(page 527\)](#)

**TTestw\_lower**

**TTestw\_lower()** returns the aggregated value for the lower end of the confidence interval for two independent series of values.

This function applies to two independent samples student's t-tests where the input data series is given in weighted two-column format.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

**Syntax:**

```
TTestw_lower (weight, grp, value [, sig [, eq_var]])
```

**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
weight	Each value in <b>value</b> can be counted one or more times according to a corresponding weight value in <b>weight</b> .
grp	The field containing the names of each of the two sample groups. If a field name for the group is not provided in the load script, the field will automatically be given the name <b>Type</b> .
value	The sample values to be evaluated. The sample values must be logically grouped as specified by exactly two values in <b>group</b> . If a field name for the sample values is not provided in the load script, the field will automatically be named <b>Value</b> .
sig	The two-tailed level of significance can be specified in <b>sig</b> . If omitted, <b>sig</b> is set to 0.025, resulting in a 95% confidence interval.
eq_var	If <b>eq_var</b> is specified as False (0), separate variances of the two samples will be assumed. If <b>eq_var</b> is specified as True (1), equal variances between the samples will be assumed.


**Limitations:**

Text values, NULL values and missing values in the expression value will result in the function returning NULL.

**Examples:**

```
TTestw_lower( weight, Group, Value )
TTestw_lower( weight, Group, Value, sig, false )
```

**See also:**

 [Creating a typical t-test report \(page 527\)](#)

**TTestw\_sig**

**TTestw\_sig()** returns the aggregated student's t-test 2-tailed level of significance for two independent series of values.

This function applies to two independent samples student's t-tests where the input data series is given in weighted two-column format.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.



**Syntax:**

```
TTestw_sig ( weight, grp, value [, eq_var])
```

**Return data type:** numeric

**Arguments:**

## Arguments

Argument	Description
weight	Each value in <b>value</b> can be counted one or more times according to a corresponding weight value in <b>weight</b> .
grp	The field containing the names of each of the two sample groups. If a field name for the group is not provided in the load script, the field will automatically be given the name <b>Type</b> .
value	The sample values to be evaluated. The sample values must be logically grouped as specified by exactly two values in <b>group</b> . If a field name for the sample values is not provided in the load script, the field will automatically be named <b>Value</b> .
eq_var	If <b>eq_var</b> is specified as False (0), separate variances of the two samples will be assumed. If <b>eq_var</b> is specified as True (1), equal variances between the samples will be assumed.


**Limitations:**

Text values, NULL values and missing values in the expression value will result in the function returning NULL.

**Examples:**

```
TTestw_sig( weight, Group, Value )
TTestw_sig( weight, Group, Value, false )
```

**See also:**

 [Creating a typical t-test report \(page 527\)](#)

**TTestw\_sterr**

**TTestw\_sterr()** returns the aggregated student's t-test standard error of the mean difference for two independent series of values.

This function applies to two independent samples student's t-tests where the input data series is given in weighted two-column format.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

### Syntax:

```
TTestw_sterr (weight, grp, value [, eq_var])
```

**Return data type:** numeric

### Arguments:

#### Arguments

Argument	Description
weight	Each value in <b>value</b> can be counted one or more times according to a corresponding weight value in <b>weight</b> .
grp	The field containing the names of each of the two sample groups. If a field name for the group is not provided in the load script, the field will automatically be given the name <b>Type</b> .
value	The sample values to be evaluated. The sample values must be logically grouped as specified by exactly two values in <b>group</b> . If a field name for the sample values is not provided in the load script, the field will automatically be named <b>Value</b> .
eq_var	If <b>eq_var</b> is specified as False (0), separate variances of the two samples will be assumed. If <b>eq_var</b> is specified as True (1), equal variances between the samples will be assumed.


### Limitations:

Text values, NULL values and missing values in the expression value will result in the function returning NULL.

### Examples:

```
TTestw_sterr( weight, Group, value )
TTestw_sterr( weight, Group, value, false )
```

### See also:

 [Creating a typical t-test report \(page 527\)](#)

### TTestw\_t

**TTestw\_t()** returns the aggregated t value for two independent series of values.

This function applies to two independent samples student's t-tests where the input data series is given in weighted two-column format.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

### Syntax:

```
ttestw_t (weight, grp, value [, eq_var])
```

**Return data type:** numeric

### Arguments:

#### Arguments

Argument	Description
value	The sample values to be evaluated. The sample values must be logically grouped as specified by exactly two values in <b>group</b> . If a field name for the sample values is not provided in the load script, the field will automatically be named <b>Value</b> .
weight	Each value in <b>value</b> can be counted one or more times according to a corresponding weight value in <b>weight</b> .
grp	The field containing the names of each of the two sample groups. If a field name for the group is not provided in the load script, the field will automatically be given the name <b>Type</b> .
eq_var	If <b>eq_var</b> is specified as False (0), separate variances of the two samples will be assumed. If <b>eq_var</b> is specified as True (1), equal variances between the samples will be assumed.


### Limitations:

Text values, NULL values and missing values in the expression value will result in the function returning NULL.

### Examples:

```
TTestw_t( weight, Group, value )
TTestw_t( weight, Group, value, false )
```

### See also:

 [Creating a typical t-test report \(page 527\)](#)

TTestw\_upper

**TTestw\_upper()** returns the aggregated value for the upper end of the confidence interval for two independent series of values.

This function applies to two independent samples student's t-tests where the input data series is given in weighted two-column format.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

### Syntax:

```
TTestw_upper (weight, grp, value [, sig [, eq_var]])
```

**Return data type:** numeric

### Arguments:

#### Arguments

Argument	Description
weight	Each value in <b>value</b> can be counted one or more times according to a corresponding weight value in <b>weight</b> .
grp	The field containing the names of each of the two sample groups. If a field name for the group is not provided in the load script, the field will automatically be given the name <b>Type</b> .
value	The sample values to be evaluated. The sample values must be logically grouped as specified by exactly two values in <b>group</b> . If a field name for the sample values is not provided in the load script, the field will automatically be named <b>Value</b> .
sig	The two-tailed level of significance can be specified in <b>sig</b> . If omitted, <b>sig</b> is set to 0.025, resulting in a 95% confidence interval.
eq_var	If <b>eq_var</b> is specified as False (0), separate variances of the two samples will be assumed. If <b>eq_var</b> is specified as True (1), equal variances between the samples will be assumed.


### Limitations:

Text values, NULL values and missing values in the expression value will result in the function returning NULL.

### Examples:

```
TTestw_upper( weight, Group, value )
TTestw_upper( weight, Group, value, sig, false )
```

### See also:

 [Creating a typical t-test report \(page 527\)](#)

TTest1\_conf

**TTest1\_conf()** returns the aggregated confidence interval value for a series of values.

This function applies to one-sample student's t-tests.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

**Syntax:**

```
TTest1_conf (value [, sig ])
```

**Return data type:** numeric

**Arguments:**

## Arguments

Argument	Description
value	The samples to be evaluated. If a field name for the sample values is not provided in the load script, the field will automatically be named <b>Value</b> .
sig	The two-tailed level of significance can be specified in <b>sig</b> . If omitted, <b>sig</b> is set to 0.025, resulting in a 95% confidence interval.


**Limitations:**

Text values, NULL values and missing values in the expression value will result in the function returning NULL.

**Examples:**

```
TTest1_conf( value )  
TTest1_conf( value, 0.005 )
```

**See also:**

 [Creating a typical t-test report \(page 527\)](#)

**TTest1\_df**

**TTest1\_df()** returns the aggregated student's t-test df value (degrees of freedom) for a series of values.

This function applies to one-sample student's t-tests.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

**Syntax:**

```
TTest1_df (value)
```

**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
value	The samples to be evaluated. If a field name for the sample values is not provided in the load script, the field will automatically be named <b>Value</b> .

**Limitations:**


Text values, NULL values and missing values in the expression value will result in the function returning NULL.

**Example:**

```
TTest1_df( value )
```

---

**See also:**

 [Creating a typical t-test report \(page 527\)](#)

TTest1\_dif

**TTest1\_dif()** returns the aggregated student's t-test mean difference for a series of values.

This function applies to one-sample student's t-tests.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

**Syntax:**

```
TTest1_dif (value)
```

**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
value	The samples to be evaluated. If a field name for the sample values is not provided in the load script, the field will automatically be named <b>Value</b> .

### Limitations:


Text values, NULL values and missing values in the expression value will result in the function returning NULL.

### Example:

```
TTest1_dif( value )
```

---

### See also:

 [Creating a typical t-test report \(page 527\)](#)

### TTest1\_lower

**TTest1\_lower()** returns the aggregated value for the lower end of the confidence interval for a series of values.

This function applies to one-sample student's t-tests.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

### Syntax:

```
TTest1_lower (value [, sig])
```

**Return data type:** numeric

### Arguments:

#### Arguments

Argument	Description
value	The samples to be evaluated. If a field name for the sample values is not provided in the load script, the field will automatically be named <b>Value</b> .
sig	The two-tailed level of significance can be specified in <b>sig</b> . If omitted, <b>sig</b> is set to 0.025, resulting in a 95% confidence interval.


### Limitations:

Text values, NULL values and missing values in the expression value will result in the function returning NULL.

### Examples:

```
TTest1_lower( Value )  
TTest1_lower( value, 0.005 )
```

**See also:**

 [Creating a typical t-test report \(page 527\)](#)

TTest1\_sig

**TTest1\_sig()** returns the aggregated student's t-test 2-tailed level of significance for a series of values.

This function applies to one-sample student's t-tests.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

**Syntax:**

```
TTest1_sig (value)
```

**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
value	The samples to be evaluated. If a field name for the sample values is not provided in the load script, the field will automatically be named <b>Value</b> .

**Limitations:**


Text values, NULL values and missing values in the expression value will result in the function returning NULL.

**Example:**

```
TTest1_sig( value )
```

---

**See also:**

 [Creating a typical t-test report \(page 527\)](#)

TTest1\_sterr

**TTest1\_sterr()** returns the aggregated student's t-test standard error of the mean difference for a series of values.

This function applies to one-sample student's t-tests.



If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

**Syntax:**

```
TTest1_sterr (value)
```

**Return data type:** numeric

**Arguments:**

## Arguments

Argument	Description
value	The samples to be evaluated. If a field name for the sample values is not provided in the load script, the field will automatically be named <b>Value</b> .


**Limitations:**

Text values, NULL values and missing values in the expression value will result in the function returning NULL.

**Example:**

```
TTest1_sterr( value )
```

**See also:**

 [Creating a typical t-test report \(page 527\)](#)

TTest1\_t

**TTest1\_t()** returns the aggregated t value for a series of values.

This function applies to one-sample student's t-tests.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

**Syntax:**

```
TTest1_t (value)
```

**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
value	The samples to be evaluated. If a field name for the sample values is not provided in the load script, the field will automatically be named <b>Value</b> .


**Limitations:**

Text values, NULL values and missing values in the expression value will result in the function returning NULL.

**Example:**

```
TTest1_t( value )
```

**See also:**

 [Creating a typical t-test report \(page 527\)](#)

**TTest1\_upper**

**TTest1\_upper()** returns the aggregated value for the upper end of the confidence interval for a series of values.

This function applies to one-sample student's t-tests.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

**Syntax:**

```
TTest1_upper (value [, sig])
```

**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
value	The samples to be evaluated. If a field name for the sample values is not provided in the load script, the field will automatically be named <b>Value</b> .
sig	The two-tailed level of significance can be specified in <b>sig</b> . If omitted, <b>sig</b> is set to 0.025, resulting in a 95% confidence interval.

### Limitations:


Text values, NULL values and missing values in the expression value will result in the function returning NULL.

### Examples:

```
TTest1_upper( value )  
TTest1_upper( value, 0.005 )
```

---

### See also:

 [Creating a typical t-test report \(page 527\)](#)

### TTest1w\_conf

**TTest1w\_conf()** is a **numeric** function that returns the aggregated confidence interval value for a series of values.

This function applies to one-sample student's t-tests where the input data series is given in weighted two-column format.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

### Syntax:

```
TTest1w_conf (weight, value [, sig ])
```

**Return data type:** numeric

### Arguments:

#### Arguments

Argument	Description
value	The samples to be evaluated. If a field name for the sample values is not provided in the load script, the field will automatically be named <b>Value</b> .
weight	Each value in <b>value</b> can be counted one or more times according to a corresponding weight value in <b>weight</b> .
sig	The two-tailed level of significance can be specified in <b>sig</b> . If omitted, <b>sig</b> is set to 0.025, resulting in a 95% confidence interval.

### Limitations:


Text values, NULL values and missing values in the expression value will result in the function returning NULL.

### Examples:

```
TTest1w_conf( weight, value )  
TTest1w_conf( weight, value, 0.005 )
```

---

### See also:

 [Creating a typical t-test report \(page 527\)](#)

TTest1w\_df

**TTest1w\_df()** returns the aggregated student's t-test df value (degrees of freedom) for a series of values.

This function applies to one-sample student's t-tests where the input data series is given in weighted two-column format.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

### Syntax:

```
TTest1w_df (weight, value)
```

**Return data type:** numeric

### Arguments:

#### Arguments

Argument	Description
value	The samples to be evaluated. If a field name for the sample values is not provided in the load script, the field will automatically be named <b>Value</b> .
weight	Each value in <b>value</b> can be counted one or more times according to a corresponding weight value in <b>weight</b> .

### Limitations:


Text values, NULL values and missing values in the expression value will result in the function returning NULL.

### Example:

```
TTest1w_df( weight, value )
```

---

### See also:

 [Creating a typical t-test report \(page 527\)](#)

### TTest1w\_dif

**TTest1w\_dif()** returns the aggregated student's t-test mean difference for a series of values.

This function applies to one-sample student's t-tests where the input data series is given in weighted two-column format.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

#### Syntax:

```
TTest1w_dif (weight, value)
```

**Return data type:** numeric

#### Arguments:

##### Arguments

Argument	Description
value	The samples to be evaluated. If a field name for the sample values is not provided in the load script, the field will automatically be named <b>Value</b> .
weight	Each value in <b>value</b> can be counted one or more times according to a corresponding weight value in <b>weight</b> .

#### Limitations:


Text values, NULL values and missing values in the expression value will result in the function returning NULL.

#### Example:

```
TTest1w_dif( weight, value )
```

---

#### See also:

 [Creating a typical t-test report \(page 527\)](#)

### TTest1w\_lower

**TTest1w\_lower()** returns the aggregated value for the lower end of the confidence interval for a series of values.

This function applies to one-sample student's t-tests where the input data series is given in weighted two-column format.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

**Syntax:**

```
TTest1w_lower (weight, value [, sig ])
```

**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
value	The samples to be evaluated. If a field name for the sample values is not provided in the load script, the field will automatically be named <b>Value</b> .
weight	Each value in <b>value</b> can be counted one or more times according to a corresponding weight value in <b>weight</b> .
sig	The two-tailed level of significance can be specified in <b>sig</b> . If omitted, <b>sig</b> is set to 0.025, resulting in a 95% confidence interval.

**Limitations:**


Text values, NULL values and missing values in the expression value will result in the function returning NULL.

**Examples:**

```
TTest1w_lower( weight, value )  
TTest1w_lower( weight, value, 0.005 )
```

---

**See also:**

 [Creating a typical t-test report \(page 527\)](#)

**TTest1w\_sig**

**TTest1w\_sig()** returns the aggregated student's t-test 2-tailed level of significance for a series of values.

This function applies to one-sample student's t-tests where the input data series is given in weighted two-column format.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

**Syntax:**

```
TTest1w_sig (weight, value)
```

**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
value	The samples to be evaluated. If a field name for the sample values is not provided in the load script, the field will automatically be named <b>Value</b> .
weight	Each value in <b>value</b> can be counted one or more times according to a corresponding weight value in <b>weight</b> .

**Limitations:**


Text values, NULL values and missing values in the expression value will result in the function returning NULL.

**Example:**

```
TTest1w_sig( weight, value )
```

---

**See also:**

 [Creating a typical t-test report \(page 527\)](#)

TTest1w\_sterr

**TTest1w\_sterr()** returns the aggregated student's t-test standard error of the mean difference for a series of values.

This function applies to one-sample student's t-tests where the input data series is given in weighted two-column format.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

**Syntax:**

```
TTest1w_sterr (weight, value)
```

**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
value	The samples to be evaluated. If a field name for the sample values is not provided in the load script, the field will automatically be named <b>Value</b> .
weight	Each value in <b>value</b> can be counted one or more times according to a corresponding weight value in <b>weight</b> .

**Limitations:**


Text values, NULL values and missing values in the expression value will result in the function returning NULL.

**Example:**

```
TTest1w_sterr( weight, value )
```

---

**See also:**

 [Creating a typical t-test report \(page 527\)](#)

TTest1w\_t

**TTest1w\_t()** returns the aggregated t value for a series of values.

This function applies to one-sample student's t-tests where the input data series is given in weighted two-column format.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

**Syntax:**

```
TTest1w_t ( weight, value)
```



**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
value	The samples to be evaluated. If a field name for the sample values is not provided in the load script, the field will automatically be named <b>Value</b> .
weight	Each value in <b>value</b> can be counted one or more times according to a corresponding weight value in <b>weight</b> .

**Limitations:**


Text values, NULL values and missing values in the expression value will result in the function returning NULL.

**Example:**

```
TTest1w_t( weight, value )
```

---

**See also:**

 [Creating a typical t-test report \(page 527\)](#)

**TTest1w\_upper**

**TTest1w\_upper()** returns the aggregated value for the upper end of the confidence interval for a series of values.

This function applies to one-sample student's t-tests where the input data series is given in weighted two-column format.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

**Syntax:**

```
TTest1w_upper (weight, value [, sig])
```

**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
value	The samples to be evaluated. If a field name for the sample values is not provided in the load script, the field will automatically be named <b>Value</b> .
weight	Each value in <b>value</b> can be counted one or more times according to a corresponding weight value in <b>weight</b> .
sig	The two-tailed level of significance can be specified in <b>sig</b> . If omitted, <b>sig</b> is set to 0.025, resulting in a 95% confidence interval.

**Limitations:**


Text values, NULL values and missing values in the expression value will result in the function returning NULL.

**Examples:**

```
TTest1w_upper( weight, value )  
TTest1w_upper( weight, value, 0.005 )
```

---

**See also:**

 [Creating a typical t-test report \(page 527\)](#)

### Z-test functions

A statistical examination of two population means. A two sample z-test examines whether two samples are different and is commonly used when two normal distributions have known variances and when an experiment uses a large sample size.

The z-test statistical test functions are grouped according the type of input data series that applies to the function.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

*Examples of how to use z-test functions (page 531)*

### One column format functions

The following functions apply to z-tests with simple input data series.

ztest\_conf

**ZTest\_conf()** returns the aggregated z value for a series of values.

```
ZTest_conf() returns the aggregated z value for a series of values. (value [, sigma [, sig ]])
```

ztest\_dif

**ZTest\_dif()** returns the aggregated z-test mean difference for a series of values.

```
ZTest_dif() returns the aggregated z-test mean difference for a series of values. (value [, sigma])
```

ztest\_sig

**ZTest\_sig()** returns the aggregated z-test 2-tailed level of significance for a series of values.

```
ZTest_sig() returns the aggregated z-test 2-tailed level of significance for a series of values. (value [, sigma])
```

ztest\_sterr

**ZTest\_sterr()** returns the aggregated z-test standard error of the mean difference for a series of values.

```
ZTest_sterr() returns the aggregated z-test standard error of the mean difference for a series of values. (value [, sigma])
```

ztest\_z

**ZTest\_z()** returns the aggregated z value for a series of values.

```
ZTest_z() returns the aggregated z value for a series of values. (value [, sigma])
```

ztest\_lower

**ZTest\_lower()** returns the aggregated value for the lower end of the confidence interval for two independent series of values.

```
ZTest_lower() returns the aggregated value for the lower end of the confidence interval for two independent series of values. (grp, value [, sig [, eq_var]])
```

ztest\_upper

**ZTest\_upper()** returns the aggregated value for the upper end of the confidence interval for two independent series of values.

```
ZTest_upper() returns the aggregated value for the upper end of the confidence interval for two independent series of values. (grp, value [, sig [, eq_var]])
```

### Weighted two-column format functions

The following functions apply to z-tests where the input data series is given in weighted two-column format.

ztestw\_conf

**ZTestw\_conf()** returns the aggregated z confidence interval value for a series of values.

```
ZTestw_conf() returns the aggregated z confidence interval value for a series of values. (weight, value [, sigma [, sig]])
```

ztestw\_dif

**ZTestw\_dif()** returns the aggregated z-test mean difference for a series of values.

```
ZTestw_dif() returns the aggregated z-test mean difference for a series of values. (weight, value [, sigma])
```

ztestw\_lower

**ZTestw\_lower()** returns the aggregated value for the lower end of the confidence interval for two independent series of values.

```
ZTestw_lower() returns the aggregated value for the lower end of the confidence interval for two independent series of values. (weight, value [, sigma])
```

ztestw\_sig

**ZTestw\_sig()** returns the aggregated z-test 2-tailed level of significance for a series of values.

```
ZTestw_sig() returns the aggregated z-test 2-tailed level of significance for a series of values. (weight, value [, sigma])
```

ztestw\_sterr

**ZTestw\_sterr()** returns the aggregated z-test standard error of the mean difference for a series of values.

```
ZTestw_sterr() returns the aggregated z-test standard error of the mean difference for a series of values. (weight, value [, sigma])
```

ztestw\_upper

**ZTestw\_upper()** returns the aggregated value for the upper end of the confidence interval for two independent series of values.

```
ZTestw_upper() returns the aggregated value for the upper end of the confidence interval for two independent series of values. (weight, value [, sigma])
```

ztestw\_z

**ZTestw\_z()** returns the aggregated z value for a series of values.

```
ZTestw_z() returns the aggregated z value for a series of values. (weight, value [, sigma])
```

ZTest\_z

**ZTest\_z()** returns the aggregated z value for a series of values.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

**Syntax:**

```
ZTest_z(value[, sigma])
```

**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
value	The sample values to be evaluated. A population mean of 0 is assumed. If you want the test to be performed around another mean, subtract that mean from the sample values.
sigma	If known, the standard deviation can be stated in <b>sigma</b> . If <b>sigma</b> is omitted the actual sample standard deviation will be used.

**Limitations:**


Text values, NULL values and missing values in the expression value will result in the function returning NULL.

**Example:**

```
ZTest_z( value-TestValue )
```

---

**See also:**

 [Examples of how to use z-test functions \(page 531\)](#)

ZTest\_sig

**ZTest\_sig()** returns the aggregated z-test 2-tailed level of significance for a series of values.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

**Syntax:**

```
ZTest_sig(value[, sigma])
```

**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
value	The sample values to be evaluated. A population mean of 0 is assumed. If you want the test to be performed around another mean, subtract that mean from the sample values.
sigma	If known, the standard deviation can be stated in <b>sigma</b> . If <b>sigma</b> is omitted the actual sample standard deviation will be used.

**Limitations:**


Text values, NULL values and missing values in the expression value will result in the function returning NULL.

**Example:**

```
ZTest_sig(Value-Testvalue)
```

---

**See also:**

 [Examples of how to use z-test functions \(page 531\)](#)

ZTest\_dif

**ZTest\_dif()** returns the aggregated z-test mean difference for a series of values.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

**Syntax:**

```
ZTest_dif(value[, sigma])
```

**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
value	The sample values to be evaluated. A population mean of 0 is assumed. If you want the test to be performed around another mean, subtract that mean from the sample values.
sigma	If known, the standard deviation can be stated in <b>sigma</b> . If <b>sigma</b> is omitted the actual sample standard deviation will be used.

**Limitations:**


Text values, NULL values and missing values in the expression value will result in the function returning NULL.

**Example:**

```
ZTest_dif(Value-Testvalue)
```

---

**See also:**

 [Examples of how to use z-test functions \(page 531\)](#)

ZTest\_sterr

**ZTest\_sterr()** returns the aggregated z-test standard error of the mean difference for a series of values.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

**Syntax:**

```
ZTest_sterr(value[, sigma])
```

**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
value	The sample values to be evaluated. A population mean of 0 is assumed. If you want the test to be performed around another mean, subtract that mean from the sample values.
sigma	If known, the standard deviation can be stated in <b>sigma</b> . If <b>sigma</b> is omitted the actual sample standard deviation will be used.

**Limitations:**


Text values, NULL values and missing values in the expression value will result in the function returning NULL.

**Example:**

```
ZTest_sterr(Value-TestValue)
```

---

**See also:**

 [Examples of how to use z-test functions \(page 531\)](#)

ZTest\_conf

**ZTest\_conf()** returns the aggregated z value for a series of values.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

**Syntax:**

```
ZTest_conf (value[, sigma[, sig]])
```



**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
value	The sample values to be evaluated. A population mean of 0 is assumed. If you want the test to be performed around another mean, subtract that mean from the sample values.
sigma	If known, the standard deviation can be stated in <b>sigma</b> . If <b>sigma</b> is omitted the actual sample standard deviation will be used.
sig	The two-tailed level of significance can be specified in <b>sig</b> . If omitted, <b>sig</b> is set to 0.025, resulting in a 95% confidence interval.

**Limitations:**


Text values, NULL values and missing values in the expression value will result in the function returning NULL.

**Example:**

```
ZTest_conf(Value-TestValue)
```

---

**See also:**

 [Examples of how to use z-test functions \(page 531\)](#)

ZTest\_lower

**ZTest\_lower()** returns the aggregated value for the lower end of the confidence interval for two independent series of values.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

**Syntax:**

```
ZTest_lower (grp, value [, sig [, eq_var]])
```

**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
value	The sample values to be evaluated. The sample values must be logically grouped as specified by exactly two values in <b>group</b> . If a field name for the sample values is not provided in the load script, the field will automatically be named <b>Value</b> .
grp	The field containing the names of each of the two sample groups. If a field name for the group is not provided in the load script, the field will automatically be given the name <b>Type</b> .
sig	The two-tailed level of significance can be specified in <b>sig</b> . If omitted, <b>sig</b> is set to 0.025, resulting in a 95% confidence interval.
eq_var	If <b>eq_var</b> is specified as False (0), separate variances of the two samples will be assumed. If <b>eq_var</b> is specified as True (1), equal variances between the samples will be assumed.


**Limitations:**

Text values, NULL values and missing values in the expression value will result in the function returning NULL.

**Examples:**

```
ZTest_lower( Group, value )
ZTest_lower( Group, value, sig, false )
```

**See also:**

 [Examples of how to use z-test functions \(page 531\)](#)

ZTest\_upper

**ZTest\_upper()** returns the aggregated value for the upper end of the confidence interval for two independent series of values.

This function applies to independent samples student's t-tests.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

**Syntax:**

```
ZTest_upper (grp, value [, sig [, eq_var]])
```

**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
value	The sample values to be evaluated. The sample values must be logically grouped as specified by exactly two values in <b>group</b> . If a field name for the sample values is not provided in the load script, the field will automatically be named <b>Value</b> .
grp	The field containing the names of each of the two sample groups. If a field name for the group is not provided in the load script, the field will automatically be given the name <b>Type</b> .
sig	The two-tailed level of significance can be specified in <b>sig</b> . If omitted, <b>sig</b> is set to 0.025, resulting in a 95% confidence interval.
eq_var	If <b>eq_var</b> is specified as False (0), separate variances of the two samples will be assumed. If <b>eq_var</b> is specified as True (1), equal variances between the samples will be assumed.


**Limitations:**

Text values, NULL values and missing values in the expression value will result in the function returning NULL.

**Examples:**

```
ZTest_upper( Group, value )
ZTest_upper( Group, value, sig, false )
```

**See also:**

 [Examples of how to use z-test functions \(page 531\)](#)

ZTestw\_z

**ZTestw\_z()** returns the aggregated z value for a series of values.

This function applies to z-tests where the input data series is given in weighted two-column format.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

**Syntax:**

```
ZTestw_z (weight, value [, sigma])
```

**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
value	The values should be returned by <b>value</b> . A sample mean of 0 is assumed. If you want the test to be performed around another mean, subtract that value from the sample values.
weight	Each sample value in <b>value</b> can be counted one or more times according to a corresponding weight value in <b>weight</b> .
sigma	If known, the standard deviation can be stated in <b>sigma</b> . If <b>sigma</b> is omitted the actual sample standard deviation will be used.

**Limitations:**


Text values, NULL values and missing values in the expression value will result in the function returning NULL.

**Example:**

```
ZTestw_z( weight, value-TestValue)
```

---

**See also:**

 [Examples of how to use z-test functions \(page 531\)](#)

ZTestw\_sig

**ZTestw\_sig()** returns the aggregated z-test 2-tailed level of significance for a series of values.

This function applies to z-tests where the input data series is given in weighted two-column format.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

**Syntax:**

```
ZTestw_sig (weight, value [, sigma])
```

**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
value	The values should be returned by <b>value</b> . A sample mean of 0 is assumed. If you want the test to be performed around another mean, subtract that value from the sample values.
weight	Each sample value in <b>value</b> can be counted one or more times according to a corresponding weight value in <b>weight</b> .
sigma	If known, the standard deviation can be stated in <b>sigma</b> . If <b>sigma</b> is omitted the actual sample standard deviation will be used.

**Limitations:**


Text values, NULL values and missing values in the expression value will result in the function returning NULL.

**Example:**

```
ZTestw_sig( weight, value-TestValue)
```

---

**See also:**

 [Examples of how to use z-test functions \(page 531\)](#)

ZTestw\_dif

**ZTestw\_dif()** returns the aggregated z-test mean difference for a series of values.

This function applies to z-tests where the input data series is given in weighted two-column format.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

**Syntax:**

```
ZTestw_dif ( weight, value [, sigma])
```

**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
value	The values should be returned by <b>value</b> . A sample mean of 0 is assumed. If you want the test to be performed around another mean, subtract that value from the sample values.
weight	Each sample value in <b>value</b> can be counted one or more times according to a corresponding weight value in <b>weight</b> .
sigma	If known, the standard deviation can be stated in <b>sigma</b> . If <b>sigma</b> is omitted the actual sample standard deviation will be used.

**Limitations:**


Text values, NULL values and missing values in the expression value will result in the function returning NULL.

**Example:**

```
ZTestw_dif( weight, value-Testvalue)
```

---

**See also:**

 [Examples of how to use z-test functions \(page 531\)](#)

ZTestw\_sterr

**ZTestw\_sterr()** returns the aggregated z-test standard error of the mean difference for a series of values.

This function applies to z-tests where the input data series is given in weighted two-column format.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

**Syntax:**

```
ZTestw_sterr (weight, value [, sigma])
```

**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
value	The values should be returned by <b>value</b> . A sample mean of 0 is assumed. If you want the test to be performed around another mean, subtract that value from the sample values.
weight	Each sample value in <b>value</b> can be counted one or more times according to a corresponding weight value in <b>weight</b> .
sigma	If known, the standard deviation can be stated in <b>sigma</b> . If <b>sigma</b> is omitted the actual sample standard deviation will be used.

**Limitations:**


Text values, NULL values and missing values in the expression value will result in the function returning NULL.

**Example:**

```
ZTestw_sterr( weight, value-TestValue)
```

---

**See also:**

 [Examples of how to use z-test functions \(page 531\)](#)

ZTestw\_conf

**ZTestw\_conf()** returns the aggregated z confidence interval value for a series of values.

This function applies to z-tests where the input data series is given in weighted two-column format.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

**Syntax:**

```
ZTest_conf (weight, value[, sigma[, sig]])
```

**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
value	The sample values to be evaluated. A population mean of 0 is assumed. If you want the test to be performed around another mean, subtract that mean from the sample values.
weight	Each sample value in <b>value</b> can be counted one or more times according to a corresponding weight value in <b>weight</b> .
sigma	If known, the standard deviation can be stated in <b>sigma</b> . If <b>sigma</b> is omitted the actual sample standard deviation will be used.
sig	The two-tailed level of significance can be specified in <b>sig</b> . If omitted, <b>sig</b> is set to 0.025, resulting in a 95% confidence interval.

**Limitations:**


Text values, NULL values and missing values in the expression value will result in the function returning NULL.

**Example:**

```
ZTestw_conf( weight, value-TestValue)
```

---

**See also:**

 [Examples of how to use z-test functions \(page 531\)](#)

ZTestw\_lower

**ZTestw\_lower()** returns the aggregated value for the lower end of the confidence interval for two independent series of values.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

**Syntax:**

```
ZTestw_lower (grp, value [, sig [, eq_var]])
```



**Return data type:** numeric

**Arguments:**

Argument	Description
value	The sample values to be evaluated. The sample values must be logically grouped as specified by exactly two values in <b>group</b> . If a field name for the sample values is not provided in the load script, the field will automatically be named <b>Value</b> .
grp	The field containing the names of each of the two sample groups. If a field name for the group is not provided in the load script, the field will automatically be given the name <b>Type</b> .
sig	The two-tailed level of significance can be specified in <b>sig</b> . If omitted, <b>sig</b> is set to 0.025, resulting in a 95% confidence interval.
eq_var	If <b>eq_var</b> is specified as False (0), separate variances of the two samples will be assumed. If <b>eq_var</b> is specified as True (1), equal variances between the samples will be assumed.


**Limitations:**

Text values, NULL values and missing values in the expression value will result in the function returning NULL.

**Examples:**

```
ZTestw_lower( Group, Value )
ZTestw_lower( Group, Value, sig, false )
```

**See also:**

 [Examples of how to use z-test functions \(page 531\)](#)

ZTestw\_upper

**ZTestw\_upper()** returns the aggregated value for the upper end of the confidence interval for two independent series of values.

This function applies to independent samples student's t-tests.

If the function is used in the data load script, the values are iterated over a number of records as defined by a group by clause.

If the function is used in a chart expression, the values are iterated over the chart dimensions.

**Syntax:**

```
ZTestw_upper (grp, value [, sig [, eq_var]])
```

**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
value	The sample values to be evaluated. The sample values must be logically grouped as specified by exactly two values in <b>group</b> . If a field name for the sample values is not provided in the load script, the field will automatically be named <b>Value</b> .
grp	The field containing the names of each of the two sample groups. If a field name for the group is not provided in the load script, the field will automatically be given the name <b>Type</b> .
sig	The two-tailed level of significance can be specified in <b>sig</b> . If omitted, <b>sig</b> is set to 0.025, resulting in a 95% confidence interval.
eq_var	If <b>eq_var</b> is specified as False (0), separate variances of the two samples will be assumed. If <b>eq_var</b> is specified as True (1), equal variances between the samples will be assumed.


**Limitations:**

Text values, NULL values and missing values in the expression value will result in the function returning NULL.

**Examples:**

```
ZTestw_upper( Group, Value )
ZTestw_upper( Group, Value, sig, false )
```

**See also:**

 [Examples of how to use z-test functions \(page 531\)](#)

## Statistical test function examples

This section includes examples of statistical test functions as applied to charts and the data load script.

### Examples of how to use chi2-test functions in charts

The chi2-test functions are used to find values associated with chi squared statistical analysis.

This section describes how to build visualizations using sample data to find the values of the chi-squared distribution test functions available in Qlik Sense. Please refer to the individual chi2-test chart function topics for descriptions of syntax and arguments.

### Loading the data for the samples


There are three sets of sample data describing three different statistical samples to be loaded into the script.

Do the following:

1. Create a new app.
2. In the data load, enter the following:

```
// Sample_1 data is pre-aggregated... Note: make sure you set your DecimalSep='.' at the
top of the script.
Sample_1:
LOAD * inline [
Grp,Grade,Count
I,A,15
I,B,7
I,C,9
I,D,20
I,E,26
I,F,19
II,A,10
II,B,11
II,C,7
II,D,15
II,E,21
II,F,16
];
// Sample_2 data is pre-aggregated: If raw data is used, it must be aggregated using
count()...
Sample_2:
LOAD * inline [
Sex,Opinion,OpCount
1,2,58
1,1,11
1,0,10
2,2,35
2,1,25
2,0,23 ] (delimiter is ',');
// Sample_3a data is transformed using the crosstable statement...
Sample_3a:
crosstable(Gender, Actual) LOAD
Description,
[Men (Actual)] as Men,
[Women (Actual)] as women;
LOAD * inline [
Men (Actual),women (Actual),Description
58,35,Agree
11,25,Neutral
10,23,Disagree ] (delimiter is ',');
// Sample_3b data is transformed using the crosstable statement...
Sample_3b:
crosstable(Gender, Expected) LOAD
Description,
[Men (Expected)] as Men,
[Women (Expected)] as Women;
LOAD * inline [
Men (Expected),women (Expected),Description
```



```
45.35,47.65,Agree
17.56,18.44,Neutral
16.09,16.91,Disagree ] (delimiter is ',');
// Sample_3a and Sample_3b will result in a (fairly harmless) synthetic Key...
```

3. Click  to load data.

### Creating the chi2-test chart function visualizations

#### Example: Sample 1

Do the following:

1. In the data load editor, click  to go to the app view and then click the sheet you created before.  
The sheet view is opened.
2. Click  **Edit sheet** to edit the sheet.
3. From **Charts** add a table, and from **Fields** add Grp, Grade, and Count as dimensions.  
This table shows the sample data.
4. Add another table with the following expression as a dimension.  
`valueList('p', 'df', 'chi2')`  
This uses the synthetic dimensions function to create labels for the dimensions with the names of the three chi2-test functions.
5. Add the following expression to the table as a measure.  
`IF(ValueList('p', 'df', 'Chi2')='p', Chi2Test_p(Grp, Grade, Count),  
IF(ValueList('p', 'df', 'Chi2')='df', Chi2Test_df(Grp, Grade, Count),  
Chi2Test_Chi2(Grp, Grade, Count)))`  
This has the effect of putting the resulting value of each chi2-test function in the table next to its associated synthetic dimension.
6. Set the **Number formatting** of the measure to **Number** and **3Significant figures**.



*In the expression for the measure, you could use the following expression instead: `pick (Match(ValueList('p', 'df', 'Chi2'), 'p', 'df', 'Chi2'), Chi2Test_p (Grp, Grade, Count), Chi2Test_df(Grp, Grade, Count), Chi2Test_Chi2(Grp, Grade, Count))`*

#### Result:

The resulting table for the chi2-test functions for the Sample 1 data will contain the following values:

Results table		
<b>p</b>	<b>df</b>	<b>Chi2</b>
0.820	5	2.21

#### Example: Sample 2

Do the following:

1. In the sheet you were editing in the example Sample 1, from **Charts** add a table, and from **Fields** add Sex, Opinion, and OpCount as dimensions.
2. Make a copy of the results table from Sample 1 using the **Copy** and **Paste** commands. Edit the expression in the measure and replace the arguments in all three chi2-test functions with the names of the fields used in the Sample 2 data, for example: `chi2Test_p(Sex,Opinion,OpCount)`.

**Result:**

The resulting table for the chi2-test functions for the Sample 2 data will contain the following values:

<b>p</b>	<b>df</b>	<b>Chi2</b>
0.000309	2	16.2

**Example: Sample 3**

Do the following:

1. Create two more tables in the same way as in the examples for Sample 1 and Sample 2 data. In the dimensions table, use the following fields as dimensions: Gender, Description, Actual, and Expected.
2. In the results table, use the names of the fields used in the Sample 3 data, for example: `chi2Test_p(Gender,Description,Actual,Expected)`.

**Result:**

The resulting table for the chi2-test functions for the Sample 3 data will contain the following values:

<b>p</b>	<b>df</b>	<b>Chi2</b>
0.000308	2	16.2

Examples of how to use chi2-test functions in the data load script

The chi2-test functions are used to find values associated with chi squared statistical analysis. This section describes how to use the chi-squared distribution test functions available in Qlik Sense in the data load script. Please refer to the individual chi2-test script function topics for descriptions of syntax and arguments.

This example uses a table containing the number of students achieving a grade (A-F) for two groups of students (I and II).


Data table

Group	A	B	C	D	E	F
I	15	7	9	20	26	19
II	10	11	7	15	21	16

### Loading the sample data

Do the following:

1. Create a new app.
2. In the data load editor, enter the following:  

```
// sample_1 data is pre-aggregated... Note: make sure you set your DecimalSep='.' at the top of the script.
sample_1:
LOAD * inline [
Grp,Grade,Count
I,A,15
I,B,7
I,C,9
I,D,20
I,E,26
I,F,19
II,A,10
II,B,11
II,C,7
II,D,15
II,E,21
II,F,16
];
```
3. Click  to load data.


You have now loaded the sample data.

### Loading the chi2-test function values

Now we will load the chi2-test values based on the sample data in a new table, grouped by Grp.

Do the following:

1. In the data load editor, add the following at the end of the script:  

```
// sample_1 data is pre-aggregated... Note: make sure you set your DecimalSep='.' at the top of the script.
chi2_table:
LOAD Grp,
Chi2Test_chi2(Grp, Grade, Count) as chi2,
Chi2Test_df(Grp, Grade, Count) as df,
Chi2Test_p(Grp, Grade, Count) as p
resident Sample_1 group by Grp;
```
2. Click  to load data.

You have now loaded the chi2-test values in a table named Chi2\_table.

### Results

You can view the resulting chi2-test values in the data model viewer under **Preview**, they should look like this:

Results

Grp	chi2	df	p
I	16.00	5	0.007
II	9.40	5	0.094

### Creating a typical t-test report

A typical student t-test report can include tables with **Group Statistics** and **Independent Samples Test** results.

In the following sections we will build these tables using Qlik Sense t-test functions applied to two independent groups of samples, Observation and Comparison. The corresponding tables for these samples would look like this:

Group statistics

Type	N	Mean	Standard Deviation	Standard Error Mean
Comparison	20	11.95	14.61245	3.2674431
Observation	20	27.15	12.507997	2.7968933

Independent sample test

Type	conf	t	df	Sig. (2-tailed)	Mean Difference	Standard Error Difference	95% Confidence Interval (Lower)	95% Confidence Interval (Upper)
Equal Variance not Assumed	0	3.534	37.116717335823	0.001	15.2	4.30101	6.48625	23.9137
Equal Variance Assumed	8.706939	3.534	38	0.001	15.2	4.30101	6.49306	23.9069

### Loading the sample data

Do the following:

1. Create a new app with a new sheet.
2. Enter the following in the data load editor:

Table1:

```
Crosstable (Type, value)
```

```
Load recno() as ID, * inline [
```

```
Observation|Comparison
```

```
35|2
```

```
40|27
```

```
12|38
```

```
15|31
```

```
21|1
```

```
14|19
```

```
46|1
```

```
10|34
```

```
28|3
```

```
48|1
```

```
16|2
```

```
30|3
```

```
32|2
```

```
48|1
```

```
31|2
```

```
22|1
```


```
12|3
```

```
39|29
```

```
19|37
```



```
25|2 ] (delimiter is '|');
```

In this load script, **recno()** is included because **crosstable** requires three arguments. So, **recno()** simply provides an extra argument, in this case an ID for each row. Without it, **Comparison** sample values would not be loaded.

3. Click  to load data.

### Creating the Group statistics table

Do the following:

1. In the data load editor, click  to go to app view, and then click the sheet you created before.  
This opens the sheet view.
2. Click  **Edit sheet** to edit the sheet.
3. From **Charts**, add a table, and from **Fields**, add Type as a dimension to the table.



4. Add the following expressions as measures.

Example expressions

Label	Expression
N	Count(Value)
Mean	Avg(Value)
Standard Deviation	Stdev(Value)
Standard Error Mean	Sterr(Value)

5. Click **Sorting** and make sure Type is at the top of the sorting list.

**Result:**


A Group statistics table for these samples would look like this:

Group statistics

Type	N	Mean	Standard Deviation	Standard Error Mean
Comparison	20	11.95	14.61245	3.2674431
Observation	20	27.15	12.507997	2.7968933

**Creating the Independent sample test table**

Do the following:

1. Click  **Edit sheet** to edit the sheet.
2. From **Charts** add a table with the following expression as a dimension to the table. `=valueList(Dual('Equal variance not Assumed', 0), Dual('Equal variance Assumed', 1))` and give it the label Type.

3. Add the following expressions as measures:

Example expressions

Label	Expression
conf	if(ValueList (Dual('Equal Variance not Assumed', 0), Dual('Equal Variance Assumed', 1)),TTest_conf(Type, Value),TTest_conf(Type, Value, 0))
t	if(ValueList (Dual('Equal Variance not Assumed', 0), Dual('Equal Variance Assumed', 1)),TTest_t(Type, Value),TTest_t(Type, Value, 0))
df	if(ValueList (Dual('Equal Variance not Assumed', 0), Dual('Equal Variance Assumed', 1)),TTest_df(Type, Value),TTest_df(Type, Value, 0))
Sig. (2-tailed)	if(ValueList (Dual('Equal Variance not Assumed', 0), Dual('Equal Variance Assumed', 1)),TTest_sig(Type, Value),TTest_sig(Type, Value, 0))
Mean Difference	TTest_dif(Type, Value)
Standard Error Difference	if(ValueList (Dual('Equal Variance not Assumed', 0), Dual('Equal Variance Assumed', 1)),TTest_sterr(Type, Value),TTest_sterr(Type, Value, 0))
95% Confidence Interval (Lower)	if(ValueList (Dual('Equal Variance not Assumed', 0), Dual('Equal Variance Assumed', 1)),TTest_lower(Type, Value,(1-(95)/100)/2),TTest_lower (Type, Value,(1-(95)/100)/2, 0))
95% Confidence Interval (Upper)	if(ValueList (Dual('Equal Variance not Assumed', 0), Dual('Equal Variance Assumed', 1)),TTest_upper(Type, Value,(1-(95)/100)/2),TTest_upper (Type, Value,(1-(95)/100)/2, 0))

**Result:**

Independent sample test

Type	conf	t	df	Sig. (2-tailed)	Mean Difference	Standard Error Difference	95% Confidence Interval (Lower)	95% Confidence Interval (Upper)
Equal Variance not Assumed	0	3.534	37.116717335823	0.001	15.2	4.30101	6.48625	23.9137

Type	conf	t	df	Sig. (2-tailed)	Mean Difference	Standard Error Difference	95% Confidence Interval (Lower)	95% Confidence Interval (Upper)
Equal Variance Assumed	8.706939	3.534	38	0.001	15.2	4.30101	6.49306	23.9069

### Examples of how to use z-test functions

The z-test functions are used to find values associated with z-test statistical analysis for large data samples, usually greater than 30, and where the variance is known.

This section describes how to build visualizations using sample data to find the values of the z-test functions available in Qlik Sense. Please refer to the individual z-test chart function topics for descriptions of syntax and arguments.

#### Loading the sample data

The sample data used here is the same as that used in the t-test function examples. The sample data size would normally be considered too small for z-test analysis, but is sufficient for the purposes of illustrating the use of the different z-test functions in Qlik Sense.

Do the following:

1. Create a new app with a new sheet.



*If you created an app for the t-test functions, you could use that and create a new sheet for these functions.*

2. In the data load editor, enter the following:

```
Table1:
Crosstable (Type, value)
Load recno() as ID, * inline [
Observation|Comparison
35|2
40|27
12|38
15|31
21|1
14|19
46|1
10|34
28|3
48|1
16|2
```

```

30|3
32|2
48|1
31|2
22|1
12|3
39|29
19|37
25|2 ] (delimiter is '|');



```

In this load script, **recno()** is included because **crostable** requires three arguments. So, **recno()** simply provides an extra argument, in this case an ID for each row. Without it, **Comparison** sample values would not be loaded.

3. Click  to load data.

### Creating the z-test table

Do the following:

1. In the data load editor, click  to go to app view, and then click the sheet you created above.  
The sheet view is opened.
2. Click  **Edit sheet** to edit the sheet.
3. From **Charts** add a table, and from **Fields** add Type as a dimension.
4. Add the following expressions to the table as measures

Example expressions

Label	Expression
ZTest Conf	ZTest_conf(Value)
ZTest Dif	ZTest_dif(Value)
ZTest Sig	ZTest_sig(Value)
ZTest Sterr	ZTest_sterr(Value)
ZTest Z	ZTest_z(Value)



*You might wish to adjust the number formatting of the measures to see meaningful values. The table will be easier to read if you set number formatting on most of the measures to **Number>Simple**, instead of **Auto**. But for ZTest Sig, for example, use the number formatting: **Custom**, and then adjust the format pattern to **#.#####**.*

### Result:

The resulting table for the z-test functions for the sample data will contain the following values:

z-test results table

Type	ZTest Conf	ZTest Dif	ZTest Sig	ZTest Sterr	ZTest Z
Comparison	6.40	11.95	0.000123	3.27	3.66



Type	ZTest Conf	ZTest Dif	ZTest Sig	ZTest Sterr	ZTest Z
Observation	5.48	27.15	0.000000	2.80	9.71

### Creating the z-testw table

The z-testw functions are for use when the input data series occurs in weighted two-column format. The expressions require a value for the argument weight.

The examples here use the value 2 throughout, but you could use an expression, which would define a value for weight for each observation.

Do the following:

1. In the data load editor, click  to go to app view, and then click the sheet you created above.  
The sheet view is opened.
2. Click  **Edit sheet** to edit the sheet.
3. From **Charts** add a table, and from **Fields** add Type as a dimension.
4. Add the following expressions to the table as measures.

Example expressions

Label	Expression
ZTestw Conf	ZTestw_conf(2,Value)
ZTestw Dif	ZTestw_dif(2,Value)
ZTestw Sig	ZTestw_sig(2,Value)
ZTestw Sterr	ZTestw_sterr(2,Value)
ZTestw Z	ZTestw_z(2,Value)

Use the same number formatting as in the z-test functions example.

### Result:

The resulting table for the z-testw functions will contain the following values:

z-testw results table

Type	ZTestw Conf	ZTestw Dif	ZTestw Sig	ZTestw Sterr	ZTestw Z
Comparison	4.47	11.95	8.037185e-08	2.28	5.24
Observation	3.83	27.15	0	1.95	13.91

## String aggregation functions

This section describes string-related aggregation functions.

Each function is described further after the overview. You can also click the function name in the syntax to immediately access the details for that specific function.

### String aggregation functions in the data load script

#### Concat

**Concat()** is used to combine string values. The script function returns the aggregated string concatenation of all values of the expression iterated over a number of records as defined by a **group by** clause.

```
Concat ([ distinct ] expression [, delimiter [, sort-weight]])
```

#### FirstValue

**FirstValue()** returns the value that was loaded first from the records defined by the expression, sorted by a **group by** clause.



*This function is only available as a script function.*

```
FirstValue (expression)
```

#### LastValue

**LastValue()** returns the value that was loaded last from the records defined by the expression, sorted by a **group by** clause.



*This function is only available as a script function.*

```
LastValue (expression)
```

#### MaxString

**MaxString()** finds string values in the expression and returns the last text value sorted alphabetically over a number of records, as defined by a **group by** clause.

```
MaxString (expression )
```

#### MinString

**MinString()** finds string values in the expression and returns the first text value sorted alphabetically over a number of records, as defined by a **group by** clause.

```
MinString (expression )
```

### String aggregation functions in charts

The following chartfunctions are available for aggregating strings in charts

#### Concat

**Concat()** is used to combine string values. The function returns the aggregated string concatenation of all the values of the expression evaluated over each dimension.

```
Concat - chart function({[SetExpression] [DISTINCT] [TOTAL [<fld{, fld}>]]  
string[, delimiter[, sort_weight]])
```

MaxString

**MaxString()** finds string values in the expression or field and returns the last text value in alphabetical sort order.

```
MaxString - chart function({[SetExpression] [TOTAL [<fld{, fld}>]]) expr)
```

MinString

**MinString()** finds string values in the expression or field and returns the first text value in alphabetical sort order.

```
MinString - chart function({[SetExpression] [TOTAL [<fld {, fld}>]]) expr)
```

Concat

**Concat()** is used to combine string values. The script function returns the aggregated string concatenation of all values of the expression iterated over a number of records as defined by a **group by** clause.

**Syntax:**

```
Concat ([ distinct ] string [, delimiter [, sort-weight]])
```

**Return data type:** string

**Arguments:**

The expression or field containing the string to be processed.

Arguments

Argument	Description
string	The expression or field containing the string to be processed.
delimiter	Each value may be separated by the string found in delimiter.
sort-weight	The order of concatenation may be determined by the value of the dimension <b>sort-weight</b> , if present, with the string corresponding to the lowest value appearing first in the concatenation.
distinct	If the word <b>distinct</b> occurs before the expression, all duplicates are disregarded.

**Examples and results:**

Add the example script to your app and run it. To see the result, add the fields listed in the results column to a sheet in your app.

## Examples and results

Example	Result	Results once added to a sheet
<p><b>TeamData:</b>  LOAD * inline [  SalesGroup Team Date Amount  East Gamma 01/05/2013 20000  East Gamma 02/05/2013 20000  West Zeta 01/06/2013 19000  East Alpha 01/07/2013 25000  East Delta 01/08/2013 14000  West Epsilon 01/09/2013 17000  West Eta 01/10/2013 14000  East Beta 01/11/2013 20000  West Theta 01/12/2013 23000  ] (delimiter is ' ');</p> <p><b>Concat1:</b>  LOAD SalesGroup,Concat(Team) as  TeamConcat1 Resident TeamData Group By  SalesGroup;</p>	SalesGroup  East  West	TeamConcat1  AlphaBetaDeltaGammaGamma  EpsilonEtaThetaZeta
<p>Given that the <b>TeamData</b> table is loaded as in the previous example:</p> <p>LOAD SalesGroup,Concat(distinct Team,'-') as TeamConcat2 Resident TeamData Group By SalesGroup;</p>	SalesGroup  East  West	TeamConcat2  Alpha-Beta-Delta-Gamma  Epsilon-Eta-Theta-Zeta
<p>Given that the <b>TeamData</b> table is loaded as in the previous example. Because the argument for <b>sort-weight</b> is added, the results are ordered by the value of the dimension Amount:</p> <p>LOAD SalesGroup,Concat(distinct Team,'-',Amount) as TeamConcat2 Resident TeamData Group By SalesGroup;</p>	SalesGroup  East  West	TeamConcat2  Delta-Beta-Gamma-Alpha  Eta-Epsilon-Zeta-Theta

## Concat - chart function

**Concat()** is used to combine string values. The function returns the aggregated string concatenation of all the values of the expression evaluated over each dimension.

**Syntax:**

```
Concat({[SetExpression] [DISTINCT] [TOTAL [<fld{, fld}>]]} string[, delimiter [, sort_weight]])
```



**Return data type:** string

**Arguments:**

Arguments

Argument	Description
string	The expression or field containing the string to be processed.
delimiter	Each value may be separated by the string found in delimiter.
sort-weight	The order of concatenation may be determined by the value of the dimension <b>sort-weight</b> , if present, with the string corresponding to the lowest value appearing first in the concatenation.
SetExpression	By default, the aggregation function will aggregate over the set of possible records defined by the selection. An alternative set of records can be defined by a set analysis expression.
DISTINCT	If the word <b>DISTINCT</b> occurs before the function arguments, duplicates resulting from the evaluation of the function arguments are disregarded.
TOTAL	<p>If the word <b>TOTAL</b> occurs before the function arguments, the calculation is made over all possible values given the current selections, and not just those that pertain to the current dimensional value, that is, it disregards the chart dimensions.</p> <p>By using <b>TOTAL [&lt;fld {fld}&gt;]</b>, where the <b>TOTAL</b> qualifier is followed by a list of one or more field names as a subset of the chart dimension variables, you create a subset of the total possible values.</p>

**Examples and results:**

Results table

SalesGroup	Amount	Concat(Team)	Concat(TOTAL <SalesGroup> Team)
East	25000	Alpha	AlphaBetaDeltaGammaGamma
East	20000	BetaGammaGamma	AlphaBetaDeltaGammaGamma
East	14000	Delta	AlphaBetaDeltaGammaGamma
West	17000	Epsilon	EpsilonEtaThetaZeta
West	14000	Eta	EpsilonEtaThetaZeta
West	23000	Theta	EpsilonEtaThetaZeta
West	19000	Zeta	EpsilonEtaThetaZeta

## Function examples

Example	Result
Concat(Team)	The table is constructed from the dimensions SalesGroup and Amount, and variations on the measure Concat(Team). Ignoring the Totals result, note that even though there is data for eight values of Team spread across two values of SalesGroup, the only result of the measure Concat(Team) that concatenates more than one Team string value in the table is the row containing the dimension Amount 20000, which gives the result BetaGammaGamma. This is because there are three values for the Amount 20000 in the input data. All other results remain unconcatenated when the measure is spanned across the dimensions because there is only one value of Team for each combination of SalesGroup and Amount.
Concat (DISTINCT Team, ', ')	Beta, Gamma. because the DISTINCT qualifier means the duplicate Gamma result is disregarded. Also, the delimiter argument is defined as a comma followed by a space.
Concat (TOTAL <SalesGroup> Team)	All the string values for all values of Team are concatenated if the TOTAL qualifier is used. With the fieldselection <SalesGroup> specified, this divides the results into the two values of the dimension SalesGroup. For the SalesGroupEast, the results are AlphaBetaDeltaGammaGamma. For the SalesGroupWest, the results are EpsilonEtaThetaZeta.
Concat (TOTAL <SalesGroup> Team, ';', Amount)	By adding the argument for <b>sort-weight</b> : Amount, the results are ordered by the value of the dimension Amount. The results becomes DeltaBetaGammaGammaAlpha and EtaEpsilonZetaTheta.

Data used in example:

```
TeamData:
LOAD * inline [
SalesGroup|Team|Date|Amount
East|Gamma|01/05/2013|20000
East|Gamma|02/05/2013|20000
west|Zeta|01/06/2013|19000
East|Alpha|01/07/2013|25000
East|Delta|01/08/2013|14000
west|Epsilon|01/09/2013|17000
west|Eta|01/10/2013|14000
East|Beta|01/11/2013|20000
west|Theta|01/12/2013|23000
] (delimiter is '|');
```

## FirstValue

**FirstValue()** returns the value that was loaded first from the records defined by the expression, sorted by a **group by** clause.



*This function is only available as a script function.*

### Syntax:

```
FirstValue ( expr)
```

**Return data type:** dual

### Arguments:

Arguments

Argument	Description
expr	The expression or field containing the data to be measured.

### Limitations:

If no text value is found, NULL is returned.

### Examples and results:

Add the example script to your app and run it. To see the result, add the fields listed in the results column to a sheet in your app.

Resulting data

Example	Result	Results on a sheet
<pre>TeamData: LOAD * inline [ SalesGroup Team Date Amount East Gamma 01/05/2013 20000 East Gamma 02/05/2013 20000 west Zeta 01/06/2013 19000 East Alpha 01/07/2013 25000 East Delta 01/08/2013 14000 west Epsilon 01/09/2013 17000 west Eta 01/10/2013 14000 East Beta 01/11/2013 20000 west Theta 01/12/2013 23000 ] (delimiter is ' ');  FirstValue1: LOAD SalesGroup,FirstValue(Team) as FirstTeamLoaded Resident TeamData Group By SalesGroup;</pre>	<p>SalesGroup</p> <p>East</p> <p>West</p>	<p>FirstTeamLoaded</p> <p>Gamma</p> <p>Zeta</p>

### LastValue

**LastValue()** returns the value that was loaded last from the records defined by the expression, sorted by a **group by** clause.



*This function is only available as a script function.*

### Syntax:

```
LastValue ( expr )
```

**Return data type:** dual

### Arguments:

#### Arguments

Argument	Description
expr	The expression or field containing the data to be measured.

### Limitations:

If no text value is found, NULL is returned.

### Examples and results:

Add the example script to your app and run it. Then add, at least, the fields listed in the results column to a sheet in our app to see the result.

To get the same look as in the result column below, in the properties panel, under Sorting, switch from Auto to Custom, then deselect numerical and alphabetical sorting.

Example	Result	Result with custom sorting
<pre>TeamData: LOAD * inline [ SalesGroup Team Date Amount East Gamma 01/05/2013 20000 East Gamma 02/05/2013 20000 West Zeta 01/06/2013 19000 East Alpha 01/07/2013 25000 East Delta 01/08/2013 14000 West Epsilon 01/09/2013 17000 West Eta 01/10/2013 14000 East Beta 01/11/2013 20000 West Theta 01/12/2013 23000 ] (delimiter is ' ');  LastValue1: LOAD SalesGroup,LastValue(Team) as LastTeamLoaded Resident TeamData Group By SalesGroup;</pre>	<p>SalesGroup</p> <p>East</p> <p>West</p>	<p>LastTeamLoaded</p> <p>Beta</p> <p>Theta</p>

## MaxString

**MaxString()** finds string values in the expression and returns the last text value sorted alphabetically over a number of records, as defined by a **group by** clause.

### Syntax:

```
MaxString ( expr )
```

**Return data type:** dual

**Arguments:**

Argument	Description
expr	The expression or field containing the data to be measured.

**Limitations:**

If no text value is found, NULL is returned.

**Examples and results:**

Add the example script to your app and run it. To see the result, add the fields listed in the results column to a sheet in your app.

Example	Result	
<pre>TeamData: LOAD * inline [ SalesGroup Team Date Amount East Gamma 01/05/2013 20000 East Gamma 02/05/2013 20000 West Zeta 01/06/2013 19000 East Alpha 01/07/2013 25000 East Delta 01/08/2013 14000 West Epsilon 01/09/2013 17000 West Eta 01/10/2013 14000 East Beta 01/11/2013 20000 West Theta 01/12/2013 23000 ] (delimiter is ' ');  Concat1: LOAD SalesGroup,MaxString(Team) as MaxString1 Resident TeamData Group By SalesGroup;</pre>	SalesGroup East West	MaxString1 Gamma Zeta
<p>Given that the <b>TeamData</b> table is loaded as in the previous example, and your data load scripthis has the SET statement:</p> <pre>SET DateFormat='DD/MM/YYYY';  LOAD SalesGroup,MaxString(Date) as MaxString2 Resident TeamData Group By SalesGroup;</pre>	SalesGroup East West	MaxString2 01/11/2013 01/12/2013

### MaxString - chart function

**MaxString()** finds string values in the expression or field and returns the last text value in alphabetical sort order.

**Syntax:**

```
MaxString([SetExpression] [TOTAL [<fld{, fld}>]]) expr)
```

**Return data type:** dual

**Arguments:**

Arguments

Argument	Description
expr	The expression or field containing the data to be measured.
SetExpression	By default, the aggregation function will aggregate over the set of possible records defined by the selection. An alternative set of records can be defined by a set analysis expression.
TOTAL	<p>If the word <b>TOTAL</b> occurs before the function arguments, the calculation is made over all possible values given the current selections, and not just those that pertain to the current dimensional value, that is, it disregards the chart dimensions.</p> <p>By using <b>TOTAL [&lt;fld {fld}&gt;]</b>, where the <b>TOTAL</b> qualifier is followed by a list of one or more field names as a subset of the chart dimension variables, you create a subset of the total possible values.</p>

**Limitations:**

If the expression contains no values with a string representation NULL is returned.

**Examples and results:**

Results table

SalesGroup	Amount	MaxString(Team)	MaxString(Date)
East	14000	Delta	2013/08/01
East	20000	Gamma	2013/11/01
East	25000	Alpha	2013/07/01
West	14000	Eta	2013/10/01
West	17000	Epsilon	2013/09/01
West	19000	Zeta	2013/06/01
West	23000	Theta	2013/12/01

### Function examples

Example	Result
MaxString (Team)	There are three values of 20000 for the dimension Amount: two of Gamma (on different dates), and one of Beta. The result of the measure MaxString (Team) is therefore Gamma, because this is the highest value in the sorted strings.
MaxString (Date)	2013/11/01 is the greatest Date value of the three associated with the dimension Amount. This assumes your script has the SET statement <code>SET DateFormat='YYYY-MM-DD';</code>

Data used in example:

```
TeamData:
LOAD * inline [
SalesGroup|Team|Date|Amount
East|Gamma|01/05/2013|20000
East|Gamma|02/05/2013|20000
West|Zeta|01/06/2013|19000
East|Alpha|01/07/2013|25000
East|Delta|01/08/2013|14000
West|Epsilon|01/09/2013|17000
West|Eta|01/10/2013|14000
East|Beta|01/11/2013|20000
West|Theta|01/12/2013|23000
] (delimiter is '|');
```

### MinString

**MinString()** finds string values in the expression and returns the first text value sorted alphabetically over a number of records, as defined by a **group by** clause.

#### Syntax:

```
MinString ( expr )
```

**Return data type:** dual

#### Arguments:

##### Arguments

Argument	Description
expr	The expression or field containing the data to be measured.

#### Limitations:

If no text value is found, NULL is returned.

### Examples and results:

Add the example script to your app and run it. To see the result, add the fields listed in the results column to a sheet in your app.

Resulting data

Example	Result	
<b>TeamData:</b> LOAD * inline [ SalesGroup Team Date Amount East Gamma 01/05/2013 20000 East Gamma 02/05/2013 20000 West Zeta 01/06/2013 19000 East Alpha 01/07/2013 25000 East Delta 01/08/2013 14000 West Epsilon 01/09/2013 17000 West Eta 01/10/2013 14000 East Beta 01/11/2013 20000 West Theta 01/12/2013 23000 ] (delimiter is ' ');  <b>Concat1:</b> LOAD SalesGroup,MinString(Team) as MinString1 Resident TeamData Group By SalesGroup;	SalesGroup	MinString1
	East	Alpha
	West	Epsilon
Given that the <b>TeamData</b> table is loaded as in the previous example, and your data load scrip has the SET statement: SET DateFormat='DD/MM/YYYY';  LOAD SalesGroup,MinString(Date) as MinString2 Resident TeamData Group By SalesGroup;	SalesGroup	MinString2
	East	01/05/2013
	West	01/06/2013

### MinString - chart function

**MinString()** finds string values in the expression or field and returns the first text value in alphabetical sort order.

#### Syntax:

```
MinString({[SetExpression] [TOTAL [<fld {, fld}>]]) expr)
```

**Return data type:** dual

#### Arguments:

Arguments

Argument	Description
expr	The expression or field containing the data to be measured.



Argument	Description
SetExpression	By default, the aggregation function will aggregate over the set of possible records defined by the selection. An alternative set of records can be defined by a set analysis expression.
TOTAL	<p>If the word <b>TOTAL</b> occurs before the function arguments, the calculation is made over all possible values given the current selections, and not just those that pertain to the current dimensional value, that is, it disregards the chart dimensions.</p> <p>By using <b>TOTAL [&lt;fld {fld}&gt;]</b>, where the <b>TOTAL</b> qualifier is followed by a list of one or more field names as a subset of the chart dimension variables, you create a subset of the total possible values.</p>

### Examples and results:

Sample data

SalesGroup	Amount	MinString(Team)	MinString(Date)
East	14000	Delta	2013/08/01
East	20000	Beta	2013/05/01
East	25000	Alpha	2013/07/01
West	14000	Eta	2013/10/01
West	17000	Epsilon	2013/09/01
West	19000	Zeta	2013/06/01
West	23000	Theta	2013/12/01

Function examples

Examples	Results
MinString (Team)	There are three values of 20000 for the dimension Amount: two of Gamma (on different dates), and one of Beta. The result of the measure MinString (Team) is therefore Beta, because this is the first value in the sorted strings.
MinString (Date)	2013/11/01 is the earliest Date value of the three associated with the dimension Amount. This assumes your script has the SET statement <code>SET DateFormat='YYYY-MM-DD';</code>

### Data used in example:

```
TeamData:
LOAD * inline [
SalesGroup|Team|Date|Amount
East|Gamma|01/05/2013|20000
East|Gamma|02/05/2013|20000
west|Zeta|01/06/2013|19000
East|Alpha|01/07/2013|25000
```

```
East|Delta|01/08/2013|14000
West|Epsilon|01/09/2013|17000
West|Eta|01/10/2013|14000
East|Beta|01/11/2013|20000
West|Theta|01/12/2013|23000
] (delimiter is '|');
```

### Synthetic dimension functions

A synthetic dimension is created in the app from values generated from the synthetic dimension functions and not directly from fields in the data model. When values generated by a synthetic dimension function are used in a chart as a calculated dimension, this creates a synthetic dimension. Synthetic dimensions allow you to create, for example, charts with dimensions with values arising from your data, that is, dynamic dimensions.



*Synthetic dimensions are not affected by selections.*

The following synthetic dimension functions can be used in charts.

#### ValueList

**ValueList()** returns a set of listed values, which, when used in a calculated dimension, will form a synthetic dimension.

```
ValueList - chart function (v1 {, Expression})
```

#### ValueLoop

ValueLoop() returns a set of iterated values which, when used in a calculated dimension, will form a synthetic dimension.

```
ValueLoop - chart function(from [, to [, step ]])
```

#### ValueList - chart function

**ValueList()** returns a set of listed values, which, when used in a calculated dimension, will form a synthetic dimension.



*In charts with a synthetic dimension created with the **ValueList** function it is possible to reference the dimension value corresponding to a specific expression cell by restating the **ValueList** function with the same parameters in the chart expression. The function may of course be used anywhere in the layout, but apart from when used for synthetic dimensions it will only be meaningful inside an aggregation function.*



*Synthetic dimensions are not affected by selections.*

#### Syntax:

```
ValueList (v1 {, ...})
```

**Return data type:** dual

**Arguments:**

Arguments

Argument	Description
v1	Static value (usually a string, but can be a number).
{,...}	Optional list of static values.

**Examples and results:**

Function examples

Example	Result																											
ValueList ('Number of Orders', 'Average Order Size', 'Total Amount')	When used to create a dimension in a table, for example, this results in the three string values as row labels in the table. These can then be referenced in an expression.																											
=IF( ValueList ('Number of Orders', 'Average Order Size', 'Total Amount') = 'Number of Orders', count (SaleID), IF( ValueList ('Number of Orders', 'Average Order Size', 'Total Amount') = 'Average Order Size', avg (Amount), sum (Amount) ))	<p>This expression takes the values from the created dimension and references them in a nested IF statement as input to three aggregation functions:</p> <table border="1"> <thead> <tr> <th colspan="3">ValueList()</th> </tr> <tr> <th>Created dimension</th> <th>Year</th> <th>Added expression</th> </tr> </thead> <tbody> <tr> <td></td> <td></td> <td>522.00</td> </tr> <tr> <td>Number of Orders</td> <td>2012</td> <td>5.00</td> </tr> <tr> <td>Number of Orders</td> <td>2013</td> <td>7.00</td> </tr> <tr> <td>Average Order Size</td> <td>2012</td> <td>13.20</td> </tr> <tr> <td>Average Order Size</td> <td>2013</td> <td>15.43</td> </tr> <tr> <td>Total Amount</td> <td>2012</td> <td>66.00</td> </tr> <tr> <td>Total Amount</td> <td>2013</td> <td>108.00</td> </tr> </tbody> </table>	ValueList()			Created dimension	Year	Added expression			522.00	Number of Orders	2012	5.00	Number of Orders	2013	7.00	Average Order Size	2012	13.20	Average Order Size	2013	15.43	Total Amount	2012	66.00	Total Amount	2013	108.00
ValueList()																												
Created dimension	Year	Added expression																										
		522.00																										
Number of Orders	2012	5.00																										
Number of Orders	2013	7.00																										
Average Order Size	2012	13.20																										
Average Order Size	2013	15.43																										
Total Amount	2012	66.00																										
Total Amount	2013	108.00																										

Data used in examples:

```

SalesPeople:
LOAD * INLINE [
SalesID|SalesPerson|Amount|Year
1|1|12|2013
2|1|23|2013
3|1|17|2013
4|2|9|2013
5|2|14|2013
6|2|29|2013

```

```
7|2|4|2013
8|1|15|2012
9|1|16|2012
10|2|11|2012
11|2|17|2012
12|2|7|2012
] (delimiter is '|');
```

### ValueLoop - chart function

ValueLoop() returns a set of iterated values which, when used in a calculated dimension, will form a synthetic dimension.

The values generated will start with the **from** value and end with the **to** value including intermediate values in increments of step.



*In charts with a synthetic dimension created with the **ValueLoop** function it is possible to reference the dimension value corresponding to a specific expression cell by restating the **ValueLoop** function with the same parameters in the chart expression. The function may of course be used anywhere in the layout, but apart from when used for synthetic dimensions it will only be meaningful inside an aggregation function.*



*Synthetic dimensions are not affected by selections.*

#### Syntax:

```
ValueLoop (from [, to [, step ]])
```

**Return data type:** dual

#### Arguments:

##### Arguments

Arguments	Description
from	Start value in the set of values to be generated.
to	End value in the set of values to be generated.
step	Size of increment between values.

#### Examples and results:

##### Function examples

Example	Result
ValueLoop (1, 10)	This creates a dimension in a table, for example, that can be used for purposes such as numbered labeling. The example here results in values numbered 1 to 10. These values can then be referenced in an expression.
ValueLoop (2, 10,2)	This example results in values numbered 2, 4, 6, 8, and 10 because the argument step has a value of 2.

### Nested aggregations

You may come across situations where you need to apply an aggregation to the result of another aggregation. This is referred to as nesting aggregations.

You cannot nest aggregations in most chart expressions. You can, however, nest aggregations if you use the **TOTAL** qualifier in the inner aggregation function.



*No more than 100 levels of nesting is allowed.*

### Nested aggregations with the TOTAL qualifier

#### Example:

You want to calculate the sum of the field **Sales**, but only include transactions with an **OrderDate** equal to the last year. The last year can be obtained via the aggregation function **Max (TOTAL Year (OrderDate))**.

The following aggregation would return the desired result:

```
Sum(If(Year(OrderDate)=Max(TOTAL Year(OrderDate)), Sales))
```

Qlik Sense requires the inclusion of the **TOTAL** qualifier this type of nesting. It is necessary for the desired comparison. This type of nesting need is quite common and is a good practice.

---

#### See also:

[Aggr - chart function \(page 549\)](#)

## 8.3 Aggr - chart function

**Aggr()** returns an array of values for the expression calculated over the stated dimension or dimensions. For example, the maximum value of sales, per customer, per region.

The **Aggr** function is used for nested aggregations, in which its first parameter (the inner aggregation) is calculated once per dimensional value. The dimensions are specified in the second parameter (and subsequent parameters).

In addition, the **Aggr** function should be enclosed in an outer aggregation function, using the array of results from the **Aggr** function as input to the aggregation in which it is nested.

#### Syntax:

```
Aggr ({SetExpression} [DISTINCT] [NODISTINCT ] expr, StructuredParameter{,  
StructuredParameter})
```

**Return data type:** dual

**Arguments:**

### Arguments

Argument	Description
expr	An expression consisting of an aggregation function. By default, the aggregation function will aggregate over the set of possible records defined by the selection.
StructuredParameter	<p>StructuredParameter consists of a dimension and optionally, sorting criteria in the format: (Dimension(sort-type, ordering))</p> <p>The dimension is a single field and cannot be an expression. The dimension is used to determine the array of values the Aggr expression is calculated for.</p> <p>If sorting criteria are included, the array of values created by the Aggr function, calculated for the dimension, is sorted. This is important when the sort order affects the result of the expression the Aggr function is enclosed in.</p> <p>For details of how to use sorting criteria, see <a href="#">Adding sorting criteria to the dimension in the structured parameter</a>.</p>
SetExpression	By default, the aggregation function will aggregate over the set of possible records defined by the selection. An alternative set of records can be defined by a set analysis expression.
DISTINCT	If the expression argument is preceded by the <b>distinct</b> qualifier or if no qualifier is used at all, each distinct combination of dimension values will generate only one return value. This is the normal way aggregations are made – each distinct combination of dimension values will render one line in the chart.
NODISTINCT	If the expression argument is preceded by the <b>nodistinct</b> qualifier, each combination of dimension values may generate more than one return value, depending on underlying data structure. If there is only one dimension, the <b>aggr</b> function will return an array with the same number of elements as there are rows in the source data.

Basic aggregation functions, such as **Sum**, **Min**, and **Avg**, return a single numerical value, whereas the **Aggr()** function can be compared to creating a temporary staged result set (a virtual table), over which another aggregation can be made. For example, by computing an average sales value by summing the sales by customer in an **Aggr()** statement, and then calculating the average of the summed results: **Avg(TOTAL Aggr(Sum(Sales),Customer))**.



Use the `Aggr()` function in calculated dimensions if you want to create nested chart aggregations on multiple levels.

### Limitations:

Each dimension in an `Aggr()` function must be a single field, and cannot be an expression (calculated dimension).

### Adding sorting criteria to the dimension in the structured parameter

In its basic form, the argument `StructuredParameter` in the `Aggr` function syntax is a single dimension. The expression: `Aggr(Sum(Sales, Month))` finds the total value of sales for each month. However, when enclosed in another aggregation function, there can be unexpected results unless sorting criteria are used. This is because some dimensions can be sorted numerically or alphabetically, and so on.

In the `StructuredParameter` argument in the `Aggr` function, you can specify sorting criteria on the dimension in your expression. This way, you impose a sort order on the virtual table that is produced by the `Aggr` function.

The argument `StructuredParameter` has the following syntax:

```
(FieldName, (Sort-type, Ordering))
```

Structured parameters can be nested:

```
(FieldName, (FieldName2, (Sort-type, Ordering)))
```

Sort-type can be: `NUMERIC`, `TEXT`, `FREQUENCY`, or `LOAD_ORDER`.

The Ordering types associated with each Sort-type are as follows:

Allowed ordering types

Sort-type	Allowed Ordering types
NUMERIC	ASCENDING, DESCENDING, or REVERSE
TEXT	ASCENDING, A2Z, DESCENDING, REVERSE, or Z2A
FREQUENCY	DESCENDING, REVERSE or ASCENDING
LOAD_ORDER	ASCENDING, ORIGINAL, DESCENDING, or REVERSE

The ordering types `REVERSE` and `DESCENDING` are equivalent.

For Sort-type `TEXT`, the ordering types `ASCENDING` and `A2Z` are equivalent, and `DESCENDING`, `REVERSE`, and `Z2A` are equivalent.

For Sort-type `LOAD_ORDER`, the ordering types `ASCENDING` and `ORIGINAL` are equivalent.

### Examples: Chart expressions using Aggr

Examples - chart expressions

#### Chart expression example 1

##### Load script

Load the following data as an inline load in the data load editor to create the chart expression example below.

ProductData:

```
LOAD * inline [  
Customer|Product|UnitsSales|UnitPrice  
Astrida|AA|4|16  
Astrida|AA|10|15  
Astrida|BB|9|9  
Betacab|BB|5|10  
Betacab|CC|2|20  
Betacab|DD|25|25  
Canutility|AA|8|15  
Canutility|CC|0|19  
] (delimiter is '|');
```

##### Chart expression

Create a KPI visualization in a Qlik Sense sheet. Add the following expression to the KPI, as a measure:

```
Avg(Aggr(Sum(UnitsSales*UnitPrice), Customer))
```

##### Result

376.7

##### Explanation

The expression `Aggr(Sum(UnitsSales*UnitPrice), customer)` finds the total value of sales by **Customer**, and returns an array of values: 295, 715, and 120 for the three **Customer** values.

Effectively, we have built a temporary list of values without having to create an explicit table or column containing those values.

These values are used as input to the **Avg()** function to find the average value of sales, 376.7.

#### Chart expression example 2

##### Load script

Load the following data as an inline load in the data load editor to create the chart expression example below.

ProductData:

```
LOAD * inline [  

```



```
Customer|Product|UnitSales|UnitPrice
Astrida|AA|4|16
Astrida|AA|10|15
Astrida|BB|10|15
Astrida|BB|9|9
Betacab|BB|5|10
Betacab|BB|7|12
Betacab|CC|2|22
Betacab|CC|4|20
Betacab|DD|25|25
Canutility|AA|8|15
Canutility|AA|5|11
Canutility|CC|0|19
] (delimiter is '|');
```

### Chart expression

Create a table visualization in a Qlik Sense sheet with **Customer**, **Product**, **UnitPrice**, and **UnitSales** as dimensions. Add the following expression to the table, as a measure:

```
Aggr(NODISTINCT Max(UnitPrice), Customer, Product)
```

### Result

Customer	Product	UnitPrice	UnitSales	Aggr(NODISTINCT Max(UnitPrice), Customer, Product)
Astrida	AA	15	10	16
Astrida	AA	16	4	16
Astrida	BB	9	9	15
Astrida	BB	15	10	15
Betacab	BB	10	5	12
Betacab	BB	12	7	12
Betacab	CC	20	4	22
Betacab	CC	22	2	22
Betacab	DD	25	25	25
Canutility	AA	11	5	15
Canutility	AA	15	8	15
Canutility	CC	19	0	19

### Explanation

An array of values: 16, 16, 15, 15, 12, 12, 22, 22, 25, 15, 15, and 19. The **nodistinct** qualifier means that the array contains one element for each row in the source data: each is the maximum **UnitPrice** for each **Customer** and **Product**.

### Chart expression example 3

#### Load script

Load the following data as an inline load in the data load editor to create the chart expression example below.

```
Set vNumberOfOrders = 1000;
```

```
OrderLines:
```

```
Load
```

```
    RowNo() as OrderLineID,  
    OrderID,  
    OrderDate,  
    Round((Year(OrderDate)-2005)*1000*Rand()*Rand()*Rand1) as Sales  
    While Rand()<=0.5 or IterNo()=1;
```

```
Load * Where OrderDate<=Today();
```

```
Load
```

```
    Rand() as Rand1,  
    Date(MakeDate(2013)+Floor((365*4+1)*Rand())) as OrderDate,  
    RecNo() as OrderID  
    Autogenerate vNumberOfOrders;
```

```
Calendar:
```

```
Load distinct
```

```
    Year(OrderDate) as Year,  
    Month(OrderDate) as Month,  
    OrderDate  
    Resident OrderLines;
```

#### Chart expressions

Create a table visualization in a Qlik Sense sheet with **Year** and **Month** as dimensions. Add the following expressions to the table as measures:

- Sum(Sales)
- Sum(Aggr( Rangesum(Above(Sum(Sales),0,12)), (Year, (Numeric, Ascending)), (Month, (Numeric, Ascending)) )) labeled as Structured Aggr() in the table.

#### Result

Year	Month	Sum(Sales)	Structured Aggr()
2013	Jan	53495	53495
2013	Feb	48580	102075

Year	Month	Sum(Sales)	Structured Aggr()
2013	Mar	25651	127726
2013	Apr	36585	164311
2013	May	61211	225522
2013	Jun	23689	249211
2013	Jul	42311	291522
2013	Aug	41913	333435
2013	Sep	28886	362361
2013	Oct	25977	388298
2013	Nov	44455	432753
2013	Dec	64144	496897
2014	Jan	67775	67775

### Explanation

This example displays the aggregated values over a twelve month period for each year in chronological ascending order, hence the structured parameters (Numeric, Ascending) part of the **Aggr()** expression. Two specific dimensions are required as structured parameters: **Year** and **Month**, sorted (1) **Year** (numeric) and (2) **Month** (numeric). These two dimensions must be used in the table or chart visualization. This is necessary for the dimension list of the **Aggr()** function to correspond with the dimensions of the object used in the visualization.

You can compare the difference between these measures in a table or in separate line charts:

- `Sum(Aggr( Rangesum(Above(Sum(Sales),0,12)), (Year), (Month) ))`
- `Sum(Aggr( Rangesum(Above(Sum(Sales),0,12)), (Year, (Numeric, Ascending)), (Month, (Numeric, Ascending)) ))`

It should be clear to see that only the latter expression performs the desired accumulation of aggregated values.

### See also:

 [Basic aggregation functions \(page 331\)](#)

## 8.4 Color functions

These functions can be used in expressions associated with setting and evaluating the color properties of chart objects, as well as in data load scripts.



*Qlik Sense supports the color functions **Color()**, **qliktechblue**, and **qliktechgray** for backwards compatibility reasons, but use of them is not recommended.*

### ARGB

**ARGB()** is used in expressions to set or evaluate the color properties of a chart object, where the color is defined by a red component **r**, a green component **g**, and a blue component **b**, with an alpha factor (opacity) of **alpha**.

```
ARGB (alpha, r, g, b)
```

### HSL

**HSL()** is used in expressions to set or evaluate the color properties of a chart object, where the color is defined by values of **hue**, **saturation**, and **luminosity** between 0 and 1.

```
HSL (hue, saturation, luminosity)
```

### RGB

**RGB()** returns an integer corresponding to the color code of the color defined by the three parameters: the red component **r**, the green component **g**, and the blue component **b**. These components must have integer values between 0 and 255. The function can be used in expressions to set or evaluate the color properties of a chart object.

```
RGB (r, g, b)
```

### Colormix1

**Colormix1()** is used in expressions to return an ARGB color representation from a two color gradient, based on a value between 0 and 1.

```
Colormix1 (Value , ColorZero , ColorOne)
```

Value is a real number between 0 and 1.

- If Value = 0 ColorZero is returned.
- If Value = 1 ColorOne is returned.
- If 0 < Value < 1 the appropriate intermediate shading is returned.

ColorZero is a valid RGB color representation for the color to be associated with the low end of the interval.

ColorOne is a valid RGB color representation for the color to be associated with the high end of the interval.

### Example:

```
colormix1(0.5, red(), blue())
```

returns:

```
ARGB(255,64,0,64) (purple)
```



### Colormix2

**Colormix2()** is used in expressions to return an ARGB color representation from a two color gradient, based on a value between -1 and 1, with the possibility to specify an intermediate color for the center (0) position.

**Colormix2** (Value ,ColorMinusOne , ColorOne[ , ColorZero])

Value is a real number between -1 and 1.

- If Value = -1 the first color is returned.
- If Value = 1 the second color is returned.
- If  $-1 < \text{Value} < 1$  the appropriate color mix is returned.

ColorMinusOne is a valid RGB color representation for the color to be associated with the low end of the interval.

ColorOne is a valid RGB color representation for the color to be associated with the high end of the interval.

ColorZero is an optional valid RGB color representation for the color to be associated with the center of the interval.

### SysColor

**SysColor()** returns the ARGB color representation for the Windows system color nr, where nr corresponds to the parameter to the Windows API function **GetSysColor(nr)**.

**SysColor** (nr)

### ColorMapHue

**ColorMapHue()** returns an ARGB value of a color from a colormap that varies the hue component of the HSV color model. The colormap starts with red, passes through yellow, green, cyan, blue, magenta, and returns to red. x must be specified as a value between 0 and 1.

**ColorMapHue** (x)

### ColorMapJet

**ColorMapJet()** returns an ARGB value of a color from a colormap that starts with blue, passes through cyan, yellow and orange, and returns to red. x must be specified as a value between 0 and 1.

**ColorMapJet** (x)

## Pre-defined color functions

The following functions can be used in expressions for pre-defined colors. Each function returns an RGB color representation.

Optionally a parameter for alpha factor can be given, in which case an ARGB color representation is returned. An alpha factor of 0 corresponds to full transparency, and an alpha factor of 255 corresponds to full opacity. If a value for alpha is not entered, it is assumed to be 255.

Pre-defined color functions

Color function	RGB value
black ([alpha])	(0,0,0)
blue([alpha])	(0,0,128)
brown([alpha])	(128,128,0)
cyan([alpha])	(0,128,128)
darkgray([alpha])	(128,128,128)
green([alpha])	(0,128,0)
lightblue([alpha])	(0,0,255)
lightcyan([alpha])	(0,255,255)
lightgray([alpha])	(192,192,192)
lightgreen([alpha])	(0,255,0)
lightmagenta([alpha])	(255,0,255)
lightred([alpha])	(255,0,0)
magenta([alpha])	(128,0,128)
red([alpha])	(128,0,0)
white([alpha])	(255,255,255)
yellow([alpha])	(255,255,0)

**Examples and results:**

Examples and results

Examples	Results
Blue()	RGB(0,0,128)
Blue(128)	ARGB(128,0,0,128)

**ARGB**

**ARGB()** is used in expressions to set or evaluate the color properties of a chart object, where the color is defined by a red component **r**, a green component **g**, and a blue component **b**, with an alpha factor (opacity) of **alpha**.

**Syntax:**

```
ARGB(alpha, r, g, b)
```

**Return data type:** dual

**Arguments:**

Arguments

Argument	Description
alpha	Transparency value in the range 0 - 255. 0 corresponds to full transparency and 255 corresponds to full opacity.
r, g, b	Red, green, and blue component values. A color component of 0 corresponds to no contribution and one of 255 to full contribution.



*All arguments must be expressions that resolve to integers in the range 0 to 255.*

If interpreting the numeric component and formatting it in hexadecimal notation, the values of the color components are easier to see. For example, light green has the number 4 278 255 360, which in hexadecimal notation is FF00FF00. The first two positions 'FF' (255) denote the **alpha** channel. The next two positions '00' denote the amount of **red**, the next two positions 'FF' denote the amount of **green**, and the final two positions '00' denote the amount of **blue**.

**RGB**

**RGB()** returns an integer corresponding to the color code of the color defined by the three parameters: the red component **r**, the green component **g**, and the blue component **b**. These components must have integer values between 0 and 255. The function can be used in expressions to set or evaluate the color properties of a chart object.

**Syntax:**

```
RGB(r, g, b)
```

**Return data type:** dual

**Arguments:**

### Arguments

Argument	Description
r, g, b	Red, green, and blue component values. A color component of 0 corresponds to no contribution and one of 255 to full contribution.



*All arguments must be expressions that resolve to integers in the range 0 to 255.*

If interpreting the numeric component and formatting it in hexadecimal notation, the values of the color components are easier to see. For example, light green has the number 4 278 255 360, which in hexadecimal notation is FF00FF00. The first two positions 'FF' (255) denote the **alpha** channel. In the functions **RGB** and **HSL**, this is always 'FF' (opaque). The next two positions '00' denote the amount of **red**, the next two positions 'FF' denote the amount of **green**, and the final two positions '00' denote the amount of **blue**.

Example: Chart expression

This example applies a custom color to a chart.

Data used in this example:


```
ProductSales:
Load * Inline
[Country,Sales,Budget
Sweden,100000,50000
Germany, 125000, 175000
Norway, 74850, 68500
Ireland, 45000, 48000
Sweden,98000,50000
Germany, 115000, 175000
Norway, 71850, 68500
Ireland, 31000, 48000
] (delimiter is ',');
```

Enter the following expression in the **Colors and legend** propertiespanel:

```
If (Sum(Sales)>Sum(Budget),RGB(255,0,0),RGB(100,80,120))
```

Result:





Example: Load script

The following example displays the equivalent RGB values for values in hex format:

```
Load
Text(R & G & B) as Text,
RGB(R,G,B)      as Color;
Load
Num#(R,'(HEX)') as R,
Num#(G,'(HEX)') as G,
Num#(B,'(HEX)') as B
Inline
[R,G,B
01,02,03
AA,BB,CC];
Result:
```

Text	Color
010203	RGB(1,2,3)
AABBCC	RGB(170,187,204)

## HSL

**HSL()** is used in expressions to set or evaluate the color properties of a chart object, where the color is defined by values of **hue**, **saturation**, and **luminosity** between 0 and 1.

### Syntax:

```
HSL (hue, saturation, luminosity)
```

**Return data type:** dual

**Arguments:**

Arguments

Argument	Description
hue, saturation, luminosity	hue, saturation, and luminosity component values ranging between 0 and 1.



*All arguments must be expressions that resolve to integers in the range 0 to 1.*

If interpreting the numeric component and formatting it in hexadecimal notation, the RGB values of the color components are easier to see. For example, light green has the number 4 278 255 360, which in hexadecimal notation is FF00FF00 and RGB (0,255,0). This is equivalent to HSL (80/240, 240/240, 120/240) - a HSL value of (0.33, 1, 0.5).

## 8.5 Conditional functions

The conditional functions all evaluate a condition and then return different answers depending on the condition value. The functions can be used in the data load script and in chart expressions.

### Conditional functions overview

Each function is described further after the overview. You can also click the function name in the syntax to immediately access the details for that specific function.

#### **alt**

The **alt** function returns the first of the parameters that has a valid number representation. If no such match is found, the last parameter will be returned. Any number of parameters can be used.

```
alt (expr1 [ , expr2 , expr3 , ... ] , else)
```

#### **class**

The **class** function assigns the first parameter to a class interval. The result is a dual value with  $a \leq x < b$  as the textual value, where  $a$  and  $b$  are the upper and lower limits of the bin, and the lower bound as numeric value.

```
class (expression, interval [ , label [ , offset ]])
```

#### **coalesce**

The **coalesce** function returns the first of the parameters that has a valid non-NULL representation. Any number of parameters can be used.

```
coalesce(expr1 [ , expr2 , expr3 , ...])
```

### if

The **if** function returns a value depending on whether the condition provided with the function evaluates as True or False.

```
if (condition , then , else)
```

### match

The **match** function compares the first parameter with all the following ones and returns the numeric location of the expressions that match. The comparison is case sensitive.

```
match ( str, expr1 [ , expr2,...exprN ])
```

### mixmatch

The **mixmatch** function compares the first parameter with all the following ones and returns the numeric location of the expressions that match. The comparison is case insensitive and insensitive to the Japanese Hiragana and Katakana character systems.

```
mixmatch ( str, expr1 [ , expr2,...exprN ])
```

### pick

The pick function returns the *n*:th expression in the list.

```
pick (n, expr1[ , expr2,...exprN])
```

### wildmatch

The **wildmatch** function compares the first parameter with all the following ones and returns the number of the expression that matches. It permits the use of wildcard characters ( \* and ? ) in the comparison strings. \* matches any sequence of characters. ? matches any single character. The comparison is case insensitive and insensitive to the Japanese Hiragana and Katakana character systems.

```
wildmatch ( str, expr1 [ , expr2,...exprN ])
```

### alt

The **alt** function returns the first of the parameters that has a valid number representation. If no such match is found, the last parameter will be returned. Any number of parameters can be used.

#### Syntax:

```
alt(expr1[ , expr2 , expr3 , ...] , else)
```

#### Arguments:

##### Arguments

Argument	Description
expr1	The first expression to check for a valid number representation.
expr2	The second expression to check for a valid number representation.

Argument	Description
expr3	The third expression to check for a valid number representation.
else	Value to return if none of the previous parameters has a valid number representation.

The alt function is often used with number or date interpretation functions. This way, Qlik Sense can test different date formats in a prioritized order. It can also be used to handle NULL values in numerical expressions.

### Examples:

#### Examples

Example	Result
<pre>alt( date#( dat , 'YYYY/MM/DD' ),     date#( dat , 'MM/DD/YYYY' ),     date#( dat , 'MM/DD/YY' ),     'No valid date' )</pre>	This expression will test if the field date contains a date according to any of the three specified date formats. If so, it will return a dual value containing the original string and a valid number representation of a date. If no match is found, the text 'No valid date' will be returned (without any valid number representation).
<pre>alt(Sales,0) + alt(Margin,0)</pre>	This expression adds the fields Sales and Margin, replacing any missing value (NULL) with a 0.

## class

The **class** function assigns the first parameter to a class interval. The result is a dual value with  $a \leq x < b$  as the textual value, where a and b are the upper and lower limits of the bin, and the lower bound as numeric value.

### Syntax:

```
class(expression, interval [ , label [ , offset ]])
```

### Arguments:

#### Arguments

Argument	Description
interval	A number that specifies the bin width.
label	An arbitrary string that can replace the 'x' in the result text.
offset	A number that can be used as offset from the default starting point of the classification. The default starting point is normally 0.

### Examples:

#### Examples

Example	Result
<code>class( var,10 ) with var = 23</code>	returns '20<=x<30'
<code>class( var,5, 'value' ) with var = 23</code>	returns '20<= value <25'
<code>class( var,10, 'x',5 ) with var = 23</code>	returns '15<=x<25'

### Example - Load script using class

Example: load script

#### Load script

In this example, we load a table containing name and age of people. We want to add a field that classifies each person according to an age group with a ten year interval. The original source table looks like the following.

#### Results

Name	Age
John	25
Karen	42
Yoshi	53

To add the age group classification field, you can add a preceding load statement using the **class** function.

Create a new tab in the data load editor, and then load the following data as an inline load. Create the table below in Qlik Sense to see the results.

```
LOAD *,
class(Age, 10, 'age') AS Agegroup;
```

```
LOAD * INLINE
[ Age, Name
25, John
42, Karen
53, Yoshi];
```

**Results**

Results

Name	Age	Agegroup
John	25	20 <= age < 30
Karen	42	40 <= age < 50
Yoshi	53	50 <= age < 60

**coalesce**

The **coalesce** function returns the first of the parameters that has a valid non-NULL representation. Any number of parameters can be used.

**Syntax:**

```
coalesce(expr1[ , expr2 , expr3 , ...])
```

**Arguments:**

Arguments

Argument	Description
expr1	The first expression to check for a valid non-NULL representation.
expr2	The second expression to check for a valid non-NULL representation.
expr3	The third expression to check for a valid non-NULL representation.

**Examples:**


Examples

Example	Result
	This expression changes all the NULL values of a field to 'N/A'.
<code>coalesce(ProductDescription, ProductName, ProductCode, 'no description available')</code>	This expression will select between three different product description fields, for when some fields may not have values for the product. The first of the fields, in the order given, with a non-null value will be returned. If none of the fields contain a value, the result will be 'no description available'.

Example	Result
<code>Coalesce(TextBetween(FileName, '''', '''), FileName)</code>	This expression will trim potential enclosing quotes from the field <i>FileName</i> . If the <i>FileName</i> given is quoted, these are removed, and the enclosed, unquoted <i>FileName</i> is returned. If the <i>TextBetween</i> function doesn't find the delimiters it returns null, which the <b>Coalesce</b> rejects, returning instead the raw <i>FileName</i> .

## if

The **if** function returns a value depending on whether the condition provided with the function evaluates as True or False.



### Syntax:

```
if(condition , then [, else])
```

#### Arguments

Argument	Description
condition	Expression that is interpreted logically.
then	Expression that can be of any type. If the <i>condition</i> is True, then the if function returns the value of the <i>then</i> expression.
else	Expression that can be of any type. If the <i>condition</i> is False, then the if function returns the value of the <i>else</i> expression.  This parameter is optional. If the <i>condition</i> is False, NULL is returned if you have not specified else.

### Example

Example	Result
<code>if( Amount &gt;= 0, 'OK', 'Alarm' )</code>	This expression tests if the amount is a positive number (0 or larger) and return 'OK' if it is. If the amount is less than 0, 'Alarm' is returned.

### Example - Load script using if

Example: Load script

#### Load script

If can be used in load script with other methods and objects, including variables. For example, if you set a variable *threshold* and want to include a field in the data model based on that threshold, you can do the following.

Create a new tab in the data load editor, and then load the following data as an inline load. Create the table below in Qlik Sense to see the results.

Transactions:

```
Load * Inline [
transaction_id, transaction_date, transaction_amount, transaction_quantity, customer_id, size,
color_code
3750, 20180830, 23.56, 2, 2038593, L, Red
3751, 20180907, 556.31, 6, 203521, m, orange
3752, 20180916, 5.75, 1, 5646471, s, blue
3753, 20180922, 125.00, 7, 3036491, l, black
3754, 20180922, 484.21, 13, 049681, xs, Red
3756, 20180922, 59.18, 2, 2038593, M, Blue
3757, 20180923, 177.42, 21, 203521, XL, black
];
```

```
set threshold = 100;
```

```
/* Create new table called Transaction_Buckets
Compare transaction_amount field from Transaction table to threshold of 100.
Output results into a new field called Compared to Threshold
*/
```

Transaction\_Buckets:

```
Load
    transaction_id,
    If(transaction_amount > $(threshold), 'Greater than $(threshold)', 'Less than $(threshold)')
as [Compared to Threshold]
Resident Transactions;
```



### Results

Qlik Sense table showing the output from using the *if* function in the load script.

transaction_id	Compared to Threshold
3750	Less than 100
3751	Greater than 100
3752	Less than 100
3753	Greater than 100
3754	Greater than 100
3756	Less than 100
3757	Greater than 100

### Examples - Chart expressions using if

Examples: Chart expressions

#### Chart expression 1

#### Load script

Create a new tab in the data load editor, and then load the following data as an inline load. After loading the data, create the chart expression examples below in a Qlik Sense table.

MyTable:

```
LOAD * inline [Date, Location, Incidents
1/3/2016, Beijing, 0
1/3/2016, Boston, 12
1/3/2016, Stockholm, 3
1/3/2016, Toronto, 0
1/4/2016, Beijing, 0
1/4/2016, Boston, 8];
```

Qlik Sense table showing examples of the *if* function in a chart expression.

Date	Location	Incidents	if(Incidents>=10, 'Critical', 'Ok' )	if(Incidents>=10, 'Critical', If( Incidents>=1 and Incidents<10, 'Warning', 'Ok'))
1/3/2016	Beijing	0	Ok	Ok
1/3/2016	Boston	12	Critical	Critical
1/3/2016	Stockholm	3	Ok	Warning
1/3/2016	Toronto	0	Ok	Ok

Date	Location	Incidents	if(Incidents>=10, 'Critical', 'Ok' )	if(Incidents>=10, 'Critical', If( Incidents>=1 and Incidents<10, 'Warning', 'Ok'))
1/4/2016	Beijing	0	Ok	Ok
1/4/2016	Boston	8	Ok	Warning

### Chart expression 2

In a new app, add the following script in a new tab in the data load editor, and then load the data. You can then create the table with the chart expressions below.

```
SET FirstWeekDay=0;
Load
Date(MakeDate(2022)+RecNo()-1) as Date
Autogenerate 14;
```

Qlik Sense table showing an example of the *if* function in a chart expression.

Date	WeekDay(Date)	If(WeekDay (Date)>=5,'WeekEnd','Normal Day')
1/1/2022	Sat	WeekEnd
1/2/2022	Sun	WeekEnd
1/3/2022	Mon	Normal Day
1/4/2022	Tue	Normal Day
1/5/2022	Wed	Normal Day
1/6/2022	Thu	Normal Day
1/7/2022	Fri	Normal Day
1/8/2022	Sat	WeekEnd
1/9/2022	Sun	WeekEnd
1/10/2022	Mon	Normal Day
1/11/2022	Tue	Normal Day
1/12/2022	Wed	Normal Day
1/13/2022	Thu	Normal Day
1/14/2022	Fri	Normal Day

### match

The **match** function compares the first parameter with all the following ones and returns the numeric location of the expressions that match. The comparison is case sensitive.

### Syntax:

```
match( str, expr1 [ , expr2, ...exprN ])
```



If you want to use case insensitive comparison, use the **mixmatch** function. If you want to use case insensitive comparison and wildcards, use the **wildmatch** function.

### Example: Load script using match

Example: Load script

#### Load script

You can use match to load a subset of data. For example, you can return a numeric value for an expression in the function. You can then limit the data loaded based on the numeric value. Match returns 0 if there is no match. All expressions that are not matched in this example will therefore return 0 and will be excluded from the data load by the WHERE statement.

Create a new tab in the data load editor, and then load the following data as an inline load. Create the table below in Qlik Sense to see the results.

Transactions:

```
Load * Inline [
transaction_id, transaction_date, transaction_amount, transaction_quantity, customer_id, size,
color_code
3750, 20180830, 23.56, 2, 2038593, L, Red
3751, 20180907, 556.31, 6, 203521, m, orange
3752, 20180916, 5.75, 1, 5646471, s, blue
3753, 20180922, 125.00, 7, 3036491, l, Black
3754, 20180922, 484.21, 13, 049681, xs, Red
3756, 20180922, 59.18, 2, 2038593, M, Blue
3757, 20180923, 177.42, 21, 203521, XL, Black
];
```

```
/*
```

```
Create new table called Transaction_Buckets
Create new fields called Customer, and Color code - Blue and Black
Load Transactions table.
```

```
Match returns 1 for 'Blue', 2 for 'Black'.
Does not return a value for 'blue' because match is case sensitive.
Only values that returned numeric value greater than 0
are loaded by WHERE statement into Transactions_Buckets table.
*/
```

Transaction\_Buckets:

```
Load
customer_id,
customer_id as [Customer],
color_code as [Color Code Blue and Black]
Resident Transactions
where match(color_code, 'Blue', 'Black') > 0;
```

### Results

Qlik Sense table showing the output from using the match function in the load script

Color Code Blue and Black	Customer
Black	203521
Black	3036491
Blue	2038593

### Examples - Chart expressions using match

Examples: Chart expressions

#### Chart expression 1

#### Load script

Create a new tab in the data load editor, and then load the following data as an inline load. After loading the data, create the chart expression examples below in a Qlik Sense table.

MyTable:

```
Load * inline [Cities, Count
Toronto, 123
Toronto, 234
Toronto, 231
Boston, 32
Boston, 23
Boston, 1341
Beijing, 234
Beijing, 45
Beijing, 235
Stockholm, 938
Stockholm, 39
Stockholm, 189
zurich, 2342
zurich, 9033
zurich, 0039];
```

The first expression in the table below returns 0 for Stockholm because 'Stockholm' is not included in the list of expressions in the **match** function. It also returns 0 for 'Zurich' because the **match** comparison is case-sensitive.

Qlik Sense table showing examples of the *match* function in a chart expression

Cities	<code>match(Cities,'Toronto','Boston','Beijing','Zurich')</code>	<code>match(Cities,'Toronto','Boston','Beijing','Stockholm','zurich')</code>
Beijing	3	3
Boston	2	2
Stockholm	0	4
Toronto	1	1
zurich	0	5

### Chart expression 2

You can use `match` to perform a custom sort for an expression.

By default, columns sort numerically or alphabetically, depending on the data.

Qlik Sense table showing an example of the default sort order

Cities
Beijing
Boston
Stockholm
Toronto
zurich

To change the order, do the following:

1. Open the **Sorting** section for your chart in the **Properties** panel.
2. Turn off auto sorting for the column on which you want to do a custom sort.
3. Deselect **Sort numerically** and **Sort alphabetically**.
4. Select **Sort by expression**, and then enter an expression similar to the following:  
`=match( Cities, 'Toronto','Boston','Beijing','Stockholm','zurich')`  
 The sort order on the Cities column changes.

Qlik Sense table showing an example of changing the sort order using the *match* function

Cities
Toronto
Boston
Beijing

Cities
Stockholm
zurich

You can also view the numeric value that is returned.

Qlik Sense table showing an example of the numeric values that are returned from the *match* function

Cities	Cities & ' - ' & match ( Cities, 'Toronto','Boston', 'Beijing','Stockholm','zurich')
Toronto	Toronto - 1
Boston	Boston - 2
Beijing	Beijing - 3
Stockholm	Stockholm - 4
zurich	zurich - 5

### mixmatch

The **mixmatch** function compares the first parameter with all the following ones and returns the numeric location of the expressions that match. The comparison is case insensitive and insensitive to the Japanese Hiragana and Katakana character systems.

#### Syntax:

```
mixmatch( str, expr1 [ , expr2,...exprN ])
```

If you instead want to use case sensitive comparison, use the **match** function. If you want to use case insensitive comparison and wildcards, use the **wildmatch** function.

### Example - Load script using mixmatch

Example: Load script

#### Load script

You can use mixmatch to load a subset of data. For example, you can return a numeric value for an expression in the function. You can then limit the data loaded based on the numeric value.

Mixmatch returns 0 if there is no match. All expressions that are not matched in this example will therefore return 0 and will be excluded from the data load by the WHERE statement.

Create a new tab in the data load editor, and then load the following data as an inline load. Create the table below in Qlik Sense to see the results.

```
Load * Inline [
transaction_id, transaction_date, transaction_amount, transaction_quantity, customer_id, size,
color_code
3750, 20180830, 23.56, 2, 2038593, L, Red
```

```
3751, 20180907, 556.31, 6, 203521, m, orange
3752, 20180916, 5.75, 1, 5646471, s, blue
3753, 20180922, 125.00, 7, 3036491, l, Black
3754, 20180922, 484.21, 13, 049681, xs, Red
3756, 20180922, 59.18, 2, 2038593, M, Blue
3757, 20180923, 177.42, 21, 203521, XL, Black
];

/*
Create new table called Transaction_Buckets
Create new fields called Customer, and Color code - Black, Blue, blue
Load Transactions table.
Mixmatch returns 1 for 'Black', 2 for 'Blue'.
Also returns 3 for 'blue' because mixmatch is not case sensitive.
Only values that returned numeric value greater than 0
are loaded by WHERE statement into Transactions_Buckets table.
*/

Transaction_Buckets:
Load
    customer_id,
    customer_id as [Customer],
    color_code as [Color Code - Black, Blue, blue]
Resident Transactions
where mixmatch(color_code, 'Black', 'Blue') > 0;
```

### Results

Qlik Sense table showing the output from using the mixmatch function in the load script.

Color Code Black, Blue, blue	Customer
Black	203521
Black	3036491
Blue	2038593
blue	5646471

### Examples - Chart expressions using mixmatch

Examples: Chart expressions

Create a new tab in the data load editor, and then load the following data as an inline load. After loading the data, create the chart expression examples below in a Qlik Sense table.

#### Chart expression 1

```
MyTable:
Load * inline [Cities, Count
Toronto, 123
Toronto, 234
Toronto, 231
```

```

Boston, 32
Boston, 23
Boston, 1341
Beijing, 234
Beijing, 45
Beijing, 235
Stockholm, 938
Stockholm, 39
Stockholm, 189
zurich, 2342
zurich, 9033
zurich, 0039];

```

The first expression in the table below returns 0 for Stockholm because 'Stockholm' is not included in the list of expressions in the **mixmatch** function. It returns 4 for 'Zurich' because the **mixmatch** comparison is not case-sensitive.

Qlik Sense table showing examples of the *mixmatch* function in a chart expression

Cities	mixmatch(Cities,'Toronto','Boston','Beijing','Zurich')	mixmatch(Cities,'Toronto','Boston','Beijing','Stockholm','Zurich')
Beijing	3	3
Boston	2	2
Stockholm	0	4
Toronto	1	1
zurich	4	5

### Chart expression 2

You can use *mixmatch* to perform a custom sort for an expression.

By default, columns sort alphabetically or numerically, depending on the data.

Qlik Sense table showing an example of the default sort order

Cities
Beijing
Boston
Stockholm
Toronto
zurich

To change the order, do the following:



1. Open the **Sorting** section for your chart in the **Properties** panel.
2. Turn off auto sorting for the column on which you want to do a custom sort.
3. Deselect **Sort numerically** and **Sort alphabetically**.
4. Select **Sort by expression**, and then enter the following expression:  
`=mixmatch( Cities, 'Toronto','Boston','Beijing','Stockholm','Zurich')`  
 The sort order on the Cities column changes.

Qlik Sense table showing an example of changing the sort order using the *mixmatch* function.

Cities
Toronto
Boston
Beijing
Stockholm
zurich

You can also view the numeric value that is returned.

Qlik Sense table showing an example of the numeric values that are returned from the *mixmatch* function.

Cities	Cities & ' - ' & mixmatch ( Cities, 'Toronto','Boston','Beijing','Stockholm','Zurich')
Toronto	Toronto - 1
Boston	Boston - 2
Beijing	Beijing - 3
Stockholm	Stockholm - 4
zurich	zurich - 5

### pick

The pick function returns the *n*:th expression in the list.

#### Syntax:

```
pick(n, expr1[ , expr2, ...exprN])
```

#### Arguments:

##### Arguments

Argument	Description
n	<i>n</i> is an integer between 1 and N.

**Example:**

Example

Example	Result
<code>pick( N, 'A','B',4, 6 )</code>	returns 'B' if N = 2 returns 4 if N = 3

**wildmatch**

The **wildmatch** function compares the first parameter with all the following ones and returns the number of the expression that matches. It permits the use of wildcard characters ( \* and ?) in the comparison strings. \* matches any sequence of characters. ? matches any single character. The comparison is case insensitive and insensitive to the Japanese Hiragana and Katakana character systems.

**Syntax:**

```
wildmatch( str, expr1 [ , expr2,...exprN ] )
```

If you want to use comparison without wildcards, use the **match** or **mixmatch** functions.

**Example: Load script using wildmatch**

Example: Load script

**Load script**

You can use wildmatch to load a subset of data. For example, you can return a numeric value for an expression in the function. You can then limit the data loaded based on the numeric value.

Wildmatch returns 0 if there is no match. All expressions that are not matched in this example will therefore return 0 and will be excluded from the data load by the WHERE statement.

Create a new tab in the data load editor, and then load the following data as an inline load. Create the table below in Qlik Sense to see the results.

Transactions:

```
Load * Inline [
transaction_id, transaction_date, transaction_amount, transaction_quantity, customer_id, size,
color_code
3750, 20180830, 23.56, 2, 2038593, L, Red
3751, 20180907, 556.31, 6, 203521, m, orange
3752, 20180916, 5.75, 1, 5646471, S, blue
3753, 20180922, 125.00, 7, 3036491, l, black
3754, 20180922, 484.21, 13, 049681, xs, Red
3756, 20180922, 59.18, 2, 2038593, M, blue
3757, 20180923, 177.42, 21, 203521, xL, black
];
```

```
/*
```

```
Create new table called Transaction_Buckets
```

Create new fields called Customer, and Color code - Black, Blue, blue, red  
Load Transactions table.  
wildmatch returns 1 for 'Black', 'Blue', and 'blue', and 2 for 'Red'.  
Only values that returned numeric value greater than 0  
are loaded by WHERE statement into Transactions\_Buckets table.  
\*/

```
Transaction_Buckets:
Load
    customer_id,
    customer_id as [Customer],
    color_code as [Color Code Black, Blue, blue, Red]
Resident Transactions
where wildmatch(color_code,'B1*','R??') > 0;
```

### Results

Qlik Sense table showing the output from using the  
*wildmatch* function in the load script

Color Code Black, Blue, blue, Red	Customer
Black	203521
Black	3036491
Blue	2038593
blue	5646471
Red	049681
Red	2038593

### Examples: Chart expressions using wildmatch

Example: Chart expression

#### Chart expression 1

Create a new tab in the data load editor, and then load the following data as an inline load. After loading the data, create the chart expression examples below in a Qlik Sense table.

```
MyTable:
Load * inline [Cities, Count
Toronto, 123
Toronto, 234
Toronto, 231
Boston, 32
Boston, 23
Boston, 1341
Beijing, 234
Beijing, 45
Beijing, 235
Stockholm, 938
```

```
Stockholm, 39
Stockholm, 189
zurich, 2342
zurich, 9033
zurich, 0039];
```

The first expression in the table below returns 0 for Stockholm because 'Stockholm' is not included in the list of expressions in the **wildmatch** function. It also returns 0 for 'Boston' because ? only matches on a single character.

Qlik Sense table showing examples of the *wildmatch* function in a chart expression

Cities	wildmatch(Cities,'Tor*','?ton','Beijing','*urich')	wildmatch(Cities,'Tor*','???ton','Beijing','Stockholm','*urich')
Beijing	3	3
Boston	0	2
Stockholm	0	4
Toronto	1	1
zurich	4	5

### Chart expression 2

You can use wildmatch to perform a custom sort for an expression.

By default, columns sort numerically or alphabetically, depending on the data.

Qlik Sense table showing an example of the default sort order

Cities
Beijing
Boston
Stockholm
Toronto
zurich

To change the order, do the following:

1. Open the **Sorting** section for your chart in the **Properties** panel.
2. Turn off auto sorting for the column on which you want to do a custom sort.
3. Deselect **Sort numerically** and **Sort alphabetically**.
4. Select **Sort by expression**, and then enter an expression similar to the following:  
`=wildmatch( Cities, 'Tor*','???ton','Beijing','Stockholm','*urich')`  
 The sort order on the Cities column changes.

Qlik Sense table showing an example of changing the sort order using the *wildmatch* function.

Cities
Toronto
Boston
Beijing
Stockholm
zurich

You can also view the numeric value that is returned.

Qlik Sense table showing an example of the numeric values that are returned from the *wildmatch* function

Cities	Cities & ' - ' & wildmatch ( Cities, 'Tor*', '???ton', 'Beijing', 'Stockholm', '*urich')
Toronto	Toronto - 1
Boston	Boston - 2
Beijing	Beijing - 3
Stockholm	Stockholm - 4
zurich	zurich - 5

### 8.6 Counter functions

This section describes functions related to record counters during **LOAD** statement evaluation in the data load script. The only function that can be used in chart expressions is **RowNo()**.

Some counter functions do not have any parameters, but the trailing parentheses are however still required.

#### Counter functions overview

Each function is described further after the overview. You can also click the function name in the syntax to immediately access the details for that specific function.

##### **autonumber**

This script function returns a unique integer value for each distinct evaluated value of *expression* encountered during the script execution. This function can be used e.g. for creating a compact memory representation of a complex key.

```
autonumber (expression[ , AutoID])
```

##### **autonumberhash128**

This script function calculates a 128-bit hash of the combined input expression values and the returns a unique integer value for each distinct hash value encountered during the script execution. This function can be used for example for creating a compact memory representation of a complex

key.

```
autonumberhash128 (expression {, expression})
```

### **autonumberhash256**

This script function calculates a 256-bit hash of the combined input expression values and returns a unique integer value for each distinct hash value encountered during the script execution. This function can be used e.g. for creating a compact memory representation of a complex key.

```
autonumberhash256 (expression {, expression})
```

### **IterNo**

This script function returns an integer indicating for which time one single record is evaluated in a **LOAD** statement with a **while** clause. The first iteration has number 1. The **IterNo** function is only meaningful if used together with a **while** clause.

```
IterNo ( )
```

### **RecNo**

This script functions returns an integer for the number of the currently read row of the current table. The first record is number 1.

```
RecNo ( )
```

### **RowNo - script function**

This function returns an integer for the position of the current row in the resulting Qlik Sense internal table. The first row is number 1.

```
RowNo ( )
```

### **RowNo - chart function**

**RowNo()** returns the number of the current row within the current column segment in a table. For bitmap charts, **RowNo()** returns the number of the current row within the chart's straight table equivalent.

```
RowNo - chart function([TOTAL])
```

## autonumber

This script function returns a unique integer value for each distinct evaluated value of *expression* encountered during the script execution. This function can be used e.g. for creating a compact memory representation of a complex key.



*You can only connect **autonumber** keys that have been generated in the same data load, as the integer is generated according to the order the table is read. If you need to use keys that are persistent between data loads, independent of source data sorting, you should use the **hash128**, **hash160** or **hash256** functions.*

### **Syntax:**

```
autonumber (expression[ , AutoID])
```

### Arguments:

Argument	Description
AutoID	In order to create multiple counter instances if the <b>autonumber</b> function is used on different keys within the script, the optional parameter <i>AutoID</i> can be used for naming each counter.

### Example: Creating a composite key

In this example we create a composite key using the **autonumber** function to conserve memory. The example is brief for demonstration purpose, but would be meaningful with a table containing a large number of rows.

Example data

Region	Year	Month	Sales
North	2014	May	245
North	2014	May	347
North	2014	June	127
South	2014	June	645
South	2013	May	367
South	2013	May	221

The source data is loaded using inline data. Then we add a preceding load, which creates a composite key from the Region, Year and Month fields.

```
RegionSales:
LOAD *,
AutoNumber(Region&Year&Month) as RYMkey;
```

```
LOAD * INLINE
[ Region, Year, Month, Sales
North, 2014, May, 245
North, 2014, May, 347
North, 2014, June, 127
South, 2014, June, 645
South, 2013, May, 367
South, 2013, May, 221
];
```

The resulting table looks like this:

Results table

Region	Year	Month	Sales	RYMkey
North	2014	May	245	1
North	2014	May	347	1
North	2014	June	127	2
South	2014	June	645	3
South	2013	May	367	4
South	2013	May	221	4

In this example you can refer to the RYMkey, for example 1, instead of the string 'North2014May' if you need to link to another table.

Now we load a source table of costs in a similar way. The Region, Year and Month fields are excluded in the preceding load to avoid creating a synthetic key, we are already creating a composite key with the **autonumber** function, linking the tables.

```
RegionCosts:
LOAD Costs,
AutoNumber(Region&Year&Month) as RYMkey;
```

```
LOAD * INLINE
[ Region, Year, Month, Costs
South, 2013, May, 167
North, 2014, May, 56
North, 2014, June, 199
south, 2014, June, 64
south, 2013, May, 172
south, 2013, May, 126
];
```

Now we can add a table visualization to a sheet, and add the Region, Year and Month fields, as well as Sum measures for the sales and the costs. The table will look like this:

Results table

Region	Year	Month	Sum([Sales])	Sum([Costs])
Totals	-	-	1952	784
North	2014	June	127	199
North	2014	May	592	56
South	2014	June	645	64
South	2013	May	588	465



## autonumberhash128

This script function calculates a 128-bit hash of the combined input expression values and returns a unique integer value for each distinct hash value encountered during the script execution. This function can be used for example for creating a compact memory representation of a complex key.



You can only connect **autonumberhash128** keys that have been generated in the same data load, as the integer is generated according to the order the table is read. If you need to use keys that are persistent between data loads, independent of source data sorting, you should use the **hash128**, **hash160** or **hash256** functions.

### Syntax:

```
autonumberhash128 (expression {, expression})
```

### Example: Creating a composite key

In this example we create a composite key using the **autonumberhash128** function to conserve memory. The example is brief for demonstration purpose, but would be meaningful with a table containing a large number of rows.

Example data

Region	Year	Month	Sales
North	2014	May	245
North	2014	May	347
North	2014	June	127
South	2014	June	645
South	2013	May	367
South	2013	May	221

The source data is loaded using inline data. Then we add a preceding load, which creates a composite key from the Region, Year and Month fields.

```
RegionSales:
LOAD *,
AutoNumberHash128(Region, Year, Month) as RYMkey;
```

```
LOAD * INLINE
[ Region, Year, Month, Sales
North, 2014, May, 245
North, 2014, May, 347
North, 2014, June, 127
South, 2014, June, 645
South, 2013, May, 367
```

## 8 Script and chart functions

```
South, 2013, May, 221  
];
```

The resulting table looks like this:

Results table

Region	Year	Month	Sales	RYMkey
North	2014	May	245	1
North	2014	May	347	1
North	2014	June	127	2
South	2014	June	645	3
South	2013	May	367	4
South	2013	May	221	4

In this example you can refer to the RYMkey, for example 1, instead of the string 'North2014May' if you need to link to another table.

Now we load a source table of costs in a similar way. The Region, Year and Month fields are excluded in the preceding load to avoid creating a synthetic key, we are already creating a composite key with the **autonumberhash128** function, linking the tables.

```
RegionCosts:  
LOAD Costs,  
AutoNumberHash128(Region, Year, Month) as RYMkey;
```

```
LOAD * INLINE  
[ Region, Year, Month, Costs  
South, 2013, May, 167  
North, 2014, May, 56  
North, 2014, June, 199  
South, 2014, June, 64  
South, 2013, May, 172  
South, 2013, May, 126  
];
```

Now we can add a table visualization to a sheet, and add the Region, Year and Month fields, as well as Sum measures for the sales and the costs. The table will look like this:

Results table

Region	Year	Month	Sum([Sales])	Sum([Costs])
Totals	-	-	1952	784
North	2014	June	127	199
North	2014	May	592	56

Region	Year	Month	Sum([Sales])	Sum([Costs])
South	2014	June	645	64
South	2013	May	588	465

## autonumberhash256

This script function calculates a 256-bit hash of the combined input expression values and returns a unique integer value for each distinct hash value encountered during the script execution. This function can be used e.g. for creating a compact memory representation of a complex key.



*You can only connect **autonumberhash256** keys that have been generated in the same data load, as the integer is generated according to the order the table is read. If you need to use keys that are persistent between data loads, independent of source data sorting, you should use the **hash128**, **hash160** or **hash256** functions.*

### Syntax:

```
autonumberhash256 (expression {, expression})
```

### Example: Creating a composite key

In this example we create a composite key using the **autonumberhash256** function to conserve memory. The example is brief for demonstration purpose, but would be meaningful with a table containing a large number of rows.

Example table

Region	Year	Month	Sales
North	2014	May	245
North	2014	May	347
North	2014	June	127
South	2014	June	645
South	2013	May	367
South	2013	May	221

The source data is loaded using inline data. Then we add a preceding load, which creates a composite key from the Region, Year and Month fields.

```
RegionSales:
LOAD *,
AutoNumberHash256(Region, Year, Month) as RYMkey;
```

```
LOAD * INLINE
```

```
[ Region, Year, Month, Sales
North, 2014, May, 245
North, 2014, May, 347
North, 2014, June, 127
South, 2014, June, 645
South, 2013, May, 367
South, 2013, May, 221
];
```

The resulting table looks like this:

Results table

Region	Year	Month	Sales	RYMkey
North	2014	May	245	1
North	2014	May	347	1
North	2014	June	127	2
South	2014	June	645	3
South	2013	May	367	4
South	2013	May	221	4

In this example you can refer to the RYMkey, for example 1, instead of the string 'North2014May' if you need to link to another table.

Now we load a source table of costs in a similar way. The Region, Year and Month fields are excluded in the preceding load to avoid creating a synthetic key, we are already creating a composite key with the **autonumberhash256** function, linking the tables.

```
RegionCosts:
LOAD Costs,
AutoNumberHash256(Region, Year, Month) as RYMkey;
```

```
LOAD * INLINE
[ Region, Year, Month, Costs
South, 2013, May, 167
North, 2014, May, 56
North, 2014, June, 199
South, 2014, June, 64
South, 2013, May, 172
South, 2013, May, 126
];
```

Now we can add a table visualization to a sheet, and add the Region, Year and Month fields, as well as Sum measures for the sales and the costs. The table will look like this:

Results table

Region	Year	Month	Sum([Sales])	Sum([Costs])
Totals	-	-	1952	784
North	2014	June	127	199
North	2014	May	592	56
South	2014	June	645	64
South	2013	May	588	465

## IterNo

This script function returns an integer indicating for which time one single record is evaluated in a **LOAD** statement with a **while** clause. The first iteration has number 1. The **IterNo** function is only meaningful if used together with a **while** clause.

### Syntax:

```
IterNo( )
```

Examples and results:

### Example:

```
LOAD
  IterNo() as Day,
  Date( StartDate + IterNo() - 1 ) as Date
  while StartDate + IterNo() - 1 <= EndDate;

LOAD * INLINE
[StartDate, EndDate
2014-01-22, 2014-01-26
];
```

This **LOAD** statement will generate one record per date within the range defined by **StartDate** and **EndDate**.

In this example, the resulting table will look like this:

Results table

Day	Date
1	2014-01-22
2	2014-01-23
3	2014-01-24

Day	Date
4	2014-01-25
5	2014-01-26

### RecNo

This script functions returns an integer for the number of the currently read row of the current table. The first record is number 1.

#### Syntax:

```
RecNo ( )
```

In contrast to **RowNo( )**, which counts rows in the resulting Qlik Sense table, **RecNo( )**, counts the records in the raw data table and is reset when a raw data table is concatenated to another.

#### Example: Data load script

Raw data table load:

```
Tab1:  
LOAD * INLINE  
[A, B  
1, aa  
2, cc  
3, ee];
```

```
Tab2:  
LOAD * INLINE  
[C, D  
5, xx  
4, yy  
6, zz];
```

Loading record and row numbers for selected rows:

```
QTab:  
LOAD *,  
RecNo( ),  
RowNo( )  
resident Tab1 where A<>2;
```

```
LOAD  
C as A,  
D as B,  
RecNo( ),  
RowNo( )  
resident Tab2 where A<>5;
```

```
//We don't need the source tables anymore, so we drop them  
Drop tables Tab1, Tab2;
```

The resulting Qlik Sense internal table:

Results table

A	B	RecNo( )	RowNo( )
1	aa	1	1
3	ee	3	2
4	yy	2	3
6	zz	3	4

## RowNo

This function returns an integer for the position of the current row in the resulting Qlik Sense internal table. The first row is number 1.

### Syntax:

```
RowNo( [TOTAL] )
```

In contrast to **RecNo( )**, which counts the records in the raw data table, the **RowNo( )** function does not count records that are excluded by **where** clauses and is not reset when a raw data table is concatenated to another.



*If you use preceding load, that is, a number of stacked **LOAD** statements reading from the same table, you can only use **RowNo( )** in the top **LOAD** statement. If you use **RowNo( )** in subsequent **LOAD** statements, 0 is returned.*

### Example: Data load script

Raw data table load:

```
Tab1:
LOAD * INLINE
[A, B
1, aa
2, cc
3, ee];
```

```
Tab2:
LOAD * INLINE
[C, D
5, xx
4, yy
6, zz];
```

Loading record and row numbers for selected rows:

```
QTab:
LOAD *,
RecNo( ),
RowNo( )
```

```
resident Tab1 where A<>2;
```

```
LOAD
```

```
C as A,
```

```
D as B,
```

```
RecNo( ),
```

```
RowNo( )
```

```
resident Tab2 where A<>5;
```

```
//We don't need the source tables anymore, so we drop them
```

```
Drop tables Tab1, Tab2;
```

The resulting Qlik Sense internal table:

Results table

A	B	RecNo( )	RowNo( )
1	aa	1	1
3	ee	3	2
4	yy	2	3
6	zz	3	4

### RowNo - chart function

**RowNo()** returns the number of the current row within the current column segment in a table. For bitmap charts, **RowNo()** returns the number of the current row within the chart's straight table equivalent.

If the table or table equivalent has multiple vertical dimensions, the current column segment will include only rows with the same values as the current row in all dimension columns, except for the column showing the last dimension in the inter-field sort order.

#### Column segments

	Region	Country	Population	Rank(Population)
Column segment #1	Americas	Mexico	128,932,753	2
	Americas	Canada	37,742,154	3
	Americas	United States of America	331,002,051	1
Column segment #2	Europe	Sweden	10,099,265	4
	Europe	United Kingdom	67,886,011	2
	Europe	France	65,273,511	3
	Europe	Germany	83,783,942	1



*Sorting on y-values in charts or sorting by expression columns in tables is not allowed when this chart function is used in any of the chart's expressions. These sort alternatives are therefore automatically disabled. When you use this chart function in a visualization or table, the sorting of the visualization will revert back to the sorted input to this function.*

#### Syntax:

```
RowNo ( [ TOTAL ] )
```



**Return data type:** integer

**Arguments:**

Argument	Description
TOTAL	If the table is one-dimensional or if the qualifier <b>TOTAL</b> is used as argument, the current column segment is always equal to the entire column.

### Example: Chart expression using RowNo

Example - chart expression

Load script

Load the following data as an inline load in the data load editor to create the chart expression examples below.

```
Temp:
LOAD * inline [
Customer|Product|OrderNumber|UnitSales|UnitPrice
Astrida|AA|1|4|16
Astrida|AA|7|10|15
Astrida|BB|4|9|9
Betacab|CC|6|5|10
Betacab|AA|5|2|20
Betacab|BB|1|25| 25
Canutility|AA|3|8|15
Canutility|CC|5|4|19
Divadip|CC|2|4|16
Divadip|DD|3|1|25
] (delimiter is '|');
```

### Chart expression

Create a table visualization in a Qlik Sense sheet with **Customer** and **UnitSales** as dimensions. Add **RowNo( )** and **RowNo(TOTAL)** as measures labeled **Row in Segment** and **Row Number**, respectively. Add the following expression to the table as a measure.

```
If( RowNo( )=1, 0, UnitSales / Above( UnitSales ))
```

Result

Customer	UnitSales	Row in Segment	Row Number	If( RowNo( )=1, 0, UnitSales / Above( UnitSales ))
Astrida	4	1	1	0
Astrida	9	2	2	2.25
Astrida	10	3	3	1.11111111111111

Customer	UnitSales	Row in Segment	Row Number	If ( RowNo( )=1, 0, UnitSales / Above( UnitSales ) )
Betacab	2	1	4	0
Betacab	5	2	5	2.5
Betacab	25	3	6	5
Canutility	4	1	7	0
Canutility	8	2	8	2
Divadip	1	1	9	0
Divadip	4	2	10	4

### Explanation

The **Row in Segment** column shows the results 1,2,3 for the column segment containing the values of UnitSales for customer Astrida. The row numbering then begins at 1 again for the next column segment, which is Betacab.

The **Row Number** column disregards the dimensions because of the TOTAL argument for RowNo() and counts the rows in the table.

This expression returns 0 for the first row in each column segment, so the column shows:

0, 2.25, 1.111111, 0, 2.5, 5, 0, 2, 0, and 4.

### See also:

 [Above - chart function \(page 1277\)](#)

## 8.7 Date and time functions

Qlik Sense date and time functions are used to transform and convert date and time values. All functions can be used in both the data load script and in chart expressions.

Functions are based on a date-time serial number that equals the number of days since December 30, 1899. The integer value represents the day and the fractional value represents the time of the day.

Qlik Sense uses the numerical value of the parameter, so a number is valid as a parameter also when it is not formatted as a date or a time. If the parameter does not correspond to numerical value, for example, because it is a string, then Qlik Sense attempts to interpret the string according to the date and time environment variables.

If the time format used in the parameter does not correspond to the one set in the environment variables, Qlik Sense will not be able to make a correct interpretation. To resolve this, either change the settings or use an interpretation function.

In the examples for each function, the default time and date formats hh:mm:ss and YYYY-MM-DD (ISO 8601) are assumed.



When processing a timestamp with a date or time function, Qlik Sense ignores any daylight savings time parameters unless the date or time function includes a geographical position.

For example, `convertToLocalTime( filetime('Time.qvd'), 'Paris')` would use daylight savings time parameters while `convertToLocalTime(filetime('Time.qvd'), 'GMT-01:00')` would not use daylight savings time parameters.

### Date and time functions overview

Each function is described further after the overview. You can also click the function name in the syntax to immediately access the details for that specific function.

#### Integer expressions of time

##### **second**

This function returns an integer representing the second when the fraction of the **expression** is interpreted as a time according to the standard number interpretation.

```
second (expression)
```

##### **minute**

This function returns an integer representing the minute when the fraction of the **expression** is interpreted as a time according to the standard number interpretation.

```
minute (expression)
```

##### **hour**

This function returns an integer representing the hour when the fraction of the **expression** is interpreted as a time according to the standard number interpretation.

```
hour (expression)
```

##### **day**

This function returns an integer representing the day when the fraction of the **expression** is interpreted as a date according to the standard number interpretation.

```
day (expression)
```

##### **week**

This function returns an integer representing the week number according to ISO 8601. The week number is calculated from the date interpretation of the expression, according to the standard number interpretation.

```
week (expression)
```

### month

This function returns a dual value: a month name as defined in the environment variable **MonthNames** and an integer between 1-12. The month is calculated from the date interpretation of the expression, according to the standard number interpretation.

```
month (expression)
```

### year

This function returns an integer representing the year when the **expression** is interpreted as a date according to the standard number interpretation.

```
year (expression)
```

### weekyear

This function returns the year to which the week number belongs according to the environment variables. The week number ranges between 1 and approximately 52.

```
weekyear (expression)
```

### weekday

This function returns a dual value with:

- A day name as defined in the environment variable **DayNames**.
- An integer between 0-6 corresponding to the nominal day of the week (0-6).

```
weekday (date)
```

## Timestamp functions

### now

This function returns a timestamp of the current time. The function returns values in the **TimeStamp** system variable format. The default **timer\_mode** value is 1.

```
now ([ timer_mode])
```

### today

This function returns the current date. The function returns values in the `DateFormat` system variable format.

```
today ([timer_mode])
```

### LocalTime

This function returns a timestamp of the current time for a specified time zone.

```
localtime ([timezone [, ignoreDST ]])
```

## Make functions

### makedate

This function returns a date calculated from the year **YYYY**, the month **MM** and the day **DD**.

```
makedate (YYYY [ , MM [ , DD ] ])
```

### **makeweekdate**

This function returns a date calculated from the year, the week number, and the day of week .

```
makeweekdate (YYYY [ , WW [ , D ] ])
```

### **maketime**

This function returns a time calculated from the hour **hh**, the minute **mm**, and the second **ss**.

```
maketime (hh [ , mm [ , ss [ .fff ] ] ])
```

## Other date functions

### **AddMonths**

This function returns the date occurring **n** months after **startdate** or, if **n** is negative, the date occurring **n** months before **startdate**.

```
addmonths (startdate, n , [ , mode])
```

### **AddYears**

This function returns the date occurring **n** years after **startdate** or, if **n** is negative, the date occurring **n** years before **startdate**.

```
addyears (startdate, n)
```

### **yeartodate**

This function finds if the input timestamp falls within the year of the date the script was last loaded, and returns True if it does, False if it does not.

```
yeartodate (date [ , yearoffset [ , firstmonth [ , todaydate] ] ])
```

## Timezone functions

### **timezone**

This function returns the time zone, as defined on the computer where the Qlik engine is running.

```
timezone ( )
```

### **GMT**

This function returns the current Greenwich Mean Time, as derived from the regional settings.

```
GMT ( )
```

### **UTC**

Returns the current Coordinated Universal Time.

```
UTC ( )
```

### **daylightsaving**

Returns the current adjustment for daylight saving time, as defined in Windows.

```
daylightsaving ( )
```

### **converttolocaltime**

Converts a UTC or GMT timestamp to local time as a dual value. The place can be any of a number of cities, places and time zones around the world.

```
converttolocaltime (timestamp [, place [, ignore_dst=false]])
```

### Set time functions

#### **setdateyear**

This function takes as input a **timestamp** and a **year** and updates the **timestamp** with the **year** specified in input.

```
setdateyear (timestamp, year)
```

#### **setdateyearmonth**

This function takes as input a **timestamp**, a **month** and a **year** and updates the **timestamp** with the **year** and the **month** specified in input.

```
setdateyearmonth (timestamp, year, month)
```

### In... functions

#### **inyear**

This function returns True if **timestamp** lies inside the year containing **base\_date**.

```
inyear (date, basedate , shift [, first_month_of_year = 1])
```

#### **inyeartodate**

This function returns True if **timestamp** lies inside the part of year containing **base\_date** up until and including the last millisecond of **base\_date**.

```
inyeartodate (date, basedate , shift [, first_month_of_year = 1])
```

#### **inquarter**

This function returns True if **timestamp** lies inside the quarter containing **base\_date**.

```
inquarter (date, basedate , shift [, first_month_of_year = 1])
```

#### **inquartertodate**

This function returns True if **timestamp** lies inside the part of the quarter containing **base\_date** up until and including the last millisecond of **base\_date**.

```
inquartertodate (date, basedate , shift [, first_month_of_year = 1])
```

#### **inmonth**

This function returns True if **timestamp** lies inside the month containing **base\_date**.

```
inmonth (date, basedate , shift)
```

#### **inmonthtodate**

Returns True if **date** lies inside the part of month containing **basedate** up until and including the last millisecond of **basedate**.

```
inmonthtodate (date, basedate , shift)
```

### **inmonths**

This function finds if a timestamp falls within the same month, bi-month, quarter, four-month period, or half-year as a base date. It is also possible to find if the timestamp falls within a previous or following time period.

```
inmonths (n, date, basedate , shift [, first_month_of_year = 1])
```

### **inmonthstodate**

This function finds if a timestamp falls within the part a period of the month, bi-month, quarter, four-month period, or half-year up to and including the last millisecond of **base\_date**. It is also possible to find if the timestamp falls within a previous or following time period.

```
inmonthstodate (n, date, basedate , shift [, first_month_of_year = 1])
```

### **inweek**

This function returns True if **timestamp** lies inside the week containing **base\_date**.

```
inweek (date, basedate , shift [, weekstart])
```

### **inweektodate**

This function returns True if **timestamp** lies inside the part of week containing **base\_date** up until and including the last millisecond of **base\_date**.

```
inweektodate (date, basedate , shift [, weekstart])
```

### **inlunarweek**

This function determines if **timestamp** lies inside the lunar week containing **base\_date**. Lunar weeks in Qlik Sense are defined by counting January 1 as the first day of the week., Apart from the final week of the year, each week will contain exactly seven days.

```
inlunarweek (date, basedate , shift [, weekstart])
```

### **inlunarweektodate**

This function finds if **timestamp** lies inside the part of the lunar week up to and including the last millisecond of **base\_date**. Lunar weeks in Qlik Sense are defined by counting January 1 as the first day of the week and, apart from the final week of the year, will contain exactly seven days.

```
inlunarweektodate (date, basedate , shift [, weekstart])
```

### **inday**

This function returns True if **timestamp** lies inside the day containing **base\_timestamp**.

```
inday (timestamp, basetimestamp , shift [, daystart])
```

### **indaytotime**

This function returns True if **timestamp** lies inside the part of day containing **base\_timestamp** up until and including the exact millisecond of **base\_timestamp**.

```
indaytotime (timestamp, basetimestamp , shift [, daystart])
```

### Start ... end functions

#### **yearstart**

This function returns a timestamp corresponding to the start of the first day of the year containing **date**. The default output format will be the **DateFormat** set in the script.

```
yearstart ( date [, shift = 0 [, first_month_of_year = 1]])
```

#### **yearend**

This function returns a value corresponding to a timestamp of the last millisecond of the last day of the year containing **date**. The default output format will be the **DateFormat** set in the script.

```
yearend ( date [, shift = 0 [, first_month_of_year = 1]])
```

#### **yearname**

This function returns a four-digit year as display value with an underlying numeric value corresponding to a timestamp of the first millisecond of the first day of the year containing **date**.

```
yearname (date [, shift = 0 [, first_month_of_year = 1]] )
```

#### **quarterstart**

This function returns a value corresponding to a timestamp of the first millisecond of the quarter containing **date**. The default output format will be the **DateFormat** set in the script.

```
quarterstart (date [, shift = 0 [, first_month_of_year = 1]])
```

#### **quarterend**

This function returns a value corresponding to a timestamp of the last millisecond of the quarter containing **date**. The default output format will be the **DateFormat** set in the script.

```
quarterend (date [, shift = 0 [, first_month_of_year = 1]])
```

#### **quartername**

This function returns a display value showing the months of the quarter (formatted according to the **MonthNames** script variable) and year with an underlying numeric value corresponding to a timestamp of the first millisecond of the first day of the quarter.

```
quartername (date [, shift = 0 [, first_month_of_year = 1]])
```

#### **monthstart**

This function returns a value corresponding to a timestamp of the first millisecond of the first day of the month containing **date**. The default output format will be the **DateFormat** set in the script.

```
monthstart (date [, shift = 0])
```

#### **monthend**

This function returns a value corresponding to a timestamp of the last millisecond of the last day of the month containing **date**. The default output format will be the **DateFormat** set in the script.

```
monthend (date [, shift = 0])
```



### monthname

This function returns a display value showing the month (formatted according to the **MonthNames** script variable) and year with an underlying numeric value corresponding to a timestamp of the first millisecond of the first day of the month.

```
monthname (date [, shift = 0])
```

### monthsstart

This function returns a value corresponding to the timestamp of the first millisecond of the month, bi-month, quarter, four-month period, or half-year containing a base date. It is also possible to find the timestamp for a previous or following time period. The default output format is the **DateFormat** set in the script.

```
monthsstart (n, date [, shift = 0 [, first_month_of_year = 1]])
```

### monthsend

This function returns a value corresponding to a timestamp of the last millisecond of the month, bi-month, quarter, four-month period, or half-year containing a base date. It is also possible to find the timestamp for a previous or following time period.

```
monthsend (n, date [, shift = 0 [, first_month_of_year = 1]])
```

### monthsname

This function returns a display value representing the range of the months of the period (formatted according to the **MonthNames** script variable) as well as the year. The underlying numeric value corresponds to a timestamp of the first millisecond of the month, bi-month, quarter, four-month period, or half-year containing a base date.

```
monthsname (n, date [, shift = 0 [, first_month_of_year = 1]])
```

### weekstart

This function returns a value corresponding to a timestamp of the first millisecond of the first day of the calendar week containing **date**. The default output format is the **DateFormat** set in the script.

```
weekstart (date [, shift = 0 [, weekoffset = 0]])
```

### weekend

This function returns a value corresponding to a timestamp of the last millisecond of the last day of the calendar week containing **date**. The default output format will be the **DateFormat** set in the script.

```
weekend (date [, shift = 0 [, weekoffset = 0]])
```

### weekname

This function returns a value showing the year and week number with an underlying numeric value corresponding to a timestamp of the first millisecond of the first day of the week containing **date**.

```
weekname (date [, shift = 0 [, weekoffset = 0]])
```

### **lunarweekstart**

This function returns a value corresponding to a timestamp of the first millisecond of the first day of the lunar week containing **date**. Lunar weeks in Qlik Sense are defined by counting January 1 as the first day of the week and, apart from the final week of the year, will contain exactly seven days.

```
lunarweekstart (date [, shift = 0 [, weekoffset = 0]])
```

### **lunarweekend**

This function returns a value corresponding to a timestamp of the last millisecond of the last day of the lunar week containing **date**. Lunar weeks in Qlik Sense are defined by counting January 1 as the first day of the week and, apart from the final week of the year, will contain exactly seven days.

```
lunarweekend (date [, shift = 0 [, weekoffset = 0]])
```

### **lunarweekname**

This function returns a display value showing the year and lunar week number corresponding to a timestamp of the first millisecond of the first day of the lunar week containing **date**. Lunar weeks in Qlik Sense are defined by counting January 1 as the first day of the week and, apart from the final week of the year, will contain exactly seven days.

```
lunarweekname (date [, shift = 0 [, weekoffset = 0]])
```

### **daystart**

This function returns a value corresponding to a timestamp with the first millisecond of the day contained in the **time** argument. The default output format will be the **TimestampFormat** set in the script.

```
daystart (timestamp [, shift = 0 [, dayoffset = 0]])
```

### **dayend**

This function returns a value corresponding to a timestamp of the final millisecond of the day contained in **time**. The default output format will be the **TimestampFormat** set in the script.

```
dayend (timestamp [, shift = 0 [, dayoffset = 0]])
```

### **dayname**

This function returns a value showing the date with an underlying numeric value corresponding to a timestamp of the first millisecond of the day containing **time**.

```
dayname (timestamp [, shift = 0 [, dayoffset = 0]])
```

## Day numbering functions

### **age**

The **age** function returns the age at the time of **timestamp** (in completed years) of somebody born on **date\_of\_birth**.

```
age (timestamp, date_of_birth)
```

### networkdays

The **networkdays** function returns the number of working days (Monday-Friday) between and including **start\_date** and **end\_date** taking into account any optionally listed **holiday**.

```
networkdays (start:date, end_date {, holiday})
```

### firstworkdate

The **firstworkdate** function returns the latest starting date to achieve **no\_of\_workdays** (Monday-Friday) ending no later than **end\_date** taking into account any optionally listed holidays. **end\_date** and **holiday** should be valid dates or timestamps.

```
firstworkdate (end_date, no_of_workdays {, holiday} )
```

### lastworkdate

The **lastworkdate** function returns the earliest ending date to achieve **no\_of\_workdays** (Monday-Friday) if starting at **start\_date** taking into account any optionally listed **holiday**. **start\_date** and **holiday** should be valid dates or timestamps.

```
lastworkdate (start_date, no_of_workdays {, holiday})
```

### daynumberofyear

This function calculates the day number of the year in which a timestamp falls. The calculation is made from the first millisecond of the first day of the year, but the first month can be offset.

```
daynumberofyear (date[,firstmonth])
```

### daynumberofquarter

This function calculates the day number of the quarter in which a timestamp falls. This function is used when creating a Master Calendar.

```
daynumberofquarter (date[,firstmonth])
```

## addmonths

This function returns the date occurring **n** months after **startdate** or, if **n** is negative, the date occurring **n** months before **startdate**.

### Syntax:


```
AddMonths (startdate, n , [ , mode])
```

### Return data type: dual

The `addmonths()` function adds or subtracts a defined number of months, *n*, from a `startdate` and returns the resultant date.


The `mode` argument will impact `startdate` values on or after the 28th of the month. By setting the `mode` argument to 1, the `addmonths()` function returns a date that is equal in relative distance to the end of the month as the `startdate`.

Example diagram of `addmonths()` function



For example, February 28 is the last day of the month. If the `addmonths()` function, with a mode of 1, is used to return the date two months later, the function will return the last date of April, April 30.

Example diagram of `addmonths()` function, with `mode=1`



### Arguments

Argument	Description
startdate	The start date as a time stamp, for example '2012-10-12'.
n	Number of months as a positive or negative integer.
mode	Specifies if the month is added relative to the beginning or to the end of the month. Default mode is 0 for additions relative to the beginning of the month. Set mode to 1 for additions relative to the end of the month. When mode is set to 1 and the input date is the 28th or above, the function checks how many days are left to reach the end of the month on the startdate. The same number of days to reach the end of the month are set on the date returned.

### When to use it

The `addmonths()` function will commonly be used in an expression to find a date a given number of months before or after a period of time.

For example, the `addmonths()` function can be used to identify the end date of mobile phone contracts.

### Function examples

Example	Result
<code>addmonths ('01/29/2003' ,3)</code>	Returns '04/29/2003'.
<code>addmonths ('01/29/2003' ,3,0)</code>	Returns '04/29/2003'.

Example	Result
<code>addmonths ('01/29/2003', 3, 1)</code>	Returns '04/28/2003'.
<code>addmonths ('01/29/2003', 1, 0)</code>	Returns '02/28/2003'.
<code>addmonths ('01/29/2003', 1, 1)</code>	Returns '02/26/2003'.
<code>addmonths ('02/28/2003', 1, 0)</code>	Returns '03/28/2003'.
<code>addmonths ('02/28/2003', 1, 1)</code>	Returns '03/31/2003'.
<code>addmonths ('01/29/2003', -3)</code>	Returns '10/29/2002'.

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Example 1 – No additional arguments

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions between 2020 and 2022, which is loaded into a table called `Transactions`.
- The date field provided in the `DateFormat` system variable (MM/DD/YYYY) format.
- The creation of a field, `two_months_later`, that returns the date for two months after the transaction took place.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
  Load
    *,
    addmonths(date,2) as two_months_later
```

```
    ;
Load
*
Inline
[
id,date,amount
8188,'01/10/2020',37.23
8189,'02/28/2020',17.17
8190,'04/09/2020',88.27
8191,'04/16/2020',57.42
8192,'05/21/2020',53.80
8193,'08/14/2020',82.06
8194,'10/07/2020',40.39
8195,'12/05/2020',87.21
8196,'01/22/2021',95.93
8197,'02/03/2021',45.89
8198,'03/17/2021',36.23
8199,'04/23/2021',25.66
8200,'05/04/2021',82.77
8201,'06/30/2021',69.98
8202,'07/26/2021',76.11
8203,'12/27/2021',25.12
8204,'02/02/2022',46.23
8205,'02/26/2022',84.21
8206,'03/07/2022',96.24
8207,'03/11/2022',67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- two\_months\_later


Results table

date	two_months_later
01/10/2020	03/10/2020
02/28/2020	04/28/2020
04/09/2020	06/09/2020
04/16/2020	06/16/2020
05/21/2020	07/21/2020
08/14/2020	10/14/2020
10/07/2020	12/07/2020
12/05/2020	02/05/2021

date	two_months_later
01/22/2021	03/22/2021
02/03/2021	04/03/2021
03/17/2021	05/17/2021
04/23/2021	06/23/2021
05/04/2021	07/04/2021
06/30/2021	08/30/2021
07/26/2021	09/26/2021
12/27/2021	02/27/2022
02/02/2022	04/02/2022
02/26/2022	04/26/2022
03/07/2022	05/07/2022
03/11/2022	05/11/2022

The `two_months_later` field is created in the preceding load statement by using the `addmonths()` function. The first argument provided identifies which date is being evaluated. The second argument is the number of months to add or subtract from the `startdate`. In this instance, the value of 2 is provided.

*Diagram of `addmonths()` function, example with no additional arguments*



Transaction 8193 took place on August 14. Therefore, the `addmonths()` function returns October 14, 2020 for the `two_months_later` field.

### Example 2 – Relative month end

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of month-end transactions in 2022, which is loaded into a table called `Transactions`.
- The date field provided in the `DateFormat` system variable (MM/DD/YYYY) format.
- The creation of a field, `relative_two_months_prior`, that returns the relative month-end date for two months before the transaction took place.

### Load script

```
SET DateFormat='MM/DD/YYYY';

Transactions:
  Load
    *,
    addmonths(date,-2,1) as relative_two_months_prior
  ;

Load
*
Inline
[
id,date,amount
8188,'01/28/2022',37.23
8189,'01/31/2022',57.54
8190,'02/28/2022',17.17
8191,'04/29/2022',88.27
8192,'04/30/2022',57.42
8193,'05/31/2022',53.80
8194,'08/14/2022',82.06
8195,'10/07/2022',40.39
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- `date`
- `relative_two_months_prior`

Results table


<code>date</code>	<code>relative_two_months_prior</code>
01/28/2022	11/27/2021
01/31/2022	11/30/2021
02/28/2022	12/31/2021
04/29/2022	02/27/2022
04/30/2022	02/28/2022
05/31/2022	03/31/2022



date	relative_two_months_prior
08/14/2022	06/14/2022
10/07/2022	08/07/2022

The `relative_two_months_prior` field is created in the preceding load statement by using the `addmonths()` function. The first argument provided identifies which date is being evaluated. The second argument is the number of months to add or subtract from the `startdate`. In this instance, the value of `-2` is provided. The final argument is the mode, with a value of `1`, which forces the function to calculate the relative month-end date for all dates greater than or equal to 28.

*Diagram of `addmonths()` function, example with `n=-2`*



Transaction 8191 takes place on April 29, 2022. Initially, two months prior would set the month to February. Then, due to the third argument of the function setting the mode to 1 and the day value being later than the 27th, the function calculates the relative month-end value. The function identifies that the 29th is the second last day of April and therefore returns the second last day of February, the 27th.

### Example 3– Chart object example

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains the same dataset and scenario as the first example.

However, in this example, the unchanged dataset is loaded into the application. The calculation that returns the date for two months after the transaction took place is created as a measure in a chart object.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
8188,'01/10/2020',37.23
8189,'02/28/2020',17.17
8190,'04/09/2020',88.27
8191,'04/16/2020',57.42
8192,'05/21/2020',53.80
8193,'08/14/2020',82.06
8194,'10/07/2020',40.39
8195,'12/05/2020',87.21
8196,'01/22/2021',95.93
8197,'02/03/2021',45.89
8198,'03/17/2021',36.23
8199,'04/23/2021',25.66
8200,'05/04/2021',82.77
8201,'06/30/2021',69.98
8202,'07/26/2021',76.11
8203,'12/27/2021',25.12
8204,'02/02/2022',46.23
8205,'02/26/2022',84.21
8206,'03/07/2022',96.24
8207,'03/11/2022',67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension: date.

Create the following measure:

```
=addmonths(date,2)
```


Results table

date	=addmonths(date,2)
01/10/2020	03/10/2020
02/28/2020	04/28/2020
04/09/2020	06/09/2020
04/16/2020	06/16/2020
05/21/2020	07/21/2020
08/14/2020	10/14/2020
10/07/2020	12/07/2020
12/05/2020	02/05/2021
01/22/2021	03/22/2021
02/03/2021	04/03/2021
03/17/2021	05/17/2021

date	=addmonths(date,2)
04/23/2021	06/23/2021
05/04/2021	07/04/2021
06/30/2021	08/30/2021
07/26/2021	09/26/2021
12/27/2021	02/27/2022
02/02/2022	04/02/2022
02/26/2022	04/26/2022
03/07/2022	05/07/2022
03/11/2022	05/11/2022

The `two_months_later` measure is created in the chart object by using the `addmonths()` function. The first argument provided identifies which date is being evaluated. The second argument is the number of months to add or subtract from the `startdate`. In this instance, the value of 2 is provided.

*Diagram of `addmonths()` function, chart object example*



Transaction 8193 took place on August 14. Therefore, the `addmonths()` function returns the October 14, 2020 for the `two_months_later` field.

### Example 4 – Scenario

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset which is loaded into a table called `mobilePlans`.
- Information with the contract ID, start date, contract length, and monthly fee.

The end user would like a chart object that displays, by contract ID, the termination date of each phone contract.

### Load script

```

Mobile_Plans:
Load
*
Inline
[
contract_id,start_date,contract_length,monthly_fee
8188,'01/13/2020',18,37.23
8189,'02/26/2020',24,17.17
8190,'03/27/2020',36,88.27
8191,'04/16/2020',24,57.42
8192,'05/21/2020',24,53.80
8193,'08/14/2020',12,82.06
8194,'10/07/2020',18,40.39
8195,'12/05/2020',12,87.21
8196,'01/22/2021',12,95.93
8197,'02/03/2021',18,45.89
8198,'03/17/2021',24,36.23
8199,'04/23/2021',24,25.66
8200,'05/04/2021',12,82.77
8201,'06/30/2021',12,69.98
8202,'07/26/2021',12,76.11
8203,'12/27/2021',36,25.12
8204,'06/06/2022',24,46.23
8205,'07/18/2022',12,84.21
8206,'11/14/2022',12,96.24
8207,'12/12/2022',18,67.67
];

```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- contract\_id
- start\_date
- contract\_length

Create the following measure to calculate the end date of each contract:

```
=addmonths(start_date,contract_length, 0)
```

Results table

contract_id	start_date	contract_length	=addmonths(start_date,contract_length,0)
8188	01/13/2020	18	07/13/2021
8189	02/26/2020	24	02/26/2022
8190	03/27/2020	36	03/27/2023
8191	04/16/2020	24	04/16/2022

contract_id	start_date	contract_length	=addmonths(start_date,contract_length,0)
8192	05/21/2020	24	05/21/2022
8193	08/14/2020	12	08/14/2021
8194	10/07/2020	18	04/07/2022
8195	12/05/2020	12	12/05/2021
8196	01/22/2021	12	01/22/2022
8197	02/03/2021	18	08/03/2022
8198	03/17/2021	24	03/17/2023
8199	04/23/2021	24	04/23/2023
8200	05/04/2021	12	05/04/2022
8201	06/30/2021	12	06/30/2022
8202	07/26/2021	12	07/26/2022
8203	12/27/2021	36	12/27/2024
8204	06/06/2022	24	06/06/2024
8205	07/18/2022	12	07/18/2023
8206	11/14/2022	12	11/14/2023
8207	12/12/2022	18	06/12/2024

## addyears


This function returns the date occurring **n** years after **startdate** or, if **n** is negative, the date occurring **n** years before **startdate**.

### Syntax:

**AddYears** (startdate, n)

**Return data type:** dual

Example diagram of `addyears()` function



The `addyears()` function adds or subtracts a defined number of years, **n**, from a `startdate`. It then returns the resulting date.

### Arguments

Argument	Description
startdate	The start date as a time stamp, for example '2012-10-12'.
n	Number of years as a positive or negative integer.

### Function examples

Example	Result
addyears ('01/29/2010',3)	Returns '01/29/2013'.
addyears ('01/29/2010',-1)	Returns '01/29/2009'.

## Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

## Example 1 – Simple example

Load script and results

### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions between 2020 and 2022, which is loaded into a table called `Transactions`.
- The date field provided in the `DateFormat` system variable (MM/DD/YYYY) format.
- The creation of a field, `two_years_later`, that returns the date for two years after the transaction took place.

### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:  
Load
```

```
*,
    addyears(date,2) as two_years_later
;

Load
*
Inline
[
id,date,amount
8188,'01/10/2020',37.23
8189,'02/28/2020',17.17
8190,'04/09/2020',88.27
8191,'04/16/2020',57.42
8192,'05/21/2020',53.80
8193,'08/14/2020',82.06
8194,'10/07/2020',40.39
8195,'12/05/2020',87.21
8196,'01/22/2021',95.93
8197,'02/03/2021',45.89
8198,'03/17/2021',36.23
8199,'04/23/2021',25.66
8200,'05/04/2021',82.77
8201,'06/30/2021',69.98
8202,'07/26/2021',76.11
8203,'12/27/2021',25.12
8204,'02/02/2022',46.23
8205,'02/26/2022',84.21
8206,'03/07/2022',96.24
8207,'03/11/2022',67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- two\_years\_later


Results table

date	two_years_later
01/10/2020	01/10/2022
02/28/2020	02/28/2022
04/09/2020	04/09/2022
04/16/2020	04/16/2022
05/21/2020	05/21/2022
08/14/2020	08/14/2022
10/07/2020	10/07/2022

date	two_years_later
12/05/2020	12/05/2022
01/22/2021	01/22/2023
02/03/2021	02/03/2023
03/17/2021	03/17/2023
04/23/2021	04/23/2023
05/04/2021	05/04/2023
06/30/2021	06/30/2023
07/26/2021	07/26/2023
12/27/2021	12/27/2023
02/02/2022	02/02/2024
02/26/2022	02/26/2024
03/07/2022	03/07/2024
03/11/2022	03/11/2024

The `two_years_later` field is created in the preceding load statement by using the `addyears()` function. The first argument provided identifies which date is being evaluated. The second argument is the number of years to add or subtract from the start date. In this instance, the value of 2 is provided.

*Diagram of `addyears()` function, basic example*



Transaction 8193 took place on August 14, 2020. Therefore, the `addyears()` function returns August 14, 2022 for the `two_years_later` field.

### Example 2 – Chart object example

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:



- A dataset containing a set of transactions between 2020 and 2022, which is loaded into a table called `Transactions`.
- The date field provided in the `DateFormat` system variable (MM/DD/YYYY) format.

In a chart object, create a measure, `prior_year_date`, that returns the date one year prior to when the transaction takes place.

### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
```

```
8188,'01/10/2020',37.23
```

```
8189,'02/28/2020',17.17
```

```
8190,'04/09/2020',88.27
```

```
8191,'04/16/2020',57.42
```

```
8192,'05/21/2020',53.80
```

```
8193,'08/14/2020',82.06
```

```
8194,'10/07/2020',40.39
```

```
8195,'12/05/2020',87.21
```

```
8196,'01/22/2021',95.93
```

```
8197,'02/03/2021',45.89
```

```
8198,'03/17/2021',36.23
```

```
8199,'04/23/2021',25.66
```

```
8200,'05/04/2021',82.77
```

```
8201,'06/30/2021',69.98
```

```
8202,'07/26/2021',76.11
```

```
8203,'12/27/2021',25.12
```

```
8204,'02/02/2022',46.23
```

```
8205,'02/26/2022',84.21
```

```
8206,'03/07/2022',96.24
```

```
8207,'03/11/2022',67.67
```

```
];
```

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension: `date`.

Create the following measure to calculate the date one year prior to each transaction:

```
=addyears(date,-1)
```


Results table

<code>date</code>	<code>=addyears(date,-1)</code>
01/10/2020	01/10/2019

date	=addyears(date,-1)
02/28/2020	02/28/2019
04/09/2020	04/09/2019
04/16/2020	04/16/2019
05/21/2020	05/21/2019
08/14/2020	08/14/2019
10/07/2020	10/07/2019
12/05/2020	12/05/2019
01/22/2021	01/22/2020
02/03/2021	02/03/2020
03/17/2021	03/17/2020
04/23/2021	04/23/2020
05/04/2021	05/04/2020
06/30/2021	06/30/2020
07/26/2021	07/26/2020
12/27/2021	12/27/2020
02/02/2022	02/02/2021
02/26/2022	02/26/2021
03/07/2022	03/07/2021
03/11/2022	03/11/2021

The `one_year_prior` measure is created in the chart object by using the `addyears()` function. The first argument provided identifies which date is being evaluated. The second argument is the number of years to add or subtract from the `startdate`. In this instance, the value of `-1` is provided.

*Diagram of `addyears()` function, chart object example*



Transaction 8193 took place on August 14. Therefore, the `addyears()` function returns August 14, 2019 for the `one_year_prior` field.

### Example 3 – Scenario

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset which is loaded into a table called `warranties`.
- Information with the product ID, purchase date, warranty length, and purchase price.

The end user would like a chart object that displays, by product ID, the warranty termination date of each product.

#### Load script

```
warranties:
Load
*
Inline
[
product_id,purchase_date,warranty_length,purchase_price
8188, '01/13/2020', 4, 32000
8189, '02/26/2020', 2, 28000
8190, '03/27/2020', 3, 41000
8191, '04/16/2020', 4, 17000
8192, '05/21/2020', 2, 25000
8193, '08/14/2020', 1, 59000
8194, '10/07/2020', 2, 12000
8195, '12/05/2020', 3, 12000
8196, '01/22/2021', 4, 24000
8197, '02/03/2021', 1, 50000
8198, '03/17/2021', 2, 80000
8199, '04/23/2021', 3, 10000
8200, '05/04/2021', 4, 30000
8201, '06/30/2021', 3, 30000
8202, '07/26/2021', 4, 20000
8203, '12/27/2021', 4, 10000
8204, '06/06/2022', 2, 25000
8205, '07/18/2022', 1, 32000
8206, '11/14/2022', 1, 30000
8207, '12/12/2022', 4, 22000
];
```

#### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- product\_id
- purchase\_date
- warranty\_length

Create the following measure to calculate the end date of each product's warranty:

```
=addyears(purchase_date,warranty_length)
```

Results table

product_id	purchase_date	warranty_length	=addyears(purchase_date,warranty_length)
8188	01/13/2020	4	01/13/2024
8189	02/26/2020	2	02/26/2022
8190	03/27/2020	3	03/27/2023
8191	04/16/2020	4	04/16/2024
8192	05/21/2020	2	05/21/2022
8193	08/14/2020	1	08/14/2021
8194	10/07/2020	2	10/07/2022
8195	12/05/2020	3	12/05/2023
8196	01/22/2021	4	01/22/2025
8197	02/03/2021	1	02/03/2022
8198	03/17/2021	2	03/17/2023
8199	04/23/2021	3	04/23/2024
8200	05/04/2021	4	05/04/2025
8201	06/30/2021	3	06/30/2024
8202	07/26/2021	4	07/26/2025
8203	12/27/2021	4	12/27/2025
8204	06/06/2022	2	06/06/2024
8205	07/18/2022	1	07/18/2023
8206	11/14/2022	1	11/14/2023
8207	12/12/2022	4	12/12/2026

### age

The **age** function returns the age at the time of **timestamp** (in completed years) of somebody born on **date\_of\_birth**.

**Syntax:**

```
age(timestamp, date_of_birth)
```

Can be an expression.

**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
<b>timestamp</b>	The timestamp, or expression resolving to a timestamp, up to which to calculate the completed number of years.
<b>date_of_birth</b>	Date of birth of the person whose age is being calculated. Can be an expression.

Examples and results:

These examples use the date format **DD/MM/YYYY**. The date format is specified in the **SET DateFormat** statement at the top of your data load script. Change the format in the examples to suit your requirements.

Scripting examples

Example	Result
age('25/01/2014', '29/10/2012')	Returns 1.
age('29/10/2014', '29/10/2012')	Returns 2.

**Example:**

Add the example script to your app and run it. To see the result, add the fields listed in the results column to a sheet in your app.

```

Employees:
LOAD * INLINE [
Member|DateOfBirth
John|28/03/1989
Linda|10/12/1990
Steve|5/2/1992
Birg|31/3/1993
Raj|19/5/1994
Prita|15/9/1994
Su|11/12/1994
Goran|2/3/1995
Sunny|14/5/1996
Ajoa|13/6/1996
Daphne|7/7/1998
Biffy|4/8/2000
] (delimiter is |);
AgeTable:
Load *,
age('20/08/2015', DateOfBirth) As Age
Resident Employees;
Drop table Employees;

```

The resulting table shows the returned values of age for each of the records in the table.

Results table

Member	DateOfBirth	Age
John	28/03/1989	26
Linda	10/12/1990	24
Steve	5/2/1992	23
Birg	31/3/1993	22
Raj	19/5/1994	21
Prita	15/9/1994	20
Su	11/12/1994	20
Goran	2/3/1995	20
Sunny	14/5/1996	19
Ajoa	13/6/1996	19
Daphne	7/7/1998	17
Biffy	4/8/2000	15

### converttolocaltime

Converts a UTC or GMT timestamp to local time as a dual value. The place can be any of a number of cities, places and time zones around the world.



#### Syntax:

```
ConvertToLocalTime(timestamp [, place [, ignore_dst=false]])
```

**Return data type:** dual

Arguments

Argument	Description
<b>timestamp</b>	The timestamp, or expression resolving to a timestamp, to convert.

Argument	Description
<b>place</b>	<p>A place or timezone from the table of valid places and timezones below. Alternatively, you can use GMT or UTC to define the local time. The following values and time offset ranges are valid:</p> <ul style="list-style-type: none"> <li>• GMT</li> <li>• GMT-12:00 - GMT-01:00</li> <li>• GMT+01:00 - GMT+14:00</li> <li>• UTC</li> <li>• UTC-12:00 - UTC-01:00</li> <li>• UTC+01:00 - UTC+14:00</li> </ul> <div style="border: 1px solid #ccc; padding: 5px; margin-top: 10px;"> <p> If you use a DST offset (that is, you specify an <b>ignore_dst</b> argument value evaluating to False), you must specify a place, rather than a GMT offset, in the <b>place</b> argument. This is because adjusting for Daylight Saving Time requires latitudinal information in addition to the longitudinal information provided by a GMT offset. For information, see <i>Using GMT offsets in combination with DST</i> (page 626).</p> </div> <div style="border: 1px solid #ccc; padding: 5px; margin-top: 10px;"> <p> You can only use standard time offsets. It's not possible to use an arbitrary time offset, for example, GMT-04:27.</p> </div>
<b>ignore_dst</b>	<p>If this argument evaluates to True, DST (daylight saving time) is ignored. Valid argument values evaluating to True include -1 and true().</p> <p>If this argument evaluates to False, the timestamp is adjusted for daylight saving time. Valid argument values evaluating to False include 0 and false().</p> <p>If the <b>ignore_dst</b> argument value is invalid, the function evaluates the expression as if the <b>ignore_dst</b> value evaluates to True. If the <b>ignore_dst</b> argument value is not specified, the function evaluates the expression as if the <b>ignore_dst</b> value evaluates to False.</p>

Valid places and time zones

A-C	D-K	L-R	S-Z
Abu Dhabi	Darwin	La Paz	Samoa
Adelaide	Dhaka	Lima	Santiago
Alaska	Eastern Time (US & Canada)	Lisbon	Sapporo
Amsterdam	Edinburgh	Ljubljana	Sarajevo

## 8 Script and chart functions

<b>A-C</b>	<b>D-K</b>	<b>L-R</b>	<b>S-Z</b>
Arizona	Ekaterinburg	London	Saskatchewan
Astana	Fiji	Madrid	Seoul
Athens	Georgetown	Magadan	Singapore
Atlantic Time (Canada)	Greenland	Mazatlan	Skopje
Auckland	Greenwich Mean Time : Dublin	Melbourne	Sofia
Azores	Guadalajara	Mexico City	Solomon Is.
Baghdad	Guam	Mid-Atlantic	Sri Jayawardenepura
Baku	Hanoi	Minsk	St. Petersburg
Bangkok	Harare	Monrovia	Stockholm
Beijing	Hawaii	Monterrey	Sydney
Belgrade	Helsinki	Moscow	Taipei
Berlin	Hobart	Mountain Time (US & Canada)	Tallinn
Bern	Hong Kong	Mumbai	Tashkent
Bogota	Indiana (East)	Muscat	Tbilisi
Brasilia	International Date Line West	Nairobi	Tehran
Bratislava	Irkutsk	New Caledonia	Tokyo
Brisbane	Islamabad	New Delhi	Urumqi
Brussels	Istanbul	Newfoundland	Warsaw
Bucharest	Jakarta	Novosibirsk	Wellington
Budapest	Jerusalem	Nuku'alofa	West Central Africa
Buenos Aires	Kabul	Osaka	Vienna
Cairo	Kamchatka	Pacific Time (US & Canada)	Vilnius
Canberra	Karachi	Paris	Vladivostok
Cape Verde Is.	Kathmandu	Perth	Volgograd
Caracas	Kolkata	Port Moresby	Yakutsk
Casablanca	Krasnoyarsk	Prague	Yerevan



## 8 Script and chart functions

A-C	D-K	L-R	S-Z
Central America	Kuala Lumpur	Pretoria	Zagreb
Central Time (US & Canada)	Kuwait	Quito	-
Chennai	Kyiv	Riga	-
Chihuahua	-	Riyadh	-
Chongqing	-	Rome	-
Copenhagen	-	-	-

Examples and results:

### Scripting examples

Example	Result
<code>ConvertToLocalTime('2023-08-14 08:39:47','Paris')</code>	Returns '2023-08-14 10:39:47' and the corresponding internal timestamp representation.
<code>ConvertToLocalTime(UTC(), 'Stockholm')</code>	Returns the time for Stockholm, adjusting for daylight saving time.
<code>ConvertToLocalTime(UTC(), 'Stockholm', -1)</code>	Returns the time for Stockholm, without daylight saving time adjustment.
<code>ConvertToLocalTime(UTC(), 'GMT-05:00')</code>	Returns the time for the North American east coast, for example, New York. No adjustment is made for daylight saving time because a GMT offset, rather than a place, is specified.
<code>ConvertToLocalTime(UTC(), 'New York', -1)</code>	Returns the time for the North American east coast (New York), without daylight saving time adjustment.
<code>ConvertToLocalTime(UTC(), 'New York', True())</code>	Returns the time for the North American east coast (New York), without daylight saving time adjustment.
<code>ConvertToLocalTime(UTC(), 'New York', 0)</code>	Returns the time for the North American east coast (New York), adjusting for daylight saving time.
<code>ConvertToLocalTime(UTC(), 'New York', False())</code>	Returns the time for the North American east coast (New York), adjusting for daylight saving time.

### Using GMT offsets in combination with DST

Following the implementation of International Components for Unicode (ICU) libraries in Qlik Sense, the use of GMT (Greenwich Mean Time) offsets in combination with DST (Daylight Saving Time) requires additional latitudinal information.

GMT is a longitudinal (east-west) offset, whereas DST is a latitudinal (north-south) offset. For example, Helsinki (Finland) and Johannesburg (South Africa) share the same GMT+02:00 offset, but they do not share the same DST offset. This means that, further to the GMT offset, any DST offset requires information on the latitudinal position of the local time zone (geographical time zone input) in order to have full information about local DST conditions.

### day

This function returns an integer representing the day when the fraction of the **expression** is interpreted as a date according to the standard number interpretation.

The function returns the day of the month for a particular date. It is commonly used to derive a day field as part of a calendar dimension.

#### Syntax:

```
day (expression)
```

**Return data type:** integer

#### Function examples

Example	Result
day( 1971-10-12 )	returns 12
day( 35648 )	returns 6, because 35648 = 1997-08-06

### Example 1 – DateFormat dataset (script)

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset of dates named `Master_Calendar`. The `DateFormat` system variable is set to `DD/MM/YYYY`.
- A preceding load that creates an additional field, named `day_of_month`, using the `day()` function.
- An additional field, named `long_date`, using the `date()` function to express the full month name.

### Load script

```
SET DateFormat='DD/MM/YYYY';

Master_Calendar:
Load
    date,
    date(date, 'dd-MMMM-YYYY') as long_date,
    day(date) as day_of_month
Inline
[
date
03/11/2022
03/12/2022
03/13/2022
03/14/2022
03/15/2022
03/16/2022
03/17/2022
03/18/2022
03/19/2022
03/20/2022
03/21/2022
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- long\_date
- day\_of\_month

Results table

date	long_date	day_of_month
03/11/2022	11-March- 2022	11
03/12/2022	12-March- 2022	12
03/13/2022	13-March- 2022	13
03/14/2022	14-March- 2022	14
03/15/2022	15-March- 2022	15
03/16/2022	16-March- 2022	16
03/17/2022	17-March- 2022	17
03/18/2022	18-March- 2022	18
03/19/2022	19-March- 2022	19

date	long_date	day_of_month
03/20/2022	20-March- 2022	20
03/21/2022	21-March- 2022	21

The day of the month is correctly evaluated by the `day()` function in the script.

### Example 2 – ANSI dates (script)

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset of dates named `Master_Calendar`. The `DateFormat` system variable `DD/MM/YYYY` is used. However, the dates that are included in the dataset are in ANSI standard date format.
- A preceding load that creates an additional field, named `day_of_month`, using the `date()` function.
- An additional field, named `long_date`, using the `date()` function to express the date with the full month name.

#### Load script

```
SET DateFormat='DD/MM/YYYY';
Master_Calendar:
Load
    date,
    date(date, 'dd-MMMM-YYYY') as long_date,
    day(date) as day_of_month
```

```
Inline
[
date
2022-03-11
2022-03-12
2022-03-13
2022-03-14
2022-03-15
2022-03-16
2022-03-17
2022-03-18
2022-03-19
2022-03-20
2022-03-21
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- long\_date
- day\_of\_month

Results table

date	long_date	day_of_month
03/11/2022	11-March- 2022	11
03/12/2022	12-March- 2022	12
03/13/2022	13-March- 2022	13
03/14/2022	14-March- 2022	14
03/15/2022	15-March- 2022	15
03/16/2022	16-March- 2022	16
03/17/2022	17-March- 2022	17
03/18/2022	18-March- 2022	18
03/19/2022	19-March- 2022	19
03/20/2022	20-March- 2022	20
03/21/2022	21-March- 2022	21

The day of the month is correctly evaluated by the `day()` function in the script.

### Example 3 – Unformatted dates (script)

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset of dates named `master_calendar`. The `dateFormat` system variable `DD/MM/YYYY` is used.
- A preceding load that creates an additional field, named `day_of_month`, using the `day()` function.
- The original unformatted date, named `unformatted_date`.
- An additional field, named `long_date`, using the `date()` is used to convert the numerical date into a formatted date field.

### Load script

```
SET DateFormat='DD/MM/YYYY';

Master_Calendar:
Load
    unformatted_date,
    date(unformatted_date,'dd-MMMM-YYYY') as long_date,
    day(date) as day_of_month

Inline
[
unformatted_date
44868
44898
44928
44958
44988
45018
45048
45078
45008
45038
45068
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- unformatted\_date
- long\_date
- day\_of\_month

Results table

unformatted_date	long_date	day_of_month
44868	03-November- 2022	3
44898	03-December- 2022	3
44928	02-January- 2023	2
44958	01-February- 2023	1
44988	03-March- 2023	3
45008	23-March- 2023	23
45018	02-April- 2023	2
45038	22-April- 2023	22

unformatted_date	long_date	day_of_month
45048	02-May- 2023	2
45068	22-May- 2023	22
45078	01-June- 2023	1

The day of the month is correctly evaluated by the `day()` function in the script.

### Example 4 – Calculating expiry month (chart)

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset of orders placed in March named `orders`. The table contains three fields:
  - `id`
  - `order_date`
  - `amount`

#### Load script

Orders:

Load

```
    id,  
    order_date,  
    amount
```

Inline

```
[  
id,order_date,amount  
1,03/01/2022,231.24  
2,03/02/2022,567.28  
3,03/03/2022,364.28  
4,03/04/2022,575.76  
5,03/05/2022,638.68  
6,03/06/2022,785.38  
7,03/07/2022,967.46  
8,03/08/2022,287.67  
9,03/09/2022,764.45  
10,03/10/2022,875.43  
11,03/11/2022,957.35  
];
```

#### Results

Load the data and open a sheet. Create a new table and add this field as a dimension: `order_date`.

To calculate the delivery date, create this measure `=day(order_date+5)`.

Results table

<b>order_date</b>	<b>=day(order_date+5)</b>
03/11/2022	16
03/12/2022	17
03/13/2022	18
03/14/2022	19
03/15/2022	20
03/16/2022	21
03/17/2022	22
03/18/2022	23
03/19/2022	24
03/20/2022	25
03/21/2022	26

The `day()` function correctly determines that an order placed on the 11th of March would be delivered on the 16th based on a 5 day delivery period.

### dayend

This function returns a value corresponding to a timestamp of the final millisecond of the day contained in **time**. The default output format will be the **TimestampFormat** set in the script.

#### Syntax:

```
DayEnd(time[, [period_no[, day_start]])
```

#### When to use it

The `dayend()` function is commonly used as part of an expression when the user would like the calculation to use the fraction of the day that has not yet occurred. For example, to calculate the total expenses still to be incurred during the day.

**Return data type:** dual

Arguments

<b>Argument</b>	<b>Description</b>
<b>time</b>	The timestamp to evaluate.



Argument	Description
<b>period_no</b>	<b>period_no</b> is an integer, or expression that resolves to an integer, where the value 0 indicates the day that contains <b>time</b> . Negative values in <b>period_no</b> indicate preceding days and positive values indicate succeeding days.
<b>day_start</b>	To specify that days do not starting at midnight, indicate an offset as a fraction of a day in <b>day_start</b> . For example, 0.125 to denote 3:00 AM. In other words, to create the offset, divide the start time by 24 hours. For example, for a day to begin at 7:00 AM, use the fraction 7/24.

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

#### Function examples

Example	Result
<code>dayend('01/25/2013 16:45:00')</code>	Returns 01/25/2013 23:59:59. PM
<code>dayend('01/25/2013 16:45:00', -1)</code>	Returns 01/24/2013 23:59:59. PM
<code>dayend('01/25/2013 16:45:00', 0, 0.5)</code>	Returns 01/26/2013 11:59:59. PM

### Example 1 - Basic script

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a list of dates is loaded into a table named "Calendar".
- The default `DateFormat` system variable (MM/DD/YYYY).
- A preceding load to create an additional field 'EOD\_timestamp', using the `dayend()` function.

### Load script

```
SET TimestampFormat='M/D/YYYY h:mm:ss[.fff] TT';
```

```
Calendar:
```

```
    Load
        date,
        dayend(date) as EOD_timestamp
    ;
```

```
Load
```

```
date
```

```
Inline
```

```
[
```

```
date
```

```
03/11/2022 1:47:15 AM
```

```
03/12/2022 4:34:58 AM
```

```
03/13/2022 5:15:55 AM
```

```
03/14/2022 9:25:14 AM
```

```
03/15/2022 10:06:54 AM
```

```
03/16/2022 10:44:42 AM
```

```
03/17/2022 11:33:30 AM
```

```
03/18/2022 12:58:14 PM
```

```
03/19/2022 4:23:12 PM
```

```
03/20/2022 6:42:15 PM
```

```
03/21/2022 7:41:16 PM
```

```
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- EOD\_timestamp

Results table

date	EOD_timestamp
03/11/2022 1:47:15 AM	3/11/2022 11:59:59 PM
03/12/2022 4:34:58 AM	3/12/2022 11:59:59 PM
03/13/2022 5:15:55 AM	3/13/2022 11:59:59 PM
03/14/2022 9:25:14 AM	3/14/2022 11:59:59 PM
03/15/2022 10:06:54 AM	3/15/2022 11:59:59 PM
03/16/2022 10:44:42 AM	3/16/2022 11:59:59 PM
03/17/2022 11:33:30 AM	3/17/2022 11:59:59 PM
03/18/2022 12:58:14 PM	3/18/2022 11:59:59 PM
03/19/2022 4:23:12 PM	3/19/2022 11:59:59 PM

date	EOD_timestamp
03/20/2022 6:42:15 PM	3/20/2022 11:59:59 PM
03/21/2022 7:41:16 PM	3/21/2022 11:59:59 PM

As you can see in the table above, the end of day timestamp is generated for each date in our dataset. The timestamp is in the format of the system variable `TimestampFormat M/D/YYYY h:mm:ss [.fff] TT`.

### Example 2 – period\_no

#### Load script and results

##### Overview

Open the Data load editor and add the load script below to a new tab.

You will load a dataset containing service bookings into a table named 'Services'.

The dataset includes the following fields:

- service\_id
- service\_date
- amount

You will create two new fields in the table:

- deposit\_due\_date: The date when the deposit should be received. This is the end of the day three days before the service\_date.
- final\_payment\_due\_date: The date when the final payment should be received. This is the end of the day seven days after the service\_date.

The two fields above are created in a preceding load using the `dayend()` function and they supply the first two parameters, `time` and `period_no`.

#### Load script

```
SET TimestampFormat='M/D/YYYY h:mm:ss[.fff] TT';
```

```
Services:
```

```
  Load
    *,
    dayend(service_date,-3) as deposit_due_date,
    dayend(service_date,7) as final_payment_due_date
  ;
```

```
  Load
    service_id,
    service_date,
    amount
  Inline
  [
```

```

service_id, service_date, amount
1,03/11/2022 9:25:14 AM,231.24
2,03/12/2022 10:06:54 AM,567.28
3,03/13/2022 10:44:42 AM,364.28
4,03/14/2022 11:33:30 AM,575.76
5,03/15/2022 12:58:14 PM,638.68
6,03/16/2022 4:23:12 PM,785.38
7,03/17/2022 6:42:15 PM,967.46
8,03/18/2022 7:41:16 PM,287.67
9,03/19/2022 8:14:15 PM,764.45
10,03/20/2022 9:23:51 PM,875.43
11,03/21/2022 10:04:41 PM,957.35
];

```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- service\_date
- deposit\_due\_date
- final\_payment\_due\_date

Results table

service_date	deposit_due_date	final_payment_due_date
03/11/2022 9:25:14 AM	3/8/2022 11:59:59 PM	3/18/2022 11:59:59 PM
03/12/2022 10:06:54 AM	3/9/2022 11:59:59 PM	3/19/2022 11:59:59 PM
03/13/2022 10:44:42 AM	3/10/2022 11:59:59 PM	3/20/2022 11:59:59 PM
03/14/2022 11:33:30 AM	3/11/2022 11:59:59 PM	3/21/2022 11:59:59 PM
03/15/2022 12:58:14 PM	3/12/2022 11:59:59 PM	3/22/2022 11:59:59 PM
03/16/2022 4:23:12 PM	3/13/2022 11:59:59 PM	3/23/2022 11:59:59 PM
03/17/2022 6:42:15 PM	3/14/2022 11:59:59 PM	3/24/2022 11:59:59 PM
03/18/2022 7:41:16 PM	3/15/2022 11:59:59 PM	3/25/2022 11:59:59 PM
03/19/2022 8:14:15 PM	3/16/2022 11:59:59 PM	3/26/2022 11:59:59 PM
03/20/2022 9:23:51 PM	3/17/2022 11:59:59 PM	3/27/2022 11:59:59 PM
03/21/2022 10:04:41 PM	3/18/2022 11:59:59 PM	3/28/2022 11:59:59 PM

The values of the new fields are in the timestampFormat `M/D/YYYY h:mm:ss[.fff] TT`. Because the function `dayend()` was used, the timestamp values are all the last millisecond of the day.

The deposit due date values are three days before the service date because the second argument passed in the `dayend()` function is negative.

The final payment due date values are seven days after the service date because the second argument passed in the `dayend()` function is positive.

### Example 3 – day\_start script

#### Load script and results

##### Overview

Open the Data load editor and add the load script below in a new tab.

The dataset and scenario used in this example is the same as in the previous example.

As in the previous example, you will create two new fields:

- `deposit_due_date`: The date when the deposit should be received. This is the end of the day three days before the `service_date`.
- `final_payment_due_date`: The date when the final payment should be received. This is the end of the day seven days after the `service_date`.

However, your company would like to operate under a policy where the working day begins at 5 PM and ends at 5 PM the following day. Your company can then monitor transactions that occur in those working hours.

To achieve these requirements, the two fields above are created in a preceding load using the `dayend()` function and use all three arguments, `time`, `period_no`, and `day_start`.

##### Load Script

```
SET TimestampFormat='M/D/YYYY h:mm:ss[.fff] TT';
```

```
Services:
```

```
Load
```

```
*
```

```
dayend(service_date,-3,17/24) as deposit_due_date,
```

```
dayend(service_date,7,17/24) as final_payment_due_date
```

```
;
```

```
Load
```

```
service_id,
```

```
service_date,
```

```
amount
```

```
Inline
```

```
[
```

```
service_id, service_date, amount
```

```
1,03/11/2022 9:25:14 AM,231.24
```

```
2,03/12/2022 10:06:54 AM,567.28
```

```
3,03/13/2022 10:44:42 AM,364.28
```

```
4,03/14/2022 11:33:30 AM,575.76
```

```
5,03/15/2022 12:58:14 PM,638.68
```

```
6,03/16/2022 4:23:12 PM,785.38
```

```
7,03/17/2022 6:42:15 PM,967.46
```

```
8,03/18/2022 7:41:16 PM,287.67
```

```
9,03/19/2022 8:14:15 PM,764.45
```

```
10,03/20/2022 9:23:51 PM,875.43
```

```
11,03/21/2022 10:04:41 PM,957.35  
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- `service_date`
- `deposit_due_date`
- `final_payment_due_date`

Results table

<code>service_date</code>	<code>deposit_due_date</code>	<code>final_payment_due_date</code>
03/11/2022 9:25:14 AM	3/8/2022 4:59:59 PM	3/18/2022 4:59:59 PM
03/12/2022 10:06:54 AM	3/9/2022 4:59:59 PM	3/19/2022 4:59:59 PM
03/13/2022 10:44:42 AM	3/10/2022 4:59:59 PM	3/20/2022 4:59:59 PM
03/14/2022 11:33:30 AM	3/11/2022 4:59:59 PM	3/21/2022 4:59:59 PM
03/15/2022 12:58:14 PM	3/12/2022 4:59:59 PM	3/22/2022 4:59:59 PM
03/16/2022 4:23:12 PM	3/13/2022 4:59:59 PM	3/23/2022 4:59:59 PM
03/17/2022 6:42:15 PM	3/14/2022 4:59:59 PM	3/24/2022 4:59:59 PM
03/18/2022 7:41:16 PM	3/15/2022 4:59:59 PM	3/25/2022 4:59:59 PM
03/19/2022 8:14:15 PM	3/16/2022 4:59:59 PM	3/26/2022 4:59:59 PM
03/20/2022 9:23:51 PM	3/17/2022 4:59:59 PM	3/27/2022 4:59:59 PM
03/21/2022 10:04:41 PM	3/18/2022 4:59:59 PM	3/28/2022 4:59:59 PM

While the dates remain the same as in Example 2, the dates now have a timestamp of the last millisecond before 5:00 PM because the value of the third argument, `day_start`, passed into the `dayend()` function is 17/24.

### Example 4 – Chart example

#### Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The dataset and scenario used in this example is the same as in the previous two examples. The company would like to operate under a policy where the working day begins at 5:00 PM and ends at 5:00 PM the following day.

As in the previous example, you will create two new fields:

- `deposit_due_date`: The date when the deposit should be received. This is the end of the day three days before the `service_date`.
- `final_payment_due_date`: The date when the final payment should be received. This is the end of the day seven days after the `service_date`.

### Load Script

```
SET TimestampFormat='M/D/YYYY h:mm:ss[.fff] TT';
```

```
Services:
```

```
Load
```

```
service_id,
```

```
service_date,
```

```
amount
```

```
Inline
```

```
[
```

```
service_id, service_date, amount
```

```
1,03/11/2022 9:25:14 AM,231.24
```

```
2,03/12/2022 10:06:54 AM,567.28
```

```
3,03/13/2022 10:44:42 AM,364.28
```

```
4,03/14/2022 11:33:30 AM,575.76
```

```
5,03/15/2022 12:58:14 PM,638.68
```

```
6,03/16/2022 4:23:12 PM,785.38
```

```
7,03/17/2022 6:42:15 PM,967.46
```

```
8,03/18/2022 7:41:16 PM,287.67
```

```
9,03/19/2022 8:14:15 PM,764.45
```

```
10,03/20/2022 9:23:51 PM,875.43
```

```
11,03/21/2022 10:04:41 PM,957.35
```

```
];
```

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension:

```
service_date.
```

To create the `deposit_due_date` field, create this measure.

```
=dayend(service_date,-3,17/24).
```

Then, to create the `final_payment_due_date` field, create this measure:

```
=dayend(service_date,7,17/24).
```

Results table

<code>service_date</code>	<code>=dayend(service_date,-3,17/24)</code>	<code>=dayend(service_date,7,17/24)</code>
03/11/2022	3/8/2022 16:59:59 PM	3/18/2022 16:59:59 PM
03/12/2022	3/9/2022 16:59:59 PM	3/19/2022 16:59:59 PM
03/13/2022	3/10/2022 16:59:59 PM	3/20/2022 16:59:59 PM

<b>service_date</b>	<b>=dayend(service_date,-3,17/24)</b>	<b>=dayend(service_date,7,17/24)</b>
03/14/2022	3/11/2022 16:59:59 PM	3/21/2022 16:59:59 PM
03/15/2022	3/12/2022 16:59:59 PM	3/22/2022 16:59:59 PM
03/16/2022	3/13/2022 16:59:59 PM	3/23/2022 16:59:59 PM
03/17/2022	3/14/2022 16:59:59 PM	3/24/2022 16:59:59 PM
03/18/2022	3/15/2022 16:59:59 PM	3/25/2022 16:59:59 PM
03/19/2022	3/16/2022 16:59:59 PM	3/26/2022 16:59:59 PM
03/20/2022	3/17/2022 16:59:59 PM	3/27/2022 16:59:59 PM
03/21/2022	3/18/2022 16:59:59 PM	3/28/2022 16:59:59 PM

The values of the new fields are in the `TimestampFormat M/D/YYYY h:mm:ss[.fff] TT`. Because the function `dayend()` was used, the timestamp values are all the last millisecond of the day.

The payment due date values are three days before the service date because the second argument passed in the `dayend()` function is negative.

The final payment due date values are seven days after the service date because the second argument passed in the `dayend()` function is positive.

The dates have a timestamp of the last millisecond before 5:00 PM because the value of the third argument, `day_start`, that passed into the `dayend()` function is `17/24`.

### Arguments

<b>Argument</b>	<b>Description</b>
<b>time</b>	The timestamp to evaluate.
<b>period_no</b>	<b>period_no</b> is an integer, or expression that resolves to an integer, where the value 0 indicates the day that contains <b>time</b> . Negative values in <b>period_no</b> indicate preceding days and positive values indicate succeeding days.
<b>day_start</b>	To specify that days do not starting at midnight, indicate an offset as a fraction of a day in <b>day_start</b> . For example, 0.125 to denote 3:00 AM.

## daylightsaving

Returns the current adjustment for daylight saving time, as defined in Windows.

### Syntax:

```
DaylightSaving( )
```

**Return data type:** dual

### Example:

```
daylightsaving( )
```



## dayname

This function returns a value showing the date with an underlying numeric value corresponding to a timestamp of the first millisecond of the day containing **time**.

### Syntax:

```
DayName (time[, period_no [, day_start]])
```

**Return data type:** dual

### Arguments:

#### Arguments

Argument	Description
<b>time</b>	The timestamp to evaluate.
<b>period_no</b>	<b>period_no</b> is an integer, or expression that resolves to an integer, where the value 0 indicates the day that contains <b>time</b> . Negative values in <b>period_no</b> indicate preceding days and positive values indicate succeeding days.
<b>day_start</b>	To specify that days do not starting at midnight, indicate an offset as a fraction of a day in <b>day_start</b> . For example, 0.125 to denote 3:00 AM.

Examples and results:

These examples use the date format **DD/MM/YYYY**. The date format is specified in the **SET DateFormat** statement at the top of your data load script. Change the format in the examples to suit your requirements.

#### Scripting examples

Example	Result
dayname('25/01/2013 16:45:00')	Returns 25/01/2013.
dayname('25/01/2013 16:45:00', -1)	Returns 24/01/2013.
dayname('25/01/2013 16:45:00', 0, 0.5 )	Returns 25/01/2013.  Displaying the full timestamp shows the underlying numeric value corresponds to '25/01/2013 12:00:00.000.

### Example:

Add the example script to your app and run it. To see the result, add the fields listed in the results column to a sheet in your app.

## 8 Script and chart functions

---

In this example, the day name is created from the timestamp that marks the beginning of the day after each invoice date in the table.

```
TempTable:
LOAD RecNo() as InvID, * Inline [
InvDate
28/03/2012
10/12/2012
5/2/2013
31/3/2013
19/5/2013
15/9/2013
11/12/2013
2/3/2014
14/5/2014
13/6/2014
7/7/2014
4/8/2014
];
```

```
InvoiceData:
LOAD *,
DayName(InvDate, 1) AS DName
Resident TempTable;
Drop table TempTable;
```

The resulting table contains the original dates and a column with the return value of the dayname() function. You can display the full timestamp by specifying the formatting in the propertiespanel.

Results table

<b>InvDate</b>	<b>DName</b>
28/03/2012	29/03/2012 00:00:00
10/12/2012	11/12/2012 00:00:00
5/2/2013	07/02/2013 00:00:00
31/3/2013	01/04/2013 00:00:00
19/5/2013	20/05/2013 00:00:00
15/9/2013	16/09/2013 00:00:00
11/12/2013	12/12/2013 00:00:00
2/3/2014	03/03/2014 00:00:00
14/5/2014	15/05/2014 00:00:00
13/6/2014	14/06/2014 00:00:00
7/7/2014	08/07/2014 00:00:00
4/8/2014	05/08/2014 00:00:00

## daynumberofquarter

This function calculates the day number of the quarter in which a timestamp falls. This function is used when creating a Master Calendar.

### Syntax:

```
DayNumberOfQuarter(timestamp[,start_month])
```

**Return data type:** integer

### Arguments

Argument	Description
<b>timestamp</b>	The date or timestamp to evaluate.
<b>start_month</b>	By specifying a <b>start_month</b> between 2 and 12 (1, if omitted), the beginning of the year may be moved forward to the first day of any month. For example, if you want to work with a fiscal year starting March 1, specify <b>start_month</b> = 3.

These examples use the date format **DD/MM/YYYY**. The date format is specified in the **SET DateFormat** statement at the top of your data load script. Change the format in the examples to suit your requirements.

### Function examples

Example	Result
DayNumberOfQuarter('12/09/2014')	Returns 74, the day number of the current quarter.
DayNumberOfQuarter('12/09/2014',3)	Returns 12, the day number of the current quarter. In this case, the first quarter starts with March (because start_month is specified as 3). This means that the current quarter is the third quarter, which started on September 1.

## Example 1 – January start of year (script)

Load script and results

### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A simple dataset containing a list of dates, which is loaded into a table named calendar. The default DateFormat system variable MM/DD/YYYY is used.
- A preceding load that creates an additional field named daynrqtr, using the DayNumberOfQuarter() function.

Aside from the date, no additional parameters are provided to the function.

### Load script

```
SET DateFormat='MM/DD/YYYY';

Calendar:
Load
    date,
    DayNumberOfQuarter(date) as DayNrQtr
    ;

Load
date
Inline
[
date
01/01/2022
01/10/2022
01/31/2022
02/01/2022
02/10/2022
02/28/2022
03/01/2022
03/31/2022
04/01/2022
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- daynrqtr

Results table

date	daynrqtr
01/01/2022	1
01/10/2022	10
01/31/2022	31
02/01/2022	32
02/10/2022	41
02/28/2022	59
03/01/2022	61
03/31/2022	91
04/01/2022	1

The first day of the year is January 1 because no second argument was passed into the `DayNumberOfQuarter()` function.

January 1st is the 1st day of the quarter whilst February 1st is the 32nd day of the quarter. The 31st of March is the 91st and final day of the quarter, whilst the 1st of April is the 1st day of the 2nd Quarter.

### Example 2 – February start of year (script)

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same dataset from the first example.
- The default `DateFormat` system variable `MM/DD/YYYY` is used.
- A `start_month` argument beginning on February 1. This sets the financial year to February 1.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Calendar:
```

```
Load
```

```
    date,  
    DayNumberOfQuarter(date,2) as DayNrQtr  
;
```

```
Load
```

```
date
```

```
Inline
```

```
[
```

```
date
```

```
01/01/2022
```

```
01/10/2022
```

```
01/31/2022
```

```
02/01/2022
```

```
02/10/2022
```

```
02/28/2022
```

```
03/01/2022
```

```
03/31/2022
```

```
04/01/2022
```

```
];
```

#### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- daynrqtr

Results table

<b>date</b>	<b>daynrqtr</b>
01/01/2022	62
01/10/2022	71
01/31/2022	92
02/01/2022	1
02/10/2022	10
02/28/2022	28
03/01/2022	30
03/31/2022	60
04/01/2022	61

The first day of the year is the 1st of February because the second argument passed into the `dayNumberOfQuarter()` function was 2.

The first quarter of the year operates between February and April whilst the fourth quarter operates between November and January. This is shown in the results table where February 1st is the 1st day of the quarter whilst January 31st is the 92nd and last day of the quarter.

### Example 3 – January start of year (chart)

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same dataset from the first example.
- The default `DateFormat` system variable `MM/DD/YYYY` is used.

However, in this example, the unchanged dataset is loaded into the application. The value of the day of the quarter is calculated via a measure in a chart object.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Calendar:  
Load  
date  
Inline  
[  
date
```

```
01/01/2022
01/10/2022
01/31/2022
02/01/2022
02/10/2022
02/28/2022
03/01/2022
03/31/2022
04/01/2022
];
```

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension: date.

Create the following measure:

```
=daynumberofquarter(date)
```

Results table

date	=daynumberofquarter(date)
01/01/2022	1
01/10/2022	10
01/31/2022	31
02/01/2022	32
02/10/2022	41
02/28/2022	59
03/01/2022	61
03/31/2022	91
04/01/2022	1

The first day of the year is the 1st of January because no second argument passed into the `DayNumberOfQuarter()` function.

January 1st is the 1st day of the quarter whilst February 1st is the 32nd day of the quarter. The 31st of March is the 91st and final day of the quarter, whilst the 1st of April is the 1st day of the 2nd Quarter.

### Example 4 – February start of year (chart)

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same dataset from the first example.
- The default `DateFormat` system variable `MM/DD/YYYY` is used.
- The financial year runs from the 1st of February to the 31st of January.

However, in this example, the unchanged dataset is loaded into the application. The value of the day of the quarter is calculated via a measure in a chart object.

### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Calendar:
Load
date
inline
[
date
01/01/2022
01/10/2022
01/31/2022
02/01/2022
02/10/2022
02/28/2022
03/01/2022
03/31/2022
04/01/2022
];
```

### Chart object

Load the data and open a sheet. Create a new table and add this field as a dimension: `date`.

Create the following measure:

```
=daynumberofquarter(date,2)
```

### Results

Results table

<b>date</b>	<b>=daynumberofquarter(date,2)</b>
01/01/2022	62
01/10/2022	71
01/31/2022	92
02/01/2022	1
02/10/2022	10
02/28/2022	28



date	=daynumberofquarter(date,2)
03/01/2022	30
03/31/2022	60
04/01/2022	61

The first day of the year is the 1st of January because the second argument passed into the `DayNumberOfQuarter()` function was 2.

The first quarter of the year operates between February and April whilst the fourth quarter operates between November and January. This is evidenced in the results table where February 1st is the 1st day of the quarter whilst January 31st is the 92nd and last day of the quarter.

### daynumberofyear

This function calculates the day number of the year in which a timestamp falls. The calculation is made from the first millisecond of the first day of the year, but the first month can be offset.

#### Syntax:

```
DayNumberOfYear(timestamp[, start_month])
```

**Return data type:** integer

#### Arguments

Argument	Description
<b>timestamp</b>	The date or timestamp to evaluate.
<b>start_month</b>	By specifying a <b>start_month</b> between 2 and 12 (1, if omitted), the beginning of the year may be moved forward to the first day of any month. For example, if you want to work with a fiscal year starting March 1, specify <b>start_month</b> = 3.

These examples use the date format **DD/MM/YYYY**. The date format is specified in the **SET DateFormat** statement at the top of your data load script. Change the format in the examples to suit your requirements.

#### Function examples

Example	Result
<code>DayNumberOfYear( '12/09/2014' )</code>	Returns 256, the day number counted from the first of the year.
<code>DayNumberOfYear( '12/09/2014', 3 )</code>	Returns 196, the number of the day, as counted from 1 March.

### Example 1 – January start of year (script)

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A simple dataset containing a list of dates, which is loaded into a table named `calendar`. The default `DateFormat` system variable `MM/DD/YYYY` is used.
- A preceding load that creates an additional field named `daynryear`, using the `DayNumberOfYear()` function.

Aside from the date, no additional parameters are provided to the function.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
calendar:
```

```
Load
```

```
    date,  
    DayNumberOfYear(date) as daynryear  
;
```

```
Load
```

```
date
```

```
InLine
```

```
[
```

```
date
```

```
01/01/2022
```

```
01/10/2022
```

```
01/31/2022
```

```
02/01/2022
```

```
02/10/2022
```

```
06/30/2022
```

```
07/26/2022
```

```
10/31/2022
```

```
11/01/2022
```

```
12/31/2022
```

```
];
```

#### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- `date`
- `daynryear`

Results table

<b>date</b>	<b>daynryear</b>
01/01/2022	1
01/10/2022	10
01/31/2022	31
02/01/2022	32
02/10/2022	41
06/30/2022	182
07/26/2022	208
10/31/2022	305
11/01/2022	306
12/31/2022	366

The first day of the year is the 1st of January because no second argument was passed into the `DayNumberOfYear()` function.

January 1st is the 1st day of the quarter whilst February 1st is the 32nd day of the year. The 30th of June is the 182nd whilst the 31st of December is the 366th and final day of the year.

### Example 2 – November start of year (script)

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same dataset from the first example.
- The default `DateFormat` system variable `MM/DD/YYYY` is used
- A `start_month` argument beginning on November 1. This sets the financial year to November 1.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Calendar:
```

```
Load
```

```
    date,  
    DayNumberOfYear(date,11) as daynryear  
;
```

```
Load
```

```
date
inline
[
date
01/01/2022
01/10/2022
01/31/2022
02/01/2022
02/10/2022
06/30/2022
07/26/2022
10/31/2022
11/01/2022
12/31/2022
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- daynryear

Results table

date	daynryear
01/01/2022	62
01/10/2022	71
01/31/2022	92
02/01/2022	93
02/10/2022	102
06/30/2022	243
07/26/2022	269
10/31/2022	366
11/01/2022	1
12/31/2022	61

The first day of the year is the 1st of November because the second argument passed into the `DayNumberOfYear()` function was 11.

January 1st is the 1st day of the quarter whilst February 1st is the 32nd day of the year. The 30th of June is the 182nd whilst the 31st of December is the 366th and final day of the year.

### Example 3 – January start of year (chart)

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same dataset from the first example.
- The default `DateFormat` system variable `MM/DD/YYYY` is used.

However, in this example, the unchanged dataset is loaded into the application. The value of the day of the quarter is calculated via a measure in a chart object.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Calendar:
Load
date
Inline
[
date
01/01/2022
01/10/2022
01/31/2022
02/01/2022
02/10/2022
06/30/2022
07/26/2022
10/31/2022
11/01/2022
12/31/2022
];
```

#### Results

Load the data and open a sheet. Create a new table and add this field as a dimension: `date`.

Create the following measure:

```
=daynumberofyear(date)
```

Results table

<b>date</b>	<b>=daynumberofyear(date)</b>
01/01/2022	1
01/10/2022	10

<b>date</b>	<b>=daynumberofyear(date)</b>
01/31/2022	31
02/01/2022	32
02/10/2022	41
06/30/2022	182
07/26/2022	208
10/31/2022	305
11/01/2022	306
12/31/2022	366

The first day of the year is the 1st of January because no second argument was passed into the DayNumberOfYear() function.

January 1st is the 1st day of the year whilst February 1st is the 32nd day of the year. The 30th of June is the 182nd whilst the 31st of December is the 366th and final day of the year.

### Example 4 – November start of year (chart)

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same dataset from the first example.
- The default DateFormat system variable MM/DD/YYYY is used.
- The financial year runs from the 1st of November to the 31st of October.

However, in this example, the unchanged dataset is loaded into the application. The value of the day of the year is calculated via a measure in a chart object.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
Calendar:
Load
date
Inline
[
date
01/01/2022
01/10/2022
01/31/2022
02/01/2022
```

```
02/10/2022
06/30/2022
07/26/2022
10/31/2022
11/01/2022
12/31/2022
];
```

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension: date.

Create the following measure:

```
=daynumberofyear(date)
```

Results table

date	=daynumberofyear(date,11)
01/01/2022	62
01/10/2022	71
01/31/2022	92
02/01/2022	93
02/10/2022	102
06/30/2022	243
07/26/2022	269
10/31/2022	366
11/01/2022	1
12/31/2022	61

The first day of the year is the 1st of November because the second argument passed into the `DayNumberOfYear()` function was 11.

The financial year operates between November and October. This is shown in the results table where November 1st is the 1st day of the year whilst October 31st is the 366th and last day of the year.

### daystart

This function returns a value corresponding to a timestamp with the first millisecond of the day contained in the **time** argument. The default output format will be the **TimestampFormat** set in the script.

#### Syntax:

```
DayStart(time[, [period_no[, day_start]])
```

**Return data type:** dual

#### Arguments

Argument	Description
<b>time</b>	The timestamp to evaluate.
<b>period_no</b>	<b>period_no</b> is an integer, or expression that resolves to an integer, where the value 0 indicates the day that contains <b>time</b> . Negative values in <b>period_no</b> indicate preceding days and positive values indicate succeeding days.
<b>day_start</b>	To specify that days do not starting at midnight, indicate an offset as a fraction of a day in <b>day_start</b> . For example, 0.125 to denote 3:00 AM. In other words, to create the offset, divide the start time by 24 hours. For example, for a day to begin at 7:00 AM, use the fraction 7/24.

### When to use it

The `daystart()` function is commonly used as part of an expression when the user would like the calculation to use the fraction of the day that has elapsed thus far. For example, it could be used to calculate the total wages earned by employees in the day so far.

These examples use the timestamp format 'M/D/YYYY h:mm:ss[.fff] TT'. The timestamp format is specified in the `SET Timestamp` statement at the top of your data load script. Change the format in the examples to suit your requirements.

#### Function examples

Example	Result
<code>daystart('01/25/2013 4:45:00 PM')</code>	Returns 1/25/2013 12:00:00 AM.
<code>daystart('1/25/2013 4:45:00 PM', -1)</code>	Returns 1/24/2013 12:00:00 AM.
<code>daystart('1/25/2013 16:45:00',0,0.5 )</code>	Returns 1/25/2013 12:00:00 PM.

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.



### Example 1 - Simple example

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A simple dataset containing a list of dates, which is loaded into a table named calendar.
- The default `TimestampFormat` system variable (`(M/D/YYYY h:mm:ss[.fff] TT)`) is used.
- A preceding load which creates an additional field named `SOD_timestamp`, using the `daystart()` function.

Aside from the date, no additional parameters are provided to the function.

#### Load script

```
SET TimestampFormat='M/D/YYYY h:mm:ss[.fff] TT';
```

```
Calendar:
```

```
  Load
    date,
    daystart(date) as SOD_timestamp
  ;
```

```
Load
```

```
date
```

```
Inline
```

```
[
```

```
date
```

```
03/11/2022 1:47:15 AM
```

```
03/12/2022 4:34:58 AM
```

```
03/13/2022 5:15:55 AM
```

```
03/14/2022 9:25:14 AM
```

```
03/15/2022 10:06:54 AM
```

```
03/16/2022 10:44:42 AM
```

```
03/17/2022 11:33:30 AM
```

```
03/18/2022 12:58:14 PM
```

```
03/19/2022 4:23:12 PM
```

```
03/20/2022 6:42:15 PM
```

```
03/21/2022 7:41:16 PM
```

```
];
```

#### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- SOD\_timestamp

Results table

<b>date</b>	<b>SOD_timestamp</b>
03/11/2022 1:47:15 AM	3/11/2022 12:00:00 AM
03/12/2022 4:34:58 AM	3/12/2022 12:00:00 AM
03/13/2022 5:15:55 AM	3/13/2022 12:00:00 AM
03/14/2022 9:25:14 AM	3/14/2022 12:00:00 AM
03/15/2022 10:06:54 AM	3/15/2022 12:00:00 AM
03/16/2022 10:44:42 AM	3/16/2022 12:00:00 AM
03/17/2022 11:33:30 AM	3/17/2022 12:00:00 AM
03/18/2022 12:58:14 PM	3/18/2022 12:00:00 AM
03/19/2022 4:23:12 PM	3/19/2022 12:00:00 AM
03/20/2022 6:42:15 PM	3/20/2022 12:00:00 AM
03/21/2022 7:41:16 PM	3/21/2022 12:00:00 AM

As can be seen in the table above, the end of day timestamp is generated for each date in our dataset. The timestamp is in the format of the system variable `TimestampFormat M/D/YYYY h:mm:ss [.fff] TT`.

### Example 2 - period\_no

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing parking fines, which is loaded into a table named `Fines`. The dataset includes the following fields:
  - `id`
  - `due_date`
  - `number_plate`
  - `amount`
- A preceding load using the `daystart()` function and supplying all three parameters: `time`, `period_no`, and `day_start`. This preceding load creates the following two new date fields:
  - An `early_repayment_period` date field, beginning seven days before the payment is due.
  - A `late_penalty_period` date field, beginning 14 days after the payment is due.

### Load script

```
SET TimestampFormat='M/D/YYYY h:mm:ss[.fff] TT';

Fines:
    Load
        *,
        daystart(due_date,-7) as early_repayment_period,
        daystart(due_date,14) as late_penalty_period
    ;

Load
*
Inline
[
id, due_date, number_plate, amount
1,02/11/2022, 573RJG,50.00
2,03/25/2022, SC41854,50.00
3,04/14/2022, 8EHZ378,50.00
4,06/28/2022, 8HSS198,50.00
5,08/15/2022, 1221665,50.00
6,11/16/2022, EAK473,50.00
7,01/17/2023, KD6822,50.00
8,03/22/2023, 1GGLB,50.00
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- due\_date
- early\_repayment\_period
- late\_penalty\_period

Results table

due_date	early_repayment_period	late_penalty_period
02/11/2022 9:25:14 AM	2/4/2022 12:00:00 AM	2/25/2022 12:00:00 AM
03/25/2022 10:06:54 AM	3/18/2022 12:00:00 AM	4/8/2022 12:00:00 AM
04/14/2022 10:44:42 AM	4/7/2022 12:00:00 AM	4/28/2022 12:00:00 AM
06/28/2022 11:33:30 AM	6/21/2022 12:00:00 AM	7/12/2022 12:00:00 AM
08/15/2022 12:58:14 PM	8/8/2022 12:00:00 AM	8/29/2022 12:00:00 AM
11/16/2022 4:23:12 PM	11/9/2022 12:00:00 AM	11/30/2022 12:00:00 AM
01/17/2023 6:42:15 PM	1/10/2023 12:00:00 AM	1/31/2023 12:00:00 AM
03/22/2023 7:41:16 PM	3/15/2023 12:00:00 AM	4/5/2023 12:00:00 AM

The values of the new fields are in the `TimestampFormat` `M/DD/YYYY tt`. Because the function `daystart()` was used, the timestamp values are all the first millisecond of the day.

The early repayment period values are seven days before the due date, as a result of the second argument being passed in the `daystart()` function being negative.

The late repayment period values are 14 days after the due date, as a result of the second argument being passed in the `daystart()` function being positive.

### Example 3 - day\_start

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same dataset and scenario as the previous example.
- The same preceding load as the previous example.

In this example, we set the working day to begin and end at 7:00 AM each day.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Fines:
```

```
    Load
        *,
        daystart(due_date,-7,7/24) as early_repayment_period,
        daystart(due_date,14, 7/24) as late_penalty_period
    ;
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id, due_date, number_plate, amount
```

```
1,02/11/2022, 573RJG,50.00
```

```
2,03/25/2022, SC41854,50.00
```

```
3,04/14/2022, 8EHZ378,50.00
```

```
4,06/28/2022, 8HSS198,50.00
```

```
5,08/15/2022, 1221665,50.00
```

```
6,11/16/2022, EAK473,50.00
```

```
7,01/17/2023, KD6822,50.00
```

```
8,03/22/2023, 1GGLB,50.00
```

```
];
```

#### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- `due_date`
- `early_repayment_period`
- `late_penalty_period`

Results table

<code>due_date</code>	<code>early_repayment_period</code>	<code>late_penalty_period</code>
02/11/2022	2/3/2022 7:00:00 AM	2/24/2022 7:00:00 AM
03/25/2022	3/17/2022 7:00:00 AM	4/7/2022 7:00:00 AM
04/14/2022	4/6/2022 7:00:00 AM	4/27/2022 7:00:00 AM
06/28/2022	6/20/2022 7:00:00 AM	7/11/2022 7:00:00 AM
08/15/2022	8/7/2022 7:00:00 AM	8/28/2022 7:00:00 AM
11/16/2022	11/8/2022 7:00:00 AM	11/29/2022 7:00:00 AM
01/17/2023	1/9/2023 7:00:00 AM	1/30/2023 7:00:00 AM
03/22/2023	3/14/2023 7:00:00 AM	4/4/2023 7:00:00 AM

The dates now have a timestamp of 7:00 AM because the value of the `day_start` argument which was passed into the `daystart()` function was `7/24`. This sets the beginning of the day to 7:00 AM.

Because the `due_date` field does not have a timestamp, it is treated as 12:00 AM, which is thus still part of the previous day, since the days start and end at 7:00 AM. Therefore, the early repayment period for a fine due on February 11 begins on February 3 at 7:00 AM.

### Example 4 - Chart object example

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

This example uses the same dataset and scenario as the previous example.

However, only the original `Fines` table is loaded into the application, with the two additional due dates values being calculated in a chart object.

#### Load script

```
SET TimestampFormat='M/D/YYYY h:mm:ss[.fff] TT';
```

```
Fines:
```

```
  Load
```

```
*
```

```
Inline
```

```
[
```

```
id, due_date, numer_plate, amount
```

```
1,02/11/2022 9:25:14 AM, 573RJG,50.00
2,03/25/2022 10:06:54 AM, SC41854,50.00
3,04/14/2022 10:44:42 AM, 8EHZ378,50.00
4,06/28/2022 11:33:30 AM, 8HSS198,50.00
5,08/15/2022 12:58:14 PM, 1221665,50.00
6,11/16/2022 4:23:12 PM, EAK473,50.00
7,01/17/2023 6:42:15 PM, KD6822,50.00
8,03/22/2023 7:41:16 PM, 1GGLB,50.00
];
```

### Results

#### Do the following:

1. Load the data and open a sheet. Create a new table and add this field as a dimension: `due_date`.
2. To create the `early_repayment_period` field, create the following measure:  
`=daystart(due_date,-7,7/24)`
3. To create the `late_penalty_period` field, create the following measure:  
`=daystart(due_date,14,7/24)`

Results table

<b>due_date</b>	<b>=daystart(due_date,-7,7/24)</b>	<b>=daystart(due_date,14,7/24)</b>
02/11/2022 9:25:14 AM	2/4/2022 7:00:00 AM	2/25/2022 7:00:00 AM
03/25/2022 10:06:54 AM	3/18/2022 7:00:00 AM	4/8/2022 7:00:00 AM
04/14/2022 10:44:42 AM	4/7/2022 7:00:00 AM	4/28/2022 7:00:00 AM
06/28/2022 11:33:30 AM	6/21/2022 7:00:00 AM	7/12/2022 7:00:00 AM
08/15/2022 12:58:14 PM	8/8/2022 7:00:00 AM	8/29/2022 7:00:00 AM
11/16/2022 4:23:12 PM	11/9/2022 7:00:00 AM	11/30/2022 7:00:00 AM
01/17/2023 6:42:15 PM	1/10/2023 7:00:00 AM	1/31/2023 7:00:00 AM
03/22/2023 7:41:16 PM	3/15/2023 7:00:00 AM	4/5/2023 7:00:00 AM

The values of the new fields are in the `TimestampFormat M/D/YYYY h:mm:ss[.fff] TT`. Because the `daystart()` function was used, the timestamp values correspond to the first millisecond of the day.

The early repayment period values are seven days before the due date, since the second argument passed in the `daystart()` function was negative.

The late repayment period values are 14 days after the due date, since the second argument passed in the `daystart()` function was positive.

The dates have a timestamp of 7:00 AM because the value of the third argument passed into the `daystart()` function, `day_start`, was 7/24.

## firstworkdate

The **firstworkdate** function returns the latest starting date to achieve **no\_of\_workdays** (Monday-Friday) ending no later than **end\_date** taking into account any optionally listed holidays. **end\_date** and **holiday** should be valid dates or timestamps.

### Syntax:

```
firstworkdate(end_date, no_of_workdays {, holiday} )
```

**Return data type:** integer

### Arguments:

#### Arguments

Argument	Description
<b>end_date</b>	The timestamp of end date to evaluate.
<b>no_of_workdays</b>	The number of working days to achieve.
<b>holiday</b>	Holiday periods to exclude from working days. A holiday is stated as a string constant date. You can specify multiple holiday dates, separated by commas.  <b>Example:</b> '12/25/2013', '12/26/2013', '12/31/2013', '01/01/2014'

Examples and results:

These examples use the date format **DD/MM/YYYY**. The date format is specified in the **SET DateFormat** statement at the top of your data load script. Change the format in the examples to suit your requirements.

#### Scripting examples

Example	Result
firstworkdate ('29/12/2014', 9)	Returns '17/12/2014'.
firstworkdate ('29/12/2014', 9, '25/12/2014', '26/12/2014')	Returns 15/12/2014 because a holiday period of two days is taken into account.

### Example:

Add the example script to your app and run it. To see the result, add the fields listed in the results column to a sheet in your app.

ProjectTable:

```
LOAD *, recno() as InVID, INLINE [
EndDate
28/03/2015
10/12/2015
5/2/2016
```

```

31/3/2016
19/5/2016
15/9/2016
] ;
NrDays:
Load *,
FirstWorkDate(EndDate,120) As StartDate
Resident ProjectTable;
Drop table ProjectTable;

```

The resulting table shows the returned values of FirstWorkDate for each of the records in the table.

Results table

InVID	EndDate	StartDate
1	28/03/2015	13/10/2014
2	10/12/2015	26/06/2015
3	5/2/2016	24/08/2015
4	31/3/2016	16/10/2015
5	19/5/2016	04/12/2015
6	15/9/2016	01/04/2016

## GMT

This function returns the current Greenwich Mean Time, as derived from the regional settings. The function returns values in the `TimestampFormat` system variable format.

Whenever the app is reloaded, any load script table, variable or chart object that uses the `GMT` function will be adjusted to the latest current Greenwich Mean Time as derived from the system clock.

### Syntax:

```
GMT ( )
```

**Return data type:** dual

These examples use the timestamp format `M/D/YYYY h:mm:ss[.fff] TT`. The date format is specified in the `SET TimestampFormat` statement at the top of your data load script. Change the format in the examples to suit your requirements.

Function examples

Example	Result
GMT()	3/28/2022 2:47:36 PM



### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Example 1 - Variable (script)

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab. This example will set the current Greenwich Mean Time as a variable in the load script using the `GMT` function.

#### Load script

```
LET vGMT = GMT();
```

#### Results

Load the data and create a sheet. Create a text box using the **Text & image** chart object.

Add this measure to the text box:

```
=vGMT
```

The text box should contain a line of text with a date and time, similar to the one shown below:

```
3/28/2022 2:47:36 PM
```

### Example 2 - November start of year (script)

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing overdue library books, which is loaded into a table named overdue. The default `DateFormat` system variable `MM/DD/YYYY` is used.
- The creation of a new field called `days_overdue`, which calculates how many day overdue each book is.

### Load script

```
SET DateFormat='MM/DD/YYYY';

Overdue:
  Load
    *,
    Floor(GMT()-due_date) as days_overdue
  ;

Load
*
Inline
[
cust_id,book_id,due_date
1,4,01/01/2021,
2,24,01/10/2021,
6,173,01/31/2021,
31,281,02/01/2021,
86,265,02/10/2021,
52,465,06/30/2021,
26,537,07/26/2021,
92,275,10/31/2021,
27,455,11/01/2021,
27,46,12/31/2021
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- `due_date`
- `book_id`
- `days_overdue`

Results table

<b>due_date</b>	<b>book_id</b>	<b>days_overdue</b>
01/01/2021	4	455
01/10/2021	24	446
01/31/2021	173	425
02/01/2021	281	424
02/10/2021	265	415

due_date	book_id	days_overdue
06/30/2021	465	275
07/26/2021	537	249
10/31/2021	275	152
11/01/2021	455	151
12/31/2021	46	91

The values in the `days_overdue` field are calculated by finding the difference between the current Greenwich Mean Time, using the `GMT()` function, and the original due date. In order to calculate only the days, the results are rounded off to the nearest whole number using the `Floor()` function.

### Example 3 - chart object (chart)

Load script and chart expression

#### Overview

Open the Data load editor, and add the load script below to a new tab. The load script contains the same dataset as the previous example. The default `DateFormat` system variable `MM/DD/YYYY` is used.

However, in this example, the unchanged dataset is loaded into the application. The value of the number of days overdue is calculated via a measure in a chart object.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Overdue:
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
  cust_id,book_id,due_date
```

```
  1,4,01/01/2021,
```

```
  2,24,01/10/2021,
```

```
  6,173,01/31/2021,
```

```
  31,281,02/01/2021,
```

```
  86,265,02/10/2021,
```

```
  52,465,06/30/2021,
```

```
  26,537,07/26/2021,
```

```
  92,275,10/31/2021,
```

```
  27,455,11/01/2021,
```

```
  27,46,12/31/2021
```

```
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- due\_date
- book\_id

Create the following measure:

```
=Floor(GMT() - due_date)
```

Results table

due_date	book_id	=Floor(GMT()-due_date)
01/01/2021	4	455
01/10/2021	24	446
01/31/2021	173	425
02/01/2021	281	424
02/10/2021	265	415
06/30/2021	465	275
07/26/2021	537	249
10/31/2021	275	152
11/01/2021	455	151
12/31/2021	46	91

The values in the `days_overdue` field are calculated by finding the difference between the current Greenwich Mean Time, using the `GMT()` function, and the original due date. In order to calculate only the days, the results are rounded off to the nearest whole number using the `Floor()` function.

### hour

This function returns an integer representing the hour when the fraction of the **expression** is interpreted as a time according to the standard number interpretation.

#### Syntax:

```
hour (expression)
```

**Return data type:** integer

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors.

You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Function examples

Example	Result
hour( '09:14:36' )	The text string supplied is implicitly converted to a timestamp as it matches the timestamp format defined in the TimestampFormat variable. The expression returns 9.
hour( '0.5555' )	The expression returns 13 ( Because 0.5555 = 13:19:55 ).

### Example 1 – Variable (script)

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing transactions by timestamp
- The default `Timestamp` system variable (M/D/YYYY h:mm:ss[.fff] TT)

Create a field 'hour', calculating when purchases took place.

#### Load script

```
SET TimestampFormat='M/D/YYYY h:mm:ss[.fff] TT';
```

```
Transactions:
```

```
Load
  *,
  hour(date) as hour
;
Load
*
Inline
[
id,date,amount
9497, '2022-01-05 19:04:57', 47.25,
9498, '2022-01-03 14:21:53', 51.75,
9499, '2022-01-03 05:40:49', 73.53,
9500, '2022-01-04 18:49:38', 15.35,
```

```
9501, '2022-01-01 22:10:22', 31.43,  
9502, '2022-01-05 19:34:46', 13.24,  
9503, '2022-01-04 22:58:34', 74.34,  
9504, '2022-01-06 11:29:38', 50.00,  
9505, '2022-01-02 08:35:54', 36.34,  
9506, '2022-01-06 08:49:09', 74.23  
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- hour

Results table

date	hour
2022-01-01 22:10:22	22
2022-01-02 08:35:54	8
2022-01-03 05:40:49	5
2022-01-03 14:21:53	14
2022-01-04 18:49:38	18
2022-01-04 22:58:34	22
2022-01-05 19:04:57	19
2022-01-05 19:34:46	19
2022-01-06 08:49:09	8
2022-01-06 11:29:38	11

The values in the hour field are created by using the `hour()` function and passing the date as the expression in the preceding load statement.

### Example 2 – Chart object (chart)

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same dataset from the first example.
- The default `timestamp` system variable (`(M/D/YYYY h:mm:ss[.fff] TT)`).

However, in this example, the dataset, unchanged, is loaded into the application. The 'hour' values are calculated via a measure in a chart object.

### Load Script

```
SET TimestampFormat='M/D/YYYY h:mm:ss[.fff] TT';
```

Transactions:

Load

\*

Inline

[

id,date,amount

9497,'2022-01-05 19:04:57',47.25,

9498,'2022-01-03 14:21:53',51.75,

9499,'2022-01-03 05:40:49',73.53,

9500,'2022-01-04 18:49:38',15.35,

9501,'2022-01-01 22:10:22',31.43,

9502,'2022-01-05 19:34:46',13.24,

9503,'2022-01-04 22:58:34',74.34,

9504,'2022-01-06 11:29:38',50.00,

9505,'2022-01-02 08:35:54',36.34,

9506,'2022-01-06 08:49:09',74.23

];

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension: date.

To calculate the 'hour', create the following measure:

```
=hour(date)
```

Results table

due_date	=hour(date)
2022-01-01 22:10:22	22
2022-01-02 08:35:54	8
2022-01-03 05:40:49	5
2022-01-03 14:21:53	14
2022-01-04 18:49:38	18
2022-01-04 22:58:34	22
2022-01-05 19:04:57	19
2022-01-05 19:34:46	19
2022-01-06 08:49:09	8
2022-01-06 11:29:38	11

The values for 'hour' are created by using the `hour()` function and passing the date as the expression in a measure for the chart object.


### inday

This function returns True if **timestamp** lies inside the day containing **base\_timestamp**.

#### Syntax:

```
InDay (timestamp, base_timestamp, period_no[, day_start])
```

Diagram of `inday` function



The `inday()` function uses the `base_timestamp` argument to identify which day the timestamp falls into. The start time of the day is, by default, midnight; but you can change the start time of the day by using the `day_start` argument of the `inday()` function. Once this day is defined, the function will return Boolean results when comparing the prescribed timestamp values to that day.

#### When to use it

The `inday()` function returns a Boolean result. Typically, this type of function will be used as a condition in an `if` expression. This returns an aggregation or calculation dependent on whether a date evaluated occurred in the day of the timestamp in question.

For example, the `inday()` function can be used to identify all equipment manufactured in a given day.

**Return data type:** Boolean

In Qlik Sense, the Boolean true value is represented by -1, and the false value is represented by 0.

#### Arguments

Argument	Description
<code>timestamp</code>	The date and time that you want to compare with <code>base_timestamp</code> .
<code>base_timestamp</code>	Date and time that is used to evaluate the timestamp.
<code>period_no</code>	The day can be offset by <code>period_no</code> . <code>period_no</code> is an integer, where the value 0 indicates the day which contains <code>base_timestamp</code> . Negative values in <code>period_no</code> indicate preceding days and positive values indicate succeeding days.
<code>day_start</code>	If you want to work with days not starting midnight, indicate an offset as a fraction of a day in <code>day_start</code> , For example, 0.125 to denote 3 AM.



### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

Function examples

Example	Result
<code>inday ('01/12/2006 12:23:00 PM', '01/12/2006 12:00:00 AM', 0)</code>	Returns True
<code>inday ('01/12/2006 12:23:00 PM', '01/13/2006 12:00:00 AM', 0)</code>	Returns False
<code>inday ('01/12/2006 12:23:00 PM', '01/12/2006 12:00:00 AM', -1)</code>	Returns False
<code>inday ('01/11/2006 12:23:00 PM', '01/12/2006 12:00:00 AM', -1)</code>	Returns True
<code>inday ('01/12/2006 12:23:00 PM', '01/12/2006 12:00:00 AM', 0, 0.5)</code>	Returns False
<code>inday ('01/12/2006 11:23:00 AM', '01/12/2006 12:00:00 AM', 0, 0.5)</code>	Returns True

### Example 1 – Load statement (script)

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing transactions by timestamp which is loaded into a table called `Transactions`.
- A date field which is provided in the `Timestamp` system variable (`M/D/YYYY h:mm:ss[.fff] TT`) format.
- A preceding load which contains the `inday()` function which is set as the `in_day` field.

#### Load script

```
SET TimestampFormat='M/D/YYYY h:mm:ss[.fff] TT';
```

```
Transactions:
  Load
```

```
*,
    inday(date,'01/05/2022 12:00:00 AM', 0) as in_day
;
Load
*
Inline
[
id,date,amount
9497,'01/01/2022 7:34:46 PM',13.24
9498,'01/01/2022 10:10:22 PM',31.43
9499,'01/02/2022 8:35:54 AM',36.34
9500,'01/03/2022 2:21:53 PM',51.75
9501,'01/04/2022 6:49:38 PM',15.35
9502,'01/04/2022 10:58:34 PM',74.34
9503,'01/05/2022 5:40:49 AM',73.53
9504,'01/05/2022 11:29:38 AM',50.00
9505,'01/05/2022 7:04:57 PM',47.25
9506,'01/06/2022 8:49:09 AM',74.23
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- in\_day

Results table

<b>date</b>	<b>in_day</b>
01/01/2022 7:34:46 PM	0
01/01/2022 10:10:22 PM	0
01/02/2022 8:35:54 AM	0
01/03/2022 2:21:53 PM	0
01/04/2022 6:49:38 PM	0
01/04/2022 10:58:34 PM	0
01/05/2022 5:40:49 AM	-1
01/05/2022 11:29:38 AM	-1
01/05/2022 7:04:57 PM	-1
01/06/2022 8:49:09 AM	0

The `in_day` field is created in the preceding load statement by using the `inday()` function and passing the date field, a hard-coded timestamp for January 5 and a `period_no` of 0 as the function's arguments.

### Example 2 – period\_no

Load script and results

### Overview

The load script uses the same dataset and scenario that were used in the first example.

However, in this example, the task is to calculate whether the transaction date occurred two days before January 5.

### Load script

```
SET TimestampFormat='M/D/YYYY h:mm:ss[.fff] TT';
```

```
Transactions:
```

```
    Load
        *,
        inday(date, '01/05/2022 12:00:00 AM', -2) as in_day
    ;
```

```
Load
```

```
*
```

```
Inline
```

```
[
id,date,amount
9497,'01/01/2022 7:34:46 PM',13.24
9498,'01/01/2022 10:10:22 PM',31.43
9499,'01/02/2022 8:35:54 AM',36.34
9500,'01/03/2022 2:21:53 PM',51.75
9501,'01/04/2022 6:49:38 PM',15.35
9502,'01/04/2022 10:58:34 PM',74.34
9503,'01/05/2022 5:40:49 AM',73.53
9504,'01/05/2022 11:29:38 AM',50.00
9505,'01/05/2022 7:04:57 PM',47.25
9506,'01/06/2022 8:49:09 AM',74.23
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- in\_day

Results table

date	in_day
01/01/2022 7:34:46 PM	0
01/01/2022 10:10:22 PM	0
01/02/2022 8:35:54 AM	0
01/03/2022 2:21:53 PM	-1
01/04/2022 6:49:38 PM	0

date	in_day
01/04/2022 10:58:34 PM	0
01/05/2022 5:40:49 AM	0
01/05/2022 11:29:38 AM	0
01/05/2022 7:04:57 PM	0
01/06/2022 8:49:09 AM	0

In this instance, because a `period_no` of -2 is used as the offset argument in the `inday()` function, the function determines whether each transaction date took place on January 3. This can be verified in the output table where one transaction returns a Boolean result of TRUE.

### Example 3 – day\_start

Load script and results

#### Overview

The load script uses the same dataset and scenario that were used in the previous examples.

However, in this example, the company policy is that the workday begins and ends at 7 AM.

#### Load script

```
SET TimestampFormat='M/D/YYYY h:mm:ss[.fff] TT';
```

```
Transactions:
```

```
Load
    *,
    inday(date, '01/05/2022 12:00:00 AM', 0, 7/24) as in_day
;

Load
*
Inline
[
id,date,amount
9497, '01/01/2022 7:34:46 PM', 13.24
9498, '01/01/2022 10:10:22 PM', 31.43
9499, '01/02/2022 8:35:54 AM', 36.34
9500, '01/03/2022 2:21:53 PM', 51.75
9501, '01/04/2022 6:49:38 PM', 15.35
9502, '01/04/2022 10:58:34 PM', 74.34
9503, '01/05/2022 5:40:49 AM', 73.53
9504, '01/05/2022 11:29:38 AM', 50.00
9505, '01/05/2022 7:04:57 PM', 47.25
9506, '01/06/2022 8:49:09 AM', 74.23
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- in\_day

Results table

date	in_day
01/01/2022 7:34:46 PM	0
01/01/2022 10:10:22 PM	0
01/02/2022 8:35:54 AM	0
01/03/2022 2:21:53 PM	0
01/04/2022 6:49:38 PM	-1
01/04/2022 10:58:34 PM	-1
01/05/2022 5:40:49 AM	-1
01/05/2022 11:29:38 AM	0
01/05/2022 7:04:57 PM	0
01/06/2022 8:49:09 AM	0

Because the `start_day` argument of `7/24`, which is 7 AM, is used in the `inday()` function, the function determines whether each transaction date took place on January 4 from 7 AM and January 5 before 7 AM.

This can be verified in the output table where transactions that take place after 7 AM on January 4 return a Boolean result of TRUE whilst transactions that take place after 7 AM on January 5 return a Boolean result of FALSE.

### Example 4 – Chart object

Load script and chart expression

#### Overview

The load script uses the same dataset and scenario that were used in the previous examples.

However, in this example, the dataset is unchanged and loaded into the application. You will calculate to determine if a transaction takes place on January 5 by creating a measure in a chart object.

#### Load script

Transactions:  
Load

```
*
Inline
[
id,date,amount
9497,'01/01/2022 7:34:46 PM',13.24
9498,'01/01/2022 10:10:22 PM',31.43
9499,'01/02/2022 8:35:54 AM',36.34
9500,'01/03/2022 2:21:53 PM',51.75
9501,'01/04/2022 6:49:38 PM',15.35
9502,'01/04/2022 10:58:34 PM',74.34
9503,'01/05/2022 5:40:49 AM',73.53
9504,'01/05/2022 11:29:38 AM',50.00
9505,'01/05/2022 7:04:57 PM',47.25
9506,'01/06/2022 8:49:09 AM',74.23
];
```

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension:

- date

To calculate whether a transaction takes place on January 5, create the following measure:

```
=inday(date,'01/05/2022 12:00:00 AM',0)
```

Results table

date	inday(date,'01/05/2022 12:00:00 AM',0)
01/01/2022 7:34:46 PM	0
01/01/2022 10:10:22 PM	0
01/02/2022 8:35:54 AM	0
01/03/2022 2:21:53 PM	0
01/04/2022 6:49:38 PM	0
01/04/2022 10:58:34 PM	0
01/05/2022 5:40:49 AM	-1
01/05/2022 11:29:38 AM	-1
01/05/2022 7:04:57 PM	-1
01/06/2022 8:49:09 AM	0

### Example 5 – Scenario

Load script and results

#### Overview

In this example, it has been identified that due to equipment error, products that were manufactured on January 5 were defective. The end user would like a chart object that displays, by date, the status of which products that were manufactured were 'defective' or 'faultless' and the cost of the products manufactured on January 5.

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset which is loaded into a table called 'Products'.
- The table contains the following fields:
  - product ID
  - manufacture time
  - cost price

#### Load script

```
Products:
Load
*
Inline
[
product_id,manufacture_date,cost_price
9497,'01/01/2022 7:34:46 PM',13.24
9498,'01/01/2022 10:10:22 PM',31.43
9499,'01/02/2022 8:35:54 AM',36.34
9500,'01/03/2022 2:21:53 PM',51.75
9501,'01/04/2022 6:49:38 PM',15.35
9502,'01/04/2022 10:58:34 PM',74.34
9503,'01/05/2022 5:40:49 AM',73.53
9504,'01/05/2022 11:29:38 AM',50.00
9505,'01/05/2022 7:04:57 PM',47.25
9506,'01/06/2022 8:49:09 AM',74.23
];
```

#### Results

Load the data and open a sheet. Create a new table and add this field as a dimension:

```
=dayname(manufacture_date)
```

Create the following measures:

- =if(only(InDay(manufacture\_date,makedate(2022,01,05),0)), 'Defective', 'Faultless')
- =sum(cost\_price)

Set the measure's **Number Formatting** to **Money**.

Under **Appearance**, turn off **Totals**.

Results table

dayname (manufacture_ date)	=if(only(InDay(manufacture_date,makedate (2022,01,05),0)), 'Defective', 'Faultless')	=sum (cost_ price)
01/01/2022	Faultless	44.67
01/02/2022	Faultless	36.34
01/03/2022	Faultless	51.75
01/04/2022	Faultless	89.69
01/05/2022	Defective	170.78
01/06/2022	Faultless	74.23

The `inday()` function returns a Boolean value when evaluating the manufacturing dates of each of the products. For any product manufactured on January 5, the `inday()` function returns a Boolean value of TRUE and marks the products as 'Defective'. For any product returning a value of FALSE, and therefore not manufactured on that day, it marks the products as 'Faultless'.

### indaytotime


This function returns True if **timestamp** lies inside the part of day containing **base\_timestamp** up until and including the exact millisecond of **base\_timestamp**.

#### Syntax:

```
InDayToTime (timestamp, base_timestamp, period_no[, day_start])
```

The `indaytotime()` function returns a Boolean result depending on when a timestamp value occurs during the segment of the day. The start boundary of this segment is the start of the day, which is set as midnight by default; the start of the day can be modified by the `day_start` argument of the `indaytotime()` function. The end boundary of the day segment is determined by a `base_timestamp` argument of the function.

Diagram of `indaytotime` function.





### When to use it

The `indaytotime()` function returns a Boolean result. Typically, this type of function will be used as a condition in an `if` expression. The `indaytotime()` function returns an aggregation or calculation depending on if a timestamp occurred in the segment of the day up to and including the time of the base timestamp.

For example, the `indaytotime()` function can be used to show the sum of ticket sales for shows that have taken place so far today.

**Return data type:** Boolean

In Qlik Sense, the Boolean true value is represented by -1, and the false value is represented by 0.

### Arguments

Argument	Description
<code>timestamp</code>	The date and time that you want to compare with <code>base_timestamp</code> .
<code>base_timestamp</code>	Date and time that is used to evaluate the timestamp.
<code>period_no</code>	The day can be offset by <code>period_no</code> . <code>period_no</code> is an integer, where the value 0 indicates the day which contains <code>base_timestamp</code> . Negative values in <code>period_no</code> indicate preceding days and positive values indicate succeeding days.
<code>day_start</code>	(optional) If you want to work with days not starting midnight, indicate an offset as a fraction of a day in <code>day_start</code> . For example, use 0.125 to denote 3 AM.

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Function examples

Example	Result
<code>indaytotime ('01/12/2006 12:23:00 PM', '01/12/2006 11:59:00 PM', 0)</code>	Returns True
<code>indaytotime ('01/12/2006 12:23:00 PM', '01/12/2006 12:00:00 AM', 0)</code>	Returns False
<code>indaytotime '01/11/2006 12:23:00 PM', '01/12/2006 11:59:00 PM', -1)</code>	Returns True

### Example 1 – no additional arguments

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions for the period between January 4 and 5 is loaded into a table called 'Transactions'.
- A date field which is provided in the timestamp system variable (M/D/YYYY h:mm:ss[.fff] TT) format.
- A preceding load which contains the `indaytotime()` function which is set as the 'in\_day\_to\_time', field that determines whether each of the transactions take place before 9:00 AM.

#### Load script

```
SET TimestampFormat='M/D/YYYY h:mm:ss[.fff] TT';
```

Transactions:

```
Load
  *
  ,
  indaytotime(date,'01/05/2022 9:00:00 AM',0) as in_day_to_time
  ;
```

Load

\*

Inline

```
[
id,date,amount
8188,'01/04/2022 3:41:54 AM',25.66
8189,'01/04/2022 4:19:43 AM',87.21
8190,'01/04/2022 4:53:47 AM',53.80
8191,'01/04/2022 8:38:53 AM',69.98
8192,'01/04/2022 10:37:52 AM',57.42
8193,'01/04/2022 1:54:10 PM',45.89
8194,'01/04/2022 5:53:23 PM',82.77
8195,'01/04/2022 8:13:26 PM',36.23
8196,'01/04/2022 10:00:49 PM',76.11
8197,'01/05/2022 7:45:37 AM',82.06
8198,'01/05/2022 8:44:36 AM',17.17
8199,'01/05/2022 11:26:08 AM',40.39
8200,'01/05/2022 6:43:08 PM',37.23
8201,'01/05/2022 10:54:10 PM',88.27
8202,'01/05/2022 11:09:09 PM',95.93
];
```

#### Results


Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- in\_day\_to\_time

Results table

date	in_day_to_time
01/04/2022 3:41:54 AM	0
01/04/2022 4:19:43 AM	0
01/04/2022 04:53:47 AM	0
01/04/2022 8:38:53 AM	0
01/04/2022 10:37:52 AM	0
01/04/2022 1:54:10 PM	0
01/04/2022 5:53:23 PM	0
01/04/2022 8:13:26 PM	0
01/04/2022 10:00:49 PM	0
01/05/2022 7:45:37 AM	-1
01/05/2022 8:44:36 AM	-1
01/05/2022 11:26:08 AM	0
01/05/2022 6:43:08 PM	0
01/05/2022 10:54:10 PM	0
01/05/2022 11:09:09 PM	0

Example 1 diagram of indaytotime function with 9:00 AM limit..



The `in_day_to_time` field is created in the preceding load statement by using the `indaytotime()` function and passing the date field, a hard-coded timestamp for 9:00 AM January 5 and an offset of 0 as the function's arguments. Any transactions that occur between midnight and 9:00 AM on January 5 return TRUE.

### Example 2 – period\_no

Load script and results

### Overview

The load script uses the same dataset and scenario that were used in the first example.

However, in this example, you will calculate whether the transaction date occurred one day before 9:00 AM on January 5.

### Load script

```
SET TimestampFormat='M/D/YYYY h:mm:ss[.fff] TT';

Transactions:
  Load
    *,
    indaytotime(date,'01/05/2022 9:00:00 AM', -1) as in_day_to_time
  ;

Load
*
Inline
[
id,date,amount
8188,'01/04/2022 3:41:54 AM',25.66
8189,'01/04/2022 4:19:43 AM',87.21
8190,'01/04/2022 4:53:47 AM',53.80
8191,'01/04/2022 8:38:53 AM',69.98
8192,'01/04/2022 10:37:52 AM',57.42
8193,'01/04/2022 1:54:10 PM',45.89
8194,'01/04/2022 5:53:23 PM',82.77
8195,'01/04/2022 8:13:26 PM',36.23
8196,'01/04/2022 10:00:49 PM',76.11
8197,'01/05/2022 7:45:37 AM',82.06
8198,'01/05/2022 8:44:36 AM',17.17
8199,'01/05/2022 11:26:08 AM',40.39
8200,'01/05/2022 6:43:08 PM',37.23
8201,'01/05/2022 10:54:10 PM',88.27
8202,'01/05/2022 11:09:09 PM',95.93
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:


- date
- in\_day\_to\_time

Results table

date	in_day_to_time
01/04/2022 3:41:54 AM	-1
01/04/2022 4:19:43 AM	-1

date	in_day_to_time
01/04/2022 04:53:47 AM	-1
01/04/2022 8:38:53 AM	-1
01/04/2022 10:37:52 AM	0
01/04/2022 1:54:10 PM	0
01/04/2022 5:53:23 PM	0
01/04/2022 8:13:26 PM	0
01/04/2022 10:00:49 PM	0
01/05/2022 7:45:37 AM	0
01/05/2022 8:44:36 AM	0
01/05/2022 11:26:08 AM	0
01/05/2022 6:43:08 PM	0
01/05/2022 10:54:10 PM	0
01/05/2022 11:09:09 PM	0

Example 2 diagram of *indaytotime* function with transactions from January 4.



In this example, because an offset of -1 was used as the offset argument in the `indaytotime()` function, the function determines whether each transaction date took place before 9:00 AM on January 4. This can be verified in the output table where a transaction returns a Boolean result of TRUE.

### Example 3 – day\_start

Load script and results

#### Overview

The same dataset and scenario as the first example are used.

However, in this example, the company policy is that the workday begins and ends at 8AM.

### Load script

```
SET TimestampFormat='M/D/YYYY h:mm:ss[.fff] TT';

Transactions:
  Load
    *,
    indaytotime(date,'01/05/2022 9:00:00 AM', 0,8/24) as in_day_to_time
  ;

Load
*
Inline
[
id,date,amount
8188,'01/04/2022 3:41:54 AM',25.66
8189,'01/04/2022 4:19:43 AM',87.21
8190,'01/04/2022 4:53:47 AM',53.80
8191,'01/04/2022 8:38:53 AM',69.98
8192,'01/04/2022 10:37:52 AM',57.42
8193,'01/04/2022 1:54:10 PM',45.89
8194,'01/04/2022 5:53:23 PM',82.77
8195,'01/04/2022 8:13:26 PM',36.23
8196,'01/04/2022 10:00:49 PM',76.11
8197,'01/05/2022 7:45:37 AM',82.06
8198,'01/05/2022 8:44:36 AM',17.17
8199,'01/05/2022 11:26:08 AM',40.39
8200,'01/05/2022 6:43:08 PM',37.23
8201,'01/05/2022 10:54:10 PM',88.27
8202,'01/05/2022 11:09:09 PM',95.93
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:


- date
- in\_day\_to\_time

Results table

date	in_day_to_time
01/04/2022 3:41:54 AM	0
01/04/2022 4:19:43 AM	0
01/04/2022 04:53:47 AM	0
01/04/2022 8:38:53 AM	0
01/04/2022 10:37:52 AM	0
01/04/2022 1:54:10 PM	0
01/04/2022 5:53:23 PM	0

date	in_day_to_time
01/04/2022 8:13:26 PM	0
01/04/2022 10:00:49 PM	0
01/05/2022 7:45:37 AM	0
01/05/2022 8:44:36 AM	-1
01/05/2022 11:26:08 AM	0
01/05/2022 6:43:08 PM	0
01/05/2022 10:54:10 PM	0
01/05/2022 11:09:09 PM	0

Example 3 diagram of `indaytotime` function with transactions from 8:00 AM to 9:00 AM.,



Because the `start_day` argument of 8/24, which equates to 8:00 AM, is used in the `indaytotime()` function, each day begins and ends at 8:00 AM. Therefore, the `indaytotime()` function will return a Boolean result of TRUE for any transaction that took place between 8:00 AM and 9:00 AM on January 5.

### Example 4 – Chart object

Load script and chartexpression

#### Overview

The same dataset and scenario as the first example are used.

However, in this example, the dataset is unchanged and loaded into the application. You will calculate to determine if a transaction takes place on January 5 before 9:00 AM by creating a measure in a chart object.

#### Load script

Transactions:

Load

\*

Inline

[

id,date,amount

```

8188, '01/04/2022 3:41:54 AM', 25.66
8189, '01/04/2022 4:19:43 AM', 87.21
8190, '01/04/2022 4:53:47 AM', 53.80
8191, '01/04/2022 8:38:53 AM', 69.98
8192, '01/04/2022 10:37:52 AM', 57.42
8193, '01/04/2022 1:54:10 PM', 45.89
8194, '01/04/2022 5:53:23 PM', 82.77
8195, '01/04/2022 8:13:26 PM', 36.23
8196, '01/04/2022 10:00:49 PM', 76.11
8197, '01/05/2022 7:45:37 AM', 82.06
8198, '01/05/2022 8:44:36 AM', 17.17
8199, '01/05/2022 11:26:08 AM', 40.39
8200, '01/05/2022 6:43:08 PM', 37.23
8201, '01/05/2022 10:54:10 PM', 88.27
8202, '01/05/2022 11:09:09 PM', 95.93
];

```

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension:

date.

To determine if a transaction takes place on January 5 before 9:00 AM, create the following measure:

```
=indaytotime(date, '01/05/2022 9:00:00 AM', 0)
```

Results table

<b>date</b>	<b>=indaytotime(date, '01/05/2022 9:00:00 AM', 0)</b>
01/04/2022 3:41:54 AM	0
01/04/2022 4:19:43 AM	0
01/04/2022 04:53:47 AM	0
01/04/2022 8:38:53 AM	0
01/04/2022 10:37:52 AM	0
01/04/2022 1:54:10 PM	0
01/04/2022 5:53:23 PM	0
01/04/2022 8:13:26 PM	0
01/04/2022 10:00:49 PM	0
01/05/2022 7:45:37 AM	-1
01/05/2022 8:44:36 AM	-1
01/05/2022 11:26:08 AM	0
01/05/2022 6:43:08 PM	0
01/05/2022 10:54:10 PM	0
01/05/2022 11:09:09 PM	0



The `in_day_to_time` measure is created in the chart object by using the `indaytotime()` function and passing the date field, a hard-coded timestamp for 9:00 AM on January 5 and an offset of 0 as the function's arguments. Any transactions that occur between midnight and 9:00 AM on January 5 return TRUE. This is validated in the results table.

### Example 5 – Scenario

Load script and results

#### Overview

In this example, a dataset containing ticket sales for a local cinema is loaded into a table called `Ticket_Sales`. Today is May 3, 2022 and it is 11:00 AM.

The user would like a KPI chart object to show the revenue earned from all shows that have taken place so far today.

#### Load script

```
SET TimestampFormat='M/D/YYYY h:mm:ss[.fff] TT';
```

```
Ticket_Sales:
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
sale ID, show time, ticket price
```

```
1,05/01/2022 09:30:00 AM,10.50
```

```
2,05/03/2022 05:30:00 PM,21.00
```

```
3,05/03/2022 09:30:00 AM,10.50
```

```
4,05/03/2022 09:30:00 AM,31.50
```

```
5,05/03/2022 09:30:00 AM,10.50
```

```
6,05/03/2022 12:00:00 PM,42.00
```

```
7,05/03/2022 12:00:00 PM,10.50
```

```
8,05/03/2022 05:30:00 PM,42.00
```

```
9,05/03/2022 08:00:00 PM,31.50
```

```
10,05/04/2022 10:30:00 AM,31.50
```

```
11,05/04/2022 12:00:00 PM,10.50
```

```
12,05/04/2022 05:30:00 PM,10.50
```

```
13,05/05/2022 05:30:00 PM,21.00
```

```
14,05/06/2022 12:00:00 PM,21.00
```

```
15,05/07/2022 09:30:00 AM,42.00
```

```
16,05/07/2022 10:30:00 AM,42.00
```

```
17,05/07/2022 10:30:00 AM,10.50
```

```
18,05/07/2022 05:30:00 PM,10.50
```

```
19,05/08/2022 05:30:00 PM,21.00
```

```
20,05/11/2022 09:30:00 AM,10.50
```

```
];
```

#### Results

Do the following:

1. Create a KPI object.
2. Create a measure that will show the sum of all ticket sales for shows that have taken place today so far using the `indaytotime()` function:

```
=sum(if(indaytotime([show time],'05/03/2022 11:00:00 AM'),0),[ticket price],0))
```

3. Create a label for the KPI object, 'Current Revenue'.
4. Set the measure's **Number Formatting** to **Money**.

The sum total of ticket sales up to 11:00 AM on May 3, 2022 is \$52.50.

The `indaytotime()` function returns a Boolean value when comparing the show times of each of the ticket sales to the current time ('05/03/2022 11:00:00 AM'). For any show on May 3 before 11:00 AM, the `indaytotime()` function returns a Boolean value of TRUE and its ticket price will be included in the sum total.

### inlunarweek

This function determines if **timestamp** lies inside the lunar week containing **base\_date**. Lunar weeks in Qlik Sense are defined by counting January 1 as the first day of the week., Apart from the final week of the year, each week will contain exactly seven days.

#### Syntax:

```
InLunarWeek (timestamp, base_date, period_no[, first_week_day])
```

**Return data type:** Boolean



*In Qlik Sense, the Boolean true value is represented by -1, and the false value is represented by 0.*

The `inlunarweek()` function determines which lunar week the `base_date` falls into. It then returns a Boolean result once it has determined whether each timestamp value occurs during the same lunar week as the `base_date`.

*Diagram of `inlunarweek()` function*



### When to use it

The `inLunarweek()` function returns a Boolean result. Typically, this type of function will be used as a condition in an IF expression. This would return an aggregation or calculation dependent on whether the date evaluated occurred during the lunar week in question.

For example, the `inLunarweek()` function can be used to identify all equipment manufactured in a particular lunar week.

#### Arguments

Argument	Description
<b>timestamp</b>	The date that you want to compare with <b>base_date</b> .
<b>base_date</b>	Date that is used to evaluate the lunar week.
<b>period_no</b>	The lunar week can be offset by <b>period_no</b> . <code>period_no</code> is an integer, where the value 0 indicates the lunar week which contains <b>base_date</b> . Negative values in <b>period_no</b> indicate preceding lunar weeks and positive values indicate succeeding lunar weeks.
<b>first_week_day</b>	An offset that may be greater than or less than zero. This changes the beginning of the year by the specified number of days and/or fractions of a day.

#### Function examples

Example	Result
<code>inLunarweek('01/12/2013', '01/14/2013', 0)</code>	Returns <code>TRUE</code> , since the value of <code>timestamp</code> , 01/12/2013, falls in the week 01/08/2013 to 01/14/2013.
<code>inLunarweek('01/12/2013', '01/07/2013', 0)</code>	Returns <code>FALSE</code> , since the <code>base_date</code> 01/07/2013 is in the lunar week defined as 01/01/2013 to 01/07/2013.
<code>inLunarweek('01/12/2013', '01/14/2013', -1)</code>	Returns <code>FALSE</code> . Specifying a value of <code>period_no</code> as -1 shifts the week to the previous week, 01/01/2013 to 01/07/2013.
<code>inLunarweek('01/07/2013', '01/14/2013', -1)</code>	Returns <code>TRUE</code> . In comparison with the previous example, the <code>timestamp</code> is in the following week, after into account the shift backwards.
<code>inLunarweek('01/11/2006', '01/08/2006', 0, 3)</code>	Returns <code>FALSE</code> . Specifying a value of 3 for <code>first_week_day</code> means that the start of the year is calculated from 01/04/2013. Therefore, the value of <code>base_date</code> falls in the first week, and the value of <code>timestamp</code> falls in the week 01/11/2013 to 01/17/2013.

The `inLunarweek()` function is often used in combination with the following functions:

### Related functions

Function	Interaction
<i>lunarweekname</i> (page 865)	This function is used to determine the lunar week number of the year in which an input date occurs.

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Example 1 - No additional arguments

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset of transactions for the month of January, which is loaded into a table called `Transactions`.
- The date field has been provided in the `DateFormat` system variable (MM/DD/YYYY) format.

Create a field, `in_lunar_week`, that determines whether the transactions took place in the same lunar week as January 10.

#### Load script

```
SET DateFormat='MM/DD/YYYY';

Transactions:
  Load
    *,
    inlunarweek(date,'01/10/2022', 0) as in_lunar_week
  ;
Load
*
Inline
[
id,date,amount
```

```
8183, '1/5/2022', 42.32
8184, '1/6/2022', 68.22
8185, '1/7/2022', 15.25
8186, '1/8/2022', 25.26
8187, '1/9/2022', 37.23
8188, '1/10/2022', 37.23
8189, '1/11/2022', 17.17
8190, '1/12/2022', 88.27
8191, '1/13/2022', 57.42
8192, '1/14/2022', 53.80
8193, '1/15/2022', 82.06
8194, '1/16/2022', 87.21
8195, '1/17/2022', 95.93
8196, '1/18/2022', 45.89
8197, '1/19/2022', 36.23
8198, '1/20/2022', 25.66
8199, '1/21/2022', 82.77
8200, '1/22/2022', 69.98
8201, '1/23/2022', 76.11
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:


- date
- in\_lunar\_week

Results table

date	in_lunar_week
1/5/2022	0
1/6/2022	0
1/7/2022	0
1/8/2022	-1
1/9/2022	-1
1/10/2022	-1
1/11/2022	-1
1/12/2022	-1
1/13/2022	-1
1/14/2022	-1
1/15/2022	0
1/16/2022	0
1/17/2022	0

date	in_lunar_week
1/18/2022	0
1/19/2022	0
1/20/2022	0
1/21/2022	0
1/22/2022	0
1/23/2022	0

*inLunarweek()* function, basic example



The `in_lunar_week` field is created in the preceding load statement by using the `inLunarweek()` function, then passing the following as the function's arguments:

- The date field
- A hard-coded date for January 10 as the `base_date`
- `Aperiod_no` of 0

Because lunar weeks begin on January 1, January 10 would fall in the lunar week that begins on January 8 and ends on January 14. Therefore, any transactions that occur between those two dates in January would return a Boolean value of `TRUE`. This is validated in the results table.

## Example 2 - `period_no`

Examples and results:

### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same dataset and scenario as the first example.
- The date field has been provided in the `DateFormat` system variable (MM/DD/YYYY) format.

However, in this example, the task is to create a field, `2_lunar_weeks_later`, that determines whether or not the transactions took place two lunar weeks after January 10.

### Load script

```
SET DateFormat='MM/DD/YYYY';

Transactions:
  Load
    *,
    inlunarweek(date,'01/10/2022', 2) as [2_lunar_weeks_later]
  ;

Load
*
Inline
[
id,date,amount
8183,'1/5/2022',42.32
8184,'1/6/2022',68.22
8185,'1/7/2022',15.25
8186,'1/8/2022',25.26
8187,'1/9/2022',37.23
8188,'1/10/2022',37.23
8189,'1/11/2022',17.17
8190,'1/12/2022',88.27
8191,'1/13/2022',57.42
8192,'1/14/2022',53.80
8193,'1/15/2022',82.06
8194,'1/16/2022',87.21
8195,'1/17/2022',95.93
8196,'1/18/2022',45.89
8197,'1/19/2022',36.23
8198,'1/20/2022',25.66
8199,'1/21/2022',82.77
8200,'1/22/2022',69.98
8201,'1/23/2022',76.11
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:


- date
- 2\_lunar\_weeks\_later

Results table

date	2_lunar_weeks_later
1/5/2022	0
1/6/2022	0
1/7/2022	0
1/8/2022	0

date	2_lunar_weeks_later
1/9/2022	0
1/10/2022	0
1/11/2022	0
1/12/2022	0
1/13/2022	0
1/14/2022	0
1/15/2022	0
1/16/2022	0
1/17/2022	0
1/18/2022	0
1/19/2022	0
1/20/2022	0
1/21/2022	0
1/22/2022	-1
1/23/2022	-1

*inLunarweek()* function, *period\_no* example



In this instance, because a *period\_no* of 2 was used as the offset argument in the *inLunarweek()* function, the function defines the week beginning on January 22 as the lunar week to validate transactions against. Therefore, any transaction that takes place between the January 22 and January 28 will return a Boolean result of `TRUE`.

### Example 3 - first\_week\_day

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.



The load script uses the same dataset and scenario as the first example. However, in the example, we set lunar weeks to begin on January 6.

- The same dataset and scenario as the first example.
- The default `DateFormat` system variable `MM/DD/YYYY` is used.
- A `first_week_day` argument of 5. This sets lunar weeks to begin on January 5.

### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
  Load
    *,
    inlunarweek(date,'01/10/2022', 0,5) as in_lunar_week
  ;
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
```

```
8183,'1/5/2022',42.32
```

```
8184,'1/6/2022',68.22
```

```
8185,'1/7/2022',15.25
```

```
8186,'1/8/2022',25.26
```

```
8187,'1/9/2022',37.23
```

```
8188,'1/10/2022',37.23
```

```
8189,'1/11/2022',17.17
```

```
8190,'1/12/2022',88.27
```

```
8191,'1/13/2022',57.42
```

```
8192,'1/14/2022',53.80
```

```
8193,'1/15/2022',82.06
```

```
8194,'1/16/2022',87.21
```

```
8195,'1/17/2022',95.93
```

```
8196,'1/18/2022',45.89
```

```
8197,'1/19/2022',36.23
```

```
8198,'1/20/2022',25.66
```

```
8199,'1/21/2022',82.77
```

```
8200,'1/22/2022',69.98
```

```
8201,'1/23/2022',76.11
```

```
];
```

### Results


Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- in\_lunar\_week

Results table

date	in_lunar_week
1/5/2022	0
1/6/2022	-1
1/7/2022	-1
1/8/2022	-1
1/9/2022	-1
1/10/2022	-1
1/11/2022	-1
1/12/2022	-1
1/13/2022	0
1/14/2022	0
1/15/2022	0
1/16/2022	0
1/17/2022	0
1/18/2022	0
1/19/2022	0
1/20/2022	0
1/21/2022	0
1/22/2022	0
1/23/2022	0

*inLunarweek()* function, *first\_week\_day* example



In this instance, because the *first\_week\_date* argument of 5 is used in the *inLunarweek()* function, it offsets the start of the lunar week calendar to January 6. Therefore, January 10 falls in the lunar week beginning on January 6 and ending on January 12. Any transaction that falls between these two dates will return a Boolean value of `TRUE`.

### Example 4 - Chart object

Load script and chart expression:

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same dataset and scenario as the first example.
- The date field has been provided in the `DateFormat` system variable (MM/DD/YYYY) format.

However, in this example, the unchanged dataset is loaded into the application. The calculation that determines whether the transactions took place in the same lunar week as January 10 is created as a measure in a chart object of the application.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
```

```
8183,'1/5/2022',42.32
```

```
8184,'1/6/2022',68.22
```

```
8185,'1/7/2022',15.25
```

```
8186,'1/8/2022',25.26
```

```
8187,'1/9/2022',37.23
```

```
8188,'1/10/2022',37.23
```

```
8189,'1/11/2022',17.17
```

```
8190,'1/12/2022',88.27
```

```
8191,'1/13/2022',57.42
```

```
8192,'1/14/2022',53.80
```

```
8193,'1/15/2022',82.06
```

```
8194,'1/16/2022',87.21
```

```
8195,'1/17/2022',95.93
```

```
8196,'1/18/2022',45.89
```

```
8197,'1/19/2022',36.23
```

```
8198,'1/20/2022',25.66
```

```
8199,'1/21/2022',82.77
```

```
8200,'1/22/2022',69.98
```

```
8201,'1/23/2022',76.11
```

```
];
```

#### Results

Load the data and open a sheet. Create a new table and add this field as a dimension: date.

To calculate whether a transaction takes place in the lunar week that contains January 10, create the following measure:

```
= inlunarweek(date, '01/10/2022', 0)
```

Results table

<b>date</b>	<b>=inlunarweek(date,'01/10/2022', 0)</b>
1/5/2022	0
1/6/2022	0
1/7/2022	0
1/8/2022	-1
1/9/2022	-1
1/10/2022	-1
1/11/2022	-1
1/12/2022	-1
1/13/2022	-1
1/14/2022	-1
1/15/2022	0
1/16/2022	0
1/17/2022	0
1/18/2022	0
1/19/2022	0
1/20/2022	0
1/21/2022	0
1/22/2022	0
1/23/2022	0

### Example 5 - Scenario

Load script and chart expression:

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset which is loaded into a table called `Products`.
- Information consisting of product ID, manufacture date, and cost price.

It has been identified that due to equipment error, products that were manufactured in the lunar week that included January 12 were defective. The end user would like a chart object that displays, by lunar week name, the status of whether the products manufactured were 'defective' or 'faultless' and the cost of the products manufactured in that month.

### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
product_id,manufacture_date,cost_price
```

```
8183,'1/5/2022',42.32
```

```
8184,'1/6/2022',68.22
```

```
8185,'1/7/2022',15.25
```

```
8186,'1/8/2022',25.26
```

```
8187,'1/9/2022',37.23
```

```
8188,'1/10/2022',37.23
```

```
8189,'1/11/2022',17.17
```

```
8190,'1/12/2022',88.27
```

```
8191,'1/13/2022',57.42
```

```
8192,'1/14/2022',53.80
```

```
8193,'1/15/2022',82.06
```

```
8194,'1/16/2022',87.21
```

```
8195,'1/17/2022',95.93
```

```
8196,'1/18/2022',45.89
```

```
8197,'1/19/2022',36.23
```

```
8198,'1/20/2022',25.66
```

```
8199,'1/21/2022',82.77
```

```
8200,'1/22/2022',69.98
```

```
8201,'1/23/2022',76.11
```

```
];
```

### Results

#### Do the following:

1. Load the data and open a sheet. Create a new table.
2. Create a dimension to show the month names:  
`=lunarweekname(manufacture_date)`
3. Create a measure to identify which of the products are defective and which are faultless using the `inlunarweek()` function:  
`=if(only(inlunarweek(manufacture_date,makedate(2022,01,12),0)), 'Defective','Faultless')`
4. Create a measure to sum the `cost_price` of the products:

```
=sum(cost_price)
```

5. Set the measure's **Number formatting** to **Money**.
6. Under **Appearance**, turn off **Totals**.

Results table

lunarweekname (manufacture_date)	=if(only(inlunarweek(manufacture_date,makedate(2022,01,12),0)), 'Defective','Faultless')	sum(cost_price)
2022/01	Faultless	\$125.79
2022/02	Defective	\$316.38
2022/03	Faultless	\$455.75
2022/04	Faultless	\$146.09

The `inlunarweek()` function returns a Boolean value when evaluating the manufacturing dates of each of the products. For any product manufactured in the lunar week that contains January 10, the `inlunarweek()` function returns a Boolean value of `TRUE` and marks the products as 'Defective'. For any product returning a value of `FALSE`, and therefore not manufactured in that week, it marks the products as 'Faultless'.

## inlunarweektodate

This function finds if **timestamp** lies inside the part of the lunar week up to and including the last millisecond of **base\_date**. Lunar weeks in Qlik Sense are defined by counting January 1 as the first day of the week and, apart from the final week of the year, will contain exactly seven days.

### Syntax:


```
InLunarWeekToDate (timestamp, base_date, period_no [, first_week_day])
```

**Return data type:** Boolean



*In Qlik Sense, the Boolean true value is represented by -1, and the false value is represented by 0.*

Example diagram of `inlunarweektodate()` function



## 8 Script and chart functions

The `inlunarweektoday()` function acts as the end point of the lunar week. In contrast, the `inlunarweek()` function, determines which lunar week the `base_date` falls into. For example, if the `base_date` were January 5, any timestamp between January 1 and January 5 would return a Boolean result of `TRUE`, while dates on January 6 and 7, and later, would return a Boolean result of `FALSE`.

### Arguments

Argument	Description
<b>timestamp</b>	The date that you want to compare with <b>base_date</b> .
<b>base_date</b>	Date that is used to evaluate the lunar week.
<b>period_no</b>	The lunar week can be offset by <b>period_no</b> . <code>period_no</code> is an integer, where the value 0 indicates the lunar week which contains <b>base_date</b> . Negative values in <b>period_no</b> indicate preceding lunar weeks and positive values indicate succeeding lunar weeks.
<b>first_week_day</b>	An offset that may be greater than or less than zero. This changes the beginning of the year by the specified number of days and/or fractions of a day.

### When to use it

The `inlunarweektoday()` function returns a Boolean result. Typically, this type of function will be used as a condition in an IF expression. The `inlunarweektoday()` function would be used when the user would like the calculation to return an aggregation or calculation, dependent on whether the evaluated date occurred during a particular segment of the week in question.

For example, the `inlunarweektoday()` function can be used to identify all equipment manufactured in a particular week up to and including a particular date.

### Function examples

Example	Result
<code>inlunarweektoday('01/12/2013', '01/13/2013', 0)</code>	Returns <code>TRUE</code> , since the value of the <code>timestamp</code> , 01/12/2013, falls in the part of the week 01/08/2013 to 01/13/2013.
<code>inlunarweektoday('01/12/2013', '01/11/2013', 0)</code>	Returns <code>FALSE</code> , since the value of the <code>timestamp</code> is later than the value of <code>base_date</code> , even though the two dates are in the same lunar week before 01/12/2012.
<code>inlunarweektoday('01/12/2006', '01/05/2006', 1)</code>	Returns <code>TRUE</code> . Specifying a value of 1 for <code>period_no</code> shifts the <code>base_date</code> forward one week, so the value of <code>timestamp</code> falls in the part of the lunar week.

The `inlunarweektoday()` function is often used in combination with the following functions:

### Related functions

Function	Interaction
<i>lunarweekname</i> (page 865)	This function is used to determine the lunar week number of the year in which an input date occurs.

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Example 1 - No additional arguments

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions for the month of January, which is loaded into a table called `Transactions`. The default `DateFormat` system variable `MM/DD/YYYY` is used.
- Create a field `in_lunar_week_to_date`, that determines which transactions took place in lunar week to date of January 10.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
    Load
        *,
        inlunarweektoday(date,'01/10/2022', 0) as in_lunar_week_to_date
    ;

Load
*
Inline
[
id,date,amount
8188,'1/10/2022',37.23
8189,'1/17/2022',17.17
8190,'1/26/2022',88.27
8191,'1/12/2022',57.42
8192,'1/19/2022',53.80
8193,'1/21/2022',82.06
8194,'1/1/2022',40.39
8195,'1/27/2022',87.21
```



```
8196, '1/11/2022', 95.93
8197, '1/29/2022', 45.89
8198, '1/31/2022', 36.23
8199, '1/18/2022', 25.66
8200, '1/23/2022', 82.77
8201, '1/15/2022', 69.98
8202, '1/4/2022', 76.11
];
```

### Results


Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- in\_lunar\_week\_to\_date

Results table

date	in_lunar_week_to_date
1/1/2022	0
1/4/2022	0
1/10/2022	-1
1/11/2022	0
1/12/2022	0
1/15/2022	0
1/17/2022	0
1/18/2022	0
1/19/2022	0
1/21/2022	0
1/23/2022	0
1/26/2022	0
1/27/2022	0
1/29/2022	0
1/31/2022	0

*inlunarweektodate()* function, no additional arguments



The `in_lunar_week_to_date` field is created in the preceding load statement by using the `inlunarweektodate()` function and passing the `date` field, a hard-coded date for January 10 as our `base_date`, and an offset of 0 as the function's arguments.

Because lunar weeks begin on January 1, January 10 would fall in the lunar week that begins on January 8; and because we are using the `inlunarweektodate()` function, that lunar week would then end on the 10th. Therefore, any transactions that occur between those two dates in January would return a Boolean value of `TRUE`. This is validated in the results table.

### Example 2 - period\_no

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains the same dataset and scenario as the first example. However, in this example, the task is to create a field, `2_lunar_weeks_later`, that determines whether or not the transactions took place two weeks after the lunar week to date of January 1.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
Transactions:
  Load
    *,
    inlunarweektodate(date,'01/10/2022', 2) as [2_lunar_weeks_later]
  ;
Load
*
Inline
[
id,date,amount
8188,'1/10/2022',37.23
8189,'1/17/2022',17.17
8190,'1/26/2022',88.27
8191,'1/12/2022',57.42
8192,'1/19/2022',53.80
8193,'1/21/2022',82.06
8194,'1/1/2022',40.39
8195,'1/27/2022',87.21
```

```
8196, '1/11/2022', 95.93
8197, '1/29/2022', 45.89
8198, '1/31/2022', 36.23
8199, '1/18/2022', 25.66
8200, '1/23/2022', 82.77
8201, '1/15/2022', 69.98
8202, '1/4/2022', 76.11
];
```

### Results


Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- 2\_lunar\_weeks\_later

Results table

date	2_lunar_weeks_later
1/1/2022	0
1/4/2022	0
1/10/2022	0
1/11/2022	0
1/12/2022	0
1/15/2022	0
1/17/2022	0
1/18/2022	0
1/19/2022	0
1/21/2022	0
1/23/2022	-1
1/26/2022	0
1/27/2022	0
1/29/2022	0
1/31/2022	0

*inlunarweektodate()* function, *period\_no* example



In this instance, the `inlunarweektodate()` function determines that the lunar week up to January 10 equates to three days (January 8, 9, 10). Since a `period_no` of 2 was used as the offset argument, this lunar week is shifted by 14 days. Therefore, this defines that three-day lunar week to include January 22, 23, and 24. Any transaction that takes place between January 22 and January 24 will return a Boolean result of `TRUE`.

### Example 3 - first\_week\_day

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same dataset and scenario as the first example.
- The default `DateFormat` system variable `MM/DD/YYYY` is used.
- A `first_week_date` argument of 3. This sets lunar weeks to begin on January 3.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

Transactions:

```
Load
  *,
  inlunarweek(date,'01/10/2022', 0,3) as in_lunar_week_to_date
;
```

Load

\*

Inline

```
[
id,date,amount
8188,'1/10/2022',37.23
8189,'1/17/2022',17.17
8190,'1/26/2022',88.27
8191,'1/12/2022',57.42
8192,'1/19/2022',53.80
8193,'1/21/2022',82.06
8194,'1/1/2022',40.39
```

```
8195, '1/27/2022', 87.21
8196, '1/11/2022', 95.93
8197, '1/29/2022', 45.89
8198, '1/31/2022', 36.23
8199, '1/18/2022', 25.66
8200, '1/23/2022', 82.77
8201, '1/15/2022', 69.98
8202, '1/4/2022', 76.11
];
```

### Results


Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- in\_lunar\_week\_to\_date

Results table

date	in_lunar_week_to_date
1/1/2022	0
1/4/2022	-1
1/10/2022	-1
1/11/2022	0
1/12/2022	0
1/15/2022	0
1/17/2022	0
1/18/2022	0
1/19/2022	0
1/21/2022	0
1/23/2022	0
1/26/2022	0
1/27/2022	0
1/29/2022	0
1/31/2022	0

*inLunarweekToDate() function, first\_week\_day example*



In this instance, because the `first_week_date` argument of 3 is used in the `inLunarweek()` function, the first lunar week will be from January 3 to January 10. Because January 10 is also the `base_date`, any transaction that falls between these two dates will return a Boolean value of `TRUE`.

### Example 4 - Chart object example

Load script and chart expression

#### Overview

Open the Data load editor, and add the load script below to a new tab.

The load script contains the same dataset and scenario as the first example.

However, in this example, the unchanged dataset is loaded into the application. The calculation that determines whether the transactions took place in the lunar week up to January 10 is created as a measure in a chart object of the application.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
```

```
8188,'1/10/2022',37.23
```

```
8189,'1/17/2022',17.17
```

```
8190,'1/26/2022',88.27
```

```
8191,'1/12/2022',57.42
```

```
8192,'1/19/2022',53.80
```

```
8193,'1/21/2022',82.06
```

```
8194,'1/1/2022',40.39
```

```
8195,'1/27/2022',87.21
```

```
8196,'1/11/2022',95.93
```

```
8197,'1/29/2022',45.89
```

```
8198,'1/31/2022',36.23
```

```
8199,'1/18/2022',25.66
```

```
8200, '1/23/2022', 82.77
8201, '1/15/2022', 69.98
8202, '1/4/2022', 76.11
];
```

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension: date.


Create the following measure:

```
=inlunarweektodate(date, '01/10/2022', 0)
```

Results table

date	=inlunarweektodate(date, '01/10/2022', 0)
1/1/2022	0
1/4/2022	0
1/10/2022	-1
1/11/2022	0
1/12/2022	0
1/15/2022	0
1/17/2022	0
1/18/2022	0
1/19/2022	0
1/21/2022	0
1/23/2022	0
1/26/2022	0
1/27/2022	0
1/29/2022	0
1/31/2022	0

*inlunarweektodate()* function, chart object example



The `in_lunar_week_to_date` measure is created in the chart object by using the `inlunarweektodate()` function and passing the date field, a hard-coded date for January 10 as our `base_date`, and an offset of 0 as the function's arguments.

Because lunar weeks begin on January 1, January 10 would fall in the lunar week that begins on January 8. Additionally, since we are using the `inlunarweektodate()` function, that lunar week would then terminate on the 10th. Therefore, any transactions that occur between those two dates in January would return a Boolean value of `TRUE`. This is validated in the results table.

### Example 5 - Scenario

Load script and chart expressions

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset which is loaded into a table called `Products`.
- Information consisting of product ID, manufacture date, and cost price.

It has been identified that due to equipment error, products that were manufactured in the lunar week of January 12 were defective. The issue was resolved on January 13. The end user would like a chart object that displays, by week, the status of whether the products manufactured 'defective' or 'faultless' and the cost of the products manufactured in that week.

#### Load script

```
SET TimestampFormat='M/D/YYYY h:mm:ss[.fff]';
```

```
Products:
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
product_id,manufacture_date,cost_price
```

```
8188, '01/02/2022 12:22:06', 37.23
```

```
8189, '01/05/2022 01:02:30', 17.17
```

```
8190, '01/06/2022 15:36:20', 88.27
```

```
8191, '01/08/2022 10:58:35', 57.42
```

```
8192, '01/09/2022 08:53:32', 53.80
```

```
8193, '01/10/2022 21:13:01', 82.06
```

```
8194, '01/11/2022 00:57:13', 40.39
```

```
8195, '01/12/2022 09:26:02', 87.21
```

```
8196, '01/13/2022 15:05:09', 95.93
```

```
8197, '01/14/2022 18:44:57', 45.89
```

```
8198, '01/15/2022 06:10:46', 36.23
```

```
8199, '01/16/2022 06:39:27', 25.66
```

```
8200, '01/17/2022 10:44:16', 82.77
```

```
8201, '01/18/2022 18:48:17', 69.98
```

```
8202, '01/26/2022 04:36:03', 76.11
```



```
8203, '01/27/2022 08:07:49', 25.12
8204, '01/28/2022 12:24:29', 46.23
8205, '01/30/2022 11:56:56', 84.21
8206, '01/30/2022 14:40:19', 96.24
8207, '01/31/2022 05:28:21', 67.67
];
```

### Results

#### Do the following:

1. Load the data and open a sheet. Create a new table.
2. Create a dimension to show the week names:  
=weekname(manufacture\_date)
3. Next, create a dimension which uses the inLunarWeekToDate() function to identify which of the products are defective and which are faultless:  
=if(inLunarWeekToDate(manufacture\_date,makedate(2022,01,12),0),'Defective','Faultless')
4. Create a measure to sum the cost\_price of the products:  
=sum(cost\_price)
5. Set the measure's **Number formatting** to **Money**.

Results table

=lunarweekname (manufacture_date)	=if(InLunarWeekToDate(manufacture_date,makedate(2022,01,12),0),'Defective','Faultless')	=Sum(cost_price)
2022/01	Faultless	\$142.67
2022/02	Defective	\$320.88
2022/02	Faultless	\$141.82
2022/03	Faultless	\$214.64
2022/04	Faultless	\$147.46
2022/05	Faultless	\$248.12

The inLunarWeekToDate() function returns a Boolean value when evaluating the manufacturing dates of each of the products. For those that return a Boolean value of TRUE, it marks the products as 'defective'. For any product returning a value of FALSE, and therefore not made in the lunar week up to January 12, it marks the products as 'Faultless'.


### inmonth

This function returns True if **timestamp** lies inside the month containing **base\_date**.

#### Syntax:

```
InMonth (timestamp, base_date, period_no)
```

Diagram of `inmonth` function.



In other words, the `inmonth()` function determines if a set of dates fall into this month and returns a Boolean value based on a `base_date` that identifies the month.

### When to use it

The `inmonth()` function returns a Boolean result. Typically, this type of function will be used as a condition in an `if` expression. This returns an aggregation or calculation depending on whether a date occurred in the month, including the date in question.

For example, the `inmonth()` function can be used to identify all equipment manufactured in a specific month.

**Return data type:** Boolean

In Qlik Sense, the Boolean true value is represented by -1, and the false value is represented by 0.

### Arguments

Argument	Description
<code>timestamp</code>	The date that you want to compare with <code>base_date</code> .
<code>base_date</code>	Date that is used to evaluate the month. It is important to note that the <code>base_date</code> can be any day within a month.
<code>period_no</code>	The month can be offset by <code>period_no</code> . <code>period_no</code> is an integer, where the value 0 indicates the month which contains <code>base_date</code> . Negative values in <code>period_no</code> indicate preceding months and positive values indicate succeeding months.

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Function examples

Example	Result
<code>inmonth ('25/01/2013', '01/01/2013', 0)</code>	Returns True
<code>inmonth('25/01/2013', '23/04/2013', 0)</code>	Returns False
<code>inmonth ('25/01/2013', '01/01/2013', -1)</code>	Returns False
<code>inmonth ('25/12/2012', '17/01/2013', -1)</code>	Returns True

### Example 1 – No additional arguments

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions for the first half of 2022.
- A preceding load with an additional variable 'in\_month', that determines whether transactions took place in April.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
Load
*
inmonth(date,'04/01/2022', 0) as in_month
;
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
```

```
8188,'1/10/2022',37.23
```

```
8189,'1/14/2022',17.17
```

```
8190,'1/20/2022',88.27
```

```
8191,'1/22/2022',57.42
```

```
8192,'2/1/2022',53.80
```

```
8193,'2/2/2022',82.06
```

```
8194,'2/20/2022',40.39
```

```
8195,'4/11/2022',87.21
```

```
8196,'4/13/2022',95.93
```

```
8197,'4/15/2022',45.89
```

```
8198,'4/25/2022',36.23
```

```
8199,'5/20/2022',25.66
```

```
8200,'5/22/2022',82.77
```

```
8201, '6/19/2022', 69.98
8202, '6/22/2022', 76.11
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- in\_month

Function examples

date	in_month
1/10/2022	0
1/14/2022	0
1/20/2022	0
1/22/2022	0
2/1/2022	0
2/2/2022	0
2/20/2022	0
4/11/2022	-1
4/13/2022	-1
4/15/2022	-1
4/25/2022	-1
5/20/2022	0
5/22/2022	0
6/19/2022	0
6/22/2022	0

The 'in\_month' field is created in the preceding load statement by using the `inmonth()` function and passing the date field, a hard-coded date of April 1, as our `base_date` and a `period_no` of 0 as the function's arguments.

The `base_date` identifies the month that will return a Boolean result of TRUE. Therefore, all transactions that occurred in April return TRUE which is validated in the results table.

### Example 2 – period\_no

Load script and results

### Overview

The same dataset and scenario from the first example are used.

However, in this example, you will create a field, '2\_months\_prior', that determines whether the transactions took place two months before April.

### Load script

```
SET DateFormat='MM/DD/YYYY';

Transactions:
Load
    *,
    inmonth(date,'04/01/2022', -2) as [2_months_prior]
Inline
[
id,date,amount
8188,'1/10/2022',37.23
8189,'1/14/2022',17.17
8190,'1/20/2022',88.27
8191,'1/22/2022',57.42
8192,'2/1/2022',53.80
8193,'2/2/2022',82.06
8194,'2/20/2022',40.39
8195,'4/11/2022',87.21
8196,'4/13/2022',95.93
8197,'4/15/2022',45.89
8198,'4/25/2022',36.23
8199,'5/20/2022',25.66
8200,'5/22/2022',82.77
8201,'6/19/2022',69.98
8202,'6/22/2022',76.11
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- 2\_months\_prior

#### Function examples

<b>date</b>	<b>2_months_prior</b>
1/10/2022	0
1/14/2022	0
1/20/2022	0
1/22/2022	0
2/1/2022	-1
2/2/2022	-1
2/20/2022	-1

<b>date</b>	<b>2_months_prior</b>
4/11/2022	0
4/13/2022	0
4/15/2022	0
4/25/2022	0
5/20/2022	0
5/22/2022	0
6/19/2022	0
6/22/2022	0

Using -2 as the `period_no` argument in the `inmonth()` function shifts the month defined by the `base_date` argument two months prior. In this example it changes the defined month from April to February.

Therefore, any transaction that takes place in February will return a Boolean result of TRUE.

### Example 3 – Chart object

Load script and chartexpression

#### Overview

The same dataset and scenario from the previous examples are used.

However, in this example, the dataset is unchanged and loaded into the application. The calculation that determines whether transactions took place in April is created as a measure in a chart object of the application.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
```

```
8188,'1/10/2022',37.23
```

```
8189,'1/14/2022',17.17
```

```
8190,'1/20/2022',88.27
```

```
8191,'1/22/2022',57.42
```

```
8192,'2/1/2022',53.80
```

```
8193,'2/2/2022',82.06
```

```
8194,'2/20/2022',40.39
```

```
8195,'4/11/2022',87.21
```

```
8196,'4/13/2022',95.93
```

```
8197,'4/15/2022',45.89
```

```
8198, '4/25/2022', 36.23
8199, '5/20/2022', 25.66
8200, '5/22/2022', 82.77
8201, '6/19/2022', 69.98
8202, '6/22/2022', 76.11
];
```

### Chart object

Load the data and open a sheet. Create a new table and add this field as a dimension:

date

To calculate whether a transaction takes place in April, create the following measure:

```
=inmonth(date, '04/01/2022', 0)
```

### Results

	Function examples
date	=inmonth(date, '04/01/2022', 0)
1/10/2022	0
1/14/2022	0
1/20/2022	0
1/22/2022	0
2/1/2022	0
2/2/2022	0
2/20/2022	0
4/11/2022	-1
4/13/2022	-1
4/15/2022	-1
4/25/2022	-1
5/20/2022	0
5/22/2022	0
6/19/2022	0
6/22/2022	0

### Example 4 – Scenario

Load script and results

#### Overview

In this example, a dataset is loaded into a table called 'products'. The table contains the following fields:

- Product ID
- Manufacture date
- Cost price

Due to equipment error, products that were manufactured in the month of July 2022 were defective. The issue was resolved on July 27, 2022.

The end user would like a chart that displays, by month, the status of products that were manufactured as 'defective' (Boolean TRUE) or 'faultless' (Boolean FALSE) and the cost of the products manufactured in that month.

### Load script

Products:

Load

\*

Inline

[

product\_id,manufacture\_date,cost\_price

8188,'1/19/2022',37.23

8189,'1/7/2022',17.17

8190,'2/28/2022',88.27

8191,'2/5/2022',57.42

8192,'3/16/2022',53.80

8193,'4/1/2022',82.06

8194,'5/7/2022',40.39

8195,'5/16/2022',87.21

8196,'6/15/2022',95.93

8197,'6/26/2022',45.89

8198,'7/9/2022',36.23

8199,'7/22/2022',25.66

8200,'7/23/2022',82.77

8201,'7/27/2022',69.98

8202,'8/2/2022',76.11

8203,'8/8/2022',25.12

8204,'8/19/2022',46.23

8205,'9/26/2022',84.21

8206,'10/14/2022',96.24

8207,'10/29/2022',67.67

];

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension:

=monthname(manufacture\_date)

Create the following measures

- =sum(cost\_price)
- =if(only(inmonth(manufacture\_date,makedate(2022,07,01),0)),'Defective','Faultless')



1. Set the measure's **Number Formatting** to **Money**.
2. Under **Appearance**, turn off **Totals**.

Results table

monthname (manufacture_date)	=if(only(inmonth(manufacture_date,makedate(2022,07,01),0)),'Defective','Faultless')	sum(cost_price)
Jan 2022	Faultless	\$54.40
Feb 2022	Faultless	\$145.69
Mar 2022	Faultless	\$53.80
Apr 2022	Faultless	\$82.06
May 2022	Faultless	\$127.60
Jun 2022	Faultless	\$141.82
Jul 2022	Defective	\$214.64
Aug 2022	Faultless	\$147.46
Sep 2022	Faultless	\$84.21
Oct 2022	Faultless	\$163.91

The `inmonth()` function returns a Boolean value when evaluating the manufacturing dates of each of the products. For any product manufactured in July 2022, the `inmonth()` function returns a Boolean value of True and marks the products as 'Defective'. For any product returning a value of False, and therefore not manufactured in July, it marks the products as 'Faultless'.

## inmonths

This function finds if a timestamp falls within the same month, bi-month, quarter, four-month period, or half-year as a base date. It is also possible to find if the timestamp falls within a previous or following time period.


### Syntax:

```
InMonths (n_months, timestamp, base_date, period_no [, first_month_of_year])
```

**Return data type:** Boolean

In Qlik Sense, the Boolean true value is represented by -1, and the false value is represented by 0.

Diagram of `inmonths()` function



The `inmonths()` function divides the year into segments based on the `n_months` argument provided. It then determines whether each timestamp evaluated falls into the same segment as the `base_date` argument. If, however, a `period_no` argument is provided, the function determines whether the timestamps fall into a previous or following period from the `base_date`.

The following segments of the year are available in the function as `n_month` arguments.

`n_month` arguments

Period	Number of months
month	1
bi-month	2
quarter	3
four months	4
half-year	6

### When to use it

The `inmonths()` function returns a Boolean result. Typically, this type of function will be used as a condition in an `if` expression. By using the `inmonths()` function, you can select the period that you want to be evaluated. For example, letting the user identify products manufactured in the month, quarter, or half-year of a certain period.

**Return data type:** Boolean

In Qlik Sense, the Boolean true value is represented by -1, and the false value is represented by 0.

Arguments

Argument	Description
<code>n_months</code>	The number of months that defines the period. An integer or expression that resolves to an integer that must be one of: 1 (equivalent to the <code>inmonth()</code> function), 2 (bi-month), 3 (equivalent to the <code>inquarter()</code> function), 4 (four-month period), or 6 (half year).

Argument	Description
<b>timestamp</b>	The date that you want to compare with <b>base_date</b> .
<b>base_date</b>	Date that is used to evaluate the period.
<b>period_no</b>	The period can be offset by <b>period_no</b> , an integer, or expression resolving to an integer, where the value 0 indicates the period that contains <b>base_date</b> . Negative values in <b>period_no</b> indicate preceding periods and positive values indicate succeeding periods.
<b>first_month_of_year</b>	If you want to work with (fiscal) years not starting in January, indicate a value between 2 and 12 in <b>first_month_of_year</b> .

You can use the following values to set the first month of year in the `first_month_of_year` argument:

first\_month\_of\_year values

Month	Value
February	2
March	3
April	4
May	5
June	6
July	7
August	8
September	9
October	10
November	11
December	12

## Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Function examples

Example	Result
<code>inmonths(4, '01/25/2013', '04/25/2013', 0)</code>	Returns TRUE. Because the value of timestamp, 01/25/2013, lies within the four-month period 01/01/2013 to 04/30/2013, in which the value of base_date, 04/25/2013 lies.
<code>inmonths(4, '05/25/2013', '04/25/2013', 0)</code>	Returns FALSE. Because 05/25/2013 is outside the same period as the previous example.
<code>inmonths(4, '11/25/2012', '02/01/2013', -1)</code>	Returns TRUE. Because the value of period_no, -1, shifts the search period back one period of four months (the value of n-months), which makes the search period 09/01/2012 to 12/31/2012.
<code>inmonths(4, '05/25/2006', '03/01/2006', 0, 3)</code>	Returns TRUE. Because the value of first_month_of_year is set to 3, which makes the search period 03/01/2006 to 07/30/2006 instead of 01/01/2006 to 04/30/2006.

### Example 1 - No additional arguments

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions for 2022 is loaded into a table called 'Transactions'.
- A preceding load with an additional variable 'in\_months', that determines which transactions took place in the same quarter as May 15, 2022.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
  Load
    *,
    inmonths(3,date,'05/15/2022', 0) as in_months
  ;
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
```

```
8188,'2/19/2022',37.23
```

```
8189,'3/7/2022',17.17
```

```
8190,'3/30/2022',88.27
```

```
8191,'4/5/2022',57.42
```

```
8192, '4/16/2022', 53.80
8193, '5/1/2022', 82.06
8194, '5/7/2022', 40.39
8195, '5/22/2022', 87.21
8196, '6/15/2022', 95.93
8197, '6/26/2022', 45.89
8198, '7/9/2022', 36.23
8199, '7/22/2022', 25.66
8200, '7/23/2022', 82.77
8201, '7/27/2022', 69.98
8202, '8/2/2022', 76.11
8203, '8/8/2022', 25.12
8204, '8/19/2022', 46.23
8205, '9/26/2022', 84.21
8206, '10/14/2022', 96.24
8207, '10/29/2022', 67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- in\_months


Results table

date	in_months
2/19/2022	0
3/7/2022	0
3/30/2022	0
4/5/2022	-1
4/16/2022	-1
5/1/2022	-1
5/7/2022	-1
5/22/2022	-1
6/15/2022	-1
6/26/2022	-1
7/9/2022	0
7/22/2022	0
7/23/2022	0
7/27/2022	0

date	in_months
8/2/2022	0
8/8/2022	0
8/19/2022	0
9/26/2022	0
10/14/2022	0
10/29/2022	0

The 'in\_months' field is created in the preceding load statement by using the `inmonths()` function. The first argument provided is 3 which divides the year into quarter segments. The second argument identifies which field is being evaluated, the date field in this example. The third argument is a hard-coded date for the for May 15 which is the `base_date` and a `period_no` of 0 is the final argument.

*Diagram of `inmonths()` function with quarter segments*



May falls into the second quarter of the year. Therefore, any transaction that occurs between April 1 and June 30 will return a Boolean result of TRUE. This is validated in the results table.

## Example 2 - `period_no`

Load script and results

### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions for 2022 is loaded into a table called 'Transactions'.
- A preceding load with an additional variable, 'previous\_quarter', that determines whether transactions took place in the quarter before May 15, 2022.

### Load script

```
SET DateFormat='MM/DD/YYYY';
```

Transactions:

```
Load
    *,
    inmonths(3,date,'05/15/2022', -1) as previous_quarter
;

Load
*
Inline
[
id,date,amount
8188,'2/19/2022',37.23
8189,'3/7/2022',17.17
8190,'3/30/2022',88.27
8191,'4/5/2022',57.42
8192,'4/16/2022',53.80
8193,'5/1/2022',82.06
8194,'5/7/2022',40.39
8195,'5/22/2022',87.21
8196,'6/15/2022',95.93
8197,'6/26/2022',45.89
8198,'7/9/2022',36.23
8199,'7/22/2022',25.66
8200,'7/23/2022',82.77
8201,'7/27/2022',69.98
8202,'8/2/2022',76.11
8203,'8/8/2022',25.12
8204,'8/19/2022',46.23
8205,'9/26/2022',84.21
8206,'10/14/2022',96.24
8207,'10/29/2022',67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- previous\_quarter


Results table

date	previous quarter
2/19/2022	-1
3/7/2022	-1
3/30/2022	-1
4/5/2022	0
4/16/2022	0
5/1/2022	0

date	previous quarter
5/7/2022	0
5/22/2022	0
6/15/2022	0
6/26/2022	0
7/9/2022	0
7/22/2022	0
7/23/2022	0
7/27/2022	0
8/2/2022	0
8/8/2022	0
8/19/2022	0
9/26/2022	0
10/14/2022	0
10/29/2022	0

The function evaluates whether transactions occurred in the first quarter of the year by using -1 as the `period_no` argument in the `inmonths()` function. May 15 is the `base_date` and falls into the second quarter of the year (April-June).

*Diagram of `inmonths()` function with quarter segments and the `period_no` set to -1*



Therefore, any transaction that occurs between January and March will return a Boolean result of TRUE.



### Example 3 - first\_month\_of\_year

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions for 2022 is loaded into a table called 'transactions'.
- A preceding load with an additional variable, 'in\_months', that determines which transactions took place in the same quarter as May 15, 2022.

In this example, the organizational policy is for March to be the first month of the financial year.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
  Load
    *,
    inmonths(3,date,'05/15/2022', 0, 3) as in_months
  ;
```

```
Load
```

```
*
```

```
Inline
```

```
[
id,date,amount
8188,'2/19/2022',37.23
8189,'3/7/2022',17.17
8190,'3/30/2022',88.27
8191,'4/5/2022',57.42
8192,'4/16/2022',53.80
8193,'5/1/2022',82.06
8194,'5/7/2022',40.39
8195,'5/22/2022',87.21
8196,'6/15/2022',95.93
8197,'6/26/2022',45.89
8198,'7/9/2022',36.23
8199,'7/22/2022',25.66
8200,'7/23/2022',82.77
8201,'7/27/2022',69.98
8202,'8/2/2022',76.11
8203,'8/8/2022',25.12
8204,'8/19/2022',46.23
8205,'9/26/2022',84.21
8206,'10/14/2022',96.24
8207,'10/29/2022',67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:


- date
- in\_months

Results table

date	in_months
2/19/2022	0
3/7/2022	-1
3/30/2022	-1
4/5/2022	-1
4/16/2022	-1
5/1/2022	-1
5/7/2022	-1
5/22/2022	-1
6/15/2022	0
6/26/2022	0
7/9/2022	0
7/22/2022	0
7/23/2022	0
7/27/2022	0
8/2/2022	0
8/8/2022	0
8/19/2022	0
9/26/2022	0
10/14/2022	0
10/29/2022	0

By using 3 as the `first_month_of_year` argument in the `inmonths()` function, the function begins the year on March 1. The `inmonths()` function then divides the year into quarters: Mar-May, Jun-Aug, Sep-Nov, Dec-Feb. Therefore, May 15 falls into the first quarter of the year (March-May).

Diagram of `inmonths()` function with March set as first month of the year



Any transaction that occurs in these months will return a Boolean result of TRUE.

### Example 4 - Chart object example

Load script and chart expression

#### Overview

The same dataset and scenario from the first example are used.

However, in this example, the dataset is unchanged and loaded into the application. The calculation that determines whether transactions took place in the same quarter as May 15, 2022 is created as a measure in a chart in the app.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
```

```
8188,'2/19/2022',37.23
```

```
8189,'3/7/2022',17.17
```

```
8190,'3/30/2022',88.27
```

```
8191,'4/5/2022',57.42
```

```
8192,'4/16/2022',53.80
```

```
8193,'5/1/2022',82.06
```

```
8194,'5/7/2022',40.39
```

```
8195,'5/22/2022',87.21
```

```
8196,'6/15/2022',95.93
```

```
8197,'6/26/2022',45.89
```

```
8198,'7/9/2022',36.23
```

```
8199,'7/22/2022',25.66
```

```
8200,'7/23/2022',82.77
```

```
8201,'7/27/2022',69.98
```

```
8202,'8/2/2022',76.11
```

```
8203,'8/8/2022',25.12
```

```
8204,'8/19/2022',46.23
```

```
8205, '9/26/2022', 84.21
8206, '10/14/2022', 96.24
8207, '10/29/2022', 67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension:

- date

To calculate whether transactions took place in the same quarter as May 15, create the following measure:


```
=inmonths(3,date,'05/15/2022', 0)
```

Results table

date	=inmonths(3,date,'05/15/2022', 0)
2/19/2022	0
3/7/2022	0
3/30/2022	0
4/5/2022	-1
4/16/2022	-1
5/1/2022	-1
5/7/2022	-1
5/22/2022	-1
6/15/2022	-1
6/26/2022	-1
7/9/2022	0
7/22/2022	0
7/23/2022	0
7/27/2022	0
8/2/2022	0
8/8/2022	0
8/19/2022	0
9/26/2022	0
10/14/2022	0
10/29/2022	0

The 'in\_months' field is created in the chart by using the `inmonths()` function. The first argument provided is 3 which divides the year into quarter segments. The second argument identifies which field is being evaluated, the date field in this example. The third argument is a hard-coded date for the for May 15 which is the `base_date` and a `period_no` of 0 is the final argument.

*Diagram of `inmonths()` function with quarter segments*



May falls into the second quarter of the year. Therefore, any transaction that occurs between April 1 and June 30 will return a Boolean result of TRUE. This is validated in the results table.

### Example 5 - Scenario

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset which is loaded into a table called 'Products'.
- The table contains the following fields:
  - product ID
  - product type
  - manufacture date
  - cost price

The end user would like a chart that displays, by product type, the cost of products manufactured in the first segment of 2021. The user would like to be able to define the length of this segment.

#### Load script

```
SET vPeriod = 1;

Products:
Load
*
Inline
[
product_id,product_type,manufacture_date,cost_price
8188,product A,'2/19/2022',37.23
```

```
8189,product D,'3/7/2022',17.17
8190,product C,'3/30/2022',88.27
8191,product B,'4/5/2022',57.42
8192,product D,'4/16/2022',53.80
8193,product D,'5/1/2022',82.06
8194,product A,'5/7/2022',40.39
8195,product B,'5/22/2022',87.21
8196,product C,'6/15/2022',95.93
8197,product B,'6/26/2022',45.89
8198,product C,'7/9/2022',36.23
8199,product D,'7/22/2022',25.66
8200,product D,'7/23/2022',82.77
8201,product A,'7/27/2022',69.98
8202,product A,'8/2/2022',76.11
8203,product B,'8/8/2022',25.12
8204,product B,'8/19/2022',46.23
8205,product B,'9/26/2022',84.21
8206,product C,'10/14/2022',96.24
8207,product D,'10/29/2022',67.67
];
```

### Results

Load the data and open a sheet.

At the start of the load script a variable, `vPeriod`, is created that is tied to the variable input control.

Do the following:

1. In the assets panel, click **Custom objects**.
2. Select **Qlik Dashboard bundle**, create a **Variable input** object.
3. Enter a title for the chart object.
4. Under **Variable**, select **vPeriod** as the name and set the object to show as a **Drop down**.
5. Under **Values**, click **Dynamic** values. Enter the following:  
`= '1~month|2~bi-month|3~quarter|4~tertia|6~half-year'`.
6. Add a new table to the sheet.
7. Under **Data** in the properties panel, add `product_type` as a dimension.
8. Add the following expression as a measure:  
`=sum(if(inmonths($(vPeriod),manufacture_date,makedate(2022,01,01),0),cost_price,0))`
9. Set the measure's **Number formatting** to **Money**.

Results table

product_type	=sum(if(inmonths(\$(vPeriod),manufacture_date,makedate(2022,01,01),0),cost_price,0))
product A	\$88.27
product B	\$37.23
product C	\$17.17
product D	\$0.00

The `inmonths()` function uses the user input as its argument to define the size of the starting segment of the year. The function passes in the manufacture date of each of the products as the `inmonths()` function's second argument. By using January 1 as the third argument in the `inmonths()` function, products with manufacture dates that fall in the opening segment of the year will return a Boolean value of `TRUE` and therefore the sum function will add the costs of those products.

### inmonthstodate


This function finds if a timestamp falls within the part a period of the month, bi-month, quarter, four-month period, or half-year up to and including the last millisecond of `base_date`. It is also possible to find if the timestamp falls within a previous or following time period.

#### Syntax:

```
InMonths (n_months, timestamp, base_date, period_no[, first_month_of_year ])
```

**Return data type:** Boolean

*Diagram of inmonthstodate function.*



#### Arguments


Argument	Description
<b>n_months</b>	The number of months that defines the period. An integer or expression that resolves to an integer that must be one of: 1 (equivalent to the <code>inmonth()</code> function), 2 (bi-month), 3 (equivalent to the <code>inquarter()</code> function), 4 (four-month period), or 6 (half year).
<b>timestamp</b>	The date that you want to compare with <b>base_date</b> .
<b>base_date</b>	Date that is used to evaluate the period.
<b>period_no</b>	The period can be offset by <b>period_no</b> , an integer, or expression resolving to an integer, where the value 0 indicates the period that contains <b>base_date</b> . Negative values in <b>period_no</b> indicate preceding periods and positive values indicate succeeding periods.
<b>first_month_of_year</b>	If you want to work with (fiscal) years not starting in January, indicate a value between 2 and 12 in <b>first_month_of_year</b> .

## 8 Script and chart functions

In the `inmonthstodate()` function, the `base_date` acts as the end point of the particular year segment that it is part of.

For example, if the year was broken into tertial segments, and the `base_date` was May 15, any timestamp between the start of January and end of April would return a Boolean result of FALSE. Dates between May 1 and May 15 would return TRUE. The rest of the year would return FALSE.

*Diagram of Boolean results range of `inmonthstodate` function.*



The following segments of the year are available in the function as `n_month` arguments.

n_month arguments	
Period	Number of months
month	1
bi-month	2
quarter	3
tertial	4
half-year	6

### When to use it

The `inmonthstodate()` function returns a Boolean result. Typically, this type of function is used as a condition in an `if` expression. By using the `inmonthstodate()` function, you can select the period you want to be evaluated. For example, providing an input variable that lets the user identify the products manufactured in the month, quarter, or half-year of a period, up to a certain date.

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET dateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.



### Function examples

Example	Result
<code>inmonthstodate(4, '01/25/2013', '04/25/2013', 0)</code>	Returns True, because the value of timestamp, 01/25/2013, lies within the four-month period 01/01/2013 up to the end of 04/25/2013, in which the value of base_date, 04/25/2013 lies.
<code>inmonthstodate(4, '04/26/2013', '04/25/2006', 0)</code>	Returns False, because 04/26/2013 is outside the same period as the previous example.
<code>inmonthstodate(4, '09/25/2005', '02/01/2006', -1)</code>	Returns True, because the value of period_no, -1, shifts the search period back one period of four months (the value of n-months), which makes the search period 01/09/2005 to 02/01/2006.
<code>inmonthstodate(4, '04/25/2006', '06/01/2006', 0, 3)</code>	Returns True, because the value of first_month_of_year is set to 3, which makes the search period 03/01/2006 to 06/01/2006 instead of 05/01/2006 to 06/01/2006.

### Example 1 – No additional arguments

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions for 2022 that is loaded into a table called 'Transactions'.
- A date field in the DateFormat system variable (MM/DD/YYYY) format.
- A preceding load statement containing:
  - The `inmonthstodate()` function that is set as the field, 'in\_months\_to\_date'. This determines which transactions took place in the quarter up until May 15, 2022.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
  Load
  *,
  inmonthstodate(3,date,'05/15/2022', 0) as in_months_to_date
  ;
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
```

```
8188, '1/19/2022', 37.23
```

```
8189, '1/7/2022', 17.17
```

```
8190, '2/28/2022', 88.27
8191, '2/5/2022', 57.42
8192, '3/16/2022', 53.80
8193, '4/1/2022', 82.06
8194, '5/7/2022', 40.39
8195, '5/16/2022', 87.21
8196, '6/15/2022', 95.93
8197, '6/26/2022', 45.89
8198, '7/9/2022', 36.23
8199, '7/22/2022', 25.66
8200, '7/23/2022', 82.77
8201, '7/27/2022', 69.98
8202, '8/2/2022', 76.11
8203, '8/8/2022', 25.12
8204, '8/19/2022', 46.23
8205, '9/26/2022', 84.21
8206, '10/14/2022', 96.24
8207, '10/29/2022', 67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- in\_months\_to\_date

Results table


date	in_months_to_date
1/7/2022	0
1/19/2022	0
2/5/2022	0
2/28/2022	0
3/16/2022	0
4/1/2022	-1
5/7/2022	-1
5/16/2022	0
6/15/2022	0
6/26/2022	0
7/9/2022	0
7/22/2022	0
7/23/2022	0

date	in_months_to_date
7/27/2022	0
8/2/2022	0
8/8/2022	0
8/19/2022	0
9/26/2022	0
10/14/2022	0
10/29/2022	0

The 'in\_months\_to\_date' field is created in the preceding load statement by using the `inmonthstodate` () function.

The first argument provided is 3, dividing the year into quarter segments. The second argument identifies which field is being evaluated. The third argument is a hard-coded date for May 15, which is the `base_date` that defines the end boundary of the segment. A `period_no` of 0 is the final argument.

*Diagram of inmonthstodate function with no additional arguments.*



Any transaction that occurs between April 1 and May 15 returns a Boolean result of TRUE. Transaction dates outside of that period return FALSE.

### Example 2 – period\_no

Load script and results

#### Overview

The same dataset and scenario as the first example are used.

However, in this example, the task is to create a field, 'previous\_qtr\_to\_date', that determines if the transactions took place a quarter before May 15.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

Transactions:

```
Load
*,
```

```
inmonthstodate(3,date,'05/15/2022', -1) as previous_qtr_to_date
;
Load
*
Inline
[
id,date,amount
8188,'1/19/2022',37.23
8189,'1/7/2022',17.17
8190,'2/28/2022',88.27
8191,'2/5/2022',57.42
8192,'3/16/2022',53.80
8193,'4/1/2022',82.06
8194,'5/7/2022',40.39
8195,'5/16/2022',87.21
8196,'6/15/2022',95.93
8197,'6/26/2022',45.89
8198,'7/9/2022',36.23
8199,'7/22/2022',25.66
8200,'7/23/2022',82.77
8201,'7/27/2022',69.98
8202,'8/2/2022',76.11
8203,'8/8/2022',25.12
8204,'8/19/2022',46.23
8205,'9/26/2022',84.21
8206,'10/14/2022',96.24
8207,'10/29/2022',67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- previous\_qtr\_to\_date

Results table


date	previous_qtr_to_date
1/7/2022	-1
1/19/2022	-1
2/5/2022	-1
2/28/2022	0
3/16/2022	0
4/1/2022	0
5/7/2022	0
5/16/2022	0

date	previous_qtr_to_date
6/15/2022	0
6/26/2022	0
7/9/2022	0
7/22/2022	0
7/23/2022	0
7/27/2022	0
8/2/2022	0
8/8/2022	0
8/19/2022	0
9/26/2022	0
10/14/2022	0
10/29/2022	0

By using `-1` as the `period_no` argument in the `inmonthstodate()` function, the function shifts the boundaries of the comparator year segment by a quarter.

May 15 falls into the second quarter of the year and therefore the segment initially equates to between April 1 and May 15. The `period_no` argument offsets this segment by a negative three months. The date boundaries become January 1 to February 15.

*Diagram of `inmonthstodate` function with `period_no` set to `-1`.*



Therefore, any transaction that occurs between January 1 and February 15 will return a Boolean result of TRUE.

### Example 3 – first\_month\_of\_year

Load script and results

#### Overview

The same dataset and scenario as the first example are used.

In this example, the organizational policy is for March to be the first month of the financial year.

Create a field, 'in\_months\_to\_date', that determines which transactions took place in the same quarter up to May 15, 2022.

### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
Load
```

```
*
```

```
inmonthstodate(3,date,'05/15/2022',0,3) as in_months_to_date
```

```
;
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
```

```
8188,'1/19/2022',37.23
```

```
8189,'1/7/2022',17.17
```

```
8190,'2/28/2022',88.27
```

```
8191,'2/5/2022',57.42
```

```
8192,'3/16/2022',53.80
```

```
8193,'4/1/2022',82.06
```

```
8194,'5/7/2022',40.39
```

```
8195,'5/16/2022',87.21
```

```
8196,'6/15/2022',95.93
```

```
8197,'6/26/2022',45.89
```

```
8198,'7/9/2022',36.23
```

```
8199,'7/22/2022',25.66
```

```
8200,'7/23/2022',82.77
```

```
8201,'7/27/2022',69.98
```

```
8202,'8/2/2022',76.11
```

```
8203,'8/8/2022',25.12
```

```
8204,'8/19/2022',46.23
```

```
8205,'9/26/2022',84.21
```

```
8206,'10/14/2022',96.24
```

```
8207,'10/29/2022',67.67
```

```
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- in\_months\_to\_date

Results table

<b>date</b>	<b>previous_qtr_to_date</b>
1/7/2022	0
1/19/2022	0
2/5/2022	0
2/28/2022	0
3/16/2022	-1
4/1/2022	-1
5/7/2022	-1
5/16/2022	0
6/15/2022	0
6/26/2022	0
7/9/2022	0
7/22/2022	0
7/23/2022	0
7/27/2022	0
8/2/2022	0
8/8/2022	0
8/19/2022	0
9/26/2022	0
10/14/2022	0
10/29/2022	0

By using 3 as the `first_month_of_year` argument in the `inmonthstodate()` function, the function begins the year on March 1 and then divides the year into quarters based on the first argument provided. Therefore, the quarter segments are:

- Mar-May
- Jun-Aug
- Sep-Nov
- Dec-Feb

The `base_date` of May 15 then segments the Mar-May quarter by setting its end boundary as May 15.

Diagram of `inmonthstodate` function with March set as first month of the year.



Therefore, any transaction that occurs between March 1 and May 15 will return a Boolean result of TRUE, and transactions with dates outside these boundaries will return a value of FALSE.

### Example 4 – Chart example

Load script and chart expression

#### Overview

The same dataset and scenario as the first example are used.

In this example, the dataset is unchanged and loaded into the app. The task is to create a calculation that determines whether transactions took place in the same quarter as May 15 as a measure in a chart of the app.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

Transactions:

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
```

```
8188,'1/19/2022',37.23
```

```
8189,'1/7/2022',17.17
```

```
8190,'2/28/2022',88.27
```

```
8191,'2/5/2022',57.42
```

```
8192,'3/16/2022',53.80
```

```
8193,'4/1/2022',82.06
```

```
8194,'5/7/2022',40.39
```

```
8195,'5/16/2022',87.21
```

```
8196,'6/15/2022',95.93
```

```
8197,'6/26/2022',45.89
```

```
8198,'7/9/2022',36.23
```

```
8199,'7/22/2022',25.66
```

```
8200,'7/23/2022',82.77
```

```
8201,'7/27/2022',69.98
```

```
8202,'8/2/2022',76.11
```

```
8203,'8/8/2022',25.12
```

```
8204,'8/19/2022',46.23
```

```
8205,'9/26/2022',84.21
```



```
8206, '10/14/2022', 96.24  
8207, '10/29/2022', 67.67  
];
```

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension:

date

To calculate whether transactions took place in the same quarter as May 15, create the following measure:

```
=inmonthstodate(3,date,'05/15/2022', 0)
```

Results table


date	=inmonthstodate(3,date,'05/15/2022', 0)
1/7/2022	0
1/19/2022	0
2/5/2022	0
2/28/2022	0
3/16/2022	0
4/1/2022	-1
5/7/2022	-1
5/16/2022	0
6/15/2022	0
6/26/2022	0
7/9/2022	0
7/22/2022	0
7/23/2022	0
7/27/2022	0
8/2/2022	0
8/8/2022	0
8/19/2022	0
9/26/2022	0
10/14/2022	0
10/29/2022	0

The 'in\_months\_to\_date' measure is created in the chart by using the inmonthstodate() function.

## 8 Script and chart functions

The first argument provided is 3, dividing the year into quarter segments. The second argument identifies which field is being evaluated. The third argument is a hard-coded date May 15 which is the `base_date` that defines the end boundary of the segment. A `period_no` of 0 is the final argument.

*Diagram of `inmonthstodate` function with quarter segments.*



Any transaction that occurs between April 1 and May 15 will return a Boolean result of TRUE. Transaction dates outside of that segment will return FALSE.

### Example 5 – Scenario

Load script and results

#### Overview

In this example, a dataset is loaded into a table called 'sales'. The table contains the following fields:

- Product ID
- Product type
- Sales date
- Sales price

The end user would like a chart that displays, by product type, the sales of products sold in the period leading up to December 24, 2022. The user would like to be able to define the length of this period.

#### Load script

```
SET vPeriod = 1;

Products:
Load
*
Inline
[
product_id,product_type,sales_date,sales_price
8188,product A,'9/19/2022',37.23
8189,product D,'10/27/2022',17.17
8190,product C,'10/30/2022',88.27
8191,product B,'10/31/2022',57.42
8192,product D,'11/16/2022',53.80
8193,product D,'11/28/2022',82.06
8194,product A,'12/2/2022',40.39
8195,product B,'12/5/2022',87.21
```

```
8196,product C, '12/15/2022', 95.93
8197,product B, '12/16/2022', 45.89
8198,product C, '12/19/2022', 36.23
8199,product D, '12/22/2022', 25.66
8200,product D, '12/23/2022', 82.77
8201,product A, '12/24/2022', 69.98
8202,product A, '12/24/2022', 76.11
8203,product B, '12/26/2022', 25.12
8204,product B, '12/27/2022', 46.23
8205,product B, '12/27/2022', 84.21
8206,product C, '12/28/2022', 96.24
8207,product D, '12/29/2022', 67.67
];
```

### Results

Load the data and open a sheet.

At the start of the load script a variable, `vPeriod`, is created that is tied to the variable input control.

Do the following:

1. In the assets panel, click **Custom objects**.
2. Select **Qlik Dashboard bundle** and add a **Variable input** to your sheet.
3. Enter a title for the chart.
4. Under **Variable**, select **vPeriod** as the name and set the object to show as a **Drop down**.
5. Under **Values**, click **Dynamic values**. Enter the following:  
`= '1~month|2~bi-month|3~quarter|4~tertia|6~half-year'`.
6. Add a new table to the sheet.
7. Under **Data** in the properties panel, add `product_type` as a dimension.
8. Add the following expression as a measure:  
`=sum(if(inmonthstodate($(vPeriod), sales_date, makedate(2022, 12, 24), 0), sales_price, 0))`
9. Set the measure's **Number formatting** to **Money**.

Results table

product_type	=sum(if(inmonthstodate(\$(vPeriod), sales_date, makedate(2022, 12, 24), 0), sales_price, 0))
product A	\$186.48
product B	\$190.52
product C	\$220.43
product D	\$261.46

The `inmonthstodate()` function uses the user input as its argument to define the size of the starting segment of the year.

The function passes in the sales date of each of the products as the `inmonthstodate()` function's second argument. By using December 24 as the third argument in the `inmonthstodate()` function, products with sales dates that occur in the defined period up to and including December 24 return a Boolean value of `TRUE`. The sum function adds the sales of these products.

### inmonthtodate


Returns True if **date** lies inside the part of month containing **basedate** up until and including the last millisecond of **basedate**.

#### Syntax:

```
InMonthToDate (timestamp, base_date, period_no)
```

**Return data type:** Boolean

*Diagram of inmonthtodate function.*



The `inmonthtodate()` function identifies a selected month as a segment. The start boundary is the beginning of the month. The end boundary can be set as a later date in the month. It then determines whether a set of dates fall into this segment or not, returning a `TRUE` or `FALSE` Boolean value.

#### Arguments

Argument	Description
<b>timestamp</b>	The date that you want to compare with <b>base_date</b> .
<b>base_date</b>	Date that is used to evaluate the month.
<b>period_no</b>	The month can be offset by <b>period_no</b> . <b>period_no</b> is an integer, where the value 0 indicates the month which contains <b>base_date</b> . Negative values in <b>period_no</b> indicate preceding months and positive values indicate succeeding months.

#### When to use it

The `inmonthtodate()` function returns a Boolean result. Typically, this type of function is used as a condition in an `if` expression. The `inmonthtodate()` function returns an aggregation or calculation that depends on whether a date occurred in the month up to and including the date in question.

For example, the `inmonthtodate()` function can be used to identify all equipment manufactured in a month up to a specific date.

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

#### Function examples

Example	Result
<code>inmonthtodate ('01/25/2013', '25/01/2013', 0)</code>	Returns True
<code>inmonthtodate ('01/25/2013', '24/01/2013', 0)</code>	Returns False
<code>inmonthtodate ('01/25/2013', '28/02/2013', -1)</code>	Returns True

### Example 1 – No additional arguments

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions for 2022 is loaded into a table called 'Transactions'.
- A date field is provided in the `DateFormat` system variable (MM/DD/YYYY) format.
- A preceding load statement containing:
  - The `inmonthtodate()` function which is set as the field, 'in\_month\_to\_date'. This determines which transactions took place between July 1 and July 26, 2022.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
  Load
  *,
  inmonthtodate(date,'07/26/2022', 0) as in_month_to_date
  ;
Load
*
Inline
```

```
[
id,date,amount
8188,'1/19/2022',37.23
8189,'1/7/2022',17.17
8190,'2/28/2022',88.27
8191,'2/5/2022',57.42
8192,'3/16/2022',53.80
8193,'4/1/2022',82.06
8194,'5/7/2022',40.39
8195,'5/16/2022',87.21
8196,'6/15/2022',95.93
8197,'6/26/2022',45.89
8198,'7/9/2022',36.23
8199,'7/22/2022',25.66
8200,'7/23/2022',82.77
8201,'7/27/2022',69.98
8202,'8/2/2022',76.11
8203,'8/8/2022',25.12
8204,'8/19/2022',46.23
8205,'9/26/2022',84.21
8206,'10/14/2022',96.24
8207,'10/29/2022',67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- in\_month\_to\_date

Results table

date	in_month_to_date
1/7/2022	0
1/19/2022	0
2/5/2022	0
2/28/2022	0
3/16/2022	0
4/1/2022	0
5/7/2022	0
5/16/2022	0
6/15/2022	0
6/26/2022	0
7/9/2022	-1


date	in_month_to_date
7/22/2022	-1
7/23/2022	-1
7/27/2022	0
8/2/2022	0
8/8/2022	0
8/19/2022	0
9/26/2022	0
10/14/2022	0
10/29/2022	0

The 'in\_month\_to\_date' field is created in the preceding load statement by using the `inmonthtoday()` function.

The first argument identifies which field is being evaluated. The second argument is a hard-coded date, July 26, which is the `base_date`. This `base_date` argument identifies which month is segmented and the end boundary of that segment.

A `period_no` of 0 is the final argument meaning that the function is not comparing months preceding or following the segmented month.

*Diagram of `inmonthtoday` function with no additional arguments.*



As a result, any transaction that occurs between July 1 and July 26 returns a Boolean result of TRUE. Any transaction that occurs in July after July 26 returns a Boolean result of FALSE as will any transaction in any other month of the year.

### Example 2 – `period_no`

Load script and results

#### Overview

The same dataset and scenario as the first example are used.

In this example, the task is to create a field, 'six\_months\_prior', that determines which transactions took place a full six months before July 1 and July 26.

### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
    Load
        *,
        inmonthtodate(date,'07/26/2022', -6) as six_months_prior
    ;
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
```

```
8188,'1/19/2022',37.23
```

```
8189,'1/7/2022',17.17
```

```
8190,'2/28/2022',88.27
```

```
8191,'2/5/2022',57.42
```

```
8192,'3/16/2022',53.80
```

```
8193,'4/1/2022',82.06
```

```
8194,'5/7/2022',40.39
```

```
8195,'5/16/2022',87.21
```

```
8196,'6/15/2022',95.93
```

```
8197,'6/26/2022',45.89
```

```
8198,'7/9/2022',36.23
```

```
8199,'7/22/2022',25.66
```

```
8200,'7/23/2022',82.77
```

```
8201,'7/27/2022',69.98
```

```
8202,'8/2/2022',76.11
```

```
8203,'8/8/2022',25.12
```

```
8204,'8/19/2022',46.23
```

```
8205,'9/26/2022',84.21
```

```
8206,'10/14/2022',96.24
```

```
8207,'10/29/2022',67.67
```

```
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- six\_months\_prior

Results table


date	six_months_prior
1/7/2022	-1
1/19/2022	-1



date	six_months_prior
2/5/2022	0
2/28/2022	0
3/16/2022	0
4/1/2022	0
5/7/2022	0
5/16/2022	0
6/15/2022	0
6/26/2022	0
7/9/2022	0
7/22/2022	0
7/23/2022	0
7/27/2022	0
8/2/2022	0
8/8/2022	0
8/19/2022	0
9/26/2022	0
10/14/2022	0
10/29/2022	0

By using -6 as the `period_no` argument in the `inmonthtoday()` function, the boundaries of the comparator month segment shift by six months. Initially the month segment equates to between July 1 and July 26. The `period_no` then offsets this segment by a negative six months and the date boundaries are shifted and fall between January 1 and January 26.

*Diagram of `inmonthtoday` function with `period_no` set to -6.*



As a result, any transaction that occurs between January 1 and January 26 will return a Boolean result of TRUE.

### Example 3 – Chart example

Load script and chartexpression

#### Overview

The same dataset and scenario as the first example are used.

In this example, the dataset is unchanged and loaded into the app. The task is to create a calculation that determines whether transactions took place between July 1 and July 26 as a measure in a chart of the app.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
```

```
8188,'1/19/2022',37.23
```

```
8189,'1/7/2022',17.17
```

```
8190,'2/28/2022',88.27
```

```
8191,'2/5/2022',57.42
```

```
8192,'3/16/2022',53.80
```

```
8193,'4/1/2022',82.06
```

```
8194,'5/7/2022',40.39
```

```
8195,'5/16/2022',87.21
```

```
8196,'6/15/2022',95.93
```

```
8197,'6/26/2022',45.89
```

```
8198,'7/9/2022',36.23
```

```
8199,'7/22/2022',25.66
```

```
8200,'7/23/2022',82.77
```

```
8201,'7/27/2022',69.98
```

```
8202,'8/2/2022',76.11
```

```
8203,'8/8/2022',25.12
```

```
8204,'8/19/2022',46.23
```

```
8205,'9/26/2022',84.21
```

```
8206,'10/14/2022',96.24
```

```
8207,'10/29/2022',67.67
```

```
];
```

#### Results

Load the data and open a sheet. Create a new table and add this field as a dimension:

```
date
```

To calculate whether transactions took place between July 1 and July 26, create the following measure:

```
=inmonthtoday(date, '07/26/2022', 0)
```


Results table

<b>date</b>	<b>=inmonthtoday(date,'07/26/2022', 0)</b>
1/7/2022	0
1/19/2022	0
2/5/2022	0
2/28/2022	0
3/16/2022	0
4/1/2022	0
5/7/2022	0
5/16/2022	0
6/15/2022	0
6/26/2022	0
7/9/2022	-1
7/22/2022	-1
7/23/2022	-1
7/27/2022	0
8/2/2022	0
8/8/2022	0
8/19/2022	0
9/26/2022	0
10/14/2022	0
10/29/2022	0

The 'in\_month\_to\_date' field measure is created in the chart by using the `inmonthtoday()` function.

The first argument identifies which field is being evaluated. The second argument is a hard-coded date, July 26, which is the `base_date`. This `base_date` argument identifies which month is segmented and the end boundary of that segment. A `period_no` of 0 is the final argument. This means that the function is not comparing months preceding or following the segmented month.

Diagram of `inmonthtoday` function with no additional arguments.



As a result, any transaction that occurs between July 1 and July 26 returns a Boolean result of TRUE. Any transaction that occurs in July after July 26 returns a Boolean result of FALSE as will any transaction in any other month of the year.

### Example 4 – Scenario

Load script and results

#### Overview

In this example, a dataset is loaded into a table called 'Products'. The table contains the following fields:

- Product ID
- Manufacture date
- Cost price

Due to equipment error, products that were manufactured in the month of July 2022 were defective. The issue was resolved on July 27, 2022.

The end user would like a chart that displays, by month, the status of products that were manufactured as 'defective' (Boolean TRUE) or 'faultless' (Boolean FALSE) and the cost of the products manufactured in that month.

#### Load script

```
Products:
Load
*
Inline
[
product_id,manufacture_date,cost_price
8188,'1/19/2022',37.23
8189,'1/7/2022',17.17
8190,'2/28/2022',88.27
8191,'2/5/2022',57.42
8192,'3/16/2022',53.80
8193,'4/1/2022',82.06
8194,'5/7/2022',40.39
8195,'5/16/2022',87.21
8196,'6/15/2022',95.93
```

```
8197, '6/26/2022', 45.89
8198, '7/9/2022', 36.23
8199, '7/22/2022', 25.66
8200, '7/23/2022', 82.77
8201, '7/27/2022', 69.98
8202, '8/2/2022', 76.11
8203, '8/8/2022', 25.12
8204, '8/19/2022', 46.23
8205, '9/26/2022', 84.21
8206, '10/14/2022', 96.24
8207, '10/29/2022', 67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- =monthname(manufacture\_date)
- =if(Inmonthtodate(manufacture\_date,makedate(2022,07,26),0),'Defective','Faultless')

To calculate the sum cost of the products, create this measure:

```
=sum(cost_price)
```

Set the measure's **Number Formatting** to **Money**.

Results table

monthname (manufacture_date)	if(Inmonthtodate(manufacture_date,makedate (2022,07,26),0),'Defective','Faultless')	Sum(cost_ price)
Jan 2022	Faultless	\$54.40
Feb 2022	Faultless	\$145.69
Mar 2022	Faultless	\$53.80
Apr 2022	Faultless	\$82.06
May 2022	Faultless	\$127.60
Jun 2022	Faultless	\$141.82
Jul 2022	Defective	\$144.66
Jul 2022	Faultless	\$69.98
Aug 2022	Faultless	\$147.46
Sep 2022	Faultless	\$84.21
Oct 2022	Faultless	\$163.91

The `inmonthtodate()` function returns a Boolean value when evaluating the manufacturing dates of each of the products.

For the dates that return a Boolean value of TRUE, the product is marked as 'Defective'. For any product returning a value of FALSE, and therefore not made in the month up to and including July 26, it marks the products as 'Faultless'.

### inquarter

This function returns True if **timestamp** lies inside the quarter containing **base\_date**.


#### Syntax:

```
InQuarter (timestamp, base_date, period_no[, first_month_of_year])
```

**Return data type:** Boolean

In Qlik Sense, the Boolean true value is represented by -1, and the false value is represented by 0.

*Diagram of inquarter() function's range*



In other words, the `inquarter()` function divides the year into four equal quarters between January 1 and December 31. You can use the `first_month_of_year` argument to change what month is considered the first in your app and the quarters will change based on that argument. The `base_date`, the function identifies which quarter should be used as the comparator for the function. Finally, the function returns a Boolean result when comparing date values to that quarter segment.

#### When to use it

The `inquarter()` function returns a Boolean result. Typically, this type of function will be used as a condition in an `if` expression. This returns an aggregation or calculation that depends on whether a date occurred in the selected quarter.

For example, the `inquarter()` function can be used to identify all equipment manufactured in a quarter segment based on the dates when the equipment was manufactured.

#### Arguments

Argument	Description
<b>timestamp</b>	The date that you want to compare with <b>base_date</b> .
<b>base_date</b>	Date that is used to evaluate the quarter.

Argument	Description
<b>period_no</b>	The quarter can be offset by <b>period_no</b> . <b>period_no</b> is an integer, where the value 0 indicates the quarter which contains <b>base_date</b> . Negative values in <b>period_no</b> indicate preceding quarters and positive values indicate succeeding quarters.
<b>first_month_of_year</b>	If you want to work with (fiscal) years not starting in January, indicate a value between 2 and 12 in <b>first_month_of_year</b> .

You can use the following values to set the first month of year in the `first_month_of_year` argument:

`first_month_of_year` values

Month	Value
February	2
March	3
April	4
May	5
June	6
July	7
August	8
September	9
October	10
November	11
December	12

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET dateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Function examples

Example	Result
<code>inquarter ('01/25/2013', '01/01/2013', 0)</code>	Returns TRUE
<code>inquarter ('01/25/2013', '04/01/2013', 0)</code>	Returns FALSE
<code>inquarter ('01/25/2013', '01/01/2013', -1)</code>	Returns FALSE
<code>inquarter ('12/25/2012', '01/01/2013', -1)</code>	Returns TRUE
<code>inquarter ('01/25/2013', '03/01/2013', 0, 3)</code>	Returns FALSE
<code>inquarter ('03/25/2013', '03/01/2013', 0, 3)</code>	Returns TRUE

### Example 1 - No additional arguments

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions in 2022 which is loaded into a table called 'Transactions'.
- A preceding load which contains the `inquarter()` function that is set as the 'in\_quarter' field and determines which transactions took place in the same quarter as May 15, 2022.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
Load
*
    inquarter (date,'05/15/2022', 0) as in_quarter
;
```

```
Load
```

```
*
```

```
Inline
```

```
[
id,date,amount
8188,'1/19/2022',37.23
8189,'1/7/2022',17.17
8190,'2/28/2022',88.27
8191,'2/5/2022',57.42
8192,'3/16/2022',53.80
8193,'4/1/2022',82.06
8194,'5/7/2022',40.39
8195,'5/16/2022',87.21
8196,'6/15/2022',95.93
```



```
8197, '6/26/2022', 45.89
8198, '7/9/2022', 36.23
8199, '7/22/2022', 25.66
8200, '7/23/2022', 82.77
8201, '7/27/2022', 69.98
8202, '8/2/2022', 76.11
8203, '8/8/2022', 25.12
8204, '8/19/2022', 46.23
8205, '9/26/2022', 84.21
8206, '10/14/2022', 96.24
8207, '10/29/2022', 67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- in\_quarter


Results table

date	in_quarter
1/7/2022	0
1/19/2022	0
2/5/2022	0
2/28/2022	0
3/16/2022	0
4/1/2022	-1
5/7/2022	-1
5/16/2022	-1
6/15/2022	-1
6/26/2022	-1
7/9/2022	0
7/22/2022	0
7/23/2022	0
7/27/2022	0
8/2/2022	0
8/8/2022	0
8/19/2022	0

date	in_quarter
9/26/2022	0
10/14/2022	0
10/29/2022	0

The 'in\_quarter' field is created in the preceding load statement by using the `inquarter()` function. The first argument identifies which field is being evaluated. The second argument is a hard-coded date for May 15 that identifies which quarter to define as the comparator. A `period_no` of 0 is the final argument and ensures the `inquarter()` function does not compare quarters preceding or following the segmented quarter.

*Diagram of `inquarter()` function with May 15 as the base date*



Any transaction that occurs between April 1 and the end of June 30 returns a Boolean result of TRUE.

### Example 2 - period\_no

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions in 2022 which is loaded into a table called 'Transactions'.
- A preceding load which contains the `inquarter()` function that is set as the 'previous\_quarter' field, and determines which transactions took place in the quarter preceding the quarter of May 15, 2022.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

Transactions:

```
Load
    *,
```

```
    inquarter (date,'05/15/2022', -1) as previous_qtr
;
Load
*
Inline
[
id,date,amount
8188,'1/19/2022',37.23
8189,'1/7/2022',17.17
8190,'2/28/2022',88.27
8191,'2/5/2022',57.42
8192,'3/16/2022',53.80
8193,'4/1/2022',82.06
8194,'5/7/2022',40.39
8195,'5/16/2022',87.21
8196,'6/15/2022',95.93
8197,'6/26/2022',45.89
8198,'7/9/2022',36.23
8199,'7/22/2022',25.66
8200,'7/23/2022',82.77
8201,'7/27/2022',69.98
8202,'8/2/2022',76.11
8203,'8/8/2022',25.12
8204,'8/19/2022',46.23
8205,'9/26/2022',84.21
8206,'10/14/2022',96.24
8207,'10/29/2022',67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- previous\_qtr


Results table

date	previous_qtr
1/7/2022	-1
1/19/2022	-1
2/5/2022	-1
2/28/2022	-1
3/16/2022	-1
4/1/2022	0
5/7/2022	0
5/16/2022	0

date	previous_qtr
6/15/2022	0
6/26/2022	0
7/9/2022	0
7/22/2022	0
7/23/2022	0
7/27/2022	0
8/2/2022	0
8/8/2022	0
8/19/2022	0
9/26/2022	0
10/14/2022	0
10/29/2022	0

Using `-1` as the `period_no` argument in the `inqarter()` function shifts the boundaries of the comparator quarter back by a full quarter. May 15 falls into the second quarter of the year and therefore the segment initially equates to the quarter of April 1 to June 30. The `period_no` offsets this segment by a negative three months and causes the date boundaries to become January 1 to March 30.

*Diagram of `inqarter()` function with May 15 as the base date*



Therefore, any transaction that occurs between January 1 and March 30 will return a Boolean result of TRUE.

### Example 3 - first\_month\_of\_year

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions in 2022 which is loaded into a table called 'Transactions'.
- A preceding load which contains the `inquarter()` function that is set as the 'in\_quarter' field, and determines which transactions took place in the same quarter as May 15, 2022.

However, in this example, the organizational policy is for March to be the first month of the financial year.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
    Load
        *,
        inquarter (date, '05/15/2022', 0, 3) as in_quarter
    ;
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
```

```
8188, '1/19/2022', 37.23
```

```
8189, '1/7/2022', 17.17
```

```
8190, '2/28/2022', 88.27
```

```
8191, '2/5/2022', 57.42
```

```
8192, '3/16/2022', 53.80
```

```
8193, '4/1/2022', 82.06
```

```
8194, '5/7/2022', 40.39
```

```
8195, '5/16/2022', 87.21
```

```
8196, '6/15/2022', 95.93
```

```
8197, '6/26/2022', 45.89
```

```
8198, '7/9/2022', 36.23
```

```
8199, '7/22/2022', 25.66
```

```
8200, '7/23/2022', 82.77
```

```
8201, '7/27/2022', 69.98
```

```
8202, '8/2/2022', 76.11
```

```
8203, '8/8/2022', 25.12
```

```
8204, '8/19/2022', 46.23
```

```
8205, '9/26/2022', 84.21
```

```
8206, '10/14/2022', 96.24
```

```
8207, '10/29/2022', 67.67
```

```
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:


- date
- previous\_qtr

Results table

<b>date</b>	<b>previous_qtr</b>
1/7/2022	0
1/19/2022	0
2/5/2022	0
2/28/2022	0
3/16/2022	-1
4/1/2022	-1
5/7/2022	-1
5/16/2022	-1
6/15/2022	0
6/26/2022	0
7/9/2022	0
7/22/2022	0
7/23/2022	0
7/27/2022	0
8/2/2022	0
8/8/2022	0
8/19/2022	0
9/26/2022	0
10/14/2022	0
10/29/2022	0

Using 3 as the `first_month_of_year` argument in the `inquarter()` function sets March 1 as the start of the year and then divides the year into quarters. Therefore, the quarter segments are Mar-May, Jun-Aug, Sep-Nov, Dec-Feb. The `base_date` of May 15 sets the Mar-May quarter as the comparator quarter for the function.

Diagram of `inquarter()` function with March set as the first month of the year



Therefore, any transaction that occurs between March 1 and May 31 will return a Boolean result of TRUE.

### Example 4 - Chart object example

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions in 2022 which is loaded into a table called 'Transactions'.
- A preceding load which contains the `inquarter()` function that is set as the 'in\_quarter' field, and determines which transactions took place in the same quarter as May 15, 2022.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

Transactions:

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
```

```
8188,'1/19/2022',37.23
```

```
8189,'1/7/2022',17.17
```

```
8190,'2/28/2022',88.27
```

```
8191,'2/5/2022',57.42
```

```
8192,'3/16/2022',53.80
```

```
8193,'4/1/2022',82.06
```

```
8194,'5/7/2022',40.39
```

```
8195,'5/16/2022',87.21
```

```
8196,'6/15/2022',95.93
```

```
8197,'6/26/2022',45.89
```

```
8198,'7/9/2022',36.23
```

```
8199,'7/22/2022',25.66
```

```
8200, '7/23/2022', 82.77
8201, '7/27/2022', 69.98
8202, '8/2/2022', 76.11
8203, '8/8/2022', 25.12
8204, '8/19/2022', 46.23
8205, '9/26/2022', 84.21
8206, '10/14/2022', 96.24
8207, '10/29/2022', 67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension:

- date

Create the following measure to calculate whether transactions took place in the same quarter as May 15:

```
=inquarter(date, '05/15/2022', 0)
```

Results table


date	in_quarter
1/7/2022	0
1/19/2022	0
2/5/2022	0
2/28/2022	0
3/16/2022	0
4/1/2022	-1
5/7/2022	-1
5/16/2022	-1
6/15/2022	-1
6/26/2022	-1
7/9/2022	0
7/22/2022	0
7/23/2022	0
7/27/2022	0
8/2/2022	0
8/8/2022	0
8/19/2022	0
9/26/2022	0



date	in_quarter
10/14/2022	0
10/29/2022	0

The 'in\_quarter' measure is created in the chart by using the `inquarter()` function. The first argument identifies which field is being evaluated. The second argument is a hard-coded date for May 15 that identifies which quarter to define as the comparator. A `period_no` of 0 is the final argument and ensures the `inquarter()` function does not compare quarters preceding or following the segmented quarter.

*Diagram of `inquarter()` function with May 15 as the base date*



Any transaction that occurs between April 1 and the end of June 30 returns a Boolean result of TRUE.

### Example 5 - Scenario

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset which is loaded into a table called 'Products'.
- The table contains the following fields:
  - product ID
  - product type
  - manufacture date
  - cost price

It has been identified that due to equipment error, products that were manufactured in the quarter of May 15, 2022 were defective. The end user would like a chart that displays, by quarter name, the status of which products manufactured were 'defective' or 'faultless' and the cost of the products manufactured in that quarter.

### Load script

Products:

Load

\*

Inline

[

product\_id,manufacture\_date,cost\_price

8188,'1/19/2022',37.23

8189,'1/7/2022',17.17

8190,'2/28/2022',88.27

8191,'2/5/2022',57.42

8192,'3/16/2022',53.80

8193,'4/1/2022',82.06

8194,'5/7/2022',40.39

8195,'5/16/2022',87.21

8196,'6/15/2022',95.93

8197,'6/26/2022',45.89

8198,'7/9/2022',36.23

8199,'7/22/2022',25.66

8200,'7/23/2022',82.77

8201,'7/27/2022',69.98

8202,'8/2/2022',76.11

8203,'8/8/2022',25.12

8204,'8/19/2022',46.23

8205,'9/26/2022',84.21

8206,'10/14/2022',96.24

8207,'10/29/2022',67.67

];

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension:

```
=quartername(manufacture_date)
```

Create the following measures:

- =if(only(InQuarter(manufacture\_date,makedate(2022,05,15),0)), 'Defective', 'Faultless'), to identify which of the products are defective and which are faultless using the inquarter() function.
- =sum(cost\_price), to show the sum of the cost of each product.

### Do the following:

1. Set the measure's **Number Formatting** to **Money**.
2. Under **Appearance**, turn off **Totals**.

Results table

quartername (manufacture_date)	=if(only(InQuarter(manufacture_date,makedate(2022,05,15),0)),'Defective','Faultless')	Sum (cost_price)
Jan-Mar 2022	Faultless	253.89
Apr-Jun 2022	Defective	351.48
Jul-Sep 2022	Faultless	446.31
Oct-Dec 2022	Faultless	163.91

The `inquarter()` function returns a Boolean value when evaluating the manufacturing dates of each of the products. For any product manufactured in the quarter that contains May 15, the `inquarter()` function returns a Boolean value of TRUE and marks the products as 'Defective'. For any product returning a value of FALSE, and therefore not manufactured in that quarter, it marks the products as 'Faultless'.

## inquartertodate

This function returns True if **timestamp** lies inside the part of the quarter containing **base\_date** up until and including the last millisecond of **base\_date**.

### Syntax:


```
InQuarterToDate (timestamp, base_date, period_no [, first_month_of_year])
```

**Return data type:** Boolean



*In Qlik Sense, the Boolean true value is represented by -1, and the false value is represented by 0.*

Diagram of `inquartertodate` function



The `inquartertodate()` function divides the year into four equal quarters between January 1 and December 31 (or the user-defined start of year and its corresponding end date). Using the `base_`

date, the function will then segment a particular quarter, with the `base_date` identifying both which quarter and the maximum allowed date for that quarter segment. Finally, the function returns a Boolean result when comparing the prescribed date values to that segment.

### Arguments

Argument	Description
<b>timestamp</b>	The date that you want to compare with <b>base_date</b> .
<b>base_date</b>	Date that is used to evaluate the quarter.
<b>period_no</b>	The quarter can be offset by <b>period_no</b> . <b>period_no</b> is an integer, where the value 0 indicates the quarter which contains <b>base_date</b> . Negative values in <b>period_no</b> indicate preceding quarters and positive values indicate succeeding quarters.
<b>first_month_of_year</b>	If you want to work with (fiscal) years not starting in January, indicate a value between 2 and 12 in <b>first_month_of_year</b> .

### When to use it

The `inquartertodate()` function returns a Boolean result. Typically, this type of function will be used as a condition in an `if` expression. The `inquartertodate()` function would be used to return an aggregation or calculation dependent on whether a date evaluated occurred in the quarter up to and including the date in question.

For example, the `inquartertodate()` function can be used to identify all equipment manufactured in a quarter up to a specific date.

### Function examples

Example	Result
<code>inquartertodate('01/25/2013', '03/25/2013', 0)</code>	Returns <code>TRUE</code> , since the value of <code>timestamp</code> , 01/25/2013, lies within the three-month period from 01/01/2013 to 03/25/2013, in which the value of <code>base_date</code> , 03/25/2013, lies.
<code>inquartertodate('04/26/2013', '03/25/2013', 0)</code>	Returns <code>FALSE</code> , since 04/26/2013 is outside the same period as the previous example.
<code>inquartertodate('02/25/2013', '06/09/2013', -1)</code>	Returns <code>TRUE</code> , since the value of <code>period_no</code> , -1, shifts the search period back one period of three months (one quarter of the year). This makes the search period 01/01/2013 to 03/09/2013.
<code>inquartertodate('03/25/2006', '04/15/2006', 0, 2)</code>	Returns <code>TRUE</code> , since the value of <code>first_month_of_year</code> is set to 2, which makes the search period 02/01/2006 to 04/15/2006 instead of 04/01/2006 to 04/15/2006.

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors.

You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Example 1 – No additional arguments

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions for 2022, which is loaded into a table called Transactions.
- The date field provided in the `DateFormat` system variable (MM/DD/YYYY) format.
- The creation of a field, `in_quarter_to_date`, that determines which transactions took place in the quarter up until May 15, 2022.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
Load
    *,
    inquartertoday(date,'05/15/2022', 0) as in_quarter_to_date
;
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
8188,'1/19/2022',37.23
8189,'1/7/2022',17.17
8190,'2/28/2022',88.27
8191,'2/5/2022',57.42
8192,'3/16/2022',53.80
8193,'4/1/2022',82.06
8194,'5/7/2022',40.39
8195,'5/16/2022',87.21
8196,'6/15/2022',95.93
8197,'6/26/2022',45.89
8198,'7/9/2022',36.23
8199,'7/22/2022',25.66
```

```
8200, '7/23/2022', 82.77
8201, '7/27/2022', 69.98
8202, '8/2/2022', 76.11
8203, '8/8/2022', 25.12
8204, '8/19/2022', 46.23
8205, '9/26/2022', 84.21
8206, '10/14/2022', 96.24
8207, '10/29/2022', 67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- in\_quarter\_to\_date


Results table

date	in_quarter_to_date
1/7/2022	0
1/19/2022	0
2/5/2022	0
2/28/2022	0
3/16/2022	0
4/1/2022	-1
5/7/2022	-1
5/16/2022	0
6/15/2022	0
6/26/2022	0
7/9/2022	0
7/22/2022	0
7/23/2022	0
7/27/2022	0
8/2/2022	0
8/8/2022	0
8/19/2022	0
9/26/2022	0
10/14/2022	0
10/29/2022	0

## 8 Script and chart functions

The `in_quarter_to_date` field is created in the preceding load statement by using the `inquartertoday()` function. The first argument provided identifies which field is being evaluated. The second argument is a hard-coded date for the for May 15, which is the `base_date` that identifies which quarter to segment and defines the end boundary of that segment. A `period_no` of 0 is the final argument, meaning that the function is not comparing quarters preceding or following the segmented quarter.

*Diagram of `inquartertoday` function, no additional arguments*



Any transaction that occurs in between April 1 and May 15 returns a Boolean result of `TRUE`. Transactions dates of May 16 and later will return `FALSE`, as do any transactions before April 1.

### Example 2 – `period_no`

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same dataset and scenario as the first example.
- The creation of a field, `previous_qtr_to_date`, that determines which transactions took place a full quarter before the quarter segment ending on May 15, 2022.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
Load
    *,
    inquartertoday(date,'05/15/2022', -1) as previous_qtr_to_date
;
Load
*
Inline
[
id,date,amount
8188,'1/19/2022',37.23
```

```
8189, '1/7/2022', 17.17
8190, '2/28/2022', 88.27
8191, '2/5/2022', 57.42
8192, '3/16/2022', 53.80
8193, '4/1/2022', 82.06
8194, '5/7/2022', 40.39
8195, '5/16/2022', 87.21
8196, '6/15/2022', 95.93
8197, '6/26/2022', 45.89
8198, '7/9/2022', 36.23
8199, '7/22/2022', 25.66
8200, '7/23/2022', 82.77
8201, '7/27/2022', 69.98
8202, '8/2/2022', 76.11
8203, '8/8/2022', 25.12
8204, '8/19/2022', 46.23
8205, '9/26/2022', 84.21
8206, '10/14/2022', 96.24
8207, '10/29/2022', 67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- previous\_qtr\_to\_date

Results table


date	previous_qtr_to_date
1/7/2022	-1
1/19/2022	-1
2/5/2022	-1
2/28/2022	0
3/16/2022	0
4/1/2022	0
5/7/2022	0
5/16/2022	0
6/15/2022	0
6/26/2022	0
7/9/2022	0
7/22/2022	0
7/23/2022	0



date	previous_qtr_to_date
7/27/2022	0
8/2/2022	0
8/8/2022	0
8/19/2022	0
9/26/2022	0
10/14/2022	0
10/29/2022	0

A `period_no` value of -1 indicates that the `inquartertodate` () function compares the input quarter segment to the preceding quarter. May 15 falls into the second quarter of the year, so the segment initially equates to between April 1 and May 15. The `period_no` then offsets this segment by three months earlier, causing the date boundaries to become January 1 to February 15.

*Diagram of inquartertodate function, period\_no example*



Therefore, any transaction that occurs between January 1 and February 15 will return a Boolean result of `TRUE`.

### Example 3 – first\_month\_of\_year

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same dataset and scenario as the first example.
- The creation of a field, `in_quarter_to_date`, that determines which transactions took place in the same quarter up to May 15, 2022.

In this example, we set March as the first month of the fiscal year.

### Load script

```
SET DateFormat='MM/DD/YYYY';

Transactions:
  Load
    *,
    inquartertoday(date,'05/15/2022', 0,3) as in_quarter_to_date
  ;

Load
*
Inline
[
id,date,amount
8188,'1/19/2022',37.23
8189,'1/7/2022',17.17
8190,'2/28/2022',88.27
8191,'2/5/2022',57.42
8192,'3/16/2022',53.80
8193,'4/1/2022',82.06
8194,'5/7/2022',40.39
8195,'5/16/2022',87.21
8196,'6/15/2022',95.93
8197,'6/26/2022',45.89
8198,'7/9/2022',36.23
8199,'7/22/2022',25.66
8200,'7/23/2022',82.77
8201,'7/27/2022',69.98
8202,'8/2/2022',76.11
8203,'8/8/2022',25.12
8204,'8/19/2022',46.23
8205,'9/26/2022',84.21
8206,'10/14/2022',96.24
8207,'10/29/2022',67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- in\_quarter\_to\_date

Results table

date	in_quarter_to_date
1/7/2022	0
1/19/2022	0
2/5/2022	0
2/28/2022	0


<b>date</b>	<b>in_quarter_to_date</b>
3/16/2022	-1
4/1/2022	-1
5/7/2022	-1
5/16/2022	0
6/15/2022	0
6/26/2022	0
7/9/2022	0
7/22/2022	0
7/23/2022	0
7/27/2022	0
8/2/2022	0
8/8/2022	0
8/19/2022	0
9/26/2022	0
10/14/2022	0
10/29/2022	0

By using 3 as the `first_month_of_year` argument in the `inquartertoday()` function, the function begins the year on March 1, and then divides the year into quarters. Therefore, the quarter segments are:

- March to May
- June to August
- September to November
- December to February

The `base_date` of May 15 then segments the March to May quarter by setting its end boundary as May 15.

Diagram of `inquartertoday` function, `first_month_of_year` example



Therefore, any transaction that occurs in between the March 1 and May 15 will return a Boolean result of `TRUE`, while transactions with dates outside these boundaries will return a value of `FALSE`.

### Example 4 – Chart object example

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains the same dataset and scenario as the first example. However, in this example, the unchanged dataset is loaded into the application. The calculation that determines which transactions took place in the same quarter as May 15 is created as a measure in the chart object.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

Transactions:

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
```

```
8188,'1/19/2022',37.23
```

```
8189,'1/7/2022',17.17
```

```
8190,'2/28/2022',88.27
```

```
8191,'2/5/2022',57.42
```

```
8192,'3/16/2022',53.80
```

```
8193,'4/1/2022',82.06
```

```
8194,'5/7/2022',40.39
```

```
8195,'5/16/2022',87.21
```

```
8196,'6/15/2022',95.93
```

```
8197,'6/26/2022',45.89
```

```
8198,'7/9/2022',36.23
```

```
8199,'7/22/2022',25.66
```

```
8200,'7/23/2022',82.77
```

```
8201,'7/27/2022',69.98
```

```
8202, '8/2/2022', 76.11
8203, '8/8/2022', 25.12
8204, '8/19/2022', 46.23
8205, '9/26/2022', 84.21
8206, '10/14/2022', 96.24
8207, '10/29/2022', 67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension:date.

Create the following measure:

```
=inquartertoday(date, '05/15/2022', 0)
```


Results table

date	=inquartertoday(date,'05/15/2022', 0)
1/7/2022	0
1/19/2022	0
2/5/2022	0
2/28/2022	0
3/16/2022	0
4/1/2022	-1
5/7/2022	-1
5/16/2022	0
6/15/2022	0
6/26/2022	0
7/9/2022	0
7/22/2022	0
7/23/2022	0
7/27/2022	0
8/2/2022	0
8/8/2022	0
8/19/2022	0
9/26/2022	0
10/14/2022	0
10/29/2022	0

## 8 Script and chart functions

The `in_quarter_to_date` measure is created in a chart object by using the `inquartertodate()` function. The first argument is the date field being evaluated. The second argument is a hard-coded date for May 15, which is the `base_date` that identifies which quarter to segment and defines the end boundary of that segment. A `period_no` of 0 is the final argument, meaning that the function is not comparing quarters preceding or following the segmented quarter.

*Diagram of `inquartertodate` function, chart object example*



Any transaction that occurs between April 1 and May 15 returns a Boolean result of `TRUE`. Transactions on May 16 and later will return `FALSE`, as do any transactions before April 1.

### Example 5 – Scenario

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset which is loaded into a table called `Products`.
- Information concerning product ID, manufacture date, and cost price.

On May 15, 2022, a piece of equipment error was identified in the manufacturing process and resolved. Products that were manufactured in that quarter up to this date will be defective. The end user would like a chart object that displays, by quarter name, the status of whether the product is 'defective' or 'faultless' and the cost of the products manufactured in that quarter to date.

#### Load script

```
Products:
Load
*
Inline
[
product_id,manufacture_date,cost_price
8188,'1/19/2022',37.23
8189,'1/7/2022',17.17
8190,'2/28/2022',88.27
8191,'2/5/2022',57.42
```

```
8192, '3/16/2022', 53.80
8193, '4/1/2022', 82.06
8194, '5/7/2022', 40.39
8195, '5/16/2022', 87.21
8196, '6/15/2022', 95.93
8197, '6/26/2022', 45.89
8198, '7/9/2022', 36.23
8199, '7/22/2022', 25.66
8200, '7/23/2022', 82.77
8201, '7/27/2022', 69.98
8202, '8/2/2022', 76.11
8203, '8/8/2022', 25.12
8204, '8/19/2022', 46.23
8205, '9/26/2022', 84.21
8206, '10/14/2022', 96.24
8207, '10/29/2022', 67.67
];
```

### Results

#### Do the following:

1. Load the data and open a sheet. Create a new table. Create a dimension to show the quarter names:  
=quartername(manufacture\_date)
2. Next, create a dimension to identify which of the products are defective and which are faultless:  
=if(inquartertodate(manufacture\_date,makedate(2022,05,15),0), 'Defective', 'Faultless')
3. Create a measure to sum the cost\_price of the products:  
=sum(cost\_price)
4. Set the measure's **Number formatting to Money**.

Results table

quartername (manufacture_date)	if(inquartertodate(manufacture_date,makedate(2022,05,15),0), 'Defective', 'Faultless')	Sum(cost_price)
Jan-Mar 2022	Faultless	\$253.89
Apr-Jun 2022	Faultless	\$229.03
Apr-Jun 2022	Defective	\$122.45
Jul-Sep 2022	Faultless	\$446.31
Oct-Dec 2022	Faultless	\$163.91

The `inquartertodate()` function returns a Boolean value when evaluating the manufacturing dates of each of the products. For those that return a Boolean value of `TRUE`, it marks the products as 'defective'. For any product returning a value of `FALSE`, and therefore not made in the quarter up to and including May 15, it marks the products as 'Faultless'.

## inweek

This function returns True if **timestamp** lies inside the week containing **base\_date**.


### Syntax:

```
InWeek (timestamp, base_date, period_no[, first_week_day])
```

**Return data type:** Boolean

In Qlik Sense, the Boolean true value is represented by -1, and the false value is represented by 0.

*Diagram of inweek() function's range*



The `inweek()` function uses the `base_date` argument to identify which seven-day period the date falls into. The start day of the week is based on the `FirstWeekDay` system variable. However, you can also change the first day of the week by using the `first_week_day` argument of the `inweek()` function.

After the selected week has been defined, the function will return Boolean results when comparing the prescribed date values to that week segment.

### When to use it

The `inweek()` function returns a Boolean result. Typically, this type of function will be used as a condition in an `if` expression. The `inweek()` function returns an aggregation or calculation which depends on whether a date evaluated occurred in the week with the selected date of the `base_date` argument.

For example, the `inweek()` function can be used to identify all equipment manufactured in a specific week.

### Arguments

Argument	Description
<b>timestamp</b>	The date that you want to compare with <b>base_date</b> .
<b>base_date</b>	Date that is used to evaluate the week.



Argument	Description
<b>period_no</b>	The week can be offset by <b>period_no</b> . <b>period_no</b> is an integer, where the value 0 indicates the week which contains <b>base_date</b> . Negative values in <b>period_no</b> indicate preceding weeks and positive values indicate succeeding weeks.
<b>first_week_day</b>	By default, the first day of the week is Sunday (as determined by the FirstWeekDay system variable), starting at midnight between Saturday and Sunday. The <b>first_week_day</b> parameter supersedes the <b>FirstWeekDay</b> variable. To indicate the week starting on another day, specify a flag between 0 and 6.

first\_week\_day values

Day	Value
Monday	0
Tuesday	1
Wednesday	2
Thursday	3
Friday	4
Saturday	5
Sunday	6

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

Function examples

Example	Result
<code>inweek ('01/12/2006', '01/14/2006', 0)</code>	Returns TRUE
<code>inweek ('01/12/2006', '01/20/2006', 0 )</code>	Returns FALSE

Example	Result
inweek ( '01/12/2006', '01/14/2006', -1 )	Returns FALSE
inweek ( '01/07/2006', '01/14/2006', -1)	Returns TRUE
inweek ( '01/12/2006', '01/09/2006', 0, 3)	Returns FALSE because first_week_day is specified as 3 (Thursday), which makes 01/12/2006 the first day of the week following the week containing 01/09/2006.

These topics may help you work with this function:

### Related topics

Topic	Default Flag / Value	Description
<a href="#">FirstWeekDay (page 228)</a>	6 / Sunday	Defines the start day of each week.

### Example 1 - No additional arguments

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions for the month of January 2022 which is loaded into a table called 'Transactions'.
- The firstweekday system variable which is set to 6 (Sunday).
- A preceding load which contains the following:
  - The inweek() function, set as the field 'in\_week' that determines which transactions took place in the week of January 14, 2022.
  - The weekday() function, set as the field 'week\_day' that shows which day of the week corresponds to each date.

#### Load script

```
SET FirstWeekDay=6;
SET DateFormat='MM/DD/YYYY';
```

Transactions:

```
Load
*,
weekday(date) as week_day,
```

```
        inweek(date,'01/14/2022', 0) as in_week
    ;
Load
*
Inline
[
id,date,amount
8188,'01/02/2022',37.23
8189,'01/05/2022',17.17
8190,'01/06/2022',88.27
8191,'01/08/2022',57.42
8192,'01/09/2022',53.80
8193,'01/10/2022',82.06
8194,'01/11/2022',40.39
8195,'01/12/2022',87.21
8196,'01/13/2022',95.93
8197,'01/14/2022',45.89
8198,'01/15/2022',36.23
8199,'01/16/2022',25.66
8200,'01/17/2022',82.77
8201,'01/18/2022',69.98
8202,'01/26/2022',76.11
8203,'01/27/2022',25.12
8204,'01/28/2022',46.23
8205,'01/29/2022',84.21
8206,'01/30/2022',96.24
8207,'01/31/2022',67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- week\_day
- in\_week

Results table

<b>date</b>	<b>week_day</b>	<b>in_week</b>
01/02/2022	Sun	0
01/05/2022	Wed	0
01/06/2022	Thu	0
01/08/2022	Sat	0
01/09/2022	Sun	-1
01/10/2022	Mon	-1
01/11/2022	Tue	-1

<b>date</b>	<b>week_day</b>	<b>in_week</b>
01/12/2022	Wed	-1
01/13/2022	Thu	-1
01/14/2022	Fri	-1
01/15/2022	Sat	-1
01/16/2022	Sun	0
01/17/2022	Mon	0
01/18/2022	Tue	0
01/26/2022	Wed	0
01/27/2022	Thu	0
01/28/2022	Fri	0
01/29/2022	Sat	0
01/30/2022	Sun	0
01/31/2022	Mon	0

The 'in\_week' field is created in the preceding load statement by using the `inweek()` function. The first argument identifies which field is being evaluated. The second argument is a hard-coded date for January 14 which is the `base_date`. The `base_date` argument works in with the `FirstweekDay` system variable to identify the comparator week. A `period_no` of 0 — meaning that the function is not comparing weeks preceding or following the segmented week — is the final argument.

The `FirstweekDay` system variable determines that weeks begin on a Sunday and end on a Saturday. Therefore, January would be broken into weeks according to the diagram below, with the dates between January 9 and 15 providing the valid period for the `inweek()` calculation:

Diagram of calendar with the `inweek()` function's range highlighted

Sun	Mon	Tue	Wed	Thu	Fri	Sat
						1
2	3	4	5	6	7	8
9	10	11	12	13	14	15
16	17	18	19	20	21	22
23	24	25	26	27	28	29
30	31					

Any transaction that occurs between January 9 and the 15 of January returns a Boolean result of `TRUE`.

### Example 2 - `period_no`

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same dataset containing a set of transactions for 2022 is loaded into a table called 'Transactions'.
- The `Firstweekday` system variable which is set to 6 (Sunday).
- A preceding load which contains the following:
  - The `inweek ()` function, set as the field 'prev\_week' that determines which transactions took place a full week before the week of January 14, 2022.

- The `weekday()` function, set as the field 'week\_day' that shows which day of the week corresponds to each date.

### Load script

```
SET FirstWeekDay=6;
SET DateFormat='MM/DD/YYYY';

Transactions:
    Load
        *,
        weekday(date) as week_day,
        inweek(date, '01/14/2022', -1) as prev_week
    ;

Load
*
Inline
[
id,date,amount
8188,'01/02/2022',37.23
8189,'01/05/2022',17.17
8190,'01/06/2022',88.27
8191,'01/08/2022',57.42
8192,'01/09/2022',53.80
8193,'01/10/2022',82.06
8194,'01/11/2022',40.39
8195,'01/12/2022',87.21
8196,'01/13/2022',95.93
8197,'01/14/2022',45.89
8198,'01/15/2022',36.23
8199,'01/16/2022',25.66
8200,'01/17/2022',82.77
8201,'01/18/2022',69.98
8202,'01/26/2022',76.11
8203,'01/27/2022',25.12
8204,'01/28/2022',46.23
8205,'01/29/2022',84.21
8206,'01/30/2022',96.24
8207,'01/31/2022',67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- week\_day
- prev\_week

Results table

<b>date</b>	<b>week_day</b>	<b>prev_week</b>
01/02/2022	Sun	-1
01/05/2022	Wed	-1
01/06/2022	Thu	-1
01/08/2022	Sat	-1
01/09/2022	Sun	0
01/10/2022	Mon	0
01/11/2022	Tue	0
01/12/2022	Wed	0
01/13/2022	Thu	0
01/14/2022	Fri	0
01/15/2022	Sat	0
01/16/2022	Sun	0
01/17/2022	Mon	0
01/18/2022	Tue	0
01/26/2022	Wed	0
01/27/2022	Thu	0
01/28/2022	Fri	0
01/29/2022	Sat	0
01/30/2022	Sun	0
01/31/2022	Mon	0

Using -1 as the `period_no` argument in the `inweek()` function shifts the boundaries of the comparator week back by a full seven days. With a `period_no` of 0 the week would be between January 9 and 15. But in this example, the `period_no` of -1 shifts the start and end boundary of this segment backwards by one week. The date boundaries become January 2 to January 8.

Diagram of calendar with the `inweek()` function's range highlighted

Sun	Mon	Tue	Wed	Thu	Fri	Sat
						1
2	3	4	5	6	7	8
9	10	11	12	13	14	15
16	17	18	19	20	21	22
23	24	25	26	27	28	29
30	31					

Therefore, any transaction that occurs between January 2 and January 8 will return a Boolean result of TRUE.

### Example 3 - first\_week\_day

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same dataset containing a set of transactions for 2022 is loaded into a table called 'Transactions'.
- The `FirstweekDay` system variable which is set to 6 (Sunday).
- A preceding load which contains the following:
  - The `inweek()` function, set as the field 'in\_week' that determines which transactions took place in the week of January 14, 2022.



- The `weekday()` function, set as the field 'week\_day' that shows which day of the week corresponds to each date.

### Load script

```
SET FirstWeekDay=6;
SET DateFormat='MM/DD/YYYY';

Transactions:
  Load
    *,
    weekday(date) as week_day,
    inweek(date,'01/14/2022', 0, 0) as in_week
  ;

Load
*
Inline
[
id,date,amount
8188,'01/02/2022',37.23
8189,'01/05/2022',17.17
8190,'01/06/2022',88.27
8191,'01/08/2022',57.42
8192,'01/09/2022',53.80
8193,'01/10/2022',82.06
8194,'01/11/2022',40.39
8195,'01/12/2022',87.21
8196,'01/13/2022',95.93
8197,'01/14/2022',45.89
8198,'01/15/2022',36.23
8199,'01/16/2022',25.66
8200,'01/17/2022',82.77
8201,'01/18/2022',69.98
8202,'01/26/2022',76.11
8203,'01/27/2022',25.12
8204,'01/28/2022',46.23
8205,'01/29/2022',84.21
8206,'01/30/2022',96.24
8207,'01/31/2022',67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- week\_day
- in\_week

Results table

<b>date</b>	<b>week_day</b>	<b>in_week</b>
01/02/2022	Sun	0
01/05/2022	Wed	0
01/06/2022	Thu	0
01/08/2022	Sat	0
01/09/2022	Sun	0
01/10/2022	Mon	-1
01/11/2022	Tue	-1
01/12/2022	Wed	-1
01/13/2022	Thu	-1
01/14/2022	Fri	-1
01/15/2022	Sat	-1
01/16/2022	Sun	-1
01/17/2022	Mon	0
01/18/2022	Tue	0
01/26/2022	Wed	0
01/27/2022	Thu	0
01/28/2022	Fri	0
01/29/2022	Sat	0
01/30/2022	Sun	0
01/31/2022	Mon	0

Using 0 as the `first_week_day` argument in the `inweek()` function supersedes the `FirstweekDay` system variable and sets Monday as the first day of the week.

Diagram of calendar with the `inweek()` function's range highlighted

Sun	Mon	Tue	Wed	Thu	Fri	Sat
						1
2	3	4	5	6	7	8
9	10	11	12	13	14	15
16	17	18	19	20	21	22
23	24	25	26	27	28	29
30	31					

Therefore, any transaction that occurs between January 10 and 16 will return a Boolean result of TRUE.

### Example 4 - Chart object example

Load script and chart expression

#### Overview

The same dataset and scenario as the first example are used.

However, in this example, the dataset is unchanged and loaded into the application. Create a measure in the results table to determine which transactions took place in the week of January 14, 2022.

#### Load script

```
SET FirstweekDay=6;
SET DateFormat='MM/DD/YYYY';
```

Transactions:

```
Load
*
Inline
[
id,date,amount
8188,'01/02/2022',37.23
8189,'01/05/2022',17.17
8190,'01/06/2022',88.27
8191,'01/08/2022',57.42
8192,'01/09/2022',53.80
8193,'01/10/2022',82.06
8194,'01/11/2022',40.39
8195,'01/12/2022',87.21
8196,'01/13/2022',95.93
8197,'01/14/2022',45.89
8198,'01/15/2022',36.23
8199,'01/16/2022',25.66
8200,'01/17/2022',82.77
8201,'01/18/2022',69.98
8202,'01/26/2022',76.11
8203,'01/27/2022',25.12
8204,'01/28/2022',46.23
8205,'01/29/2022',84.21
8206,'01/30/2022',96.24
8207,'01/31/2022',67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension:

- date

Create the following measures:

- =inweek (date,'01/14/2022',0), to calculate whether transactions took place in the same week as January 14.
- =weekday(date), to show which day of the week corresponds to each date.

Results table

date	week_day	=inweek (date,'01/14/2022',0)
01/02/2022	Sun	0
01/05/2022	Wed	0
01/06/2022	Thu	0
01/08/2022	Sat	0
01/09/2022	Sun	-1
01/10/2022	Mon	-1

<b>date</b>	<b>week_day</b>	<b>=inweek (date,'01/14/2022',0)</b>
01/11/2022	Tue	-1
01/12/2022	Wed	-1
01/13/2022	Thu	-1
01/14/2022	Fri	-1
01/15/2022	Sat	-1
01/16/2022	Sun	0
01/17/2022	Mon	0
01/18/2022	Tue	0
01/26/2022	Wed	0
01/27/2022	Thu	0
01/28/2022	Fri	0
01/29/2022	Sat	0
01/30/2022	Sun	0
01/31/2022	Mon	0

The 'in\_week' measure is created in chart by using the `inweek()` function. The first argument identifies which field is being evaluated. The second argument is a hard-coded date for January 14 which is the `base_date`. The `base_date` argument works in with the `FirstweekDay` system variable to identify the comparator week. A `period_no` of 0 is the final argument.

The `FirstweekDay` system variable determines that weeks begin on a Sunday and end on a Saturday. Therefore, January would be broken into weeks according to the diagram below, with the dates between January 9 and 15 providing the valid period for the `inweek()` calculation:

Diagram of calendar with the `inweek()` function's range highlighted

Sun	Mon	Tue	Wed	Thu	Fri	Sat
						1
2	3	4	5	6	7	8
9	10	11	12	13	14	15
16	17	18	19	20	21	22
23	24	25	26	27	28	29
30	31					

Any transaction that occurs between January 9 and the 15 of January returns a Boolean result of `TRUE`.

### Example 5 - Scenario

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset which is loaded into a table called 'Products'.
- The table contains the following fields:
  - product ID
  - product type
  - manufacture date
  - cost price

It has been identified that due to equipment error, products that were manufactured in the week of January 12 were defective. The end user would like a chart that displays, by week, the status of which products manufactured were 'defective' or 'faultless' and the cost of the products manufactured in that week.

### Load script

```
Products:
Load
*
Inline
[
product_id,manufacture_date,cost_price
8188,'01/02/2022',37.23
8189,'01/05/2022',17.17
8190,'01/06/2022',88.27
8191,'01/08/2022',57.42
8192,'01/09/2022',53.80
8193,'01/10/2022',82.06
8194,'01/11/2022',40.39
8195,'01/12/2022',87.21
8196,'01/13/2022',95.93
8197,'01/14/2022',45.89
8198,'01/15/2022',36.23
8199,'01/16/2022',25.66
8200,'01/17/2022',82.77
8201,'01/18/2022',69.98
8202,'01/26/2022',76.11
8203,'01/27/2022',25.12
8204,'01/28/2022',46.23
8205,'01/29/2022',84.21
8206,'01/30/2022',96.24
8207,'01/31/2022',67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension:

- =weekname(manufacture\_date)

Create the following measures:

- =if(only(inweek(manufacture\_date,makedate(2022,01,12),0)), 'defective', 'Faultless'), to identify which of the products are defective and which are faultless using the inweek() function.
- =sum(cost\_price), to show the sum of the cost of each product.

**Do the following:**

1. Set the measure's **Number Formatting** to **Money**.
2. Under **Appearance**, turn off **Totals**.

Results table

<b>weekname (manufacture_date)</b>	<b>=if(only(inweek(manufacture_date,makedate(2022,01,12),0)), 'Defective','Faultless')</b>	<b>Sum(cost_price)</b>
2022/02	Faultless	200.09
2022/03	Defective	441.51
2022/04	Faultless	178.41
2022/05	Faultless	231.67
2022/06	Faultless	163.91

The `inweek()` function returns a Boolean value when evaluating the manufacturing dates of each of the products. For any product manufactured in the week of January 12, the `inweek()` function returns a Boolean value of TRUE and marks the products as 'Defective'. For any product returning a value of FALSE, and therefore not manufactured in that week, it marks the products as 'Faultless'.

**inweektodate**

This function returns True if **timestamp** lies inside the part of week containing **base\_date** up until and including the last millisecond of **base\_date**.


**Syntax:**

```
InWeekToDate (timestamp, base_date, period_no [, first_week_day])
```

**Return data type:** Boolean



*In Qlik Sense, the Boolean true value is represented by -1, and the false value is represented by 0.*

Diagram of `inweektodate` function



## 8 Script and chart functions

The `inweektoday()` function uses the `base_date` parameter to identify a maximum boundary date of a week segment, as well as its corresponding date for the start of the week, which is based on the `FirstWeekDay` system variable (or user-defined `first_week_day` parameter). Once this week segment has been defined, the function will then return Boolean results when comparing the prescribed date values to that segment.

### When to use it

The `inweektoday()` function returns a Boolean result. Typically, this type of function will be used as a condition in an `if` expression. This will return an aggregation or calculation dependent on whether a date evaluated occurred during the week in question up to and including a particular date.

For example, the `inweektoday()` function can be used to calculate all sales made during a specified week up to a particular date.

#### Arguments

Argument	Description
<b>timestamp</b>	The date that you want to compare with <b>base_date</b> .
<b>base_date</b>	Date that is used to evaluate the week.
<b>period_no</b>	The week can be offset by <b>period_no</b> . <b>period_no</b> is an integer, where the value 0 indicates the week which contains <b>base_date</b> . Negative values in <b>period_no</b> indicate preceding weeks and positive values indicate succeeding weeks.
<b>first_week_day</b>	By default, the first day of the week is Sunday (as determined by the <code>FirstWeekDay</code> system variable), starting at midnight between Saturday and Sunday. The <b>first_week_day</b> parameter supersedes the <b>FirstWeekDay</b> variable. To indicate the week starting on another day, specify a flag between 0 and 6.  For a week starting on Monday and ending on Sunday, use a flag of 0 for Monday, 1 for Tuesday, 2 for Wednesday, 3 for Thursday, 4 for Friday, 5 for Saturday, and 6 for Sunday.

#### Function examples

Example	Interaction
<code>inweektoday('01/12/2006', '01/12/2006', 0)</code>	Returns TRUE.
<code>inweektoday('01/12/2006', '01/11/2006', 0)</code>	Returns FALSE.
<code>inweektoday('01/12/2006', '01/18/2006', -1)</code>	Returns FALSE. Because <code>period_no</code> is specified as -1, the effective data that <code>timestamp</code> is measured against is 01/11/2006.

Example	Interaction
<code>inweektodate ('01/11/2006', '01/12/2006', 0, 3 )</code>	Returns <code>FALSE</code> , since <code>first_week_day</code> is specified as 3 (Thursday), which makes 01/12/2006 the first day of the week following the week containing 01/12/2006.

These topics may help you work with this function:

### Related topics

Topic	Default Flag / Value	Description
<a href="#">FirstWeekDay (page 228)</a>	6 / Sunday	Defines the start day of each week.

## Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET dateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

## Example 1 – No additional arguments

Load script and results

### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions for the month of January 2022, which is loaded into a table called `Transactions`.
- The data field provided in the `timestampFormat='M/D/YYYY h:mm:ss[.fff]'` format.
- The creation of a field, `in_week_to_date`, which determines which transactions took place in the week up until January 14, 2022.
- The creation of an additional field, named `weekday`, using the `weekday()` function. This new field is created to show which day of the week corresponds to each date.

### Load script

```
SET timestampFormat='M/D/YYYY h:mm:ss[.fff]';
SET FirstWeekDay=6;
```

Transactions:

```
Load
    *,
    weekday(date) as week_day,
    inweektodate(date,'01/14/2022', 0) as in_week_to_date
;

Load
*
Inline
[
id,date,amount
8188,'2022-01-02 12:22:06',37.23
8189,'2022-01-05 01:02:30',17.17
8190,'2022-01-06 15:36:20',88.27
8191,'2022-01-08 10:58:35',57.42
8192,'2022-01-09 08:53:32',53.80
8193,'2022-01-10 21:13:01',82.06
8194,'2022-01-11 00:57:13',40.39
8195,'2022-01-12 09:26:02',87.21
8196,'2022-01-13 15:05:09',95.93
8197,'2022-01-14 18:44:57',45.89
8198,'2022-01-15 06:10:46',36.23
8199,'2022-01-16 06:39:27',25.66
8200,'2022-01-17 10:44:16',82.77
8201,'2022-01-18 18:48:17',69.98
8202,'2022-01-26 04:36:03',76.11
8203,'2022-01-27 08:07:49',25.12
8204,'2022-01-28 12:24:29',46.23
8205,'2022-01-30 11:56:56',84.21
8206,'2022-01-30 14:40:19',96.24
8207,'2022-01-31 05:28:21',67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- week\_day
- in\_week\_to\_date

Results table

date	week_day	in_week_to_date
2022-01-02 12:22:06	Sun	0
2022-01-05 01:02:30	Wed	0
2022-01-06 15:36:20	Thu	0
2022-01-08 10:58:35	Sat	0
2022-01-09 08:53:32	Sun	-1

<b>date</b>	<b>week_day</b>	<b>in_week_to_date</b>
2022-01-10 21:13:01	Mon	-1
2022-01-11 00:57:13	Tue	-1
2022-01-12 09:26:02	Wed	-1
2022-01-13 15:05:09	Thu	-1
2022-01-14 18:44:57	Fri	-1
2022-01-15 06:10:46	Sat	0
2022-01-16 06:39:27	Sun	0
2022-01-17 10:44:16	Mon	0
2022-01-18 18:48:17	Tue	0
2022-01-26 04:36:03	Wed	0
2022-01-27 08:07:49	Thu	0
2022-01-28 12:24:29	Fri	0
2022-01-30 11:56:56	Sun	0
2022-01-30 14:40:19	Sun	0
2022-01-31 05:28:21	Mon	0

The `in_week_to_date` field is created in the preceding load statement by using the `inweektodate()` function. The first argument provided identifies which field is being evaluated. The second argument is a hard-coded date for January 14, which is the `base_date` that identifies which week to segment and defines the end boundary of that segment. A `period_no` of 0 is the final argument, meaning that the function is not comparing weeks preceding or following the segmented week.

The `Firstweekday` system variable determines that weeks begin on a Sunday and end on a Saturday. Therefore, January would be broken into weeks according to the diagram below, with the dates between January 9 and 14 providing the valid period for the `inweekdodate()` calculation:

Calendar diagram showing transaction dates which would return a Boolean result of TRUE

Sun	Mon	Tue	Wed	Thur	Fri	Sat
						1
2	3	4	5	6	7	8
9	10	11	12	13	14	15
16	17	18	19	20	21	22
23	24	25	26	27	28	29
30	31					

Any transaction that occurs in between January 9 and 14 returns a Boolean result of TRUE.  
Transactions before and after the dates return a Boolean result of FALSE.

### Example 2 – period\_no

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same dataset and scenario as the first example.
- The creation of a field, `prev_week_to_date`, that determines which transactions took place a full week before the week segment ending on January 14, 2022.
- The creation of an additional field, named `weekday`, using the `weekday()` function. This is to show which day of the week corresponds to each date.

#### Load script

```
SET FirstWeekDay=6;
SET TimestampFormat='M/D/YYYY h:mm:ss[.fff]';
Transactions:
  Load
    *,
    weekday(date) as week_day,
    inweektodate(date,'01/14/2022', -1) as prev_week_to_date
  ;
Load
*
Inline
[
id,date,amount
```

```
8188, '2022-01-02 12:22:06', 37.23
8189, '2022-01-05 01:02:30', 17.17
8190, '2022-01-06 15:36:20', 88.27
8191, '2022-01-08 10:58:35', 57.42
8192, '2022-01-09 08:53:32', 53.80
8193, '2022-01-10 21:13:01', 82.06
8194, '2022-01-11 00:57:13', 40.39
8195, '2022-01-12 09:26:02', 87.21
8196, '2022-01-13 15:05:09', 95.93
8197, '2022-01-14 18:44:57', 45.89
8198, '2022-01-15 06:10:46', 36.23
8199, '2022-01-16 06:39:27', 25.66
8200, '2022-01-17 10:44:16', 82.77
8201, '2022-01-18 18:48:17', 69.98
8202, '2022-01-26 04:36:03', 76.11
8203, '2022-01-27 08:07:49', 25.12
8204, '2022-01-28 12:24:29', 46.23
8205, '2022-01-30 11:56:56', 84.21
8206, '2022-01-30 14:40:19', 96.24
8207, '2022-01-31 05:28:21', 67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- week\_day
- prev\_week\_to\_date

Results table

date	week_day	prev_week_to_date
2022-01-02 12:22:06	Sun	-1
2022-01-05 01:02:30	Wed	-1
2022-01-06 15:36:20	Thu	-1
2022-01-08 10:58:35	Sat	0
2022-01-09 08:53:32	Sun	0
2022-01-10 21:13:01	Mon	0
2022-01-11 00:57:13	Tue	0
2022-01-12 09:26:02	Wed	0
2022-01-13 15:05:09	Thu	0
2022-01-14 18:44:57	Fri	0
2022-01-15 06:10:46	Sat	0

date	week_day	prev_week_to_date
2022-01-16 06:39:27	Sun	0
2022-01-17 10:44:16	Mon	0
2022-01-18 18:48:17	Tue	0
2022-01-26 04:36:03	Wed	0
2022-01-27 08:07:49	Thu	0
2022-01-28 12:24:29	Fri	0
2022-01-30 11:56:56	Sun	0
2022-01-30 14:40:19	Sun	0
2022-01-31 05:28:21	Mon	0

A `period_no` value of -1 indicates that the `inweektoday()` function compares the input quarter segment to the preceding week. The week segment initially equates to between January 9 and January 14. The `period_no` then offsets both the start and end boundary of this segment to one week earlier, causing the date boundaries to become January 2 to January 7.

*Calendar diagram showing transaction dates which would return a Boolean result of TRUE*

Sun	Mon	Tue	Wed	Thu	Fri	Sat
						1
2	3	4	5	6	7	8
9	10	11	12	13	14	15
16	17	18	19	20	21	22
23	24	25	26	27	28	29
30	31					

Therefore, any transaction that occurs between January 2 and 8 (not including January 8 itself) will return a Boolean result of `TRUE`.

### Example 3 – first\_week\_day

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same dataset and scenario as the first example.
- The creation of a field, `in_week_to_date`, that determines which transactions took place in the week up until January 14, 2022.
- The creation of an additional field, named `weekday`, using the `weekday()` function. This is to show which day of the week corresponds to each date.

In this example, we consider Monday as the first day of the week.

### Load script

```
SET FirstWeekDay=6;
SET TimestampFormat='M/D/YYYY h:mm:ss[.fff]';

Transactions:
  Load
    *,
    weekday(date) as week_day,
    inweektodate(date,'01/14/2022', 0, 0) as in_week_to_date
  ;
Load
*
Inline
[
id,date,amount
8188,'2022-01-02 12:22:06',37.23
8189,'2022-01-05 01:02:30',17.17
8190,'2022-01-06 15:36:20',88.27
8191,'2022-01-08 10:58:35',57.42
8192,'2022-01-09 08:53:32',53.80
8193,'2022-01-10 21:13:01',82.06
8194,'2022-01-11 00:57:13',40.39
8195,'2022-01-12 09:26:02',87.21
8196,'2022-01-13 15:05:09',95.93
8197,'2022-01-14 18:44:57',45.89
8198,'2022-01-15 06:10:46',36.23
8199,'2022-01-16 06:39:27',25.66
8200,'2022-01-17 10:44:16',82.77
8201,'2022-01-18 18:48:17',69.98
8202,'2022-01-26 04:36:03',76.11
8203,'2022-01-27 08:07:49',25.12
8204,'2022-01-28 12:24:29',46.23
8205,'2022-01-30 11:56:56',84.21
8206,'2022-01-30 14:40:19',96.24
8207,'2022-01-31 05:28:21',67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- `date`
- `week_day`



- `in_week_to_date`

Results table

<b>date</b>	<b>week_day</b>	<b>in_week_to_date</b>
2022-01-02 12:22:06	Sun	0
2022-01-05 01:02:30	Wed	0
2022-01-06 15:36:20	Thu	0
2022-01-08 10:58:35	Sat	0
2022-01-09 08:53:32	Sun	0
2022-01-10 21:13:01	Mon	-1
2022-01-11 00:57:13	Tue	-1
2022-01-12 09:26:02	Wed	-1
2022-01-13 15:05:09	Thu	-1
2022-01-14 18:44:57	Fri	-1
2022-01-15 06:10:46	Sat	0
2022-01-16 06:39:27	Sun	0
2022-01-17 10:44:16	Mon	0
2022-01-18 18:48:17	Tue	0
2022-01-26 04:36:03	Wed	0
2022-01-27 08:07:49	Thu	0
2022-01-28 12:24:29	Fri	0
2022-01-30 11:56:56	Sun	0
2022-01-30 14:40:19	Sun	0
2022-01-31 05:28:21	Mon	0

By using 0 as the `first_week_day` argument in the `inweektoday()` function, the function argument supersedes the `FirstWeekDay` system variable and sets Monday as the first day of the week.

Calendar diagram showing transaction dates which would return a Boolean result of TRUE

Mon	Tue	Wed	Thu	Fri	Sat	Sun
					1	2
3	4	5	6	7	8	9
10	11	12	13	14	15	16
17	18	19	20	21	22	17
24	25	26	27	28	29	30
31						

Therefore, any transaction that occurs in between January 10 and 14 will return a Boolean result of TRUE, while transactions with dates outside these boundaries will return a value of FALSE.

### Example 4 – Chart object example

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains the same dataset and scenario as the first example. However, in this example, the unchanged dataset is loaded into the application. The calculation that determines which transactions took place in the week up until January 14, 2022 is created as a measure in the chart object.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

Transactions:

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
```

```
8188,'2022-01-02 12:22:06',37.23
```

```
8189,'2022-01-05 01:02:30',17.17
```

```
8190,'2022-01-06 15:36:20',88.27
```

```
8191,'2022-01-08 10:58:35',57.42
```

```
8192,'2022-01-09 08:53:32',53.80
```

```
8193,'2022-01-10 21:13:01',82.06
```

```
8194,'2022-01-11 00:57:13',40.39
```

```
8195, '2022-01-12 09:26:02', 87.21
8196, '2022-01-13 15:05:09', 95.93
8197, '2022-01-14 18:44:57', 45.89
8198, '2022-01-15 06:10:46', 36.23
8199, '2022-01-16 06:39:27', 25.66
8200, '2022-01-17 10:44:16', 82.77
8201, '2022-01-18 18:48:17', 69.98
8202, '2022-01-26 04:36:03', 76.11
8203, '2022-01-27 08:07:49', 25.12
8204, '2022-01-28 12:24:29', 46.23
8205, '2022-01-30 11:56:56', 84.21
8206, '2022-01-30 14:40:19', 96.24
8207, '2022-01-31 05:28:21', 67.67
];
```

### Results

#### Do the following:

1. Load the data and open a sheet. Create a new table and add this field as a dimension: date.
2. To calculate whether transactions took place in the same week up until the 14th of January, create the following measure:  
=inweektoday(date, '01/14/2022', 0)
3. To show which day of the week corresponds to each date, create an additional measure:  
=weekday(date)

Results table

date	week_day	in_week_to_date
2022-01-02 12:22:06	Sun	0
2022-01-05 01:02:30	Wed	0
2022-01-06 15:36:20	Thu	0
2022-01-08 10:58:35	Sat	0
2022-01-09 08:53:32	Sun	-1
2022-01-10 21:13:01	Mon	-1
2022-01-11 00:57:13	Tue	-1
2022-01-12 09:26:02	Wed	-1
2022-01-13 15:05:09	Thu	-1
2022-01-14 18:44:57	Fri	-1
2022-01-15 06:10:46	Sat	0
2022-01-16 06:39:27	Sun	0
2022-01-17 10:44:16	Mon	0

## 8 Script and chart functions

date	week_day	in_week_to_date
2022-01-18 18:48:17	Tue	0
2022-01-26 04:36:03	Wed	0
2022-01-27 08:07:49	Thu	0
2022-01-28 12:24:29	Fri	0
2022-01-30 11:56:56	Sun	0
2022-01-30 14:40:19	Sun	0
2022-01-31 05:28:21	Mon	0

The `in_week_to_date` field is created as a measure in the chart object using the `inweektodate()` function. The first argument provided identifies which field is being evaluated. The second argument is a hard-coded date for January 14, which is the `base_date` that identifies which week to segment and defines the end boundary of that segment. A `period_no` of 0 is the final argument, meaning that the function is not comparing weeks preceding or following the segmented week.

The `Firstweekday` system variable determines that weeks begin on a Sunday and end on a Saturday. Therefore, January would be broken into weeks according to the diagram below, with the dates between January 9 and 14 providing the valid period for the `inweekdodate()` calculation:

*Calendar diagram showing transaction dates which would return a Boolean result of TRUE*

Sun	Mon	Tue	Wed	Thu	Fri	Sat
						1
2	3	4	5	6	7	8
9	10	11	12	13	14	15
16	17	18	19	20	21	22
23	24	25	26	27	28	29
30	31					

Any transaction that occurs in between January 9 and 14 returns a Boolean result of `TRUE`. Transactions before and after the dates return a Boolean result of `FALSE`.

### Example 5 – Scenario

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset which is loaded into a table called `Products`.
- Information concerning product ID, manufacture date, and cost price.

It has been identified that due to equipment error, products that were manufactured in the week of January 12 were defective. The issue was resolved on January 13. The end user would like a chart object that displays, by week, the status of whether the products manufactured are 'defective' or 'faultless', and the cost of the products manufactured in that week.

#### Load script

```
Products:
Load
*
Inline
[
product_id,manufacture_date,cost_price
8188,'2022-01-02 12:22:06',37.23
8189,'2022-01-05 01:02:30',17.17
8190,'2022-01-06 15:36:20',88.27
8191,'2022-01-08 10:58:35',57.42
8192,'2022-01-09 08:53:32',53.80
8193,'2022-01-10 21:13:01',82.06
8194,'2022-01-11 00:57:13',40.39
8195,'2022-01-12 09:26:02',87.21
8196,'2022-01-13 15:05:09',95.93
8197,'2022-01-14 18:44:57',45.89
8198,'2022-01-15 06:10:46',36.23
8199,'2022-01-16 06:39:27',25.66
8200,'2022-01-17 10:44:16',82.77
8201,'2022-01-18 18:48:17',69.98
8202,'2022-01-26 04:36:03',76.11
8203,'2022-01-27 08:07:49',25.12
8204,'2022-01-28 12:24:29',46.23
8205,'2022-01-30 11:56:56',84.21
8206,'2022-01-30 14:40:19',96.24
8207,'2022-01-31 05:28:21',67.67
];
```

## Results

### Do the following:

1. Load the data and open a sheet. Create a new table. Create a dimension to show the week names:  
=weekname(manufacture\_date)
2. Next, create a dimension to identify which of the products are defective and which are faultless:  
=if(inweektodate(manufacture\_date,makedate(2022,01,12),0),'Defective','Faultless')
3. Create a measure to sum the cost\_price of the products:  
=sum(cost\_price)
4. Set the measure's **Number formatting** to **Money**.

Results table

weekname (manufacture_date)	if(inweektodate(manufacture_date,makedate(2022,01,12),0),'Defective','Faultless')	Sum(cost_price)
2022/02	Faultless	\$200.09
2022/03	Defective	\$263.46
2022/03	Faultless	\$178.05
2022/04	Faultless	\$178.41
2022/05	Faultless	\$147.46
2022/06	Faultless	\$248.12

The inweektodate() function returns a Boolean value when evaluating the manufacturing dates of each of the products. For those that return a Boolean value of TRUE, it marks the products as 'defective'. For any product returning a value of FALSE, and therefore not made in the week up to January 12, it marks the products as 'Faultless'.

## inyear

This function returns True if **timestamp** lies inside the year containing **base\_date**.


### Syntax:

```
InYear (timestamp, base_date, period_no [, first_month_of_year])
```

**Return data type:** Boolean

In Qlik Sense, the Boolean true value is represented by -1, and the false value is represented by 0.

Diagram of `inyear()` function's range



The `inyear()` function returns a Boolean result when comparing the selected date values to a year defined by the `base_date`.

### When to use it

The `inyear()` function returns a Boolean result. Typically, this type of function will be used as a condition in an `if` expression. This returns an aggregation or calculation dependent on whether a date evaluated occurred in the year in question. For example, the `inyear()` function can be used to identify all sales that occurred in a defined year.

### Arguments

Argument	Description
<b>timestamp</b>	The date that you want to compare with <b>base_date</b> .
<b>base_date</b>	Date that is used to evaluate the year.
<b>period_no</b>	The year can be offset by <b>period_no</b> . <b>period_no</b> is an integer, where the value 0 indicates the year that contains <b>base_date</b> . Negative values in <b>period_no</b> indicate preceding years, and positive values indicate succeeding years.
<b>first_month_of_year</b>	If you want to work with (fiscal) years not starting in January, indicate a value between 2 and 12 in <b>first_month_of_year</b> .

You can use the following values to set the first month of year in the `first_month_of_year` argument:

`first_month_of_year` values

Month	Value
February	2
March	3
April	4
May	5
June	6
July	7

Month	Value
August	8
September	9
October	10
November	11
December	12

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

#### Function examples

Example	Result
<code>inyear ('01/25/2013', '01/01/2013', 0 )</code>	Returns TRUE
<code>inyear ('01/25/2012', '01/01/2013', 0)</code>	Returns FALSE
<code>inyear ('01/25/2013', '01/01/2013', -1)</code>	Returns FALSE
<code>inyear ('01/25/2012', '01/01/2013', -1 )</code>	Returns TRUE
<code>inyear ('01/25/2013', '01/01/2013', 0, 3)</code>	Returns TRUE  The value of <code>base_date</code> and <code>first_month_of_year</code> specify that timestamp must fall within 01/03/2012 and 02/28/2013
<code>inyear ('03/25/2013', '07/01/2013', 0, 3 )</code>	Returns TRUE



### Example 1 - Basic example

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions between 2020 and 2022 which is loaded into a table called 'Transactions'.
- A preceding load which contains the `inyear()` function that is set as the 'in\_year' field and determines which transactions took place in the same year as July 26, 2021.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
Transactions:
  Load
    *,
    inyear(date,'07/26/2021', 0) as in_year
  ;
Load
*
Inline
[
id,date,amount
8188,'01/13/2020',37.23
8189,'02/26/2020',17.17
8190,'03/27/2020',88.27
8191,'04/16/2020',57.42
8192,'05/21/2020',53.80
8193,'08/14/2020',82.06
8194,'10/07/2020',40.39
8195,'12/05/2020',87.21
8196,'01/22/2021',95.93
8197,'02/03/2021',45.89
8198,'03/17/2021',36.23
8199,'04/23/2021',25.66
8200,'05/04/2021',82.77
8201,'06/30/2021',69.98
8202,'07/26/2021',76.11
8203,'12/27/2021',25.12
8204,'06/06/2022',46.23
8205,'07/18/2022',84.21
8206,'11/14/2022',96.24
8207,'12/12/2022',67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:


- date
- in\_year

Results table

<b>date</b>	<b>in_year</b>
01/13/2020	0
02/26/2020	0
03/27/2020	0
04/16/2020	0
05/21/2020	0
08/14/2020	0
10/07/2020	0
12/05/2020	0
01/22/2021	-1
02/03/2021	-1
03/17/2021	-1
04/23/2021	-1
05/04/2021	-1
06/30/2021	-1
07/26/2021	-1
12/27/2021	-1
06/06/2022	0
07/18/2022	0
11/14/2022	0
12/12/2022	0

The 'in\_year' field is created in the preceding load statement by using the `inyear()` function. The first argument identifies which field is being evaluated. The second argument is a hard-coded date for July 26, 2021 which is the `base_date` that determines the comparator year. A `period_no` of 0 is the final argument meaning that the `inyear()` function does not compare years preceding or following the year.

Diagram of `inyear()` function's range with July 26 as the base date



Any transaction that occurs in 2021 returns a Boolean result of TRUE.

### Example 2 - period\_no

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions between 2020 and 2022 which is loaded into a table called 'transactions'.
- A preceding load which contains the `inyear()` function that is set as the 'previous\_year' field, and determines which transactions took place in the year before the year containing July 26, 2021.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
Transactions:
  Load
    *,
    inyear(date,'07/26/2021', -1) as previous_year
  ;
Load
*
Inline
[
id,date,amount
8188,'01/13/2020',37.23
8189,'02/26/2020',17.17
8190,'03/27/2020',88.27
8191,'04/16/2020',57.42
8192,'05/21/2020',53.80
8193,'08/14/2020',82.06
8194,'10/07/2020',40.39
8195,'12/05/2020',87.21
8196,'01/22/2021',95.93
```

```
8197, '02/03/2021', 45.89
8198, '03/17/2021', 36.23
8199, '04/23/2021', 25.66
8200, '05/04/2021', 82.77
8201, '06/30/2021', 69.98
8202, '07/26/2021', 76.11
8203, '12/27/2021', 25.12
8204, '06/06/2022', 46.23
8205, '07/18/2022', 84.21
8206, '11/14/2022', 96.24
8207, '12/12/2022', 67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- previous\_year


Results table

date	previous_year
01/13/2020	-1
02/26/2020	-1
03/27/2020	-1
04/16/2020	-1
05/21/2020	-1
08/14/2020	-1
10/07/2020	-1
12/05/2020	-1
01/22/2021	0
02/03/2021	0
03/17/2021	0
04/23/2021	0
05/04/2021	0
06/30/2021	0
07/26/2021	0
12/27/2021	0
06/06/2022	0

date	previous_year
07/18/2022	0
11/14/2022	0
12/12/2022	0

Using -1 as the `period_no` argument in the `inyear()` function shifts the boundaries of the comparator year back by a full year. 2021 is initially identified as the comparator year. The `period_no` offsets the comparator year by one, making 2020 the comparator year.

Diagram of `inyear()` function's range with the `period_no` argument set to -1



Therefore, any transaction that occurs in 2020 returns a Boolean result of TRUE.

### Example 3 - first\_month\_of\_year

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions between 2020 and 2022 which is loaded into a table called 'transactions'.
- A preceding load which contains the `inyear()` function that is set as the 'in\_year' field, and determines which transactions took place in the same year as July 26, 2021.

However, in this example, the organizational policy is for March to be the first month of the financial year.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
Transactions:
```

```
Load
    *,
    inyear(date,'07/26/2021', 0, 3) as in_year
;

Load
*
Inline
[
id,date,amount
8188,'01/13/2020',37.23
8189,'02/26/2020',17.17
8190,'03/27/2020',88.27
8191,'04/16/2020',57.42
8192,'05/21/2020',53.80
8193,'08/14/2020',82.06
8194,'10/07/2020',40.39
8195,'12/05/2020',87.21
8196,'01/22/2021',95.93
8197,'02/03/2021',45.89
8198,'03/17/2021',36.23
8199,'04/23/2021',25.66
8200,'05/04/2021',82.77
8201,'06/30/2021',69.98
8202,'07/26/2021',76.11
8203,'12/27/2021',25.12
8204,'06/06/2022',46.23
8205,'07/18/2022',84.21
8206,'11/14/2022',96.24
8207,'12/12/2022',67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- in\_year


Results table

date	in_year
01/13/2020	0
02/26/2020	0
03/27/2020	0
04/16/2020	0
05/21/2020	0
08/14/2020	0
10/07/2020	0

date	in_year
12/05/2020	0
01/22/2021	0
02/03/2021	0
03/17/2021	-1
04/23/2021	-1
05/04/2021	-1
06/30/2021	-1
07/26/2021	-1
12/27/2021	-1
06/06/2022	0
07/18/2022	0
11/14/2022	0
12/12/2022	0

Using 3 as the `first_month_of_year` argument in the `inyear()` function begins the year on March 1 and ends the year at the end of February.

*Diagram of `inyear()` function's range with March set as the first month of the year*



Therefore, any transaction that occurs between March 1, 2021 and March 1, 2022 will return a Boolean result of TRUE.

### Example 4 - Chart object example

Load script and chart expression

#### Overview

The same dataset and scenario as the first example are used.

However, in this example, the dataset is unchanged and loaded into the application. The calculation that determines whether transactions took place in the same year as July 26, 2021 is created as a measure in a chart object of the application.

### Load script

```
SET DateFormat='MM/DD/YYYY';
Transactions:
Load
*
Inline
[
id,date,amount
8188,'01/13/2020',37.23
8189,'02/26/2020',17.17
8190,'03/27/2020',88.27
8191,'04/16/2020',57.42
8192,'05/21/2020',53.80
8193,'08/14/2020',82.06
8194,'10/07/2020',40.39
8195,'12/05/2020',87.21
8196,'01/22/2021',95.93
8197,'02/03/2021',45.89
8198,'03/17/2021',36.23
8199,'04/23/2021',25.66
8200,'05/04/2021',82.77
8201,'06/30/2021',69.98
8202,'07/26/2021',76.11
8203,'12/27/2021',25.12
8204,'06/06/2022',46.23
8205,'07/18/2022',84.21
8206,'11/14/2022',96.24
8207,'12/12/2022',67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension:

- date

To calculate whether transactions took place in the same year as July 26, 2021, create the following measure:

- =inyear(date,'07/26/2021', 0)

Results table


date	=inyear(date,'07/26/2021',0)
01/13/2020	0
02/26/2020	0



date	=inyear(date,'07/26/2021',0)
03/27/2020	0
04/16/2020	0
05/21/2020	0
08/14/2020	0
10/07/2020	0
12/05/2020	0
01/22/2021	-1
02/03/2021	-1
03/17/2021	-1
04/23/2021	-1
05/04/2021	-1
06/30/2021	-1
07/26/2021	-1
12/27/2021	-1
06/06/2022	0
07/18/2022	0
11/14/2022	0
12/12/2022	0

The 'in\_year' field is created in the chart by using the `inyear()` function. The first argument identifies which field is being evaluated. The second argument is a hard-coded date for July 26, 2021 which is the `base_date` that determines the comparator year. A `period_no` of 0 is the final argument meaning that the `inyear()` function does not compare years preceding or following the year.

*Diagram of `inyear()` function's range with July 27 as the base date*



Any transaction that occurs in 2021 returns a Boolean result of TRUE.

### Example 5 - Scenario

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset which is loaded into a table called 'Products'.
- The table contains the following fields:
  - product ID
  - product type
  - manufacture date
  - cost price

The end user would like a chart object that displays, by product type, the cost of the products manufactured in 2021.

#### Load script

```
Products:
Load
*
Inline
[
product_id,product_type,manufacture_date,cost_price
8188,product A,'01/13/2020',37.23
8189,product B,'02/26/2020',17.17
8190,product B,'03/27/2020',88.27
8191,product C,'04/16/2020',57.42
8192,product D,'05/21/2020',53.80
8193,product D,'08/14/2020',82.06
8194,product C,'10/07/2020',40.39
8195,product B,'12/05/2020',87.21
8196,product A,'01/22/2021',95.93
8197,product B,'02/03/2021',45.89
8198,product C,'03/17/2021',36.23
8199,product C,'04/23/2021',25.66
8200,product B,'05/04/2021',82.77
8201,product D,'06/30/2021',69.98
8202,product D,'07/26/2021',76.11
8203,product D,'12/27/2021',25.12
8204,product C,'06/06/2022',46.23
8205,product C,'07/18/2022',84.21
8206,product A,'11/14/2022',96.24
8207,product B,'12/12/2022',67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension:

- product\_type

To calculate the sum of each product that was manufactured in 2021, create the following measure:

- `=sum(if(InYear(manufacture_date,makedate(2021,01,01),0),cost_price,0))`

### Do the following:

1. Set the measure's **Number Formatting** to **Money**.
2. Under **Appearance**, turn off **Totals**.

Results table

product_type	=sum(if(InYear(manufacture_date,makedate(2021,01,01),0),cost_price,0))
product A	\$95.93
product B	\$128.66
product C	\$61.89
product D	\$171.21

The `inyear()` function returns a Boolean value when evaluating the manufacturing dates of each of the products. For any product manufactured in 2021, the `inyear()` function returns a Boolean value of TRUE and shows the sum of the `cost_price`.

### inyeartodate

This function returns True if **timestamp** lies inside the part of year containing **base\_date** up until and including the last millisecond of **base\_date**.

#### Syntax:


```
InYearToDate (timestamp, base_date, period_no[, first_month_of_year])
```

**Return data type:** Boolean



*In Qlik Sense, the Boolean true value is represented by -1, and the false value is represented by 0.*

Diagram of `inyeartodate` function



The `inyeartodate()` function will segment a particular portion of the year with the `base_date`, identifying the maximum allowed date for that year segment. The function then evaluates whether a date field or value falls into this segment and returns a Boolean result.

### Arguments

Argument	Description
<b>timestamp</b>	The date that you want to compare with <b>base_date</b> .
<b>base_date</b>	Date that is used to evaluate the year.
<b>period_no</b>	The year can be offset by <b>period_no</b> . <b>period_no</b> is an integer, where the value 0 indicates the year that contains <b>base_date</b> . Negative values in <b>period_no</b> indicate preceding years, and positive values indicate succeeding years.
<b>first_month_of_year</b>	If you want to work with (fiscal) years not starting in January, indicate a value between 2 and 12 in <b>first_month_of_year</b> .

### When to use it

The `inyeartodate()` function returns a Boolean result. Typically, this type of function will be used as a condition in an `if` expression. This would return an aggregation or calculation dependent on whether a date evaluated occurred in the year up to and including the date in question.

For example, the `inyeartodate()` function can be used to identify all equipment manufactured in a year up to a specific date.

These examples use the date format `MM/DD/YYYY`. The date format is specified in the `SET DateFormat` statement at the top of your data load script. Change the format in the examples to suit your requirements.

### Function examples

Example	Result
<code>inyeartodate ('01/25/2013', '02/01/2013', 0)</code>	Returns <code>TRUE</code> .
<code>inyeartodate ('01/25/2012', '01/01/2013', 0)</code>	Returns <code>FALSE</code> .

Example	Result
<code>inyeartodate</code> ( '01/25/2012', '02/01/2013', -1)	Returns <code>TRUE</code> .
<code>inyeartodate</code> ( '11/25/2012', '01/31/2013', 0, 4 )	Returns <code>TRUE</code> . The value of <code>timestamp</code> falls inside the fiscal year beginning in the fourth month and before the value of <code>base_date</code> .
<code>inyeartodate</code> ( '3/31/2013', '01/31/2013', 0, 4 )	Returns <code>FALSE</code> . Compared with the previous example, the value of <code>timestamp</code> is still inside the fiscal year, but it is after the value of <code>base_date</code> , so it falls outside the part of the year.

## Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

## Example 1 – No additional arguments

Load script and results

### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions between 2020 and 2022, which is loaded into a table called `Transactions`.
- The date field provided in the `DateFormat` system variable (MM/DD/YYYY) format.
- The creation of a field, `in_year_to_date`, that determines which transactions took place in the year up until July 26, 2021.

### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
Load
    *,
    inyeartodate(date,'07/26/2021', 0) as in_year_to_date
;

Load
*
Inline
[
id,date,amount
8188,'01/13/2020',37.23
8189,'02/26/2020',17.17
8190,'03/27/2020',88.27
8191,'04/16/2020',57.42
8192,'05/21/2020',53.80
8193,'06/14/2020',82.06
8194,'08/07/2020',40.39
8195,'09/05/2020',87.21
8196,'01/22/2021',95.93
8197,'02/03/2021',45.89
8198,'03/17/2021',36.23
8199,'04/23/2021',25.66
8200,'05/04/2021',82.77
8201,'06/30/2021',69.98
8202,'07/26/2021',76.11
8203,'07/27/2021',25.12
8204,'06/06/2022',46.23
8205,'07/18/2022',84.21
8206,'11/14/2022',96.24
8207,'12/12/2022',67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- in\_year\_to\_date

Results table

date	in_year_to_date
01/13/2020	0
02/26/2020	0
03/27/2020	0
04/16/2020	0
05/21/2020	0
06/14/2020	0
08/07/2020	0

date	in_year_to_date
09/05/2020	0
01/22/2021	-1
02/03/2021	-1
03/17/2021	-1
04/23/2021	-1
05/04/2021	-1
06/30/2021	-1
07/26/2021	-1
07/27/2021	0
06/06/2022	0
07/18/2022	0
11/14/2022	0
12/12/2022	0

The `in_year_to_date` field is created in the preceding load statement by using the `inyeartodate()` function. The first argument provided identifies which field is being evaluated.

The second argument is a hard-coded date for the for the July 26, 2021, which is the `base_date` that identifies the end boundary of the year segment. A `period_no` of 0 is the final argument, meaning that the function is not comparing years preceding or following the segmented year.

*Diagram of `inyeartodate` function, no additional arguments*



Any transaction that occurs in between January 1 and July 26 returns a Boolean result of `TRUE`. Transactions dates before 2021 and beyond July 26, 2021 return `FALSE`.

### Example 2 – `period_no`

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same dataset and scenario as the first example.
- The creation of a field, `previous_year_to_date`, that determines which transactions took place a full year before the year segment ending on July 26, 2021.

### Load script

```
SET DateFormat='MM/DD/YYYY';
```

Transactions:

```
Load
    *,
    inyeartodate(date,'07/26/2021', -1) as previous_year_to_date
;

Load
*
Inline
[
id,date,amount
8188,'01/13/2020',37.23
8189,'02/26/2020',17.17
8190,'03/27/2020',88.27
8191,'04/16/2020',57.42
8192,'05/21/2020',53.80
8193,'06/14/2020',82.06
8194,'08/07/2020',40.39
8195,'09/05/2020',87.21
8196,'01/22/2021',95.93
8197,'02/03/2021',45.89
8198,'03/17/2021',36.23
8199,'04/23/2021',25.66
8200,'05/04/2021',82.77
8201,'06/30/2021',69.98
8202,'07/26/2021',76.11
8203,'07/27/2021',25.12
8204,'06/06/2022',46.23
8205,'07/18/2022',84.21
8206,'11/14/2022',96.24
8207,'12/12/2022',67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- previous\_year\_to\_date




Results table

date	previous_year_to_date
01/13/2020	-1
02/26/2020	-1
03/27/2020	-1
04/16/2020	-1
05/21/2020	-1
06/14/2020	-1
08/07/2020	0
09/05/2020	0
01/22/2021	0
02/03/2021	0
03/17/2021	0
04/23/2021	0
05/04/2021	0
06/30/2021	0
07/26/2021	0
07/27/2021	0
06/06/2022	0
07/18/2022	0
11/14/2022	0
12/12/2022	0

A `period_no` value of -1 indicates that the `inyeartodate` ( ) function compares the input quarter segment to the preceding year. With an input date of July 26, 2021, the segment from January 1, 2021 to July 26, 2021 was initially identified as the year-to-date. The `period_no` then offsets this segment by a full year earlier, causing the date boundaries to become January 1 to July 26, 2020.

*Diagram of inyeartodate function, period\_no example*



Therefore, any transaction that occurs between January 1 and July 26, 2020 will return a Boolean result of `TRUE`.

### Example 3 – `first_month_of_year`

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same dataset and scenario as the first example.
- The creation of a field, `in_year_to_date`, that determines which transactions took place in the same year up to July 26, 2021.

In this example, we set March as the first month of the fiscal year.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
    Load
        *,
        inyeartodate(date, '07/26/2021', 0,3) as in_year_to_date
    ;

Load
*
Inline
[
id,date,amount
8188, '01/13/2020', 37.23
8189, '02/26/2020', 17.17
8190, '03/27/2020', 88.27
8191, '04/16/2020', 57.42
8192, '05/21/2020', 53.80
8193, '06/14/2020', 82.06
8194, '08/07/2020', 40.39
8195, '09/05/2020', 87.21
8196, '01/22/2021', 95.93
8197, '02/03/2021', 45.89
8198, '03/17/2021', 36.23
8199, '04/23/2021', 25.66
8200, '05/04/2021', 82.77
8201, '06/30/2021', 69.98
8202, '07/26/2021', 76.11
8203, '07/27/2021', 25.12
8204, '06/06/2022', 46.23
8205, '07/18/2022', 84.21
8206, '11/14/2022', 96.24
```

```
8207, '12/12/2022', 67.67  
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:


- date
- in\_year\_to\_date

Results table

date	in_year_to_date
01/13/2020	0
02/26/2020	0
03/27/2020	0
04/16/2020	0
05/21/2020	0
06/14/2020	0
08/07/2020	0
09/05/2020	0
01/22/2021	0
02/03/2021	0
03/17/2021	-1
04/23/2021	-1
05/04/2021	-1
06/30/2021	-1
07/26/2021	-1
07/27/2021	0
06/06/2022	0
07/18/2022	0
11/14/2022	0
12/12/2022	0

By using 3 as the `first_month_of_year` argument in the `inyeartodate()` function, the function begins the year on March 1. The `base_date` of July 26, 2021 then sets the end date for that year segment.

Diagram of `inyeartodate` function, `first_month_of_year` example



Therefore, any transaction that occurs between March 1 and July 26, 2021 will return a Boolean result of `TRUE`, while transactions with dates outside these boundaries will return a value of `FALSE`.

### Example 4 – Chart object example

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains the same dataset and scenario as the first example. However, in this example, the unchanged dataset is loaded into the application. The calculation that determines which transactions took place in the same year up to July 26, 2021 is created as a measure in a chart object in the application.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
```

```
8188,'01/13/2020',37.23
```

```
8189,'02/26/2020',17.17
```

```
8190,'03/27/2020',88.27
```

```
8191,'04/16/2020',57.42
```

```
8192,'05/21/2020',53.80
```

```
8193,'06/14/2020',82.06
```

```
8194,'08/07/2020',40.39
```

```
8195,'09/05/2020',87.21
```

```
8196,'01/22/2021',95.93
```

```
8197,'02/03/2021',45.89
```

```
8198,'03/17/2021',36.23
```

```
8199,'04/23/2021',25.66
```

```
8200,'05/04/2021',82.77
```

```
8201,'06/30/2021',69.98
```

```
8202,'07/26/2021',76.11
```

```
8203,'07/27/2021',25.12
```

```
8204, '06/06/2022', 46.23
8205, '07/18/2022', 84.21
8206, '11/14/2022', 96.24
8207, '12/12/2022', 67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension:date.

Create the following measure:

```
=inyeartodate(date, '07/26/2021', 0)
```

Results table

<b>date</b>	<b>=inyeartodate(date, '07/26/2021', 0)</b>
01/13/2020	0
02/26/2020	0
03/27/2020	0
04/16/2020	0
05/21/2020	0
06/14/2020	0
08/07/2020	0
09/05/2020	0
01/22/2021	-1
02/03/2021	-1
03/17/2021	-1
04/23/2021	-1
05/04/2021	-1
06/30/2021	-1
07/26/2021	-1
07/27/2021	0
06/06/2022	0
07/18/2022	0
11/14/2022	0
12/12/2022	0

The `in_year_to_date` measure is created in the chart object by using the `inyeartodate()` function. The first argument provided identifies which field is being evaluated. The second argument is a hard-coded date for July 26, 2021, which is the `base_date` that identifies the end boundary of the comparator year segment. A `period_no` of 0 is the final argument, meaning that the function is not comparing years preceding or following the segmented year.

*Diagram of inyeartodate function, chart object example*



Any transaction that occurs between January 1 and July 26, 2021 returns a Boolean result of `TRUE`. Transaction dates before 2021 and after July 26, 2021 return `FALSE`.

### Example 5 – Scenario

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset which is loaded into a table called `Products`.
- Information concerning product ID, product type, manufacture date, and cost price.

The end user would like a chart object that displays, by product type, the cost of the products manufactured in 2021 up to July 26.

#### Load script

```
Products:
Load
*
Inline
[
product_id,product_type,manufacture_date,cost_price
8188,product A,'01/13/2020',37.23
8189,product B,'02/26/2020',17.17
8190,product B,'03/27/2020',88.27
8191,product C,'04/16/2020',57.42
8192,product D,'05/21/2020',53.80
8193,product D,'08/14/2020',82.06
8194,product C,'10/07/2020',40.39
8195,product B,'12/05/2020',87.21
8196,product A,'01/22/2021',95.93
```

```
8197,product B,'02/03/2021',45.89
8198,product C,'03/17/2021',36.23
8199,product C,'04/23/2021',25.66
8200,product B,'05/04/2021',82.77
8201,product D,'06/30/2021',69.98
8202,product D,'07/26/2021',76.11
8203,product D,'12/27/2021',25.12
8204,product C,'06/06/2022',46.23
8205,product C,'07/18/2022',84.21
8206,product A,'11/14/2022',96.24
8207,product B,'12/12/2022',67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension:product\_type.

Create a measure that calculates the sum of each product that was manufactured in 2021 before July 27:

```
=sum(if(inyeartodate(manufacture_date,makedate(2021,07,26)),0),cost_price,0))
```

Set the measure's **Number formatting** to **Money**.

Results table

product_type	=sum(if(inyeartodate(manufacture_date,makedate(2021,07,26)),0),cost_price,0))
product A	\$95.93
product B	\$128.66
product C	\$61.89
product D	\$146.09

The `inyeartodate()` function returns a Boolean value when evaluating the manufacturing dates of each of the products. For any product manufactured in 2021 before July 27, the `inyeartodate()` function returns a Boolean value of `TRUE` and sums the `cost_price`.

Product D is the only product that was also manufactured after July 26th in 2021. The entry with `product_ID` 8203 was manufactured on December 27 and cost \$25.12. Therefore, this cost was not included in the total for Product D in the chart object.

### lastworkdate

The **lastworkdate** function returns the earliest ending date to achieve **no\_of\_workdays** (Monday-Friday) if starting at **start\_date** taking into account any optionally listed **holiday**. **start\_date** and **holiday** should be valid dates or timestamps.

#### Syntax:

```
lastworkdate(start_date, no_of_workdays {, holiday})
```

**Return data type:** integer

*A calendar that shows how the `lastworkdate()` function is used*

Sun	Mon	Tue	Wed	Thu	Fri	Sat
	1	2	3	4	5	6
7	8	9	10 start_date	11	12	13
14	15	16	17	18	19	20
21	22	23	24	25	26 end_date	27
28	29	30	31			

### Limitations

There is no method to modify the `lastworkdate()` function for regions or scenarios that involve anything other than a work week that begins on Monday and ends on Friday.

The holiday parameter must be a string constant. It does not accept an expression.

### When to use it

The `lastworkdate()` function is commonly used as part of an expression when the user would like to calculate the proposed end date of a project or assignment, based on when the project begins and the holidays that will occur in that period.

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.



Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Arguments

Argument	Description
<b>start_date</b>	The start date to evaluate.
<b>no_of_workdays</b>	The number of working days to achieve.
<b>holiday</b>	Holiday periods to exclude from working days. A holiday is stated as a string constant date. You can specify multiple holiday dates, separated by commas.  <b>Example:</b> '12/25/2013', '12/26/2013', '12/31/2013', '01/01/2014'

### Example 1 - Basic example

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing project IDs, project start dates, and the estimated effort, in days, required for the projects. The dataset is loaded into a table called 'Projects'.
- A preceding load which contains the `Lastworkdate()` function which is set as the field 'end\_date' and identifies when each project is scheduled to end.

#### Load script

```
SET DateFormat='MM/DD/YYYY';

Projects:
  Load
    *,
    Lastworkdate(start_date,effort) as end_date
  ;

Load
id,
start_date,
effort
Inline
[
id,start_date,effort
1,01/01/2022,14
```

```
2,02/10/2022,17  
3,05/17/2022,5  
4,06/01/2022,12  
5,08/10/2022,26  
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- id
- start\_date
- effort
- end\_date

Results table

id	start_date	effort	end_date
1	01/01/2022	14	01/20/2022
2	02/10/2022	17	03/04/2022
3	05/17/2022	5	05/23/2022
4	06/01/2022	12	06/16/2022
5	08/10/2022	26	09/14/2022

Because there are no scheduled holidays, the function adds the defined number of working days, Monday to Friday, to the start date to find the earliest possible end date.

The following calendar shows the start and end date for project 3, with the working days highlighted in green.

A calendar that shows the start and end date of project 3

Sun	Mon	Tue	Wed	Thu	Fri	Sat
1	2	3	4	5	6	7
8	9	10	11	12	13	14
15	16	17 Start Date	18	19	20	21
22	23 End Date	24	25	26	27	28
29	30	31				

### Example 2 - Single holiday

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing project IDs, project start dates, and the estimated effort, in days, required for the projects. The dataset is loaded into a table called 'Projects'.
- A preceding load which contains the `lastworkdate()` function which is set as the field 'end\_date' and identifies when each project is scheduled to end.

However, there is one holiday scheduled on May 18, 2022. The `lastworkdate()` function in the preceding load includes the holiday in its third argument to identify when each project is scheduled to end.

### Load script

```
SET DateFormat='MM/DD/YYYY';

Projects:
  Load
    *,
    LastWorkDate(start_date,effort, '05/18/2022') as end_date
  ;
Load
id,
start_date,
effort
Inline
[
id,start_date,effort
1,01/01/2022,14
2,02/10/2022,17
3,05/17/2022,5
4,06/01/2022,12
5,08/10/2022,26
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- id
- start\_date
- effort
- end\_date

Results table

id	start_date	effort	end_date
1	01/01/2022	14	01/20/2022
2	02/10/2022	17	03/04/2022
3	05/17/2022	5	05/24/2022
4	06/01/2022	12	06/16/2022
5	08/10/2022	26	09/14/2022

The single scheduled holiday is entered as the third argument in the `LastWorkDate()` function. As a result, the end date for project 3 is shifted one day later because the holiday takes place on one of the working days before the end date.

The following calendar shows the start and end date for project 3 and shows that the holiday changes the end date of the project by one day.

## 8 Script and chart functions

A calendar that shows the start and end date of project 3 with a holiday on May 18

Sun	Mon	Tue	Wed	Thu	Fri	Sat
1	2	3	4	5	6	7
8	9	10	11	12	13	14
15	16	17 Start Date	18 Holiday	19	20	21
22	23	24 End Date	25	26	27	28
29	30	31				

### Example 3 - Multiple holidays

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing project IDs, project start dates, and the estimated effort, in days, required for the projects. The dataset is loaded into a table called 'projects'.
- A preceding load which contains the `lastworkdate()` function which is set as the field 'end\_date' and identifies when each project is scheduled to end.

However, there are three holidays scheduled for May 19, 20, 21, and 22. The `lastworkdate()` function in the preceding load includes each of the holidays in its third argument to identify when each project is scheduled to end.

### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Projects:
```

```
    Load
        *,
        LastWorkDate(start_date,effort, '05/19/2022','05/20/2022','05/21/2022','05/22/2022') as
    end_date
    ;
Load
id,
start_date,
effort
Inline
[
id,start_date,effort
1,01/01/2022,14
2,02/10/2022,17
3,05/17/2022,5
4,06/01/2022,12
5,08/10/2022,26
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- id
- start\_date
- effort
- end\_date

Results table

id	start_date	effort	end_date
1	01/01/2022	14	01/20/2022
2	02/10/2022	17	03/04/2022
3	05/17/2022	5	05/25/2022
4	06/01/2022	12	06/16/2022
5	08/10/2022	26	09/14/2022

The four holidays are entered as a list of arguments in the `Lastworkdate()` function after the start date and number of working days.

The following calendar shows the start and end date for project 3 and shows that the holidays change the end date of the project by three days.

A calendar that shows the start and end date of project 3 with holidays from May 19 to 22

Sun	Mon	Tue	Wed	Thu	Fri	Sat
1	2	3	4	5	6	7
8	9	10	11	12	13	14
15	16	17 Start Date	18	19 Holiday	20 Holiday	21 Holiday
22 Holiday	23	24	25 End Date	26	27	28
29	30	31				

### Example 4 - Single holiday (chart)

Load script and chart expression

#### Overview

The same dataset and scenario as the first example are used.

However, in this example, the dataset is unchanged and loaded into the app. The end\_date field is calculated as a measure in a chart.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

Projects:

```
Load
id,
start_date,
effort
inline
[
```

```
id,start_date,effort
1,01/01/2022,14
2,02/10/2022,17
3,05/17/2022,5
4,06/01/2022,12
5,08/10/2022,26
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- id
- start\_date
- effort

To calculate the end\_date, create the following measure:

- =LastWorkDate(start\_date,effort,'05/18/2022')

Results table

id	start_date	effort	=LastWorkDate(start_date,effort,'05/18/2022')
1	01/01/2022	14	01/20/2022
2	02/10/2022	17	03/04/2022
3	05/17/2022	5	05/23/2022
4	06/01/2022	12	06/16/2022
5	08/10/2022	26	09/14/2022

The single scheduled holiday is entered as a measure in the chart. As a result, the end date for project 3 is shifted one day later because the holiday takes place on one of the working days before the end date.

The following calendar shows the start and end date for project 3 and shows that the holiday changes the end date of the project by one day.



## 8 Script and chart functions

A calendar that shows the start and end date of project 3 with a holiday on May 18

Sun	Mon	Tue	Wed	Thu	Fri	Sat
1	2	3	4	5	6	7
8	9	10	11	12	13	14
15	16	17 Start Date	18 Holiday	19	20	21
22	23	24 End Date	25	26	27	28
29	30	31				

### localtime


This function returns a timestamp of the current time for a specified time zone.

#### Syntax:

```
LocalTime([timezone [, ignoreDST ]])
```

**Return data type:** dual

#### Arguments

Argument	Description
<b>timezone</b>	<p>The <b>timezone</b> is specified as a string containing any of the geographical places listed under <b>Time Zone</b> in the <b>Windows Control Panel</b> for <b>Date and Time</b> or as a string in the form 'GMT+hh:mm'. A list of accepted places and time zones is also presented in the table below.</p> <p>If no time zone is specified, the local time is returned.</p> <div style="border: 1px solid gray; padding: 10px; margin-top: 10px;"> <p> <i>If you use a DST offset (that is, you specify an <b>ignoreDST</b> argument value evaluating to False), you must specify a place, rather than a GMT offset, in the <b>place</b> argument. This is because adjusting for Daylight Saving Time requires latitudinal information in addition to the longitudinal information provided by a GMT offset. For more information, see <i>Using GMT offsets in combination with DST</i> (page 852).</i></p> </div>
<b>ignoreDST</b>	<p>If this argument evaluates to True, DST (daylight saving time) is ignored. Valid argument values evaluating to True include -1 and <code>true()</code>.</p> <p>If this argument evaluates to False, the timestamp is adjusted for daylight saving time. Valid argument values evaluating to False include 0 and <code>false()</code>.</p> <p>If the <b>ignoreDST</b> argument value is invalid, the function evaluates the expression as if the <b>ignore_dst</b> value evaluates to True. If the <b>ignoreDST</b> argument value is not specified, the function evaluates the expression as if the <b>ignore_dst</b> value evaluates to False.</p>

#### Valid places and time zones

A-C	D-K	L-R	S-Z
Abu Dhabi	Darwin	La Paz	Samoa
Adelaide	Dhaka	Lima	Santiago
Alaska	Eastern Time (US & Canada)	Lisbon	Sapporo
Amsterdam	Edinburgh	Ljubljana	Sarajevo
Arizona	Ekaterinburg	London	Saskatchewan
Astana	Fiji	Madrid	Seoul
Athens	Georgetown	Magadan	Singapore

## 8 Script and chart functions

<b>A-C</b>	<b>D-K</b>	<b>L-R</b>	<b>S-Z</b>
Atlantic Time (Canada)	Greenland	Mazatlan	Skopje
Auckland	Greenwich Mean Time : Dublin	Melbourne	Sofia
Azores	Guadalajara	Mexico City	Solomon Is.
Baghdad	Guam	Mid-Atlantic	Sri Jayawardenepura
Baku	Hanoi	Minsk	St. Petersburg
Bangkok	Harare	Monrovia	Stockholm
Beijing	Hawaii	Monterrey	Sydney
Belgrade	Helsinki	Moscow	Taipei
Berlin	Hobart	Mountain Time (US & Canada)	Tallinn
Bern	Hong Kong	Mumbai	Tashkent
Bogota	Indiana (East)	Muscat	Tbilisi
Brasilia	International Date Line West	Nairobi	Tehran
Bratislava	Irkutsk	New Caledonia	Tokyo
Brisbane	Islamabad	New Delhi	Urumqi
Brussels	Istanbul	Newfoundland	Warsaw
Bucharest	Jakarta	Novosibirsk	Wellington
Budapest	Jerusalem	Nuku'alofa	West Central Africa
Buenos Aires	Kabul	Osaka	Vienna
Cairo	Kamchatka	Pacific Time (US & Canada)	Vilnius
Canberra	Karachi	Paris	Vladivostok
Cape Verde Is.	Kathmandu	Perth	Volgograd
Caracas	Kolkata	Port Moresby	Yakutsk
Casablanca	Krasnoyarsk	Prague	Yerevan
Central America	Kuala Lumpur	Pretoria	Zagreb
Central Time (US & Canada)	Kuwait	Quito	-
Chennai	Kyiv	Riga	-

A-C	D-K	L-R	S-Z
Chihuahua	-	Riyadh	-
Chongqing	-	Rome	-
Copenhagen	-	-	-

### Examples and results:

The examples below are based on the function being called on 2023-08-14 08:39:47 local time, with the local time zone of the server or desktop environment being GMT-05:00, and in a region which has implemented daylight saving time as of this listed date.

#### Scripting examples

Example	Result
<code>localtime ()</code>	Returns the local time 2023-08-14 08:39:47.
<code>localtime ('London')</code>	Returns the local time in London, 2023-08-14 13:39:47.
<code>localtime ('GMT+02:00')</code>	Returns the local time in the timezone of GMT+02:00, 2023-08-14 14:39:47. No adjustment is made for daylight saving time because a GMT offset, rather than a place, is specified.
<code>localtime ('Paris',-1)</code>	Returns the local time in Paris with daylight savings time ignored, 2023-08-14 13:39:47.
<code>localtime ('Paris',True())</code>	Returns the local time in Paris with daylight savings time ignored, 2023-08-14 13:39:47.
<code>localtime ('Paris',0)</code>	Returns the local time in Paris, taking daylight savings time into account, 2023-08-14 14:39:47.
<code>localtime ('Paris',False ())</code>	Returns the local time in Paris, taking daylight savings time into account, 2023-08-14 14:39:47.

### Using GMT offsets in combination with DST

Following the implementation of International Components for Unicode (ICU) libraries in Qlik Sense, the use of GMT (Greenwich Mean Time) offsets in combination with DST (Daylight Saving Time) requires additional latitudinal information.

GMT is a longitudinal (east-west) offset, whereas DST is a latitudinal (north-south) offset. For example, Helsinki (Finland) and Johannesburg (South Africa) share the same GMT+02:00 offset, but they do not share the same DST offset. This means that, further to the GMT offset, any DST offset requires information on the latitudinal position of the local time zone (geographical time zone input) in order to have full information about local DST conditions.

## lunarweekend

This function returns a value corresponding to a timestamp of the last millisecond of the last day of the lunar week containing **date**. Lunar weeks in Qlik Sense are defined by counting January 1 as the first day of the week and, apart from the final week of the year, will contain exactly seven days.

### Syntax:

```
LunarweekEnd(date[, period_no[, first_week_day]])
```

**Return data type:** dual

*Example diagram of lunarweekend() function*



The `lunarweekend()` function determines which lunar week the date falls into. It then returns a timestamp, in date format, for the last millisecond of that week.

### Arguments

Argument	Description
<b>date</b>	The date or timestamp to evaluate.
<b>period_no</b>	<b>period_no</b> is an integer or expression resolving to an integer, where the value 0 indicates the lunar week which contains <b>date</b> . Negative values in <b>period_no</b> indicate preceding lunar weeks and positive values indicate succeeding lunar weeks.
<b>first_week_day</b>	An offset that may be greater than or less than zero. This changes the beginning of the year by the specified number of days and/or fractions of a day.

### When to use it

The `lunarweekend()` function is commonly used as part of an expression when the user would like the calculation to use the fraction of the week that has not yet occurred. Unlike the `weekend()` function, the final lunar week of each calendar year will end on December 31. For example, the `lunarweekend()` function can be used to calculate interest not yet incurred during the week.

### Function examples

Example	Result
<code>lunarweekend('01/12/2013')</code>	Returns 01/14/2013 23:59:59.

Example	Result
<code>lunarweekend('01/12/2013', -1)</code>	Returns 01/07/2013 23:59:59.
<code>lunarweekend('01/12/2013', 0, 1)</code>	Returns 01/15/2013 23:59:59.

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Example 1 – No additional arguments

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions for 2022, which is loaded into a table called Transactions.
- The date field provided in the `DateFormat` system variable (MM/DD/YYYY) format.
- The creation of a field, `end_of_week`, that returns a timestamp for the end of the lunar week in which the transactions took place.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
  Load
    *,
    lunarweekend(date) as end_of_week,
    timestamp(lunarweekend(date)) as end_of_week_timestamp
  ;

Load
*
Inline
[
id,date,amount
```

```
8188,1/7/2022,17.17
8189,1/19/2022,37.23
8190,2/28/2022,88.27
8191,2/5/2022,57.42
8192,3/16/2022,53.80
8193,4/1/2022,82.06
8194,5/7/2022,40.39
8195,5/16/2022,87.21
8196,6/15/2022,95.93
8197,6/26/2022,45.89
8198,7/9/2022,36.23
8199,7/22/2022,25.66
8200,7/23/2022,82.77
8201,7/27/2022,69.98
8202,8/2/2022,76.11
8203,8/8/2022,25.12
8204,8/19/2022,46.23
8205,9/26/2022,84.21
8206,10/14/2022,96.24
8207,10/29/2022,67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- end\_of\_week
- end\_of\_week\_timestamp

Results table


date	end_of_week	end_of_week_timestamp
1/7/2022	01/07/2022	1/7/2022 11:59:59 PM
1/19/2022	01/21/2022	1/21/2022 11:59:59 PM
2/5/2022	02/11/2022	2/11/2022 11:59:59 PM
2/28/2022	03/04/2022	3/4/2022 11:59:59 PM
3/16/2022	03/18/2022	3/18/2022 11:59:59 PM
4/1/2022	04/01/2022	4/1/2022 11:59:59 PM
5/7/2022	05/13/2022	5/13/2022 11:59:59 PM
5/16/2022	05/20/2022	5/20/2022 11:59:59 PM
6/15/2022	06/17/2022	6/17/2022 11:59:59 PM
6/26/2022	07/01/2022	7/1/2022 11:59:59 PM
7/9/2022	07/15/2022	7/15/2022 11:59:59 PM

date	end_of_week	end_of_week_timestamp
7/22/2022	07/22/2022	7/22/2022 11:59:59 PM
7/23/2022	07/29/2022	7/29/2022 11:59:59 PM
7/27/2022	07/29/2022	7/29/2022 11:59:59 PM
8/2/2022	08/05/2022	8/5/2022 11:59:59 PM
8/8/2022	08/12/2022	8/12/2022 11:59:59 PM
8/19/2022	08/19/2022	8/19/2022 11:59:59 PM
9/26/2022	09/30/2022	9/30/2022 11:59:59 PM
10/14/2022	10/14/2022	10/14/2022 11:59:59 PM
10/29/2022	11/04/2022	11/4/2022 11:59:59 PM

The `end_of_week` field is created in the preceding load statement by using the `lunarweekend()` function, and passing the `date` field as the function's argument.

The `lunarweekend()` function identifies which lunar week the date value falls into, returning a timestamp for the last millisecond of that week.

*Diagram of `lunarweekend()` function, example with no additional arguments*



Transaction 8189 took place on January 19. The `lunarweekend()` function identifies that the lunar week begins on January 15. Therefore, the `end_of_week` value for that transaction returns the last millisecond of the lunar week, which is January 21 at 11:59:59 PM.

### Example 2 – `period_no`

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:



- The same dataset and scenario as the first example.
- The creation of a field, `previous_lunar_week_end`, that returns the timestamp for the end of the lunar week before the transaction took place.

### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
Load
```

```
*,
```

```
lunarweekend(date,-1) as previous_lunar_week_end,
```

```
timestamp(lunarweekend(date,-1)) as previous_lunar_week_end_timestamp
```

```
;
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
```

```
8188,1/7/2022,17.17
```

```
8189,1/19/2022,37.23
```

```
8190,2/28/2022,88.27
```

```
8191,2/5/2022,57.42
```

```
8192,3/16/2022,53.80
```

```
8193,4/1/2022,82.06
```

```
8194,5/7/2022,40.39
```

```
8195,5/16/2022,87.21
```

```
8196,6/15/2022,95.93
```

```
8197,6/26/2022,45.89
```

```
8198,7/9/2022,36.23
```

```
8199,7/22/2022,25.66
```

```
8200,7/23/2022,82.77
```

```
8201,7/27/2022,69.98
```

```
8202,8/2/2022,76.11
```

```
8203,8/8/2022,25.12
```

```
8204,8/19/2022,46.23
```

```
8205,9/26/2022,84.21
```

```
8206,10/14/2022,96.24
```

```
8207,10/29/2022,67.67
```

```
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:


- `date`
- `previous_lunar_week_end`
- `previous_lunar_week_end_timestamp`

Results table

<b>date</b>	<b>previous_lunar_week_end</b>	<b>previous_lunar_week_end_timestamp</b>
1/7/2022	12/31/2021	12/31/2021 11:59:59 PM
1/19/2022	01/14/2022	1/14/2022 11:59:59 PM
2/5/2022	02/04/2022	2/4/2022 11:59:59 PM
2/28/2022	02/25/2022	2/25/2022 11:59:59 PM
3/16/2022	03/11/2022	3/18/2022 11:59:59 PM
4/1/2022	03/25/2022	3/25/2022 11:59:59 PM
5/7/2022	05/06/2022	5/6/2022 11:59:59 PM
5/16/2022	05/13/2022	5/13/2022 11:59:59 PM
6/15/2022	06/10/2022	6/10/2022 11:59:59 PM
6/26/2022	06/24/2022	6/24/2022 11:59:59 PM
7/9/2022	07/08/2022	7/8/2022 11:59:59 PM
7/22/2022	07/15/2022	7/15/2022 11:59:59 PM
7/23/2022	07/22/2022	7/22/2022 11:59:59 PM
7/27/2022	07/22/2022	7/22/2022 11:59:59 PM
8/2/2022	07/29/2022	7/29/2022 11:59:59 PM
8/8/2022	08/05/2022	8/5/2022 11:59:59 PM
8/19/2022	08/12/2022	8/12/2022 11:59:59 PM
9/26/2022	09/23/2022	9/23/2022 11:59:59 PM
10/14/2022	10/07/2022	10/7/2022 11:59:59 PM
10/29/2022	10/28/2022	10/28/2022 11:59:59 PM

In this instance, because a `period_no` of -1 was used as the offset argument in the `lunarweekend()` function, the function first identifies the lunar week in which the transactions took place. It then shifts one week prior and identifies the final millisecond of that lunar week.

Diagram of `lunarweekend()` function, `period_no` example



Transaction 8189 took place on January 19. The `lunarweekend()` function identifies that the lunar week begins on January 15. Therefore, the previous lunar week began on the January 8 and ended on January 14 at 11:59:59 PM; this is the value that is returned for the `previous_lunar_week_end` field.

### Example 3 – `first_week_day`

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains the same dataset and scenario as the first example. In this example, we set lunar weeks to begin on January 5.

#### Load script

```
SET DateFormat='MM/DD/YYYY';

Transactions:
  Load
    *,
    lunarweekend(date,0,4) as end_of_week,
    timestamp(lunarweekend(date,0,4)) as end_of_week_timestamp
  ;
Load
*
Inline
[
id,date,amount
8188,1/7/2022,17.17
8189,1/19/2022,37.23
8190,2/28/2022,88.27
8191,2/5/2022,57.42
8192,3/16/2022,53.80
8193,4/1/2022,82.06
8194,5/7/2022,40.39
8195,5/16/2022,87.21
8196,6/15/2022,95.93
8197,6/26/2022,45.89
```

```
8198,7/9/2022,36.23
8199,7/22/2022,25.66
8200,7/23/2022,82.77
8201,7/27/2022,69.98
8202,8/2/2022,76.11
8203,8/8/2022,25.12
8204,8/19/2022,46.23
8205,9/26/2022,84.21
8206,10/14/2022,96.24
8207,10/29/2022,67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- end\_of\_week
- end\_of\_week\_timestamp


Results table

<b>date</b>	<b>end_of_week</b>	<b>end_of_week_timestamp</b>
1/7/2022	01/11/2022	1/11/2022 11:59:59 PM
1/19/2022	01/25/2022	1/25/2022 11:59:59 PM
2/5/2022	02/08/2022	2/8/2022 11:59:59 PM
2/28/2022	03/01/2022	3/1/2022 11:59:59 PM
3/16/2022	03/22/2022	3/22/2022 11:59:59 PM
4/1/2022	04/05/2022	4/5/2022 11:59:59 PM
5/7/2022	05/10/2022	5/10/2022 11:59:59 PM
5/16/2022	05/17/2022	5/17/2022 11:59:59 PM
6/15/2022	06/21/2022	6/21/2022 11:59:59 PM
6/26/2022	06/28/2022	6/28/2022 11:59:59 PM
7/9/2022	07/12/2022	7/12/2022 11:59:59 PM
7/22/2022	07/26/2022	7/26/2022 11:59:59 PM
7/23/2022	07/26/2022	7/26/2022 11:59:59 PM
7/27/2022	08/02/2022	8/2/2022 11:59:59 PM
8/2/2022	08/02/2022	8/2/2022 11:59:59 PM
8/8/2022	08/09/2022	8/9/2022 11:59:59 PM
8/19/2022	08/23/2022	8/23/2022 11:59:59 PM

date	end_of_week	end_of_week_timestamp
9/26/2022	09/27/2022	9/27/2022 11:59:59 PM
10/14/2022	10/18/2022	10/18/2022 11:59:59 PM
10/29/2022	11/01/2022	11/1/2022 11:59:59 PM

In this instance, because the `first_week_date` argument of 4 is used in the `lunarweekend()` function, it offsets the start of the year from January 1 to January 5.

*Diagram of `lunarweekend()` function, `first_week_day` example*



Transaction 8189 took place on January 19. Due to lunar weeks beginning on January 5, the `lunarweekend()` function identifies that the lunar week containing January 19 also begins on January 19. Therefore, the end of that lunar week occurs on January 25 at 11:59:59 PM; this is the value returned for the `end_of_week` field.

### Example 4 – Chart object example

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains the same dataset and scenario as the first example.

However, in this example, the unchanged dataset is loaded into the application. The calculation that returns a timestamp for the end of the lunar week in which the transactions took place is created as a measure in a chart object of the application.

#### Load script

```

Transactions:
Load
*
Inline
[
id,date,amount
8188,1/7/2022,17.17

```

```

8189,1/19/2022,37.23
8190,2/28/2022,88.27
8191,2/5/2022,57.42
8192,3/16/2022,53.80
8193,4/1/2022,82.06
8194,5/7/2022,40.39
8195,5/16/2022,87.21
8196,6/15/2022,95.93
8197,6/26/2022,45.89
8198,7/9/2022,36.23
8199,7/22/2022,25.66
8200,7/23/2022,82.77
8201,7/27/2022,69.98
8202,8/2/2022,76.11
8203,8/8/2022,25.12
8204,8/19/2022,46.23
8205,9/26/2022,84.21
8206,10/14/2022,96.24
8207,10/29/2022,67.67
];

```

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension: date.

Add the following measures:

```
=lunarweekend(date)
```

```
=timestamp(lunarweekend(date))
```

Results table


date	=lunarweekend(date)	=timestamp(lunarweekend(date))
1/7/2022	01/07/2022	1/7/2022 11:59:59 PM
1/19/2022	01/21/2022	1/21/2022 11:59:59 PM
2/5/2022	02/11/2022	2/11/2022 11:59:59 PM
2/28/2022	03/04/2022	3/4/2022 11:59:59 PM
3/16/2022	03/18/2022	3/18/2022 11:59:59 PM
4/1/2022	04/01/2022	4/1/2022 11:59:59 PM
5/7/2022	05/13/2022	5/13/2022 11:59:59 PM
5/16/2022	05/20/2022	5/20/2022 11:59:59 PM
6/15/2022	06/17/2022	6/17/2022 11:59:59 PM
6/26/2022	07/01/2022	7/1/2022 11:59:59 PM
7/9/2022	07/15/2022	7/15/2022 11:59:59 PM

date	=lunarweekend(date)	=timestamp(lunarweekend(date))
7/22/2022	07/22/2022	7/22/2022 11:59:59 PM
7/23/2022	07/29/2022	7/29/2022 11:59:59 PM
7/27/2022	07/29/2022	7/29/2022 11:59:59 PM
8/2/2022	08/05/2022	8/5/2022 11:59:59 PM
8/8/2022	08/12/2022	8/12/2022 11:59:59 PM
8/19/2022	08/19/2022	8/19/2022 11:59:59 PM
9/26/2022	09/30/2022	9/30/2022 11:59:59 PM
10/14/2022	10/14/2022	10/14/2022 11:59:59 PM
10/29/2022	11/04/2022	11/4/2022 11:59:59 PM

The `end_of_week` measure is created in the chart object by using the `lunarweekend()` function, and passing the `date` field as the function's argument.

The `lunarweekend()` function identifies which lunar week the date value falls into, returning a timestamp for the last millisecond of that week.

*Diagram of `lunarweekend()` function, chart object example*



Transaction 8189 took place on January 19. The `lunarweekend()` function identifies that the lunar week begins on January 15. Therefore, the `end_of_week` value for that transaction returns the last millisecond of the lunar week, which is January 21 at 11:59:59 PM.

### Example 5 – Scenario

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset which is loaded into a table called `Employee_Expenses`.
- The employee IDs, employee name and the average daily expense claims of each employee.

The end user would like a chart object that displays, by employee ID and employee name, the estimated expense claims still to be incurred for the remainder of the lunar week.

### Load script

```
Employee_Expenses :
Load
*
Inline
[
employee_id,employee_name,avg_daily_claim
182,Mark, $15
183,Deryck, $12.5
184,Dexter, $12.5
185,Sydney,$27
186,Agatha,$18
];
```

### Results

#### Do the following:

1. Load the data and open a sheet. Create a new table.
2. Add the following fields as dimensions.
  - `employee_id`
  - `employee_name`
3. Next, create the following measure to calculate the accumulated interest:  
`=(lunarweekend(today(1))-today(1))*avg_daily_claim`
4. Set the measure's **Number formatting** to **Money**.

Results table

<code>employee_id</code>	<code>employee_name</code>	<code>=(lunarweekend(today(1))-today(1))*avg_daily_claim</code>
182	Mark	\$75.00
183	Deryck	\$62.50
184	Dexter	\$62.50
185	Sydney	\$135.00
186	Agatha	\$90.00

The `lunarweekend()` function, by using today's date as its only argument, returns the end date of the current lunar week. Then, by subtracting today's date from the lunar week end date, the expression returns the number of days that remain this week.



This value is then multiplied by the average daily expense claim by each employee to calculate the estimated value of claims each employee is expected to make in the remaining lunar week.

### lunarweekname


This function returns a display value showing the year and lunar week number corresponding to a timestamp of the first millisecond of the first day of the lunar week containing **date**. Lunar weeks in Qlik Sense are defined by counting January 1 as the first day of the week and, apart from the final week of the year, will contain exactly seven days.

#### Syntax:

```
LunarWeekName (date [, period_no[, first_week_day]])
```

**Return data type:** dual

*Example diagram of Lunarweekname() function*



The Lunarweekname() function determines which lunar week the date falls into, beginning a week count from January 1. It then returns a value comprised of year/weekcount.

#### Arguments

Argument	Description
<b>date</b>	The date or timestamp to evaluate.
<b>period_no</b>	<b>period_no</b> is an integer or expression resolving to an integer, where the value 0 indicates the lunar week which contains <b>date</b> . Negative values in <b>period_no</b> indicate preceding lunar weeks and positive values indicate succeeding lunar weeks.
<b>first_week_day</b>	An offset that may be greater than or less than zero. This changes the beginning of the year by the specified number of days and/or fractions of a day.

### When to use it

The Lunarweekname() function is useful when you would like to compare aggregations by lunar weeks. For example, the function could be used to determine the total sales of products by lunar week. Lunar weeks are useful when you would like to ensure that all values contained in the first week of the year contain only values from January 1 at the earliest.

These dimensions can be created in the load script by using the function to create a field in a Master Calendar table. The function can also be used directly in a chart as a calculated dimension.

### Function examples

Example	Result
<code>lunarweekname('01/12/2013')</code>	Returns 2006/02.
<code>lunarweekname('01/12/2013', -1)</code>	Returns 2006/01.
<code>lunarweekname('01/12/2013', 0, 1)</code>	Returns 2006/02.

## Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

## Example 1 – date with no additional arguments

Load script and results

### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions for 2022, which is loaded into a table called Transactions.
- The date field provided in the `DateFormat` system variable (MM/DD/YYYY) format.
- The creation of a field, `lunar_week_name`, that returns the year and week number for the lunar week in which the transactions took place.

### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
  Load
    *,
    lunarweekname(date) as lunar_week_name
  ;
```

Load

\*

Inline

[

id,date,amount

8188,1/7/2022,17.17

8189,1/19/2022,37.23

8190,2/28/2022,88.27

8191,2/5/2022,57.42

8192,3/16/2022,53.80

8193,4/1/2022,82.06

8194,5/7/2022,40.39

8195,5/16/2022,87.21

8196,6/15/2022,95.93

8197,6/26/2022,45.89

8198,7/9/2022,36.23

8199,7/22/2022,25.66

8200,7/23/2022,82.77

8201,7/27/2022,69.98

8202,8/2/2022,76.11

8203,8/8/2022,25.12

8204,8/19/2022,46.23

8205,9/26/2022,84.21

8206,10/14/2022,96.24

8207,10/29/2022,67.67

];

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- lunar\_week\_name

Results table


date	lunar_week_name
1/7/2022	2022/01
1/19/2022	2022/03
2/5/2022	2022/06
2/28/2022	2022/09
3/16/2022	2022/11
4/1/2022	2022/13
5/7/2022	2022/19
5/16/2022	2022/20
6/15/2022	2022/24

date	lunar_week_name
6/26/2022	2022/26
7/9/2022	2022/28
7/22/2022	2022/29
7/23/2022	2022/30
7/27/2022	2022/30
8/2/2022	2022/31
8/8/2022	2022/32
8/19/2022	2022/33
9/26/2022	2022/39
10/14/2022	2022/41
10/29/2022	2022/44

The `lunar_week_name` field is created in the preceding load statement by using the `lunarweekname()` function, and passing the date field as the function's argument.

The `lunarweekname()` function identifies which lunar week the date value falls into, returning the year and week number of that date.

*Diagram of `lunarweekname()` function, example with no additional arguments*



Transaction 8189 took place on January 19. The `lunarweekname()` function identifies that this date falls into the lunar week beginning on January 15; this is the third lunar week of the year. Therefore, the `lunar_week_name` value returned for that transaction is 2022/03.

### Example 2 – date with `period_no` argument

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same dataset and scenario as the first example.
- The creation of a field, `previous_lunar_week_name`, that returns the year and week number for the lunar week prior to when the transactions took place.

### Load script

```
SET DateFormat='MM/DD/YYYY';

Transactions:
  Load
    *,
    lunarweekname(date,-1) as previous_lunar_week_name
  ;
Load
*
Inline
[
id,date,amount
8188,1/7/2022,17.17
8189,1/19/2022,37.23
8190,2/28/2022,88.27
8191,2/5/2022,57.42
8192,3/16/2022,53.80
8193,4/1/2022,82.06
8194,5/7/2022,40.39
8195,5/16/2022,87.21
8196,6/15/2022,95.93
8197,6/26/2022,45.89
8198,7/9/2022,36.23
8199,7/22/2022,25.66
8200,7/23/2022,82.77
8201,7/27/2022,69.98
8202,8/2/2022,76.11
8203,8/8/2022,25.12
8204,8/19/2022,46.23
8205,9/26/2022,84.21
8206,10/14/2022,96.24
8207,10/29/2022,67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- `date`
- `previous_lunar_week_name`


Results table

<code>date</code>	<code>previous_lunar_week_name</code>
1/7/2022	2021/52

date	previous_lunar_week_name
1/19/2022	2022/02
2/5/2022	2022/05
2/28/2022	2022/08
3/16/2022	2022/10
4/1/2022	2022/12
5/7/2022	2022/18
5/16/2022	2022/19
6/15/2022	2022/23
6/26/2022	2022/25
7/9/2022	2022/27
7/22/2022	2022/28
7/23/2022	2022/29
7/27/2022	2022/29
8/2/2022	2022/30
8/8/2022	2022/31
8/19/2022	2022/32
9/26/2022	2022/38
10/14/2022	2022/40
10/29/2022	2022/43

In this instance, because a `period_no` of -1 was used as the offset argument in the `lunarweekname()` function, the function first identifies the lunar week in which the transactions took place. It then returns the year and the number of one week prior.

*Diagram of `lunarweekname()` function, `period_no` example*



Transaction 8189 took place on January 19. The `lunarweekname()` function identifies that this transaction took place in the third lunar week of the year, so it then returns the year and value for one week prior, 2022/02, for the `previous_lunar_week_name` field.

### Example 3 – date with `first_week_day` argument

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains the same dataset and scenario as the first example. In this example, we set lunar weeks to begin on January 5.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
  Load
    *,
    lunarweekname(date,0,4) as lunar_week_name
  ;
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
```

```
8188,1/7/2022,17.17
```

```
8189,1/19/2022,37.23
```

```
8190,2/28/2022,88.27
```

```
8191,2/5/2022,57.42
```

```
8192,3/16/2022,53.80
```

```
8193,4/1/2022,82.06
```

```
8194,5/7/2022,40.39
```

```
8195,5/16/2022,87.21
```

```
8196,6/15/2022,95.93
```

```
8197,6/26/2022,45.89
```

```
8198,7/9/2022,36.23
```

```
8199,7/22/2022,25.66
```

```
8200,7/23/2022,82.77
```

```
8201,7/27/2022,69.98
```

```
8202,8/2/2022,76.11
```

```
8203,8/8/2022,25.12
```

```
8204,8/19/2022,46.23
```

```
8205,9/26/2022,84.21
```

```
8206,10/14/2022,96.24
```

```
8207,10/29/2022,67.67
```

```
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:


- date
- lunar\_week\_name

Results table

<b>date</b>	<b>lunar_week_name</b>
1/7/2022	2022/01
1/19/2022	2022/03
2/5/2022	2022/05
2/28/2022	2022/08
3/16/2022	2022/11
4/1/2022	2022/13
5/7/2022	2022/18
5/16/2022	2022/19
6/15/2022	2022/24
6/26/2022	2022/25
7/9/2022	2022/27
7/22/2022	2022/29
7/23/2022	2022/29
7/27/2022	2022/30
8/2/2022	2022/30
8/8/2022	2022/31
8/19/2022	2022/33
9/26/2022	2022/38
10/14/2022	2022/41
10/29/2022	2022/43



Diagram of `lunarweekname()` function, `first_week_day` example



In this instance, because the `first_week_date` argument of 4 is used in the `lunarweekname()` function, it offsets the start of lunar weeks from January 1 to January 5.

Transaction 8188 took place on January 7. Due to lunar weeks beginning on January 5, the `lunarweekname()` function identifies that the lunar week containing January 7 is the first lunar week of the year. Therefore, the returned `lunar_week_name` value for that transaction is 2022/01.

### Example 4 – Chart object example

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains the same dataset and scenario as the first example.

However, in this example, the unchanged dataset is loaded into the application. The calculation that returns the lunar week number and year in which the transactions took place is created as a measure in a chart object of the application.

#### Load script

```
Transactions:
Load
*
Inline
[
id,date,amount
8188,1/7/2022,17.17
8189,1/19/2022,37.23
8190,2/28/2022,88.27
8191,2/5/2022,57.42
8192,3/16/2022,53.80
8193,4/1/2022,82.06
8194,5/7/2022,40.39
8195,5/16/2022,87.21
8196,6/15/2022,95.93
8197,6/26/2022,45.89
```

```
8198,7/9/2022,36.23
8199,7/22/2022,25.66
8200,7/23/2022,82.77
8201,7/27/2022,69.98
8202,8/2/2022,76.11
8203,8/8/2022,25.12
8204,8/19/2022,46.23
8205,9/26/2022,84.21
8206,10/14/2022,96.24
8207,10/29/2022,67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension: date.

To calculate the start date of the lunar week in which a transaction takes place, create the following measure:

```
=lunarweekname(date)
```

Results table


<b>date</b>	<b>=lunarweekname(date)</b>
1/7/2022	2022/01
1/19/2022	2022/03
2/5/2022	2022/06
2/28/2022	2022/09
3/16/2022	2022/11
4/1/2022	2022/13
5/7/2022	2022/19
5/16/2022	2022/20
6/15/2022	2022/24
6/26/2022	2022/26
7/9/2022	2022/28
7/22/2022	2022/29
7/23/2022	2022/30
7/27/2022	2022/30
8/2/2022	2022/31
8/8/2022	2022/32
8/19/2022	2022/33

date	=lunarweekname(date)
9/26/2022	2022/39
10/14/2022	2022/41
10/29/2022	2022/44

The `lunar_week_name` measure is created in the chart object by using the `lunarweekname()` function and passing the date field as the function's argument.

The `lunarweekname()` function identifies which lunar week the date value falls into, returning the year and week number of that date.

*Diagram of `lunarweekname()` function, chart object example*



Transaction 8189 took place on January 19. The `lunarweekname()` function identifies that this date falls into the lunar week beginning on January 15; this is the third lunar week of the year. Therefore, the `lunar_week_name` value for that transaction is 2022/03.

### Example 5 – Scenario

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions for 2022, which is loaded into a table called Transactions.
- The date field provided in the `dateFormat` system variable (MM/DD/YYYY) format.

The end user would like a chart object that presents the total sales by week for the current year. Week 1, with a length of seven days, should begin on January 1. This could be achieved even when this dimension is not available in the data model by using the `lunarweekname()` function as a calculated dimension in the chart.

### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
```

```
8188,1/7/2022,17.17
```

```
8189,1/19/2022,37.23
```

```
8190,2/28/2022,88.27
```

```
8191,2/5/2022,57.42
```

```
8192,3/16/2022,53.80
```

```
8193,4/1/2022,82.06
```

```
8194,5/7/2022,40.39
```

```
8195,5/16/2022,87.21
```

```
8196,6/15/2022,95.93
```

```
8197,6/26/2022,45.89
```

```
8198,7/9/2022,36.23
```

```
8199,7/22/2022,25.66
```

```
8200,7/23/2022,82.77
```

```
8201,7/27/2022,69.98
```

```
8202,8/2/2022,76.11
```

```
8203,8/8/2022,25.12
```

```
8204,8/19/2022,46.23
```

```
8205,9/26/2022,84.21
```

```
8206,10/14/2022,96.24
```

```
8207,10/29/2022,67.67
```

```
];
```

### Results

#### Do the following:

1. Load the data and open a sheet. Create a new table.
2. Create a calculated dimension using the following expression:  
=lunarweekname(date)
3. Calculate total sales using the following aggregation measure:  
=sum(amount)
4. Set the measure's **Number formatting** to **Money**.

Results table

=lunarweekname(date)	=sum(amount)
2022/01	\$17.17
2022/03	\$37.23
2022/06	\$57.42

<b>=lunarweekname(date)</b>	<b>=sum(amount)</b>
2022/09	\$88.27
2022/11	\$53.80
2022/13	\$82.06
2022/19	\$40.39
2022/20	\$87.21
2022/24	\$95.93
2022/26	\$45.89
2022/28	\$36.23
2022/29	\$25.66
2022/30	\$152.75
2022/31	\$76.11
2022/32	\$25.12
2022/33	\$46.23
2022/39	\$84.21
2022/41	\$96.24
2022/44	\$67.67

## lunarweekstart

This function returns a value corresponding to a timestamp of the first millisecond of the first day of the lunar week containing **date**. Lunar weeks in Qlik Sense are defined by counting January 1 as the first day of the week and, apart from the final week of the year, will contain exactly seven days.


### Syntax:

```
LunarweekStart(date[, period_no[, first_week_day]])
```

**Return data type:** dual

The `lunarweekstart()` function determines which lunar week the date falls into. It then returns a timestamp, in date format, for the first millisecond of that week.

Example diagram of `lunarweekstart()` function



### Arguments

Argument	Description
<b>date</b>	The date or timestamp to evaluate.
<b>period_no</b>	<b>period_no</b> is an integer or expression resolving to an integer, where the value 0 indicates the lunar week which contains <b>date</b> . Negative values in <b>period_no</b> indicate preceding lunar weeks and positive values indicate succeeding lunar weeks.
<b>first_week_day</b>	An offset that may be greater than or less than zero. This changes the beginning of the year by the specified number of days and/or fractions of a day.

### When to use it

The `lunarweekstart()` function is commonly used as part of an expression when the user would like the calculation to use the fraction of the week that has elapsed thus far. Unlike the `weekstart()` function, at the start of each new calendar year, week's begin on January 1 and each subsequent week begins seven days later. The `lunarweekstart()` function is not affected by the `Firstweekday` system variable.

For example, the `lunarweekstart()` can be used to calculate the interest that has been accumulated in a week to date.

### Function examples

Example	Result
<code>lunarweekstart ('01/12/2013')</code>	Returns 01/08/2013.
<code>lunarweekstart ('01/12/2013', -1)</code>	Returns 01/01/2013.
<code>lunarweekstart ('01/12/2013', 0, 1 )</code>	Returns 01/09/2013, because setting <code>first_week_day</code> to 1 means the beginning of the year is changed to 01/02/2013.

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Example 1 – No additional arguments

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions for 2022, which is loaded into a table called Transactions.
- The date field provided in the `DateFormat` system variable (MM/DD/YYYY) format.
- The creation of a field `start_of_week`, that returns a timestamp for the start of the lunar week in which the transactions took place.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
  Load
    *
    ,
    lunarweekstart(date) as start_of_week,
    timestamp(lunarweekstart(date)) as start_of_week_timestamp
  ;
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
8188,1/7/2022,17.17
8189,1/19/2022,37.23
8190,2/28/2022,88.27
8191,2/5/2022,57.42
8192,3/16/2022,53.80
```

```
8193,4/1/2022,82.06
8194,5/7/2022,40.39
8195,5/16/2022,87.21
8196,6/15/2022,95.93
8197,6/26/2022,45.89
8198,7/9/2022,36.23
8199,7/22/2022,25.66
8200,7/23/2022,82.77
8201,7/27/2022,69.98
8202,8/2/2022,76.11
8203,8/8/2022,25.12
8204,8/19/2022,46.23
8205,9/26/2022,84.21
8206,10/14/2022,96.24
8207,10/29/2022,67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- start\_of\_week
- start\_of\_week\_timestamp

Results table

date	start_of_week	start_of_week_timestamp
1/7/2022	01/01/2022	1/1/2022 12:00:00 AM
1/19/2022	01/15/2022	1/15/2022 12:00:00 AM
2/5/2022	02/05/2022	2/5/2022 12:00:00 AM
2/28/2022	02/26/2022	2/26/2022 12:00:00 AM
3/16/2022	03/12/2022	3/12/2022 12:00:00 AM
4/1/2022	03/26/2022	3/26/2022 12:00:00 AM
5/7/2022	05/07/2022	5/7/2022 12:00:00 AM
5/16/2022	05/14/2022	5/14/2022 12:00:00 AM
6/15/2022	06/11/2022	6/11/2022 12:00:00 AM
6/26/2022	06/25/2022	6/25/2022 12:00:00 AM
7/9/2022	07/09/2022	7/9/2022 12:00:00 AM
7/22/2022	07/16/2022	7/16/2022 12:00:00 AM
7/23/2022	07/23/2022	7/23/2022 12:00:00 AM
7/27/2022	07/23/2022	7/23/2022 12:00:00 AM
8/2/2022	07/30/2022	7/30/2022 12:00:00 AM




date	start_of_week	start_of_week_timestamp
8/8/2022	08/06/2022	8/6/2022 12:00:00 AM
8/19/2022	08/13/2022	8/13/2022 12:00:00 AM
9/26/2022	09/24/2022	9/24/2022 12:00:00 AM
10/14/2022	10/08/2022	10/8/2022 12:00:00 AM
10/29/2022	10/29/2022	10/29/2022 12:00:00 AM

The `start_of_week` field is created in the preceding load statement by using the `lunarweekstart()` function and passing the `date` field as the function's argument.

The `lunarweekstart()` function identifies the lunar week into which the date falls, returning a timestamp for the first millisecond of that week.

*Diagram of `lunarweekstart()` function, example with no additional arguments*



Transaction 8189 took place on January 19. The `lunarweekstart()` function identifies that the lunar week begins on January 15. Therefore, the `start_of_week` value for that transaction returns the first millisecond of that day, which is January 15 at 12:00:00 AM.

### Example 2 – `period_no`

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same dataset and scenario as the first example.
- The creation of a field, `previous_lunar_week_start`, that returns the timestamp for the start of the lunar week before the transaction took place.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

Transactions:

```

Load
    *,
    lunarweekstart(date,-1) as previous_lunar_week_start,
    timestamp(lunarweekstart(date,-1)) as previous_lunar_week_start_timestamp
;

Load
*
Inline
[
id,date,amount
8188,1/7/2022,17.17
8189,1/19/2022,37.23
8190,2/28/2022,88.27
8191,2/5/2022,57.42
8192,3/16/2022,53.80
8193,4/1/2022,82.06
8194,5/7/2022,40.39
8195,5/16/2022,87.21
8196,6/15/2022,95.93
8197,6/26/2022,45.89
8198,7/9/2022,36.23
8199,7/22/2022,25.66
8200,7/23/2022,82.77
8201,7/27/2022,69.98
8202,8/2/2022,76.11
8203,8/8/2022,25.12
8204,8/19/2022,46.23
8205,9/26/2022,84.21
8206,10/14/2022,96.24
8207,10/29/2022,67.67
];

```

### Results


Results table

date	previous_lunar_week_start	previous_lunar_week_start_timestamp
1/7/2022	12/24/2021	12/24/2021 12:00:00 AM
1/19/2022	01/08/2022	1/8/2022 12:00:00 AM
2/5/2022	01/29/2022	1/29/2022 12:00:00 AM
2/28/2022	02/19/2022	2/19/2022 12:00:00 AM
3/16/2022	03/05/2022	3/5/2022 12:00:00 AM
4/1/2022	03/19/2022	3/19/2022 12:00:00 AM
5/7/2022	04/30/2022	4/30/2022 12:00:00 AM
5/16/2022	05/07/2022	5/7/2022 12:00:00 AM
6/15/2022	06/04/2022	6/4/2022 12:00:00 AM

date	previous_lunar_week_start	previous_lunar_week_start_timestamp
6/26/2022	06/18/2022	6/18/2022 12:00:00 AM
7/9/2022	07/02/2022	7/2/2022 12:00:00 AM
7/22/2022	07/09/2022	7/9/2022 12:00:00 AM
7/23/2022	07/16/2022	7/16/2022 12:00:00 AM
7/27/2022	07/16/2022	7/16/2022 12:00:00 AM
8/2/2022	07/23/2022	7/23/2022 12:00:00 AM
8/8/2022	07/30/2022	7/30/2022 12:00:00 AM
8/19/2022	08/06/2022	8/6/2022 12:00:00 AM
9/26/2022	09/17/2022	9/17/2022 12:00:00 AM
10/14/2022	10/01/2022	10/1/2022 12:00:00 AM
10/29/2022	10/22/2022	10/22/2022 12:00:00 AM

In this instance, because a `period_no` of `-1` was used as the offset argument in the `lunarweekstart()` function, the function first identifies the lunar week that the transactions take place in. It then shifts one week prior and identifies the first millisecond of that lunar week.

*Diagram of `lunarweekstart()` function, `period_no` example*



Transaction 8189 took place on January 19. The `lunarweekstart()` function identifies that the lunar week begins on January 15. Therefore, the previous lunar week began on January 8 at 12:00:00 AM; this is the value returned for the `previous_lunar_week_start` field.

### Example 3 – `first_week_day`

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains the same dataset and scenario as the first example. In this example, we set lunar weeks to begin on January 5.

### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
    Load
        *,
        lunarweekstart(date,0,4) as start_of_week,
        timestamp(lunarweekstart(date,0,4)) as start_of_week_timestamp
    ;
```

```
Load
```

```
*
```

```
Inline
```

```
[
id,date,amount
8188,1/7/2022,17.17
8189,1/19/2022,37.23
8190,2/28/2022,88.27
8191,2/5/2022,57.42
8192,3/16/2022,53.80
8193,4/1/2022,82.06
8194,5/7/2022,40.39
8195,5/16/2022,87.21
8196,6/15/2022,95.93
8197,6/26/2022,45.89
8198,7/9/2022,36.23
8199,7/22/2022,25.66
8200,7/23/2022,82.77
8201,7/27/2022,69.98
8202,8/2/2022,76.11
8203,8/8/2022,25.12
8204,8/19/2022,46.23
8205,9/26/2022,84.21
8206,10/14/2022,96.24
8207,10/29/2022,67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:


- date
- start\_of\_week
- start\_of\_week\_timestamp

Results table

date	start_of_week	start_of_week_timestamp
1/7/2022	01/05/2022	1/5/2022 12:00:00 AM
1/19/2022	01/19/2022	1/19/2022 12:00:00 AM
2/5/2022	02/02/2022	2/2/2022 12:00:00 AM
2/28/2022	02/23/2022	2/23/2022 12:00:00 AM
3/16/2022	03/16/2022	3/16/2022 12:00:00 AM
4/1/2022	03/30/2022	3/30/2022 12:00:00 AM
5/7/2022	05/04/2022	5/4/2022 12:00:00 AM
5/16/2022	05/11/2022	5/11/2022 12:00:00 AM
6/15/2022	06/15/2022	6/15/2022 12:00:00 AM
6/26/2022	06/22/2022	6/22/2022 12:00:00 AM
7/9/2022	07/06/2022	7/6/2022 12:00:00 AM
7/22/2022	07/20/2022	7/20/2022 12:00:00 AM
7/23/2022	07/20/2022	7/20/2022 12:00:00 AM
7/27/2022	07/27/2022	7/27/2022 12:00:00 AM
8/2/2022	07/27/2022	7/27/2022 12:00:00 AM
8/8/2022	08/03/2022	8/3/2022 12:00:00 AM
8/19/2022	08/17/2022	8/17/2022 12:00:00 AM
9/26/2022	09/21/2022	9/21/2022 12:00:00 AM
10/14/2022	10/12/2022	10/12/2022 12:00:00 AM
10/29/2022	10/26/2022	10/26/2022 12:00:00 AM

In this instance, because the `first_week_date` argument of 4 is used in the `lunarweekstart()` function, it offsets the start of the year from January 1 to January 5.

*Diagram of `lunarweekstart()` function, `first_week_day` example*



Transaction 8189 took place on January 19. Due to lunar weeks beginning on January 5, the `Tunarweekstart()` function identifies that the lunar week containing January 19 begins on January 19 at 12:00:00 AM as well. Therefore, that is the value returned for the `start_of_week` field.

### Example 4 – Chart object example

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains the same dataset and scenario as the first example.

However, in this example, the unchanged dataset is loaded into the application. The calculation that returns a timestamp for the start of the lunar week in which the transactions took place is created as a measure in a chart object of the application.

#### Load script

```
Transactions:
Load
*
Inline
[
id,date,amount
8188,1/7/2022,17.17
8189,1/19/2022,37.23
8190,2/28/2022,88.27
8191,2/5/2022,57.42
8192,3/16/2022,53.80
8193,4/1/2022,82.06
8194,5/7/2022,40.39
8195,5/16/2022,87.21
8196,6/15/2022,95.93
8197,6/26/2022,45.89
8198,7/9/2022,36.23
8199,7/22/2022,25.66
8200,7/23/2022,82.77
8201,7/27/2022,69.98
8202,8/2/2022,76.11
8203,8/8/2022,25.12
8204,8/19/2022,46.23
8205,9/26/2022,84.21
8206,10/14/2022,96.24
8207,10/29/2022,67.67
];
```

#### Results

Load the data and open a sheet. Create a new table and add this field as a dimension: `date`.

Add the following measures:

```
=lunarweekstart(date)
```

```
=timestamp(lunarweekstart(date))
```


Results table

<b>date</b>	<b>=lunarweekstart(date)</b>	<b>=timestamp(lunarweekstart(date))</b>
1/7/2022	01/01/2022	1/1/2022 12:00:00 AM
1/19/2022	01/15/2022	1/15/2022 12:00:00 AM
2/5/2022	02/05/2022	2/5/2022 12:00:00 AM
2/28/2022	02/26/2022	2/26/2022 12:00:00 AM
3/16/2022	03/12/2022	3/12/2022 12:00:00 AM
4/1/2022	03/26/2022	3/26/2022 12:00:00 AM
5/7/2022	05/07/2022	5/7/2022 12:00:00 AM
5/16/2022	05/14/2022	5/14/2022 12:00:00 AM
6/15/2022	06/11/2022	6/11/2022 12:00:00 AM
6/26/2022	06/25/2022	6/25/2022 12:00:00 AM
7/9/2022	07/09/2022	7/9/2022 12:00:00 AM
7/22/2022	07/16/2022	7/16/2022 12:00:00 AM
7/23/2022	07/23/2022	7/23/2022 12:00:00 AM
7/27/2022	07/23/2022	7/23/2022 12:00:00 AM
8/2/2022	07/30/2022	7/30/2022 12:00:00 AM
8/8/2022	08/06/2022	8/6/2022 12:00:00 AM
8/19/2022	08/13/2022	8/13/2022 12:00:00 AM
9/26/2022	09/24/2022	9/24/2022 12:00:00 AM
10/14/2022	10/08/2022	10/8/2022 12:00:00 AM
10/29/2022	10/29/2022	10/29/2022 12:00:00 AM

The `start_of_week` measure is created in the chart object by using the `lunarweekstart()` function, and passing the date field as the function's argument.

The `lunarweekstart()` function identifies which lunar week the date value falls into, returning a timestamp for the last millisecond of that week.

Diagram of `lunarweekstart()` function, chart object example



Transaction 8189 took place on January 19. The `lunarweekstart()` function identifies that the lunar week begins on January 15. Therefore, the `start_of_week` value for that transaction is first millisecond of that day, which is the January 15 at 12:00:00 AM.

### Example 5 – Scenario

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of loan balances, which is loaded into a table called Loans.
- Data consisting of loan IDs, the balance at the beginning of the week, and the simple interest rate charged on each loan per annum.

The end user would like a chart object that displays, by loan ID, the current interest that has been accrued on each loan in the week to date.

#### Load script

```
Loans:
Load
*
Inline
[
loan_id,start_balance,rate
8188,$10000.00,0.024
8189,$15000.00,0.057
8190,$17500.00,0.024
8191,$21000.00,0.034
8192,$90000.00,0.084
];
```



**Results****Do the following:**

1. Load the data and open a sheet. Create a new table.
2. Add the following fields as dimensions.
  - loan\_id
  - start\_balance
3. Next, create the following measure to calculate the accumulated interest:  

$$=start\_balance*(rate*(today(1)-lunarweekstart(today(1)))/365)$$
4. Set the measure's **Number formatting** to **Money**.

Results table

loan_id	start_balance	=start_balance*(rate*(today(1)-lunarweekstart (today(1)))/365)
8188	\$10000.00	\$15.07
8189	\$15000.00	\$128.84
8190	\$17500.00	\$63.29
8191	\$21000.00	\$107.59
8192	\$90000.00	\$1139.18

The `lunarweekstart()` function, using today's date as its only argument, returns the start date of the current year. By subtracting that result from the current date, the expression returns the number of days that have elapsed so far this week.

This value is then multiplied by the interest rate and divided by 365 to return the effective interest rate incurred for this period. The result is then multiplied by the starting balance of the loan to return the interest that has been accrued so far this week.

**makedate**

This function returns a date calculated from the year **YYYY**, the month **MM** and the day **DD**.

**Syntax:**

```
MakeDate (YYYY [ , MM [ , DD ] ])
```

**Return data type:** dual

Arguments

Argument	Description
YYYY	The year as an integer.

Argument	Description
MM	The month as an integer. If no month is stated, 1 (January) is assumed.
DD	The day as an integer. If no day is stated, 1 (the 1st) is assumed.

### When to use it

The `makedate()` function would commonly be used in the script for data generation to generate a calendar. This could also be used when the date field is not directly available as date, but needs some transformations to extract year, month and day components.

These examples use the date format MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement at the top of your data load script. Change the format in the examples to suit your requirements.

#### Function examples

Example	Result
<code>makedate(2012)</code>	Returns 01/01/2012.
<code>makedate(12)</code>	Returns 01/01/2012.
<code>makedate(2012, 12)</code>	Returns 12/01/2012.
<code>makedate(2012, 2, 14)</code>	Returns 02/14/2012.

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Example 1 – Basic example

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions for 2018, which is loaded into a table called Transactions.
- The date field provided in the DateFormat system variable (MM/DD/YYYY) format.
- The creation of a field, transaction\_date, that returns a date in the format MM/DD/YYYY.

### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
Load
    *,
    makedate(transaction_year, transaction_month, transaction_day) as transaction_date
;
Load * Inline [
transaction_id, transaction_year, transaction_month, transaction_day, transaction_amount,
transaction_quantity, customer_id
3750, 2018, 08, 30, 12423.56, 23, 2038593
3751, 2018, 09, 07, 5356.31, 6, 203521
3752, 2018, 09, 16, 15.75, 1, 5646471
3753, 2018, 09, 22, 1251, 7, 3036491
3754, 2018, 09, 22, 21484.21, 1356, 049681
3756, 2018, 09, 22, -59.18, 2, 2038593
3757, 2018, 09, 23, 3177.4, 21, 203521
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- transaction\_year
- transaction\_month
- transaction\_day
- transaction\_date

Results table

transaction_year	transaction_month	transaction_day	transaction_date
2018	08	30	08/30/2018
2018	09	07	09/07/2018
2018	09	16	09/16/2018
2018	09	22	09/22/2018
2018	09	23	09/23/2018

The transaction\_date field is created in the preceding load statement by using the makedate() function and passing the year, month, day fields as function arguments.

The function then combines and converts these values into a date field, returning the results in the format of the `DateFormat` system variable.

### Example 2 – Modified DateFormat

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same dataset and scenario as the first example.
- The creation of a field, `transaction_date`, in the format `DD/MM/YYYY` without modifying the `DateFormat` system variable.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
  Load
    *,
    date(makedate(transaction_year, transaction_month, transaction_day), 'DD/MM/YYYY') as
  transaction_date
  ;
Load * Inline [
transaction_id, transaction_year, transaction_month, transaction_day, transaction_amount,
transaction_quantity, customer_id
3750, 2018, 08, 30, 12423.56, 23, 2038593
3751, 2018, 09, 07, 5356.31, 6, 203521
3752, 2018, 09, 16, 15.75, 1, 5646471
3753, 2018, 09, 22, 1251, 7, 3036491
3754, 2018, 09, 22, 21484.21, 1356, 049681
3756, 2018, 09, 22, -59.18, 2, 2038593
3757, 2018, 09, 23, 3177.4, 21, 203521
];
```

#### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- `transaction_year`
- `transaction_month`
- `transaction_day`
- `transaction_date`

Results table

transaction_year	transaction_month	transaction_day	transaction_date
2018	08	30	30/08/2018
2018	09	07	07/09/2018
2018	09	16	16/09/2018
2018	09	22	22/09/2018
2018	09	23	23/09/2018

In this instance, the `makedate()` function is nested inside the `date()` function. The second argument of the `date()` function sets the format of the `makedate()` function results as the required DD/MM/YYYY.

### Example 3 – Chart object example

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions for 2018, which is loaded into a table called Transactions.
- The transaction dates provided across two fields: year and month.

Create a chart object measure `transaction_date`, that returns a date in the format MM/DD/YYYY.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
Load * Inline [
```

```
transaction_id, transaction_year, transaction_month, transaction_amount, transaction_quantity,  
customer_id
```

```
3750, 2018, 08, 12423.56, 23, 2038593
```

```
3751, 2018, 09, 5356.31, 6, 203521
```

```
3752, 2018, 09, 15.75, 1, 5646471
```

```
3753, 2018, 09, 1251, 7, 3036491
```

```
3754, 2018, 09, 21484.21, 1356, 049681
```

```
3756, 2018, 09, -59.18, 2, 2038593
```

```
3757, 2018, 09, 3177.4, 21, 203521
```

```
];
```

#### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- year
- month

To determine the `transaction_date`, create this measure:

```
=makedate(transaction_year, transaction_month)
```

Results table

<b>transaction_year</b>	<b>transaction_month</b>	<b>transaction_date</b>
2018	08	08/01/2018
2018	09	09/01/2018

The `transaction_date` measure is created in the chart object by using the `makedate()` function, and passing the year and month fields as function arguments.

The function then combines these values, as well as the assumed day value of 01. These values are then converted into a date field, returning the results in the format of the `dateFormat` system variable.

### Example 4 – Scenario

Load script and chart expression

#### Overview

Create a calendar dataset for the calendar year of 2022.

#### Load script

```
SET DateFormat='MM/DD/YYYY';

Calendar:
    load
        *
        where year(date)=2022;
    load
        date(recno()+makedate(2021,12,31)) as date
    AutoGenerate 400;
```

#### Results

Results table

<b>date</b>
01/01/2022
01/02/2022

<b>date</b>
01/03/2022
01/04/2022
01/05/2022
01/06/2022
01/07/2022
01/08/2022
01/09/2022
01/10/2022
01/11/2022
01/12/2022
01/13/2022
01/14/2022
01/15/2022
01/16/2022
01/17/2022
01/18/2022
01/19/2022
01/20/2022
01/21/2022
01/22/2022
01/23/2022
01/24/2022
01/25/2022
+ 340 more rows

The `makedate()` function creates a date value for December 31, 2021. The `recno()` function provides the record number of the current record being loaded into the table, starting from 1. Therefore, the first record has the date January 1, 2022. Each successive `recno()` will then increment this date by 1. This expression is wrapped in a `date()` function to convert the value into a date. This process is repeated 400 times by the `autogenerate` function. Finally, by using a preceding load, a `where` condition can be used to only load dates from year 2022. This script generates a calendar containing every date in 2022.

## maketime

This function returns a time calculated from the hour **hh**, the minute **mm**, and the second **ss**.

### Syntax:

```
MakeTime (hh [ , mm [ , ss ] ])
```

**Return data type:** dual

#### Arguments

Argument	Description
hh	The hour as an integer.
mm	The minute as an integer. If no minute is stated, 00 is assumed.
ss	The second as an integer. If no second is stated, 00 is assumed.

### When to use it

The `maketime()` function would commonly be used in the script for data generation to generate a time field. Sometimes, when the time field is derived from input text, this function could be used to construct the time using its components.

These examples use the time format `h:mm:ss`. The time format is specified in the `SET TimeFormat` statement at the top of your data load script. Change the format in the examples to suit your requirements.

#### Function examples

Example	Result
<code>maketime(22)</code>	Returns 22:00:00.
<code>maketime(22, 17)</code>	Returns 22:17:00.
<code>maketime(22,17,52 )</code>	Returns 22:17:52.

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: `MM/DD/YYYY`. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.



Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Example 1 – maketime()

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions , which is loaded into a table called `Transactions`.
- Transaction times provided across three fields: `hours`, `minutes`, and `seconds`.
- The creation of a field, `transaction_time`, that returns the time in the format of the `TimeFormat` system variable.

#### Load script

```
SET TimeFormat='h:mm:ss TT';
```

```
Transactions:
```

```
    Load
        *,
        maketime(transaction_hour, transaction_minute, transaction_second) as transaction_time
    ;
Load * Inline [
transaction_id, transaction_hour, transaction_minute, transaction_second, transaction_amount,
transaction_quantity, customer_id
3750, 18, 43, 30, 12423.56, 23, 2038593
3751, 6, 32, 07, 5356.31, 6, 203521
3752, 12, 09, 16, 15.75, 1, 5646471
3753, 21, 43, 41, 7, 3036491
3754, 17, 55, 22, 21484.21, 1356, 049681
3756, 2, 52, 22, -59.18, 2, 2038593
3757, 9, 25, 23, 3177.4, 21, 203521
];
```

#### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- `transaction_hour`
- `transaction_minute`

- transaction\_second
- transaction\_time

Results table

transaction_hour	transaction_minute	transaction_second	transaction_time
2	52	22	2:52:22 AM
6	32	07	6:32:07 AM
9	25	23	9:25:23 AM
12	09	16	12:09:16 PM
17	55	22	5:55:22 PM
18	43	30	6:43:30 PM
21	43	41	9:43:41 PM

The `transaction_time` field is created in the preceding load statement by using the `maketime()` function, and passing the hour, minute, and second fields as function arguments.

The function then combines and converts these values into a time field, returning the results in the time format of the `TimeFormat` system variable.

### Example 2 – time() function

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same dataset and scenario as the first example.
- The creation of a field, `transaction_time`, which will allow us to show the results in 24-hour time format without modifying the `TimeFormat` system variable.

#### Load script

```
SET TimeFormat='h:mm:ss TT';
```

```
Transactions:
```

```
  Load
    *,
    time(maketime(transaction_hour, transaction_minute, transaction_second), 'h:mm:ss') as
transaction_time
  ;
Load * Inline [
transaction_id, transaction_hour, transaction_minute, transaction_second, transaction_amount,
transaction_quantity, customer_id
```

```
3750, 18, 43, 30, 12423.56, 23, 2038593
3751, 6, 32, 07, 5356.31, 6, 203521
3752, 12, 09, 16, 15.75, 1, 5646471
3753, 21, 43, 41, 7, 3036491
3754, 17, 55, 22, 21484.21, 1356, 049681
3756, 2, 52, 22, -59.18, 2, 2038593
3757, 9, 25, 23, 3177.4, 21, 203521
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- transaction\_hour
- transaction\_minute
- transaction\_second
- transaction\_time

Results table

transaction_hour	transaction_minute	transaction_second	transaction_time
2	52	22	2:52:22
6	32	07	6:32:07
9	25	23	9:25:23
12	09	16	12:09:16
17	55	22	17:55:22
18	43	30	18:43:30
21	43	41	21:43:41

In this instance, the `maketime()` function is nested inside the `time()` function. The second argument of the `time()` function sets the format of the `maketime()` function results as the required `h:mm:ss`.

### Example 3 – Chart object example

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions, which is loaded into a table called `Transactions`.
- Transaction times provided across two fields: `hours` and `minutes`.

- The creation of a field, `transaction_time`, that returns the time in the format of the `TimeFormat` system variable.

Create a chart object measure `transaction_time`, that returns a time in the format `h:mm:ss TT`.

### Load script

```
SET TimeFormat='h:mm:ss TT';
```

```
Transactions:
```

```
Load * Inline [  
transaction_id, transaction_hour, transaction_minute, transaction_amount, transaction_  
quantity, customer_id  
3750, 18, 43, 12423.56, 23, 2038593  
3751, 6, 32, 5356.31, 6, 203521  
3752, 12, 09, 15.75, 1, 5646471  
3753, 21, 43, 7, 3036491  
3754, 17, 55, 21484.21, 1356, 049681  
3756, 2, 52, -59.18, 2, 2038593  
3757, 9, 25, 3177.4, 21, 203521  
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- `transaction_hour`
- `transaction_minute`

To calculate the `transaction_time`, create this measure:

```
=maketime(transaction_hour,transaction_minute)
```

Results table

<code>transaction_hour</code>	<code>transaction_minute</code>	<code>=maketime(transaction_hour, transaction_minute)</code>
2	52	2:52:00 AM
6	32	6:32:00 AM
9	25	9:25:00 AM
12	09	12:09:00 PM
17	55	5:55:00 PM
18	43	6:43:00 PM
21	43	9:43:00 PM

The `transaction_time` measure is created in the chart object by using the `maketime()` function, and passing the hour and minute fields as function arguments.

The function then combines these values, and seconds are assumed to be 00. These values are then converted into a time field, returning the results in the format of the `TimeFormat` system variable.

### Example 4 – Scenario

Load script and chart expression

#### Overview

Create a calendar dataset for the month of January 2022, broken out into eight-hour increments.

#### Load script

```
SET TimestampFormat='M/D/YYYY h:mm:ss[.fff] TT';

tmpCalendar:
    load
        *
        where year(date)=2022;
load
    date(recno()+makedate(2021,12,31)) as date
AutoGenerate 31;

Left join(tmpCalendar)
load
    maketime((recno()-1)*8,00,00) as time
autogenerate 3;

Calendar:
load
    timestamp(date + time) as timestamp
resident tmpCalendar;

drop table tmpCalendar;
```

#### Results

Results table

timestamp
1/1/2022 12:00:00 AM
1/1/2022 8:00:00 AM
1/1/2022 4:00:00 PM
1/2/2022 12:00:00 AM
1/2/2022 8:00:00 AM
1/2/2022 4:00:00 PM

<b>timestamp</b>
1/3/2022 12:00:00 AM
1/3/2022 8:00:00 AM
1/3/2022 4:00:00 PM
1/4/2022 12:00:00 AM
1/4/2022 8:00:00 AM
1/4/2022 4:00:00 PM
1/5/2022 12:00:00 AM
1/5/2022 8:00:00 AM
1/5/2022 4:00:00 PM
1/6/2022 12:00:00 AM
1/6/2022 8:00:00 AM
1/6/2022 4:00:00 PM
1/7/2022 12:00:00 AM
1/7/2022 8:00:00 AM
1/7/2022 4:00:00 PM
1/8/2022 12:00:00 AM
1/8/2022 8:00:00 AM
1/8/2022 4:00:00 PM
1/9/2022 12:00:00 AM
+ 68 more rows

The initial `autogenerate` function creates a calendar containing all the dates in January in a table called `tmpcalendar`.

A second table, containing three records, is created. For each record, `recno() - 1` is taken (values 0, 1, 2) and the result is multiplied by 8. As a result, this generates the values 0, 8 16. These values are used as the hour parameter in a `makeTime()` function, with minute and second values of 0. As a result, the table contains three time fields: 12:00:00 AM, 8:00:00 AM, and 4:00:00 PM.

This table is joined to the `tmpcalendar` table. Because there are no matching fields between the two tables for the join, the time rows are added to each date row. As a result, each date row is now repeated three times with each time value.

Finally, the Calendar table is created from a resident load of the `tmpcalendar` table. The date and time fields are concatenated and wrapped in the `timestamp()` function to create the timestamp field.

The `tmpcalendar` table is then dropped.

## makeweekdate

This function returns a date calculated from the year, the week number, and the day of week .



### Syntax:

```
MakeWeekDate(weekyear [, week [, weekday [, first_week_day [, broken_weeks [, reference_day]]]])
```

### Return data type: dual

The `makeweekdate()` function is available both as script and chart function. The function will calculate the date based on the parameters passed into the function.

#### Arguments

Argument	Description
<b>weekyear</b>	<p>The year as defined by the <code>weekyear()</code> function for the specific date, that is the year to which the week number belongs.</p> <div style="border: 1px solid #ccc; padding: 5px; margin-top: 10px;"> <p> <i>The week year can in some cases be different from the calendar year, for example if week 1 starts already in December of the previous year.</i></p> </div>
<b>week</b>	<p>The week number as defined by the <code>week()</code> function for the specific date.</p> <p>If no week number is stated, 1 is assumed.</p>
<b>weekday</b>	<p>The day-of-week as defined by the <code>weekday()</code> function for the date in question. 0 is the first day of the week, and 6 is the last day of the week.</p> <p>If no day-of-week is stated, 0 is assumed.</p> <div style="border: 1px solid #ccc; padding: 5px; margin-top: 10px;"> <p> <i>Even though 0 always means first day of the week and 6 is always the last, which weekdays that corresponds to is determined by the <b>first_week_day</b> parameter. If omitted, the value of variable <b>FirstWeekDay</b> is used.</i></p> </div> <p>If broken weeks are used, together with an impossible combination of parameters, this may lead to a result that does not belong to the chosen year.</p> <p><b>Example:</b></p> <pre>MakeweekDate(2021, 1, 0, 6, 1)</pre> <p>Returns 'Dec 27 2020' since this day is the first day (the Sunday) of the specified week. Jan 1 2021 was a Friday.</p>

Argument	Description
<b>first_week_day</b>	Specifies the day on which the week starts. If omitted, the value of variable <b>FirstWeekDay</b> is used.  The possible values <b>first_week_day</b> are 0 for Monday, 1 for Tuesday, 2 for Wednesday, 3 for Thursday, 4 for Friday, 5 for Saturday, and 6 for Sunday.  For more information about the system variable, see <i>FirstWeekDay</i> (page 228).
<b>broken_weeks</b>	If you don't specify <b>broken_weeks</b> , the value of variable <b>BrokenWeeks</b> is used to define whether weeks are broken or not.
<b>reference_day</b>	If you don't specify <b>reference_day</b> , the value of variable <b>ReferenceDay</b> is used to define which day in January to set as reference day to define week 1.

### When to use it

The `makeweekdate()` function would commonly be used in the script for data generation to generate a list of dates, or to construct dates when the year, week and day-of-week are provided in the input data.

The following examples assume:

```
SET FirstWeekDay=0;
SET BrokenWeeks=0;
SET ReferenceDay=4;
```

#### Function examples

Example	Result
<code>makeweekdate(2014,6,6)</code>	returns 02/09/2014
<code>makeweekdate(2014,6,1)</code>	returns 02/04/2014
<code>makeweekdate(2014,6)</code>	returns 02/03/2014 (weekday 0 is assumed)

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.



### Example 1 – day included

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing weekly sales total for 2022 in a table called sales.
- Transaction dates provided across three fields: year, week, and sales.
- A preceding load which is used to create a measure end\_of\_week, using the makeweekdate() function to return the date for the Friday of that week in the format MM/DD/YYYY.

To prove that the date returned is a Friday, the end\_of\_week expression is also wrapped in the weekday() function to show the day of the week.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
SET FirstWeekDay=0;
SET BrokenWeeks=0;
SET ReferenceDay=4;
```

Transactions:

```
Load
    *,
    makeweekdate(transaction_year, transaction_week,4) as end_of_week,
    weekday(makeweekdate(transaction_year, transaction_week,4)) as week_day
;
Load * Inline [
transaction_year, transaction_week, sales
2022, 01, 10000
2022, 02, 11250
2022, 03, 9830
2022, 04, 14010
2022, 05, 28402
2022, 06, 9992
2022, 07, 7292
];
```

#### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- transaction\_year
- transaction\_week
- end\_of\_week
- week\_day

Results table

transaction_year	transaction_week	end_of_week	week_day
2022	01	01/07/2022	Fri
2022	02	01/14/2022	Fri
2022	03	01/21/2022	Fri
2022	04	01/28/2022	Fri
2022	05	02/04/2022	Fri
2022	06	02/11/2022	Fri
2022	07	02/18/2022	Fri

The `end_of_week` field is created in the preceding load statement by using the `makeweekdate()` function. The `transaction_year`, `transaction_week` fields are passed through the function as the year and week arguments. A value of 4 is used for the day argument.

The function then combines and converts these values into a date field, returning the results in the format of the `DateFormat` system variable.

The `makeweekdate()` function, and its arguments are also wrapped in a `weekday()` function to return the `week_day` field; and as can be seen in the table above, the `week_day` field shows that these dates do occur on a Friday.

### Example 2 – day excluded

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing weekly sales totals for 2022 in a table called `sales`.
- Transaction dates provided across three fields: `year`, `week`, and `sales`.
- A preceding load, which is used to create a measure, `first_day_of_week`, using the `makeweekdate()` function. This will return the date for the Monday of that week in the format `MM/DD/YYYY`.

To prove that the date returned is a Monday, the `first_day_of_week` expression is also wrapped in the `weekday()` function to show the day of the week.

#### Load script

```
SET DateFormat='MM/DD/YYYY';  
SET FirstWeekDay=0;  
SET BrokenWeeks=0;
```

```
SET ReferenceDay=4;
```

```
Transactions:
```

```
    Load
        *,
        makeweekdate(transaction_year, transaction_week) as first_day_of_week,
        weekday(makeweekdate(transaction_year, transaction_week)) as week_day
    ;
Load * Inline [
transaction_year, transaction_week, sales
2022, 01, 10000
2022, 02, 11250
2022, 03, 9830
2022, 04, 14010
2022, 05, 28402
2022, 06, 9992
2022, 07, 7292
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- transaction\_year
- transaction\_week
- first\_day\_of\_week
- week\_day

Results table

transaction_year	transaction_week	first_day_of_week	week_day
2022	01	01/03/2022	Mon
2022	02	01/10/2022	Mon
2022	03	01/17/2022	Mon
2022	04	01/24/2022	Mon
2022	05	01/31/2022	Mon
2022	06	02/07/2022	Mon
2022	07	02/14/2022	Mon

The `first_day_of_week` field is created in the preceding load statement by using the `makeweekdate()` function. The `transaction_year` and `transaction_week` parameters are passed as function arguments, and the day parameter is left blank.

The function then combines and converts these values into a date field, returning the results in the format of the `DateFormat` system variable.

The `makeweekdate()` function and its arguments are also wrapped in a `weekday()` function to return the `week_day` field. As can be seen in the table above, the `week_day` field returns Monday in all cases since that parameter was left blank in the `makeweekdate()` function, which defaults to 0 (first day of the week), and first day of the week is set to Monday by the `FirstWeekDay` system variable.

### Example 3 – Chart object example

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing weekly sales totals for 2022 in a table called `sales`.
- Transaction dates provided across three fields: `year`, `week`, and `sales`.

In this example, a chart object will be used to create a measure equivalent to the `end_of_week` calculation from the first example. This measure will use the `makeweekdate()` function to return the date for the Friday of that week in the format `MM/DD/YYYY`.

To prove that the date returned is a Friday, a second measure is created to return the day of the week.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
SET FirstWeekDay=0;
SET BrokenWeeks=0;
SET ReferenceDay=4;

Master_Calendar:
Load * Inline [
transaction_year, transaction_week, sales
2022, 01, 10000
2022, 02, 11250
2022, 03, 9830
2022, 04, 14010
2022, 05, 28402
2022, 06, 9992
2022, 07, 7292
];
```

## Results

### Do the following:

1. Load the data and open a sheet. Create a new table and add these fields as dimensions:
  - transaction\_year
  - transaction\_week
2. To perform the calculation equivalent to that of the end\_of\_weekfield from the first example, create the following measure:  
`=makeweekdate(transaction_year,transaction_week,4)`
3. To calculate the day of the week for each transaction, create the following measure:  
`=weekday(makeweekdate(transaction_year,transaction_week,4))`

Results table

transaction_year	transaction_week	=makeweekdate(transaction_year,transaction_week,4)	=weekday(makeweekdate(transaction_year,transaction_week,4))
2022	01	01/07/2022	Fri
2022	02	01/14/2022	Fri
2022	03	01/21/2022	Fri
2022	04	01/28/2022	Fri
2022	05	02/04/2022	Fri
2022	06	02/11/2022	Fri
2022	07	02/18/2022	Fri

An equivalent field to end\_of\_week is created in the chart object as a measure by using the makeweekdate() function. The transaction\_year and transaction\_week fields are passed as year and week arguments. A value of 4 is used for the day argument.

The function then combines and converts these values into a date field, returning the results in the format of the dateFormat system variable.

The makeweekdate() function and its arguments are also wrapped in a weekday() function to return a calculation equivalent to that of the week\_day field from the first example. As can be seen in the table above, the last column on the right shows that these dates do occur on a Friday.

## Example 4 – Scenario

Load script and chart expression

### Overview

In this example, create a list of dates containing all the Fridays for the year 2022.

Open the Data load editor and add the load script below to a new tab.

### Load script

```
SET DateFormat='MM/DD/YYYY';
SET FirstWeekDay=0;
SET BrokenWeeks=0;
SET ReferenceDay=4;

Calendar:
  Load
    *,
    weekday(date) as weekday
  where year(date)=2022;
Load
  makeweekdate(2022,recno()-2,4) as date
AutoGenerate 60;
```

### Results

Results table

date	weekday
01/07/2022	Fri
01/14/2022	Fri
01/21/2022	Fri
01/28/2022	Fri
02/04/2022	Fri
02/11/2022	Fri
02/18/2022	Fri
02/25/2022	Fri
03/04/2022	Fri
03/11/2022	Fri
03/18/2022	Fri
03/25/2022	Fri
04/01/2022	Fri
04/08/2022	Fri
04/15/2022	Fri
04/22/2022	Fri
04/29/2022	Fri

date	weekday
05/06/2022	Fri
05/13/2022	Fri
05/20/2022	Fri
05/27/2022	Fri
06/03/2022	Fri
06/10/2022	Fri
06/17/2022	Fri
+ 27 more rows	

The `makeweekdate()` function finds each Friday in 2022. Using a week parameter of `-2` ensures that no dates are missed. Finally, a preceding load creates an additional `weekday` field for clarity, to show that each date value is a Friday.

### minute

This function returns an integer representing the minute when the fraction of the **expression** is interpreted as a time according to the standard number interpretation.

#### Syntax:

```
minute (expression)
```

**Return data type:** integer

#### When to use it

The `minute()` function is useful when you would like to compare aggregations by minute. For example, you could use the function if you would like to see activity count distribution by minute.

These dimensions can be created either in the load script by using the function to create a field in a Master Calendar table. Alternatively, they can be used directly in a chart as a calculated dimension.

#### Function examples

Example	Result
<code>minute ( '09:14:36' )</code>	Returns 14.
<code>minute ( '0.5555' )</code>	Returns 19 ( Because $0.5555 = 13:19:55$ ).

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default

date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Example 1 – Variable (script)

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing transactions by timestamp, which is loaded into a table called Transactions.
- The default `timestamp` system variable (`(M/D/YYYY h:mm:ss[.fff] TT)`) is used.
- The creation of a field, `minute`, to calculate when transactions took place.

#### Load script

```
SET TimestampFormat='M/D/YYYY h:mm:ss[.fff] TT';
```

```
Transactions:
```

```
Load
  *,
  minute(timestamp) as minute
;
```

```
Load
```

```
*
```

```
Inline
```

```
[
id,timestamp,amount
9497,'2022-01-05 19:04:57',47.25,
9498,'2022-01-03 14:21:53',51.75,
9499,'2022-01-03 05:40:49',73.53,
9500,'2022-01-04 18:49:38',15.35,
9501,'2022-01-01 22:10:22',31.43,
9502,'2022-01-05 19:34:46',13.24,
9503,'2022-01-04 22:58:34',74.34,
9504,'2022-01-06 11:29:38',50.00,
9505,'2022-01-02 08:35:54',36.34,
9506,'2022-01-06 08:49:09',74.23
];
```



### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- timestamp
- minute

Results table

timestamp	minute
2022-01-01 22:10:22	10
2022-01-02 08:35:54	35
2022-01-03 05:40:49	40
2022-01-03 14:21:53	21
2022-01-04 18:49:38	49
2022-01-04 22:58:34	58
2022-01-05 19:04:57	4
2022-01-05 19:34:46	34
2022-01-06 08:49:09	49
2022-01-06 11:29:38	29

The values in the `minute` field are created by using the `minute()` function and passing the `timestamp` as the expression in the preceding load statement.

### Example 2 – Chart object (chart)

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same dataset and scenario as the first example.
- The default `Timestamp` system variable (`(M/D/YYYY h:mm:ss[.fff] TT)`) is used.

However, in this example, the unchanged dataset is loaded into the application. The `minute` values are calculated via a measure in a chart object.

#### Load script

```
SET TimestampFormat='M/D/YYYY h:mm:ss[.fff] TT';
```

Transactions:

Load

\*

Inline

[

id,timestamp,amount

9497,'2022-01-05 19:04:57',47.25,

9498,'2022-01-03 14:21:53',51.75,

9499,'2022-01-03 05:40:49',73.53,

9500,'2022-01-04 18:49:38',15.35,

9501,'2022-01-01 22:10:22',31.43,

9502,'2022-01-05 19:34:46',13.24,

9503,'2022-01-04 22:58:34',74.34,

9504,'2022-01-06 11:29:38',50.00,

9505,'2022-01-02 08:35:54',36.34,

9506,'2022-01-06 08:49:09',74.23

];

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension: `timestamp`.

Create the following measure:

```
=minute(timestamp)
```

Results table

timestamp	minute
2022-01-01 22:10:22	10
2022-01-02 08:35:54	35
2022-01-03 05:40:49	40
2022-01-03 14:21:53	21
2022-01-04 18:49:38	49
2022-01-04 22:58:34	58
2022-01-05 19:04:57	4
2022-01-05 19:34:46	34
2022-01-06 08:49:09	49
2022-01-06 11:29:38	29

The values for `minute` are created by using the `minute()` function and passing the `timestamp` as the expression in a measure for the chart object.

### Example 3 – Scenario

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset of timestamps, which is generated to represent entries at a ticket barrier.
- Information with each timestamp and its corresponding id, which is loaded into a table called Ticket\_Barrier\_Tracker.
- The default timestamp system variable (M/D/YYYY h:mm:ss[.fff] TT) is used.

The user would like a chart object that shows, by minute, the count of barrier entries.

#### Load script

```
SET TimestampFormat='M/D/YYYY h:mm:ss[.fff] TT';

tmpTimeStampCreator:
    load
        *
        where year(date)=2022;
load
    date(recno()+makedate(2021,12,31)) as date
AutoGenerate 1;

join load
    maketime(floor(rand()*24),floor(rand()*59),floor(rand()*59)) as time
autogenerate 10000;

Ticket_Barrier_Tracker:
load
    recno() as id,
    timestamp(date + time) as timestamp
resident tmpTimeStampCreator;

drop table tmpTimeStampCreator;
```

#### Results

##### Do the following:

1. Load the data and open a sheet. Create a new table.
2. Create a calculated dimension using the following expression:  
=minute(timestamp)
3. Add the following aggregation measure to calculate total count of entries:

=count(id)

4. Set the measure's **Number formatting** to **Money**.

Results table

<b>minute(timestamp)</b>	<b>=count(id)</b>
0	174
1	171
2	175
3	165
4	188
5	176
6	158
7	187
8	178
9	178
10	197
11	161
12	166
13	184
14	159
15	161
16	152
17	160
18	176
19	164
20	170
21	170
22	142
23	145
24	155
+ 35 more rows	

## month

This function returns a dual value: a month name as defined in the environment variable **MonthNames** and an integer between 1-12. The month is calculated from the date interpretation of the expression, according to the standard number interpretation.

The function returns the name of the month in the format of the `monthName` system variable for a particular date. It is commonly used to create a day field as a dimension in a Master Calendar.

### Syntax:

```
month (expression)
```

**Return data type:** integer

### Function examples

Example	Result
<code>month( 2012-10-12 )</code>	returns Oct
<code>month( 35648 )</code>	returns Aug, because 35648 = 1997-08-06

## Example 1 – DateFormat dataset (script)

Load script and results

### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset of dates named `master_calendar`. The `dateFormat` system variable is set to `DD/MM/YYYY`.
- A preceding load that creates an additional field, named `month_name`, using the `month()` function.
- An additional field, named `long_date`, using the `date()` function to express the full date.

### Load script

```
SET DateFormat='DD/MM/YYYY';
```

```
Master_Calendar:
```

```
Load
```

```
    date,
    date(date, 'dd-MMM-YYYY') as long_date,
    month(date) as month_name
```

```
Inline
```

```
[
```

```
date
03/01/2022
03/02/2022
03/03/2022
03/04/2022
03/05/2022
03/06/2022
03/07/2022
03/08/2022
03/09/2022
03/10/2022
03/11/2022
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- long\_date
- month\_name

Results table

date	long_date	month_name
03/01/2022	03-January- 2022	Jan
03/02/2022	03-February- 2022	Feb
03/03/2022	03-March- 2022	Mar
03/04/2022	03-April- 2022	Apr
03/05/2022	03-May- 2022	May
03/06/2022	03-June- 2022	Jun
03/07/2022	03-July- 2022	Jul
03/08/2022	03-August- 2022	Aug
03/09/2022	03-September- 2022	Sep
03/10/2022	03-October- 2022	Oct
03/11/2022	03-November- 2022	Nov

The month name is correctly evaluated by the `month()` function in the script.

### Example 2 – ANSI dates (script)

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset of dates named `master_calendar`. The `DateFormat` system variable `DD/MM/YYYY` is used. However, the dates that are included in the dataset are in ANSI standard date format.
- A preceding load that creates an additional field, named `month_name`, using the `month()` function.
- An additional field, named `long_date`, using the `date()` function to express the full date.

### Load script

```
SET DateFormat='DD/MM/YYYY';
Master_Calendar:
Load
    date,
    date(date,'dd-MMMM-YYYY') as long_date,
    month(date) as month_name
```

```
Inline
[
date
2022-01-11
2022-02-12
2022-03-13
2022-04-14
2022-05-15
2022-06-16
2022-07-17
2022-08-18
2022-09-19
2022-10-20
2022-11-21
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- `date`
- `long_date`
- `month_name`

Results table

<b>date</b>	<b>long_date</b>	<b>month_name</b>
03/11/2022	11-March- 2022	11
03/12/2022	12-March- 2022	12
03/13/2022	13-March- 2022	13
03/14/2022	14-March- 2022	14

date	long_date	month_name
03/15/2022	15-March- 2022	15
03/16/2022	16-March- 2022	16
03/17/2022	17-March- 2022	17
03/18/2022	18-March- 2022	18
03/19/2022	19-March- 2022	19
03/20/2022	20-March- 2022	20
03/21/2022	21-March- 2022	21

The month name is correctly evaluated by the `month()` function in the script.

### Example 3 – Unformatted dates (script)

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset of dates named `master_calendar`. The `dateFormat` system variable `DD/MM/YYYY` is used.
- A preceding load that creates an additional field, named `month_name`, using the `month()` function.
- The original unformatted date, named `unformatted_date`.
- An additional field, named `long_date`, using the `date()` function to express the full date.

#### Load script

```
SET dateFormat='DD/MM/YYYY';
```

```
Master_calendar:
```

```
Load
```

```
    unformatted_date,  
    date(unformatted_date, 'dd-MMM-YYYY') as long_date,  
    month(unformatted_date) as month_name
```

```
Inline
```

```
[
```

```
unformatted_date
```

```
44868
```

```
44898
```

```
44928
```

```
44958
```

```
44988
```



```
45018
45048
45078
45008
45038
45068
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- unformatted\_date
- long\_date
- month\_name

Results table

unformatted_date	long_date	month_name
44868	03-January- 2022	Jan
44898	03-February- 2022	Feb
44928	03-March- 2022	Mar
44958	03-April- 2022	Apr
44988	03-May- 2022	May
45018	03-June- 2022	Jun
45048	03-July- 2022	Jul
45078	03-August- 2022	Aug
45008	03-September- 2022	Sep
45038	03-October- 2022	Oct
45068	03-November- 2022	Nov

The month name is correctly evaluated by the `month()` function in the script.

### Example 4 – Calculating expiry month

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset of orders placed in March named subscriptions. The table contains three fields:
  - id
  - order\_date
  - amount

### Load script

Subscriptions:

Load

```
    id,  
    order_date,  
    amount
```

Inline

```
[  
id,order_date,amount  
1,03/01/2022,231.24  
2,03/02/2022,567.28  
3,03/03/2022,364.28  
4,03/04/2022,575.76  
5,03/05/2022,638.68  
6,03/06/2022,785.38  
7,03/07/2022,967.46  
8,03/08/2022,287.67  
9,03/09/2022,764.45  
10,03/10/2022,875.43  
11,03/11/2022,957.35  
];
```

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension: order\_date.

To calculate the month an order will expire, create this measure =month(order\_date+180).

Results table

order_date	=month(order_date+180)
03/01/2022	Jul
03/02/2022	Aug
03/03/2022	Aug
03/04/2022	Sep
03/05/2022	Oct
03/06/2022	Nov
03/07/2022	Dec
03/08/2022	Jan

<b>order_date</b>	<b>=month(order_date+180)</b>
03/09/2022	Mar
03/10/2022	Apr
03/11/2022	May

The `month()` function correctly determines that an order placed on the 11th of March would expire in July.

### monthend


This function returns a value corresponding to a timestamp of the last millisecond of the last day of the month containing `date`. The default output format will be the `DateFormat` set in the script.

#### Syntax:

**MonthEnd**(date[, period\_no])

In other words, the `monthend()` function determines which month the date falls into. It then returns a timestamp, in date format, for the last millisecond of that month.

*Diagram of monthend function.*



#### When to use it

The `monthend()` function is used as part of an expression when you would like the calculation to use the fraction of the month that has not yet occurred. For example, if you want to calculate the total interest not yet incurred during the month.

**Return data type:** dual

#### Arguments

Argument	Description
<b>date</b>	The date or timestamp to evaluate.
<b>period_no</b>	<b>period_no</b> is an integer, which, if 0 or omitted, indicates the month that contains <b>date</b> . Negative values in <b>period_no</b> indicate preceding months and positive values indicate succeeding months.

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

#### Function examples

Example	Result
<code>monthend('02/19/2012')</code>	Returns 02/29/2012 23:59:59.
<code>monthend('02/19/2001', -1)</code>	Returns 01/31/2001 23:59:59.

### Example 1 – Basic example

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions for 2022 that is loaded into a table called 'Transactions'.
- A date field in the `DateFormat` system variable (MM/DD/YYYY) format.
- A preceding load statement that contains:
  - The `monthend()` function which is set as the 'end\_of\_month' field.
  - The `timestamp` function which is set as the 'end\_of\_month\_timestamp' field.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
  Load
    *,
    monthend(date) as end_of_month,
    timestamp(monthend(date)) as end_of_month_timestamp
  ;
```

```
Load
```

```
*
Inline
[
id,date,amount
8188,1/7/2022,17.17
8189,1/19/2022,37.23
8190,2/28/2022,88.27
8191,2/5/2022,57.42
8192,3/16/2022,53.80
8193,4/1/2022,82.06
8194,5/7/2022,40.39
8195,5/16/2022,87.21
8196,6/15/2022,95.93
8197,6/26/2022,45.89
8198,7/9/2022,36.23
8199,7/22/2022,25.66
8200,7/23/2022,82.77
8201,7/27/2022,69.98
8202,8/2/2022,76.11
8203,8/8/2022,25.12
8204,8/19/2022,46.23
8205,9/26/2022,84.21
8206,10/14/2022,96.24
8207,10/29/2022,67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- id
- date
- end\_of\_month
- end\_of\_month\_timestamp

Results table

id	date	end_of_month	end_of_month_timestamp
8188	1/7/2022	01/31/2022	1/31/2022 11:59:59 PM
8189	1/19/2022	01/31/2022	1/31/2022 11:59:59 PM
8190	2/5/2022	02/28/2022	2/28/2022 11:59:59 PM
8191	2/28/2022	02/28/2022	2/28/2022 11:59:59 PM
8192	3/16/2022	03/31/2022	3/31/2022 11:59:59 PM
8193	4/1/2022	04/30/2022	4/30/2022 11:59:59 PM
8194	5/7/2022	05/31/2022	5/31/2022 11:59:59 PM
8195	5/16/2022	05/31/2022	5/31/2022 11:59:59 PM


## 8 Script and chart functions

id	date	end_of_month	end_of_month_timestamp
8196	6/15/2022	06/30/2022	6/30/2022 11:59:59 PM
8197	6/26/2022	06/30/2022	6/30/2022 11:59:59 PM
8198	7/9/2022	07/31/2022	7/31/2022 11:59:59 PM
8199	7/22/2022	07/31/2022	7/31/2022 11:59:59 PM
8200	7/23/2022	07/31/2022	7/31/2022 11:59:59 PM
8201	7/27/2022	07/31/2022	7/31/2022 11:59:59 PM
8202	8/2/2022	08/31/2022	8/31/2022 11:59:59 PM
8203	8/8/2022	08/31/2022	8/31/2022 11:59:59 PM
8204	8/19/2022	08/31/2022	8/31/2022 11:59:59 PM
8205	9/26/2022	09/30/2022	9/30/2022 11:59:59 PM
8206	10/14/2022	10/31/2022	10/31/2022 11:59:59 PM
8207	10/29/2022	10/31/2022	10/31/2022 11:59:59 PM

The 'end\_of\_month' field is created in the preceding load statement by using the `monthend()` function and passing the date field as the function's argument.

The `monthend()` function identifies which month the date value falls into returning a timestamp for the last millisecond of that month.

*Diagram of monthend function with March as the selected month.*



Transaction 8192 took place on March 16. The `monthend()` function returns the last millisecond of that month, which is March 31 at 11:59:59 PM.

### Example 2 – period\_no

Load script and results

#### Overview

The same dataset and scenario as the first example are used.

In this example, the task is to create a field, 'previous\_month\_end', that returns the timestamp for the end of the month before the transaction took place.

### Load script

```
SET DateFormat='MM/DD/YYYY';

Transactions:
  Load
    *,
    monthend(date,-1) as previous_month_end,
    timestamp(monthend(date,-1)) as previous_month_end_timestamp
  ;
Load
*
Inline
[
id,date,amount
8188,1/7/2022,17.17
8189,1/19/2022,37.23
8190,2/28/2022,88.27
8191,2/5/2022,57.42
8192,3/16/2022,53.80
8193,4/1/2022,82.06
8194,5/7/2022,40.39
8195,5/16/2022,87.21
8196,6/15/2022,95.93
8197,6/26/2022,45.89
8198,7/9/2022,36.23
8199,7/22/2022,25.66
8200,7/23/2022,82.77
8201,7/27/2022,69.98
8202,8/2/2022,76.11
8203,8/8/2022,25.12
8204,8/19/2022,46.23
8205,9/26/2022,84.21
8206,10/14/2022,96.24
8207,10/29/2022,67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- id
- date
- previous\_month\_end
- previous\_month\_end\_timestamp


## 8 Script and chart functions

Results table

id	date	previous_month_end	previous_month_end_timestamp
8188	1/7/2022	12/31/2021	12/31/2021 11:59:59 PM
8189	1/19/2022	12/31/2021	12/31/2021 11:59:59 PM
8190	2/5/2022	01/31/2022	1/31/2022 11:59:59 PM
8191	2/28/2022	01/31/2022	1/31/2022 11:59:59 PM
8192	3/16/2022	02/28/2022	2/28/2022 11:59:59 PM
8193	4/1/2022	03/31/2022	3/31/2022 11:59:59 PM
8194	5/7/2022	04/30/2022	4/30/2022 11:59:59 PM
8195	5/16/2022	04/30/2022	4/30/2022 11:59:59 PM
8196	6/15/2022	05/31/2022	5/31/2022 11:59:59 PM
8197	6/26/2022	05/31/2022	5/31/2022 11:59:59 PM
8198	7/9/2022	06/30/2022	6/30/2022 11:59:59 PM
8199	7/22/2022	06/30/2022	6/30/2022 11:59:59 PM
8200	7/23/2022	06/30/2022	6/30/2022 11:59:59 PM
8201	7/27/2022	06/30/2022	6/30/2022 11:59:59 PM
8202	8/2/2022	07/31/2022	7/31/2022 11:59:59 PM
8203	8/8/2022	07/31/2022	7/31/2022 11:59:59 PM
8204	8/19/2022	07/31/2022	7/31/2022 11:59:59 PM
8205	9/26/2022	08/31/2022	8/31/2022 11:59:59 PM
8206	10/14/2022	09/30/2022	9/30/2022 11:59:59 PM
8207	10/29/2022	09/30/2022	9/30/2022 11:59:59 PM

The `monthend()` function first identifies the month that the transactions take place in as `aperiod_no` of -1 is used as the offset argument. It then shifts one month prior and identifies the final millisecond of that month.

*Diagram of `monthend` function with the `period_no` variable.*





Transaction 8192 took place on March 16. The `monthend()` function identifies that the month before the transaction took place in was February. It then returns the final millisecond of that month, February 28 at 11:59:59 PM.

### Example 3 – Chart example

Load script and chart expression

#### Overview

The same dataset and scenario as the first example are used.

In this example, the dataset is unchanged and loaded into the app. The task is to create a calculation that returns a timestamp for the end of the month when the transactions took place as a measure in a chart of the app.

#### Load script

```
Transactions:
Load
*
Inline
[
id,date,amount
8188,1/7/2022,17.17
8189,1/19/2022,37.23
8190,2/28/2022,88.27
8191,2/5/2022,57.42
8192,3/16/2022,53.80
8193,4/1/2022,82.06
8194,5/7/2022,40.39
8195,5/16/2022,87.21
8196,6/15/2022,95.93
8197,6/26/2022,45.89
8198,7/9/2022,36.23
8199,7/22/2022,25.66
8200,7/23/2022,82.77
8201,7/27/2022,69.98
8202,8/2/2022,76.11
8203,8/8/2022,25.12
8204,8/19/2022,46.23
8205,9/26/2022,84.21
8206,10/14/2022,96.24
8207,10/29/2022,67.67
];
```

#### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- id

## 8 Script and chart functions

---

To calculate the end date of the month that a transaction takes place in, create the following measures:

- `=monthend(date)`
- `=timestamp(monthend(date))`


Results table

<b>id</b>	<b>date</b>	<b>=monthend(date)</b>	<b>=timestamp(monthend(date))</b>
8188	10/14/2022	10/31/2022	10/31/2022 11:59:59 PM
8189	10/29/2022	10/31/2022	10/31/2022 11:59:59 PM
8190	9/26/2022	09/30/2022	9/30/2022 11:59:59 PM
8191	8/2/2022	08/31/2022	8/31/2022 11:59:59 PM
8192	8/8/2022	08/31/2022	8/31/2022 11:59:59 PM
8193	8/19/2022	08/31/2022	8/31/2022 11:59:59 PM
8194	7/9/2022	07/31/2022	7/31/2022 11:59:59 PM
8195	7/22/2022	07/31/2022	7/31/2022 11:59:59 PM
8196	7/23/2022	07/31/2022	7/31/2022 11:59:59 PM
8197	7/27/2022	07/31/2022	7/31/2022 11:59:59 PM
8198	6/15/2022	06/30/2022	6/30/2022 11:59:59 PM
8199	6/26/2022	06/30/2022	6/30/2022 11:59:59 PM
8200	5/7/2022	05/31/2022	5/31/2022 11:59:59 PM
8201	5/16/2022	05/31/2022	5/31/2022 11:59:59 PM
8202	4/1/2022	04/30/2022	4/30/2022 11:59:59 PM
8203	3/16/2022	03/31/2022	3/31/2022 11:59:59 PM
8204	2/5/2022	02/28/2022	2/28/2022 11:59:59 PM
8205	2/28/2022	02/28/2022	2/28/2022 11:59:59 PM
8206	1/7/2022	01/31/2022	1/31/2022 11:59:59 PM
8207	1/19/2022	01/31/2022	1/31/2022 11:59:59 PM

The 'end\_of\_month' measure is created in the chart by using the `monthend()` function and passing the date field as the function's argument.

The `monthend()` function identifies which month the date value falls into and returns a timestamp for the last millisecond of that month.

Diagram of `monthend` function with the `period_no` variable.



Transaction 8192 took place on March 16. The `monthend()` function returns the last millisecond of that month, which is March 31 at 11:59:59 PM.

### Example 4 – Scenario

Load script and results

#### Overview

In this example, a dataset is loaded into a table called 'Employee\_Expenses'. The table contains the following fields:

- Employee IDs
- Employee names
- The average daily expense claims of each employee.

The end user would like a chart that displays, by employee id and employee name, the estimated expense claim for the remainder of the month.

#### Load script

```
Employee_Expenses :
Load
*
Inline
[
employee_id,employee_name,avg_daily_claim
182,Mark, $15
183,Deryck, $12.5
184,Dexter, $12.5
185,sydney,$27
186,Agatha,$18
];
```

#### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- employee\_id
- employee\_name

To calculate the accumulated interest, create this measure:

```
=floor(monthend(today(1),0)-today(1))*avg_daily_claim
```



*This measure is dynamic and will produce different table results depending on the date when you load the data.*

Set the measure's **Number formatting** to **Money**.

Results table

employee_id	employee_name	=floor(monthend(today(1),0)-today(1))*avg_daily_claim
182	Mark	\$30.00
183	Deryck	\$25.00
184	Dexter	\$25.00
185	Sydney	\$54.00
186	Agatha	\$36.00

The `monthend()` function returns the end date of the current month by using today's date as its only argument. The expression returns the number of days that remain this month by subtracting today's date from the month end date.

This value is then multiplied by the average daily expense claim by each employee to calculate the estimated value of claims each employee is expected to make in the remaining month.

## monthname


This function returns a display value showing the month (formatted according to the **MonthNames** script variable) and year with an underlying numeric value corresponding to a timestamp of the first millisecond of the first day of the month.

### Syntax:

```
MonthName (date[, period_no])
```

**Return data type:** dual

*Diagram of monthname function*



### Arguments

Argument	Description
<b>date</b>	The date or timestamp to evaluate.
<b>period_no</b>	<b>period_no</b> is an integer, which, if 0 or omitted, indicates the month that contains <b>date</b> . Negative values in <b>period_no</b> indicate preceding months and positive values indicate succeeding months.

### Function examples

Example	Result
<code>monthname('10/19/2013')</code>	Returns Oct 2013
<code>monthname('10/19/2013', -1)</code>	Returns Sep 2013

## Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Example 1 – Basic example

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions for 2022, which is loaded into a table called Transactions.
- The date field provided in the `dateFormat` system variable (MM/DD/YYYY) format.
- The creation of a field, `transaction_month`, that returns the month in which the transactions took place.

#### Load script

```
SET DateFormat='MM/DD/YYYY';  
SET MonthNames='Jan;Feb;Mar;Apr;May;Jun;Jul;Aug;Sep;Oct;Nov;Dec';
```

Transactions:

```
Load  
    *,  
    monthname(date) as transaction_month  
    ;
```

Load

\*

Inline

[

id,date,amount

8188,1/7/2022,17.17

8189,1/19/2022,37.23

8190,2/28/2022,88.27

8191,2/5/2022,57.42

8192,3/16/2022,53.80

8193,4/1/2022,82.06

8194,5/7/2022,40.39

8195,5/16/2022,87.21

8196,6/15/2022,95.93

8197,6/26/2022,45.89

8198,7/9/2022,36.23

8199,7/22/2022,25.66

8200,7/23/2022,82.77

8201,7/27/2022,69.98

8202,8/2/2022,76.11

8203,8/8/2022,25.12

8204,8/19/2022,46.23

8205,9/26/2022,84.21

8206,10/14/2022,96.24

8207,10/29/2022,67.67

];

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:


- date
- transaction\_month

Results table

<b>date</b>	<b>transaction_month</b>
1/7/2022	Jan 2022
1/19/2022	Jan 2022
2/5/2022	Feb 2022
2/28/2022	Feb 2022
3/16/2022	Mar 2022
4/1/2022	Apr 2022
5/7/2022	May 2022
5/16/2022	May 2022
6/15/2022	Jun 2022
6/26/2022	Jun 2022
7/9/2022	Jul 2022
7/22/2022	Jul 2022
7/23/2022	Jul 2022
7/27/2022	Jul 2022
8/2/2022	Aug 2022
8/8/2022	Aug 2022
8/19/2022	Aug 2022
9/26/2022	Sep 2022
10/14/2022	Oct 2022
10/29/2022	Oct 2022

The `transaction_month` field is created in the preceding load statement by using the `monthname()` function and passing the `date` field as the function's argument.

Diagram of monthname function, basic example



The `monthname()` function identifies that transaction 8192 took place in March 2022, and returns this value using the `MonthNames` system variable.

### Example 2 – period\_no

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same inline dataset and scenario as the first example.
- The creation of a field, `transaction_previous_month`, that returns the timestamp for the end of the month before the transaction took place.

#### Load script

```
SET DateFormat='MM/DD/YYYY';  
SET MonthNames='Jan;Feb;Mar;Apr;May;Jun;Jul;Aug;Sep;Oct;Nov;Dec';
```

Transactions:

```
Load  
*,  
monthname(date,-1) as transaction_previous_month  
;
```

Load

\*

Inline

```
[  
id,date,amount  
8188,1/7/2022,17.17  
8189,1/19/2022,37.23  
8190,2/28/2022,88.27  
8191,2/5/2022,57.42  
8192,3/16/2022,53.80  
8193,4/1/2022,82.06  
8194,5/7/2022,40.39
```



```
8195, 5/16/2022, 87.21
8196, 6/15/2022, 95.93
8197, 6/26/2022, 45.89
8198, 7/9/2022, 36.23
8199, 7/22/2022, 25.66
8200, 7/23/2022, 82.77
8201, 7/27/2022, 69.98
8202, 8/2/2022, 76.11
8203, 8/8/2022, 25.12
8204, 8/19/2022, 46.23
8205, 9/26/2022, 84.21
8206, 10/14/2022, 96.24
8207, 10/29/2022, 67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- transaction\_previous\_month


Results table

<b>date</b>	<b>transaction_previous_month</b>
1/7/2022	Dec 2021
1/19/2022	Dec 2021
2/5/2022	Jan 2022
2/28/2022	Jan 2022
3/16/2022	Feb 2022
4/1/2022	Mar 2022
5/7/2022	Apr 2022
5/16/2022	Apr 2022
6/15/2022	May 2022
6/26/2022	May 2022
7/9/2022	Jun 2022
7/22/2022	Jun 2022
7/23/2022	Jun 2022
7/27/2022	Jun 2022
8/2/2022	Jul 2022
8/8/2022	Jul 2022
8/19/2022	Jul 2022

date	transaction_previous_month
9/26/2022	Aug 2022
10/14/2022	Sep 2022
10/29/2022	Sep 2022

In this instance, because a `period_no` of -1 was used as the offset argument in the `monthname()` function, the function first identifies the month that the transactions take place in. It then shifts to one month prior and returns the month name and year.

*Diagram of monthname function, period\_no example*



Transaction 8192 took place on March 16. The `monthname()` function identifies that the month before the transaction took place was February and returns the month, in the `MonthNames` system variable format, along with the year 2022.

### Example 3 – Chart object example

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains the same inline dataset and scenario as the first example. However, in this example, the unchanged dataset is loaded into the application. The calculation that returns a timestamp for the end of the month when the transactions took place is created as a measure in a chart object of the application.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
SET MonthNames='Jan;Feb;Mar;Apr;May;Jun;Jul;Aug;Sep;Oct;Nov;Dec';
```

```
Transactions:
Load
```

```
*
Inline
[
id,date,amount
8188,1/7/2022,17.17
8189,1/19/2022,37.23
8190,2/28/2022,88.27
8191,2/5/2022,57.42
8192,3/16/2022,53.80
8193,4/1/2022,82.06
8194,5/7/2022,40.39
8195,5/16/2022,87.21
8196,6/15/2022,95.93
8197,6/26/2022,45.89
8198,7/9/2022,36.23
8199,7/22/2022,25.66
8200,7/23/2022,82.77
8201,7/27/2022,69.98
8202,8/2/2022,76.11
8203,8/8/2022,25.12
8204,8/19/2022,46.23
8205,9/26/2022,84.21
8206,10/14/2022,96.24
8207,10/29/2022,67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension:date.

Create the following measure:

```
=monthname(date)
```


Results table

<b>date</b>	<b>=monthname(date)</b>
1/7/2022	Jan 2022
1/19/2022	Jan 2022
2/5/2022	Feb 2022
2/28/2022	Feb 2022
3/16/2022	Mar 2022
4/1/2022	Apr 2022
5/7/2022	May 2022
5/16/2022	May 2022
6/15/2022	Jun 2022

date	=monthname(date)
6/26/2022	Jun 2022
7/9/2022	Jul 2022
7/22/2022	Jul 2022
7/23/2022	Jul 2022
7/27/2022	Jul 2022
8/2/2022	Aug 2022
8/8/2022	Aug 2022
8/19/2022	Aug 2022
9/26/2022	Sep 2022
10/14/2022	Oct 2022
10/29/2022	Oct 2022

The month\_name measure is created in the chart object by using the monthname() function and passing the date field as the function's argument.

*Diagram of monthname function, chart object example*



The monthname() function identifies that transaction 8192 took place in March 2022, and returns this value using the MonthNames system variable.

### monthsend


This function returns a value corresponding to the timestamp of the last millisecond of the month, bi-month, quarter, four-month period, or half-year containing a base date. It is also possible to find the timestamp for the end of a previous or following time period. The default output format is the DateFormat set in the script.

#### Syntax:

```
MonthsEnd(n_months, date[, period_no [, first_month_of_year]])
```

**Return data type:** dual

Diagram of `monthsend` function.



### Arguments

Argument	Description
<b>n_months</b>	The number of months that defines the period. An integer or expression that resolves to an integer that must be one of: 1 (equivalent to the <code>inmonth()</code> function), 2 (bi-month), 3 (equivalent to the <code>inquarter()</code> function), 4 (four-month period), or 6 (half year).
<b>date</b>	The date or timestamp to evaluate.
<b>period_no</b>	The period can be offset by <b>period_no</b> , an integer, or expression resolving to an integer, where the value 0 indicates the period that contains <b>base_date</b> . Negative values in <b>period_no</b> indicate preceding periods and positive values indicate succeeding periods.
<b>first_month_of_year</b>	If you want to work with (fiscal) years not starting in January, indicate a value between 2 and 12 in <b>first_month_of_year</b> .

The `monthsend()` function divides the year into segments based on the `n_months` argument provided. It then evaluates what segment each date provided falls into and returns the last millisecond, in date format, of that segment. The function can return the end timestamp from preceding or following segments as well as redefine the first month of the year.

The following segments of the year are available in the function as `n_month` arguments.

### n\_month arguments

Period	Number of months
month	1
bi-month	2
quarter	3
four months	4
half-year	6

### When to use it

The `monthsend()` function is used as part of an expression when the user would like the calculation to use the fraction of the month that has elapsed so far. The user has the opportunity, using a variable to select the period of their choosing. For example, the `monthsend()` can provide an input variable to let the user calculate the total interest not yet incurred during the month, quarter, or half-year.

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

Function examples

Example	Result
<code>monthsend(4, '07/19/2013')</code>	Returns 08/31/2013.
<code>monthsend(4, '10/19/2013', -1)</code>	Returns 08/31/2013.
<code>monthsend(4, '10/19/2013', 0, 2)</code>	Returns 01/31/2014. Because the start of the year becomes month 2.

### Example 1 - Basic example

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions for 2022 is loaded into a table called 'Transactions'.
- A date field provided in the `DateFormat` system variable (MM/DD/YYYY) format.
- A preceding load statement containing:
  - The `monthsend` function which is set as the field, 'bi\_monthly\_end'. This groups transactions into bi-monthly segments.

- The `timestamp` function which returns the starting timestamp of the segment for each transaction.

### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
    Load
    *,
    monthsend(2,date) as bi_monthly_end,
    timestamp(monthsend(2,date)) as bi_monthly_end_timestamp
    ;
Load
*
Inline
[
id,date,amount
8188,1/7/2022,17.17
8189,1/19/2022,37.23
8190,2/28/2022,88.27
8191,2/5/2022,57.42
8192,3/16/2022,53.80
8193,4/1/2022,82.06
8194,5/7/2022,40.39
8195,5/22/2022,87.21
8196,6/15/2022,95.93
8197,6/26/2022,45.89
8198,7/9/2022,36.23
8199,7/22/2022,25.66
8200,7/23/2022,82.77
8201,7/27/2022,69.98
8202,8/2/2022,76.11
8203,8/8/2022,25.12
8204,8/19/2022,46.23
8205,9/26/2022,84.21
8206,10/14/2022,96.24
8207,10/29/2022,67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:


- `id`
- `date`
- `bi_monthly_end`
- `bi_monthly_end_timestamp`

Results table

id	date	bi_monthly_end	bi_monthly_end_timestamp
8188	1/7/2022	02/28/2022	2/28/2022 11:59:59 PM
8189	1/19/2022	02/28/2022	2/28/2022 11:59:59 PM
8190	2/5/2022	02/28/2022	2/28/2022 11:59:59 PM
8191	2/28/2022	02/28/2022	2/28/2022 11:59:59 PM
8192	3/16/2022	04/30/2022	4/30/2022 11:59:59 PM
8193	4/1/2022	04/30/2022	4/30/2022 11:59:59 PM
8194	5/7/2022	06/30/2022	6/30/2022 11:59:59 PM
8195	5/22/2022	06/30/2022	6/30/2022 11:59:59 PM
8196	6/15/2022	06/30/2022	6/30/2022 11:59:59 PM
8197	6/26/2022	06/30/2022	6/30/2022 11:59:59 PM
8198	7/9/2022	08/31/2022	8/31/2022 11:59:59 PM
8199	7/22/2022	08/31/2022	8/31/2022 11:59:59 PM
8200	7/23/2022	08/31/2022	8/31/2022 11:59:59 PM
8201	7/27/2022	08/31/2022	8/31/2022 11:59:59 PM
8202	8/2/2022	08/31/2022	8/31/2022 11:59:59 PM
8203	8/8/2022	08/31/2022	8/31/2022 11:59:59 PM
8204	8/19/2022	08/31/2022	8/31/2022 11:59:59 PM
8205	9/26/2022	10/31/2022	10/31/2022 11:59:59 PM
8206	10/14/2022	10/31/2022	10/31/2022 11:59:59 PM
8207	10/29/2022	10/31/2022	10/31/2022 11:59:59 PM

The 'bi\_monthly\_end' field is created in the preceding load statement by using the `monthsend()` function. The first argument provided is 2, dividing the year into bi-monthly segments. The second argument identifies which field is being evaluated.

*Diagram of monthsend function with bi-monthly segments.*





Transaction 8195 takes place on May 22. The `monthsend()` function initially divides the year into bi-monthly segments. Transaction 8195 falls into the segment between May 1 and June 30. As a result, the function returns the last millisecond of this segment, 06/30/2022 11:59:59 PM.

### Example 2 - period\_no

Load script and results

#### Overview

The same dataset and scenario as the first example are used.

In this example, the task is to create a field, 'prev\_bi\_monthly\_end', that returns the first millisecond of the bi-monthly segment before the transaction took place.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
    Load
    *,
    monthsend(2,date,-1) as prev_bi_monthly_end,
    timestamp(monthsend(2,date,-1)) as prev_bi_monthly_end_timestamp
    ;
Load
*
Inline
[
id,date,amount
8188,1/7/2022,17.17
8189,1/19/2022,37.23
8190,2/28/2022,88.27
8191,2/5/2022,57.42
8192,3/16/2022,53.80
8193,4/1/2022,82.06
8194,5/7/2022,40.39
8195,5/22/2022,87.21
8196,6/15/2022,95.93
8197,6/26/2022,45.89
8198,7/9/2022,36.23
8199,7/22/2022,25.66
8200,7/23/2022,82.77
8201,7/27/2022,69.98
8202,8/2/2022,76.11
8203,8/8/2022,25.12
8204,8/19/2022,46.23
8205,9/26/2022,84.21
8206,10/14/2022,96.24
8207,10/29/2022,67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:


- id
- date
- prev\_bi\_monthly\_end
- prev\_bi\_monthly\_end\_timestamp

Results table

id	date	prev_bi_monthly_end	prev_bi_monthly_end_timestamp
8188	1/7/2022	12/31/2021	12/31/2021 11:59:59 PM
8189	1/19/2022	12/31/2021	12/31/2021 11:59:59 PM
8190	2/5/2022	12/31/2021	12/31/2021 11:59:59 PM
8191	2/28/2022	12/31/2021	12/31/2021 11:59:59 PM
8192	3/16/2022	02/28/2022	2/28/2022 11:59:59 PM
8193	4/1/2022	02/28/2022	2/28/2022 11:59:59 PM
8194	5/7/2022	04/30/2022	4/30/2022 11:59:59 PM
8195	5/22/2022	04/30/2022	4/30/2022 11:59:59 PM
8196	6/15/2022	04/30/2022	4/30/2022 11:59:59 PM
8197	6/26/2022	04/30/2022	4/30/2022 11:59:59 PM
8198	7/9/2022	06/30/2022	6/30/2022 11:59:59 PM
8199	7/22/2022	06/30/2022	6/30/2022 11:59:59 PM
8200	7/23/2022	06/30/2022	6/30/2022 11:59:59 PM
8201	7/27/2022	06/30/2022	6/30/2022 11:59:59 PM
8202	8/2/2022	06/30/2022	6/30/2022 11:59:59 PM
8203	8/8/2022	06/30/2022	6/30/2022 11:59:59 PM
8204	8/19/2022	06/30/2022	6/30/2022 11:59:59 PM
8205	9/26/2022	08/31/2022	8/31/2022 11:59:59 PM
8206	10/14/2022	08/31/2022	8/31/2022 11:59:59 PM
8207	10/29/2022	08/31/2022	8/31/2022 11:59:59 PM

By using -1 as the `period_no` argument in the `monthsend()` function, after initially dividing a year into bi-monthly segments, the function returns the last millisecond of the previous bi-monthly segment to when a transaction takes place.

Diagram of `monthsend` function that returns the previous bi-monthly segment.



Transaction 8195 occurs in the segment between May and June. As a result, the previous bi-monthly segment was between March 1 and April 30 and so the function returns the last millisecond of this segment, 04/30/2022 11:59:59 PM.

### Example 3 – first\_month\_of\_year

Load script and results

#### Overview

The same dataset and scenario as the first example are used.

In this example, the organizational policy is for April to be the first month of the financial year.

Create a field, 'bi\_monthly\_end', that groups transactions into bi-monthly segments and returns the last millisecond timestamp of the segment for each transaction.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

Transactions:

```
Load
*,
monthsend(2,date,0,4) as bi_monthly_end,
timestamp(monthsend(2,date,0,4)) as bi_monthly_end_timestamp
;
```

Load

\*

Inline

```
[
id,date,amount
8188,1/7/2022,17.17
8189,1/19/2022,37.23
8190,2/28/2022,88.27
8191,2/5/2022,57.42
8192,3/16/2022,53.80
8193,4/1/2022,82.06
8194,5/7/2022,40.39
8195,5/22/2022,87.21
8196,6/15/2022,95.93
```

```
8197,6/26/2022,45.89
8198,7/9/2022,36.23
8199,7/22/2022,25.66
8200,7/23/2022,82.77
8201,7/27/2022,69.98
8202,8/2/2022,76.11
8203,8/8/2022,25.12
8204,8/19/2022,46.23
8205,9/26/2022,84.21
8206,10/14/2022,96.24
8207,10/29/2022,67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- id
- date
- bi\_monthly\_end
- bi\_monthly\_end\_timestamp


Results table

id	date	bi_monthly_end	bi_monthly_end_timestamp
8188	1/7/2022	01/31/2022	1/31/2022 11:59:59 PM
8189	1/19/2022	01/31/2022	1/31/2022 11:59:59 PM
8190	2/5/2022	03/31/2022	3/31/2022 11:59:59 PM
8191	2/28/2022	03/31/2022	3/31/2022 11:59:59 PM
8192	3/16/2022	03/31/2022	3/31/2022 11:59:59 PM
8193	4/1/2022	05/31/2022	5/31/2022 11:59:59 PM
8194	5/7/2022	05/31/2022	5/31/2022 11:59:59 PM
8195	5/22/2022	05/31/2022	5/31/2022 11:59:59 PM
8196	6/15/2022	07/31/2022	7/31/2022 11:59:59 PM
8197	6/26/2022	07/31/2022	7/31/2022 11:59:59 PM
8198	7/9/2022	07/31/2022	7/31/2022 11:59:59 PM
8199	7/22/2022	07/31/2022	7/31/2022 11:59:59 PM
8200	7/23/2022	07/31/2022	7/31/2022 11:59:59 PM
8201	7/27/2022	07/31/2022	7/31/2022 11:59:59 PM
8202	8/2/2022	09/30/2022	9/30/2022 11:59:59 PM
8203	8/8/2022	09/30/2022	9/30/2022 11:59:59 PM

id	date	bi_monthly_end	bi_monthly_end_timestamp
8204	8/19/2022	09/30/2022	9/30/2022 11:59:59 PM
8205	9/26/2022	09/30/2022	9/30/2022 11:59:59 PM
8206	10/14/2022	11/30/2022	11/30/2022 11:59:59 PM
8207	10/29/2022	11/30/2022	11/30/2022 11:59:59 PM

By using 4 as the `first_month_of_year` argument in the `monthsend()` function, the function begins the year on April 1. It then divides the year into bi-monthly segments: Apr-May, Jun-Jul, Aug-Sep, Oct-Nov, Dec-Jan, Feb-Mar.

*Diagram of monthsend function with the first month of the year set as April*



Transaction 8195 took place on May 22 and falls into the segment between April 1 and May 31. As a result, the function returns the last millisecond of this segment, 05/31/2022 11:59:59 PM.

### Example 4 - Chart object example

Load script and chart expression

#### Overview

The same dataset and scenario as the first example are used. However in this example, the dataset is unchanged, and loaded into the app.

In this example, the task is to create a calculation that groups transactions into bi-monthly segments and returns the last millisecond timestamp of the segment for each transaction as a measure in a chart object of an app.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
```

```
8188,2/19/2022,37.23
```

```

8189, 3/7/2022, 17.17
8190, 3/30/2022, 88.27
8191, 4/5/2022, 57.42
8192, 4/16/2022, 53.80
8193, 5/1/2022, 82.06
8194, 5/7/2022, 40.39
8195, 5/22/2022, 87.21
8196, 6/15/2022, 95.93
8197, 6/26/2022, 45.89
8198, 7/9/2022, 36.23
8199, 7/22/2022, 25.66
8200, 7/23/2022, 82.77
8201, 7/27/2022, 69.98
8202, 8/2/2022, 76.11
8203, 8/8/2022, 25.12
8204, 8/19/2022, 46.23
8205, 9/26/2022, 84.21
8206, 10/14/2022, 96.24
8207, 10/29/2022, 67.67
];

```

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension:

date

To fetch the last millisecond timestamp of the bi-monthly segment when the transaction took place, create the following measures:

- =monthsEnd(2, date)
- =timestamp(monthsend(2, date))


Results table

id	date	=monthsend(2, date)	=timestamp(monthsend(2, date))
8188	1/7/2022	02/28/2022	2/28/2022 11:59:59 PM
8189	1/19/2022	02/28/2022	2/28/2022 11:59:59 PM
8190	2/5/2022	02/28/2022	2/28/2022 11:59:59 PM
8191	2/28/2022	02/28/2022	2/28/2022 11:59:59 PM
8192	3/16/2022	04/30/2022	4/30/2022 11:59:59 PM
8193	4/1/2022	04/30/2022	4/30/2022 11:59:59 PM
8194	5/7/2022	06/30/2022	6/30/2022 11:59:59 PM
8195	5/22/2022	06/30/2022	6/30/2022 11:59:59 PM
8196	6/15/2022	06/30/2022	6/30/2022 11:59:59 PM
8197	6/26/2022	06/30/2022	6/30/2022 11:59:59 PM

id	date	=monthsend(2,date)	=timestamp(monthsend(2,date))
8198	7/9/2022	08/31/2022	8/31/2022 11:59:59 PM
8199	7/22/2022	08/31/2022	8/31/2022 11:59:59 PM
8200	7/23/2022	08/31/2022	8/31/2022 11:59:59 PM
8201	7/27/2022	08/31/2022	8/31/2022 11:59:59 PM
8202	8/2/2022	08/31/2022	8/31/2022 11:59:59 PM
8203	8/8/2022	08/31/2022	8/31/2022 11:59:59 PM
8204	8/19/2022	08/31/2022	8/31/2022 11:59:59 PM
8205	9/26/2022	10/31/2022	10/31/2022 11:59:59 PM
8206	10/14/2022	10/31/2022	10/31/2022 11:59:59 PM
8207	10/29/2022	10/31/2022	10/31/2022 11:59:59 PM

The 'bi\_monthly\_end' field is created as a measure in the chart object by using the monthsend() function. The first argument provided is 2, which divides the year into bi-monthly segments. The second argument identifies which field is being evaluated.

*Diagram of monthsend function with bi-monthly segments.*



Transaction 8195 takes place on May 22. The monthsend() function initially divides the year into bi-monthly segments. Transaction 8195 falls into the segment between May 1 and June 30. As a result, the function returns the first millisecond of this segment, 06/30/2022 11:59:59 PM.

### Example 5 – Scenario

Load script and results

#### Overview

Open the data load editor and add the load script below to a new tab.

In this example, a dataset is loaded into a table called 'Employee\_Expenses'. The table contains the following fields:

- Employee IDs
- Employee names

- The average daily expense claims of each employee.

The end user would like a chart that displays, by employee id and employee name, the estimated expense claim for the remainder of a period of their own choosing. The financial year begins in January.

### Load script

```
SET vPeriod = 1;

Employee_Expenses:
Load
*
Inline
[
employee_id,employee_name,avg_daily_claim
182,Mark, $15
183,Deryck, $12.5
184,Dexter, $12.5
185,Sydney,$27
186,Agatha,$18
];
```

### Results

Load the data and open a new sheet.

At the start of the load script, a variable, `vPeriod`, is created that is tied to the variable input control.

Do the following:

1. In the assets panel, click **Custom objects**.
2. Select **Qlik Dashboard bundle**, create a **Variable input** object.
3. Enter a title for the chart object.
4. Under **Variable**, select **vPeriod** as the name and set the object to show as a **Drop down**.
5. Under **Values**, click **Dynamic values**. Enter the following:  
`= '1~month|2~bi-month|3~quarter|4~tertia1|6~half-year'`.

Create a new table and these fields as dimensions:

- `employee_id`
- `employee_name`

To calculate the accumulated interest, create this measure:

```
=floor(monthsend($(vPeriod),today(1))-today(1))*avg_daily_claim
```



*This measure is dynamic and will produce different table results depending on the date when you load the data.*

Set the measure's **Number formatting to Money**.



Results table

employee_id	employee_name	=floor(monthsend(\$vPeriod),today(1))-today(1))*avg_daily_claim
182	Mark	\$1410.00
183	Deryck	\$1175.00
184	Dexter	\$1175.00
185	Sydney	\$2538.00
186	Agatha	\$1692.00

The `monthsend()` function uses the user input as its first argument and today's date as its second argument. This returns the end date for the user selected period of time. Then, the expression returns the number of days that remain the selected period of time by subtracting today's date from this end date.

This value is then multiplied by the average daily expense claim by each employee to calculate the estimated value of claims each employee is expected to make in the remaining days of this period.

## monthsname


This function returns a display value representing the range of the months of the period (formatted according to the **MonthNames** script variable) as well as the year. The underlying numeric value corresponds to a timestamp of the first millisecond of the month, bi-month, quarter, four-month period, or half-year containing a base date.

### Syntax:

```
MonthsName(n_months, date[, period_no[, first_month_of_year]])
```

**Return data type:** dual

*Diagram of monthsname function*



The `monthsname()` function divides the year into segments based on the `n_months` argument provided. It then evaluates the segment to which each provided `date` belongs, and returns the start

## 8 Script and chart functions

---

and end month names of that segment, as well as the year. The function also provides the ability to return these boundaries from preceding or following segments, as well as redefining which is the first month of the year.

The following segments of the year are available in the function as `n_month` arguments:

Possible `n_month` arguments

Periods	Number of months
month	1
bi-month	2
quarter	3
four months	4
half-year	6

Arguments

Argument	Description
<b>n_months</b>	The number of months that defines the period. An integer or expression that resolves to an integer that must be one of: 1 (equivalent to the <code>inmonth()</code> function), 2 (bi-month), 3 (equivalent to the <code>inquarter()</code> function), 4 (four-month period), or 6 (half year).
<b>date</b>	The date or timestamp to evaluate.
<b>period_no</b>	The period can be offset by <b>period_no</b> , an integer, or expression resolving to an integer, where the value 0 indicates the period that contains <b>base_date</b> . Negative values in <b>period_no</b> indicate preceding periods and positive values indicate succeeding periods.
<b>first_month_of_year</b>	If you want to work with (fiscal) years not starting in January, indicate a value between 2 and 12 in <b>first_month_of_year</b> .

### When to use it

The `monthsname()` function is useful when you would like to provide the user with the functionality to compare aggregations by a period of their choosing. For example, you could provide an input variable to let the user see the total sales of products by month, quarter, or half-year.

These dimensions can be created either in the load script by adding the function as a field in a Master Calendar table, or alternatively, by creating the dimension directly in a chart as a calculated dimension.

### Function examples

Example	Result
monthsname(4, '10/19/2013')	Returns 'Sep-Dec 2013.' In this and the other examples, the <b>SET Monthnames</b> statement is set to Jan;Feb;Mar, and so on.
monthsname(4, '10/19/2013', -1)	Returns 'May-Aug 2013'.
monthsname(4, '10/19/2013', 0, 2)	Returns 'Oct-Jan 2014', since the year is specified to begin in month 2. Therefore, the four-month period ends on the first month of the following year.

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Example 1 – Basic example

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions for 2022, which is loaded into a table called `Transactions`.
- The date field provided in the `DateFormat` system variable (MM/DD/YYYY) format.
- The creation of a field, `bi_monthly_range`, that groups transactions into bi-monthly segments and returns the boundary names of that segment for each transaction.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
  Load
    *
```

```
        monthsname(2,date) as bi_monthly_range
    ;
Load
*
Inline
[
id,date,amount
8188,2/19/2022,37.23
8189,3/7/2022,17.17
8190,3/30/2022,88.27
8191,4/5/2022,57.42
8192,4/16/2022,53.80
8193,5/1/2022,82.06
8194,5/7/2022,40.39
8195,5/22/2022,87.21
8196,6/15/2022,95.93
8197,6/26/2022,45.89
8198,7/9/2022,36.23
8199,7/22/2022,25.66
8200,7/23/2022,82.77
8201,7/27/2022,69.98
8202,8/2/2022,76.11
8203,8/8/2022,25.12
8204,8/19/2022,46.23
8205,9/26/2022,84.21
8206,10/14/2022,96.24
8207,10/29/2022,67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- bi\_monthly\_range


Results table

date	bi_monthly_range
2/19/2022	Jan-Feb 2022
3/7/2022	Mar-Apr 2022
3/30/2022	Mar-Apr 2022
4/5/2022	Mar-Apr 2022
4/16/2022	Mar-Apr 2022
5/1/2022	May-Jun 2022
5/7/2022	May-Jun 2022
5/22/2022	May-Jun 2022

date	bi_monthly_range
6/15/2022	May-Jun 2022
6/26/2022	May-Jun 2022
7/9/2022	Jul-Aug 2022
7/22/2022	Jul-Aug 2022
7/23/2022	Jul-Aug 2022
7/27/2022	Jul-Aug 2022
8/2/2022	Jul-Aug 2022
8/8/2022	Jul-Aug 2022
8/19/2022	Jul-Aug 2022
9/26/2022	Sep-Oct 2022
10/14/2022	Sep-Oct 2022
10/29/2022	Sep-Oct 2022

The `bi_monthly_range` field is created in the preceding load statement by using the `monthsname()` function. The first argument provided is 2, dividing the year into bi-monthly segments. The second argument identifies which field is being evaluated.

*Diagram of monthsname function, basic example*



Transaction 8195 takes place on May 22. The `monthsname()` function initially divides the year into bi-monthly segments. Transaction 8195 falls into the segment between May 1 and June 30. Therefore, the function returns these months in the `monthNames` system variable format, as well as the year, May-Jun 2022.

### Example 2 – period\_no

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same inline dataset and scenario as the first example.
- The creation of a field, `prev_bi_monthly_range`, that groups transactions into bi-monthly segments and returns the previous segment boundary names for each transaction.

Add your other text here, as needed, with lists etc.

### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
    Load
        *,
        MonthsName(2,date,-1) as prev_bi_monthly_range
    ;

Load
*
Inline
[
id,date,amount
8188,2/19/2022,37.23
8189,3/7/2022,17.17
8190,3/30/2022,88.27
8191,4/5/2022,57.42
8192,4/16/2022,53.80
8193,5/1/2022,82.06
8194,5/7/2022,40.39
8195,5/22/2022,87.21
8196,6/15/2022,95.93
8197,6/26/2022,45.89
8198,7/9/2022,36.23
8199,7/22/2022,25.66
8200,7/23/2022,82.77
8201,7/27/2022,69.98
8202,8/2/2022,76.11
8203,8/8/2022,25.12
8204,8/19/2022,46.23
8205,9/26/2022,84.21
8206,10/14/2022,96.24
8207,10/29/2022,67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:


- date
- prev\_bi\_monthly\_range

Results table

<b>date</b>	<b>prev_bi_monthly_range</b>
2/19/2022	Nov-Dec 2021
3/7/2022	Jan-Feb 2022
3/30/2022	Jan-Feb 2022
4/5/2022	Jan-Feb 2022
4/16/2022	Jan-Feb 2022
5/1/2022	Mar-Apr 2022
5/7/2022	Mar-Apr 2022
5/22/2022	Mar-Apr 2022
6/15/2022	Mar-Apr 2022
6/26/2022	Mar-Apr 2022
7/9/2022	May-Jun 2022
7/22/2022	May-Jun 2022
7/23/2022	May-Jun 2022
7/27/2022	May-Jun 2022
8/2/2022	May-Jun 2022
8/8/2022	May-Jun 2022
8/19/2022	May-Jun 2022
9/26/2022	Jul-Aug 2022
10/14/2022	Jul-Aug 2022
10/29/2022	Jul-Aug 2022

In this example, -1 is used as the `period_no` argument in the `monthsname()` function. After initially dividing a year into bi-monthly segments, the function then returns the previous segment boundaries for when a transaction takes place.

Diagram of monthsname function, period\_no example



Transaction 8195 occurs in the segment between May and June. Therefore, the previous bi-monthly segment was between March 1 and April 30, and so the function returns Mar-Apr 2022.

### Example 3 – first\_month\_of\_year

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same inline dataset and scenario as the first example.
- The creation of a different field, `bi_monthly_range`, that groups transactions into bi-monthly segments and returns the segment boundaries for each transaction.

However, in this example, we also need to set April as the first month of the financial year.

#### Load script

```
SET DateFormat='MM/DD/YYYY';

Transactions:
  Load
    *,
    MonthsName(2,date,0,4) as bi_monthly_range
  ;
Load
*
Inline
[
id,date,amount
8188,2/19/2022,37.23
8189,3/7/2022,17.17
8190,3/30/2022,88.27
8191,4/5/2022,57.42
```



```
8192,4/16/2022,53.80
8193,5/1/2022,82.06
8194,5/7/2022,40.39
8195,5/22/2022,87.21
8196,6/15/2022,95.93
8197,6/26/2022,45.89
8198,7/9/2022,36.23
8199,7/22/2022,25.66
8200,7/23/2022,82.77
8201,7/27/2022,69.98
8202,8/2/2022,76.11
8203,8/8/2022,25.12
8204,8/19/2022,46.23
8205,9/26/2022,84.21
8206,10/14/2022,96.24
8207,10/29/2022,67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- bi\_monthly\_range

Results table

date	bi_monthly_range
2/19/2022	Feb-Mar 2021
3/7/2022	Feb-Mar 2021
3/30/2022	Feb-Mar 2021
4/5/2022	Apr-May 2022
4/16/2022	Apr-May 2022
5/1/2022	Apr-May 2022
5/7/2022	Apr-May 2022
5/22/2022	Apr-May 2022
6/15/2022	Jun-Jul 2022
6/26/2022	Jun-Jul 2022
7/9/2022	Jun-Jul 2022
7/22/2022	Jun-Jul 2022
7/23/2022	Jun-Jul 2022
7/27/2022	Jun-Jul 2022


date	bi_monthly_range
8/2/2022	Aug-Sep 2022
8/8/2022	Aug-Sep 2022
8/19/2022	Aug-Sep 2022
9/26/2022	Aug-Sep 2022
10/14/2022	Oct-Nov 2022
10/29/2022	Oct-Nov 2022

By using 4 as the `first_month_of_year` argument in the `monthsname()` function, the function begins the year on April 1. It then divides the year into bi-monthly segments: Apr-May, Jun-Jul, Aug-Sep, Oct-Nov, Dec-Jan, Feb-Mar.

Paragraph text for Results.

Transaction 8195 took place on May 22 and falls into the segment between April 1 and May 31. Therefore, the function returns Apr-May 2022.

*Diagram of monthsname function, first\_month\_of\_year example*



### Example 4 – Chart object example

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains the same inline dataset and scenario as the first example. However, in this example, the unchanged dataset is loaded into the application. The calculation that groups transactions into bi-monthly segments and returns the segment boundaries for each transaction is created as a measure in a chart object of the application.

### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
```

```
8188,2/19/2022,37.23
```

```
8189,3/7/2022,17.17
```

```
8190,3/30/2022,88.27
```

```
8191,4/5/2022,57.42
```

```
8192,4/16/2022,53.80
```

```
8193,5/1/2022,82.06
```

```
8194,5/7/2022,40.39
```

```
8195,5/22/2022,87.21
```

```
8196,6/15/2022,95.93
```

```
8197,6/26/2022,45.89
```

```
8198,7/9/2022,36.23
```

```
8199,7/22/2022,25.66
```

```
8200,7/23/2022,82.77
```

```
8201,7/27/2022,69.98
```

```
8202,8/2/2022,76.11
```

```
8203,8/8/2022,25.12
```

```
8204,8/19/2022,46.23
```

```
8205,9/26/2022,84.21
```

```
8206,10/14/2022,96.24
```

```
8207,10/29/2022,67.67
```

```
];
```

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension:date.

Create the following measure:

```
=monthsname(2,date)
```


Results table

date	=monthsname(2,date)
2/19/2022	Jan-Feb 2022
3/7/2022	Mar-Apr 2022
3/30/2022	Mar-Apr 2022
4/5/2022	Mar-Apr 2022
4/16/2022	Mar-Apr 2022
5/1/2022	May-Jun 2022

date	=monthsname(2,date)
5/7/2022	May-Jun 2022
5/22/2022	May-Jun 2022
6/15/2022	May-Jun 2022
6/26/2022	May-Jun 2022
7/9/2022	Jul-Aug 2022
7/22/2022	Jul-Aug 2022
7/23/2022	Jul-Aug 2022
7/27/2022	Jul-Aug 2022
8/2/2022	Jul-Aug 2022
8/8/2022	Jul-Aug 2022
8/19/2022	Jul-Aug 2022
9/26/2022	Sep-Oct 2022
10/14/2022	Sep-Oct 2022
10/29/2022	Sep-Oct 2022

The `bi_monthly_range` field is created as a measure in the chart object by using the `monthsname()` function. The first argument provided is 2, dividing the year into bi-monthly segments. The second argument identifies which field is being evaluated.

*Diagram of monthsname function, chart object example*



Transaction 8195 takes place on May 22. The `monthsname()` function initially divides the year into bi-monthly segments. Transaction 8195 falls into the segment between May 1 and June 30. Therefore, the function returns these months in the `monthNames` system variable format, as well as the year, May-Jun 2022.

### Example 5 – Scenario

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing transactions for 2022, which is loaded into a table called `Transactions`.
- The date field provided in the `DateFormat` system variable (MM/DD/YYYY) format.

The end user would like a chart object that displays total sales by a period of their own choosing. This could be achieved even when this dimension is not available in the data model, using the `monthsname()` function as a calculated dimension that is dynamically modified by a variable input control.

#### Load script

```
SET vPeriod = 1;
SET DateFormat='MM/DD/YYYY';
```

Transactions:

Load

\*

Inline

[

id,date,amount

8188, '1/7/2022', 17.17

8189, '1/19/2022', 37.23

8190, '2/28/2022', 88.27

8191, '2/5/2022', 57.42

8192, '3/16/2022', 53.80

8193, '4/1/2022', 82.06

8194, '5/7/2022', 40.39

8195, '5/16/2022', 87.21

8196, '6/15/2022', 95.93

8197, '6/26/2022', 45.89

8198, '7/9/2022', 36.23

8199, '7/22/2022', 25.66

8200, '7/23/2022', 82.77

8201, '7/27/2022', 69.98

8202, '8/2/2022', 76.11

8203, '8/8/2022', 25.12

8204, '8/19/2022', 46.23

8205, '9/26/2022', 84.21

8206, '10/14/2022', 96.24

8207, '10/29/2022', 67.67

];

### Results

Load the data and open a sheet.

At the start of the load script, a variable (`vPeriod`) has been created that will be tied to the variable input control. Next, configure the variable as a custom object in the sheet.

#### Do the following:

1. In the assets panel, click **Custom objects**.
2. Select **Qlik Dashboard bundle**, and create a **Variable input** object.
3. Enter a title for the chart object.
4. Under **Variable**, select **vPeriod** as the Name and set the object to show as a **Drop down**.
5. Under **Values**, configure the object to use dynamic values. Enter the following:  
`= '1~month|2~bi-month|3~quarter|4~tertia1|6~half-year'`

Next, create the results table.

#### Do the following:

1. Create a new table and add the following calculated dimension:  
`=monthsname($(vPeriod),date)`
2. Add this measure to calculate the total sales:  
`=sum(amount)`
3. Set the measure's **Number formatting** to **Money**. Click **Done editing**. You can now modify the data shown in the table by adjusting the time segment in the variable object.

This is what the results table will look like when the `tertia1` option is selected:

Results table

<code>monthsname(\$(vPeriod),date)</code>	<code>=sum(amount)</code>
Jan-Apr 2022	253.89
May-Aug 2022	713.58
Sep-Dec 2022	248.12

### monthsstart


This function returns a value corresponding to the timestamp of the first millisecond of the month, bi-month, quarter, four-month period, or half-year containing a base date. It is also possible to find the timestamp for a previous or following time period. The default output format is the **DateFormat** set in the script.

#### Syntax:

```
MonthsStart(n_months, date[, period_no [, first_month_of_year]])
```

**Return data type:** dual

Diagram of `monthsstart()` function



The `monthsstart()` function divides the year into segments based on the `n_months` argument provided. It then evaluates what segment each date provided falls into and returns the first millisecond of that segment, in date format. The function also provides the ability to return the start timestamp from preceding or following segments, as well as redefining which is the first month of the year.

The following segments of the year are available in the function as `n_month` arguments:

Possible `n_month` arguments

Periods	Number of months
month	1
bi-month	2
quarter	3
four months	4
half-year	6

Arguments

Argument	Description
<b>n_months</b>	The number of months that defines the period. An integer or expression that resolves to an integer that must be one of: 1 (equivalent to the <code>inmonth()</code> function), 2 (bi-month), 3 (equivalent to the <code>inquarter()</code> function), 4 (four-month period), or 6 (half year).
<b>date</b>	The date or timestamp to evaluate.
<b>period_no</b>	The period can be offset by <b>period_no</b> , an integer, or expression resolving to an integer, where the value 0 indicates the period that contains <b>base_date</b> . Negative values in <b>period_no</b> indicate preceding periods and positive values indicate succeeding periods.
<b>first_month_of_year</b>	If you want to work with (fiscal) years not starting in January, indicate a value between 2 and 12 in <b>first_month_of_year</b> .

### When to use it

The `monthsstart()` function is commonly used as part of an expression when the user would like the calculation to use the fraction of a period that has not yet occurred. This could be used, for example, to provide an input variable to let the user calculate the total interest that has been accumulated so far in the month, quarter, or half-year.

Function examples

Example	Result
<code>monthsstart(4, '10/19/2013')</code>	Returns 09/01/2013.
<code>monthsstart(4, '10/19/2013, -1)</code>	Returns 05/01/2013.
<code>monthsstart(4, '10/19/2013', 0, 2 )</code>	Returns 10/01/2013, because the start of the year becomes month 2.

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Example 1 – No additional arguments

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions for 2022, which is loaded into a table called `Transactions`.
- The date field provided in the `DateFormat` system variable (MM/DD/YYYY) format.
- The creation of a field, `bi_monthly_start`, that groups transactions into bi-monthly segments and returns the starting timestamp of the segment for each transaction.



### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
  Load
    *,
    monthsstart(2,date) as bi_monthly_start,
    timestamp(monthsstart(2,date)) as bi_monthly_start_timestamp
  ;
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
```

```
8188,2/19/2022,37.23
```

```
8189,3/7/2022,17.17
```

```
8190,3/30/2022,88.27
```

```
8191,4/5/2022,57.42
```

```
8192,4/16/2022,53.80
```

```
8193,5/1/2022,82.06
```

```
8194,5/7/2022,40.39
```

```
8195,5/22/2022,87.21
```

```
8196,6/15/2022,95.93
```

```
8197,6/26/2022,45.89
```

```
8198,7/9/2022,36.23
```

```
8199,7/22/2022,25.66
```

```
8200,7/23/2022,82.77
```

```
8201,7/27/2022,69.98
```

```
8202,8/2/2022,76.11
```

```
8203,8/8/2022,25.12
```

```
8204,8/19/2022,46.23
```

```
8205,9/26/2022,84.21
```

```
8206,10/14/2022,96.24
```

```
8207,10/29/2022,67.67
```

```
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- bi\_monthly\_start
- bi\_monthly\_start\_timestamp


Results table

date	bi_monthly_start	bi_monthly_start_timestamp
2/19/2022	01/01/2022	1/1/2022 12:00:00 AM
3/7/2022	03/01/2022	3/1/2022 12:00:00 AM

date	bi_monthly_start	bi_monthly_start_timestamp
3/30/2022	03/01/2022	3/1/2022 12:00:00 AM
4/5/2022	03/01/2022	3/1/2022 12:00:00 AM
4/16/2022	03/01/2022	3/1/2022 12:00:00 AM
5/1/2022	05/01/2022	5/1/2022 12:00:00 AM
5/7/2022	05/01/2022	5/1/2022 12:00:00 AM
5/22/2022	05/01/2022	5/1/2022 12:00:00 AM
6/15/2022	05/01/2022	5/1/2022 12:00:00 AM
6/26/2022	05/01/2022	5/1/2022 12:00:00 AM
7/9/2022	07/01/2022	7/1/2022 12:00:00 AM
7/22/2022	07/01/2022	7/1/2022 12:00:00 AM
7/23/2022	07/01/2022	7/1/2022 12:00:00 AM
7/27/2022	07/01/2022	7/1/2022 12:00:00 AM
8/2/2022	07/01/2022	7/1/2022 12:00:00 AM
8/8/2022	07/01/2022	7/1/2022 12:00:00 AM
8/19/2022	07/01/2022	7/1/2022 12:00:00 AM
9/26/2022	09/01/2022	9/1/2022 12:00:00 AM
10/14/2022	09/01/2022	9/1/2022 12:00:00 AM
10/29/2022	09/01/2022	9/1/2022 12:00:00 AM

The `bi_monthly_start` field is created in the preceding load statement by using the `monthsstart()` function. The first argument provided is 2, dividing the year into bi-monthly segments. The second argument identifies which field is being evaluated.

*Diagram of `monthsstart()` function, example with no additional arguments*



Transaction 8195 takes place on May 22. The `monthsstart()` function initially divides the year into bi-monthly segments. Transaction 8195 falls into the segment between May 1 and June 30. Therefore, the function returns the first millisecond of this segment, May 1, 2022 at 12:00:00 AM.

### Example 2 – period\_no

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same dataset and scenario as the first example.
- The creation of a field, `prev_bi_monthly_start`, that returns the first millisecond of the bi-monthly segment before the transaction took place.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
    Load
        *,
        monthsstart(2,date,-1) as prev_bi_monthly_start,
        timestamp(monthsstart(2,date,-1)) as prev_bi_monthly_start_timestamp
    ;

Load
*
Inline
[
id,date,amount
8188,2/19/2022,37.23
8189,3/7/2022,17.17
8190,3/30/2022,88.27
8191,4/5/2022,57.42
8192,4/16/2022,53.80
8193,5/1/2022,82.06
8194,5/7/2022,40.39
8195,5/22/2022,87.21
8196,6/15/2022,95.93
8197,6/26/2022,45.89
8198,7/9/2022,36.23
8199,7/22/2022,25.66
8200,7/23/2022,82.77
8201,7/27/2022,69.98
8202,8/2/2022,76.11
8203,8/8/2022,25.12
8204,8/19/2022,46.23
8205,9/26/2022,84.21
8206,10/14/2022,96.24
8207,10/29/2022,67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:


- date
- prev\_bi\_monthly\_start
- prev\_bi\_monthly\_start\_timestamp

Results table

date	prev_bi_monthly_start	prev_bi_monthly_start_timestamp
2/19/2022	11/01/2021	11/1/2021 12:00:00 AM
3/7/2022	01/01/2022	1/1/2022 12:00:00 AM
3/30/2022	01/01/2022	1/1/2022 12:00:00 AM
4/5/2022	01/01/2022	1/1/2022 12:00:00 AM
4/16/2022	01/01/2022	1/1/2022 12:00:00 AM
5/1/2022	03/01/2022	3/1/2022 12:00:00 AM
5/7/2022	03/01/2022	3/1/2022 12:00:00 AM
5/22/2022	03/01/2022	3/1/2022 12:00:00 AM
6/15/2022	03/01/2022	3/1/2022 12:00:00 AM
6/26/2022	03/01/2022	3/1/2022 12:00:00 AM
7/9/2022	05/01/2022	5/1/2022 12:00:00 AM
7/22/2022	05/01/2022	5/1/2022 12:00:00 AM
7/23/2022	05/01/2022	5/1/2022 12:00:00 AM
7/27/2022	05/01/2022	5/1/2022 12:00:00 AM
8/2/2022	05/01/2022	5/1/2022 12:00:00 AM
8/8/2022	05/01/2022	5/1/2022 12:00:00 AM
8/19/2022	05/01/2022	5/1/2022 12:00:00 AM
9/26/2022	07/01/2022	7/1/2022 12:00:00 AM
10/14/2022	07/01/2022	7/1/2022 12:00:00 AM
10/29/2022	07/01/2022	7/1/2022 12:00:00 AM

By using -1 as the `period_no` argument in the `monthsstart()` function, after initially dividing a year into bi-monthly segments, the function then returns the first millisecond of the previous bi-monthly segment to when a transaction takes place.

Diagram of `monthsstart()` function, `period_no` example



Transaction 8195 occurs in the segment between May and June. Therefore, the previous bi-monthly segment was between March 1 and April 30, so the function returns the first millisecond of this segment, March 1, 2022 at 12:00:00 AM.

### Example 3 – first\_month\_of\_year

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same dataset and scenario as the first example.
- The creation of a field, `bi_monthly_start`, that groups transactions into bi-monthly segments and returns the starting timestamp of the set for each transaction.

However, in this example, we also need to set April as the first month of the financial year.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
Load
*,
monthsstart(2,date,0,4) as bi_monthly_start,
timestamp(monthsstart(2,date,0,4)) as bi_monthly_start_timestamp
;
Load
*
Inline
[
id,date,amount
8188,1/7/2022,17.17
8189,1/19/2022,37.23
```

```
8190,2/28/2022,88.27
8191,2/5/2022,57.42
8192,3/16/2022,53.80
8193,4/1/2022,82.06
8194,5/7/2022,40.39
8195,5/16/2022,87.21
8196,6/15/2022,95.93
8197,6/26/2022,45.89
8198,7/9/2022,36.23
8199,7/22/2022,25.66
8200,7/23/2022,82.77
8201,7/27/2022,69.98
8202,8/2/2022,76.11
8203,8/8/2022,25.12
8204,8/19/2022,46.23
8205,9/26/2022,84.21
8206,10/14/2022,96.24
8207,10/29/2022,67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- bi\_monthly\_start
- bi\_monthly\_start\_timestamp


Results table

date	bi_monthly_start	bi_monthly_start_timestamp
2/19/2022	02/01/2022	2/1/2022 12:00:00 AM
3/7/2022	02/01/2022	2/1/2022 12:00:00 AM
3/30/2022	02/01/2022	2/1/2022 12:00:00 AM
4/5/2022	04/01/2022	4/1/2022 12:00:00 AM
4/16/2022	04/01/2022	4/1/2022 12:00:00 AM
5/1/2022	04/01/2022	4/1/2022 12:00:00 AM
5/7/2022	04/01/2022	4/1/2022 12:00:00 AM
5/22/2022	04/01/2022	4/1/2022 12:00:00 AM
6/15/2022	06/01/2022	6/1/2022 12:00:00 AM
6/26/2022	06/01/2022	6/1/2022 12:00:00 AM
7/9/2022	06/01/2022	6/1/2022 12:00:00 AM
7/22/2022	06/01/2022	6/1/2022 12:00:00 AM

date	bi_monthly_start	bi_monthly_start_timestamp
7/23/2022	06/01/2022	6/1/2022 12:00:00 AM
7/27/2022	06/01/2022	6/1/2022 12:00:00 AM
8/2/2022	08/01/2022	8/1/2022 12:00:00 AM
8/8/2022	08/01/2022	8/1/2022 12:00:00 AM
8/19/2022	08/01/2022	8/1/2022 12:00:00 AM
9/26/2022	08/01/2022	8/1/2022 12:00:00 AM
10/14/2022	10/01/2022	10/1/2022 12:00:00 AM
10/29/2022	10/01/2022	10/1/2022 12:00:00 AM

By using 4 as the `first_month_of_year` argument in the `monthsstart()` function, the function begins the year on April 1. It then divides the year into bi-monthly segments: Apr-May, Jun-Jul, Aug-Sep, Oct-Nov, Dec-Jan, Feb-Mar.

*Diagram of `monthsstart()` function, `first_month_of_year` example*



Transaction 8195 took place on May 22 and falls into the segment between April 1 and May 31. Therefore, the function returns the first millisecond of this segment, April 1, 2022 at 12:00:00 AM.

### Example 4 – Chart object example

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains the same dataset and scenario as the first example.

However, in this example, the unchanged dataset is loaded into the application. The calculation which groups transactions into bi-monthly segments and returns the starting timestamp of the set for each transaction is created as a measure in a chart object of the application.

### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
```

```
8188,2/19/2022,37.23
```

```
8189,3/7/2022,17.17
```

```
8190,3/30/2022,88.27
```

```
8191,4/5/2022,57.42
```

```
8192,4/16/2022,53.80
```

```
8193,5/1/2022,82.06
```

```
8194,5/7/2022,40.39
```

```
8195,5/22/2022,87.21
```

```
8196,6/15/2022,95.93
```

```
8197,6/26/2022,45.89
```

```
8198,7/9/2022,36.23
```

```
8199,7/22/2022,25.66
```

```
8200,7/23/2022,82.77
```

```
8201,7/27/2022,69.98
```

```
8202,8/2/2022,76.11
```

```
8203,8/8/2022,25.12
```

```
8204,8/19/2022,46.23
```

```
8205,9/26/2022,84.21
```

```
8206,10/14/2022,96.24
```

```
8207,10/29/2022,67.67
```

```
];
```

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension: date.

Create the following measures:

```
=monthsstart(2,date)
```

```
=timestamp(monthsstart(2,date))
```

These calculations will retrieve the starting timestamp of the bi-monthly segment in which each transaction took place.


Results table

date	=monthsstart(2,date)	=timestamp(monthsstart(2,date))
9/26/2022	09/01/2022	9/1/2022 12:00:00 AM
10/14/2022	09/01/2022	9/1/2022 12:00:00 AM
10/29/2022	09/01/2022	9/1/2022 12:00:00 AM



date	=monthsstart(2,date)	=timestamp(monthsstart(2,date))
7/9/2022	07/01/2022	7/1/2022 12:00:00 AM
7/22/2022	07/01/2022	7/1/2022 12:00:00 AM
7/23/2022	07/01/2022	7/1/2022 12:00:00 AM
7/27/2022	07/01/2022	7/1/2022 12:00:00 AM
8/2/2022	07/01/2022	7/1/2022 12:00:00 AM
8/8/2022	07/01/2022	7/1/2022 12:00:00 AM
8/19/2022	07/01/2022	7/1/2022 12:00:00 AM
5/1/2022	05/01/2022	5/1/2022 12:00:00 AM
5/7/2022	05/01/2022	5/1/2022 12:00:00 AM
5/22/2022	05/01/2022	5/1/2022 12:00:00 AM
6/15/2022	05/01/2022	5/1/2022 12:00:00 AM
6/26/2022	05/01/2022	5/1/2022 12:00:00 AM
3/7/2022	03/01/2022	3/1/2022 12:00:00 AM
3/30/2022	03/01/2022	3/1/2022 12:00:00 AM
4/5/2022	03/01/2022	3/1/2022 12:00:00 AM
4/16/2022	03/01/2022	3/1/2022 12:00:00 AM
2/19/2022	01/01/2022	1/1/2021 12:00:00 AM

Diagram of monthsstart() function, chart object example



Transaction 8195 took place on May 22. The monthsstart() function initially divides the year into bi-monthly segments. Transaction 8195 falls into the segment between May 1 and June 30. Therefore, the function returns the first millisecond of this segment, 05/01/2022 12:00:00 AM.

### Example 5 – Scenario

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of loan balances, which is loaded into a table called Loans.
- Data consisting of loan IDs, the balance at the start of the month, and the simple interest rate charged on each loan per annum.

The end user would like a chart object that displays, by loan ID, the current interest that has been accrued on each loan for the period of their choosing. The financial year begins in January.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Loans:
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
loan_id,start_balance,rate
```

```
8188,$10000.00,0.024
```

```
8189,$15000.00,0.057
```

```
8190,$17500.00,0.024
```

```
8191,$21000.00,0.034
```

```
8192,$90000.00,0.084
```

```
];
```

#### Results

Load the data and open a sheet.

At the start of the load script, a variable (`vPeriod`) has been created that will be tied to the variable input control. Next, configure the variable as a custom object in the sheet.

#### Do the following:

1. In the assets panel, click **Custom objects**.
2. Select **Qlik Dashboard bundle**, and create a **Variable input** object.
3. Enter a title for the chart object.
4. Under **Variable**, select **vPeriod** as the Name and set the object to show as a **Drop down**.
5. Under **Values**, configure the object to use dynamic values. Enter the following:  
='1~month|2~bi-month|3~quarter|4~tertia1|6~half-year'

Next, create the results table.

### Do the following:

1. Create a new table. Add the following fields as dimensions.
  - employee\_id
  - employee\_name
2. Create a measure to calculate the accumulated interest:  
`=start_balance*(rate*(today(1)-monthsstart($(vPeriod),today(1)))/365)`
3. Set the measure's **Number formatting to Money**. Click **Done editing**. You can now modify the data shown in the table by adjusting the time segment in the variable object.

This is what the results table will look like when the month period option is selected:

Results table

loan_id	start_balance	=start_balance*(rate*(today(1)-monthsstart(\$(vPeriod),today(1)))/365)
8188	\$10000.00	\$7.95
8189	\$15000.00	\$67.93
8190	\$17500.00	\$33.37
8191	\$21000.00	\$56.73
8192	\$90000.00	\$600.66

The `monthsstart()` function, using the user's input as its first argument and today's date as its second argument, returns the start date of the period of the user's choosing. By subtracting that result from the current date, the expression returns the number of days that have elapsed so far in this period.

This value is then multiplied by the interest rate and divided by 365 to return the effective interest rate incurred for this period. The result is then multiplied by the starting balance of the loan to return the interest that has been accrued so far this period.

## monthstart


This function returns a value corresponding to a timestamp of the first millisecond of the first day of the month containing **date**. The default output format will be the **DateFormat** set in the script.

### Syntax:

```
MonthStart (date[, period_no])
```

**Return data type:** dual

*Diagram of monthstart() function*



The `monthstart()` function determines which month the date falls into. It then returns a timestamp, in date format, for the first millisecond of that month.

### Arguments

Argument	Description
<b>date</b>	The date or timestamp to evaluate.
<b>period_no</b>	<b>period_no</b> is an integer, which, if 0 or omitted, indicates the month that contains <b>date</b> . Negative values in <b>period_no</b> indicate preceding months and positive values indicate succeeding months.

### When to use it

The `monthstart()` function is commonly used as part of an expression when the user would like the calculation to use the fraction of the month that has elapsed thus far. For example, it can be used to calculate the interest that has been accumulated in a month up to a certain date.

### Function examples

Example	Result
<code>monthstart('10/19/2001')</code>	Returns 10/01/2001.
<code>monthstart('10/19/2001', -1)</code>	Returns 09/01/2001.

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET dateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Example 1 – No additional arguments

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions for 2022, which is loaded into a table called Transactions.
- The date field provided in the `DateFormat` system variable (MM/DD/YYYY) format.
- The creation of a field, `start_of_month`, which returns a timestamp for the start of the month when the transactions took place.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
  Load
    *,
    monthstart(date) as start_of_month,
    timestamp(monthstart(date)) as start_of_month_timestamp
  ;
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
8188,1/7/2022,17.17
8189,1/19/2022,37.23
8190,2/28/2022,88.27
8191,2/5/2022,57.42
8192,3/16/2022,53.80
8193,4/1/2022,82.06
8194,5/7/2022,40.39
8195,5/16/2022,87.21
8196,6/15/2022,95.93
8197,6/26/2022,45.89
8198,7/9/2022,36.23
8199,7/22/2022,25.66
8200,7/23/2022,82.77
8201,7/27/2022,69.98
8202,8/2/2022,76.11
```

```
8203, 8/8/2022, 25.12
8204, 8/19/2022, 46.23
8205, 9/26/2022, 84.21
8206, 10/14/2022, 96.24
8207, 10/29/2022, 67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- start\_of\_month
- start\_of\_month\_timestamp


Results table

date	start_of_month	start_of_month_timestamp
1/7/2022	01/01/2022	1/1/2022 12:00:00 AM
1/19/2022	01/01/2022	1/1/2022 12:00:00 AM
2/5/2022	02/01/2022	2/1/2022 12:00:00 AM
2/28/2022	02/01/2022	2/1/2022 12:00:00 AM
3/16/2022	03/01/2022	3/1/2022 12:00:00 AM
4/1/2022	04/01/2022	4/1/2022 12:00:00 AM
5/7/2022	05/01/2022	5/1/2022 12:00:00 AM
5/16/2022	05/01/2022	5/1/2022 12:00:00 AM
6/15/2022	06/01/2022	6/1/2022 12:00:00 AM
6/26/2022	07/01/2022	6/1/2022 12:00:00 AM
7/9/2022	07/01/2022	7/1/2022 12:00:00 AM
7/22/2022	07/01/2022	7/1/2022 12:00:00 AM
7/23/2022	07/01/2022	7/1/2022 12:00:00 AM
7/27/2022	07/01/2022	7/1/2022 12:00:00 AM
8/2/2022	08/01/2022	8/1/2022 12:00:00 AM
8/8/2022	08/01/2022	8/1/2022 12:00:00 AM
8/19/2022	08/01/2022	8/1/2022 12:00:00 AM
9/26/2022	09/01/2022	9/1/2022 12:00:00 AM
10/14/2022	10/01/2022	10/1/2022 12:00:00 AM
10/29/2022	10/01/2022	10/1/2022 12:00:00 AM

The `start_of_month` field is created in the preceding load statement by using the `monthstart()` function and passing the date field as the function's argument.

The `monthstart()` function identifies which month the date value falls into, returning a timestamp for the first millisecond of that month.

*Diagram of `monthstart()` function, example with no additional arguments*



Transaction 8192 took place on March 16. The `monthstart()` function returns the first millisecond of that month, which is March 1 at 12:00:00 AM.

### Example 2 – `period_no`

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same dataset and scenario as the first example.
- The creation of a field, `previous_month_start`, which returns the timestamp for the start of the month before the transaction took place.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
Load
    *,
    monthstart(date,-1) as previous_month_start,
    timestamp(monthstart(date,-1)) as previous_month_start_timestamp
;

Load
*
Inline
[
id,date,amount
```

```

8188,1/7/2022,17.17
8189,1/19/2022,37.23
8190,2/28/2022,88.27
8191,2/5/2022,57.42
8192,3/16/2022,53.80
8193,4/1/2022,82.06
8194,5/7/2022,40.39
8195,5/16/2022,87.21
8196,6/15/2022,95.93
8197,6/26/2022,45.89
8198,7/9/2022,36.23
8199,7/22/2022,25.66
8200,7/23/2022,82.77
8201,7/27/2022,69.98
8202,8/2/2022,76.11
8203,8/8/2022,25.12
8204,8/19/2022,46.23
8205,9/26/2022,84.21
8206,10/14/2022,96.24
8207,10/29/2022,67.67
];

```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- previous\_month\_start
- previous\_month\_start\_timestamp

Results table


date	previous_month_start	previous_month_start_timestamp
1/7/2022	12/01/2021	12/1/2021 12:00:00 AM
1/19/2022	12/01/2021	12/1/2021 12:00:00 AM
2/5/2022	01/01/2022	1/1/2022 12:00:00 AM
2/28/2022	01/01/2022	1/1/2022 12:00:00 AM
3/16/2022	02/01/2022	2/1/2022 12:00:00 AM
4/1/2022	03/01/2022	3/1/2022 12:00:00 AM
5/7/2022	04/01/2022	4/1/2022 12:00:00 AM
5/16/2022	04/01/2022	4/1/2022 12:00:00 AM
6/15/2022	05/01/2022	5/1/2022 12:00:00 AM
6/26/2022	05/01/2022	5/1/2022 12:00:00 AM
7/9/2022	06/01/2022	6/1/2022 12:00:00 AM



date	previous_month_start	previous_month_start_timestamp
7/22/2022	06/01/2022	6/1/2022 12:00:00 AM
7/23/2022	06/01/2022	6/1/2022 12:00:00 AM
7/27/2022	06/01/2022	6/1/2022 12:00:00 AM
8/2/2022	07/01/2022	7/1/2022 12:00:00 AM
8/8/2022	07/01/2022	7/1/2022 12:00:00 AM
8/19/2022	07/01/2022	7/1/2022 12:00:00 AM
9/26/2022	08/01/2022	8/1/2022 12:00:00 AM
10/14/2022	09/01/2022	9/1/2022 12:00:00 AM
10/29/2022	09/01/2022	9/1/2022 12:00:00 AM

In this instance, because a `period_no` of `-1` was used as the offset argument in the `monthstart()` function, the function first identifies the month that the transactions take place in. It then shifts one month prior and identifies the first millisecond of that month.

*Diagram of `monthstart()` function, `period_no` example*



Transaction 8192 took place on March 16. The `monthstart()` function identifies that the month before the transaction took place in was February. It then returns the first millisecond of that month, February 1 at 12:00:00 AM.

### Example 3 – Chart object example

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains the same dataset and scenario as the first example.

However, in this example, the unchanged dataset is loaded into the application. The calculation that returns a timestamp for the start of the month when the transactions took place is created as a measure in a chart object of the application.

### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
```

```
8188,1/7/2022,17.17
```

```
8189,1/19/2022,37.23
```

```
8190,2/28/2022,88.27
```

```
8191,2/5/2022,57.42
```

```
8192,3/16/2022,53.80
```

```
8193,4/1/2022,82.06
```

```
8194,5/7/2022,40.39
```

```
8195,5/16/2022,87.21
```

```
8196,6/15/2022,95.93
```

```
8197,6/26/2022,45.89
```

```
8198,7/9/2022,36.23
```

```
8199,7/22/2022,25.66
```

```
8200,7/23/2022,82.77
```

```
8201,7/27/2022,69.98
```

```
8202,8/2/2022,76.11
```

```
8203,8/8/2022,25.12
```

```
8204,8/19/2022,46.23
```

```
8205,9/26/2022,84.21
```

```
8206,10/14/2022,96.24
```

```
8207,10/29/2022,67.67
```

```
];
```

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension: date.

To calculate the start date of the month that a transaction takes place in, create the following measures:

- =monthstart(date)
- =timestamp(monthstart(date))

Results table


date	=monthstart(date)	=timestamp(monthstart(date))
10/14/2022	10/01/2022	10/1/2022 12:00:00 AM

<b>date</b>	<b>=monthstart(date)</b>	<b>=timestamp(monthstart(date))</b>
10/29/2022	10/01/2022	10/1/2022 12:00:00 AM
9/26/2022	09/01/2022	9/1/2022 12:00:00 AM
8/2/2022	08/01/2022	8/1/2022 12:00:00 AM
8/8/2022	08/01/2022	8/1/2022 12:00:00 AM
8/19/2022	08/01/2022	8/1/2022 12:00:00 AM
7/9/2022	07/01/2022	7/1/2022 12:00:00 AM
7/22/2022	07/01/2022	7/1/2022 12:00:00 AM
7/23/2022	07/01/2022	7/1/2022 12:00:00 AM
7/27/2022	07/01/2022	7/1/2022 12:00:00 AM
6/15/2022	06/01/2022	6/1/2022 12:00:00 AM
6/26/2022	06/01/2022	6/1/2022 12:00:00 AM
5/7/2022	05/01/2022	5/1/2022 12:00:00 AM
5/16/2022	05/01/2022	5/1/2022 12:00:00 AM
4/1/2022	04/01/2022	4/1/2022 12:00:00 AM
3/16/2022	03/01/2022	3/1/2022 12:00:00 AM
2/5/2022	02/01/2022	2/1/2022 12:00:00 AM
2/28/2022	02/01/2022	2/1/2022 12:00:00 AM
1/7/2022	01/01/2022	1/1/2022 12:00:00 AM
1/19/2022	01/01/2022	1/1/2022 12:00:00 AM

The `start_of_month` measure is created in the chart object by using the `monthstart()` function and passing the date field as the function's argument.

The `monthstart()` function identifies which month the date value falls into returning a timestamp for the first millisecond of that month.

Diagram of `monthstart()` function, chart object example



Transaction 8192 took place on March 16. The `monthstart()` function identifies that the transaction took place in March and returns the first millisecond of that month, which is March 1 at 12:00:00 AM.

### Example 4 – Scenario

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of loan balances, which is loaded into a table called Loans.
- Data consisting of loan IDs, the balance at the start of the month, and the simple interest rate charged on each loan per annum.

The end user would like a chart object that displays, by loan ID, the current interest that has been accrued on each loan in the month to date.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Loans:
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
loan_id,start_balance,rate
```

```
8188,$10000.00,0.024
```

```
8189,$15000.00,0.057
```

```
8190,$17500.00,0.024
```

```
8191,$21000.00,0.034
```

```
8192,$90000.00,0.084
```

```
];
```

**Results****Do the following:**

1. Load the data and open a sheet. Create a new table and add these fields as dimensions:
  - loan\_id
  - start\_balance
2. Next, create a measure to calculate the accumulated interest:  

$$=start\_balance*(rate*(today(1)-monthstart(today(1)))/365)$$
3. Set the measure's **Number formatting** to **Money**.

Results table

loan_id	start_balance	=start_balance*(rate*(today(1)-monthstart(today(1)))/365)
8188	\$10000.00	\$16.44
8189	\$15000.00	\$58.56
8190	\$17500.00	\$28.77
8191	\$21000.00	\$48.90
8192	\$90000.00	\$517.81

The `monthstart()` function, using today's date as its only argument, returns the start date of the current month. By subtracting that result from the current date, the expression returns the number of days that have elapsed so far this month.

This value is then multiplied by the interest rate and divided by 365 to return the effective interest rate incurred for this period. The result is then multiplied by the starting balance of the loan to return the interest that has been accrued so far this month.

**networkdays**

The **networkdays** function returns the number of working days (Monday-Friday) between and including **start\_date** and **end\_date** taking into account any optionally listed **holiday**.

**Syntax:**

```
networkdays (start_date, end_date [, holiday])
```

**Return data type:** integer

*Calendar diagram displaying date range returned by networkdays function*

Sun	Mon	Tue	Wed	Thu	Fri	Sat
	1	2	3	4	5	6
7	8	9	10 start_date	11	12	13
14	15	16	17	18	19	20
21	22	23	24	25	26 end_date	27
28	29	30	31			

The networkdays function has the following limitations:

- There is no method to modify workdays. In other words, there is no way to modify the function for regions or situations that involve anything other than working Monday to Friday.
- The holiday parameter must be a string constant. Expressions are not accepted.

### Arguments

Argument	Description
<b>start_date</b>	The start date to evaluate.
<b>end_date</b>	The end date to evaluate.
<b>holiday</b>	Holiday periods to exclude from working days. A holiday is stated as a string constant date. You can specify multiple holiday dates, separated by commas.  <b>Example:</b> '12/25/2013', '12/26/2013', '12/31/2013', '01/01/2014'

### When to use it

The networkdays() function is commonly used as part of an expression when the user would like the calculation to use the number of working week days that occur between two dates. For example, if a user would like to calculate the total wages that will be earned by an employee on a PAYE (pay-as-you-earn) contract.

### Function examples

Example	Result
<code>networkdays ('12/19/2013', '01/07/2014')</code>	Returns 14. This example does not take holidays into account.
<code>networkdays ('12/19/2013', '01/07/2014', '12/25/2013', '12/26/2013')</code>	Returns 12. This example takes the holiday 12/25/2013 to 12/26/2013 into account.
<code>networkdays ('12/19/2013', '01/07/2014', '12/25/2013', '12/26/2013', '12/31/2013', '01/01/2014')</code>	Returns 10. This example takes two holiday periods into account.

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Example 1 – Basic example

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing project IDs, their start dates, and their end dates. This information is loaded into a table called `Projects`.
- The date field provided in the `DateFormat` system variable (MM/DD/YYYY) format.
- The creation of an additional field, `net_work_days`, to calculate the number of working days involved in each project.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Projects:
```

```
  Load  
    *,
```

```
        networkdays(start_date,end_date) as net_work_days
    ;
Load
id,
start_date,
end_date
Inline
[
id,start_date,end_date
1,01/01/2022,01/18/2022
2,02/10/2022,02/17/2022
3,05/17/2022,07/05/2022
4,06/01/2022,06/12/2022
5,08/10/2022,08/26/2022
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- id
- start\_date
- end\_date
- net\_work\_days

Results table

id	start_date	end_date	net_work_days
1	01/01/2022	01/18/2022	12
2	02/10/2022	02/17/2022	6
3	05/17/2022	07/05/2022	36
4	06/01/2022	06/12/2022	8
5	08/10/2022	08/26/2022	13

Because there are no scheduled holidays (this would have been present in the third argument of the `networkdays()` function), the function subtracts the `start_date` from the `end_date`, as well as all weekends, to calculate the number of working days between the two dates.



Calendar diagram highlighting work days for project 5 (no holidays)

Sun	Mon	Tue	Wed	Thu	Fri	Sat
	1	2	3	4	5	6
7	8	9	10	11	12	13
14	15	16	17	18	19	20
21	22	23	24	25	26	27
28	29	30	31			

The calendar above visually outlines the project with id of 5. Project 5 begins on Wednesday, August 10, 2022 and ends on August 26, 2022. With all Saturdays and Sundays ignored, there are 13 working days between, and including, these two dates.

### Example 2 – Single holiday

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same dataset and scenario from the previous example.
- The date field provided in the `DateFormat` system variable (MM/DD/YYYY) format.
- The creation of an additional field, `net_work_days`, to calculate the number of working days involved in each project.

In this example, there is a one-day holiday scheduled on August 19, 2022.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

Projects:

```
Load
    *,
    networkdays(start_date,end_date,'08/19/2022') as net_work_days
;

Load
id,
start_date,
end_date
Inline
[
id,start_date,end_date
1,01/01/2022,01/18/2022
2,02/10/2022,02/17/2022
3,05/17/2022,07/05/2022
4,06/01/2022,06/12/2022
5,08/10/2022,08/26/2022
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- id
- start\_date
- end\_date
- net\_work\_days

Results table

id	start_date	end_date	net_work_days
1	01/01/2022	01/18/2022	12
2	02/10/2022	02/17/2022	6
3	05/17/2022	07/05/2022	36
4	06/01/2022	06/12/2022	8
5	08/10/2022	08/26/2022	12

The single scheduled holiday is entered as the third argument in the `networkdays()` function.

Calendar diagram highlighting work days for project 5 (single holiday)

Sun	Mon	Tue	Wed	Thu	Fri	Sat
	1	2	3	4	5	6
7	8	9	10	11	12	13
14	15	16	17	18	19 Holiday	20
21	22	23	24	25	26	27
28	29	30	31			

The calendar above visually outlines project 5, demonstrating this adjustment to include the holiday. This holiday occurs during project 5 on Friday, August 19, 2022. As a result, the total `net_work_days` value for project 5 decreases by one day, from 13 to 12 days.

### Example 3 – Multiple holidays

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same dataset and scenario from the first example.
- The date field provided in the `dateFormat` system variable (MM/DD/YYYY) format.
- The creation of an additional field, `net_work_days`, to calculate the number of working days involved in each project.

However, in this example, there are four holidays scheduled from August 18 to August 21, 2022.

### Load script

```
SET DateFormat='MM/DD/YYYY';

Projects:
  Load
    *,
    networkdays(start_date,end_date,'08/18/2022','08/19/2022','08/20/2022','08/21/2022')
  as net_work_days
  ;
Load
id,
start_date,
end_date
Inline
[
id,start_date,end_date
1,01/01/2022,01/18/2022
2,02/10/2022,02/17/2022
3,05/17/2022,07/05/2022
4,06/01/2022,06/12/2022
5,08/10/2022,08/26/2022
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- id
- start\_date
- end\_date
- net\_work\_days

Results table

id	start_date	end_date	net_work_days
1	01/01/2022	01/18/2022	12
2	02/10/2022	02/17/2022	6
3	05/17/2022	07/05/2022	36
4	06/01/2022	06/12/2022	8
5	08/10/2022	08/26/2022	11

The four scheduled holidays are entered as a comma separated list, from the third argument onwards in the `networkdays()` function.

Calendar diagram highlighting work days for project 5 (multiple holidays)

Sun	Mon	Tue	Wed	Thu	Fri	Sat
	1	2	3	4	5	6
7	8	9	10	11	12	13
14	15	16	17	18 Holiday	19 Holiday	20
21	22	23	24	25	26	27
28	29	30	31			

The calendar above visually outlines project 5, demonstrating this adjustment to include these holidays. This period of scheduled holidays occurs during project 5, with two of the days occurring on a Thursday and Friday. As a result, the total `net_work_days` value for project 5 decreases from 13 to 11 days.

### Example 4 – Single holiday

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same dataset and scenario from the first example.
- The date field provided in the `dateFormat` system variable (MM/DD/YYYY) format.

There is a one-day holiday scheduled on August 19, 2022.

However, in this example, the unchanged dataset is loaded into the application. The `net_work_days` field is calculated as a measure in a chart object.

### Load script

```
SET DateFormat='MM/DD/YYYY';

Projects:
Load
id,
start_date,
end_date
Inline
[
id,start_date,end_date
1,01/01/2022,01/18/2022
2,02/10/2022,02/17/2022
3,05/17/2022,07/05/2022
4,06/01/2022,06/12/2022
5,08/10/2022,08/26/2022
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- `id`
- `start_date`
- `end_date`

Create the following measure:

```
= networkdays(start_date,end_date,'08/19/2022')
```

Results table

<b>id</b>	<b>start_date</b>	<b>end_date</b>	<b>net_work_days</b>
1	01/01/2022	01/18/2022	12
2	02/10/2022	02/17/2022	6
3	05/17/2022	07/05/2022	36
4	06/01/2022	06/12/2022	8
5	08/10/2022	08/26/2022	12

The single scheduled holiday is entered as the third argument in the `networkdays()` function.

## 8 Script and chart functions

Calendar diagram showing net work days with single holiday (chart object)

Sun	Mon	Tue	Wed	Thu	Fri	Sat
	1	2	3	4	5	6
7	8	9	10	11	12	13
14	15	16	17	18	19 Holiday	20
21	22	23	24	25	26	27
28	29	30	31			

The calendar above visually outlines project 5, demonstrating this adjustment to include the holiday. This holiday occurs during project 5 on Friday, August 19, 2022. As a result, the total `net_work_days` value for project 5 decreases by one day, from 13 to 12 days.

### now

This function returns a timestamp of the current time. The function returns values in the **TimeStamp** system variable format. The default **timer\_mode** value is 1.


#### Syntax:

```
now([ timer_mode])
```

**Return data type:** dual

The `now()` function can be used either in the load script or in chart objects.

### Arguments

Argument	Description
timer_mode	<p>Can have the following values:</p> <ul style="list-style-type: none"> <li>0 (time at last finished data load)</li> <li>1 (time at function call)</li> <li>2 (time when the app was opened)</li> </ul> <div style="border: 1px solid #ccc; padding: 10px; margin-top: 10px;">  <p><i>If you use the function in a data load script, <b>timer_mode=0</b> will result in the time of the last finished data load, while <b>timer_mode=1</b> will give the time of the function call in the current data load.</i></p> </div>



*The `now()` function has a high-performance impact, which might result in scrolling issues if the function is used within tables' expressions. Whenever its use is not strictly necessary, we recommend using the `today()` function instead. If the use of `now()` is required in a layout, we recommend using the non-default settings `now(0)` or `now(2)` when possible, as they do not require constant recalculations*

### When to use it

The `now()` function is commonly used as a component within an expression. For example, it can be used to calculate the time remaining in a product's lifecycle. The `now()` function would be used instead of the `today()` function when the expression requires the use of a fraction of a day.

The following table provides an explanation of the result returned by the `now()` function, given different values for the `timer_mode` argument:

### Function examples

timer_mode value	Result if used in load script	Result if used in chart object
0	Returns a timestamp, in the <code>timestamp</code> system variable format, of the last successful data reload prior to the latest data reload.	Returns a timestamp, in the <code>timestamp</code> system variable format, for the latest data reload.
1	Returns a timestamp, in the <code>timestamp</code> system variable format, for the latest data reload.	Returns a timestamp, in the <code>timestamp</code> system variable format, of the function call.
2	Returns a timestamp, in the <code>timestamp</code> system variable format, for when the user's session in the application began. This will not be updated unless the user reloads the script.	Returns the timestamp, in the <code>timestamp</code> system variable format, for when the user's session in the application began. This will be refreshed once a new session begins or the data in the application is reloaded.



### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Example 1 – Generation of objects using load script

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

This example creates three variables using the `now()` function. Each variable uses one of the `timer_mode` options to demonstrate their effect.

For the variables to demonstrate their purpose, reload the script and then, after a short period of time, reload the script a second time. This will result in the `now(0)` and `now(1)` variables showing different values, thereby correctly demonstrating their purpose.

#### Load script

```
LET vPreviousDataLoad = now(0);
LET vCurrentDataLoad = now(1);
LET vApplicationOpened = now(2);
```

#### Results

Once the data has been loaded for a second time, create three textboxes using the directions below.

First, create a textbox for the data which has previously been loaded.

#### Do the following:

1. Using the **Text & Image** chart object, create a textbox.
2. Add the following measure to the object:  
`=vPreviousDataLoad`
3. Under **Appearance**, select **Show titles** and add the title 'Previous Reload Time' to the object.

Next, create a textbox for the data which is currently being loaded.

**Do the following:**


1. Using the **Text & Image** chart object, create a textbox.
2. Add the following measure to the object:  
=vCurrentDataLoad
3. Under **Appearance**, select **Show titles** and add the title 'Current Reload Time' to the object.

Create a final textbox to show when the user's session in the application was started.

**Do the following:**

1. Using the **Text & Image** chart object, create a textbox.
2. Add the following measure to the object:  
=vApplicationOpened
3. Under **Appearance**, select **Show titles** and add the title 'User Session Started' to the object.

*now()* load script variables



<b>Previous Reload Time</b> 6/22/2022 8:54:03 AM	<b>Current Reload Time</b> 6/22/2022 9:02:08 AM	<b>User Session Began</b> 6/22/2022 8:40:40 AM
---	--	---

The above image shows example values for each of the created variables. For example, the values could be as follows:

- Previous Reload Time: 6/22/2022 8:54:03 AM
- Current Reload Time: 6/22/2022 9:02:08 AM
- User Session Began: 6/22/2022 8:40:40 AM

### Example 2 – Generation of objects without load script

Load script and chart expression

**Overview**

In this example, you will create three chart objects using the *now()* function, without loading any variables or data into the application. Each chart object uses one of the *timer\_mode* options to demonstrate their effect.

There is no load script for this example.

### Do the following:

1. Open the Data load editor.
2. Without changing the existing load script, click **Load data**.
3. After a short period of time, load the script a second time.

### Results

Once the data has been loaded for a second time, create three textboxes.

First, create a textbox for the latest data reload.

### Do the following:

1. Using the **Text & Image** chart object, create a textbox.
2. Add the following measure:  
`=now(0)`
3. Under **Appearance**, select **Show titles** and add the title 'Latest Data Reload' to the object.

Next, create a textbox to show the current time.

### Do the following:

1. Using the **Text & Image** chart object, create a textbox.
2. Add the following measure:  
`=now(1)`
3. Under **Appearance**, select **Show titles** and add the title 'Current Time' to the object.

Create a final textbox to show when the user's session in the application was started.

### Do the following:

1. Using the **Text & Image** chart object, create a textbox.
2. Add the following measure:  
`=now(2)`
3. Under **Appearance**, select **Show titles** and add the title 'User Session Began' to the object.

*now()* chart object examples

<b>Latest Data Reload</b> 6/22/2022 9:02:08 AM	<b>Current Time</b> 6/22/2022 9:25:16 AM	<b>User Session Began</b> 6/22/2022 8:40:40 AM
---	---	---

The above image shows example values for each of the created objects. For example, the values could be as follows:

- Latest Data Reload: 6/22/2022 9:02:08 AM
- Current Time: 6/22/2022 9:25:16 AM
- User Session Began: 6/22/2022 8:40:40 AM

The 'Latest Data Reload' chart object uses a `timer_mode` value of 0. This returns the timestamp for the last time the data was successfully reloaded.

The 'Current Time' chart object uses a `timer_mode` value of 1. This returns the current time according to the system clock. If the sheet or object is refreshed, this value will be updated.

The 'User Session Began' chart object uses a `timer_mode` value of 2. This returns the timestamp for when the application was opened, and the user's session began.

### Example 3 – Scenario

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset consisting of inventory for a cryptocurrency mining operation, which is loaded into a table called `Inventory`.
- Data with the following fields: `id`, `purchase_date`, and `wph` (watts per hour).

The user would like a table that displays, by `id`, the total cost each mining rig has incurred in the month so far, in terms of power consumption.

This value should update whenever the chart object is refreshed. The current cost of electricity is \$0.0678 per kWh.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Inventory:
Load
*
Inline
[
id,purchase_date,wph
8188,1/7/2022,1123
8189,1/19/2022,1432
8190,2/28/2022,1227
8191,2/5/2022,1322
8192,3/16/2022,1273
8193,4/1/2022,1123
8194,5/7/2022,1342
8195,5/16/2022,2342
```

```
8196,6/15/2022,1231
8197,6/26/2022,1231
8198,7/9/2022,1123
8199,7/22/2022,1212
8200,7/23/2022,1223
8201,7/27/2022,1232
8202,8/2/2022,1232
8203,8/8/2022,1211
8204,8/19/2022,1243
8205,9/26/2022,1322
8206,10/14/2022,1133
8207,10/29/2022,1231
];
```

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension: id.

Create the following measure:

```
=(now(1)-monthstart(now(1)))*24*wph/1000*0.0678
```

If the chart object was refreshed at 6/22/2022 10:39:05 AM, it would return the following results:

Results table

id	=(now(1)-monthstart(now(1)))*24*wph/1000*0.0678
8188	\$39.18
8189	\$49.97
8190	\$42.81
8191	\$46.13
8192	\$44.42
8193	\$39.18
8194	\$46.83
8195	\$81.72
8196	\$42.95
8197	\$42.95
8198	\$39.18
8199	\$42.29
8200	\$42.67
8201	\$42.99
8202	\$42.99

id	<code>=(now(1)-monthstart(now(1)))*24*wph/1000*0.0678</code>
8203	\$42.25
8204	\$43.37
8205	\$46.13
8206	\$39.53

The user would like the object results to refresh every time the object is refreshed. Therefore, the `timer_mode` argument of supplied for instances of the `now()` function in the expression. The timestamp for the start of the month, identified by using the `now()` function as the timestamp argument in the `monthstart()` function, is subtracted from the current time which is identified by the `now()` function. This provides the total amount of time that has elapsed so far this month, in days.

This value is multiplied by 24 (the number of hours in a day) and then by the value in the `wph` field.

To convert from watts per hour to kilowatts per hour, the result is divided by 1000 before finally being multiplied by the `kWH` rate supplied.

### quarterend


This function returns a value corresponding to a timestamp of the last millisecond of the quarter containing **date**. The default output format will be the **DateFormat** set in the script.

#### Syntax:

```
QuarterEnd(date[, period_no[, first_month_of_year]])
```

**Return data type:** dual

*Diagram of the quarterend() function*



The `quarterend()` function determines which quarter the date falls into. It then returns a timestamp, in date format, for the last millisecond of the last month of that quarter. The first month of the year is, by default, January. However, you can change which month is set as first by using the `first_month_of_year` argument in the `quarterend()` function.



The `quarterend()` function does not consider the `FirstMonthOfYear` system variable. The year begins on January 1 unless the `first_month_of_year` argument is used to change it.

### When to use it

The `quarterend()` function is commonly used as part of an expression when you would like the calculation to use the fraction of the quarter that has not yet occurred. For example, if you want to calculate the total interest not yet incurred during the quarter.

#### Arguments

Argument	Description
<b>date</b>	The date or timestamp to evaluate.
<b>period_no</b>	<b>period_no</b> is an integer, where the value 0 indicates the quarter which contains <b>date</b> . Negative values in <b>period_no</b> indicate preceding quarters and positive values indicate succeeding quarters.
<b>first_month_of_year</b>	If you want to work with (fiscal) years not starting in January, indicate a value between 2 and 12 in <b>first_month_of_year</b> .

You can use the following values to set the first month of year in the `first_month_of_year` argument:

`first_month_of_year` values

Month	Value
February	2
March	3
April	4
May	5
June	6
July	7
August	8
September	9
October	10
November	11
December	12

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

#### Function examples

Example	Result
<code>quarterend('10/29/2005')</code>	Returns 12/31/2005 23:59:59.
<code>quarterend('10/29/2005', -1)</code>	Returns 09/30/2005 23:59:59.
<code>quarterend('10/29/2005', 0, 3)</code>	Returns 11/30/2005 23:59:59.

### Example 1 - Basic example

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions in 2022 which is loaded into a table called 'Transactions'.
- A preceding load which contains the following:
  - The `quarterend()` function that is set as the 'end\_of\_quarter' field and returns a timestamp for the end of the quarter when the transactions took place.
  - The `timestamp()` function that is set as the 'end\_of\_quarter\_timestamp' field and returns the exact timestamp of the end of the selected quarter.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
  Load
    *,
    quarterend(date) as end_of_quarter,
    timestamp(quarterend(date)) as end_of_quarter_timestamp
```



```
;  
Load  
*  
Inline  
[  
id,date,amount  
8188,1/7/2022,17.17  
8189,1/19/2022,37.23  
8190,2/28/2022,88.27  
8191,2/5/2022,57.42  
8192,3/16/2022,53.80  
8193,4/1/2022,82.06  
8194,5/7/2022,40.39  
8195,5/16/2022,87.21  
8196,6/15/2022,95.93  
8197,6/26/2022,45.89  
8198,7/9/2022,36.23  
8199,7/22/2022,25.66  
8200,7/23/2022,82.77  
8201,7/27/2022,69.98  
8202,8/2/2022,76.11  
8203,8/8/2022,25.12  
8204,8/19/2022,46.23  
8205,9/26/2022,84.21  
8206,10/14/2022,96.24  
8207,10/29/2022,67.67  
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- id
- date
- end\_of\_quarter
- end\_of\_quarter\_timestamp

Results table

id	date	end_of_quarter	end_of_quarter_timestamp
8188	1/7/2022	03/31/2022	3/31/2022 11:59:59 PM
8189	1/19/2022	03/31/2022	3/31/2022 11:59:59 PM
8190	2/5/2022	03/31/2022	3/31/2022 11:59:59 PM
8191	2/28/2022	03/31/2022	3/31/2022 11:59:59 PM
8192	3/16/2022	03/31/2022	3/31/2022 11:59:59 PM
8193	4/1/2022	06/30/2022	6/30/2022 11:59:59 PM
8194	5/7/2022	06/30/2022	6/30/2022 11:59:59 PM


## 8 Script and chart functions

id	date	end_of_quarter	end_of_quarter_timestamp
8195	5/16/2022	06/30/2022	6/30/2022 11:59:59 PM
8196	6/15/2022	06/30/2022	6/30/2022 11:59:59 PM
8197	6/26/2022	06/30/2022	6/30/2022 11:59:59 PM
8198	7/9/2022	09/30/2022	9/30/2022 11:59:59 PM
8199	7/22/2022	09/30/2022	9/30/2022 11:59:59 PM
8200	7/23/2022	09/30/2022	9/30/2022 11:59:59 PM
8201	7/27/2022	09/30/2022	9/30/2022 11:59:59 PM
8202	8/2/2022	09/30/2022	9/30/2022 11:59:59 PM
8203	8/8/2022	09/30/2022	9/30/2022 11:59:59 PM
8204	8/19/2022	09/30/2022	9/30/2022 11:59:59 PM
8205	9/26/2022	09/30/2022	9/30/2022 11:59:59 PM
8206	10/14/2022	12/31/2022	12/31/2022 11:59:59 PM
8207	10/29/2022	12/31/2022	12/31/2022 11:59:59 PM

The 'end\_of\_quarter' field is created in the preceding load statement by using the `quarterend()` function and passing the date field as the function's argument.

The `quarterend()` function initially identifies which quarter the date value falls into and then returns a timestamp for the last millisecond of that quarter.

*Diagram of the `quarterend()` function with the quarter end of transaction 8203 identified*



Transaction 8203 took place on August 8. The `quarterend()` function identifies that the transaction took place in the third quarter, and returns the last millisecond of that quarter, which is September 30 at 11:59:59 PM.

### Example 2 - period\_no

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions in 2022 which is loaded into a table called 'Transactions'.
- A preceding load which contains the following:
  - The `quarterend()` function that is set as the 'previous\_quarter\_end' field and returns a timestamp for the end of the quarter before the transaction took place.
  - The `timestamp()` function that is set as the 'previous\_end\_of\_quarter\_timestamp' field and returns the exact timestamp of the end of the quarter before the transaction took place.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
    Load
      *,
      quarterend(date, -1) as previous_quarter_end,
      timestamp(quarterend(date, -1)) as previous_quarter_end_timestamp
    ;
Load
*
Inline
[
id,date,amount
8188,1/7/2022,17.17
8189,1/19/2022,37.23
8190,2/28/2022,88.27
8191,2/5/2022,57.42
8192,3/16/2022,53.80
8193,4/1/2022,82.06
8194,5/7/2022,40.39
8195,5/16/2022,87.21
8196,6/15/2022,95.93
8197,6/26/2022,45.89
8198,7/9/2022,36.23
8199,7/22/2022,25.66
8200,7/23/2022,82.77
8201,7/27/2022,69.98
8202,8/2/2022,76.11
8203,8/8/2022,25.12
8204,8/19/2022,46.23
8205,9/26/2022,84.21
```

```
8206,10/14/2022,96.24  
8207,10/29/2022,67.67  
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- id
- date
- previous\_quarter\_end
- previous\_quarter\_end\_timestamp


Results table

id	date	previous_quarter_end	previous_quarter_end_timestamp
8188	1/7/2022	12/31/2021	12/31/2021 11:59:59 PM
8189	1/19/2022	12/31/2021	12/31/2021 11:59:59 PM
8190	2/5/2022	12/31/2021	12/31/2021 11:59:59 PM
8191	2/28/2022	12/31/2021	12/31/2021 11:59:59 PM
8192	3/16/2022	12/31/2021	12/31/2021 11:59:59 PM
8193	4/1/2022	03/31/2022	3/31/2022 11:59:59 PM
8194	5/7/2022	03/31/2022	3/31/2022 11:59:59 PM
8195	5/16/2022	03/31/2022	3/31/2022 11:59:59 PM
8196	6/15/2022	03/31/2022	3/31/2022 11:59:59 PM
8197	6/26/2022	03/31/2022	3/31/2022 11:59:59 PM
8198	7/9/2022	06/30/2022	6/30/2022 11:59:59 PM
8199	7/22/2022	06/30/2022	6/30/2022 11:59:59 PM
8200	7/23/2022	06/30/2022	6/30/2022 11:59:59 PM
8201	7/27/2022	06/30/2022	6/30/2022 11:59:59 PM
8202	8/2/2022	06/30/2022	6/30/2022 11:59:59 PM
8203	8/8/2022	06/30/2022	6/30/2022 11:59:59 PM
8204	8/19/2022	06/30/2022	6/30/2022 11:59:59 PM
8205	9/26/2022	06/30/2022	6/30/2022 11:59:59 PM
8206	10/14/2022	09/30/2022	9/30/2022 11:59:59 PM
8207	10/29/2022	09/30/2022	9/30/2022 11:59:59 PM

## 8 Script and chart functions

Because a `period_no` of -1 is used as the offset argument in the `quarterend()` function, the function first identifies the quarter that the transactions take place in. It then shifts one quarter prior and identifies the final millisecond of that quarter.

Diagram of the `quarterend()` function with a `period_no` of -1



Transaction 8203 took place on August 8. The `quarterend()` function identifies that the quarter before the transaction took place was between April 1 and June 30. The function then returns the final millisecond of that quarter, June 30 at 11:59:59 PM.

### Example 3 - first\_month\_of\_year

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions in 2022 which is loaded into a table called 'Transactions'.
- A preceding load which contains the following:
  - The `quarterend()` function that is set as the 'end\_of\_quarter' field and returns a timestamp for the end of the quarter when the transactions took place.
  - The `timestamp()` function that is set as the 'end\_of\_quarter\_timestamp' field and returns the exact timestamp of the end of the selected quarter.

However, in this example, the company policy is that the financial year begins on March 1.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
Load
*,
quarterend(date, 0, 3) as end_of_quarter,
```

## 8 Script and chart functions

---

```
timestamp(quarterend(date, 0, 3)) as end_of_quarter_timestamp
;
Load
*
Inline
[
id,date,amount
8188,1/7/2022,17.17
8189,1/19/2022,37.23
8190,2/28/2022,88.27
8191,2/5/2022,57.42
8192,3/16/2022,53.80
8193,4/1/2022,82.06
8194,5/7/2022,40.39
8195,5/16/2022,87.21
8196,6/15/2022,95.93
8197,6/26/2022,45.89
8198,7/9/2022,36.23
8199,7/22/2022,25.66
8200,7/23/2022,82.77
8201,7/27/2022,69.98
8202,8/2/2022,76.11
8203,8/8/2022,25.12
8204,8/19/2022,46.23
8205,9/26/2022,84.21
8206,10/14/2022,96.24
8207,10/29/2022,67.67
];
```

### Results


Results table

id	date	end_of_quarter	end_of_quarter_timestamp
8188	1/7/2022	02/28/2022	2/28/2022 11:59:59 PM
8189	1/19/2022	02/28/2022	2/28/2022 11:59:59 PM
8190	2/5/2022	02/28/2022	2/28/2022 11:59:59 PM
8191	2/28/2022	02/28/2022	2/28/2022 11:59:59 PM
8192	3/16/2022	05/31/2022	5/31/2022 11:59:59 PM
8193	4/1/2022	05/31/2022	5/31/2022 11:59:59 PM
8194	5/7/2022	05/31/2022	5/31/2022 11:59:59 PM
8195	5/16/2022	05/31/2022	5/31/2022 11:59:59 PM
8196	6/15/2022	08/31/2022	8/31/2022 11:59:59 PM
8197	6/26/2022	08/31/2022	8/31/2022 11:59:59 PM
8198	7/9/2022	08/31/2022	8/31/2022 11:59:59 PM

id	date	end_of_quarter	end_of_quarter_timestamp
8199	7/22/2022	08/31/2022	8/31/2022 11:59:59 PM
8200	7/23/2022	08/31/2022	8/31/2022 11:59:59 PM
8201	7/27/2022	08/31/2022	8/31/2022 11:59:59 PM
8202	8/2/2022	08/31/2022	8/31/2022 11:59:59 PM
8203	8/8/2022	08/31/2022	8/31/2022 11:59:59 PM
8204	8/19/2022	08/31/2022	8/31/2022 11:59:59 PM
8205	9/26/2022	11/30/2022	11/30/2022 11:59:59 PM
8206	10/14/2022	11/30/2022	11/30/2022 11:59:59 PM
8207	10/29/2022	11/30/2022	11/30/2022 11:59:59 PM

Because the `first_month_of_year` argument of 3 is used in the `quarterend()` function, the start of the year moves from January 1 to March 1.

*Diagram of the `quarterend()` function with March as the first month of the year*



Transaction 8203 took place on August 8. Because the beginning of the year is March 1, the quarters in the year occur between Mar-May, Jun-Aug, Sep-Nov, and Dec-Feb.

The `quarterend()` function identifies that the transaction took place in the quarter between the start of June and of August and returns the last millisecond of that quarter, which is August 31 at 11:59:59 PM.

### Example 4 - Chart object example

Load script and chart expression

#### Overview

The same dataset and scenario as the first example are used.

However, in this example, the dataset is unchanged and loaded into the application. The calculation that returns a timestamp for the end of the quarter when the transactions took place is created as a measure in a chart in the app.

### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
```

```
8188,1/7/2022,17.17
```

```
8189,1/19/2022,37.23
```

```
8190,2/28/2022,88.27
```

```
8191,2/5/2022,57.42
```

```
8192,3/16/2022,53.80
```

```
8193,4/1/2022,82.06
```

```
8194,5/7/2022,40.39
```

```
8195,5/16/2022,87.21
```

```
8196,6/15/2022,95.93
```

```
8197,6/26/2022,45.89
```

```
8198,7/9/2022,36.23
```

```
8199,7/22/2022,25.66
```

```
8200,7/23/2022,82.77
```

```
8201,7/27/2022,69.98
```

```
8202,8/2/2022,76.11
```

```
8203,8/8/2022,25.12
```

```
8204,8/19/2022,46.23
```

```
8205,9/26/2022,84.21
```

```
8206,10/14/2022,96.24
```

```
8207,10/29/2022,67.67
```

```
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- id
- date

To calculate the end date of the quarter that a transaction takes place in, create the following measures:

- =quarterend(date)
- =timestamp(quarterend(date))

Results table

id	date	=quarterend(date)	=timestamp(quarterend(date))
8188	1/7/2022	03/31/2022	3/31/2022 11:59:59 PM
8189	1/19/2022	03/31/2022	3/31/2022 11:59:59 PM




## 8 Script and chart functions

id	date	=quarterend(date)	=timestamp(quarterend(date))
8190	2/5/2022	03/31/2022	3/31/2022 11:59:59 PM
8191	2/28/2022	03/31/2022	3/31/2022 11:59:59 PM
8192	3/16/2022	03/31/2022	3/31/2022 11:59:59 PM
8193	4/1/2022	06/30/2022	6/30/2022 11:59:59 PM
8194	5/7/2022	06/30/2022	6/30/2022 11:59:59 PM
8195	5/16/2022	06/30/2022	6/30/2022 11:59:59 PM
8196	6/15/2022	06/30/2022	6/30/2022 11:59:59 PM
8197	6/26/2022	06/30/2022	6/30/2022 11:59:59 PM
8198	7/9/2022	09/30/2022	9/30/2022 11:59:59 PM
8199	7/22/2022	09/30/2022	9/30/2022 11:59:59 PM
8200	7/23/2022	09/30/2022	9/30/2022 11:59:59 PM
8201	7/27/2022	09/30/2022	9/30/2022 11:59:59 PM
8202	8/2/2022	09/30/2022	9/30/2022 11:59:59 PM
8203	8/8/2022	09/30/2022	9/30/2022 11:59:59 PM
8204	8/19/2022	09/30/2022	9/30/2022 11:59:59 PM
8205	9/26/2022	09/30/2022	9/30/2022 11:59:59 PM
8206	10/14/2022	12/31/2022	12/31/2022 11:59:59 PM
8207	10/29/2022	12/31/2022	12/31/2022 11:59:59 PM

The 'end\_of\_quarter' field is created in the preceding load statement by using the quarterend() function and passing the date field as the function's argument.

The quarterend() function initially identifies which quarter the date value falls into and then returns a timestamp for the last millisecond of that quarter.

*Diagram of the quarterend() function with the quarter end of transaction 8203 identified*



Transaction 8203 took place on August 8. The `quarterend()` function identifies that the transaction took place in the third quarter, and returns the last millisecond of that quarter, which is September 30 at 11:59:59 PM.

### Example 5 - Scenario

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset is loaded into a table called 'Employee\_Expenses'. The table contains the following fields:
  - Employee IDs
  - Employee names
  - The average daily expense claims of each employee.

The end user would like a chart object that displays, by employee id and employee name, the estimated expense claims still to be incurred for the remainder of the quarter. The financial year begins in January.

#### Load script

```
Employee_Expenses :
Load
*
Inline
[
employee_id,employee_name,avg_daily_claim
182,Mark, $15
183,Deryck, $12.5
184,Dexter, $12.5
185,Sydney,$27
186,Agatha,$18
];
```

#### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- `employee_id`
- `employee_name`

To calculate the accumulated interest, create the following measure:

- `=(quarterend(today(1))-today(1))*avg_daily_claim`

Set the measure's **Number Formatting** to **Money**.

Results table

employee_id	employee_name	=(quarterend(today(1))-today(1))*avg_daily_claim
182	Mark	\$480.00
183	Deryck	\$400.00
184	Dexter	\$400.00
185	Sydney	\$864.00
186	Agatha	\$576.00

The `quarterend()` function uses today's date as its only argument and returns the end date of the current month. Then, it subtracts today's date from the year end date, and the expression returns the number of days that remain this month.

This value is then multiplied by the average daily expense claim of each employee to calculate the estimated value of claims each employee is expected to make in the remaining quarter.

### quartername


This function returns a display value showing the months of the quarter (formatted according to the **MonthNames** script variable) and year with an underlying numeric value corresponding to a timestamp of the first millisecond of the first day of the quarter.

#### Syntax:

```
QuarterName (date[, period_no[, first_month_of_year]])
```

**Return data type:** dual

*Diagram of quartername() function*



The `quartername()` function determines which quarter the date falls into. It then returns a value showing the start-end months of this quarter as well as the year. The underlying numeric value of this result is the first millisecond of the quarter.

Arguments

Argument	Description
<b>date</b>	The date or timestamp to evaluate.

Argument	Description
<b>period_no</b>	<b>period_no</b> is an integer, where the value 0 indicates the quarter which contains <b>date</b> . Negative values in <b>period_no</b> indicate preceding quarters and positive values indicate succeeding quarters.
<b>first_</b> <b>month_of_</b> <b>year</b>	If you want to work with (fiscal) years not starting in January, indicate a value between 2 and 12 in <b>first_month_of_year</b> .

### When to use it

The `quartername()` function is useful when you would like to compare aggregations by quarter. For example, if you would like to see the total sales of products by quarter.

This function could be used in the load script to create a field in a Master Calendar table. Alternatively, it could be used directly in a chart as a calculated dimension.

These examples use the date format MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement at the top of your data load script. Change the format in the examples to suit your requirements.

#### Function examples

Example	Result
<code>quartername('10/29/2013')</code>	Returns Oct-Dec 2013.
<code>quartername('10/29/2013', -1)</code>	Returns Jul-Sep 2013.
<code>quartername('10/29/2013', 0, 3)</code>	Returns Sep-Nov 2013.

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Example 1 – date with no additional arguments

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions for 2022, which is loaded into a table called Transactions.
- The date field provided in the `dateFormat` system variable (MM/DD/YYYY) format.
- The creation of a field, `transaction_quarter`, which returns the quarter in which the transactions took place.

Add your other text here, as needed, with lists etc.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
SET MonthNames='Jan;Feb;Mar;Apr;May;Jun;Jul;Aug;Sep;Oct;Nov;Dec';
```

```
Transactions:
```

```
Load
    *,
    quartername(date) as transaction_quarter
;
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
```

```
8188,1/7/2022,17.17
```

```
8189,1/19/2022,37.23
```

```
8190,2/28/2022,88.27
```

```
8191,2/5/2022,57.42
```

```
8192,3/16/2022,53.80
```

```
8193,4/1/2022,82.06
```

```
8194,5/7/2022,40.39
```

```
8195,5/16/2022,87.21
```

```
8196,6/15/2022,95.93
```

```
8197,6/26/2022,45.89
```

```
8198,7/9/2022,36.23
```

```
8199,7/22/2022,25.66
```

```
8200,7/23/2022,82.77
```

```
8201,7/27/2022,69.98
```

```
8202,8/2/2022,76.11
```

```
8203,8/8/2022,25.12
```

```
8204,8/19/2022,46.23
```

```
8205,9/26/2022,84.21
```

```
8206,10/14/2022,96.24
```

```
8207,10/29/2022,67.67  
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- transaction\_quarter


Results table

<b>date</b>	<b>transaction_quarter</b>
1/7/2022	Jan-Mar 2022
1/19/2022	Jan-Mar 2022
2/5/2022	Jan-Mar 2022
2/28/2022	Jan-Mar 2022
3/16/2022	Jan-Mar 2022
4/1/2022	Apr-Jun 2022
5/7/2022	Apr-Jun 2022
5/16/2022	Apr-Jun 2022
6/15/2022	Apr-Jun 2022
6/26/2022	Apr-Jun 2022
7/9/2022	Jul-Sep 2022
7/22/2022	Jul-Sep 2022
7/23/2022	Jul-Sep 2022
7/27/2022	Jul-Sep 2022
8/2/2022	Jul-Sep 2022
8/8/2022	Jul-Sep 2022
8/19/2022	Jul-Sep 2022
9/26/2022	Jul-Sep 2022
10/14/2022	Oct-Dec 2022
10/29/2022	Oct-Dec 2022

The `transaction_quarter` field is created in the preceding load statement by using the `quartername()` function and passing the `date` field as the function's argument.

The `quartername()` function initially identifies the quarter into which the date value falls. It then returns a value showing the start-end months of this quarter, as well as the year.

Diagram of `quartername()` function, example with no additional arguments



Transaction 8203 took place on August 8, 2022. The `quartername()` function identifies that the transaction took place in the third quarter, and therefore returns Jul-Sep 2022. The months are displayed in the same format as the `MonthNames` system variable.

### Example 2 – date with `period_no` argument

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same dataset and scenario as the first example.
- The creation of a field, `previous_quarter`, that returns the previous quarter to when the transactions took place.

#### Load script

```
SET DateFormat='MM/DD/YYYY';  
SET MonthNames='Jan;Feb;Mar;Apr;May;Jun;Jul;Aug;Sep;Oct;Nov;Dec';
```

Transactions:

```
Load  
*,  
quartername(date,-1) as previous_quarter  
;
```

Load

\*

Inline

```
[  
id,date,amount  
8188,1/7/2022,17.17  
8189,1/19/2022,37.23  
8190,2/28/2022,88.27  
8191,2/5/2022,57.42  
8192,3/16/2022,53.80  
8193,4/1/2022,82.06  
8194,5/7/2022,40.39  
8195,5/16/2022,87.21
```

```
8196,6/15/2022,95.93
8197,6/26/2022,45.89
8198,7/9/2022,36.23
8199,7/22/2022,25.66
8200,7/23/2022,82.77
8201,7/27/2022,69.98
8202,8/2/2022,76.11
8203,8/8/2022,25.12
8204,8/19/2022,46.23
8205,9/26/2022,84.21
8206,10/14/2022,96.24
8207,10/29/2022,67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- previous\_quarter

Results table


date	previous_quarter
1/7/2022	Oct-Dec 2021
1/19/2022	Oct-Dec 2021
2/5/2022	Oct-Dec 2021
2/28/2022	Oct-Dec 2021
3/16/2022	Oct-Dec 2021
4/1/2022	Jan-Mar 2022
5/7/2022	Jan-Mar 2022
5/16/2022	Jan-Mar 2022
6/15/2022	Jan-Mar 2022
6/26/2022	Jan-Mar 2022
7/9/2022	Apr-Jun 2022
7/22/2022	Apr-Jun 2022
7/23/2022	Apr-Jun 2022
7/27/2022	Apr-Jun 2022
8/2/2022	Apr-Jun 2022
8/8/2022	Apr-Jun 2022
8/19/2022	Apr-Jun 2022



date	previous_quarter
9/26/2022	Apr-Jun 2022
10/14/2022	Jul-Sep 2022
10/29/2022	Jul-Sep 2022

In this instance, because a `period_no` of -1 was used as the offset argument in the `quartername()` function, the function first identifies that the transactions took place in the third quarter. It then shifts one quarter prior and returns a value showing the start-end months of this quarter, as well as the year.

*Diagram of `quartername()` function, `period_no` example*



Transaction 8203 took place on August 8. The `quartername()` function identifies that the quarter before the transaction took place was between April 1 and June 30. Therefore, it returns Apr-Jun 2022.

### Example 3 – date with `first_week_day` argument

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains the same dataset and scenario as the first example. However, in this example, we need to set March 1 as the beginning of the financial year.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
SET MonthNames='Jan;Feb;Mar;Apr;May;Jun;Jul;Aug;Sep;Oct;Nov;Dec';
```

```
Transactions:
  Load
    *,
    quartername(date,0,3) as transaction_quarter
  ;
Load
```

```
*
Inline
[
id,date,amount
8188,1/7/2022,17.17
8189,1/19/2022,37.23
8190,2/28/2022,88.27
8191,2/5/2022,57.42
8192,3/16/2022,53.80
8193,4/1/2022,82.06
8194,5/7/2022,40.39
8195,5/16/2022,87.21
8196,6/15/2022,95.93
8197,6/26/2022,45.89
8198,7/9/2022,36.23
8199,7/22/2022,25.66
8200,7/23/2022,82.77
8201,7/27/2022,69.98
8202,8/2/2022,76.11
8203,8/8/2022,25.12
8204,8/19/2022,46.23
8205,9/26/2022,84.21
8206,10/14/2022,96.24
8207,10/29/2022,67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- transaction\_quarter


Results table

date	transaction_quarter
1/7/2022	Dec-Feb 2021
1/19/2022	Dec-Feb 2021
2/5/2022	Dec-Feb 2021
2/28/2022	Dec-Feb 2021
3/16/2022	Mar-May 2022
4/1/2022	Mar-May 2022
5/7/2022	Mar-May 2022
5/16/2022	Mar-May 2022
6/15/2022	Jun-Aug 2022
6/26/2022	Jun-Aug 2022

date	transaction_quarter
7/9/2022	Jun-Aug 2022
7/22/2022	Jun-Aug 2022
7/23/2022	Jun-Aug 2022
7/27/2022	Jun-Aug 2022
8/2/2022	Jun-Aug 2022
8/8/2022	Jun-Aug 2022
8/19/2022	Jun-Aug 2022
9/26/2022	Sep-Nov 2022
10/14/2022	Sep-Nov 2022
10/29/2022	Sep-Nov 2022

In this instance, because the `first_month_of_year` argument of 3 is used in the `quartername()` function, the start of the year moves from January 1 to March 1. Therefore, the quarters in the year are separated into March-May, June-August, September-November and December-February.

*Diagram of `quartername()` function, `first_week_day` example*



Transaction 8203 took place on August 8. The `quartername()` function identifies that the transaction took place in the second quarter, between the start of June and the end of August. Therefore, it returns Jun-Aug 2022.

### Example 4 – Chart object example

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains the same dataset and scenario as the first example.

However, in this example, the unchanged dataset is loaded into the application. The calculation that returns a timestamp for the end of the quarter when the transactions took place is created as a measure in a chart object of the application.

### Load script

Transactions:

Load

\*

Inline

[

id,date,amount

8188,1/7/2022,17.17

8189,1/19/2022,37.23

8190,2/28/2022,88.27

8191,2/5/2022,57.42

8192,3/16/2022,53.80

8193,4/1/2022,82.06

8194,5/7/2022,40.39

8195,5/16/2022,87.21

8196,6/15/2022,95.93

8197,6/26/2022,45.89

8198,7/9/2022,36.23

8199,7/22/2022,25.66

8200,7/23/2022,82.77

8201,7/27/2022,69.98

8202,8/2/2022,76.11

8203,8/8/2022,25.12

8204,8/19/2022,46.23

8205,9/26/2022,84.21

8206,10/14/2022,96.24

8207,10/29/2022,67.67

];

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension: date.

Create the following measure:

=quartername(date)

Results table


date	=quartername(date)
1/7/2022	Jan-Mar 2022
1/19/2022	Jan-Mar 2022
2/5/2022	Jan-Mar 2022
2/28/2022	Jan-Mar 2022
3/16/2022	Jan-Mar 2022
4/1/2022	Apr-Jun 2022
5/7/2022	Apr-Jun 2022

date	=quartername(date)
5/16/2022	Apr-Jun 2022
6/15/2022	Apr-Jun 2022
6/26/2022	Apr-Jun 2022
7/9/2022	Jul-Sep 2022
7/22/2022	Jul-Sep 2022
7/23/2022	Jul-Sep 2022
7/27/2022	Jul-Sep 2022
8/2/2022	Jul-Sep 2022
8/8/2022	Jul-Sep 2022
8/19/2022	Jul-Sep 2022
9/26/2022	Jul-Sep 2022
10/14/2022	Oct-Dec 2022
10/29/2022	Oct-Dec 2022

The transaction\_quarter measure is created in the chart object by using the quartername() function and passing the date field as the function's argument.

The quartername() function initially identifies the quarter into which the date value falls. It then returns a value showing the start-end months of this quarter, as well as the year.

*Diagram of quartername() function, chart object example*



Transaction 8203 took place on August 8, 2022. The quartername() function identifies that the transaction took place in the third quarter, and therefore returns Jul-Sep 2022. The months are displayed in the same format as the monthNames system variable.

### Example 5 – Scenario

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions for 2022, which is loaded into a table called Transactions.
- The date field provided in the `dateFormat` system variable (MM/DD/YYYY) format.

The end user would like a chart object that presents the total sales by quarter for the transactions. This could be achieved even when this dimension is not available in the data model, using the `quartername()` function as a calculated dimension in the chart.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
```

```
8188,'1/7/2022',17.17
```

```
8189,'1/19/2022',37.23
```

```
8190,'2/28/2022',88.27
```

```
8191,'2/5/2022',57.42
```

```
8192,'3/16/2022',53.80
```

```
8193,'4/1/2022',82.06
```

```
8194,'5/7/2022',40.39
```

```
8195,'5/16/2022',87.21
```

```
8196,'6/15/2022',95.93
```

```
8197,'6/26/2022',45.89
```

```
8198,'7/9/2022',36.23
```

```
8199,'7/22/2022',25.66
```

```
8200,'7/23/2022',82.77
```

```
8201,'7/27/2022',69.98
```

```
8202,'8/2/2022',76.11
```

```
8203,'8/8/2022',25.12
```

```
8204,'8/19/2022',46.23
```

```
8205,'9/26/2022',84.21
```

```
8206,'10/14/2022',96.24
```

```
8207,'10/29/2022',67.67
```

```
];
```

## Results

### Do the following:

1. Load the data and open a sheet. Create a new table.
2. Create a calculated dimension using the following expression:  
=quartername(date)
3. Next, calculate total sales using the following aggregation measure:  
=sum(amount)
4. Set the measure's **Number formatting** to **Money**.

Results table

=quartername(date)	=sum(amount)
Jul-Sep 2022	\$446.31
Apr-Jun 2022	\$351.48
Jan-Mar 2022	\$253.89
Oct-Dec 2022	\$163.91

## quarterstart


This function returns a value corresponding to a timestamp of the first millisecond of the quarter containing **date**. The default output format will be the **DateFormat** set in the script.

### Syntax:

```
QuarterStart (date[, period_no[, first_month_of_year]])
```

**Return data type:** dual

*Diagram of quarterstart() function*



The quarterstart() function determines which quarter the date falls into. It then returns a timestamp, in date format, for the first millisecond of the first month of that quarter.

### Arguments

Argument	Description
<b>date</b>	The date or timestamp to evaluate.
<b>period_no</b>	<b>period_no</b> is an integer, where the value 0 indicates the quarter which contains <b>date</b> . Negative values in <b>period_no</b> indicate preceding quarters and positive values indicate succeeding quarters.
<b>first_month_of_year</b>	If you want to work with (fiscal) years not starting in January, indicate a value between 2 and 12 in <b>first_month_of_year</b> .

### When to use it

The `quarterstart()` function is commonly used as part of an expression when the user would like the calculation to use the fraction of the quarter that has elapsed thus far. For example, it could be used if a user would like to calculate the interest that has been accumulated in a quarter to date.

### Function examples

Example	Result
<code>quarterstart('10/29/2005')</code>	Returns 10/01/2005.
<code>quarterstart('10/29/2005', -1 )</code>	Returns 07/01/2005.
<code>quarterstart('10/29/2005', 0, 3)</code>	Returns 09/01/2005.

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Example 1 – No additional arguments

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:



- A dataset containing a set of transactions for 2022, which is loaded into a table called Transactions.
- The date field provided in the DateFormat system variable (MM/DD/YYYY) format.
- The creation of a field, start\_of\_quarter, which returns a timestamp for the start of the quarter when the transactions took place.

### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
    Load
        *,
        quarterstart(date) as start_of_quarter,
        timestamp(quarterstart(date)) as start_of_quarter_timestamp
    ;

Load
*
Inline
[
id,date,amount
8188,1/7/2022,17.17
8189,1/19/2022,37.23
8190,2/28/2022,88.27
8191,2/5/2022,57.42
8192,3/16/2022,53.80
8193,4/1/2022,82.06
8194,5/7/2022,40.39
8195,5/16/2022,87.21
8196,6/15/2022,95.93
8197,6/26/2022,45.89
8198,7/9/2022,36.23
8199,7/22/2022,25.66
8200,7/23/2022,82.77
8201,7/27/2022,69.98
8202,8/2/2022,76.11
8203,8/8/2022,25.12
8204,8/19/2022,46.23
8205,9/26/2022,84.21
8206,10/14/2022,96.24
8207,10/29/2022,67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:


- date
- start\_of\_quarter
- start\_of\_quarter\_timestamp

Results table

<b>date</b>	<b>start_of_quarter</b>	<b>start_of_quarter_timestamp</b>
1/7/2022	01/01/2022	1/1/2022 12:00:00 AM
1/19/2022	01/01/2022	1/1/2022 12:00:00 AM
2/5/2022	01/01/2022	1/1/2022 12:00:00 AM
2/28/2022	01/01/2022	1/1/2022 12:00:00 AM
3/16/2022	01/01/2022	1/1/2022 12:00:00 AM
4/1/2022	04/01/2022	4/1/2021 12:00:00 AM
5/7/2022	04/01/2022	4/1/2021 12:00:00 AM
5/16/2022	04/01/2022	4/1/2021 12:00:00 AM
6/15/2022	04/01/2022	4/1/2021 12:00:00 AM
6/26/2022	04/01/2022	4/1/2021 12:00:00 AM
7/9/2022	07/01/2022	7/1/2021 12:00:00 AM
7/22/2022	07/01/2022	7/1/2021 12:00:00 AM
7/23/2022	07/01/2022	7/1/2021 12:00:00 AM
7/27/2022	07/01/2022	7/1/2021 12:00:00 AM
8/2/2022	07/01/2022	7/1/2021 12:00:00 AM
8/8/2022	07/01/2022	7/1/2021 12:00:00 AM
8/19/2022	07/01/2022	7/1/2021 12:00:00 AM
9/26/2022	07/01/2022	7/1/2021 12:00:00 AM
10/14/2022	10/01/2022	10/1/2022 12:00:00 AM
10/29/2022	10/01/2022	10/1/2022 12:00:00 AM

The `start_of_quarter` field is created in the preceding load statement by using the `quarterstart()` function and passing the `date` field as the function's argument. The `quarterstart()` function initially identifies which quarter the date value falls into. It then returns a timestamp for the first millisecond of that quarter.

Diagram of `quarterstart()` function, example with no additional arguments



Transaction 8203 took place on August 8. The `quarterstart()` function identifies that the transaction took place in the third quarter, and returns the first millisecond of that quarter, which is July 1 at 12:00:00 AM.

### Example 2 – `period_no`

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same dataset and scenario as the first example.
- The creation of a field, `previous_quarter_start`, that returns the timestamp for the start of the quarter before the transaction took place.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
Load
    *,
    quarterstart(date,-1) as previous_quarter_start,
    timestamp(quarterstart(date,-1)) as previous_quarter_start_timestamp
;
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
8188,1/7/2022,17.17
8189,1/19/2022,37.23
8190,2/28/2022,88.27
8191,2/5/2022,57.42
8192,3/16/2022,53.80
8193,4/1/2022,82.06
8194,5/7/2022,40.39
```

```
8195, 5/16/2022, 87.21
8196, 6/15/2022, 95.93
8197, 6/26/2022, 45.89
8198, 7/9/2022, 36.23
8199, 7/22/2022, 25.66
8200, 7/23/2022, 82.77
8201, 7/27/2022, 69.98
8202, 8/2/2022, 76.11
8203, 8/8/2022, 25.12
8204, 8/19/2022, 46.23
8205, 9/26/2022, 84.21
8206, 10/14/2022, 96.24
8207, 10/29/2022, 67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- previous\_quarter\_start
- previous\_quarter\_start\_timestamp


Results table

date	previous_quarter_start	previous_quarter_start_timestamp
1/7/2022	10/01/2021	10/1/2021 12:00:00 AM
1/19/2022	10/01/2021	10/1/2021 12:00:00 AM
2/5/2022	10/01/2021	10/1/2021 12:00:00 AM
2/28/2022	10/01/2021	10/1/2021 12:00:00 AM
3/16/2022	10/01/2021	10/1/2021 12:00:00 AM
4/1/2022	01/01/2022	1/1/2022 12:00:00 AM
5/7/2022	01/01/2022	1/1/2022 12:00:00 AM
5/16/2022	01/01/2022	1/1/2022 12:00:00 AM
6/15/2022	01/01/2022	1/1/2022 12:00:00 AM
6/26/2022	01/01/2022	1/1/2022 12:00:00 AM
7/9/2022	04/01/2022	4/1/2021 12:00:00 AM
7/22/2022	04/01/2022	4/1/2021 12:00:00 AM
7/23/2022	04/01/2022	4/1/2021 12:00:00 AM
7/27/2022	04/01/2022	4/1/2021 12:00:00 AM
8/2/2022	04/01/2022	4/1/2021 12:00:00 AM

date	previous_quarter_start	previous_quarter_start_timestamp
8/8/2022	04/01/2022	4/1/2021 12:00:00 AM
8/19/2022	04/01/2022	4/1/2021 12:00:00 AM
9/26/2022	04/01/2022	4/1/2021 12:00:00 AM
10/14/2022	07/01/2022	7/1/2022 12:00:00 AM
10/29/2022	07/01/2022	7/1/2022 12:00:00 AM

In this instance, because a `period_no` of -1 was used as the offset argument in the `quarterstart()` function, the function first identifies the quarter that the transactions take place in. It then shifts one quarter prior and identifies the first millisecond of that quarter.

*Diagram of `quarterstart()` function, `period_no` example*



Transaction 8203 took place on August 8. The `quarterstart()` function identifies that the quarter before the transaction took place was between April 1 and June 30. It then returns the first millisecond of that quarter, April 1 at 12:00:00 AM.

### Example 3 – `first_month_of_year`

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains the same dataset and scenario as the first example. However, in this example, we need to set March 1 as the beginning of the financial year.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

Transactions:

```
Load
*,
quarterstart(date,0,3) as start_of_quarter,
```

```
timestamp(quarterstart(date,0,3)) as start_of_quarter_timestamp
;
Load
*
Inline
[
id,date,amount
8188,1/7/2022,17.17
8189,1/19/2022,37.23
8190,2/28/2022,88.27
8191,2/5/2022,57.42
8192,3/16/2022,53.80
8193,4/1/2022,82.06
8194,5/7/2022,40.39
8195,5/16/2022,87.21
8196,6/15/2022,95.93
8197,6/26/2022,45.89
8198,7/9/2022,36.23
8199,7/22/2022,25.66
8200,7/23/2022,82.77
8201,7/27/2022,69.98
8202,8/2/2022,76.11
8203,8/8/2022,25.12
8204,8/19/2022,46.23
8205,9/26/2022,84.21
8206,10/14/2022,96.24
8207,10/29/2022,67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- start\_of\_quarter
- start\_of\_quarter\_timestamp


Results table

date	start_of_quarter	start_of_quarter_timestamp
1/7/2022	12/01/2021	12/1/2021 12:00:00 AM
1/19/2022	12/01/2021	12/1/2021 12:00:00 AM
2/5/2022	12/01/2021	12/1/2021 12:00:00 AM
2/28/2022	12/01/2021	12/1/2021 12:00:00 AM
3/16/2022	03/01/2022	3/1/2022 12:00:00 AM
4/1/2022	03/01/2022	3/1/2022 12:00:00 AM
5/7/2022	03/01/2022	3/1/2022 12:00:00 AM

date	start_of_quarter	start_of_quarter_timestamp
5/16/2022	03/01/2022	3/1/2022 12:00:00 AM
6/15/2022	06/01/2022	6/1/2022 12:00:00 AM
6/26/2022	06/01/2022	6/1/2022 12:00:00 AM
7/9/2022	06/01/2022	6/1/2022 12:00:00 AM
7/22/2022	06/01/2022	6/1/2022 12:00:00 AM
7/23/2022	06/01/2022	6/1/2022 12:00:00 AM
7/27/2022	06/01/2022	6/1/2022 12:00:00 AM
8/2/2022	06/01/2022	6/1/2022 12:00:00 AM
8/8/2022	06/01/2022	6/1/2022 12:00:00 AM
8/19/2022	06/01/2022	6/1/2022 12:00:00 AM
9/26/2022	09/01/2022	9/1/2022 12:00:00 AM
10/14/2022	09/01/2022	9/1/2022 12:00:00 AM
10/29/2022	09/01/2022	9/1/2022 12:00:00 AM

In this instance, because the `first_month_of_year` argument of 3 is used in the `quarterstart()` function, the start of the year moves from January 1 to March 1.

*Diagram of `quarterstart()` function, `first_month_of_year` example*



Transaction 8203 took place on August 8. Because the beginning of the year is March 1, the quarters in the year occur between March-May, June-August, September-November and December-February. The `quarterstart()` function identifies that the transaction took place in the quarter between the start of June and of August and returns the first millisecond of that quarter, which is June 1 at 12:00:00 AM.

### Example 4 – Chart object example

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains the same dataset and scenario as the first example.

However, in this example, the unchanged dataset is loaded into the application. The calculation that returns a timestamp for the end of the quarter when the transactions took place is created as a measure in a chart object of the application.

### Load script

Transactions:

```
Load
*
Inline
[
id,date,amount
8188,1/7/2022,17.17
8189,1/19/2022,37.23
8190,2/28/2022,88.27
8191,2/5/2022,57.42
8192,3/16/2022,53.80
8193,4/1/2022,82.06
8194,5/7/2022,40.39
8195,5/16/2022,87.21
8196,6/15/2022,95.93
8197,6/26/2022,45.89
8198,7/9/2022,36.23
8199,7/22/2022,25.66
8200,7/23/2022,82.77
8201,7/27/2022,69.98
8202,8/2/2022,76.11
8203,8/8/2022,25.12
8204,8/19/2022,46.23
8205,9/26/2022,84.21
8206,10/14/2022,96.24
8207,10/29/2022,67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension: date.

Add the following measures:

- =quarterstart(date)
- =timestamp(quarterstart(date))

Results table

date	=quarterstart(date)	=timestamp(quarterstart(date))
10/14/2022	10/01/2022	10/1/2022 12:00:00 AM
10/29/2022	10/01/2022	10/1/2022 12:00:00 AM
7/9/2022	07/01/2022	7/1/2022 12:00:00 AM




## 8 Script and chart functions

date	=quarterstart(date)	=timestamp(quarterstart(date))
7/22/2022	07/01/2022	7/1/2022 12:00:00 AM
7/23/2022	07/01/2022	7/1/2022 12:00:00 AM
7/27/2022	07/01/2022	7/1/2022 12:00:00 AM
8/2/2022	07/01/2022	7/1/2022 12:00:00 AM
8/8/2022	07/01/2022	7/1/2022 12:00:00 AM
8/19/2022	07/01/2022	7/1/2022 12:00:00 AM
9/26/2022	07/01/2022	7/1/2022 12:00:00 AM
4/1/2022	04/01/2022	4/1/2022 12:00:00 AM
5/7/2022	04/01/2022	4/1/2022 12:00:00 AM
5/16/2022	04/01/2022	4/1/2022 12:00:00 AM
6/15/2022	04/01/2022	4/1/2022 12:00:00 AM
6/26/2022	04/01/2022	4/1/2022 12:00:00 AM
1/7/2022	01/01/2022	1/1/2022 12:00:00 AM
1/19/2022	01/01/2022	1/1/2022 12:00:00 AM
2/5/2022	01/01/2022	1/1/2022 12:00:00 AM
2/28/2022	01/01/2022	1/1/2022 12:00:00 AM
3/16/2022	01/01/2022	1/1/2022 12:00:00 AM

The start\_of\_quarter measure is created in the chart object by using the quarterstart() function and passing the date field as the function's argument.

The quarterstart() function identifies the quarter into which the date value falls, returning a timestamp for the first millisecond of that quarter.

*Diagram of quarterstart() function, chart object example*



Transaction 8203 took place on August 8. The quarterstart() function identifies that the transaction took place in the third quarter, and returns the first millisecond of that quarter. This returned value is July 1 at 12:00:00 AM.

### Example 5 – Scenario

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of loan balances, which is loaded into a table called Loans.
- Data consisting of loan IDs, the balance at the beginning of the quarter, and the simple interest rate charged on each loan per annum.

The end user would like a chart object that displays, by loan ID, the current interest that has been accrued on each loan in the quarter to date.

#### Load script

```
Loans:
Load
*
Inline
[
loan_id,start_balance,rate
8188,$10000.00,0.024
8189,$15000.00,0.057
8190,$17500.00,0.024
8191,$21000.00,0.034
8192,$90000.00,0.084
];
```

#### Results

##### Do the following:

1. Load the data and open a sheet. Create a new table and add these fields as dimensions:
  - loan\_id
  - start\_balance
2. Next, create this measure to calculate the accumulated interest:  
 $=start\_balance*(rate*(today(1)-quarterstart(today(1)))/365)$
3. Set the measure's **Number formatting** to **Money**.

Results table

loan_id	start_balance	$=start\_balance*(rate*(today(1)-quarterstart(today(1)))/365)$
8188	\$10000.00	\$15.07
8189	\$15000.00	\$128.84

loan_id	start_balance	=start_balance*(rate*(today(1)-quarterstart(today(1)))/365)
8190	\$17500.00	\$63.29
8191	\$21000.00	\$107.59
8192	\$90000.00	\$1139.18

The `quarterstart()` function, using today's date as its only argument, returns the start date of the current year. By subtracting that result from the current date, the expression returns the number of days that have elapsed so far this quarter.

This value is then multiplied by the interest rate and divided by 365 to return the effective interest rate incurred for this period. The result is then multiplied by the starting balance of the loan to return the interest that has been accrued so far this quarter.

### second

This function returns an integer representing the second when the fraction of the **expression** is interpreted as a time according to the standard number interpretation.

#### Syntax:

```
second (expression)
```

**Return data type:** integer

#### When to use it

The `second()` function is useful when you would like to compare aggregations by second. For example, the function can be used if you would like to see activity count distribution by second.

These dimensions can be created either in the load script by using the function to create a field in a Master Calendar table, or used directly in a chart as a calculated dimension.

#### Function examples

Example	Result
<code>second( '09:14:36' )</code>	returns 36
<code>second( '0.5555' )</code>	returns 55 ( Because 0.5555 = 13:19:55 )

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Example 1 – Variable

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing transactions by timestamp, which is loaded into a table called Transactions.
- The default `Timestamp` system variable (`(M/D/YYYY h:mm:ss[.fff] TT)`) is used.
- The creation of a field, `second`, to calculate when purchases took place.

#### Load script

```
SET TimestampFormat='M/D/YYYY h:mm:ss[.fff] TT';
```

```
Transactions:
```

```
    Load
        *,
        second(date) as second
    ;

Load
*
Inline
[
id,date,amount
9497,'01/05/2022 7:04:57 PM',47.25
9498,'01/03/2022 2:21:53 PM',51.75
9499,'01/03/2022 5:40:49 AM',73.53
9500,'01/04/2022 6:49:38 PM',15.35
9501,'01/01/2022 10:10:22 PM',31.43
9502,'01/05/2022 7:34:46 PM',13.24
9503,'01/06/2022 10:58:34 PM',74.34
9504,'01/06/2022 11:29:38 AM',50.00
9505,'01/02/2022 8:35:54 AM',36.34
9506,'01/06/2022 8:49:09 AM',74.23
];
```

#### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- second

Results table

<b>date</b>	<b>second</b>
01/01/2022 10:10:22 PM	22
01/02/2022 8:35:54 AM	54
01/03/2022 5:40:49 AM	49
01/03/2022 2:21:53 PM	53
01/04/2022 6:49:38 PM	38
01/05/2022 7:04:57 PM	57
01/05/2022 7:34:46 PM	46
01/06/2022 8:49:09 AM	9
01/06/2022 11:29:38 AM	38
01/06/2022 10:58:34 PM	34

The values in the `second` field are created by using the `second()` function and passing the date as the expression in the preceding `load` statement.

### Example 2 – Chart object

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains the same dataset and scenario as the first example. However, in this example, the unchanged dataset is loaded into the application. The `second` values are calculated via a measure in a chart object.

#### Load script

```
SET TimestampFormat='M/D/YYYY h:mm:ss[.fff] TT';
```

```
Transactions:
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
```

```
9497,'01/05/2022 7:04:57 PM',47.25
```

```
9498,'01/03/2022 2:21:53 PM',51.75
```

```
9499,'01/03/2022 5:40:49 AM',73.53
```

```
9500, '01/04/2022 6:49:38 PM', 15.35
9501, '01/01/2022 10:10:22 PM', 31.43
9502, '01/05/2022 7:34:46 PM', 13.24
9503, '01/06/2022 10:58:34 PM', 74.34
9504, '01/06/2022 11:29:38 AM', 50.00
9505, '01/02/2022 8:35:54 AM', 36.34
9506, '01/06/2022 8:49:09 AM', 74.23
];
```

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension:date.

Create the following measure:

```
=second(date)
```

Results table

date	=second(date)
01/01/2022 10:10:22 PM	22
01/02/2022 8:35:54 AM	54
01/03/2022 5:40:49 AM	49
01/03/2022 2:21:53 PM	53
01/04/2022 6:49:38 PM	38
01/05/2022 7:04:57 PM	57
01/05/2022 7:34:46 PM	46
01/06/2022 8:49:09 AM	9
01/06/2022 11:29:38 AM	38
01/06/2022 10:58:34 PM	34

The values for second are created by using the second() function and passing the date as the expression in a measure for the chart object.

### Example 3 – Scenario

Load script and chart expressions

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

## 8 Script and chart functions

---

- A dataset of timestamps, which is generated to represent the traffic to a particular festival's ticket sales website. These timestamps and a corresponding `id` are loaded into a table called `web_Traffic`.
- The `timestamp` system variable `M/D/YYYY h:mm:ss[.fff] TT` is used.

In this scenario, there were 10000 tickets, which went on sale at 9:00 AM on May 20, 2021. One minute later, the tickets were sold out.

The user would like a chart object that shows, by second, the count of visits to the website.

### Load script

```
SET TimestampFormat='M/D/YYYY h:mm:ss[.fff] TT';

tmpTimeStampCreator:
load
    makedate(2022,05,20) as date
AutoGenerate 1;

join load
    maketime(9+floor(rand()*2),0,floor(rand()*59)) as time
autogenerate 10000;

web_Traffic:
load
    recno() as id,
    timestamp(date + time) as timestamp
resident tmpTimeStampCreator;

drop table tmpTimeStampCreator;
```

### Results

#### Do the following:

1. Load the data and open a sheet. Create a new table.
2. Next, create a calculated dimensions using the following expression:  
`=second(timestamp)`
3. Create an aggregation measure to calculate the total count of entries:  
`=count(id)`

The results table will look similar to the table below, but with different values for the aggregation measure:

Results table

<code>second(timestamp)</code>	<code>=count(id)</code>
0	150
1	184

<b>second(timestamp)</b>	<b>=count(id)</b>
2	163
3	178
4	179
5	158
6	177
7	169
8	149
9	186
10	169
11	179
12	186
13	182
14	180
15	153
16	191
17	203
18	158
19	159
20	163
+ 39 more rows	

### setdateyear

This function takes as input a **timestamp** and a **year** and updates the **timestamp** with the **year** specified in input.

#### Syntax:

```
setdateyear (timestamp, year)
```



**Return data type:** dual

**Arguments:**

Arguments

Argument	Description
<b>timestamp</b>	A standard Qlik Sense timestamp (often just a date).
<b>year</b>	A four-digit year.

Examples and results:

These examples use the date format **DD/MM/YYYY**. The date format is specified in the **SET DateFormat** statement at the top of your data load script. Change the format in the examples to suit your requirements.

Scripting examples

Example	Result
<pre>setdateyear ('29/10/2005', 2013)</pre>	Returns '29/10/2013'
<pre>setdateyear ('29/10/2005 04:26:14', 2013)</pre>	<p>Returns '29/10/2013 04:26:14'</p> <p>To see the time part of the timestamp in a visualization, you must set the number formatting to Date and choose a value for Formatting that displays time values.</p>

**Example:**

Add the example script to your app and run it. To see the result, add the fields listed in the results column to a sheet in your app.

```
SetYear:
Load *,
SetDateYear(testdates, 2013) as NewYear
Inline [
testdates
1/11/2012
10/12/2012
1/5/2013
2/1/2013
19/5/2013
15/9/2013
11/12/2013
2/3/2014
14/5/2014
13/6/2014
7/7/2014
4/8/2014
];
```

The resulting table contains the original dates and a column in which the year has be set to 2013.

Results table

<b>testdates</b>	<b>NewYear</b>
1/11/2012	1/11/2013
10/12/2012	10/12/2013
2/1/2012	2/1/2013
1/5/2013	1/5/2013
19/5/2013	19/5/2013
15/9/2013	15/9/2013
11/12/2013	11/12/2013
2/3/2014	2/3/2013
14/5/2014	14/5/2013
13/6/2014	13/6/2013
7/7/2014	7/7/2013
4/8/2014	4/8/2013

### setdateyearmonth

This function takes as input a **timestamp**, a **month** and a **year** and updates the **timestamp** with the **year** and the **month** specified in input. .

#### Syntax:

```
SetDateYearMonth (timestamp, year, month)
```

**Return data type:** dual

#### Arguments:

Arguments

<b>Argument</b>	<b>Description</b>
<b>timestamp</b>	A standard Qlik Sense timestamp (often just a date).
<b>year</b>	A four-digit year.
<b>month</b>	A one or two-digit month.

Examples and results:

These examples use the date format **DD/MM/YYYY**. The date format is specified in the **SET DateFormat** statement at the top of your data load script. Change the format in the examples to suit your requirements.

### Scripting examples

Example	Result
<pre>setdateyearmonth ('29/10/2005', 2013, 3)</pre>	Returns '29/03/2013'
<pre>setdateyearmonth ('29/10/2005 04:26:14', 2013, 3)</pre>	Returns '29/03/2013 04:26:14' To see the time part of the timestamp in a visualization, you must set the number formatting to Date and choose a value for Formatting that displays time values.

### Example:

Add the example script to your app and run it. To see the result, add the fields listed in the results column to a sheet in your app.

```
SetYearMonth:
Load *,
SetDateYearMonth(testdates, 2013,3) as NewYearMonth
Inline [
testdates
1/11/2012
10/12/2012
2/1/2013
19/5/2013
15/9/2013
11/12/2013
14/5/2014
13/6/2014
7/7/2014
4/8/2014
];
```

The resulting table contains the original dates and a column in which the year has been set to 2013.

Results table

testdates	NewYearMonth
1/11/2012	1/3/2013
10/12/2012	10/3/2013
2/1/2012	2/3/2013
19/5/2013	19/3/2013
15/9/2013	15/3/2013
11/12/2013	11/3/2013
14/5/2014	14/3/2013
13/6/2014	13/3/2013

testdates	NewYearMonth
7/7/2014	7/3/2013
4/8/2014	4/3/2013

## timezone

This function returns the time zone, as defined on the computer where the Qlik engine is running.

### Syntax:

```
TimeZone ( )
```

**Return data type:** dual

### Example:

```
timezone( )
```

If you want to see a different timezone in a measure in your app, you can use the `localtime()` function in a measure.

## today

This function returns the current date. The function returns values in the `DateFormat` system variable format.

### Syntax:


```
today ([ timer_mode])
```

**Return data type:** dual

The `today()` function can be used either in the load script or in chart objects.

The default `timer_mode` value is 1.

### Arguments

Argument	Description
timer_mode	<p>Can have the following values:</p> <ul style="list-style-type: none"> <li>0 (day of last finished data load)</li> <li>1 (day of function call)</li> <li>2 (day when the app was opened)</li> </ul> <div style="border: 1px solid gray; padding: 5px; margin-top: 10px;"> <p> If you use the function in a load script, <b>timer_mode=0</b> will result in the day of the last finished data load, while <b>timer_mode=1</b> will give the day of the current data load.</p> </div>

Function examples

<b>timer_ mode value</b>	<b>Result if used in load script</b>	<b>Result if used in chart object</b>
0	Returns a date, in the <code>dateFormat</code> system variable format, of the last successful data reload prior to the latest data reload.	Returns a date, in the <code>dateFormat</code> system variable format, for the latest data reload.
1	Returns a date, in the <code>dateFormat</code> system variable format, for the latest data reload.	Returns a date, in the <code>dateFormat</code> system variable format, of the function call.
2	Returns a date, in the <code>dateFormat</code> system variable format, for when the user's session in the application began. This will not be updated unless the user reloads the script.	Returns the date, in the <code>dateFormat</code> system variable format, for when the user's session in the application began. This will be refreshed once a new session begins or the data in the application is reloaded.

### When to use it

The `today()` function is commonly used as a component within an expression. For example, it can be used to calculate the interest that has accumulated in a month up to the current date.

The following table provides an explanation of the result returned by the `today()` function, given different values for the `timer_mode` argument:

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: `MM/DD/YYYY`. The date format is specified in the `SET dateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Example 1 – Generation of objects using load script

Load script and results

#### Overview

The following example creates three variables using the `today()` function. Each variable uses one of the `timer_mode` options to demonstrate their effect.

For the variables to demonstrate their purpose, reload the script and then, after 24 hours, reload the script a second time. This will result in the `today(0)` and `today(1)` variables showing different values, thereby correctly demonstrating their purpose.

#### Load script

```
LET vPreviousDataLoad = today(0);
LET vCurrentDataLoad = today(1);
LET vApplicationOpened = today(2);
```

#### Results

Once the data has been loaded for a second time, create three textboxes using the directions below.

First, create a textbox for the data which has previously been loaded.

#### Do the following:

1. Using the **Text & Image** chart object, create a textbox.
2. Add the following measure to the object:  
`=vPreviousDataLoad`
3. Under **Appearance**, select **Show titles** and add the title 'Previous Reload Time' to the object.

Next, create a textbox for the data which is currently being loaded.

#### Do the following:

1. Using the **Text & Image** chart object, create a textbox.
2. Add the following measure to the object:  
`=vCurrentDataLoad`
3. Under **Appearance**, select **Show titles** and add the title 'Current Reload Time' to the object.

Create a final textbox to show when the user's session in the application was started.

#### Do the following:

1. Using the **Text & Image** chart object, create a textbox.
2. Add the following measure to the object:

=vApplicationOpened

3. Under **Appearance**, select **Show titles** and add the title 'User Session Started' to the object.

*Diagram of variables created using today() function in load script*

<b>Previous Reload Time</b> 06/22/2022	<b>Current Reload Time</b> 06/23/2022	<b>User Session Began</b> 06/23/2022
---	--	---

The above image shows example values for each of the created variables. For example, the values could be as follows:

- Previous Reload Time: 06/22/2022
- Current Reload Time: 06/23/2022
- User Session Began: 06/23/2022

### Example 2 – Generation of objects without load script

Load script and chart expression

#### Overview

The following example creates three chart objects using the `today()` function. Each chart object uses one of the `timer_mode` options to demonstrate their effect.

There is no load script for this example.

#### Results

Once the data has been loaded for a second time, create three textboxes.

First, create a textbox for the latest data reload.

#### Do the following:

1. Using the **Text & Image** chart object, create a textbox.
2. Add the following measure.  
`=today(0)`
3. Under **Appearance**, select **Show titles** and add the title 'Latest Data Reload' to the object.

Next, create a textbox to show the current time.

### Do the following:

1. Using the **Text & Image** chart object, create a textbox.
2. Add the following measure:  
`=today(1)`
3. Under **Appearance**, select **Show titles** and add the title 'Current Time' to the object.

Create a final textbox to show when the user's session in the application was started.

### Do the following:

1. Using the **Text & Image** chart object, create a textbox.
2. Add the following measure:  
`=today(2)`
3. Under **Appearance**, select **Show titles** and add the title 'User Session Began' to the object.

*Diagram of objects created using today() function without load script*

<b>Latest Data Reload</b> 06/23/2022	<b>Current Time</b> 06/23/2022	<b>User Session Began</b> 06/23/2022
---	-----------------------------------	---

The above image shows example values for each of the created objects. For example, the values could be as follows:

- Latest Data Reload: 06/23/2022
- Current Time: 06/23/2022
- User Session Began: 06/23/2022

The 'Latest Data Reload' chart object uses a `timer_mode` value of 0. This returns the timestamp for the last time the data was successfully reloaded.

The 'Current Time' chart object uses a `timer_mode` value of 1. This returns the current time according to the system clock. If the sheet or object is refreshed, this value will be updated.

The 'User Session Began' chart object uses a `timer_mode` value of 2. This returns the timestamp for when the application was opened, and the user's session began.

### Example 3 – Scenario

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.



The load script contains:

- A dataset containing a set of loan balances, which is loaded into a table called Loans.
- Table data with fields for loan ID, balance at the start of the month, and the simple interest rate charged on each loan per annum.

The end user would like a chart object that displays, by loan ID, the current interest that has been accrued on each loan in the month to date. Although the application is only reloaded once per week, the user would like the results to be refreshed whenever the object or application is refreshed.

### Load script

```
Loans:
Load
*
Inline
[
loan_id,start_balance,rate
8188,$10000.00,0.024
8189,$15000.00,0.057
8190,$17500.00,0.024
8191,$21000.00,0.034
8192,$90000.00,0.084
];
```

### Results

#### Do the following:

1. Load the data and open a sheet. Create a new table.
2. Add the following fields as dimensions.
  - loan\_id
  - start\_balance
3. Next, create a measure to calculate accumulated interest:  
 $=start\_balance*(rate*(today(1)-monthstart(today(1)))/365)$
4. Set the measure's **Number formatting** to **Money**.

Results table

loan_id	start_balance	$=start\_balance*(rate*(today(1)-monthstart(today(1)))/365)$
8188	\$10000.00	\$16.44
8189	\$15000.00	\$58.56
8190	\$17500.00	\$28.77
8191	\$21000.00	\$48.90
8192	\$90000.00	\$517.81

The `monthstart()` function, using the `today()` function to return today's date as its only argument, returns the start date of the current month. By subtracting that result from the current date, again using the `today()` function, the expression returns the number of days that have elapsed so far this month.

This value is then multiplied by the interest rate and divided by 365 to return the effective interest rate incurred for this period. The result is then multiplied by the starting balance of the loan to return the interest that has been accrued so far this month.

Because the value of 1 is used as the `timer_mode` argument in the `today()` functions inside the expression, each time the chart object is refreshed (by opening the application, refreshing the page, moving between sheets etc.), the date returned will be for the current date, and the results will be refreshed accordingly.

### UTC

Returns the current Coordinated Universal Time.

#### Syntax:

```
UTC ( )
```

**Return data type:** dual

#### Example:

```
utc ( )
```

### week

This function returns an integer representing the week number corresponding to the date entered.

#### Syntax:

```
week (timestamp [, first_week_day [, broken_weeks [, reference_day]])
```

**Return data type:** integer

#### Arguments

Argument	Description
<b>timestamp</b>	The date or timestamp to evaluate.
<b>first_week_day</b>	Specifies the day on which the week starts. If omitted, the value of variable <b>FirstWeekDay</b> is used.  The possible values <b>first_week_day</b> are 0 for Monday, 1 for Tuesday, 2 for Wednesday, 3 for Thursday, 4 for Friday, 5 for Saturday, and 6 for Sunday.  For more information about the system variable, see <i>FirstWeekDay (page 228)</i> .

Argument	Description
<b>broken_weeks</b>	If you don't specify <b>broken_weeks</b> , the value of variable <b>BrokenWeeks</b> will be used to define if weeks are broken or not.
<b>reference_day</b>	If you don't specify <b>reference_day</b> , the value of variable <b>ReferenceDay</b> will be used to define which day in January to set as reference day to define week 1. By default, Qlik Sense functions use 4 as the reference day. This means that week 1 must contain January 4, or put differently, that week 1 must always have at least 4 days in January.

The `week()` function determines which week the date falls into and returns the week number.

In Qlik Sense, the regional settings are fetched when the app is created, and the corresponding settings are stored in the script as environment variables. These are used to determine the week number.

This means that most European app developers gets the following environment variables, corresponding to the ISO 8601 definition:

```
Set FirstweekDay =0; // Monday as first week day
Set BrokenWeeks =0; // Use unbroken weeks
Set ReferenceDay =4; // Jan 4th is always in week 1
```

A North American app developer often gets the following environment variables:

```
Set FirstweekDay =6; // Sunday as first week day
Set BrokenWeeks =1; // Use broken weeks
Set ReferenceDay =1; // Jan 1st is always in week 1
```

The first day of the week is determined by the `FirstweekDay` system variable. You can also change the first day of the week by using the `first_week_day` argument in the `week()` function.

If your application uses broken weeks, the week number count begins on January 1 and ends on the day prior to the `FirstweekDay` system variable regardless of how many days have occurred.

If your application is using unbroken weeks, week 1 can begin in the previous year or in the first few days of January. This depends on how you use the `FirstweekDay` and the `ReferenceDay` environment variables.

### When to use it

The `week()` function is useful when you would like to compare aggregations by weeks. For example, it could be used if you would like to see the total sales of products by week. The `week()` function is chosen over `weekname()` when the user would like the calculation to not necessarily use the application's `BrokenWeeks`, `FirstweekDay`, or `ReferenceDay` system variables.

For example, if you want to see the total sales of products by week.

If the application is using unbroken weeks, week 1 may contain dates from December of the previous year or exclude dates in January of the current year. If the application is using broken weeks, week 1 may contain less than seven days..

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET dateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

The examples below assume

```
Set DateFormat= 'MM/DD/YYYY';
Set FirstWeekDay=0;
Set BrokenWeeks=0;
Set ReferenceDay=4;
```

#### Function examples

Example	Result
<code>week('12/28/2021')</code>	Returns 52.
<code>week(44614)</code>	Returns 8, since this is the serial number for 02/22/2022.
<code>week('01/03/2021')</code>	Returns 53.
<code>week('01/03/2021',6)</code>	Returns 1.

### Example 1 – Default system variables

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions for the last week of 2021 and the first two weeks of 2022, which is loaded into a table called `Transactions`.
- The date field provided in the `dateFormat` system variable (MM/DD/YYYY) format.
- The creation of a field, `week_number`, that returns the year and week number when the transactions took place.
- The creation of a field called `week_day`, showing the weekday value of each transaction date.

### Load script

```
SET DateFormat='MM/DD/YYYY';
SET FirstWeekDay=6;
SET BrokenWeeks=1;
SET ReferenceDay=0;
```

Transactions:

```
Load
    *,
    weekDay(date) as week_day,
    week(date) as week_number
;
```

Load

\*

Inline

```
[
id,date,amount
8183,12/27/2021,58.27
8184,12/28/2021,67.42
8185,12/29/2021,23.80
8186,12/30/2021,82.06
8187,12/31/2021,40.56
8188,01/01/2022,37.23
8189,01/02/2022,17.17
8190,01/03/2022,88.27
8191,01/04/2022,57.42
8192,01/05/2022,53.80
8193,01/06/2022,82.06
8194,01/07/2022,40.56
8195,01/08/2022,53.67
8196,01/09/2022,26.63
8197,01/10/2022,72.48
8198,01/11/2022,18.37
8199,01/12/2022,45.26
8200,01/13/2022,58.23
8201,01/14/2022,18.52
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- id
- date
- week\_day
- week\_number

Results table


<b>id</b>	<b>date</b>	<b>week_day</b>	<b>week_number</b>
8183	12/27/2021	Mon	53
8184	12/28/2021	Tue	53
8185	12/29/2021	Wed	53
8186	12/30/2021	Thu	53
8187	12/31/2021	Fri	53
8188	01/01/2022	Sat	1
8189	01/02/2022	Sun	2
8190	01/03/2022	Mon	2
8191	01/04/2022	Tue	2
8192	01/05/2022	Wed	2
8193	01/06/2022	Thu	2
8194	01/07/2022	Fri	2
8195	01/08/2022	Sat	2
8196	01/09/2022	Sun	3
8197	01/10/2022	Mon	3
8198	01/11/2022	Tue	3
8199	01/12/2022	Wed	3
8200	01/13/2022	Thu	3
8201	01/14/2022	Fri	3

The `week_number` field is created in the preceding load statement by using the `week()` function and passing the `date` field as the function's argument.

No other parameters are passed into the function, and therefore the following default variables that affect the `week()` function are in effect:

- `BrokenWeeks`: The week count begins on January 1
- `FirstWeekDay`: The first day of the week is Sunday

Diagram of `week()` function, using default system variables



Because the application is using the default `brokenweeks` system variable, week 1 begins on January 1, a Saturday.

Because of the default `firstweekday` system variable, weeks begin on a Sunday. The first Sunday after January 1 occurs on January 2, which is when week 2 begins.

### Example 2 – `first_week_day`

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The creation of a field, `week_number`, that returns the year and week number when the transactions took place.
- The creation of a field called `week_day`, showing the weekday value of each transaction date.

In this example, we would like to set the start of the work week to Tuesday.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
SET FirstWeekDay=6;
SET BrokenWeeks=1;
SET ReferenceDay=0;
```

Transactions:

```
Load
  *,
  weekDay(date) as week_day,
  week(date,1) as week_number
;
```

Load

\*

Inline

[

```
id,date,amount
8183,12/27/2022,58.27
8184,12/28/2022,67.42
8185,12/29/2022,23.80
8186,12/30/2022,82.06
8187,12/31/2021,40.56
8188,01/01/2022,37.23
8189,01/02/2022,17.17
8190,01/03/2022,88.27
8191,01/04/2022,57.42
8192,01/05/2022,53.80
8193,01/06/2022,82.06
8194,01/07/2022,40.56
8195,01/08/2022,53.67
8196,01/09/2022,26.63
8197,01/10/2022,72.48
8198,01/11/2022,18.37
8199,01/12/2022,45.26
8200,01/13/2022,58.23
8201,01/14/2022,18.52
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- id
- date
- week\_day
- week\_number

Results table


id	date	week_day	week_number
8183	12/27/2021	Mon	52
8184	12/28/2021	Tue	53
8185	12/29/2021	Wed	53
8186	12/30/2021	Thu	53
8187	12/31/2021	Fri	53
8188	01/01/2022	Sat	1
8189	01/02/2022	Sun	1
8190	01/03/2022	Mon	1
8191	01/04/2022	Tue	2
8192	01/05/2022	Wed	2



id	date	week_day	week_number
8193	01/06/2022	Thu	2
8194	01/07/2022	Fri	2
8195	01/08/2022	Sat	2
8196	01/09/2022	Sun	2
8197	01/10/2022	Mon	2
8198	01/11/2022	Tue	3
8199	01/12/2022	Wed	3
8200	01/13/2022	Thu	3
8201	01/14/2022	Fri	3

The application is still using broken weeks. However, the `first_week_day` argument has been set to 1 in the `week()` function. This sets the first day of the week to a Tuesday.

*Diagram of `week()` function, `first_week_day` example*



The application is using the default `brokenweeks` system variable, so week 1 begins on January 1, a Saturday.

The `first_week_day` argument of the `week()` function sets the first week day to a Tuesday. Therefore, week 53 begins on December 28, 2021.

However, because the function is still using broken weeks, week 1 will only be two days long, due to the first Tuesday after January 1 occurring on January 3.

### Example 3 – `unbroken_weeks`

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains the same dataset and scenario as the first example.

In this example, we use unbroken weeks.

### Load script

```
SET DateFormat='MM/DD/YYYY';
SET FirstWeekDay=6;
SET BrokenWeeks=1;
SET ReferenceDay=0;
```

Transactions:

```
Load
    *,
    weekDay(date) as week_day,
    week(date,6,0) as week_number
;
```

Load

\*

Inline

[

id,date,amount

8183,12/27/2022,58.27

8184,12/28/2022,67.42

8185,12/29/2022,23.80

8186,12/30/2022,82.06

8187,12/31/2021,40.56

8188,01/01/2022,37.23

8189,01/02/2022,17.17

8190,01/03/2022,88.27

8191,01/04/2022,57.42

8192,01/05/2022,53.80

8193,01/06/2022,82.06

8194,01/07/2022,40.56

8195,01/08/2022,53.67

8196,01/09/2022,26.63

8197,01/10/2022,72.48

8198,01/11/2022,18.37

8199,01/12/2022,45.26

8200,01/13/2022,58.23

8201,01/14/2022,18.52


];

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- id
- date
- week\_day
- week\_number

Diagram of `week()` function, chart object example




Results table

id	date	week_day	week_number
8183	12/27/2021	Mon	52
8184	12/28/2021	Tue	52
8185	12/29/2021	Wed	52
8186	12/30/2021	Thu	52
8187	12/31/2021	Fri	52
8188	01/01/2022	Sat	52
8189	01/02/2022	Sun	1
8190	01/03/2022	Mon	1
8191	01/04/2022	Tue	1
8192	01/05/2022	Wed	1
8193	01/06/2022	Thu	1
8194	01/07/2022	Fri	1
8195	01/08/2022	Sat	1
8196	01/09/2022	Sun	2
8197	01/10/2022	Mon	2
8198	01/11/2022	Tue	2
8199	01/12/2022	Wed	2
8200	01/13/2022	Thu	2
8201	01/14/2022	Fri	2

The `first_week_date` parameter is set to 1, making Tuesday the first day of the week. The `broken_weeks` parameter is set to 0, forcing the function to use unbroken weeks. Finally, the third parameter sets the `reference_day` to 2.

The `first_week_date` parameter is set to 6, making Sunday the first day of the week. The `broken_weeks` parameter is set to 0, forcing the function to use unbroken weeks.

*Diagram of `week()` function, example using unbroken weeks*



By using unbroken weeks, week 1 does not necessarily begin on January 1; instead, it is required to have a minimum of four days. Therefore, in the dataset, week 52 concludes on Saturday, January 1, 2022. Week 1 then begins on the `FirstWeekDay` system variable, which is Sunday, January 2. This week will conclude on the following Saturday, January 8.

### Example 4 – `reference_day`

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same dataset and scenario as the third example.
- The creation of a field, `week_number`, that returns the year and week number when the transactions took place.
- The creation of a field called `week_day`, showing the weekday value of each transaction date.

Additionally, the following conditions must be met:

- The work week begins on a Tuesday.
- The company uses unbroken weeks.
- The `reference_day` value is 2. In other words, the minimum number of days in January in week 1 will be 2.

#### Load script

```
SET DateFormat='MM/DD/YYYY';  
SET FirstWeekDay=6;  
SET BrokenWeeks=1;  
SET ReferenceDay=0;
```

Transactions:

```
Load
    *,
    weekDay(date) as week_day,
    week(date,1,0,2) as week_number
;

Load
*
Inline
[
id,date,amount
8183,12/27/2022,58.27
8184,12/28/2022,67.42
8185,12/29/2022,23.80
8186,12/30/2022,82.06
8187,12/31/2021,40.56
8188,01/01/2022,37.23
8189,01/02/2022,17.17
8190,01/03/2022,88.27
8191,01/04/2022,57.42
8192,01/05/2022,53.80
8193,01/06/2022,82.06
8194,01/07/2022,40.56
8195,01/08/2022,53.67
8196,01/09/2022,26.63
8197,01/10/2022,72.48
8198,01/11/2022,18.37
8199,01/12/2022,45.26
8200,01/13/2022,58.23
8201,01/14/2022,18.52
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- id
- date
- week\_day
- week\_number


Results table

id	date	week_day	week_number
8183	12/27/2021	Mon	52
8184	12/28/2021	Tue	1
8185	12/29/2021	Wed	1
8186	12/30/2021	Thu	1
8187	12/31/2021	Fri	1

id	date	week_day	week_number
8188	01/01/2022	Sat	1
8189	01/02/2022	Sun	1
8190	01/03/2022	Mon	1
8191	01/04/2022	Tue	2
8192	01/05/2022	Wed	2
8193	01/06/2022	Thu	2
8194	01/07/2022	Fri	2
8195	01/08/2022	Sat	2
8196	01/09/2022	Sun	2
8197	01/10/2022	Mon	2
8198	01/11/2022	Tue	3
8199	01/12/2022	Wed	3
8200	01/13/2022	Thu	3
8201	01/14/2022	Fri	3

The `first_week_date` parameter is set to 1, making Tuesday the first day of the week. The `broken_weeks` parameter is set to 0, forcing the function to use unbroken weeks. Finally, the third parameter sets the `reference_day` parameter to 2.

*Diagram of `week()` function, `reference_day` example*



With the function using unbroken weeks and a `reference_day` value of 2 used as a parameter, week 1 only needs to include two days in January. Due to the first weekday being Tuesday, week 1 begins on December 28, 2021, and concludes on Monday, January 3, 2022.

### Example 5 – Chart object example

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains the same dataset and scenario as the first example.

However, in this example, the unchanged dataset is loaded into the application. The calculation that returns the week number is created as a measure in a chart object.

#### Load script

Transactions:

Load

\*

Inline

[

id,date,amount

8183,12/27/2022,58.27

8184,12/28/2022,67.42

8185,12/29/2022,23.80

8186,12/30/2022,82.06

8187,12/31/2021,40.56

8188,01/01/2022,37.23

8189,01/02/2022,17.17

8190,01/03/2022,88.27

8191,01/04/2022,57.42

8192,01/05/2022,53.80

8193,01/06/2022,82.06

8194,01/07/2022,40.56

8195,01/08/2022,53.67

8196,01/09/2022,26.63

8197,01/10/2022,72.48

8198,01/11/2022,18.37

8199,01/12/2022,45.26

8200,01/13/2022,58.23

8201,01/14/2022,18.52

];

#### Results

#### Do the following:

1. Load the data and open a sheet. Create a new table.
2. Add the following fields as dimensions:
  - id
  - date

3. Next, create the following measure:

=week (date)

4. Create a measure, week\_day, to show the weekday value of each transaction date:

=weekday(date)

Results table

<b>id</b>	<b>date</b>	<b>=week(date)</b>	<b>=weekday(date)</b>
8183	12/27/2021	53	Mon
8184	12/28/2021	53	Tue
8185	12/29/2021	53	Wed
8186	12/30/2021	53	Thu
8187	12/31/2021	53	Fri
8188	01/01/2022	1	Sat
8189	01/02/2022	2	Sun
8190	01/03/2022	2	Mon
8191	01/04/2022	2	Tue
8192	01/05/2022	2	Wed
8193	01/06/2022	2	Thu
8194	01/07/2022	2	Fri
8195	01/08/2022	2	Sat
8196	01/09/2022	3	Sun
8197	01/10/2022	3	Mon
8198	01/11/2022	3	Tue
8199	01/12/2022	3	Wed
8200	01/13/2022	3	Thu
8201	01/14/2022	3	Fri


The week\_number field is created in the preceding load statement by using the week() function and passing the date field as the function's argument.

No other parameters are passed into the function, and therefore the following default variables that affect the week() function are in effect:

- `BrokenWeeks`: The week count begins on January 1
- `FirstWeekDay`: The first day of the week is Sunday



Diagram of `week()` function, chart object example



Because the application is using the default `brokenweeks` system variable, week 1 begins on January 1, a Saturday.

Because of the default `firstweekday` system variable, weeks begin on a Sunday. The first Sunday after January 1 occurs on January 2, which is when week 2 begins.

### Example 6 – Scenario

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions for the last week of 2019 and first two weeks of 2020, which is loaded into a table called `Transactions`.
- The date field provided in the `dateFormat` system variable (MM/DD/YYYY) format.

The application primarily uses broken weeks across its dashboard. However, the end user would like a chart object that presents the total sales by week using unbroken weeks. The reference day should be January 2, with weeks beginning on a Tuesday. This could be achieved even when this dimension is not available in the data model, using the `week()` function as a calculated dimension in the chart.

#### Load script

```
SET BrokenWeeks=1;  
SET ReferenceDay=0;  
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:  
Load  
*  
Inline  
[  
id,date,amount  
8183,12/27/2019,58.27
```

```
8184,12/28/2019,67.42
8185,12/29/2019,23.80
8186,12/30/2019,82.06
8187,12/31/2019,40.56
8188,01/01/2020,37.23
8189,01/02/2020,17.17
8190,01/03/2020,88.27
8191,01/04/2020,57.42
8192,01/05/2020,53.80
8193,01/06/2020,82.06
8194,01/07/2020,40.56
8195,01/08/2020,53.67
8196,01/09/2020,26.63
8197,01/10/2020,72.48
8198,01/11/2020,18.37
8199,01/12/2020,45.26
8200,01/13/2020,58.23
8201,01/14/2020,18.52
];
```

### Results

#### Do the following:

1. Load the data and open a sheet. Create a new table.
2. Create the following calculated dimension:  
=week(date)
3. Next, create the following aggregation measure:  
=sum(amount)
4. Set the measure's **Number formatting** to **Money**.
5. Select the **Sorting** menu, and for the calculated dimension, remove custom sorting.
6. De-select the **Sort numerically** and **Sort alphabetically** options.

Results table

week(date)	sum(amount)
52	\$125.69
53	\$146.42
1	\$200.09
2	\$347.57
3	\$122.01

### weekday

This function returns a dual value with:

- A day name as defined in the environment variable **DayNames**.
- An integer between 0-6 corresponding to the nominal day of the week (0-6).


**Syntax:**

```
weekday(date [, first_week_day=0])
```

**Return data type:** dual

The `weekday()` function determines which day of the week a date occurs on. It then returns a string value representing that day.


*Diagram of `weekday()` function that returns the name of the day a date falls on*



The result returns the number value corresponding to that day of the week (0-6), based on the week's start day. For example, if the first day of the week is set to Sunday, a Wednesday will return a number value of 3. This start day is determined either by the `FIRSTWEEKDAY` system variable or the `first_week_day` function parameter.

You can use this number value as a part of an arithmetic expression. For example, multiply it by 1 to return the value itself.

*Diagram of `weekday()` function with the number value of the day being shown instead of the name of the day*

**When to use it**

The `weekday()` function is useful when you want to compare aggregations by day of the week. For example, if you want to compare the average sales of products by weekday.

These dimensions can be created in the load script by using the function to create a field in a **Master Calendar** table; or created directly in a chart as a calculated measure.

## Related topics

Topics	Interaction
<i>FirstWeekDay (page 228)</i>	Defines the start day of each week.

## Arguments

Argument	Description
<b>date</b>	The date or timestamp to evaluate.
<b>first_week_day</b>	Specifies the day on which the week starts. If omitted, the value of variable <b>FirstWeekDay</b> is used.  <i>FirstWeekDay (page 228)</i>

You can use the following values to set the day on which the week starts in the `first_week_day` argument:

## first\_week\_day values

Day	Value
Monday	0
Tuesday	1
Wednesday	2
Thursday	3
Friday	4
Saturday	5
Sunday	6

## Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.



*Unless stated otherwise, FirstweekDay is set to 0 in these examples.*

### Function examples

Example	Result
<code>weekday('10/12/1971')</code>	Returns 'Tue' and 1.
<code>weekday('10/12/1971' , 6)</code>	Returns 'Tue' and 2.  In this example, Sunday (6) is the first day of the week.
<code>SET FirstWeekDay=6;</code> ... <code>weekday('10/12/1971')</code>	Returns 'Tue' and 2.

### Example 1 - Weekday string

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions for 2022 which is loaded into a table called 'Transactions'.
- The `FirstWeekDay` system variable which is set to 6 (Sunday).
- The `DayNames` variable which is set to use the default day names.
- A preceding load which contains the `weekday()` function, which is set as the 'week\_day' field and returns the weekday the transactions took place.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
SET DayNames='Mon;Tue;Wed;Thu;Fri;Sat;Sun';
SET FirstWeekDay=6;
```

Transactions:

```
Load
*,
WeekDay(date) as week_day
;
```

Load

\*

Inline

```
[
id,date,amount
8188,01/01/2022,37.23
8189,01/02/2022,17.17
8190,01/03/2022,88.27
8191,01/04/2022,57.42
8192,01/05/2022,53.80
```

```
8193,01/06/2022,82.06  
8194,01/07/2022,40.39  
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- id
- date
- week\_day


Results table

id	date	week_day
8188	01/01/2022	Sat
8189	01/02/2022	Sun
8190	01/03/2022	Mon
8191	01/04/2022	Tue
8192	01/05/2022	Wed
8193	01/06/2022	Thu
8194	01/07/2022	Fri

The 'week\_day' field is created in the preceding load statement by using the `weekday()` function and passing the date field as the function's argument.

The `weekday()` function returns the weekday string value; that is, it returns the name of the weekday which is set by the `DayNames` system variable.

*Diagram of `weekday()` function that returns Wednesday as the weekday for transaction 8192*



Transaction 8192 took place on January 5. The `FirstWeekday` system variable sets the first day of the week as Sunday. The `weekday()` function transaction took place on a Wednesday and returns this value, in the abbreviated form of the `DayNames` system variable, in the `week_day` field.

The values in the 'week\_day' field are right aligned in the column because there is a dual number and text result for the field (Wednesday, 3). To convert the field value into its number equivalent, the field can be wrapped inside the num() function. For example, in Transaction 8192, the Wednesday value would be converted into the number 3.

### Example 2 - first\_week\_day

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions for 2022 which is loaded into a table called 'Transactions'.
- The FirstWeekDay system variable which is set to 6 (Sunday).
- The DayNames variable which is set to use the default day names.
- A preceding load which contains the weekday() function, which is set as the 'week\_day' field and returns the weekday the transactions took place.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
SET DayNames='Mon;Tue;Wed;Thu;Fri;Sat;Sun';
SET FirstWeekDay=6;
```

Transactions:

```
Load
  *,
  weekday(date,1) as week_day
;
```

Load

\*

Inline

[

id,date,amount

8188,01/01/2022,37.23

8189,01/02/2022,17.17

8190,01/03/2022,88.27

8191,01/04/2022,57.42

8192,01/05/2022,53.80

8193,01/06/2022,82.06

8194,01/07/2022,40.39

];

#### Results


Load the data and open a sheet. Create a new table and add these fields as dimensions:

- id
- date
- week\_day

Results table

id	date	week_day
8188	01/01/2022	Sat
8189	01/02/2022	Sun
8190	01/03/2022	Mon
8191	01/04/2022	Tue
8192	01/05/2022	Wed
8193	01/06/2022	Thu
8194	01/07/2022	Fri

Diagram of `weekday()` function that shows Wednesday has the dual number value of 1



Because the `first_week_day` argument is set to 1 in the `weekday()` function, the first day of the week is Tuesday. Therefore, all transactions that take place on a Tuesday will have a dual number value of 0.

Transaction 8192 took place on January 5. The `weekday()` function identifies that this is a Wednesday, and so the expression would return the dual number value of 1.

### Example 3 - Chart object example

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions for 2022 which is loaded into a table called 'Transactions'.



- The `FirstWeekDay` system variable which is set to 6 (Sunday).
- The `DayNames` variable which is set to use the default day names.

However, in this example, the dataset is unchanged and loaded into the application. The calculation that identifies the weekday value is created as a measure in a chart in the app.

### Load script

```
SET DateFormat='MM/DD/YYYY';
SET DayNames='Mon;Tue;Wed;Thu;Fri;Sat;Sun';
SET FirstWeekDay=6;
```

Transactions:

```
Load
*
Inline
[
id,date,amount
8188,01/01/2022,37.23
8189,01/02/2022,17.17
8190,01/03/2022,88.27
8191,01/04/2022,57.42
8192,01/05/2022,53.80
8193,01/06/2022,82.06
8194,01/07/2022,40.39
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- `id`
- `date`

To calculate the weekday value, create the following measure:

- `=weekday(date)`

Results table


<b>id</b>	<b>date</b>	<b>=weekday(date)</b>
8188	01/01/2022	Sat
8189	01/02/2022	Sun
8190	01/03/2022	Mon
8191	01/04/2022	Tue
8192	01/05/2022	Wed
8193	01/06/2022	Thu
8194	01/07/2022	Fri

## 8 Script and chart functions

The '=weekday(date)' field is created in the chart by using the weekday() function and passing the date field as the function's argument.

The weekday() function returns the weekday string value; that is, it returns the name of the weekday which is set by the DayNames system variable.

*Diagram of weekday() function that returns Wednesday as the weekday for transaction 8192*



Transaction 8192 took place on January 5. The FirstWeekDay system variable sets the first day of the week as Sunday. The weekday() function transaction took place on a Wednesday and returns this value, in the abbreviated form of the DayNames system variable, in the =weekday(date) field.

### Example 4 - Scenario

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions for 2022 which is loaded into a table called 'Transactions'.
- The FirstWeekDay system variable which is set to 6 (Sunday).
- The DayNames variable which is set to use the default day names.

The end user would like a chart that presents the average sales by weekday for the transactions.

#### Load script

```
SET DateFormat='MM/DD/YYYY';  
SET DayNames='Mon;Tue;Wed;Thu;Fri;Sat;Sun';  
SET FirstWeekDay=6;
```

Transactions:

```
LOAD  
  RecNo() AS id,  
  MakeDate(2022, 1, Ceil(Rand() * 31)) as date,  
  Rand() * 1000 AS amount
```

```
Autogenerate(1000);
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- =weekday(date)
- =avg(amount)

Set the measure's **Number Formatting** to **Money**.

Results table

weekday(date)	Avg(amount)
Sun	\$536.96
Mon	\$500.80
Tue	\$515.63
Wed	\$509.21
Thu	\$482.70
Fri	\$441.33
Sat	\$505.22

### weekend

This function returns a value corresponding to a timestamp of the last millisecond of the last day of the calendar week containing **date**. The default output format will be the **DateFormat** set in the script.

#### Syntax:

```
WeekEnd(timestamp [, period_no [, first_week_day ]])
```

**Return data type:** dual

The `weekend()` function determines which week the date falls into. It then returns a timestamp, in date format, for the last millisecond of that week. The first day of the week is determined by the `FirstWeekDay` environment variable. However, this can be superseded by the `first_week_day` argument in the `weekend()` function.

Arguments

Argument	Description
<b>timestamp</b>	The date or timestamp to evaluate.
<b>period_no</b>	<b>shift</b> is an integer, where the value 0 indicates the week which contains <b>date</b> . Negative values in <b>shift</b> indicate preceding weeks and positive values indicate succeeding weeks.

Argument	Description
<b>first_week_day</b>	<p>Specifies the day on which the week starts. If omitted, the value of variable <b>FirstWeekDay</b> is used.</p> <p>The possible values for <b>first_week_day</b> are 0 for Monday, 1 for Tuesday, 2 for Wednesday, 3 for Thursday, 4 for Friday, 5 for Saturday, and 6 for Sunday.</p> <p>For more information about the system variable, see <i>FirstWeekDay (page 228)</i></p>

### When to use it

The `weekend()` function is commonly used as part of an expression when the user would like the calculation to use remaining days of the week for the specified date. For example, it could be used if a user would like to calculate the total interest not yet incurred during the week.

The following examples assume:

```
SET FirstWeekDay=0;
```

Example	Result
<code>weekend('01/10/2013')</code>	Returns 01/12/2013 23:59:59.
<code>weekend('01/10/2013', -1)</code>	Returns 01/05/2013 23:59:59..
<code>weekend('01/10/2013', 0, 1)</code>	Returns 01/14/2013 23:59:59.

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

#### Examples:

If you want ISO settings for weeks and week numbers, make sure to have the following in the script:

```
Set DateFormat = 'YYYY-MM-DD';
Set FirstWeekDay =0; // Monday as first week day
Set BrokenWeeks =0; //(use unbroken weeks)
Set ReferenceDay =4; // Jan 4th is always in week 1
```

If you want US settings, make sure to have the following in the script:

```
Set DateFormat = 'M/D/YYYY';  
Set FirstWeekDay =6; // Sunday as first week day  
Set BrokenWeeks =1; //(use broken weeks)  
Set ReferenceDay =1; // Jan 1st is always in week 1
```

The examples above results in the following from the weekend() function:

Example of Weekend function

Date	ISO week end	US week end
Sat 2020 Dec 26	2020-12-27	12/26/2020
Sun 2020 Dec 27	2020-12-27	1/2/2021
Mon 2020 Dec 28	2021-01-03	1/2/2021
Tue 2020 Dec 29	2021-01-03	1/2/2021
Wed 2020 Dec 30	2021-01-03	1/2/2021
Thu 2020 Dec 31	2021-01-03	1/2/2021
Fri 2021 Jan 1	2021-01-03	1/2/2021
Sat 2021 Jan 2	2021-01-03	1/2/2021
Sun 2021 Jan 3	2021-01-03	1/9/2021
Mon 2021 Jan 4	2021-01-10	1/9/2021
Tue 2021 Jan 5	2021-01-10	1/9/2021



*The week ends are on Sundays in the ISO column, and on Saturdays in the US column.*

### Example 1 – Basic example

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions for 2022, which is loaded into a table called Transactions.
- The date field provided in the DateFormat system variable (MM/DD/YYYY) format.
- The creation of a field, end\_of\_week, that returns a timestamp for the end of the week when the transactions took place.

#### Load script

```
SET FirstWeekDay=6;
```

Transactions:

```
Load
    *,
    weekend(date) as end_of_week,
    timestamp(weekend(date)) as end_of_week_timestamp
;

Load
*
Inline
[
id,date,amount
8188,1/7/2022,17.17
8189,1/19/2022,37.23
8190,2/28/2022,88.27
8191,2/5/2022,57.42
8192,3/16/2022,53.80
8193,4/1/2022,82.06
8194,5/7/2022,40.39
8195,5/16/2022,87.21
8196,6/15/2022,95.93
8197,6/26/2022,45.89
8198,7/9/2022,36.23
8199,7/22/2022,25.66
8200,7/23/2022,82.77
8201,7/27/2022,69.98
8202,8/2/2022,76.11
8203,8/8/2022,25.12
8204,8/19/2022,46.23
8205,9/26/2022,84.21
8206,10/14/2022,96.24
8207,10/29/2022,67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- end\_of\_week
- end\_of\_week\_timestamp

Results table

date	end_of_week	end_of_week_timestamp
1/7/2022	01/08/2022	1/8/2022 11:59:59 PM
1/19/2022	01/22/2022	1/22/2022 11:59:59 PM
2/5/2022	02/05/2022	2/5/2022 11:59:59 PM
2/28/2022	03/05/2022	3/5/2022 11:59:59 PM
3/16/2022	03/19/2022	3/19/2022 11:59:59 PM


## 8 Script and chart functions

date	end_of_week	end_of_week_timestamp
4/1/2022	04/02/2022	4/2/2022 11:59:59 PM
5/7/2022	05/07/2022	5/7/2022 11:59:59 PM
5/16/2022	05/21/2022	5/21/2022 11:59:59 PM
6/15/2022	06/18/2022	6/18/2022 11:59:59 PM
6/26/2022	07/02/2022	7/2/2022 11:59:59 PM
7/9/2022	07/09/2022	7/9/2022 11:59:59 PM
7/22/2022	07/23/2022	7/23/2022 11:59:59 PM
7/23/2022	07/23/2022	7/23/2022 11:59:59 PM
7/27/2022	07/30/2022	7/30/2022 11:59:59 PM
8/2/2022	08/06/2022	8/6/2022 11:59:59 PM
8/8/2022	08/13/2022	8/13/2022 11:59:59 PM
8/19/2022	08/20/2022	8/20/2022 11:59:59 PM
9/26/2022	10/01/2022	10/1/2022 11:59:59 PM
10/14/2022	10/15/2022	10/15/2022 11:59:59 PM
10/29/2022	10/29/2022	10/29/2022 11:59:59 PM

The `end_of_week` field is created in the preceding load statement by using the `weekend()` function and passing the `date` field as the function's argument.

The `weekend()` function identifies which week the date value falls into and returns a timestamp for the last millisecond of that week.

*Diagram of `weekend()` function, basic example*



Transaction 8191 took place on February 5. The `Firstweekday` system variable sets the first day of the week to a Sunday. The `weekend()` function identifies that the first Saturday after February 5– and therefore the end of the week – was on February 5. Therefore, the `end_of_week` value for that transaction returns the last millisecond of that day, which is February 5 at 11:59:59 PM.

### Example 2 – period\_no

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same dataset and scenario as the first example.
- The creation of a field, `previous_week_end`, that returns the timestamp for the start of the week before the transaction took place.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
    Load
        *,
        weekend(date,-1) as previous_week_end,
        timestamp(weekend(date,-1)) as previous_week_end_timestamp
    ;

Load
*
Inline
[
id,date,amount
8188,1/7/2022,17.17
8189,1/19/2022,37.23
8190,2/28/2022,88.27
8191,2/5/2022,57.42
8192,3/16/2022,53.80
8193,4/1/2022,82.06
8194,5/7/2022,40.39
8195,5/16/2022,87.21
8196,6/15/2022,95.93
8197,6/26/2022,45.89
8198,7/9/2022,36.23
8199,7/22/2022,25.66
8200,7/23/2022,82.77
8201,7/27/2022,69.98
8202,8/2/2022,76.11
8203,8/8/2022,25.12
8204,8/19/2022,46.23
8205,9/26/2022,84.21
8206,10/14/2022,96.24
8207,10/29/2022,67.67
];
```



### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:


- date
- previous\_week\_end
- previous\_week\_end\_timestamp

Results table

<b>date</b>	<b>end_of_week</b>	<b>end_of_week_timestamp</b>
1/7/2022	01/01/2022	1/1/2022 11:59:59 PM
1/19/2022	01/15/2022	1/15/2022 11:59:59 PM
2/5/2022	01/29/2022	1/29/2022 11:59:59 PM
2/28/2022	02/26/2022	2/26/2022 11:59:59 PM
3/16/2022	03/12/2022	3/12/2022 11:59:59 PM
4/1/2022	03/26/2022	3/26/2022 11:59:59 PM
5/7/2022	04/30/2022	4/30/2022 11:59:59 PM
5/16/2022	05/14/2022	5/14/2022 11:59:59 PM
6/15/2022	06/11/2022	6/11/2022 11:59:59 PM
6/26/2022	06/25/2022	6/25/2022 11:59:59 PM
7/9/2022	07/02/2022	7/2/2022 11:59:59 PM
7/22/2022	07/16/2022	7/16/2022 11:59:59 PM
7/23/2022	07/16/2022	7/16/2022 11:59:59 PM
7/27/2022	07/23/2022	7/23/2022 11:59:59 PM
8/2/2022	07/30/2022	7/30/2022 11:59:59 PM
8/8/2022	08/06/2022	8/6/2022 11:59:59 PM
8/19/2022	08/13/2022	8/13/2022 11:59:59 PM
9/26/2022	09/24/2022	9/24/2022 11:59:59 PM
10/14/2022	10/08/2022	10/8/2022 11:59:59 PM
10/29/2022	10/22/2022	10/22/2022 11:59:59 PM

In this instance, because a `period_no` of `-1` was used as the offset argument in the `weekend()` function, the function first identifies the week in which the transactions take place. It then looks one week prior and identifies the last millisecond of that week.

Diagram of `weekend()` function, `period_no` example



Transaction 8196 took place on June 15. The `weekend()` function identifies that the week begins on June 12. Therefore, the previous week ends on June 11 at 11:59:59 PM; this is the value returned for the `previous_week_end` field.

### Example 3 – `first_week_day`

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains the same dataset and scenario as the first example. However, in this example, we need to set Tuesday as the first day of the work week.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

Transactions:

```
Load
    *,
    weekend(date,0,1) as end_of_week,
    timestamp(weekend(date,0,1)) as end_of_week_timestamp,
    ;
Load
*
Inline
[
id,date,amount
8188,1/7/2022,17.17
8189,1/19/2022,37.23
8190,2/28/2022,88.27
8191,2/5/2022,57.42
8192,3/16/2022,53.80
8193,4/1/2022,82.06
8194,5/7/2022,40.39
8195,5/16/2022,87.21
8196,6/15/2022,95.93
8197,6/26/2022,45.89
8198,7/9/2022,36.23
8199,7/22/2022,25.66
8200,7/23/2022,82.77
```

```
8201,7/27/2022,69.98
8202,8/2/2022,76.11
8203,8/8/2022,25.12
8204,8/19/2022,46.23
8205,9/26/2022,84.21
8206,10/14/2022,96.24
8207,10/29/2022,67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- end\_of\_week
- end\_of\_week\_timestamp

Results table

<b>date</b>	<b>end_of_week</b>	<b>end_of_week_timestamp</b>
1/7/2022	01/10/2022	1/10/2022 11:59:59 PM
1/19/2022	01/24/2022	1/24/2022 11:59:59 PM
2/5/2022	02/07/2022	2/7/2022 11:59:59 PM
2/28/2022	02/28/2022	2/28/2022 11:59:59 PM
3/16/2022	03/21/2022	3/21/2022 11:59:59 PM
4/1/2022	04/04/2022	4/4/2022 11:59:59 PM
5/7/2022	05/09/2022	5/9/2022 11:59:59 PM
5/16/2022	05/16/2022	5/16/2022 11:59:59 PM
6/15/2022	06/20/2022	6/20/2022 11:59:59 PM
6/26/2022	06/27/2022	6/27/2022 11:59:59 PM
7/9/2022	07/11/2022	7/11/2022 11:59:59 PM
7/22/2022	07/25/2022	7/25/2022 11:59:59 PM
7/23/2022	07/25/2022	7/25/2022 11:59:59 PM
7/27/2022	08/01/2022	8/1/2022 11:59:59 PM
8/2/2022	08/08/2022	8/8/2022 11:59:59 PM
8/8/2022	08/08/2022	8/8/2022 11:59:59 PM
8/19/2022	08/22/2022	8/22/2022 11:59:59 PM
9/26/2022	09/26/2022	9/26/2022 11:59:59 PM
10/14/2022	10/17/2022	10/17/2022 11:59:59 PM
10/29/2022	10/31/2022	10/31/2022 11:59:59 PM

In this instance, because the `first_week_date` argument of 1 is used in the `weekend()` function, it sets the first day of the week to Tuesday.

*Diagram of `weekend()` function, `first_week_day` example*



Transaction 8191 took place on February 5. The `weekend()` function identifies that the first Monday after this date – and therefore the end of the week and value returned – was on February 6 at 11:59:59 PM.

### Example 4 – Chart object example

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains the same dataset and scenario as the first example. However, in this example, the unchanged dataset is loaded into the application. The calculation that returns a timestamp for the end of the week when the transactions took place is created as a measure in a chart object of the application.

#### Load script

```
Transactions:
Load
*
Inline
[
id,date,amount
8188,1/7/2022,17.17
8189,1/19/2022,37.23
8190,2/28/2022,88.27
8191,2/5/2022,57.42
8192,3/16/2022,53.80
8193,4/1/2022,82.06
8194,5/7/2022,40.39
8195,5/16/2022,87.21
8196,6/15/2022,95.93
8197,6/26/2022,45.89
8198,7/9/2022,36.23
8199,7/22/2022,25.66
8200,7/23/2022,82.77
8201,7/27/2022,69.98
8202,8/2/2022,76.11
```

```
8203, 8/8/2022, 25.12
8204, 8/19/2022, 46.23
8205, 9/26/2022, 84.21
8206, 10/14/2022, 96.24
8207, 10/29/2022, 67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension: date.

To calculate the start of the week that a transaction takes place in, add the following measures:

- =weekend(date)
- =timestamp(weekend(date))

Results table

date	=weekend(date)	=timestamp(weekend(date))
1/7/2022	01/08/2022	1/8/2022 11:59:59 PM
1/19/2022	01/22/2022	1/22/2022 11:59:59 PM
2/5/2022	02/05/2022	2/5/2022 11:59:59 PM
2/28/2022	03/05/2022	3/5/2022 11:59:59 PM
3/16/2022	03/19/2022	3/19/2022 11:59:59 PM
4/1/2022	04/02/2022	4/2/2022 11:59:59 PM
5/7/2022	05/07/2022	5/7/2022 11:59:59 PM
5/16/2022	05/21/2022	5/21/2022 11:59:59 PM
6/15/2022	06/18/2022	6/18/2022 11:59:59 PM
6/26/2022	07/02/2022	7/2/2022 11:59:59 PM
7/9/2022	07/09/2022	7/9/2022 11:59:59 PM
7/22/2022	07/23/2022	7/23/2022 11:59:59 PM
7/23/2022	07/23/2022	7/23/2022 11:59:59 PM
7/27/2022	07/30/2022	7/30/2022 11:59:59 PM
8/2/2022	08/06/2022	8/6/2022 11:59:59 PM
8/8/2022	08/13/2022	8/13/2022 11:59:59 PM
8/19/2022	08/20/2022	8/20/2022 11:59:59 PM
9/26/2022	10/01/2022	10/1/2022 11:59:59 PM
10/14/2022	10/15/2022	10/15/2022 11:59:59 PM
10/29/2022	10/29/2022	10/29/2022 11:59:59 PM

The `end_of_week` measure is created in the chart object by using the `weekend()` function and passing the date field as the function's argument. The `weekend()` function identifies which week the date value falls into, returning a timestamp for the last millisecond of that week.

*Diagram of `weekend()` function, chart object example*



Transaction 8191 took place on February 5. The `FirstWeekDay` system variable sets the first day of the week to a Sunday. The `weekend()` function identifies that the first Saturday after February 5 – and therefore the end of the week – was on February 5. Therefore, the `end_of_week` value for that transaction returns the last millisecond of that day, which is February 5 at 11:59:59 PM.

### Example 5 – Scenario

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset which is loaded into a table called `Employee_Expenses`.
- Data consisting of employee IDs, employee names, and the average daily expense claims of each employee.

The end user would like a chart object that displays, by employee ID and employee name, the estimated expense claims still to be incurred for the remainder of the week.

#### Load script

```
Employee_Expenses :
Load
*
Inline
[
employee_id,employee_name,avg_daily_claim
182,Mark, $15
183,Deryck, $12.5
184,Dexter, $12.5
185,Sydney,$27
186,Agatha,$18
];
```

### Results

#### Do the following:

1. Load the data and open a sheet. Create a new table and add these fields as dimensions:
  - employee\_id
  - employee\_name
2. Next, create a measure to calculate the accumulated interest:  
`=(weekend(today(1))-today(1))*avg_daily_claim`
3. Set the measure's **Number formatting** to **Money**.

Results table

employee_id	employee_name	=(weekend(today(1))-today(1))*avg_daily_claim
182	Mark	\$90.00
183	Deryck	\$75.00
184	Dexter	\$75.00
185	Sydney	\$162.00
186	Agatha	\$108.00

The `weekend()` function, by using today's date as its only argument, returns the end date of the current week. Then, by subtracting today's date from the week end date, the expression returns the number of days that remain this week.

This value is then multiplied by the average daily expense claim by each employee to calculate the estimated value of claims that each employee is expected to make in the remaining week.

### weekname

This function returns a value showing the year and week number with an underlying numeric value corresponding to a timestamp of the first millisecond of the first day of the week containing **date**.

#### Syntax:

```
WeekName (date[, period_no [, first_week_day [, broken_weeks [, reference_day]]]])
```

The `weekname()` function determines which week the date falls into and returns the week number and year of that week. The first day of the week is determined by the `FirstWeekDay` system variable. However, you can also change the first day of the week by using the `first_week_day` argument in the `weekname()` function.

In Qlik Sense, the regional settings are fetched when the app is created, and the corresponding settings are stored in the script as environment variables.

## 8 Script and chart functions

---

A North American app developer often gets set `brokenweeks=1`; in the script, corresponding to broken weeks. A European app developer often gets set `brokenweeks=0`; in the script, corresponding to unbroken weeks.

If your application uses broken weeks, the week number count begins on the January 1 and ends on the day prior to the `Firstweekday` system variable regardless of how many days have occurred.

However, if your application is using unbroken weeks, week 1 can begin in the previous year or in the first few days in January. This depends on how you use the `ReferenceDay` and `Firstweekday` system variables.

Example of Weekname function

Date	ISO week name	US week name
Sat 2020 Dec 26	2020/52	2020/52
Sun 2020 Dec 27	2020/52	2020/53
Mon 2020 Dec 28	2020/53	2020/53
Tue 2020 Dec 29	2020/53	2020/53
Wed 2020 Dec 30	2020/53	2020/53
Thu 2020 Dec 31	2020/53	2020/53
Fri 2021 Jan 1	2020/53	2021/01
Sat 2021 Jan 2	2020/53	2021/01
Sun 2021 Jan 3	2020/53	2021/02
Mon 2021 Jan 4	2021/01	2021/02
Tue 2021 Jan 5	2021/01	2021/02

### When to use it

The `weekname()` function is useful for when you would like to compare aggregations by weeks.

For example, if you want to see the total sales of products by week. To maintain consistency with the `brokenweeks` environment variable in the application, use `weekname()` instead of `lunarweekname()`. If the application is using unbroken weeks, week 1 may contain dates from December of the previous year or exclude dates in January of the current year. If the application is using broken weeks, week 1 may contain less than seven days.

**Return data type:** dual

### Arguments

Argument	Description
<code>timestamp</code>	The date or timestamp to evaluate.



Argument	Description
<b>period_no</b>	<b>shift</b> is an integer, where the value 0 indicates the week which contains <b>date</b> . Negative values in <b>shift</b> indicate preceding weeks and positive values indicate succeeding weeks.
<b>first_week_day</b>	Specifies the day on which the week starts. If omitted, the value of variable <b>FirstWeekDay</b> is used.  The possible values <b>first_week_day</b> are 0 for Monday, 1 for Tuesday, 2 for Wednesday, 3 for Thursday, 4 for Friday, 5 for Saturday, and 6 for Sunday.  For more information about the system variable, see <i>FirstWeekDay</i> (page 228).
<b>broken_weeks</b>	If you don't specify <b>broken_weeks</b> , the value of variable <b>BrokenWeeks</b> will be used to define if weeks are broken or not.
<b>reference_day</b>	If you don't specify <b>reference_day</b> , the value of variable <b>ReferenceDay</b> will be used to define which day in January to set as reference day to define week 1. By default, Qlik Sense functions use 4 as the reference day. This means that week 1 must contain January 4, or put differently, that week 1 must always have at least 4 days in January.

## Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET dateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

The examples below assume:

```
Set FirstWeekDay=0;
Set BrokenWeeks=0;
Set ReferenceDay=4;
```

### Function examples

Example	Result
<code>weekname('01/12/2013')</code>	Returns 2013/02.
<code>weekname('01/12/2013', -1)</code>	Returns 2013/01.
<code>weekname('01/12/2013', 0, 1)</code>	Returns 2013/02.

### Example 1 – Date with no additional arguments

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions for the last week of 2021 and first two weeks of 2022 is loaded into a table called 'Transactions'.
- The `DateFormat` system variable which is set to the `MM/DD/YYYY` format.
- The `BrokenWeeks` system variable which is set to 1.
- The `FirstWeekDay` system variable which is set to 6.
- A preceding load which contains the following:
  - The `weekday()` function which is set as the field 'week\_number', that returns the year and week number when the transactions took place.
  - The `weekname()` function which is set as the field called 'week\_day', to show the weekday value of each transaction date.

#### Load script

```
SET BrokenWeeks=1;
SET DateFormat='MM/DD/YYYY';
SET FirstWeekDay=6;

Transactions:
  Load
    *,
    weekday(date) as week_day,
    weekname(date) as week_number
  ;
Load
*
Inline
[
id,date,amount
8183,12/27/2021,58.27
8184,12/28/2021,67.42
8185,12/29/2021,23.80
8186,12/30/2021,82.06
8187,12/31/2021,40.56
8188,01/01/2022,37.23
8189,01/02/2022,17.17
8190,01/03/2022,88.27
8191,01/04/2022,57.42
8192,01/05/2022,53.80
8193,01/06/2022,82.06
8194,01/07/2022,40.56
8195,01/08/2022,53.67
```

```
8196,01/09/2022,26.63
8197,01/10/2022,72.48
8198,01/11/2022,18.37
8199,01/12/2022,45.26
8200,01/13/2022,58.23
8201,01/14/2022,18.52
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- id
- date
- week\_day
- week\_number

Results table

id	date	week_day	week_number
8183	12/27/2021	Mon	2021/53
8184	12/28/2021	Tue	2021/53
8185	12/29/2021	Wed	2021/53
8186	12/30/2021	Thu	2021/53
8187	12/31/2021	Fri	2021/53
8188	01/01/2022	Sat	2022/01
8189	01/02/2022	Sun	2022/02
8190	01/03/2022	Mon	2022/02
8191	01/04/2022	Tue	2022/02
8192	01/05/2022	Wed	2022/02
8193	01/06/2022	Thu	2022/02
8194	01/07/2022	Fri	2022/02
8195	01/08/2022	Sat	2022/02
8196	01/09/2022	Sun	2022/03
8197	01/10/2022	Mon	2022/03
8198	01/11/2022	Tue	2022/03
8199	01/12/2022	Wed	2022/03
8200	01/13/2022	Thu	2022/03
8201	01/14/2022	Fri	2022/03


## 8 Script and chart functions

The 'week\_number' field is created in the preceding load statement by using the `weekname()` function and passing the date field as the function's argument.

The `weekname()` function initially identifies which week the date value falls into and returns the week number count and the year the transaction takes place.

The `Firstweekday` system variable sets Sunday as the first day of the week. The `brokenweeks` system variable sets the application to use broken weeks, meaning that week 1 will begin on January 1.

*Diagram of `weekname()` function with the default variables.*



Week 1 begins on January 1, which is a Saturday, and therefore transactions occurring on this date return the value 2022/01 (the year and week number).

*Diagram of `weekname()` function identifying the week number of transaction 8192.*



Because the application is using broken weeks and the first weekday is Sunday, transactions occurring from January 2 to January 8 return the value 2022/02 (week number 2 in 2022.) An example of this would be transaction 8192 which took place on January 5 and returns the value 2022/02 for the 'week\_number' field.

### Example 2 – period\_no

Load script and results

#### Overview

The same dataset and scenario as the first example are used.

However, in this example, the task is to create a field, 'previous\_week\_number', that returns the year, and week number, prior to when the transactions took place.

Open the Data load editor and add the following load script to a new tab.

### Load script

```
SET BrokenWeeks=1;
SET FirstWeekDay=6;

Transactions:
  Load
    *,
    weekname(date,-1) as previous_week_number
  ;
Load
*
Inline
[
id,date,amount
8183,12/27/2021,58.27
8184,12/28/2021,67.42
8185,12/29/2021,23.80
8186,12/30/2021,82.06
8187,12/31/2021,40.56
8188,01/01/2022,37.23
8189,01/02/2022,17.17
8190,01/03/2022,88.27
8191,01/04/2022,57.42
8192,01/05/2022,53.80
8193,01/06/2022,82.06
8194,01/07/2022,40.56
8195,01/08/2022,53.67
8196,01/09/2022,26.63
8197,01/10/2022,72.48
8198,01/11/2022,18.37
8199,01/12/2022,45.26
8200,01/13/2022,58.23
8201,01/14/2022,18.52
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- id
- date
- week\_day
- week\_number


Results table

id	date	week_day	week_number
8183	12/27/2021	Mon	2021/52
8184	12/28/2021	Tue	2021/52

id	date	week_day	week_number
8185	12/29/2021	Wed	2021/52
8186	12/30/2021	Thu	2021/52
8187	12/31/2021	Fri	2021/52
8188	01/01/2022	Sat	2021/52
8189	01/02/2022	Sun	2021/53
8190	01/03/2022	Mon	2021/53
8191	01/04/2022	Tue	2021/53
8192	01/05/2022	Wed	2021/53
8193	01/06/2022	Thu	2021/53
8194	01/07/2022	Fri	2021/53
8195	01/08/2022	Sat	2022/01
8196	01/09/2022	Sun	2022/02
8197	01/10/2022	Mon	2022/02
8198	01/11/2022	Tue	2022/02
8199	01/12/2022	Wed	2022/02
8200	01/13/2022	Thu	2022/02
8201	01/14/2022	Fri	2022/02

Because a `period_no` of `-1` is used as the offset argument in the `weekname()` function, the function first identifies the week that the transactions take place in. It then looks one week prior and identifies the first millisecond of that week.

*Diagram of `weekname()` function with a `period_no` offset of `-1`.*



Transaction 8192 took place on January 5, 2022. The `weekname()` function looks one week prior, December 30, 2021, and returns the week number and year for that date – 2021/53.

### Example 3 – first\_week\_day

Load script and results

#### Overview

The same dataset and scenario as the first example are used.

However, in this example, the company policy is for the work week to begin on Tuesday.

Open the Data load editor and add the following load script to a new tab.

#### Load script

```
SET BrokenWeeks=1;
SET DateFormat='MM/DD/YYYY';

Transactions:
  Load
    *,
    weekday(date) as week_day,
    weekname(date,0,1) as week_number
  ;
Load
*
Inline
[
id,date,amount
8183,12/27/2021,58.27
8184,12/28/2021,67.42
8185,12/29/2021,23.80
8186,12/30/2021,82.06
8187,12/31/2021,40.56
8188,01/01/2022,37.23
8189,01/02/2022,17.17
8190,01/03/2022,88.27
8191,01/04/2022,57.42
8192,01/05/2022,53.80
8193,01/06/2022,82.06
8194,01/07/2022,40.56
8195,01/08/2022,53.67
8196,01/09/2022,26.63
8197,01/10/2022,72.48
8198,01/11/2022,18.37
8199,01/12/2022,45.26
8200,01/13/2022,58.23
8201,01/14/2022,18.52
];
```

#### Results


Load the data and open a sheet. Create a new table and add these fields as dimensions:

- id
- date
- week\_day
- week\_number

Results table

id	date	week_day	week_number
8183	12/27/2021	Mon	2021/52
8184	12/28/2021	Tue	2021/53
8185	12/29/2021	Wed	2021/53
8186	12/30/2021	Thu	2021/53
8187	12/31/2021	Fri	2021/53
8188	01/01/2022	Sat	2022/01
8189	01/02/2022	Sun	2022/01
8190	01/03/2022	Mon	2022/01
8191	01/04/2022	Tue	2022/02
8192	01/05/2022	Wed	2022/02
8193	01/06/2022	Thu	2022/02
8194	01/07/2022	Fri	2022/02
8195	01/08/2022	Sat	2022/02
8196	01/09/2022	Sun	2022/02
8197	01/10/2022	Mon	2022/02
8198	01/11/2022	Tue	2022/03
8199	01/12/2022	Wed	2022/03
8200	01/13/2022	Thu	2022/03
8201	01/14/2022	Fri	2022/03


Diagram of `weekname()` function with Tuesday as the first day of the week.





Because the `first_week_date` argument of 1 is used in the `weekname()` function, it uses Tuesday as the first day of the week. The function therefore determines that week 53 of 2021 begins on Tuesday December 28; and, due to the application using broken weeks, week 1 begins on January 1, 2022, and ends on the last millisecond of Monday January 3, 2022.

*Diagram showing week number of transaction 8192 with Tuesday as the first day of week.*



Transaction 8192 took place on January 5, 2022. Therefore, using a `first_week_day` parameter of Tuesday, the `weekname()` function returns the value 2022/02 for the 'week\_number' field.

### Example 4 – Chart object example

Load script and chart expression

#### Overview

The same dataset and scenario as the first example are used.

However, in this example, the dataset is unchanged and loaded into the application. The calculation that returns the year number of the week for when the transactions took place is created as a measure in a chart object of the application.

#### Load script

```
SET BrokenWeeks=1;
Transactions:
Load
*
Inline
[
id,date,amount
8183,12/27/2021,58.27
8184,12/28/2021,67.42
8185,12/29/2021,23.80
8186,12/30/2021,82.06
8187,12/31/2021,40.56
8188,01/01/2022,37.23
8189,01/02/2022,17.17
8190,01/03/2022,88.27
8191,01/04/2022,57.42
8192,01/05/2022,53.80
8193,01/06/2022,82.06
8194,01/07/2022,40.56
```

```
8195,01/08/2022,53.67
8196,01/09/2022,26.63
8197,01/10/2022,72.48
8198,01/11/2022,18.37
8199,01/12/2022,45.26
8200,01/13/2022,58.23
8201,01/14/2022,18.52
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- id
- date
- =week\_day (date)

To calculate the start of the week that a transaction takes place in, create the following measure:

```
=weekname(date)
```

Results table

id	date	=weekday(date)	=weekname(date)
8183	12/27/2021	Mon	2021/53
8184	12/28/2021	Tue	2021/53
8185	12/29/2021	Wed	2021/53
8186	12/30/2021	Thu	2021/53
8187	12/31/2021	Fri	2021/53
8188	01/01/2022	Sat	2022/01
8189	01/02/2022	Sun	2022/02
8190	01/03/2022	Mon	2022/02
8191	01/04/2022	Tue	2022/02
8192	01/05/2022	Wed	2022/02
8193	01/06/2022	Thu	2022/02
8194	01/07/2022	Fri	2022/02
8195	01/08/2022	Sat	2022/02
8196	01/09/2022	Sun	2022/03
8197	01/10/2022	Mon	2022/03
8198	01/11/2022	Tue	2022/03
8199	01/12/2022	Wed	2022/03

## 8 Script and chart functions


id	date	=weekday(date)	=weekname(date)
8200	01/13/2022	Thu	2022/03
8201	01/14/2022	Fri	2022/03

The 'week\_number' field is created as a measure in the chart object by using the weekname() function and passing the date field as the function's argument.


The weekname() function initially identifies which week the date value falls into and returns the week number count and the year that the transaction takes place.

The Firstweekday system variable sets Sunday as the first day of the week. The brokenweeks system variable sets the application to use broken weeks, meaning that week 1 begins on January 1.

*Diagram showing week number with Sunday as the first day of the week.*



*Diagram showing that transaction 8192 took place in week number two.*



Because the application is using broken weeks and the first weekday is Sunday, transactions occurring from January 2 to January 8 return the value 2022/02, week number 2 in 2022. Note that transaction 8192 took place on January 5 and returns the value 2022/02 for the 'week\_number' field.

### Example 5 – Scenario

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions for the last week of 2019 and first two weeks of 2020 is loaded into a table called 'Transactions'.
- The brokenWeeks system variable which is set to 0.
- The referenceDay system variable which is set to 2.
- The dateFormat system variable which is set to the MM/DD/YYYY format.

### Load script

```
SET BrokenWeeks=0;
SET ReferenceDay=2;
SET DateFormat='MM/DD/YYYY';
```

Transactions:

```
Load
*
Inline
[
id,date,amount
8183,12/27/2019,58.27
8184,12/28/2019,67.42
8185,12/29/2019,23.80
8186,12/30/2019,82.06
8187,12/31/2019,40.56
8188,01/01/2020,37.23
8189,01/02/2020,17.17
8190,01/03/2020,88.27
8191,01/04/2020,57.42
8192,01/05/2020,53.80
8193,01/06/2020,82.06
8194,01/07/2020,40.56
8195,01/08/2020,53.67
8196,01/09/2020,26.63
8197,01/10/2020,72.48
8198,01/11/2020,18.37
8199,01/12/2020,45.26
8200,01/13/2020,58.23
8201,01/14/2020,18.52
];
```

### Results

Load the data and open a sheet. Create a new table.

Create a calculated dimension using the following expression:

```
=weekname(date)
```

To calculate total sales create the following aggregation measure:

```
=sum(amount)
```

Set the measure's **Number Formatting** to **Money**.

Results table

<b>weekname(date)</b>	<b>=sum(amount)</b>
2019/52	\$125.69
2020/01	\$346.51
2020/02	\$347.57
2020/03	\$122.01

To demonstrate the results of using the weekname() function in this scenario, add the following field as a dimension:

date

Results table with date field

<b>weekname(date)</b>	<b>date</b>	<b>=sum(amount)</b>
2019/52	12/27/2019	\$58.27
2019/52	12/28/2019	\$67.42
2020/01	12/29/2019	\$23.80
2020/01	12/30/2019	\$82.06
2020/01	12/31/2019	\$40.56
2020/01	01/01/2020	\$37.23
2020/01	01/02/2020	\$17.17
2020/01	01/03/2020	\$88.27
2020/01	01/04/2020	\$57.42
2020/02	01/05/2020	\$53.80
2020/02	01/06/2020	\$82.06
2020/02	01/07/2020	\$40.56
2020/02	01/08/2020	\$53.67
2020/02	01/09/2020	\$26.63
2020/02	01/10/2020	\$72.48
2020/02	01/11/2020	\$18.37
2020/03	01/12/2020	\$45.26
2020/03	01/13/2020	\$58.23
2020/03	01/14/2020	\$18.52

Because the application uses unbroken weeks, and week 1 requires a minimum of two days in January because of the referenceday system variable, week 1 of 2020 includes transactions from December 29, 2019.

### weekstart

This function returns a value corresponding to a timestamp of the first millisecond of the first day of the calendar week containing **date**. The default output format is the **DateFormat** set in the script.

#### Syntax:

```
WeekStart(timestamp [, period_no [, first_week_day ]])
```

**Return data type:** dual

The `weekstart()` function determines which week the date falls into. It then returns a timestamp, in date format, for the first millisecond of that week. The first day of the week is determined by the `FirstWeekDay` environment variable. However, this can be superseded by the `first_week_day` argument in the `weekstart()` function.

#### Arguments

Argument	Description
<b>timestamp</b>	The date or timestamp to evaluate.
<b>period_no</b>	<b>shift</b> is an integer, where the value 0 indicates the week which contains <b>date</b> . Negative values in <b>shift</b> indicate preceding weeks and positive values indicate succeeding weeks.
<b>first_week_day</b>	Specifies the day on which the week starts. If omitted, the value of variable <b>FirstWeekDay</b> is used.  The possible values <b>first_week_day</b> are 0 for Monday, 1 for Tuesday, 2 for Wednesday, 3 for Thursday, 4 for Friday, 5 for Saturday, and 6 for Sunday.  For more information about the system variable, see <i>FirstWeekDay</i> (page 228).

### When to use it

The `weekstart()` function is commonly used as part of an expression when the user would like the calculation to use the fraction of the week that has elapsed thus far. For example, it could be used if a user would like to calculate the total wages earned by employees in the week so far.

The following examples assume:

```
SET FirstWeekDay=0;
```

#### Function examples

Example	Result
<code>weekstart('01/12/2013')</code>	Returns 01/07/2013.
<code>weekstart('01/12/2013', -1 )</code>	Returns 11/31/2012.
<code>weekstart('01/12/2013', 0, 1)</code>	Returns 01/08/2013.

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

#### Examples:

If you want ISO settings for weeks and week numbers, make sure to have the following in the script:

```
Set DateFormat = 'YYYY-MM-DD';
Set FirstWeekDay =0; // Monday as first week day
Set BrokenWeeks =0; //(use unbroken weeks)
Set ReferenceDay =4; // Jan 4th is always in week 1
```

If you want US settings, make sure to have the following in the script:

```
Set DateFormat = 'M/D/YYYY';
Set FirstWeekDay =6; // Sunday as first week day
Set BrokenWeeks =1; //(use broken weeks)
Set ReferenceDay =1; // Jan 1st is always in week 1
```

The examples above results in the following from the `weekstart()` function:

Example of Weekstart function

Date	ISO week start	US week start
Sat 2020 Dec 26	2020-12-21	12/20/2020
Sun 2020 Dec 27	2020-12-21	12/27/2020
Mon 2020 Dec 28	2020-12-28	12/27/2020
Tue 2020 Dec 29	2020-12-28	12/27/2020
Wed 2020 Dec 30	2020-12-28	12/27/2020
Thu 2020 Dec 31	2020-12-28	12/27/2020
Fri 2021 Jan 1	2020-12-28	12/27/2020
Sat 2021 Jan 2	2020-12-28	12/27/2020
Sun 2021 Jan 3	2020-12-28	1/3/2021
Mon 2021 Jan 4	2021-01-04	1/3/2021
Tue 2021 Jan 5	2021-01-04	1/3/2021



*The week starts are on Mondays in the ISO column, and on Sundays in the US column.*

### Example 1 – No additional arguments

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions for 2022, which is loaded into a table called Transactions.
- The date field provided in the dateFormat system variable (MM/DD/YYYY) format.
- The creation of a field, start\_of\_week, that returns a timestamp for the start of the week when the transactions took place.

#### Load script

```
SET FirstWeekDay=6;
```

Transactions:

```
Load
    *,
    weekstart(date) as start_of_week,
    timestamp(weekstart(date)) as start_of_week_timestamp
;
```

Load

\*

Inline

[

```
id,date,amount
8188,1/7/2022,17.17
8189,1/19/2022,37.23
8190,2/28/2022,88.27
8191,2/5/2022,57.42
8192,3/16/2022,53.80
8193,4/1/2022,82.06
8194,5/7/2022,40.39
8195,5/16/2022,87.21
8196,6/15/2022,95.93
8197,6/26/2022,45.89
8198,7/9/2022,36.23
8199,7/22/2022,25.66
8200,7/23/2022,82.77
8201,7/27/2022,69.98
8202,8/2/2022,76.11
8203,8/8/2022,25.12
8204,8/19/2022,46.23
```



```
8205,9/26/2022,84.21
8206,10/14/2022,96.24
8207,10/29/2022,67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- start\_of\_week
- start\_of\_week\_timestamp

Results table

<b>date</b>	<b>start_of_week</b>	<b>start_of_week_timestamp</b>
1/7/2022	01/02/2022	1/2/2022 12:00:00 AM
1/19/2022	01/16/2022	1/16/2022 12:00:00 AM
2/5/2022	01/30/2022	1/30/2022 12:00:00 AM
2/28/2022	02/27/2022	2/27/2022 12:00:00 AM
3/16/2022	03/13/2022	3/13/2022 12:00:00 AM
4/1/2022	03/27/2022	3/27/2022 12:00:00 AM
5/7/2022	05/01/2022	5/1/2022 12:00:00 AM
5/16/2022	05/15/2022	5/15/2022 12:00:00 AM
6/15/2022	06/12/2022	6/12/2022 12:00:00 AM
6/26/2022	06/26/2022	6/26/2022 12:00:00 AM
7/9/2022	07/03/2022	7/3/2022 12:00:00 AM
7/22/2022	07/17/2022	7/17/2022 12:00:00 AM
7/23/2022	07/17/2022	7/17/2022 12:00:00 AM
7/27/2022	07/24/2022	7/24/2022 12:00:00 AM
8/2/2022	07/31/2022	7/31/2022 12:00:00 AM
8/8/2022	08/07/2022	8/7/2022 12:00:00 AM
8/19/2022	08/14/2022	8/14/2022 12:00:00 AM
9/26/2022	09/25/2022	9/25/2022 12:00:00 AM
10/14/2022	10/09/2022	10/9/2022 12:00:00 AM
10/29/2022	10/23/2022	10/23/2022 12:00:00 AM

The start\_of\_week field is created in the preceding load statement by using the weekstart() function and passing the date field as the function's argument.

The `weekstart()` function initially identifies which week the date value falls into, returning a timestamp for the first millisecond of that week.

*Diagram of `weekstart()` function, example with no additional arguments*



Transaction 8191 took place on February 5. The `firstweekday` system variable sets the first day of the week to a Sunday. The `weekstart()` function identifies that the first Sunday before February 5 – and therefore the start of the week – was on January 30. Therefore, the `start_of_week` value for that transaction returns the first millisecond of that day, which is January 30 at 12:00:00 AM.

### Example 2 – `period_no`

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same dataset and scenario as the first example.
- The creation of a field, `previous_week_start`, that returns the timestamp for the start of the quarter before the transaction took place.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
Load
    *,
    weekstart(date,-1) as previous_week_start,
    timestamp(weekstart(date,-1)) as previous_week_start_timestamp
;

Load
*
Inline
[
id,date,amount
8188,1/7/2022,17.17
8189,1/19/2022,37.23
8190,2/28/2022,88.27
8191,2/5/2022,57.42
8192,3/16/2022,53.80
8193,4/1/2022,82.06
8194,5/7/2022,40.39
```

```
8195, 5/16/2022, 87.21
8196, 6/15/2022, 95.93
8197, 6/26/2022, 45.89
8198, 7/9/2022, 36.23
8199, 7/22/2022, 25.66
8200, 7/23/2022, 82.77
8201, 7/27/2022, 69.98
8202, 8/2/2022, 76.11
8203, 8/8/2022, 25.12
8204, 8/19/2022, 46.23
8205, 9/26/2022, 84.21
8206, 10/14/2022, 96.24
8207, 10/29/2022, 67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- previous\_week\_start
- previous\_week\_start\_timestamp

Results table

date	previous_week_start	previous_week_start_timestamp
1/7/2022	12/26/2021	12/26/2021 12:00:00 AM
1/19/2022	01/09/2022	1/9/2022 12:00:00 AM
2/5/2022	01/23/2022	1/23/2022 12:00:00 AM
2/28/2022	02/20/2022	2/20/2022 12:00:00 AM
3/16/2022	03/06/2022	3/6/2022 12:00:00 AM
4/1/2022	03/20/2022	3/20/2022 12:00:00 AM
5/7/2022	04/24/2022	4/24/2022 12:00:00 AM
5/16/2022	05/08/2022	5/8/2022 12:00:00 AM
6/15/2022	06/05/2022	6/5/2022 12:00:00 AM
6/26/2022	06/19/2022	6/19/2022 12:00:00 AM
7/9/2022	06/26/2022	6/26/2022 12:00:00 AM
7/22/2022	07/10/2022	7/10/2022 12:00:00 AM
7/23/2022	07/10/2022	7/10/2022 12:00:00 AM
7/27/2022	07/17/2022	7/17/2022 12:00:00 AM
8/2/2022	07/24/2022	7/24/2022 12:00:00 AM

date	previous_week_start	previous_week_start_timestamp
8/8/2022	07/31/2022	7/31/2022 12:00:00 AM
8/19/2022	08/07/2022	8/7/2022 12:00:00 AM
9/26/2022	09/18/2022	9/18/2022 12:00:00 AM
10/14/2022	10/02/2022	10/2/2022 12:00:00 AM
10/29/2022	10/16/2022	10/16/2022 12:00:00 AM

In this instance, because a `period_no` of `-1` was used as the offset argument in the `weekstart()` function, the function first identifies the week that the transactions take place in. It then looks one week prior and identifies the first millisecond of that week.

*Diagram of `weekstart()` function, `period_no` example*



Transaction 8196 took place on June 15. The `weekstart()` function identifies that the week begins on June 12. Therefore, the previous week began on June 5 at 12:00:00 AM; this is the value that is returned for the `previous_week_start` field.

### Example 3 – `first_week_day`

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains the same dataset and scenario as the first example. However, in this example, we need to set Tuesday as the first day of the work week.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
Load
    *,
    weekstart(date,0,1) as start_of_week,
    timestamp(weekstart(date,0,1)) as start_of_week_timestamp
;
Load
*
```

Inline

```
[  
id,date,amount  
8188,1/7/2022,17.17  
8189,1/19/2022,37.23  
8190,2/28/2022,88.27  
8191,2/5/2022,57.42  
8192,3/16/2022,53.80  
8193,4/1/2022,82.06  
8194,5/7/2022,40.39  
8195,5/16/2022,87.21  
8196,6/15/2022,95.93  
8197,6/26/2022,45.89  
8198,7/9/2022,36.23  
8199,7/22/2022,25.66  
8200,7/23/2022,82.77  
8201,7/27/2022,69.98  
8202,8/2/2022,76.11  
8203,8/8/2022,25.12  
8204,8/19/2022,46.23  
8205,9/26/2022,84.21  
8206,10/14/2022,96.24  
8207,10/29/2022,67.67  
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- start\_of\_week
- start\_of\_week\_timestamp

Results table

date	start_of_week	start_of_week_timestamp
1/7/2022	01/04/2022	1/4/2022 12:00:00 AM
1/19/2022	01/18/2022	1/18/2022 12:00:00 AM
2/5/2022	02/01/2022	2/1/2022 12:00:00 AM
2/28/2022	02/22/2022	2/22/2022 12:00:00 AM
3/16/2022	03/15/2022	3/15/2022 12:00:00 AM
4/1/2022	03/29/2022	3/29/2022 12:00:00 AM
5/7/2022	05/03/2022	5/3/2022 12:00:00 AM
5/16/2022	05/10/2022	5/10/2022 12:00:00 AM
6/15/2022	06/14/2022	6/14/2022 12:00:00 AM

date	start_of_week	start_of_week_timestamp
6/26/2022	06/21/2022	6/21/2022 12:00:00 AM
7/9/2022	07/05/2022	7/5/2022 12:00:00 AM
7/22/2022	07/19/2022	7/19/2022 12:00:00 AM
7/23/2022	07/19/2022	7/19/2022 12:00:00 AM
7/27/2022	07/26/2022	7/26/2022 12:00:00 AM
8/2/2022	08/02/2022	8/2/2022 12:00:00 AM
8/8/2022	08/02/2022	8/2/2022 12:00:00 AM
8/19/2022	08/16/2022	8/16/2022 12:00:00 AM
9/26/2022	09/20/2022	9/20/2022 12:00:00 AM
10/14/2022	10/11/2022	10/11/2022 12:00:00 AM
10/29/2022	10/25/2022	10/25/2022 12:00:00 AM

In this instance, because the `first_week_date` argument of 1 is used in the `weekstart()` function, it sets the first day of the week to Tuesday.

*Diagram of `weekstart()` function, `first_week_day` example*



Transaction 8191 took place on February 5. The `weekstart()` function identifies that the first Tuesday before the this date – and therefore the start of the week and value returned – was February 1 at 12:00:00 AM.

### Example 4 – Chart object example

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains the same dataset and scenario as the first example.

However, in this example, the unchanged dataset is loaded into the application. The calculation that returns a timestamp for the start of the week when the transactions took place is created as a measure in a chart object of the application.

### Load script

Transactions:

```
Load
*
Inline
[
id,date,amount
8188,1/7/2022,17.17
8189,1/19/2022,37.23
8190,2/28/2022,88.27
8191,2/5/2022,57.42
8192,3/16/2022,53.80
8193,4/1/2022,82.06
8194,5/7/2022,40.39
8195,5/16/2022,87.21
8196,6/15/2022,95.93
8197,6/26/2022,45.89
8198,7/9/2022,36.23
8199,7/22/2022,25.66
8200,7/23/2022,82.77
8201,7/27/2022,69.98
8202,8/2/2022,76.11
8203,8/8/2022,25.12
8204,8/19/2022,46.23
8205,9/26/2022,84.21
8206,10/14/2022,96.24
8207,10/29/2022,67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension: date.

To calculate the start of the week in which a transaction takes place, add the following measures:

- =weekstart(date)
- =timestamp(weekstart(date))

Results table

date	start_of_week	start_of_week_timestamp
1/7/2022	01/02/2022	1/2/2022 12:00:00 AM
1/19/2022	01/16/2022	1/16/2022 12:00:00 AM
2/5/2022	01/30/2022	1/30/2022 12:00:00 AM
2/28/2022	02/27/2022	2/27/2022 12:00:00 AM
3/16/2022	03/13/2022	3/13/2022 12:00:00 AM

date	start_of_week	start_of_week_timestamp
4/1/2022	03/27/2022	3/27/2022 12:00:00 AM
5/7/2022	05/01/2022	5/1/2022 12:00:00 AM
5/16/2022	05/15/2022	5/15/2022 12:00:00 AM
6/15/2022	06/12/2022	6/12/2022 12:00:00 AM
6/26/2022	06/26/2022	6/26/2022 12:00:00 AM
7/9/2022	07/03/2022	7/3/2022 12:00:00 AM
7/22/2022	07/17/2022	7/17/2022 12:00:00 AM
7/23/2022	07/17/2022	7/17/2022 12:00:00 AM
7/27/2022	07/24/2022	7/24/2022 12:00:00 AM
8/2/2022	07/31/2022	7/31/2022 12:00:00 AM
8/8/2022	08/07/2022	8/7/2022 12:00:00 AM
8/19/2022	08/14/2022	8/14/2022 12:00:00 AM
9/26/2022	09/25/2022	9/25/2022 12:00:00 AM
10/14/2022	10/09/2022	10/9/2022 12:00:00 AM
10/29/2022	10/23/2022	10/23/2022 12:00:00 AM

The `start_of_week` measure is created in the chart object by using the `weekstart()` function and passing the date field as the function's argument.

The `weekstart()` function initially identifies which week the date value falls into, returning a timestamp for the first millisecond of that week.

*Diagram of `weekstart()` function, chart object example*



Transaction 8191 took place on February 5. The `Firstweekday` system variable sets the first day of the week to a Sunday. The `weekstart()` function identifies that the first Sunday before February 5 – and therefore the start of the week – was January 30. Therefore, the `start_of_week` value for that transaction returns the first millisecond of that day, which is January 30 at 12:00:00 AM.



### Example 5 – Scenario

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset which is loaded into a table called `Payroll`.
- Data consisting of employee IDs, employee names, and the daily wage earned by each employee.

Employees begin work on Monday and work six days per week. The `Firstweekday` system variable must not be modified.

The end user would like a chart object that displays, by employee ID and employee name, the wages earned in the week to date.

#### Load script

```
Payroll:
Load
*
Inline
[
employee_id,employee_name,day_rate
182,Mark, $150
183,Deryck, $125
184,Dexter, $125
185,Sydney,$270
186,Agatha,$128
];
```

#### Results

##### Do the following:

1. Load the data and open a sheet. Create a new table and add these fields as dimensions:
  - `employee_id`
  - `employee_name`
2. Next, create a measure to calculate the wages earned in the week to date:  
`=if(today(1)-weekstart(today(1),0,0)<7,(today(1)-weekstart(today(1),0,0))*day_rate,day_rate*6)`
3. Set the measure's **Number formatting** to **Money**.

Results table

employee_id	employee_name	=if(today(1)-weekstart(today(1),0,0)<7,(today(1)-weekstart(today(1),0,0))*day_rate,day_rate*6)
182	Mark	\$600.00
183	Deryck	\$500.00
184	Dexter	\$500.00
185	Sydney	\$1080.00
186	Agatha	\$512.00

The `weekstart()` function, by using today's date as its first argument and 0 as its third argument, sets Monday as the first day of the week and returns the start date of the current week. By subtracting that result from the current date, the expression then returns the number of days that have elapsed so far this week.

The condition then evaluates whether there have been more than six days this week. If so, the employee's `day_rate` is multiplied by 6 days. Otherwise, the `day_rate` is multiplied by the number of days that have occurred so far this week.

### weekyear

This function returns the year to which the week number belongs according to the environment variables. The week number ranges between 1 and approximately 52.

#### Syntax:

```
weekyear (timestamp [, first_week_day [, broken_weeks [, reference_day]])
```

**Return data type:** integer

Arguments

Argument	Description
<b>timestamp</b>	The date or timestamp to evaluate.
<b>first_week_day</b>	Specifies the day on which the week starts. If omitted, the value of variable <b>FirstWeekDay</b> is used.  The possible values <b>first_week_day</b> are 0 for Monday, 1 for Tuesday, 2 for Wednesday, 3 for Thursday, 4 for Friday, 5 for Saturday, and 6 for Sunday.  For more information about the system variable, see <i>FirstWeekDay</i> (page 228).
<b>broken_weeks</b>	If you don't specify <b>broken_weeks</b> , the value of variable <b>BrokenWeeks</b> will be used to define if weeks are broken or not.


## 8 Script and chart functions

Argument	Description
<b>reference_day</b>	If you don't specify <b>reference_day</b> , the value of variable <b>ReferenceDay</b> will be used to define which day in January to set as reference day to define week 1. By default, Qlik Sense functions use 4 as the reference day. This means that week 1 must contain January 4, or put differently, that week 1 must always have at least 4 days in January.

The `weekyear()` function determines which week of a year a date falls into. It then returns the year corresponding to that week number.

If `brokenweeks` is set to 0 (false), `weekyear()` will return the same as `year()`.


*Diagram of `weekyear()` function's range*



However, if the `brokenweeks` system variable is set to use unbroken weeks, week 1 must only contain a certain number of days in January based on the value specified in the `referenceDay` system variable.

For example, if a `referenceDay` value of 4 is used, week 1 must include at least four days in January. It is possible for week 1 to include dates in December of the previous year or for the final week number of a year to include dates in January of the following year. In situations like this, the `weekyear()` function will return a different value to the `year()` function.

*Diagram of `weekyear()` function's range when using unbroken weeks*



### When to use it

The `weekyear()` function is useful when you would like to compare aggregations by years. For example, if you would like to see the total sales of products by year. The `weekyear()` function is chosen over `year()` when the user would like to retain consistency with the `brokenweeks` system variable in the app.

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

#### Function examples

Example	Result
<code>weekyear('12/30/1996',0,0,4)</code>	Returns 1997, because week 1 of 1997 starts on 12/30/1996
<code>weekyear('01/02/1997',0,0,4)</code>	Returns 1997
<code>weekyear('12/28/1997',0,0,4)</code>	Returns 1997
<code>weekyear('12/30/1997',0,0,4)</code>	Returns 1998, because week 1 of 1998 starts on 12/29/1997
<code>weekyear('01/02/1999',0,0,4)</code>	Returns 1998, because week 53 of 1998 ends on 01/03/1999

#### Related topics

Topic	Interaction
<i>week</i> (page 1058)	Returns an integer representing the week number according to ISO 8601
<i>year</i> (page 1132)	Returns an integer representing the year when the expression is interpreted as a date according to the standard number interpretation.

### Example 1 - Broken weeks

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions for the last week of 2020 and first week of 2021 which is loaded into a table called 'transactions'.
- The brokenweeks variable which is set to 1.
- A preceding load which contains the following:
  - The weekyear() function, set as the field 'week\_year' that returns the year in which the transactions took place.
  - The week() function, set as the field 'week' that shows the week number of each transaction date.

#### Load script

```
SET BrokenWeeks=1;
```

```
Transactions:
```

```
    Load
    *,
    week(date) as week,
    weekyear(date) as week_year
    ;
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
```

```
8176,12/28/2020,19.42
```

```
8177,12/29/2020,23.80
```

```
8178,12/30/2020,82.06
```

```
8179,12/31/2020,40.56
```

```
8180,01/01/2021,37.23
```

```
8181,01/02/2021,17.17
```

```
8182,01/03/2021,88.27
```

```
8183,01/04/2021,57.42
```

```
8184,01/05/2021,67.42
```

```
8185,01/06/2021,23.80
```

```
8186,01/07/2021,82.06
```

```
];
```

#### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- id
- date
- week
- week\_year


Results table

id	date	week	week_year
8176	12/28/2020	53	2020
8177	12/29/2020	53	2020
8178	12/30/2020	53	2020
8179	12/31/2020	53	2020
8180	01/01/2021	1	2021
8181	01/02/2021	1	2021
8182	01/03/2021	2	2021
8183	01/04/2021	2	2021
8184	01/05/2021	2	2021
8185	01/06/2021	2	2021
8186	01/07/2021	2	2021

The 'week\_year' field is created in the preceding load statement by using the `weekyear()` function and passing the date field as the function's argument.

The `brokenweeks` system variable is set to 1 meaning that the app uses broken weeks. Week 1 begins on January 1.

*Diagram of `weekyear()` function's range with the use of broken weeks*



Transaction 8181 takes place on January 2, which is part of week 1. Therefore, it returns a value of 2021 for the 'week\_year' field.

### Example 2 - Unbroken weeks

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions for the last week of 2020 and first week of 2021 which is loaded into a table called 'transactions'.
- The brokenweeks variable which is set to 0.
- A preceding load which contains the following:
  - The weekyear() function, set as the field 'week\_year' that returns the year in which the transactions took place.
  - The week() function, set as the field 'week' that shows the week number of each transaction date.

However, in this example, the company policy is to use unbroken weeks.

#### Load script

```
SET BrokenWeeks=0;
```

```
Transactions:
```

```
    Load
    *,
    week(date) as week,
    weekyear(date) as week_year
    ;
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
```

```
8176,12/28/2020,19.42
```

```
8177,12/29/2020,23.80
```

```
8178,12/30/2020,82.06
```

```
8179,12/31/2020,40.56
```

```
8180,01/01/2021,37.23
```

```
8181,01/02/2021,17.17
```

```
8182,01/03/2021,88.27
```

```
8183,01/04/2021,57.42
```

```
8184,01/05/2021,67.42
```

```
8185,01/06/2021,23.80
```

```
8186,01/07/2021,82.06
```

```
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- id
- date
- week
- week\_year


Results table

id	date	week	week_year
8176	12/28/2020	53	2020
8177	12/29/2020	53	2020
8178	12/30/2020	53	2020
8179	12/31/2020	53	2020
8180	01/01/2021	53	2020
8181	01/02/2021	53	2020
8182	01/03/2021	1	2021
8183	01/04/2021	1	2021
8184	01/05/2021	1	2021
8185	01/06/2021	1	2021
8186	01/07/2021	1	2021

The `brokenweeks` system variable is set to 0 meaning that the application uses unbroken weeks. Therefore, week 1 is not required to begin on January 1.

Week 53 of 2020 continues until the end of January 2, 2021, with week 1 of 2021 beginning on Sunday, January 3, 2021.

*Diagram of `weekyear()` function's range with the use of unbroken weeks*



Transaction 8181 takes place on January 2, which is part of week 1. Therefore, it returns a value of 2021 for the 'week\_year' field.



### Example 3 - Chart object example

Load script and chart expression

#### Overview

The same dataset and scenario as the first example are used.

However, in this example the dataset is unchanged and loaded into the application. The calculation that returns the week number of the year when the transactions took place is created as a measure in a chart in the app.

#### Load script

```
SET BrokenWeeks=1;
```

```
Transactions:
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
```

```
8176,12/28/2020,19.42
```

```
8177,12/29/2020,23.80
```

```
8178,12/30/2020,82.06
```

```
8179,12/31/2020,40.56
```

```
8180,01/01/2021,37.23
```

```
8181,01/02/2021,17.17
```

```
8182,01/03/2021,88.27
```

```
8183,01/04/2021,57.42
```

```
8184,01/05/2021,67.42
```

```
8185,01/06/2021,23.80
```

```
8186,01/07/2021,82.06
```

```
];
```

#### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- id
- date

To calculate the week that a transaction takes place in, create the following measure:

- =week(date)

To calculate the year that a transaction takes place in based on the week number, create the following measure:

- =weekyear(date)


Results table

id	date	week	week_year
8176	12/28/2020	53	2020
8177	12/29/2020	53	2020
8178	12/30/2020	53	2020
8179	12/31/2020	53	2020
8180	01/01/2021	1	2021
8181	01/02/2021	1	2021
8182	01/03/2021	2	2021
8183	01/04/2021	2	2021
8184	01/05/2021	2	2021
8185	01/06/2021	2	2021
8186	01/07/2021	2	2021

The 'week\_year' field is created in the preceding load statement by using the `weekyear()` function and passing the date field as the function's argument.

The `brokenweeks` system variable is set to 1 meaning that the app uses broken weeks. week 1 begins on January 1.

*Diagram of `weekyear()` function's range with the use of broken weeks*



Transaction 8181 takes place on January 2, which is part of week 1. Therefore, it returns a value of 2021 for the 'week\_year' field.

### Example 4 - Scenario

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions for the last week of 2020 and first week of 2021 which is loaded into a table called 'transactions'.
- The brokenweeks variable which is set to 0. This means the app will use unbroken weeks.
- The referenceday variable which is set to 2. This means the year will begin on January 2 and will contain a minimum of two days in January.
- The firstweekday variable which is set to 1. This means the first day of the week will be Tuesday.

The company policy is to use broken weeks. The end user would like a chart that presents the total sales by year. The app uses unbroken weeks with week 1 containing a minimum of two days in January.

### Load script

```
SET BrokenWeeks=0;
SET ReferenceDay=2;
SET FirstWeekDay=1;
```

Transactions:

```
Load
*
Inline
[
id,date,amount
8176,12/28/2020,19.42
8177,12/29/2020,23.80
8178,12/30/2020,82.06
8179,12/31/2020,40.56
8180,01/01/2021,37.23
8181,01/02/2021,17.17
8182,01/03/2021,88.27
8183,01/04/2021,57.42
8184,01/05/2021,67.42
8185,01/06/2021,23.80
8186,01/07/2021,82.06
];
```

### Results

Load the data and open a sheet. Create a new table.

To calculate the year that a transaction takes place in based on the week number, create the following measure:

- =weekyear(date)

To calculate total sales, create the following measure:

- sum(amount)

Set the measure's **Number Formatting** to **Money**.

Results table

<b>weekyear(date)</b>	<b>=sum(amount)</b>
2020	19.42
2021	373.37

### year

This function returns an integer representing the year when the **expression** is interpreted as a date according to the standard number interpretation.

#### Syntax:

```
year (expression)
```

**Return data type:** integer

The `year()` function is available as both a script and chart function. The function returns the year for a particular date. It is commonly used to create a year field as a dimension in a Master Calendar.

### When to use it

The `year()` function is useful when you would like to compare aggregations by year. For example, the function could be used if you would like to see the total sales of products by year.

These dimensions can be created either in the load script by using the function to create a field in a Master Calendar table. Alternatively, it could be used directly in a chart as a calculated dimension.

Function examples

<b>Example</b>	<b>Result</b>
<code>year( '2012-10-12' )</code>	returns 2012
<code>year( '35648' )</code>	returns 1997, because 35648 = 1997-08-06

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Example 1 – DateFormat dataset (script)

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset of dates, which is loaded into a table named `Master_Calendar`.
- The default `DateFormat` system variable (`MM/DD/YYYY`) is used.
- A preceding load which is used to create an additional field, `year`, using the `year()` function.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Master_Calendar:
```

```
    Load
        date,
        year(date) as year
    ;
```

```
Load
date
Inline
[
date
12/28/2020
12/29/2020
12/30/2020
12/31/2020
01/01/2021
01/02/2021
01/03/2021
01/04/2021
01/05/2021
01/06/2021
01/07/2021
];
```

#### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- `date`
- `year`

Results table

<b>date</b>	<b>year</b>
12/28/2020	2020
12/29/2020	2020
12/30/2020	2020
12/31/2020	2020
01/01/2021	2021
01/02/2021	2021
01/03/2021	2021
01/04/2021	2021
01/05/2021	2021
01/06/2021	2021
01/07/2021	2021

### Example 2 – ANSI Dates

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset of dates, which is loaded into a table named `master_calendar`.
- The default `DateFormat` system variable (MM/DD/YYYY) is used. However, the dates included in the dataset are in ANSI standard date format.
- A preceding load, which is used to create an additional field, named `year`, using the `year()` function.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Master_Calendar:
```

```
  Load
    date,
    year(date) as year
  ;
```

```
Load
date
Inline
[
date
```

```
2020-12-28
2020-12-29
2020-12-30
2020-12-31
2021-01-01
2021-01-02
2021-01-03
2021-01-04
2021-01-05
2021-01-06
2021-01-07
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- year

Results table

date	year
2020-12-28	2020
2020-12-29	2020
2020-12-30	2020
2020-12-31	2020
2021-01-01	2021
2021-01-02	2021
2021-01-03	2021
2021-01-04	2021
2021-01-05	2021
2021-01-06	2021
2021-01-07	2021

### Example 3 – Unformatted dates

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset of dates in numerical format, which is loaded into a table named `Master_Calendar`.
- The default `DateFormat` system variable (`MM/DD/YYYY`) is used.
- A preceding load, which is used to create an additional field, `year`, using the `year()` function.

The original unformatted date is loaded, named `unformatted_date`, and to provide clarity, a further additional field, named `long_date`, is used to convert the numerical date into a formatted date field using the `date()` function.

### Load script

```
SET DateFormat='MM/DD/YYYY';

Master_Calendar:
  Load
    unformatted_date,
    date(unformatted_date) as long_date,
    year(unformatted_date) as year
  ;
Load
unformatted_date
Inline
[
unformatted_date
44868
44898
44928
44958
44988
45018
45048
45078
45008
45038
45068
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- `unformatted_date`
- `long_date`
- `year`

Results table

<code>unformatted_date</code>	<code>long_date</code>	<code>year</code>
44868	11/03/2022	2022
44898	12/03/2022	2022



unformatted_date	long_date	year
44928	01/02/2023	2023
44958	02/01/2023	2023
44988	03/03/2023	2023
45008	03/23/2023	2023
45018	04/02/2023	2023
45038	04/22/2023	2023
45048	05/02/2023	2023
45068	05/22/2023	2023
45078	06/01/2023	2023

### Example 4 – Chart object example

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

In this example, a dataset of orders placed is loaded into a table named Sales. The table contains three fields:

- id
- sales\_date
- amount

Warranties on product sales last two years from the date of sale. The task is to create a measure in a chart to determine the year in which each warranty will expire.

#### Load script

```
sales:
Load
id,
sales_date,
amount
inline
[
id,sales_date,amount
1,12/28/2020,231.24,
2,12/29/2020,567.28,
3,12/30/2020,364.28,
4,12/31/2020,575.76,
5,01/01/2021,638.68,
6,01/02/2021,785.38,
```

```
7,01/03/2021,967.46,  
8,01/04/2021,287.67  
9,01/05/2021,764.45,  
10,01/06/2021,875.43,  
11,01/07/2021,957.35  
];
```

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension: sales\_date.

Create the following measure:

```
=year(sales_date+365*2)
```

Results table

sales_date	=year(sales_date+365*2)
12/28/2020	2022
12/29/2020	2022
12/30/2020	2022
12/31/2020	2022
01/01/2021	2023
01/02/2021	2023
01/03/2021	2023
01/04/2021	2023
01/05/2021	2023
01/06/2021	2023
01/07/2021	2023

The results of this measure can be seen in the table above. To add two years to a date, multiply 365 by 2 and add the result to the sales date. Therefore, sales that took place in 2020 have an expiry year of 2022.

### yearend

This function returns a value corresponding to a timestamp of the last millisecond of the last day of the year containing **date**. The default output format will be the **DateFormat** set in the script.

#### Syntax:

```
YearEnd( date[, period_no[, first_month_of_year = 1]])
```


## 8 Script and chart functions

In other words, the `yearend()` function determines which year the date falls into. It then returns a timestamp, in date format, for the last millisecond of that year. The first month of the year is, by default, January. However, you can change which month is set as first by using the `first_month_of_year` argument in the `yearend()` function.



*The `yearend()` function does not consider the `FirstMonthOfYear` system variable. The year begins on January 1 unless the `first_month_of_year` argument is used to change it.*

Diagram of `yearend()` function.



### When to use it

The `yearend()` function is used as part of an expression when you want the calculation to use the fraction of the year that has not yet occurred. For example, if you want to calculate the total interest not yet incurred during the year.

**Return data type:** dual

### Arguments

Argument	Description
<b>date</b>	The date or timestamp to evaluate.
<b>period_no</b>	<b>period_no</b> is an integer, where the value 0 indicates the year which contains <b>date</b> . Negative values in <b>period_no</b> indicate preceding years and positive values indicate succeeding years.
<b>first_month_of_year</b>	If you want to work with (fiscal) years not starting in January, indicate a value between 2 and 12 in <b>first_month_of_year</b> .

You can use the following values to set the first month of year in the `first_month_of_year` argument:

`first_month_of_year` values

Month	Value
February	2
March	3
April	4

Month	Value
May	5
June	6
July	7
August	8
September	9
October	10
November	11
December	12

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET dateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

#### Function examples

Example	Result
<code>yearend('10/19/2001')</code>	Returns 12/31/2001 23:59:59.
<code>yearend('10/19/2001', -1)</code>	Returns 12/31/2000 23:59:59.
<code>yearend('10/19/2001', 0, 4)</code>	Returns 03/31/2002 23:59:59.

### Example 1 – No additional arguments

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions between 2020 and 2022 is loaded into a table called 'transactions'.
- The date field has been provided in the `DateFormat` system variable (MM/DD/YYYY) format.
- A preceding load statement which contains the following:
  - `yearend()` function which is set as the `year_end` field.
  - `timestamp()` function which is set as the `year_end_timestamp` field.

### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
  Load
    *,
    yearend(date) as year_end,
    timestamp(yearend(date)) as year_end_timestamp
  ;
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
```

```
8188,01/13/2020,37.23
```

```
8189,02/26/2020,17.17
```

```
8190,03/27/2020,88.27
```

```
8191,04/16/2020,57.42
```

```
8192,05/21/2020,53.80
```

```
8193,08/14/2020,82.06
```

```
8194,10/07/2020,40.39
```

```
8195,12/05/2020,87.21
```

```
8196,01/22/2021,95.93
```

```
8197,02/03/2021,45.89
```

```
8198,03/17/2021,36.23
```

```
8199,04/23/2021,25.66
```

```
8200,05/04/2021,82.77
```

```
8201,06/30/2021,69.98
```

```
8202,07/26/2021,76.11
```

```
8203,12/27/2021,25.12
```

```
8204,06/06/2022,46.23
```

```
8205,07/18/2022,84.21
```

```
8206,11/14/2022,96.24
```

```
8207,12/12/2022,67.67
```

```
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- `id`
- `date`

- year\_end
- year\_end\_timestamp


Results table

<b>id</b>	<b>date</b>	<b>year_end</b>	<b>year_end_timestamp</b>
8188	01/13/2020	12/31/2020	12/31/2020 11:59:59 PM
8189	02/26/2020	12/31/2020	12/31/2020 11:59:59 PM
8190	03/27/2020	12/31/2020	12/31/2020 11:59:59 PM
8191	04/16/2020	12/31/2020	12/31/2020 11:59:59 PM
8192	05/21/2020	12/31/2020	12/31/2020 11:59:59 PM
8193	08/14/2020	12/31/2020	12/31/2020 11:59:59 PM
8194	10/07/2020	12/31/2020	12/31/2020 11:59:59 PM
8195	12/05/2020	12/31/2020	12/31/2020 11:59:59 PM
8196	01/22/2021	12/31/2021	12/31/2021 11:59:59 PM
8197	02/03/2021	12/31/2021	12/31/2021 11:59:59 PM
8198	03/17/2021	12/31/2021	12/31/2021 11:59:59 PM
8199	04/23/2021	12/31/2021	12/31/2021 11:59:59 PM
8200	05/04/2021	12/31/2021	12/31/2021 11:59:59 PM
8201	06/30/2021	12/31/2021	12/31/2021 11:59:59 PM
8202	07/26/2021	12/31/2021	12/31/2021 11:59:59 PM
8203	12/27/2021	12/31/2021	12/31/2021 11:59:59 PM
8204	06/06/2022	12/31/2022	12/31/2022 11:59:59 PM
8205	07/18/2022	12/31/2022	12/31/2022 11:59:59 PM
8206	11/14/2022	12/31/2022	12/31/2022 11:59:59 PM
8207	12/12/2022	12/31/2022	12/31/2022 11:59:59 PM

The 'year\_end' field is created in the preceding load statement by using the `yearend()` function and passing the date field as the function's argument.

The `yearend()` function initially identifies which year the date value falls into and returns a timestamp for the last millisecond of that year.

Diagram of `yearend()` function with transaction 8199 selected.



Transaction 8199 took place on April 23, 2021. The `yearend()` function returns the last millisecond of that year, which is December 31 at 11:59:59 PM.

### Example 2 – `period_no`

Load script and results

#### Overview

The same dataset and scenario as the first example are used.

However, in this example, the task is to create a field, 'previous\_year\_end', that returns the end date timestamp of the year prior to the year in which a transaction took place.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
Load
  *,
  yearend(date,-1) as previous_year_end,
  timestamp(yearend(date,-1)) as previous_year_end_timestamp
;
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
```

```
8188,01/13/2020,37.23
```

```
8189,02/26/2020,17.17
```

```
8190,03/27/2020,88.27
```

```
8191,04/16/2020,57.42
```

```
8192,05/21/2020,53.80
```

```
8193,08/14/2020,82.06
```

```
8194,10/07/2020,40.39
```

```
8195,12/05/2020,87.21
```

```
8196,01/22/2021,95.93
```

```
8197,02/03/2021,45.89
```

```
8198,03/17/2021,36.23
```

```
8199,04/23/2021,25.66
```

```
8200,05/04/2021,82.77
```

```
8201,06/30/2021,69.98
```

```
8202,07/26/2021,76.11
```

```
8203,12/27/2021,25.12
```

```
8204,06/06/2022,46.23
8205,07/18/2022,84.21
8206,11/14/2022,96.24
8207,12/12/2022,67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- id
- date
- previous\_year\_end
- previous\_year\_end\_timestamp


Results table

id	date	previous_year_end	previous_year_end_timestamp
8188	01/13/2020	12/31/2019	12/31/2019 11:59:59 PM
8189	02/26/2020	12/31/2019	12/31/2019 11:59:59 PM
8190	03/27/2020	12/31/2019	12/31/2019 11:59:59 PM
8191	04/16/2020	12/31/2019	12/31/2019 11:59:59 PM
8192	05/21/2020	12/31/2019	12/31/2019 11:59:59 PM
8193	08/14/2020	12/31/2019	12/31/2019 11:59:59 PM
8194	10/07/2020	12/31/2019	12/31/2019 11:59:59 PM
8195	12/05/2020	12/31/2019	12/31/2019 11:59:59 PM
8196	01/22/2021	12/31/2020	12/31/2020 11:59:59 PM
8197	02/03/2021	12/31/2020	12/31/2020 11:59:59 PM
8198	03/17/2021	12/31/2020	12/31/2020 11:59:59 PM
8199	04/23/2021	12/31/2020	12/31/2020 11:59:59 PM
8200	05/04/2021	12/31/2020	12/31/2020 11:59:59 PM
8201	06/30/2021	12/31/2020	12/31/2020 11:59:59 PM
8202	07/26/2021	12/31/2020	12/31/2020 11:59:59 PM
8203	12/27/2021	12/31/2020	12/31/2020 11:59:59 PM
8204	06/06/2022	12/31/2021	12/31/2021 11:59:59 PM
8205	07/18/2022	12/31/2021	12/31/2021 11:59:59 PM
8206	11/14/2022	12/31/2021	12/31/2021 11:59:59 PM
8207	12/12/2022	12/31/2021	12/31/2021 11:59:59 PM



Because a `period_no` of `-1` was used as the offset argument in the `yearend()` function, the function first identifies the year that the transactions take place in. It then looks one year prior and identifies the last millisecond of that year.

Diagram of `yearend()` function with a `period_no` of `-1`.



Transaction 8199 takes place on April 23, 2021. The `yearend()` function returns the last millisecond of the prior year, December 31, 2020 at 11:59:59 PM, for the `'previous_year_end'` field.

### Example 3 – first\_month\_of\_year

Load script and results

#### Overview

The same dataset and scenario as the first example are used.

However, in this example, the company policy is for the year to begin from April 1.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
Load
*,
yearend(date,0,4) as year_end,
timestamp(yearend(date,0,4)) as year_end_timestamp
;
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
```

```
8188,01/13/2020,37.23
```

```
8189,02/26/2020,17.17
```

```
8190,03/27/2020,88.27
```

```
8191,04/16/2020,57.42
```

```
8192,05/21/2020,53.80
```

```
8193,08/14/2020,82.06
```

```
8194,10/07/2020,40.39
```

```
8195,12/05/2020,87.21
```

```
8196,01/22/2021,95.93
```

```
8197,02/03/2021,45.89
```

```
8198,03/17/2021,36.23
```

```
8199,04/23/2021,25.66
8200,05/04/2021,82.77
8201,06/30/2021,69.98
8202,07/26/2021,76.11
8203,12/27/2021,25.12
8204,06/06/2022,46.23
8205,07/18/2022,84.21
8206,11/14/2022,96.24
8207,12/12/2022,67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- id
- date
- year\_end
- year\_end\_timestamp


Results table

id	date	year_end	year_end_timestamp
8188	01/13/2020	03/31/2020	3/31/2020 11:59:59 PM
8189	02/26/2020	03/31/2020	3/31/2020 11:59:59 PM
8190	03/27/2020	03/31/2020	3/31/2020 11:59:59 PM
8191	04/16/2020	03/31/2021	3/31/2021 11:59:59 PM
8192	05/21/2020	03/31/2021	3/31/2021 11:59:59 PM
8193	08/14/2020	03/31/2021	3/31/2021 11:59:59 PM
8194	10/07/2020	03/31/2021	3/31/2021 11:59:59 PM
8195	12/05/2020	03/31/2021	3/31/2021 11:59:59 PM
8196	01/22/2021	03/31/2021	3/31/2021 11:59:59 PM
8197	02/03/2021	03/31/2021	3/31/2021 11:59:59 PM
8198	03/17/2021	03/31/2021	3/31/2021 11:59:59 PM
8199	04/23/2021	03/31/2022	3/31/2022 11:59:59 PM
8200	05/04/2021	03/31/2022	3/31/2022 11:59:59 PM
8201	06/30/2021	03/31/2022	3/31/2022 11:59:59 PM
8202	07/26/2021	03/31/2022	3/31/2022 11:59:59 PM
8203	12/27/2021	03/31/2022	3/31/2022 11:59:59 PM
8204	06/06/2022	03/31/2023	3/31/2023 11:59:59 PM

id	date	year_end	year_end_timestamp
8205	07/18/2022	03/31/2023	3/31/2023 11:59:59 PM
8206	11/14/2022	03/31/2023	3/31/2023 11:59:59 PM
8207	12/12/2022	03/31/2023	3/31/2023 11:59:59 PM

Because the `first_month_of_year` argument of 4 is used in the `yearend()` function, it sets the first day of the year to April 1, and the last day of the year to March 31.

*Diagram of `yearend()` function with April as the first month of the year.*



Transaction 8199 takes place on April 23, 2021. Because the `yearend()` function sets the start of the year to April 1, it returns March 31, 2022 as the 'year\_end' value for the transaction.

### Example 4 – Chart object example

Load script and chart expression

#### Overview

The same dataset and scenario as the first example are used.

However, in this example, the dataset is unchanged and loaded into the application. The calculation that returns the end date timestamp of the year in which a transaction took place is created as a measure in a chart object of the application.

#### Load script

Transactions:

Load

\*

Inline

[

id,date,amount

8188,01/13/2020,37.23

8189,02/26/2020,17.17

8190,03/27/2020,88.27

8191,04/16/2020,57.42

8192,05/21/2020,53.80

8193,08/14/2020,82.06

8194,10/07/2020,40.39

8195,12/05/2020,87.21

8196,01/22/2021,95.93

```

8197,02/03/2021,45.89
8198,03/17/2021,36.23
8199,04/23/2021,25.66
8200,05/04/2021,82.77
8201,06/30/2021,69.98
8202,07/26/2021,76.11
8203,12/27/2021,25.12
8204,06/06/2022,46.23
8205,07/18/2022,84.21
8206,11/14/2022,96.24
8207,12/12/2022,67.67
];

```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- id
- date

To calculate in which year a transaction took place, create the following measures:

- =yearend(date)
- =timestamp(yearend(date))

Results table


id	date	=yearend(date)	=timestamp(yearend(date))
8188	01/13/2020	12/31/2020	12/31/2020 11:59:59 PM
8189	02/26/2020	12/31/2020	12/31/2020 11:59:59 PM
8190	03/27/2020	12/31/2020	12/31/2020 11:59:59 PM
8191	04/16/2020	12/31/2020	12/31/2020 11:59:59 PM
8192	05/21/2020	12/31/2020	12/31/2020 11:59:59 PM
8193	08/14/2020	12/31/2020	12/31/2020 11:59:59 PM
8194	10/07/2020	12/31/2020	12/31/2020 11:59:59 PM
8195	12/05/2020	12/31/2020	12/31/2020 11:59:59 PM
8196	01/22/2021	12/31/2021	12/31/2021 11:59:59 PM
8197	02/03/2021	12/31/2021	12/31/2021 11:59:59 PM
8198	03/17/2021	12/31/2021	12/31/2021 11:59:59 PM
8199	04/23/2021	12/31/2021	12/31/2021 11:59:59 PM
8200	05/04/2021	12/31/2021	12/31/2021 11:59:59 PM
8201	06/30/2021	12/31/2021	12/31/2021 11:59:59 PM

id	date	=yearend(date)	=timestamp(yearend(date))
8202	07/26/2021	12/31/2021	12/31/2021 11:59:59 PM
8203	12/27/2021	12/31/2021	12/31/2021 11:59:59 PM
8204	06/06/2022	12/31/2022	12/31/2022 11:59:59 PM
8205	07/18/2022	12/31/2022	12/31/2022 11:59:59 PM
8206	11/14/2022	12/31/2022	12/31/2022 11:59:59 PM
8207	12/12/2022	12/31/2022	12/31/2022 11:59:59 PM

The 'end\_of\_year' measure is created in the chart object by using the yearend() function and passing the date field as the function's argument.

The yearend() function initially identifies which year the date value falls into returning a timestamp for the last millisecond of that year.

*Diagram of yearend() function that shows Transaction 8199 took place in April.*



Transaction 8199 takes place on April 23, 2021. The yearend() function returns the last millisecond of that year, which is December 31 at 11:59:59 PM.

### Example 5 – Scenario

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset is loaded into a table called 'Employee\_Expenses'. The table contains the following fields:
  - employee IDs
  - employee name
  - average daily expense claims of each employee

The end user would like a chart object that displays, by employee id and employee name, the estimated expense claims still to be incurred for the remainder of the year. The financial year begins in January.

### Load script

```
Employee_Expenses:
Load
*
Inline
[
employee_id,employee_name,avg_daily_claim
182,Mark, $15
183,Deryck, $12.5
184,Dexter, $12.5
185,Sydney,$27
186,Agatha,$18
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- employee\_id
- employee\_name

To calculate the projected expense claims, create the following measure:

```
=(yearend(today(1))-today(1))*avg_daily_claim
```

Set the measure's **Number Formatting** to **Money**.

Results table

employee_id	employee_name	=(yearend(today(1))-today(1))*avg_daily_claim
182	Mark	\$3240.00
183	Deryck	\$2700.00
184	Dexter	\$2700.00
185	Sydney	\$5832.00
186	Agatha	\$3888.00


By using today's date as its only argument, the `yearend()` function returns the end date of the current year. Then, by subtracting today's date from the year end date, the expression returns the number of days remaining in this year.

This value is then multiplied by the average daily expense claim by each employee to calculate the estimated value of claims each employee is expected to make in the remaining year.

### yearname

This function returns a four-digit year as display value with an underlying numeric value corresponding to a timestamp of the first millisecond of the first day of the year containing **date**.


Diagram of range of time of the `yearname()` function.



The `yearname()` function is different to the `year()` function as it lets you offset the date you want evaluated and lets you set the first month of the year.

If the first month of the year is not January, the function will return the two four-digit years across the twelve month period that contain the date. For example, if the start of the year is April and the date being evaluated is 06/30/2020, the result returned would be 2020-2021.

Diagram of `yearname()` function with April set as the first month of the year.



### Syntax:

```
YearName (date[, period_no[, first_month_of_year]] )
```

**Return data type:** dual

Argument	Description
<b>date</b>	The date or timestamp to evaluate.
<b>period_no</b>	<b>period_no</b> is an integer, where the value 0 indicates the year which contains <b>date</b> . Negative values in <b>period_no</b> indicate preceding years and positive values indicate succeeding years.
<b>first_month_of_year</b>	If you want to work with (fiscal) years not starting in January, indicate a value between 2 and 12 in <b>first_month_of_year</b> . The display value will then be a string showing two years.

You can use the following values to set the first month of year in the `first_month_of_year` argument:

first\_month\_of\_year values

Month	Value
February	2
March	3
April	4
May	5
June	6
July	7
August	8
September	9
October	10
November	11
December	12

### When to use it

The `yearname()` function is useful for comparing aggregations by year. For example, if you want to see the total sales of products by year.

These dimensions can be created in the load script by using the function to create a field in a Master Calendar table. They can also be created in a chart as calculated dimensions

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

#### Function examples

Example	Result
<code>yearname('10/19/2001')</code>	Returns '2001.'
<code>yearname('10/19/2001', -1)</code>	Returns '2000.'
<code>yearname('10/19/2001', 0, 4)</code>	Returns '2001-2002.'



### Related topics

Topic	Description
<i>year</i> ( <i>page</i> 1132)	This function returns an integer representing the year when the expression is interpreted as a date according to the standard number interpretation.

### Example 1 – No additional arguments

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions between 2020 and 2022 is loaded into a table called 'transactions'.
- The `DateFormat` system variable which is set to 'MM/DD/YYYY'.
- A preceding load that uses the `yearname()` and which is set as the `year_name` field.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
Load
  *,
  yearname(date) as year_name
;
```

```
Load
*
```

```
Inline
```

```
[
id,date,amount
8188,'01/13/2020',37.23
8189,'02/26/2020',17.17
8190,'03/27/2020',88.27
8191,'04/16/2020',57.42
8192,'05/21/2020',53.80
8193,'08/14/2020',82.06
8194,'10/07/2020',40.39
8195,'12/05/2020',87.21
8196,'01/22/2021',95.93
8197,'02/03/2021',45.89
8198,'03/17/2021',36.23
8199,'04/23/2021',25.66
8200,'05/04/2021',82.77
8201,'06/30/2021',69.98
8202,'07/26/2021',76.11
```

```
8203, '12/27/2021', 25.12
8204, '06/06/2022', 46.23
8205, '07/18/2022', 84.21
8206, '11/14/2022', 96.24
8207, '12/12/2022', 67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- year\_name

Results table


<b>date</b>	<b>year_name</b>
01/13/2020	2020
02/26/2020	2020
03/27/2020	2020
04/16/2020	2020
05/21/2020	2020
08/14/2020	2020
10/07/2020	2020
12/05/2020	2020
01/22/2021	2021
02/03/2021	2021
03/17/2021	2021
04/23/2021	2021
05/04/2021	2021
06/30/2021	2021
07/26/2021	2021
12/27/2021	2021
06/06/2022	2022
07/18/2022	2022
11/14/2022	2022
12/12/2022	2022

## 8 Script and chart functions

The 'year\_name' field is created in the preceding load statement by using the `yearname()` function and passing the date field as the function's argument.

The `yearname()` function identifies which year the date value falls into and returns this as a four-digit year value.

*Diagram of `yearname()` function that shows 2021 as the year value.*



### Example 2 – period\_no

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions between 2020 and 2022 is loaded into a table called 'Transactions'.
- The DateFormat system variable which is set to 'MM/DD/YYYY'.
- A preceding load that uses the `yearname()` and which is set as the `year_name` field.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
Load
*,
yearname(date,-1) as prior_year_name
;
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
```

```
8188,'01/13/2020',37.23
```

```
8189,'02/26/2020',17.17
```

```
8190,'03/27/2020',88.27
```

```
8191,'04/16/2020',57.42
```

```
8192,'05/21/2020',53.80
```

```
8193,'08/14/2020',82.06
```

```
8194,'10/07/2020',40.39
```

```
8195,'12/05/2020',87.21
```

```
8196, '01/22/2021', 95.93
8197, '02/03/2021', 45.89
8198, '03/17/2021', 36.23
8199, '04/23/2021', 25.66
8200, '05/04/2021', 82.77
8201, '06/30/2021', 69.98
8202, '07/26/2021', 76.11
8203, '12/27/2021', 25.12
8204, '06/06/2022', 46.23
8205, '07/18/2022', 84.21
8206, '11/14/2022', 96.24
8207, '12/12/2022', 67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- prior\_year\_name

Results table

date	prior_year_name
01/13/2020	2019
02/26/2020	2019
03/27/2020	2019
04/16/2020	2019
05/21/2020	2019
08/14/2020	2019
10/07/2020	2019
12/05/2020	2019
01/22/2021	2020
02/03/2021	2020
03/17/2021	2020
04/23/2021	2020
05/04/2021	2020
06/30/2021	2020
07/26/2021	2020
12/27/2021	2020
06/06/2022	2021

date	prior_year_name
07/18/2022	2021
11/14/2022	2021
12/12/2022	2021

Because a `period_no` of `-1` is used as the offset argument in the `yearname()` function, the function first identifies the year that the transactions take place in. The function then shifts one year prior and returns the resulting year.

Diagram of `yearname()` function with the `period_no` set `-1`.



### Example 3 – first\_month\_of\_year

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same dataset from the first example.
- The `DateFormat` system variable which is set to `'MM/DD/YYYY'`.
- A preceding load that uses the `yearname()` and which is set as the `year_name` field.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
Load
  *,
  yearname(date,0,4) as year_name
;
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
```

```
8188, '01/13/2020', 37.23
8189, '02/26/2020', 17.17
8190, '03/27/2020', 88.27
8191, '04/16/2020', 57.42
8192, '05/21/2020', 53.80
8193, '08/14/2020', 82.06
8194, '10/07/2020', 40.39
8195, '12/05/2020', 87.21
8196, '01/22/2021', 95.93
8197, '02/03/2021', 45.89
8198, '03/17/2021', 36.23
8199, '04/23/2021', 25.66
8200, '05/04/2021', 82.77
8201, '06/30/2021', 69.98
8202, '07/26/2021', 76.11
8203, '12/27/2021', 25.12
8204, '06/06/2022', 46.23
8205, '07/18/2022', 84.21
8206, '11/14/2022', 96.24
8207, '12/12/2022', 67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- id
- date
- year\_name

Results table


date	year_name
01/13/2020	2019-2020
02/26/2020	2019-2020
03/27/2020	2019-2020
04/16/2020	2020-2021
05/21/2020	2020-2021
08/14/2020	2020-2021
10/07/2020	2020-2021
12/05/2020	2020-2021
01/22/2021	2020-2021
02/03/2021	2020-2021
03/17/2021	2020-2021

date	year_name
04/23/2021	2021-2022
05/04/2021	2021-2022
06/30/2021	2021-2022
07/26/2021	2021-2022
12/27/2021	2021-2022
06/06/2022	2022-2023
07/18/2022	2022-2023
11/14/2022	2022-2023
12/12/2022	2022-2023

Because the `first_month_of_year` argument of 4 is used in the `yearname()` function, the start of the year moves from January 1 to April 1. Therefore, each twelve month period crosses two calendar years and the `yearname()` function returns the two four-digit years for dates evaluated.

Transaction 8198 takes place on March 17, 2021. The `yearname()` function sets the beginning of the year on April 1 and the ending on March 30. Therefore, transaction 8198 occurred in the year period from April 1, 2020 and March 30, 2021. As a result, the `yearname()` function returns the value 2020-2021.

*Diagram of `yearname()` function with March set as the first month of the year.*



## Example 4 – Chart object example

Load script and chart expression

### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same dataset from the first example.
- The `DateFormat` system variable which is set to 'MM/DD/YYYY'.

However, the field that returns the year that the transaction took place in is created as a measure in a chart object.

### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
```

```
8188,'01/13/2020',37.23
```

```
8189,'02/26/2020',17.17
```

```
8190,'03/27/2020',88.27
```

```
8191,'04/16/2020',57.42
```

```
8192,'05/21/2020',53.80
```

```
8193,'08/14/2020',82.06
```

```
8194,'10/07/2020',40.39
```

```
8195,'12/05/2020',87.21
```

```
8196,'01/22/2021',95.93
```

```
8197,'02/03/2021',45.89
```

```
8198,'03/17/2021',36.23
```

```
8199,'04/23/2021',25.66
```

```
8200,'05/04/2021',82.77
```

```
8201,'06/30/2021',69.98
```

```
8202,'07/26/2021',76.11
```

```
8203,'12/27/2021',25.12
```

```
8204,'06/06/2022',46.23
```

```
8205,'07/18/2022',84.21
```

```
8206,'11/14/2022',96.24
```

```
8207,'12/12/2022',67.67
```

```
];
```

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension:

```
date
```

To calculate the 'year\_name' field, create this measure:

```
=yearname(date)
```

Results table

<b>date</b>	<b>=yearname(date)</b>
01/13/2020	2020
02/26/2020	2020
03/27/2020	2020
04/16/2020	2020




date	=yearname(date)
05/21/2020	2020
08/14/2020	2020
10/07/2020	2020
12/05/2020	2020
01/22/2021	2021
02/03/2021	2021
03/17/2021	2021
04/23/2021	2021
05/04/2021	2021
06/30/2021	2021
07/26/2021	2021
12/27/2021	2021
06/06/2022	2022
07/18/2022	2022
11/14/2022	2022
12/12/2022	2022

The 'year\_name' measure is created in the chart object using the yearname() function and passing the date field as the function's argument.

The yearname() function identifies which year the date value falls into and returns this as a four-digit year value.

*Diagram of yearname() function with 2021 as the year value.*



### Example 5 – Scenario

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same dataset from the first example.
- The `DateFormat` system variable which is set to 'MM/DD/YYYY'.

The end user would like a chart that presents the total sales by quarter for the transactions. Use the `yearname()` function as a calculated dimension to create this chart when the `yearname()` dimension is not available in the data model.

### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
```

```
8188,'01/13/2020',37.23
```

```
8189,'02/26/2020',17.17
```

```
8190,'03/27/2020',88.27
```

```
8191,'04/16/2020',57.42
```

```
8192,'05/21/2020',53.80
```

```
8193,'08/14/2020',82.06
```

```
8194,'10/07/2020',40.39
```

```
8195,'12/05/2020',87.21
```

```
8196,'01/22/2021',95.93
```

```
8197,'02/03/2021',45.89
```

```
8198,'03/17/2021',36.23
```

```
8199,'04/23/2021',25.66
```

```
8200,'05/04/2021',82.77
```

```
8201,'06/30/2021',69.98
```

```
8202,'07/26/2021',76.11
```

```
8203,'12/27/2021',25.12
```

```
8204,'06/06/2022',46.23
```

```
8205,'07/18/2022',84.21
```

```
8206,'11/14/2022',96.24
```

```
8207,'12/12/2022',67.67
```

```
];
```

### Results

Load the data and open a sheet. Create a new table.

To compare aggregations by year, create this calculated dimension:

```
=yearname(date)
```

Create this measure:

```
=sum(amount)
```

Set the measure's **Number Formatting** to **Money**.

Results table

<b>yearname(date)</b>	<b>=sum(amount)</b>
2020	\$463.55
2021	\$457.69
2022	\$294.35

## yearstart

This function returns a timestamp corresponding to the start of the first day of the year containing **date**. The default output format will be the **DateFormat** set in the script.

### Syntax:

```
YearStart(date[, period_no[, first_month_of_year]])
```

In other words, the `yearstart()` function determines which year the date falls into. It then returns a timestamp, in date format, for the first millisecond of that year. The first month of the year is, by default, January; however, you can change which month is set as first by using the `first_month_of_year` argument in the `yearstart()` function.

*Diagram of `yearstart()` function that shows the range of time that the function can cover.*



### When to use it

The `yearstart()` function is used as part of an expression when you want the calculation to use the fraction of the year that has elapsed thus far. For example, if you want to calculate the interest that has accumulated in a year to date.

**Return data type:** dual

### Arguments

<b>Argument</b>	<b>Description</b>
<b>date</b>	The date or timestamp to evaluate.
<b>period_no</b>	<b>period_no</b> is an integer, where the value 0 indicates the year which contains <b>date</b> . Negative values in <b>period_no</b> indicate preceding years and positive values indicate succeeding years.
<b>first_month_of_year</b>	If you want to work with (fiscal) years not starting in January, indicate a value between 2 and 12 in <b>first_month_of_year</b> .

The following months can be used in the `first_month_of_year` argument:

first\_month\_of\_year values

Month	Value
February	2
March	3
April	4
May	5
June	6
July	7
August	8
September	9
October	10
November	11
December	12

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET DateFormat` statement in your data load script. The default date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

#### Function examples

Example	Result
<code>yearstart('10/19/2001')</code>	Returns 01/01/2001 00:00:00.
<code>yearstart('10/19/2001', -1)</code>	Returns 01/01/2000 00:00:00.
<code>yearstart('10/19/2001', 0, 4)</code>	Returns 04/01/2001 00:00:00.

### Example 1 – Basic example

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions between 2020 and 2022 is loaded into a table called 'transactions'.
- The date field has been provided in the `DateFormat` system variable (MM/DD/YYYY) format.
- A preceding load statement which contains the following:
  - `yearstart()` function which is set as the `year_start` field.
  - `timestamp()` function which is set as the `year_start_timestamp` field

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

Transactions:

```
Load
    *,
    yearstart(date) as year_start,
    timestamp(yearstart(date)) as year_start_timestamp
;

Load
*
Inline
[
id,date,amount
8188,01/13/2020,37.23
8189,02/26/2020,17.17
8190,03/27/2020,88.27
8191,04/16/2020,57.42
8192,05/21/2020,53.80
8193,08/14/2020,82.06
8194,10/07/2020,40.39
8195,12/05/2020,87.21
8196,01/22/2021,95.93
8197,02/03/2021,45.89
8198,03/17/2021,36.23
8199,04/23/2021,25.66
8200,05/04/2021,82.77
8201,06/30/2021,69.98
8202,07/26/2021,76.11
8203,12/27/2021,25.12
8204,06/06/2022,46.23
8205,07/18/2022,84.21
8206,11/14/2022,96.24
```

```
8207,12/12/2022,67.67  
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- id
- date
- year\_start
- year\_start\_timestamp

Results table

id	date	year_start	year_start_timestamp
8188	01/13/2020	01/01/2020	1/1/2020 12:00:00 AM
8189	02/26/2020	01/01/2020	1/1/2020 12:00:00 AM
8190	03/27/2020	01/01/2020	1/1/2020 12:00:00 AM
8191	04/16/2020	01/01/2020	1/1/2020 12:00:00 AM
8192	05/21/2020	01/01/2020	1/1/2020 12:00:00 AM
8193	08/14/2020	01/01/2020	1/1/2020 12:00:00 AM
8194	10/07/2020	01/01/2020	1/1/2020 12:00:00 AM
8195	12/05/2020	01/01/2020	1/1/2020 12:00:00 AM
8196	01/22/2021	01/01/2021	1/1/2021 12:00:00 AM
8197	02/03/2021	01/01/2021	1/1/2021 12:00:00 AM
8198	03/17/2021	01/01/2021	1/1/2021 12:00:00 AM
8199	04/23/2021	01/01/2021	1/1/2021 12:00:00 AM
8200	05/04/2021	01/01/2021	1/1/2021 12:00:00 AM
8201	06/30/2021	01/01/2021	1/1/2021 12:00:00 AM
8202	07/26/2021	01/01/2021	1/1/2021 12:00:00 AM
8203	12/27/2021	01/01/2021	1/1/2021 12:00:00 AM
8204	06/06/2022	01/01/2022	1/1/2022 12:00:00 AM
8205	07/18/2022	01/01/2022	1/1/2022 12:00:00 AM
8206	11/14/2022	01/01/2022	1/1/2022 12:00:00 AM
8207	12/12/2022	01/01/2022	1/1/2022 12:00:00 AM


The 'year\_start' field is created in the preceding load statement by using the `yearstart()` function and passing the date field as the function's argument.

## 8 Script and chart functions

---

The `yearstart()` function initially identifies which year the date value falls into and returns a timestamp for the first millisecond of that year.

*Diagram of the `yearstart()` function and transaction 8199.*



Transaction 8199 took place on April 23, 2021. The `yearstart()` function returns the first millisecond of that year, which is January 1 at 12:00:00 AM.

### Example 2 – `period_no`

Load script and results

#### Overview

The same dataset and scenario as the first example are used.

However, in this example, the task is to create a field, 'previous\_year\_start', that returns the start date timestamp of the year prior to the year in which a transaction took place.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

Transactions:

```
Load
    *,
    yearstart(date,-1) as previous_year_start,
    timestamp(yearstart(date,-1)) as previous_year_start_timestamp
;
```

Load

\*

Infile

[

id,date,amount

8188,01/13/2020,37.23

8189,02/26/2020,17.17

8190,03/27/2020,88.27

8191,04/16/2020,57.42

8192,05/21/2020,53.80

8193,08/14/2020,82.06

8194,10/07/2020,40.39

8195,12/05/2020,87.21

8196,01/22/2021,95.93

8197,02/03/2021,45.89

8198,03/17/2021,36.23

8199,04/23/2021,25.66

8200,05/04/2021,82.77

```
8201,06/30/2021,69.98
8202,07/26/2021,76.11
8203,12/27/2021,25.12
8204,06/06/2022,46.23
8205,07/18/2022,84.21
8206,11/14/2022,96.24
8207,12/12/2022,67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- id
- date
- previous\_year\_start
- previous\_year\_start\_timestamp

Results table


id	date	previous_year_start	previous_year_start_timestamp
8188	01/13/2020	01/01/2019	1/1/2019 12:00:00 AM
8189	02/26/2020	01/01/2019	1/1/2019 12:00:00 AM
8190	03/27/2020	01/01/2019	1/1/2019 12:00:00 AM
8191	04/16/2020	01/01/2019	1/1/2019 12:00:00 AM
8192	05/21/2020	01/01/2019	1/1/2019 12:00:00 AM
8193	08/14/2020	01/01/2019	1/1/2019 12:00:00 AM
8194	10/07/2020	01/01/2019	1/1/2019 12:00:00 AM
8195	12/05/2020	01/01/2019	1/1/2019 12:00:00 AM
8196	01/22/2021	01/01/2020	1/1/2020 12:00:00 AM
8197	02/03/2021	01/01/2020	1/1/2020 12:00:00 AM
8198	03/17/2021	01/01/2020	1/1/2020 12:00:00 AM
8199	04/23/2021	01/01/2020	1/1/2020 12:00:00 AM
8200	05/04/2021	01/01/2020	1/1/2020 12:00:00 AM
8201	06/30/2021	01/01/2020	1/1/2020 12:00:00 AM
8202	07/26/2021	01/01/2020	1/1/2020 12:00:00 AM
8203	12/27/2021	01/01/2020	1/1/2020 12:00:00 AM
8204	06/06/2022	01/01/2021	1/1/2021 12:00:00 AM
8205	07/18/2022	01/01/2021	1/1/2021 12:00:00 AM



id	date	previous_year_start	previous_year_start_timestamp
8206	11/14/2022	01/01/2021	1/1/2021 12:00:00 AM
8207	12/12/2022	01/01/2021	1/1/2021 12:00:00 AM

In this instance, because a `period_no` of -1 is used as the offset argument in the `yearstart()` function, the function first identifies the year that the transactions take place in. It then looks one year prior and identifies the first millisecond of that year.

Diagram of the `yearstart()` function with a `period_no` of -1.



Transaction 8199 took place on April 23, 2021. The `yearstart()` function returns the first millisecond of the prior year, January 1, 2020 at 12:00:00 AM, for the 'previous\_year\_start' field.

### Example 3 – first\_month\_of\_year

Load script and results

#### Overview

The same dataset and scenario as the first example are used.

However, in this example, the company policy is for the year to begin from April 1.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
Load
*,
yearstart(date,0,4) as year_start,
timestamp(yearstart(date,0,4)) as year_start_timestamp
;
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
```

```
8188,01/13/2020,37.23
```

```
8189,02/26/2020,17.17
```

```
8190,03/27/2020,88.27
```

```
8191,04/16/2020,57.42
```

```
8192,05/21/2020,53.80
```

```
8193,08/14/2020,82.06
8194,10/07/2020,40.39
8195,12/05/2020,87.21
8196,01/22/2021,95.93
8197,02/03/2021,45.89
8198,03/17/2021,36.23
8199,04/23/2021,25.66
8200,05/04/2021,82.77
8201,06/30/2021,69.98
8202,07/26/2021,76.11
8203,12/27/2021,25.12
8204,06/06/2022,46.23
8205,07/18/2022,84.21
8206,11/14/2022,96.24
8207,12/12/2022,67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- id
- date
- year\_start
- year\_start\_timestamp

Results table

id	date	year_start	year_start_timestamp
8188	01/13/2020	04/01/2019	4/1/2019 12:00:00 AM
8189	02/26/2020	04/01/2019	4/1/2019 12:00:00 AM
8190	03/27/2020	04/01/2019	4/1/2019 12:00:00 AM
8191	04/16/2020	04/01/2020	4/1/2020 12:00:00 AM
8192	05/21/2020	04/01/2020	4/1/2020 12:00:00 AM
8193	08/14/2020	04/01/2020	4/1/2020 12:00:00 AM
8194	10/07/2020	04/01/2020	4/1/2020 12:00:00 AM
8195	12/05/2020	04/01/2020	4/1/2020 12:00:00 AM
8196	01/22/2021	04/01/2020	4/1/2020 12:00:00 AM
8197	02/03/2021	04/01/2020	4/1/2020 12:00:00 AM
8198	03/17/2021	04/01/2020	4/1/2020 12:00:00 AM
8199	04/23/2021	04/01/2021	4/1/2021 12:00:00 AM
8200	05/04/2021	04/01/2021	4/1/2021 12:00:00 AM

id	date	year_start	year_start_timestamp
8201	06/30/2021	04/01/2021	4/1/2021 12:00:00 AM
8202	07/26/2021	04/01/2021	4/1/2021 12:00:00 AM
8203	12/27/2021	04/01/2021	4/1/2021 12:00:00 AM
8204	06/06/2022	04/01/2022	4/1/2022 12:00:00 AM
8205	07/18/2022	04/01/2022	4/1/2022 12:00:00 AM
8206	11/14/2022	04/01/2022	4/1/2022 12:00:00 AM
8207	12/12/2022	04/01/2022	4/1/2022 12:00:00 AM

In this instance, because the `first_month_of_year` argument of 4 is used in the `yearstart()` function, it sets the first day of the year to April 1, and the last day of the year to March 31.

*Diagram of the `yearstart()` function with the first month set as April.*



Transaction 8199 took place on April 23, 2021. Because the `yearstart()` function sets the start of the year to April 1 and returns it as the 'year\_start' value for the transaction.

### Example 4 – Chart object example

Load script and chart expression

#### Overview

The same dataset and scenario as the first example are used.

However, in this example, the dataset is unchanged and loaded into the application. The calculation that returns the start date timestamp of the year in which a transaction took place is created as a measure in a chart object of the application.

#### Load script

Transactions:

Load

\*

Inline

[

id,date,amount

8188,01/13/2020,37.23

8189,02/26/2020,17.17

8190,03/27/2020,88.27

```
8191,04/16/2020,57.42
8192,05/21/2020,53.80
8193,08/14/2020,82.06
8194,10/07/2020,40.39
8195,12/05/2020,87.21
8196,01/22/2021,95.93
8197,02/03/2021,45.89
8198,03/17/2021,36.23
8199,04/23/2021,25.66
8200,05/04/2021,82.77
8201,06/30/2021,69.98
8202,07/26/2021,76.11
8203,12/27/2021,25.12
8204,06/06/2022,46.23
8205,07/18/2022,84.21
8206,11/14/2022,96.24
8207,12/12/2022,67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- id
- date

To calculate in which year a transaction took place, create the following measures:

- =yearstart(date)
- =timestamp(yearstart(date))

Results table


id	date	=yearstart(date)	=timestamp(yearstart(date))
8188	06/06/2022	01/01/2022	1/1/2022 12:00:00 AM
8189	07/18/2022	01/01/2022	1/1/2022 12:00:00 AM
8190	11/14/2022	01/01/2022	1/1/2022 12:00:00 AM
8191	12/12/2022	01/01/2022	1/1/2022 12:00:00 AM
8192	01/22/2021	01/01/2021	1/1/2021 12:00:00 AM
8193	02/03/2021	01/01/2021	1/1/2021 12:00:00 AM
8194	03/17/2021	01/01/2021	1/1/2021 12:00:00 AM
8195	04/23/2021	01/01/2021	1/1/2021 12:00:00 AM
8196	05/04/2021	01/01/2021	1/1/2021 12:00:00 AM
8197	06/30/2021	01/01/2021	1/1/2021 12:00:00 AM
8198	07/26/2021	01/01/2021	1/1/2021 12:00:00 AM

id	date	=yearstart(date)	=timestamp(yearstart(date))
8199	12/27/2021	01/01/2021	1/1/2021 12:00:00 AM
8200	01/13/2020	01/01/2020	1/1/2020 12:00:00 AM
8201	02/26/2020	01/01/2020	1/1/2020 12:00:00 AM
8202	03/27/2020	01/01/2020	1/1/2020 12:00:00 AM
8203	04/16/2020	01/01/2020	1/1/2020 12:00:00 AM
8204	05/21/2020	01/01/2020	1/1/2020 12:00:00 AM
8205	08/14/2020	01/01/2020	1/1/2020 12:00:00 AM
8206	10/07/2020	01/01/2020	1/1/2020 12:00:00 AM
8207	12/05/2020	01/01/2020	1/1/2020 12:00:00 AM

The 'start\_of\_year' measure is created in the chart object by using the yearstart() function and passing the date field as the function's argument.

The yearstart() function initially identifies which year the date value falls into and returns a timestamp for the first millisecond of that year.

*Diagram of the yearstart() function and transaction 8199.*



Transaction 8199 took place on April 23, 2021. The yearstart() function returns the first millisecond of that year, which is January 1 at 12:00:00 AM.

### Example 5 – Scenario

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset is loaded into a table called 'Loans'. The table contains the following fields:
  - Loan IDs.
  - The balance at the beginning of the year.
  - The simple interest rate charged on each loan per annum.

The end user would like a chart object that displays, by loan id, the current interest that has been accrued on each loan in the year to date.

### Load script

```
Loans:
Load
*
Inline
[
loan_id,start_balance,rate
8188,$10000.00,0.024
8189,$15000.00,0.057
8190,$17500.00,0.024
8191,$21000.00,0.034
8192,$90000.00,0.084
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- loan\_id
- start\_balance

To calculate the accumulated interest, create the following measure:

```
=start_balance*(rate*(today(1)-yearstart(today(1)))/365)
```

Set the measure's **Number Formatting** to **Money**.

Results table

loan_id	start_balance	=start_balance*(rate*(today(1)-yearstart(today(1)))/365)
8188	\$10000.00	\$39.73
8189	\$15000.00	\$339.66
8190	\$17500.00	\$166.85
8191	\$21000.00	\$283.64
8192	\$90000.00	\$3003.29

The `yearstart()` function, using today's date as its only argument, returns the start date of the current year. By subtracting that result from the current date, the expression returns the number of days that have elapsed so far this year.

This value is then multiplied by the interest rate and divided by 365 to return the effective interest rate for the period. The effective interest rate for the period is then multiplied by the starting balance of the loan to return the interest that has been accrued so far this year.

## yeartodate

This function finds if the input timestamp falls within the year of the date the script was last loaded, and returns True if it does, False if it does not.

### Syntax:


```
YearToDate(timestamp[ , yearoffset [ , firstmonth [ , todaydate] ] ])
```

**Return data type:** Boolean



*In Qlik Sense, the Boolean true value is represented by -1, and the false value is represented by 0.*

Example diagram of `yeartodate()` function



If none of the optional parameters are used, the year to date means any date within one calendar year from January 1 up to and including the date of the last script execution.

In other words, the `yeartodate()` function, when triggered with no additional parameters, is used to evaluate a timestamp and return a Boolean result based on whether the date occurred within the calendar year up to and including the date that the reload took place.

However, it is also possible to supersede the start date of the year using the `firstmonth` argument, as well as to make comparisons with preceding or following years using the `yearoffset` argument.

Finally, in instances of historical datasets, the `yeartodate()` function provides a parameter to set `todaydate`, which will instead compare the timestamp to the calendar year up to and including the date provided in the `todaydate` argument.

### Arguments

Argument	Description
timestamp	The timestamp to evaluate, for example '10/12/2012'.

Argument	Description
yearoffset	By specifying a <b>yearoffset</b> , <b>yeartodate</b> returns True for the same period in another year. A negative <b>yearoffset</b> indicates a previous year, a positive offset a future year. The most recent year-to-date is achieved by specifying yearoffset = -1. If omitted, 0 is assumed.
firstmonth	By specifying a <b>firstmonth</b> between 1 and 12 (1 if omitted), the beginning of the year may be moved forward to the first day of any month. For example, if you want to work with a fiscal year beginning on May 1, specify <b>firstmonth</b> = 5. A value of 1 would indicate a fiscal year starting on January 1, and a value of 12 would indicate a fiscal year starting on December 1.
todaydate	By specifying a <b>todaydate</b> (timestamp of the last script execution if omitted) it is possible to move the day used as the upper boundary of the period.

### When to use it

The `yeartodate()` function returns a Boolean result. Typically, this type of function will be used as a condition in an if expression. This would return an aggregation or calculation dependent on whether the evaluated date occurred in the year up to and including the last reload date of the application.

For example, the `YearToDate()` function can be used to identify all equipment manufactured so far in the current year.

The following examples assume last reload time = 11/18/2011.

#### Function examples

Example	Result
<code>yeartodate( '11/18/2010')</code>	returns False
<code>yeartodate( '02/01/2011')</code>	returns True
<code>yeartodate( '11/18/2011')</code>	returns True
<code>yeartodate( '11/19/2011')</code>	returns False
<code>yeartodate( '11/19/2011', 0, 1, '12/31/2011')</code>	returns True
<code>yeartodate( '11/18/2010', -1)</code>	returns True
<code>yeartodate( '11/18/2011', -1)</code>	returns False
<code>yeartodate( '04/30/2011', 0, 5)</code>	returns False
<code>yeartodate( '05/01/2011', 0, 5)</code>	returns True

### Regional settings

Unless otherwise specified, the examples in this topic use the following date format: MM/DD/YYYY. The date format is specified in the `SET dateFormat` statement in your data load script. The default



date formatting may be different in your system, due to your regional settings and other factors. You can change the formats in the examples below to suit your requirements. Or you can change the formats in your load script to match these examples.

Default regional settings in apps are based on the regional system settings of the computer or server where Qlik Sense is installed. If the Qlik Sense server you are accessing is set to Sweden, the Data load editor will use Swedish regional settings for dates, time, and currency. These regional format settings are not related to the language displayed in the Qlik Sense user interface. Qlik Sense will be displayed in the same language as the browser you are using.

### Example 1 – Basic example

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions between 2020 and 2022, which is loaded into a table called `Transactions`.
- The date field provided in the `DateFormat` system variable (MM/DD/YYYY) format.
- The creation of a field `year_to_date`, that determines which transactions took place in the calendar year up to the date of the last reload.

At the time of writing, the date is April 26, 2022.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
  Load
    *,
    yeartodate(date) as year_to_date
  ;
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
```

```
8188,01/10/2020,37.23
```

```
8189,02/28/2020,17.17
```

```
8190,04/09/2020,88.27
```

```
8191,04/16/2020,57.42
```

```
8192,05/21/2020,53.80
```

```
8193,08/14/2020,82.06
```

```
8194,10/07/2020,40.39
```

```
8195,12/05/2020,87.21
```

```
8196,01/22/2021,95.93
```

```
8197,02/03/2021,45.89
8198,03/17/2021,36.23
8199,04/23/2021,25.66
8200,05/04/2021,82.77
8201,06/30/2021,69.98
8202,07/26/2021,76.11
8203,12/27/2021,25.12
8204,02/02/2022,46.23
8205,02/26/2022,84.21
8206,03/07/2022,96.24
8207,03/11/2022,67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:


- date
- year\_to\_date

Results table

<b>date</b>	<b>year_to_date</b>
01/10/2020	0
02/28/2020	0
04/09/2020	0
04/16/2020	0
05/21/2020	0
08/14/2020	0
10/07/2020	0
12/05/2020	0
01/22/2021	0
02/03/2021	0
03/17/2021	0
04/23/2021	0
05/04/2021	0
06/30/2021	0
07/26/2021	0
12/27/2021	0
02/02/2022	-1

date	year_to_date
02/26/2022	-1
03/07/2022	-1
03/11/2022	-1

Diagram of yeartodate() function, basic example



The `year_to_date` field is created in the preceding load statement by using the `yeartodate()` function and passing the `date` field as the function's argument.

Because no further parameters are passed into the function, the `yeartodate()` function initially identifies the reload date and therefore the boundaries for the current calendar year (starting January 1) that will return a Boolean result of `TRUE`.

Therefore, any transaction that occurs between January 1 and April 26, the reload date, will return a Boolean result of `TRUE`. Any transaction that occurs before the start of 2022 will return a Boolean result of `FALSE`.

### Example 2 – yearoffset

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same dataset and scenario as the first example.
- The creation of a field, `two_years_prior`, that determines which transactions took place a full two years before the calendar year to date.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
  Load
```

```
*,
    yeartodate(date,-2) as two_years_prior
;
Load
*
Inline
[
id,date,amount
8188,01/10/2020,37.23
8189,02/28/2020,17.17
8190,04/09/2020,88.27
8191,04/16/2020,57.42
8192,05/21/2020,53.80
8193,08/14/2020,82.06
8194,10/07/2020,40.39
8195,12/05/2020,87.21
8196,01/22/2021,95.93
8197,02/03/2021,45.89
8198,03/17/2021,36.23
8199,04/23/2021,25.66
8200,05/04/2021,82.77
8201,06/30/2021,69.98
8202,07/26/2021,76.11
8203,12/27/2021,25.12
8204,02/02/2022,46.23
8205,02/26/2022,84.21
8206,03/07/2022,96.24
8207,03/11/2022,67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- two\_years\_prior


Results table

date	two_years_prior
01/10/2020	-1
02/28/2020	-1
04/09/2020	-1
04/16/2020	-1
05/21/2020	0
08/14/2020	0
10/07/2020	0

date	two_years_prior
12/05/2020	0
01/22/2021	0
02/03/2021	0
03/17/2021	0
04/23/2021	0
05/04/2021	0
06/30/2021	0
07/26/2021	0
12/27/2021	0
02/02/2022	0
02/26/2022	0
03/07/2022	0
03/11/2022	0

By using `-2` as the `yearoffset` argument in the `yeartodate()` function, the function shifts the boundaries of the comparator calendar year segment by a full two years. Initially, the year segment equates to between January 1 and April 26, 2022. The `yearoffset` argument then offsets this segment to two years prior. The date boundaries will then fall between the January 1 and April 26, 2020.

*Diagram of `yeartodate()` function, `yearoffset` example*



Therefore, any transaction that occurs between January 1 and April 26, 2020 will return a Boolean result of `TRUE`. Any transactions that appear before or after this segment will return `FALSE`.

### Example 3 – firstmonth

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same dataset and scenario as the first example.
- The creation of a field, `year_to_date`, that determines which transactions took place in the calendar year up to the date of the last reload.

In this example, we set the start of the fiscal year to July 1.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
  Load
    *,
    yeartodate(date,0,7) as year_to_date
  ;
```

```
Load
```

```
*
```

```
Inline
```

```
[
id,date,amount
8188,01/10/2020,37.23
8189,02/28/2020,17.17
8190,04/09/2020,88.27
8191,04/16/2020,57.42
8192,05/21/2020,53.80
8193,08/14/2020,82.06
8194,10/07/2020,40.39
8195,12/05/2020,87.21
8196,01/22/2021,95.93
8197,02/03/2021,45.89
8198,03/17/2021,36.23
8199,04/23/2021,25.66
8200,05/04/2021,82.77
8201,06/30/2021,69.98
8202,07/26/2021,76.11
8203,12/27/2021,25.12
8204,02/02/2022,46.23
8205,02/26/2022,84.21
8206,03/07/2022,96.24
8207,03/11/2022,67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:


- date
- year\_to\_date

Results table

<b>date</b>	<b>year_to_date</b>
01/10/2020	0
02/28/2020	0
04/09/2020	0
04/16/2020	0
05/21/2020	0
08/14/2020	0
10/07/2020	0
12/05/2020	0
01/22/2021	0
02/03/2021	0
03/17/2021	0
04/23/2021	0
05/04/2021	0
06/30/2021	0
07/26/2021	-1
12/27/2021	-1
02/02/2022	-1
02/26/2022	-1
03/07/2022	-1
03/11/2022	-1

In this instance, because the `firstmonth` argument of 7 is used in the `yeartodate()` function, it sets the first day of the year to July 1, and the last day of the year to June 30.

Diagram of `yeartodate()` function, firstmonth example



Therefore, any transaction that occurs between July 1, 2021 and April 26, 2022, the reload date, will return a Boolean result of `TRUE`. Any transaction that occurs before July 1, 2021 will return a Boolean result of `FALSE`.

### Example 4 – todaydate

Load script and results

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- The same dataset and scenario as the first example.
- The creation of a field, `year_to_date`, that determines which transactions took place in the calendar year up to the date of the last reload.

However, in this example, we need to identify all transactions that took place in the calendar year up to and including March 1, 2022.

#### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
Load
    *,
    yeartodate(date, 0, 1, '03/01/2022') as year_to_date
;
Load
*
Inline
[
id,date,amount
8188,01/10/2020,37.23
8189,02/28/2020,17.17
8190,04/09/2020,88.27
8191,04/16/2020,57.42
8192,05/21/2020,53.80
8193,08/14/2020,82.06
```



```
8194,10/07/2020,40.39
8195,12/05/2020,87.21
8196,01/22/2021,95.93
8197,02/03/2021,45.89
8198,03/17/2021,36.23
8199,04/23/2021,25.66
8200,05/04/2021,82.77
8201,06/30/2021,69.98
8202,07/26/2021,76.11
8203,12/27/2021,25.12
8204,02/02/2022,46.23
8205,02/26/2022,84.21
8206,03/07/2022,96.24
8207,03/11/2022,67.67
];
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- date
- year\_to\_date


Results table

date	year_to_date
01/10/2020	0
02/28/2020	0
04/09/2020	0
04/16/2020	0
05/21/2020	0
08/14/2020	0
10/07/2020	0
12/05/2020	0
01/22/2021	0
02/03/2021	0
03/17/2021	0
04/23/2021	0
05/04/2021	0
06/30/2021	0
07/26/2021	0
12/27/2021	0

date	year_to_date
02/02/2022	-1
02/26/2022	-1
03/07/2022	0
03/11/2022	0

In this instance, because the `todaydate` argument of 03/01/2022 is used in the `yeartodate()` function, it sets the end boundary of the comparator calendar year segment to March 1, 2022. It is critical to provide the `firstmonth` parameter (between 1 and 12); otherwise the function will return null results.

*Diagram of `yeartodate()` function, example using `todaydate` argument*



Therefore, any transaction that occurs between January 1, 2022 and March 1, 2022, the `todaydate` parameter, will return a Boolean result of `TRUE`. Any transaction that occurs before January 1, 2022 or after March 1, 2022 will return a Boolean result of `FALSE`.

### Example 5 – Chart object example

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains the same dataset and scenario as the first example.

However, in this example, the unchanged dataset is loaded into the application. The calculation that determines which transactions took place in the calendar year up to the date of the last reload is created as a measure in a chart object of the application.

#### Load script

Transactions:

Load

\*

InLine

```
[  
id,date,amount  
8188,01/10/2020,37.23  
8189,02/28/2020,17.17  
8190,04/09/2020,88.27  
8191,04/16/2020,57.42  
8192,05/21/2020,53.80  
8193,08/14/2020,82.06  
8194,10/07/2020,40.39  
8195,12/05/2020,87.21  
8196,01/22/2021,95.93  
8197,02/03/2021,45.89  
8198,03/17/2021,36.23  
8199,04/23/2021,25.66  
8200,05/04/2021,82.77  
8201,06/30/2021,69.98  
8202,07/26/2021,76.11  
8203,12/27/2021,25.12  
8204,02/02/2022,46.23  
8205,02/26/2022,84.21  
8206,03/07/2022,96.24  
8207,03/11/2022,67.67  
];
```

### Results

Load the data and open a sheet. Create a new table and add this field as a dimension: date.

Add the following measure:

```
=yeartodate(date)
```

Results table


date	=yeartodate(date)
01/10/2020	0
02/28/2020	0
04/09/2020	0
04/16/2020	0
05/21/2020	0
08/14/2020	0
10/07/2020	0
12/05/2020	0
01/22/2021	0
02/03/2021	0
03/17/2021	0

date	=yeartodate(date)
04/23/2021	0
05/04/2021	0
06/30/2021	0
07/26/2021	0
12/27/2021	0
02/02/2022	-1
02/26/2022	-1
03/07/2022	-1
03/11/2022	-1

The `year_to_date` measure is created in the chart object by using the `yeartodate()` function and passing the `date` field as the function's argument.

Because no further parameters are passed into the function, the `yeartodate()` function initially identifies the reload date, and therefore the boundaries for the current calendar year (starting January 1) that will return a Boolean result of `TRUE`.

*Diagram of `yeartodate()` function, example using chart object*



Any transaction that occurs between January 1 and April 26, the reload date, will return a Boolean result of `TRUE`. Any transaction that occurs before the start of 2022 will return a Boolean result of `FALSE`.

### Example 6 – Scenario

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- A dataset containing a set of transactions between 2020 and 2022, which is loaded into a table called `Transactions`.
- The date field provided in the `DateFormat` system variable (MM/DD/YYYY) format.

The end user would like a KPI object that presents the total sales for the equivalent period in 2021 as the current year to date as at the last reload time.

At the time of writing, the date is June 16, 2022.

### Load script

```
SET DateFormat='MM/DD/YYYY';
```

```
Transactions:
```

```
Load
```

```
*
```

```
Inline
```

```
[
```

```
id,date,amount
```

```
8188,01/10/2020,37.23
```

```
8189,02/28/2020,17.17
```

```
8190,04/09/2020,88.27
```

```
8191,04/16/2020,57.42
```

```
8192,05/21/2020,53.80
```

```
8193,08/14/2020,82.06
```

```
8194,10/07/2020,40.39
```

```
8195,12/05/2020,87.21
```

```
8196,01/22/2021,95.93
```

```
8197,02/03/2021,45.89
```

```
8198,03/17/2021,36.23
```

```
8199,04/23/2021,25.66
```

```
8200,05/04/2021,82.77
```

```
8201,06/30/2021,69.98
```

```
8202,07/26/2021,76.11
```

```
8203,12/27/2021,25.12
```

```
8204,02/02/2022,46.23
```

```
8205,02/26/2022,84.21
```

```
8206,03/07/2022,96.24
```

```
8207,03/11/2022,67.67
```


```
];
```

### Results

#### Do the following:

1. Create a KPI object.
2. Create the following aggregation measure to calculate total sales:  
`=sum(if(yeartodate(date,-1),amount,0))`
3. Set the measure's **Number formatting** to **Money**.

*KPI yeartodate() chart for 2021*



The `yeartodate()` function returns a Boolean value when evaluating the dates of each transaction ID. Because the reload took place on June 16, 2022, the `yeartodate` function segments the year period to between 01/01/2022 and 06/16/2022. However, since a `period_no` value of -1 was used in the function, these boundaries are then shifted to the previous year. Therefore, for any transaction that occurs between 01/01/2021 and 06/16/2021, the `yeartodate()` function returns a Boolean value of `TRUE` and sums the amount.

### 8.8 Exponential and logarithmic functions

This section describes functions related to exponential and logarithmic calculations. All functions can be used in both the data load script and in chart expressions.

In the functions below, the parameters are expressions where **x** and **y** should be interpreted as real valued numbers.

#### **exp**

The natural exponential function,  $e^x$ , using the natural logarithm **e** as base. The result is a positive number.

**exp**( x )

#### **Examples and results:**

`exp(3)` returns 20.085.

#### **log**

The natural logarithm of **x**. The function is only defined if  $x > 0$ . The result is a number.

**log**( x )

### Examples and results:

`log(3)` returns 1.0986

### **log10**

The common logarithm (base 10) of **x**. The function is only defined if **x** > 0. The result is a number.

```
log10(x )
```

### Examples and results:

`log10(3)` returns 0.4771

### **pow**

Returns **x** to the power of **y**. The result is a number.

```
pow(x, y )
```

### Examples and results:

`pow(3, 3)` returns 27

### **sqr**

**x** squared (**x** to the power of 2). The result is a number.

```
sqr (x )
```

### Examples and results:

`sqr(3)` returns 9

### **sqrt**

Square root of **x**. The function is only defined if **x** >= 0. The result is a positive number.

```
sqrt(x )
```

### Examples and results:

`sqrt(3)` returns 1.732

## 8.9 Field functions

These functions can only be used in chart expressions.

Field functions either return integers or strings identifying different aspects of field selections.

### Count functions

GetAlternativeCount

**GetAlternativeCount()** is used to find the number of alternative (light gray) values in the identified field.

```
GetAlternativeCount - chart function (field_name)
```

GetExcludedCount

**GetExcludedCount()** finds the number of excluded distinct values in the identified field. Only excluded (dark gray) fields are counted. Alternative (light gray) and selected excluded (dark gray with check mark) values are not counted.

```
GetExcludedCount - chart function (page 1196) (field_name)
```

GetNotSelectedCount

This chart function returns the number of not-selected values in the field named **fieldname**. The field must be in and-mode for this function to be relevant.

```
GetNotSelectedCount - chart function(fieldname [, includeexcluded=false])
```

GetPossibleCount

**GetPossibleCount()** is used to find the number of possible values in the identified field. If the identified field includes selections, then the selected (green) fields are counted. Otherwise associated (white) values are counted.

```
GetPossibleCount - chart function(field_name)
```

GetSelectedCount

**GetSelectedCount()** finds the number of selected (green) values in a field.

```
GetSelectedCount - chart function (field_name [, include_excluded])
```

### Field and selection functions

GetCurrentSelections

**GetCurrentSelections()** returns a list of the current selections in the app. If the selections are instead made using a search string in a search box, **GetCurrentSelections()** returns the search string.

```
GetCurrentSelections - chart function([record_sep [,tag_sep [,value_sep  
[,max_values]]]])
```

GetFieldSelections

**GetFieldSelections()** returns a **string** with the current selections in a field.

```
GetFieldSelections - chart function ( field_name [, value_sep [, max_  
values]])
```



GetObjectDimension

**GetObjectDimension()** returns the name of the dimension. **Index** is an optional integer denoting the dimension that should be returned.

**GetObjectDimension** - chart function ([index])

GetObjectField

**GetObjectField()** returns the name of the dimension. **Index** is an optional integer denoting the dimension that should be returned.

**GetObjectField** - chart function ([index])

GetObjectMeasure

**GetObjectMeasure()** returns the name of the measure. **Index** is an optional integer denoting the measure that should be returned.

**GetObjectMeasure** - chart function ([index])

### GetAlternativeCount - chart function

**GetAlternativeCount()** is used to find the number of alternative (light gray) values in the identified field.

**Syntax:**

**GetAlternativeCount** (field\_name)

**Return data type:** integer

**Arguments:**

Arguments

Argument	Description
field_name	The field containing the range of data to be measured.

**Examples and results:**

The following example uses the **First name** field loaded to a filter pane.

Examples and results

Examples	Results
Given that <b>John</b> is selected in <b>First name</b> .  GetAlternativeCount ([First name])	4 as there are 4 unique and excluded (gray) values in <b>First name</b> .
Given that <b>John</b> and <b>Peter</b> are selected.  GetAlternativeCount ([First name])	3 as there are 3 unique and excluded (gray) values in <b>First name</b> .

Examples	Results
<p>Given that no values are selected in <b>First name</b>.</p> <p><code>GetAlternativeCount ([First name])</code></p>	0 as there are no selections.

Data used in example:

```
Names:
LOAD * inline [
First name|Last name|Initials|Has cellphone
John|Anderson|JA|Yes
Sue|Brown|SB|Yes
Mark|Carr|MC|No
Peter|Devonshire|PD|No
Jane|Elliot|JE|Yes
Peter|Franc|PF|Yes ] (delimiter is '|');
```

### GetCurrentSelections - chart function

**GetCurrentSelections()** returns a list of the current selections in the app. If the selections are instead made using a search string in a search box, **GetCurrentSelections()** returns the search string.

If options are used, you will need to specify `record_sep`. To specify a new line, set **record\_sep** to **chr(13)&chr(10)**.

If all but two, or all but one, values, are selected, the format 'NOT x,y' or 'NOT y' will be used respectively. If you select all values and the count of all values is greater than `max_values`, the text ALL will be returned.

#### Syntax:

```
GetCurrentSelections ([record_sep [, tag_sep [, value_sep [, max_values [, state_name]]]])
```

**Return data type:** string

#### Arguments:

##### Arguments

Arguments	Description
<code>record_sep</code>	Separator to be put between field records. The default is <CR><LF> meaning a new line.
<code>tag_sep</code>	Separator to be put between the field name tag and the field values. The default is ' '.
<code>value_sep</code>	The separator to be put between field values. The default is ','.

Arguments	Description
max_values	The maximum number of field values to be individually listed. When a larger number of values is selected, the format 'x of y values' will be used instead. The default is 6.
state_name	The name of an alternate state that has been chosen for the specific visualization. If the <b>state_name</b> argument is used, only the selections associated with the specified state name are taken into account.

### Examples and results:

The following example uses two fields loaded to different filter panes, one for **First name** name and one for **Initials**.

#### Examples and results

Examples	Results
Given that <b>John</b> is selected in <b>First name</b> . <code>GetCurrentSelections ()</code>	'First name: John'
Given that <b>John</b> and <b>Peter</b> are selected in <b>First name</b> . <code>GetCurrentSelections ()</code>	'First name: John, Peter'
Given that <b>John</b> and <b>Peter</b> are selected in <b>First name</b> and <b>JA</b> is selected in <b>Initials</b> . <code>GetCurrentSelections ()</code>	'First name: John, Peter Initials: JA'
Given that <b>John</b> is selected in <b>First name</b> and <b>JA</b> is selected in <b>Initials</b> . <code>GetCurrentSelections ( chr(13)&amp;chr(10) , ' = ' )</code>	'First name = John Initials = JA'
Given that you have selected all names except Sue in <b>First name</b> and no selections in <b>Initials</b> . <code>GetCurrentSelections (chr(13)&amp;chr(10), '=', ',', 3)</code>	'First name=NOT Sue'

Data used in example:

```
Names:
LOAD * inline [
First name|Last name|Initials|Has cellphone
John|Anderson|JA|Yes
Sue|Brown|SB|Yes
Mark|Carr|MC|No
Peter|Devonshire|PD|No
Jane|Elliot|JE|Yes
Peter|Franc|PF|Yes ] (delimiter is '|');
```

## GetExcludedCount - chart function

**GetExcludedCount()** finds the number of excluded distinct values in the identified field. Only excluded (dark gray) fields are counted. Alternative (light gray) and selected excluded (dark gray with check mark) values are not counted.

### Syntax:

```
GetExcludedCount (field_name)
```

**Return data type:** string

### Arguments:

Arguments

Arguments	Description
field_name	The field containing the range of data to be measured.

### Examples and results:

After loading the example script below into an app, create three filter panes: one for **First name**, one for **Last name**, and one for **Initials**. Each of the example expressions in the table can be added as KPI charts.

Examples and results

Examples	Results
Given that no values are selected in <b>First name</b> .  GetExcludedCount (Initials)	Result is 0 because there are no selections.
Given that <b>John</b> is selected in <b>First name</b> .  GetExcludedCount (Initials)	Result is 5. There are 5 excluded values in <b>Initials</b> with dark gray color. The <b>JA</b> value will be white as it is associated with the selection <b>John</b> in <b>First name</b> .
Given that <b>John</b> and <b>Peter</b> are selected.  GetExcludedCount (Initials)	Result is 3. <b>John</b> is associated with 1 value and <b>Peter</b> is associated with 2 values, in <b>Initials</b> .
Given that <b>John</b> and <b>Peter</b> are selected in <b>First name</b> , and then <b>Francois</b> is selected in <b>Last name</b> .  GetExcludedCount ([First name])	Result is 3. There are 3 excluded values in <b>First name</b> with dark gray color. <b>GetExcludedCount()</b> only counts excluded values. Alternative and selected excluded values are not included in the count.

Examples	Results
<p>Given that <b>John</b> and <b>Peter</b> are selected in <b>First name</b>, and then <b>Franc</b> and <b>Anderson</b> are selected in <b>Last name</b>.</p> <p><code>GetExcludedCount (Initials)</code></p>	<p>Result is 4. There are 4 excluded values in <b>Initials</b> with dark gray color. The other two values (<b>JA</b> and <b>PF</b>) will be white as they are associated with the selections <b>John</b> and <b>Peter</b> in <b>First name</b>.</p>
<p>Given that <b>John</b> and <b>Peter</b> are selected in <b>First name</b>, and then <b>Franc</b> and <b>Anderson</b> are selected in <b>Last name</b>.</p> <p><code>GetExcludedCount ([Last name])</code></p>	<p>Result is 3. There are 3 excluded values in <b>Last name</b>, and they have dark gray color: <b>Brown</b>, <b>Carr</b>, and <b>Elliot</b>. The value <b>Devonshire</b> has light gray color (indicating that it is alternative), so it is not included in the count.</p>

Data used in example:

Names:

```
LOAD * inline [
First name|Last name|Initials|Has cellphone
John|Anderson|JA|Yes
Sue|Brown|SB|Yes
Mark|Carr|MC|No
Peter|Devonshire|PD|No
Jane|Elliot|JE|Yes
Peter|Franc|PF|Yes ] (delimiter is '|');
```

### GetFieldSelections - chart function

**GetFieldSelections()** returns a **string** with the current selections in a field.

If all but two, or all but one of the values are selected, the format 'NOT x,y' or 'NOT y' will be used respectively. If you select all values and the count of all values is greater than `max_values`, the text ALL will be returned.

#### Syntax:

```
GetFieldSelections ( field_name [, value_sep [, max_values [, state_name]])
```

**Return data type:** string

Return string formats

Format	Description
'a, b, c'	<p>If the number of selected values is <code>max_values</code> or less, the string returned is a list of the selected values.</p> <p>The values are separated with <code>value_sep</code> as delimiter.</p>

Format	Description
'NOT a, b, c'	If the number of non-selected values is max_values or less, the string returned is a list of the non-selected values with NOT as a prefix.  The values are separated with value_sep as delimiter.
'x of y'	x = the number of selected values  y = the total number of values  This is returned when max_values < x < ( y - max_values).
'ALL'	Returned if all values are selected.
'-'	Returned if no value is selected.
<search string>	If you have selected using search, the search string is returned.

### Arguments:

#### Arguments

Arguments	Description
field_name	The field containing the range of data to be measured.
value_sep	The separator to be put between field values. The default is ','.
max_values	The maximum number of field values to be individually listed. When a larger number of values is selected, the format 'x of y values' will be used instead. The default is 6.
state_name	The name of an alternate state that has been chosen for the specific visualization. If the <b>state_name</b> argument is used, only the selections associated with the specified state name are taken into account.

### Examples and results:

The following example uses the **First name** field loaded to a filter pane.

#### Examples and results

Examples	Results
Given that <b>John</b> is selected in <b>First name</b> .  GetFieldSelections ([First name])	'John'

Examples	Results
Given that <b>John</b> and <b>Peter</b> are selected.  getFieldSelections ([First name])	'John,Peter'
Given that <b>John</b> and <b>Peter</b> are selected.  getFieldSelections ([First name],'; ')	'John; Peter'
Given that <b>John, Sue, Mark</b> are selected in <b>First name</b> .  getFieldSelections ([First name],';',2)	'NOT Jane;Peter', because the value 2 is stated as the value of the max_values argument. Otherwise, the result would have been John; Sue; Mark.

Data used in example:

```
Names:
LOAD * inline [
First name|Last name|Initials|Has cellphone
John|Anderson|JA|Yes
Sue|Brown|SB|Yes
Mark|Carr|MC|No
Peter|Devonshire|PD|No
Jane|Elliot|JE|Yes
Peter|Franc|PF|Yes ] (delimiter is '|');
```

### GetNotSelectedCount - chart function

This chart function returns the number of not-selected values in the field named **fieldname**. The field must be in and-mode for this function to be relevant.

#### Syntax:

```
GetNotSelectedCount (fieldname [, includeexcluded=false])
```

#### Arguments:

##### Arguments

Argument	Description
fieldname	The name of the field to be evaluated.
includeexcluded	If <b>includeexcluded</b> is stated as True, the count will include selected values which are excluded by selections in another field.

#### Examples:

```
GetNotSelectedCount( Country )
```

```
GetNotSelectedCount( Country, true )
```

## GetObjectDimension - chart function

**GetObjectDimension()** returns the name of the dimension. **Index** is an optional integer denoting the dimension that should be returned.



*You cannot use this function in a chart in the following locations: title, subtitle, footer, reference line expression and min/max expression.*



*You cannot reference the name of a dimension or measure in another object using the Object ID.*

### Syntax:

```
GetObjectDimension ([index])
```

### Example:

```
GetObjectDimension(1)
```

Example: Chart expression

*Qlik Sense table showing examples of the GetObjectDimension function in a chart expression*

transacti on_date	custom er_id	transacti on_ quantity	=GetObjectDime nsion ( )	=GetObjectDime nsion (0)	=GetObjectDime nsion (1)
2018/08/3 0	049681	13	transaction_date	transaction_date	customer_id
2018/08/3 0	203521	6	transaction_date	transaction_date	customer_id
2018/08/3 0	203521	21	transaction_date	transaction_date	customer_id

If you want to return the name of a measure use the **GetObjectMeasure** function instead.

## GetObjectField - chart function

**GetObjectField()** returns the name of the dimension. **Index** is an optional integer denoting the dimension that should be returned.



*You cannot use this function in a chart in the following locations: title, subtitle, footer, reference line expression and min/max expression.*





You cannot reference the name of a dimension or measure in another object using the Object ID.

**Syntax:**

```
GetObjectField ([index])
```

**Example:**

```
GetObjectField(1)
```

Example: Chart expression

Qlik Sense table showing examples of the GetObjectField function in a chart expression.

transactio n_date	custome r_id	transactio n_quantity	=GetObjectFiel d ()	=GetObjectFiel d (0)	=GetObjectFiel d (1)
2018/08/30	049681	13	transaction_ date	transaction_ date	customer_id
2018/08/30	203521	6	transaction_ date	transaction_ date	customer_id
2018/08/30	203521	21	transaction_ date	transaction_ date	customer_id

If you want to return the name of a measure use the **GetObjectMeasure** function instead.

## GetObjectMeasure - chart function

**GetObjectMeasure()** returns the name of the measure. **Index** is an optional integer denoting the measure that should be returned.



You cannot use this function in a chart in the following locations: title, subtitle, footer, reference line expression and min/max expression.



You cannot reference the name of a dimension or measure in another object using the Object ID.

**Syntax:**

```
GetObjectMeasure ([index])
```

**Example:**

```
GetObjectMeasure(1)
```

Example: Chart expression

*Qlik Sense table showing examples of the `GetObjectMeasure` function in a chart expression*

<b>customer_id</b>	<b>sum (transaction_quantity)</b>	<b>Avg (transaction_quantity)</b>	<b>=GetObjectMeasure ()</b>	<b>=GetObjectMeasure(0)</b>	<b>=GetObjectMeasure(1)</b>
49681	13	13	sum (transaction_quantity)	sum (transaction_quantity)	Avg(transaction_quantity)
203521	27	13.5	sum (transaction_quantity)	sum (transaction_quantity)	Avg(transaction_quantity)

If you want to return the name of a dimension use the **GetObjectField** function instead.

### GetPossibleCount - chart function

**GetPossibleCount()** is used to find the number of possible values in the identified field. If the identified field includes selections, then the selected (green) fields are counted. Otherwise associated (white) values are counted.

For fields with selections **GetPossibleCount()** returns the number of selected (green) fields.

**Return data type:** integer

#### Syntax:

```
GetPossibleCount (field_name)
```

#### Arguments:

##### Arguments

<b>Arguments</b>	<b>Description</b>
field_name	The field containing the range of data to be measured.

#### Examples and results:

The following example uses two fields loaded to different filter panes, one for **First name** name and one for **Initials**.

### Examples and results


Examples	Results
Given that <b>John</b> is selected in <b>First name</b> . GetPossibleCount ([Initials])	1 as there is 1 value in Initials associated with the selection, <b>John</b> , in <b>First name</b> .
Given that <b>John</b> is selected in <b>First name</b> . GetPossibleCount ([First name])	1 as there is 1 selection, <b>John</b> , in <b>First name</b> .
Given that <b>Peteris</b> selected in <b>First name</b> . GetPossibleCount ([Initials])	2 as Peter is associated with 2 values in <b>Initials</b> .
Given that no values are selected in <b>First name</b> . GetPossibleCount ([First name])	5 as there are no selections and there are 5 unique values in <b>First name</b> .
Given that no values are selected in <b>First name</b> . GetPossibleCount ([Initials])	6 as there are no selections and there are 6 unique values in <b>Initials</b> .

Data used in example:

```
Names:
LOAD * inline [
First name|Last name|Initials|Has cellphone
John|Anderson|JA|Yes
Sue|Brown|SB|Yes
Mark|Carr|MC|No
Peter|Devonshire|PD|No
Jane|Elliot|JE|Yes
Peter|Franc|PF|Yes ] (delimiter is '|');
```

### GetSelectedCount - chart function

**GetSelectedCount()** finds the number of selected (green) values in a field.

**Syntax:**

```
GetSelectedCount (field_name [, include_excluded [, state_name]])
```

**Return data type:** integer

**Arguments:**

## Arguments

Arguments	Description
field_name	The field containing the range of data to be measured.
include_excluded	If set to <b>True()</b> , the count will include selected values, which are currently excluded by selections in other fields. If False or omitted, these values will not be included.
state_name	The name of an alternate state that has been chosen for the specific visualization. If the <b>state_name</b> argument is used, only the selections associated with the specified state name are taken into account.

**Examples and results:**

The following example uses three fields loaded to different filter panes, one for **First name** name, one for **Initials** and one for **Has cellphone**.

## Examples and results

Examples	Results
Given that <b>John</b> is selected in <b>First name</b> .  GetSelectedCount ([First name])	1 as one value is selected in <b>First name</b> .
Given that <b>John</b> is selected in <b>First name</b> .  GetSelectedCount ([Initials])	0 as no values are selected in <b>Initials</b> .
With no selections in <b>First name</b> , select all values in <b>Initials</b> and after that select the value <b>Yes</b> in <b>Has cellphone</b> .  GetSelectedCount ([Initials], True ())	6. Although selections with <b>Initials</b> values of <b>MC</b> and <b>PD</b> have <b>Has cellphone</b> set to <b>No</b> , the result is still 6, because the <code>include_excluded</code> argument is set to <code>True()</code> .

Data used in example:

Names:

```
LOAD * inline [
First name|Last name|Initials|Has cellphone
John|Anderson|JA|Yes
Sue|Brown|SB|Yes
Mark|Carr|MC|No
Peter|Devonshire|PD|No
Jane|Elliot|JE|Yes
Peter|Franc|PF|Yes ] (delimiter is '|');
```

## 8.10 File functions

The file functions (only available in script expressions) return information about the table file which is currently being read. These functions will return NULL for all data sources except table files (exception: **ConnectString()**).

### File functions overview

Each function is described further after the overview. You can also click the function name in the syntax to immediately access the details for that specific function.

#### Attribute

This script function returns the value of the meta tags of different media files as text. The following file formats are supported: MP3, WMA, WMV, PNG and JPG. If the file **filename** does not exist, is not a supported file format or does not contain a meta tag named **attributename**, NULL will be returned.

```
Attribute (filename, attributename)
```

### ConnectString

The **ConnectString()** function returns the name of the active data connection for ODBC or OLE DB connections. The function returns an empty string if no **connect** statement has been executed, or after a **disconnect** statement.

```
ConnectString ()
```

### FileBaseName

The **FileBaseName** function returns a string containing the name of the table file currently being read, without path or extension.

```
FileBaseName ()
```

### FileDir

The **FileDir** function returns a string containing the path to the directory of the table file currently being read.

```
FileDir ()
```

### FileExtension

The **FileExtension** function returns a string containing the extension of the table file currently being read.

```
FileExtension ()
```

### FileName

The **FileName** function returns a string containing the name of the table file currently being read, without path but including the extension.

```
FileName ()
```

### FilePath

The **FilePath** function returns a string containing the full path to the table file currently being read.

```
FilePath ()
```

### FileSize

The **FileSize** function returns an integer containing the size in bytes of the file filename or, if no filename is specified, of the table file currently being read.

```
FileSize ()
```

### FileTime

The **FileTime** function returns a timestamp in UTC format of the last modification of a specified file. If a file is not specified, the function returns a timestamp in UTC of the last modification of the currently read table file.

```
FileTime ([ filename ])
```

### GetFolderPath

The **GetFolderPath** function returns the value of the Microsoft Windows *SHGetFolderPath* function. This function takes as input the name of a Microsoft Windows folder and returns the full path of the folder.

```
GetFolderPath ()
```

### QvdCreateTime

This script function returns the XML-header timestamp from a QVD file, if any is present, otherwise it returns NULL. In the timestamp, time is provided in UTC.

```
QvdCreateTime (filename)
```

### QvdFieldName

This script function returns the name of field number **fieldno** in a QVD file. If the field does not exist NULL is returned.

```
QvdFieldName (filename , fieldno)
```

### QvdNoOfFields

This script function returns the number of fields in a QVD file.

```
QvdNoOfFields (filename)
```

### QvdNoOfRecords

This script function returns the number of records currently in a QVD file.

```
QvdNoOfRecords (filename)
```

### QvdTableName

This script function returns the name of the table stored in a QVD file.

```
QvdTableName (filename)
```

## Attribute

This script function returns the value of the meta tags of different media files as text. The following file formats are supported: MP3, WMA, WMV, PNG and JPG. If the file **filename** does not exist, is not a supported file format or does not contain a meta tag named **attributename**, NULL will be returned.

### Syntax:

```
Attribute (filename, attributename)
```

A large number of meta tags can be read. The examples in this topic show which tags can be read for the respective supported file types.



You can only read meta tags saved in the file according to the relevant specification, for example ID2v3 for MP3 files or EXIF for JPG files, not meta information saved in the **Windows File Explorer**.

### Arguments:

#### Arguments

Argument	Description
filename	<p>The name of a media file including path, if needed, as a folder data connection</p> <p><b>Example: 'lib://Table Files/'</b></p> <p>In legacy scripting mode, the following path formats are also supported:</p> <ul style="list-style-type: none"> <li>absolute</li> </ul> <p><b>Example: c:\data\</b></p> <ul style="list-style-type: none"> <li>relative to the Qlik Sense app working directory.</li> </ul> <p><b>Example: data\</b></p>
attributename	The name of a meta tag.

The examples use the **GetFolderPath** function to find the paths to media files. As **GetFolderPath** is only supported in legacy mode, you need to replace the references to **GetFolderPath** with a lib:// data connection path when you use this function in standard mode or in Qlik Sense SaaS.

*File system access restriction (page 1516)*

### Example 1: MP3 files

This script reads all possible MP3 meta tags in folder *MyMusic*.

```
// Script to read MP3 meta tags
for each vExt in 'mp3'
for each vFoundFile in filelist( GetFolderPath('MyMusic') & '\*.' & vExt )
FileList:
LOAD FileLongName,
    subfield(FileLongName, '\', -1) as FileShortName,
    num(FileSize(FileLongName), '# ### ### ##', ',', ',') as FileSize,
    FileTime(FileLongName) as FileTime,
    // ID3v1.0 and ID3v1.1 tags
    Attribute(FileLongName, 'Title') as Title,
    Attribute(FileLongName, 'Artist') as Artist,
    Attribute(FileLongName, 'Album') as Album,
    Attribute(FileLongName, 'Year') as Year,
    Attribute(FileLongName, 'Comment') as Comment,
    Attribute(FileLongName, 'Track') as Track,
    Attribute(FileLongName, 'Genre') as Genre,
```



```
// ID3v2.3 tags
Attribute(FileLongName, 'AENC') as AENC, // Audio encryption
Attribute(FileLongName, 'APIC') as APIC, // Attached picture
Attribute(FileLongName, 'COMM') as COMM, // Comments
Attribute(FileLongName, 'COMR') as COMR, // Commercial frame
Attribute(FileLongName, 'ENCR') as ENCR, // Encryption method registration
Attribute(FileLongName, 'EQUA') as EQUA, // Equalization
Attribute(FileLongName, 'ETCO') as ETCO, // Event timing codes
Attribute(FileLongName, 'GEOB') as GEOB, // General encapsulated object
Attribute(FileLongName, 'GRID') as GRID, // Group identification registration
Attribute(FileLongName, 'IPLS') as IPLS, // Involved people list
Attribute(FileLongName, 'LINK') as LINK, // Linked information
Attribute(FileLongName, 'MCDI') as MCDI, // Music CD identifier
Attribute(FileLongName, 'MLLT') as MLLT, // MPEG location lookup table
Attribute(FileLongName, 'OWNE') as OWNE, // Ownership frame
Attribute(FileLongName, 'PRIV') as PRIV, // Private frame
Attribute(FileLongName, 'PCNT') as PCNT, // Play counter
Attribute(FileLongName, 'POPM') as POPM, // Popularimeter
Attribute(FileLongName, 'POSS') as POSS, // Position synchronisation frame
Attribute(FileLongName, 'RBUF') as RBUF, // Recommended buffer size
Attribute(FileLongName, 'RVAD') as RVAD, // Relative volume adjustment
Attribute(FileLongName, 'RVRB') as RVRB, // Reverb
Attribute(FileLongName, 'SYLT') as SYLT, // Synchronized lyric/text
Attribute(FileLongName, 'SYTC') as SYTC, // Synchronized tempo codes
Attribute(FileLongName, 'TALB') as TALB, // Album/Movie/Show title
Attribute(FileLongName, 'TBPM') as TBPM, // BPM (beats per minute)
Attribute(FileLongName, 'TCOM') as TCOM, // Composer
Attribute(FileLongName, 'TCON') as TCON, // Content type
Attribute(FileLongName, 'TCOP') as TCOP, // Copyright message
Attribute(FileLongName, 'TDAT') as TDAT, // Date
Attribute(FileLongName, 'TDLY') as TDLY, // Playlist delay
Attribute(FileLongName, 'TENC') as TENC, // Encoded by
Attribute(FileLongName, 'TEXT') as TEXT, // Lyricist/Text writer
Attribute(FileLongName, 'TFLT') as TFLT, // File type
Attribute(FileLongName, 'TIME') as TIME, // Time
Attribute(FileLongName, 'TIT1') as TIT1, // Content group description
Attribute(FileLongName, 'TIT2') as TIT2, // Title/songname/content description
Attribute(FileLongName, 'TIT3') as TIT3, // Subtitle/Description refinement
Attribute(FileLongName, 'TKEY') as TKEY, // Initial key
Attribute(FileLongName, 'TLAN') as TLAN, // Language(s)
Attribute(FileLongName, 'TLEN') as TLEN, // Length
Attribute(FileLongName, 'TMED') as TMED, // Media type
Attribute(FileLongName, 'TOAL') as TOAL, // Original album/movie/show title
Attribute(FileLongName, 'TOFN') as TOFN, // Original filename
Attribute(FileLongName, 'TOLY') as TOLY, // Original lyricist(s)/text writer(s)
Attribute(FileLongName, 'TOPE') as TOPE, // Original artist(s)/performer(s)
Attribute(FileLongName, 'TORY') as TORY, // Original release year
Attribute(FileLongName, 'TOWN') as TOWN, // File owner/licensee
Attribute(FileLongName, 'TPE1') as TPE1, // Lead performer(s)/Soloist(s)
Attribute(FileLongName, 'TPE2') as TPE2, // Band/orchestra/accompaniment
Attribute(FileLongName, 'TPE3') as TPE3, // Conductor/performer refinement
Attribute(FileLongName, 'TPE4') as TPE4, // Interpreted, remixed, or otherwise modified by
Attribute(FileLongName, 'TPOS') as TPOS, // Part of a set
Attribute(FileLongName, 'TPUB') as TPUB, // Publisher
Attribute(FileLongName, 'TRCK') as TRCK, // Track number/Position in set
Attribute(FileLongName, 'TRDA') as TRDA, // Recording dates
```

```

Attribute(FileLongName, 'TRSN') as TRSN, // Internet radio station name
Attribute(FileLongName, 'TRSO') as TRSO, // Internet radio station owner
Attribute(FileLongName, 'TSIZ') as TSIZ, // Size
Attribute(FileLongName, 'TSRC') as TSRC, // ISRC (international standard recording code)
Attribute(FileLongName, 'TSSE') as TSSE, // Software/Hardware and settings used for
encoding
Attribute(FileLongName, 'TYER') as TYER, // Year
Attribute(FileLongName, 'TXXX') as TXXX, // User defined text information frame
Attribute(FileLongName, 'UFID') as UFID, // Unique file identifier
Attribute(FileLongName, 'USER') as USER, // Terms of use
Attribute(FileLongName, 'USLT') as USLT, // Unsynchronized lyric/text transcription
Attribute(FileLongName, 'WCOM') as WCOM, // Commercial information
Attribute(FileLongName, 'WCOP') as WCOP, // Copyright/Legal information
Attribute(FileLongName, 'WOAF') as WOAF, // Official audio file webpage
Attribute(FileLongName, 'WOAR') as WOAR, // Official artist/performer webpage
Attribute(FileLongName, 'WOAS') as WOAS, // Official audio source webpage
Attribute(FileLongName, 'WORS') as WORS, // Official internet radio station homepage
Attribute(FileLongName, 'WPAY') as WPAY, // Payment
Attribute(FileLongName, 'WPUB') as WPUB, // Publishers official webpage
Attribute(FileLongName, 'WXXX') as WXXX; // User defined URL link frame
LOAD @1:n as FileLongName Inline "$\vFoundFile)" (fix, no labels);
Next vFoundFile
Next vExt

```

### Example 2: JPEG

This script reads all possible EXIF meta tags from JPG files in folder *MyPictures*.

```

// Script to read Jpeg Exif meta tags
for each vExt in 'jpg', 'jpeg', 'jpe', 'jfif', 'jif', 'jfi'
for each vFoundFile in filelist( GetFolderPath('MyPictures') & '\*.' & vExt )
FileList:
LOAD FileLongName,
    subfield(FileLongName, '\', -1) as FileShortName,
    num(FileSize(FileLongName), '# ### ##', ',', ',') as FileSize,
    FileTime(FileLongName) as FileTime,
    // ***** Exif Main (IFD0) Attributes *****
    Attribute(FileLongName, 'ImageWidth') as ImageWidth,
    Attribute(FileLongName, 'ImageLength') as ImageLength,
    Attribute(FileLongName, 'BitsPerSample') as BitsPerSample,
    Attribute(FileLongName, 'Compression') as Compression,
    // examples: 1=uncompressed, 2=CCITT, 3=CCITT 3, 4=CCITT 4,
    // 5=LZW, 6=JPEG (old style), 7=JPEG, 8=Deflate, 32773=PackBits RLE,
    Attribute(FileLongName, 'PhotometricInterpretation') as PhotometricInterpretation,
    // examples: 0=WhiteIsZero, 1=BlackIsZero, 2=RGB, 3=Palette, 5=CMYK, 6=YCbCr,
    Attribute(FileLongName, 'ImageDescription') as ImageDescription,
    Attribute(FileLongName, 'Make') as Make,
    Attribute(FileLongName, 'Model') as Model,
    Attribute(FileLongName, 'StripOffsets') as StripOffsets,
    Attribute(FileLongName, 'Orientation') as Orientation,
    // examples: 1=TopLeft, 2=TopRight, 3=BottomRight, 4=BottomLeft,
    // 5=LeftTop, 6=RightTop, 7=RightBottom, 8=LeftBottom,
    Attribute(FileLongName, 'SamplesPerPixel') as SamplesPerPixel,
    Attribute(FileLongName, 'RowsPerStrip') as RowsPerStrip,
    Attribute(FileLongName, 'StripByteCounts') as StripByteCounts,
    Attribute(FileLongName, 'XResolution') as XResolution,

```

## 8 Script and chart functions

---

```
Attribute(FileLongName, 'YResolution') as YResolution,
Attribute(FileLongName, 'PlanarConfiguration') as PlanarConfiguration,
// examples: 1=chunky format, 2=planar format,
Attribute(FileLongName, 'ResolutionUnit') as ResolutionUnit,
// examples: 1=none, 2=inches, 3=centimeters,
Attribute(FileLongName, 'TransferFunction') as TransferFunction,
Attribute(FileLongName, 'Software') as Software,
Attribute(FileLongName, 'DateTime') as DateTime,
Attribute(FileLongName, 'Artist') as Artist,
Attribute(FileLongName, 'HostComputer') as HostComputer,
Attribute(FileLongName, 'WhitePoint') as WhitePoint,
Attribute(FileLongName, 'PrimaryChromaticities') as PrimaryChromaticities,
Attribute(FileLongName, 'YCbCrCoefficients') as YCbCrCoefficients,
Attribute(FileLongName, 'YCbCrSubSampling') as YCbCrSubSampling,
Attribute(FileLongName, 'YCbCrPositioning') as YCbCrPositioning,
// examples: 1=centered, 2=co-sited,
Attribute(FileLongName, 'ReferenceBlackWhite') as ReferenceBlackWhite,
Attribute(FileLongName, 'Rating') as Rating,
Attribute(FileLongName, 'RatingPercent') as RatingPercent,
Attribute(FileLongName, 'ThumbnailFormat') as ThumbnailFormat,
// examples: 0=Raw Rgb, 1=Jpeg,
Attribute(FileLongName, 'Copyright') as Copyright,
Attribute(FileLongName, 'ExposureTime') as ExposureTime,
Attribute(FileLongName, 'FNumber') as FNumber,
Attribute(FileLongName, 'ExposureProgram') as ExposureProgram,
// examples: 0=Not defined, 1=Manual, 2=Normal program, 3=Aperture priority, 4=Shutter
priority,
// 5=Creative program, 6=Action program, 7=Portrait mode, 8=Landscape mode, 9=Bulb,
Attribute(FileLongName, 'ISOSpeedRatings') as ISOSpeedRatings,
Attribute(FileLongName, 'TimeZoneOffset') as TimeZoneOffset,
Attribute(FileLongName, 'SensitivityType') as SensitivityType,
// examples: 0=Unknown, 1=Standard output sensitivity (SOS), 2=Recommended exposure index
(REI),
// 3=ISO speed, 4=Standard output sensitivity (SOS) and Recommended exposure index (REI),
//5=Standard output sensitivity (SOS) and ISO Speed, 6=Recommended exposure index (REI)
and ISO Speed,
// 7=Standard output sensitivity (SOS) and Recommended exposure index (REI) and ISO speed,
Attribute(FileLongName, 'ExifVersion') as ExifVersion,
Attribute(FileLongName, 'DateTimeOriginal') as DateTimeOriginal,
Attribute(FileLongName, 'DateTimeDigitized') as DateTimeDigitized,
Attribute(FileLongName, 'ComponentsConfiguration') as ComponentsConfiguration,
// examples: 1=Y, 2=Cb, 3=Cr, 4=R, 5=G, 6=B,
Attribute(FileLongName, 'CompressedBitsPerPixel') as CompressedBitsPerPixel,
Attribute(FileLongName, 'ShutterSpeedValue') as ShutterSpeedValue,
Attribute(FileLongName, 'ApertureValue') as ApertureValue,
Attribute(FileLongName, 'BrightnessValue') as BrightnessValue, // examples: -1=Unknown,
Attribute(FileLongName, 'ExposureBiasValue') as ExposureBiasValue,
Attribute(FileLongName, 'MaxApertureValue') as MaxApertureValue,
Attribute(FileLongName, 'SubjectDistance') as SubjectDistance,
// examples: 0=Unknown, -1=Infinity,
Attribute(FileLongName, 'MeteringMode') as MeteringMode,
// examples: 0=Unknown, 1=Average, 2=CenterWeightedAverage, 3=Spot,
// 4=MultiSpot, 5=Pattern, 6=Partial, 255=Other,
Attribute(FileLongName, 'LightSource') as LightSource,
// examples: 0=Unknown, 1=Daylight, 2=Fluorescent, 3=Tungsten, 4=Flash, 9=Fine weather,
// 10=Cloudy weather, 11=Shade, 12=Daylight fluorescent,
// 13=Day white fluorescent, 14=Cool white fluorescent,
```

## 8 Script and chart functions

---

```
// 15=white fluorescent, 17=Standard light A, 18=Standard light B, 19=Standard light C,
// 20=D55, 21=D65, 22=D75, 23=D50, 24=ISO studio tungsten, 255=other light source,
Attribute(FileLongName, 'Flash') as Flash,
Attribute(FileLongName, 'FocalLength') as FocalLength,
Attribute(FileLongName, 'SubjectArea') as SubjectArea,
Attribute(FileLongName, 'MakerNote') as MakerNote,
Attribute(FileLongName, 'UserComment') as UserComment,
Attribute(FileLongName, 'SubSecTime') as SubSecTime,
Attribute(FileLongName, 'SubsecTimeOriginal') as SubsecTimeOriginal,
Attribute(FileLongName, 'SubsecTimeDigitized') as SubsecTimeDigitized,
Attribute(FileLongName, 'XPTitle') as XPTitle,
Attribute(FileLongName, 'XPComment') as XPComment,
Attribute(FileLongName, 'XPAuthor') as XPAuthor,
Attribute(FileLongName, 'XPKeywords') as XPKeywords,
Attribute(FileLongName, 'XPSubject') as XPSubject,
Attribute(FileLongName, 'FlashpixVersion') as FlashpixVersion,
Attribute(FileLongName, 'ColorSpace') as ColorSpace, // examples: 1=sRGB,
65535=Uncalibrated,
Attribute(FileLongName, 'PixelXDimension') as PixelXDimension,
Attribute(FileLongName, 'PixelYDimension') as PixelYDimension,
Attribute(FileLongName, 'RelatedSoundFile') as RelatedSoundFile,
Attribute(FileLongName, 'FocalPlaneXResolution') as FocalPlaneXResolution,
Attribute(FileLongName, 'FocalPlaneYResolution') as FocalPlaneYResolution,
Attribute(FileLongName, 'FocalPlaneResolutionUnit') as FocalPlaneResolutionUnit,
// examples: 1=None, 2=Inch, 3=Centimeter,
Attribute(FileLongName, 'ExposureIndex') as ExposureIndex,
Attribute(FileLongName, 'SensingMethod') as SensingMethod,
// examples: 1=Not defined, 2=One-chip color area sensor, 3=Two-chip color area sensor,
// 4=Three-chip color area sensor, 5=Color sequential area sensor,
// 7=Trilinear sensor, 8=Color sequential linear sensor,
Attribute(FileLongName, 'FileSource') as FileSource,
// examples: 0=Other, 1=Scanner of transparent type,
// 2=Scanner of reflex type, 3=Digital still camera,
Attribute(FileLongName, 'SceneType') as SceneType,
// examples: 1=A directly photographed image,
Attribute(FileLongName, 'CFAPattern') as CFAPattern,
Attribute(FileLongName, 'CustomRendered') as CustomRendered,
// examples: 0=Normal process, 1=Custom process,
Attribute(FileLongName, 'ExposureMode') as ExposureMode,
// examples: 0=Auto exposure, 1=Manual exposure, 2=Auto bracket,
Attribute(FileLongName, 'whiteBalance') as whiteBalance,
// examples: 0=Auto white balance, 1=Manual white balance,
Attribute(FileLongName, 'DigitalZoomRatio') as DigitalZoomRatio,
Attribute(FileLongName, 'FocalLengthIn35mmFilm') as FocalLengthIn35mmFilm,
Attribute(FileLongName, 'SceneCaptureType') as SceneCaptureType,
// examples: 0=Standard, 1=Landscape, 2=Portrait, 3=Night scene,
Attribute(FileLongName, 'GainControl') as GainControl,
// examples: 0=None, 1=Low gain up, 2=High gain up, 3=Low gain down, 4=High gain down,
Attribute(FileLongName, 'Contrast') as Contrast,
// examples: 0=Normal, 1=Soft, 2=Hard,
Attribute(FileLongName, 'Saturation') as Saturation,
// examples: 0=Normal, 1=Low saturation, 2=High saturation,
Attribute(FileLongName, 'Sharpness') as Sharpness,
// examples: 0=Normal, 1=Soft, 2=Hard,
Attribute(FileLongName, 'SubjectDistanceRange') as SubjectDistanceRange,
// examples: 0=Unknown, 1=Macro, 2=Close view, 3=Distant view,
Attribute(FileLongName, 'ImageUniqueID') as ImageUniqueID,
```

```
Attribute(FileLongName, 'BodySerialNumber') as BodySerialNumber,
Attribute(FileLongName, 'CMNT_GAMMA') as CMNT_GAMMA,
Attribute(FileLongName, 'PrintImageMatching') as PrintImageMatching,
Attribute(FileLongName, 'OffsetSchema') as OffsetSchema,
// ***** Interoperability Attributes *****
Attribute(FileLongName, 'InteroperabilityIndex') as InteroperabilityIndex,
Attribute(FileLongName, 'InteroperabilityVersion') as InteroperabilityVersion,
Attribute(FileLongName, 'InteroperabilityRelatedImageFileFormat') as
InteroperabilityRelatedImageFileFormat,
Attribute(FileLongName, 'InteroperabilityRelatedImagewidth') as
InteroperabilityRelatedImagewidth,
Attribute(FileLongName, 'InteroperabilityRelatedImageLength') as
InteroperabilityRelatedImageLength,
Attribute(FileLongName, 'InteroperabilityColorSpace') as InteroperabilityColorSpace,
// examples: 1=sRGB, 65535=Uncalibrated,
Attribute(FileLongName, 'InteroperabilityPrintImageMatching') as
InteroperabilityPrintImageMatching,
// ***** GPS Attributes *****
Attribute(FileLongName, 'GPSVersionID') as GPSVersionID,
Attribute(FileLongName, 'GPSLatitudeRef') as GPSLatitudeRef,
Attribute(FileLongName, 'GPSLatitude') as GPSLatitude,
Attribute(FileLongName, 'GPSLongitudeRef') as GPSLongitudeRef,
Attribute(FileLongName, 'GPSLongitude') as GPSLongitude,
Attribute(FileLongName, 'GPSAltitudeRef') as GPSAltitudeRef,
// examples: 0=Above sea level, 1=Below sea level,
Attribute(FileLongName, 'GPSAltitude') as GPSAltitude,
Attribute(FileLongName, 'GPSTimeStamp') as GPSTimeStamp,
Attribute(FileLongName, 'GPSSatellites') as GPSSatellites,
Attribute(FileLongName, 'GPSStatus') as GPSStatus,
Attribute(FileLongName, 'GPSMeasureMode') as GPSMeasureMode,
Attribute(FileLongName, 'GPSDOP') as GPSDOP,
Attribute(FileLongName, 'GPSSpeedRef') as GPSSpeedRef,
Attribute(FileLongName, 'GPSSpeed') as GPSSpeed,
Attribute(FileLongName, 'GPSTrackRef') as GPSTrackRef,
Attribute(FileLongName, 'GPSTrack') as GPSTrack,
Attribute(FileLongName, 'GPSImgDirectionRef') as GPSImgDirectionRef,
Attribute(FileLongName, 'GPSImgDirection') as GPSImgDirection,
Attribute(FileLongName, 'GPSMapDatum') as GPSMapDatum,
Attribute(FileLongName, 'GPSDestLatitudeRef') as GPSDestLatitudeRef,
Attribute(FileLongName, 'GPSDestLatitude') as GPSDestLatitude,
Attribute(FileLongName, 'GPSDestLongitudeRef') as GPSDestLongitudeRef,
Attribute(FileLongName, 'GPSDestLongitude') as GPSDestLongitude,
Attribute(FileLongName, 'GPSDestBearingRef') as GPSDestBearingRef,
Attribute(FileLongName, 'GPSDestBearing') as GPSDestBearing,
Attribute(FileLongName, 'GPSDestDistanceRef') as GPSDestDistanceRef,
Attribute(FileLongName, 'GPSDestDistance') as GPSDestDistance,
Attribute(FileLongName, 'GPSProcessingMethod') as GPSProcessingMethod,
Attribute(FileLongName, 'GPSAreaInformation') as GPSAreaInformation,
Attribute(FileLongName, 'GPSDateStamp') as GPSDateStamp,
Attribute(FileLongName, 'GPSDifferential') as GPSDifferential;
// examples: 0=No correction, 1=Differential correction,
LOAD @1:n as FileLongName Inline "$(vFoundFile)" (fix, no labels);
Next vFoundFile
Next vExt
```

### Example 3: Windows media files

This script reads all possible WMA/WMV ASF meta tags in folder *MyMusic*.

```
/ Script to read WMA/WMV ASF meta tags
for each vExt in 'asf', 'wma', 'wmv'
for each vFoundFile in filelist( GetFolderPath('MyMusic') & '\*.' & vExt )
FileList:
LOAD FileLongName,
    subfield(FileLongName,'\',-1) as FileShortName,
    num(FileSize(FileLongName),'# ### ### ##',',',' ') as FileSize,
    FileTime(FileLongName) as FileTime,
    Attribute(FileLongName, 'Title') as Title,
    Attribute(FileLongName, 'Author') as Author,
    Attribute(FileLongName, 'Copyright') as Copyright,
    Attribute(FileLongName, 'Description') as Description,
    Attribute(FileLongName, 'Rating') as Rating,
    Attribute(FileLongName, 'PlayDuration') as PlayDuration,
    Attribute(FileLongName, 'MaximumBitrate') as MaximumBitrate,
    Attribute(FileLongName, 'WMFSDKVersion') as WMFSDKVersion,
    Attribute(FileLongName, 'WMFSDKNeeded') as WMFSDKNeeded,
    Attribute(FileLongName, 'IsVBR') as IsVBR,
    Attribute(FileLongName, 'ASFLeakyBucketPairs') as ASFLeakyBucketPairs,
    Attribute(FileLongName, 'PeakValue') as PeakValue,
    Attribute(FileLongName, 'AverageLevel') as AverageLevel;
LOAD @1:n as FileLongName Inline "$(vFoundFile)" (fix, no labels);
Next vFoundFile
Next vExt
```

### Example 4: PNG

This script reads all possible PNG meta tags in folder *MyPictures*.

```
// Script to read PNG meta tags
for each vExt in 'png'
for each vFoundFile in filelist( GetFolderPath('MyPictures') & '\*.' & vExt )
FileList:
LOAD FileLongName,
    subfield(FileLongName,'\',-1) as FileShortName,
    num(FileSize(FileLongName),'# ### ### ##',',',' ') as FileSize,
    FileTime(FileLongName) as FileTime,
    Attribute(FileLongName, 'Comment') as Comment,
    Attribute(FileLongName, 'Creation Time') as Creation_Time,
    Attribute(FileLongName, 'Source') as Source,
    Attribute(FileLongName, 'Title') as Title,
    Attribute(FileLongName, 'Software') as Software,
    Attribute(FileLongName, 'Author') as Author,
    Attribute(FileLongName, 'Description') as Description,
    Attribute(FileLongName, 'Copyright') as Copyright;
LOAD @1:n as FileLongName Inline "$(vFoundFile)" (fix, no labels);
Next vFoundFile
Next vExt
```

## ConnectString

The **ConnectString()** function returns the name of the active data connection for ODBC or OLE DB connections. The function returns an empty string if no **connect** statement has been executed, or after a **disconnect** statement.

### Syntax:

```
ConnectString()
```

Examples and results:

Scripting examples

Example	Result
<pre>LIB CONNECT TO 'Tutorial ODBC'; ConnectString: Load ConnectString() as ConnectString AutoGenerate 1;</pre>	<p>Returns 'Tutorial ODBC' in field ConnectString.</p> <p>This example assumes that you have an available data connection called Tutorial ODBC.</p>

## FileName

The **FileName** function returns a string containing the name of the table file currently being read, without path or extension.

### Syntax:

```
FileName()
```

Examples and results:

Scripting examples

Example	Result
<pre>LOAD *, filename( ) as X from C:\UserFiles\abc.txt</pre>	<p>Will return 'abc' in field X in each record read.</p>

## FileDir

The **FileDir** function returns a string containing the path to the directory of the table file currently being read.

### Syntax:

```
FileDir()
```



*This function supports only folder data connections in standard mode.*

Examples and results:

Scripting examples

Example	Result
Load *, filedir( ) as X from C:\UserFiles\abc.txt	Will return 'C:\UserFiles' in field X in each record read.

## FileExtension

The **FileExtension** function returns a string containing the extension of the table file currently being read.

**Syntax:**

**FileExtension()**

Examples and results:

Scripting examples

Example	Result
LOAD *, FileExtension( ) as X from C:\UserFiles\abc.txt	Will return 'txt' in field X in each record read.

## FileName

The **FileName** function returns a string containing the name of the table file currently being read, without path but including the extension.

**Syntax:**

**FileName()**

Examples and results:

Scripting examples

Example	Result
LOAD *, FileName( ) as X from C:\UserFiles\abc.txt	Will return 'abc.txt' in field X in each record read.

## FilePath

The **FilePath** function returns a string containing the full path to the table file currently being read.

**Syntax:**

**FilePath()**



*This function supports only folder data connections in standard mode.*



Examples and results:

### Scripting examples

Example	Result
Load *, FilePath( ) as X from C:\UserFiles\abc.txt	Will return 'C:\UserFiles\abc.txt' in field X in each record read.

## FileSize

The **FileSize** function returns an integer containing the size in bytes of the file filename or, if no filename is specified, of the table file currently being read.

### Syntax:

**FileSize**( [filename] )

### Arguments:

#### Arguments

Argument	Description
filename	<p>The name of a file, if necessary including path, as a folder or web file data connection. If you don't specify a file name, the table file currently being read is used.</p> <p><b>Example: 'lib://Table Files/'</b></p> <p>In legacy scripting mode, the following path formats are also supported:</p> <ul style="list-style-type: none"> <li>• absolute           <p style="margin-left: 20px;"><b>Example: c:\data\</b></p> </li> <li>• relative to the Qlik Sense app working directory.           <p style="margin-left: 20px;"><b>Example: data\</b></p> </li> <li>• URL address (HTTP or FTP), pointing to a location on the Internet or an intranet.           <p style="margin-left: 20px;"><b>Example: http://www.qlik.com</b></p> </li> </ul>

Examples and results:

### Scripting examples

Example	Result
LOAD *, FileSize( ) as X from abc.txt;	Will return the size of the specified file (abc.txt) as an integer in field X in each record read.
FileSize( 'lib://DataFiles/xyz.xls' )	Will return the size of the file xyz.xls.

## FileTime

The **FileTime** function returns a timestamp in UTC format of the last modification of a specified file. If a file is not specified, the function returns a timestamp in UTC of the last modification of the currently read table file.

### Syntax:

```
FileTime( [ filename ] )
```

### Arguments:

#### Arguments

Argument	Description
filename	<p>The name of a file, if necessary including path, as a folder or web file data connection</p> <p><b>Example: 'lib://Table Files/'</b></p> <p>In legacy scripting mode, the following path formats are also supported:</p> <ul style="list-style-type: none"> <li>absolute</li> </ul> <p><b>Example: c:\data\</b></p> <ul style="list-style-type: none"> <li>relative to the Qlik Sense app working directory.</li> </ul> <p><b>Example: data\</b></p> <ul style="list-style-type: none"> <li>URL address (HTTP or FTP), pointing to a location on the Internet or an intranet.</li> </ul> <p><b>Example: http://www.qlik.com</b></p>

Examples and results:

#### Script examples

Example	Result
LOAD *, FileTime( ) as X from abc.txt;	Will return the timestamp of the last modification of the file (abc.txt) in field X in each record read.
FileTime( 'xyz.xls' )	Will return the timestamp of the last modification of the file xyz.xls.

## GetFolderPath

The **GetFolderPath** function returns the value of the Microsoft Windows *SHGetFolderPath* function. This function takes as input the name of a Microsoft Windows folder and returns the full path of the folder.



This function is not supported in standard mode. .

**Syntax:**

```
GetFolderPath (foldername)
```

**Arguments:**

## Arguments

Argument	Description
<b>foldername</b>	<p>Name of the Microsoft Windows folder.</p> <p>The folder name should not contain any space. Any space in the folder name seen in Windows Explorer should be removed from the folder name.</p> <p>Examples:</p> <p><i>MyMusic</i></p> <p><i>MyDocuments</i></p>

**Examples and results:**

The goal of this example is to get the paths of the following Microsoft Windows folders: *MyMusic*, *MyPictures* and *Windows*. Add the example script to your app and reload it.

```
LOAD
  GetFolderPath('MyMusic') as MyMusic,
  GetFolderPath('MyPictures') as MyPictures,
  GetFolderPath('windows') as windows
AutoGenerate 1;
```

Once the app is reloaded, the fields *MyMusic*, *MyPictures* and *Windows* are added to the data model. Each field contains the path to the folder defined in input. For example:

- *C:\Users\smu\Music* for the folder *MyMusic*
- *C:\Users\smu\Pictures* for the folder *MyPictures*
- *C:\Windows* for the folder *Windows*

## QvdCreateTime

This script function returns the XML-header timestamp from a QVD file, if any is present, otherwise it returns NULL. In the timestamp, time is provided in UTC.

**Syntax:**

```
QvdCreateTime (filename)
```

**Arguments:**

## Arguments

Argument	Description
filename	<p>The name of a QVD file, if necessary including path, as a folder or web data connection.</p> <p><b>Example: 'lib://Table Files/'</b></p> <p>In legacy scripting mode, the following path formats are also supported:</p> <ul style="list-style-type: none"> <li>absolute</li> </ul> <p><b>Example: c:\data\</b></p> <ul style="list-style-type: none"> <li>relative to the Qlik Sense app working directory.</li> </ul> <p><b>Example: data\</b></p> <ul style="list-style-type: none"> <li>URL address (HTTP or FTP), pointing to a location on the Internet or an intranet.</li> </ul> <p><b>Example: http://www.qlik.com</b></p>

**Example:**

```

QvdCreateTime('MyFile.qvd')
QvdCreateTime('C:\MyDir\MyFile.qvd')
QvdCreateTime('lib://DataFiles/MyFile.qvd')

```

## QvdFieldName

This script function returns the name of field number **fieldno** in a QVD file. If the field does not exist NULL is returned.

**Syntax:**

```
QvdFieldName(filename , fieldno)
```

**Arguments:**

## Arguments

Argument	Description
filename	<p>The name of a QVD file, if necessary including path, as a folder or web data connection.</p> <p><b>Example: 'lib://Table Files/'</b></p> <p>In legacy scripting mode, the following path formats are also supported:</p> <ul style="list-style-type: none"> <li>absolute</li> </ul> <p><b>Example: c:\data\</b></p> <ul style="list-style-type: none"> <li>relative to the Qlik Sense app working directory.</li> </ul> <p><b>Example: data\</b></p> <ul style="list-style-type: none"> <li>URL address (HTTP or FTP), pointing to a location on the Internet or an intranet.</li> </ul> <p><b>Example: http://www.qlik.com</b></p>
fieldno	The number of the field within the table contained in the QVD file.

**Examples:**

```
QvdFieldName ('MyFile.qvd', 5)
```

```
QvdFieldName ('c:\MyDir\MyFile.qvd', 5)
```

```
QvdFieldName ('lib://DataFiles/MyFile.qvd', 5)
```

All three examples return the name of the fifth field of the table contained in the QVD file.

## QvdNoOfFields

This script function returns the number of fields in a QVD file.

**Syntax:**

```
QvdNoOfFields (filename)
```

### Arguments:

#### Arguments

Argument	Description
filename	<p>The name of a QVD file, if necessary including path, as a folder or web data connection.</p> <p><b>Example: 'lib://Table Files/'</b></p> <p>In legacy scripting mode, the following path formats are also supported:</p> <ul style="list-style-type: none"><li>absolute</li></ul> <p><b>Example: c:\data\</b></p> <ul style="list-style-type: none"><li>relative to the Qlik Sense app working directory.</li></ul> <p><b>Example: data\</b></p> <ul style="list-style-type: none"><li>URL address (HTTP or FTP), pointing to a location on the Internet or an intranet.</li></ul> <p><b>Example: http://www.qlik.com</b></p>

### Examples:

```
QvdNoOfFields ('MyFile.qvd')  
QvdNoOfFields ('C:\MyDir\MyFile.qvd')  
QvdNoOfFields ('lib://DataFiles/MyFile.qvd')
```

## QvdNoOfRecords

**Example:** This script function returns the number of records currently in a QVD file.

### Syntax:

```
QvdNoOfRecords (filename)
```

**Arguments:**

## Arguments

Argument	Description
filename	<p>The name of a QVD file, if necessary including path, as a folder or web data connection.</p> <p><b>Example: 'lib://Table Files/'</b></p> <p>In legacy scripting mode, the following path formats are also supported:</p> <ul style="list-style-type: none"> <li>absolute</li> </ul> <p><b>Example: c:\data\</b></p> <ul style="list-style-type: none"> <li>relative to the Qlik Sense app working directory.</li> </ul> <p><b>Example: data\</b></p> <ul style="list-style-type: none"> <li>URL address (HTTP or FTP), pointing to a location on the Internet or an intranet.</li> </ul> <p><b>Example: http://www.qlik.com</b></p>

**Examples:**

```
QvdNoOfRecords ('MyFile.qvd')
QvdNoOfRecords ('C:\MyDir\MyFile.qvd')
QvdNoOfRecords ('lib://DataFiles/MyFile.qvd')
```

## QvdTableName

This script function returns the name of the table stored in a QVD file.

**Syntax:**

```
QvdTableName (filename)
```

**Arguments:**

## Arguments

Argument	Description
filename	<p>The name of a QVD file, if necessary including path, as a folder or web data connection.</p> <p><b>Example: 'lib://Table Files/'</b></p> <p>In legacy scripting mode, the following path formats are also supported:</p> <ul style="list-style-type: none"> <li>absolute</li> </ul> <p><b>Example: c:\data\</b></p> <ul style="list-style-type: none"> <li>relative to the Qlik Sense app working directory.</li> </ul> <p><b>Example: data\</b></p> <ul style="list-style-type: none"> <li>URL address (HTTP or FTP), pointing to a location on the Internet or an intranet.</li> </ul> <p><b>Example: http://www.qlik.com</b></p>

**Examples:**

```

QvdTableName ('MyFile.qvd')
QvdTableName ('C:\MyDir\MyFile.qvd')
QvdTableName ('lib://data\MyFile.qvd')

```

## 8.11 Financial functions

Financial functions can be used in the data load script and in chart expressions to calculate payments and interest rates.

For all the arguments, cash that is paid out is represented by negative numbers. Cash received is represented by positive numbers.

Listed here are the arguments that are used in the financial functions (excepting the ones beginning with **range-**).



*For all financial functions it is vital that you are consistent when specifying units for **rate** and **nper**. If monthly payments are made on a five-year loan at 6% annual interest, use 0.005 (6%/12) for **rate** and 60 (5\*12) for **nper**. If annual payments are made on the same loan, use 6% for **rate** and 5 for **nper**.*



### Financial functions overview

Each function is described further after the overview. You can also click the function name in the syntax to immediately access the details for that specific function.

#### **FV**

This function returns the future value of an investment based on periodic, constant payments and a simple annual interest.

```
FV (rate, nper, pmt [ ,pv [ , type ] ])
```

#### **nPer**

This function returns the number of periods for an investment based on periodic, constant payments and a constant interest rate.

```
nPer (rate, pmt, pv [ ,fv [ , type ] ])
```

#### **Pmt**

This function returns the payment for a loan based on periodic, constant payments and a constant interest rate. It cannot change over the life of the annuity. A payment is stated as a negative number, for example, -20.

```
Pmt (rate, nper, pv [ ,fv [ , type ] ])
```

#### **PV**

This function returns the present value of an investment.

```
PV (rate, nper, pmt [ ,fv [ , type ] ])
```

#### **Rate**

This function returns the interest rate per period on annuity. The result has a default number format of **Fix** two decimals and %.

```
Rate (nper, pmt , pv [ ,fv [ , type ] ])
```

### BlackAndSchole

The Black and Scholes model is a mathematical model for financial market derivative instruments. The formula calculates the theoretical value of an option. In Qlik Sense, the **BlackAndSchole** function returns the value according to the Black and Scholes unmodified formula (European style options).

```
BlackAndSchole (strike , time_left , underlying_price , vol , risk_free_rate , type)
```

**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
strike	The future purchase price of the stock.
time_left	The number of time periods remaining.
underlying_price	The current value of the stock.
vol	Volatility (of the stock price) expressed as a percentage in decimal form, per time period.
risk_free_rate	The risk-free rate expressed as a percentage in decimal form, per time period.
call_or_put	The type of option:  'c', 'call' or any non-zero numeric value for call options  'p', 'put' or 0 for put options.

**Limitations:**

The value of strike, time\_left, and underlying\_price must be >0.

The value of vol and risk\_free\_rate must be: <0 or >0.

Examples and results:

Scripting examples

Example	Result
<p><code>BlackAndSchole(130, 4, 68.5, 0.4, 0.04, 'call')</code></p> <p>This calculates the theoretical price of an option to buy a share that is worth 68.5 today, at a value of 130 in 4 years. The formula uses a volatility of 0.4 (40%) per year and a risk-free interest rate of 0.04 (4%).</p>	<p>Returns 11.245</p>

## FV

This function returns the future value of an investment based on periodic, constant payments and a simple annual interest.

**Syntax:**

```
FV(rate, nper, pmt [ ,pv [ , type ] ])
```

**Return data type:** numeric. By default, the result will be formatted as currency..

**Arguments:**

Arguments

Argument	Description
rate	The interest rate per period.
nper	The total number of payment periods in an annuity.
pmt	The payment made each period. It cannot change over the life of the annuity. A payment is stated as a negative number, for example, -20.
pv	The present value, or lump-sum amount, that a series of future payments is worth right now. If <b>pv</b> is omitted, it is assumed to be 0 (zero).
type	Should be 0 if payments are due at the end of the period and 1 if payments are due at the beginning of the period. If <b>type</b> is omitted, it is assumed to be 0.

Examples and results:

Scripting example

Example	Result
<p>You are paying a new household appliance by 36 monthly installments of \$20. The interest rate is 6% per annum. The bill comes at the end of every month. What is the total invested, when the last bill has been paid?</p> <p><code>FV(0.005, 36, -20)</code></p>	<p>Returns \$786.72</p>

### nPer

This function returns the number of periods for an investment based on periodic, constant payments and a constant interest rate.

**Syntax:**

```
nPer(rate, pmt, pv [ ,fv [ , type ] ])
```

**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
rate	The interest rate per period.
nper	The total number of payment periods in an annuity.

## 8 Script and chart functions

Argument	Description
pmt	The payment made each period. It cannot change over the life of the annuity. A payment is stated as a negative number, for example, -20.
pv	The present value, or lump-sum amount, that a series of future payments is worth right now. If <b>pv</b> is omitted, it is assumed to be 0 (zero).
fv	The future value, or cash balance, you want to attain after the last payment is made. If <b>fv</b> is omitted, it is assumed to be 0.
type	Should be 0 if payments are due at the end of the period and 1 if payments are due at the beginning of the period. If <b>type</b> is omitted, it is assumed to be 0.

Examples and results:

### Scripting example

Example	Result
You want to sell a household appliance by monthly installments of \$20. The interest rate is 6% per annum. The bill comes at the end of every month. How many periods are required if the value of the money received after the last bill has been paid should equal \$800?  <code>nPer(0.005, -20, 0, 800)</code>	Returns 36.56

## Pmt

This function returns the payment for a loan based on periodic, constant payments and a constant interest rate. It cannot change over the life of the annuity. A payment is stated as a negative number, for example, -20.

```
Pmt(rate, nper, pv [ ,fv [ , type ] ] )
```

**Return data type:** numeric. By default, the result will be formatted as currency..

To find the total amount paid over the duration of the loan, multiply the returned **pmt** value by **nper**.

**Arguments:**

### Arguments

Argument	Description
rate	The interest rate per period.
nper	The total number of payment periods in an annuity.
pv	The present value, or lump-sum amount, that a series of future payments is worth right now. If <b>pv</b> is omitted, it is assumed to be 0 (zero).

## 8 Script and chart functions

Argument	Description
fv	The future value, or cash balance, you want to attain after the last payment is made. If <b>fv</b> is omitted, it is assumed to be 0.
type	Should be 0 if payments are due at the end of the period and 1 if payments are due at the beginning of the period. If <b>type</b> is omitted, it is assumed to be 0.

Examples and results:

### Scripting examples

Example	Result
The following formula returns the monthly payment on a \$20,000 loan at an annual rate of 10 percent, that must be paid off in 8 months:  <code>Pmt(0.1/12,8,20000)</code>	Returns - \$2,594.66
For the same loan, if payment is due at the beginning of the period, the payment is:  <code>Pmt(0.1/12,8,20000,0,1)</code>	Returns - \$2,573.21

## PV

This function returns the present value of an investment.

```
PV(rate, nper, pmt [ ,fv [ , type ] ])
```

**Return data type:** numeric. By default, the result will be formatted as currency..

The present value is the total amount that a series of future payments is worth right now. For example, when borrowing money, the loan amount is the present value to the lender.

### Arguments:

#### Arguments

Argument	Description
rate	The interest rate per period.
nper	The total number of payment periods in an annuity.
pmt	The payment made each period. It cannot change over the life of the annuity. A payment is stated as a negative number, for example, -20.
fv	The future value, or cash balance, you want to attain after the last payment is made. If <b>fv</b> is omitted, it is assumed to be 0.
type	Should be 0 if payments are due at the end of the period and 1 if payments are due at the beginning of the period. If <b>type</b> is omitted, it is assumed to be 0.

Examples and results:

Scripting example

Example	Result
<p>What is the present value of a debt, when you have to pay \$100 at the end of each month during a five-year period, given an interest rate of 7%?</p> <p><code>PV(0.07/12, 12*5, -100, 0, 0)</code></p>	Returns \$5,050.20

### Rate

This function returns the interest rate per period on annuity. The result has a default number format of **Fix** two decimals and %.

#### Syntax:

**Rate**(*nper*, *pmt*, *pv* [, *fv* [, *type* ] ])

**Return data type:** numeric.

The **rate** is calculated by iteration and can have zero or more solutions. If the successive results of **rate** do not converge, a NULL value will be returned.

#### Arguments:

Arguments

Argument	Description
<i>nper</i>	The total number of payment periods in an annuity.
<i>pmt</i>	The payment made each period. It cannot change over the life of the annuity. A payment is stated as a negative number, for example, -20.
<i>pv</i>	The present value, or lump-sum amount, that a series of future payments is worth right now. If <b>pv</b> is omitted, it is assumed to be 0 (zero).
<i>fv</i>	The future value, or cash balance, you want to attain after the last payment is made. If <b>fv</b> is omitted, it is assumed to be 0.
<i>type</i>	Should be 0 if payments are due at the end of the period and 1 if payments are due at the beginning of the period. If <b>type</b> is omitted, it is assumed to be 0.

Examples and results:

Scripting example

Example	Result
<p>What is the interest rate of a five-year \$10,000 annuity loan with monthly payments of \$300?</p> <p><code>Rate(60, -300, 10000)</code></p>	Returns 2.00%

## 8.12 Formatting functions

The formatting functions impose the display format on the input numeric fields or expressions, Depending on data type, you can specify the characters for the decimal separator, thousands separator, and so on.

The functions all return a dual value with both the string and the number value, but can be thought of as performing a number-to-string conversion. **Dual()** is a special case, but the other formatting functions take the numeric value of the input expression and generate a string representing the number.

In contrast, the interpretation functions do the opposite: they take string expressions and evaluate them as numbers, specifying the format of the resulting number.

The functions can be used both in data load scripts and chart expressions.



*All number representations are given with a decimal point as the decimal separator.*

### Formatting functions overview

Each function is described further after the overview. You can also click the function name in the syntax to immediately access the details for that specific function.

#### ApplyCodepage

**ApplyCodepage()** applies a different code page character set to the field or text stated in the expression. The **codepage** argument must be in number format.

**ApplyCodepage** (text, codepage)

#### Date

**Date()** formats an expression as a date using the format set in the system variables in the data load script, or the operating system, or a format string, if supplied.

**Date** (number[, format])

#### Dual

**Dual()** combines a number and a string into a single record, such that the number representation of the record can be used for sorting and calculation purposes, while the string value can be used for display purposes.

**Dual** (text, number)

#### Interval

**Interval()** formats a number as a time interval using the format in the system variables in the data load script, or the operating system, or a format string, if supplied.

**Interval** (number[, format])

### Money

**Money()** formats an expression numerically as a money value, in the format set in the system variables set in the data load script, or in the operating system, unless a format string is supplied, and optional decimal and thousands separators.

```
Money (number[, format[, dec_sep [, thou_sep]])
```

### Num

**Num()** formats a number, that is it converts the numeric value of the input to display text using the format specified in the second parameter. If the second parameter is omitted, it uses the decimal and thousand separators set in the data load script. Custom decimal and thousand separator symbols are optional parameters.

```
Num (number[, format[, dec_sep [, thou_sep]])
```

### Time

**Time()** formats an expression as a time value, in the time format set in the system variables in the data load script, or in the operating system, unless a format string is supplied.


```
Time (number[, format])
```

### Timestamp

**TimeStamp()** formats an expression as a date and time value, in the timestamp format set in the system variables in the data load script, or in the operating system, unless a format string is supplied.

```
Timestamp (number[, format])
```

### See also:

 [Interpretation functions \(page 1265\)](#)

## ApplyCodepage

**ApplyCodepage()** applies a different code page character set to the field or text stated in the expression. The **codepage** argument must be in number format.



*Although ApplyCodepage can be used in chart expressions, it is more commonly used as a script function in the Data load editor. For example, as you load files that might have been saved in different character sets out of your control, you can apply the code page that represents the character set you require.*

### Syntax:

```
ApplyCodepage (text, codepage)
```



**Return data type:** string

**Arguments:**

Arguments

Argument	Description
text	Field or text to which you want to apply a different code page, given by the argument <b>codepage</b> .
codepage	Number representing the code page to be applied to the field or expression given by <b>text</b> .

Examples and results:

Scripting examples

Example	Result
<pre>LOAD ApplyCodepage (ROWX,1253) as GreekProduct, ApplyCodepage (ROWY, 1255) as HebrewProduct, ApplyCodepage (ROWZ, 65001) as EnglishProduct; SQL SELECT ROWX, ROWY, ROWZ From Products;</pre>	<p>When loading from SQL the source might have a mixture of different character sets: Cyrillic, Hebrew, and so on, from the UTF-8 format. These would be required to be loaded row by row, applying a different code page for each row.</p> <p>The <b>codepage</b> value 1253 represents Windows Greek character set, the value 1255 represents Hebrew, and the value 65001 represents standard Latin UTF-8 characters.</p>

**See also:** *Character set (page 165)*

## Date

**Date()** formats an expression as a date using the format set in the system variables in the data load script, or the operating system, or a format string, if supplied.

**Syntax:**

**Date** (number [, format])

**Return data type:** dual

**Arguments:**

Arguments

Argument	Description
number	The number to be formatted.

## 8 Script and chart functions

Argument	Description
format	String describing the format of the resulting string. If no format string is supplied, the date format set in the system variables in the dtat load script or the operating system is used.

Examples and results:

The examples below assume the following default settings:

- Date setting 1: YY-MM-DD
- Date setting 2: M/D/YY

### Example:

```
Date( A )  
where A=35648
```

Results table

Results	Setting 1	Setting 2
String:	97-08-06	8/6/97
Number:	35648	35648

### Example:

```
Date( A, 'YY.MM.DD' )  
where A=35648
```

Results table

Results	Setting 1	Setting 2
String:	97.08.06	97.08.06
Number:	35648	35648

### Example:

```
Date( A, 'DD.MM.YYYY' )  
where A=35648.375
```

Results table

Results	Setting 1	Setting 2
String:	06.08.1997	06.08.1997
Number:	35648.375	35648.375

**Example:**

```
Date( A, 'YY.MM.DD' )
where A=8/6/97
```

Results table

Results	Setting 1	Setting 2
String:	NULL (nothing)	97.08.06
Number:	NULL	35648

## Dual

**Dual()** combines a number and a string into a single record, such that the number representation of the record can be used for sorting and calculation purposes, while the string value can be used for display purposes.

**Syntax:**

```
Dual (text, number)
```

**Return data type:** dual



*All dual return values are right-aligned.*

**Arguments:**

Arguments

Argument	Description
text	The string value to be used in combination with the number argument.
number	The number to be used in combination with the string in the string argument.

In Qlik Sense, all field values are potentially dual values. This means that the field values can have both a numeric value and a textual value. An example is a date that could have a numeric value of 40908 and the textual representation '2011-12-31'.



*When several data items read into one field have different string representations but the same valid number representation, they will all share the first string representation encountered.*



The **dual** function is typically used early in the script, before other data is read into the field concerned, in order to create that first string representation, which will be shown in filter panes.

Examples and results:

#### Scripting examples

Example	Description
<p>Add the following examples to your script and run it.</p> <pre>Load dual ( NameDay,NumDay ) as DayOfWeek inline [ NameDay,NumDay Monday,0 Tuesday,1 Wednesday,2 Thursday,3 Friday,4 Saturday,5 Sunday,6 ];</pre>	<p>The field DayOfWeek can be used in a visualization as a dimension for example. In a table with the week days are automatically sorted into their correct number sequence, instead of alphabetical order.</p>
<pre>Load Dual('Q' &amp; Ceil (Month(Now())/3), Ceil(Month(Now())/3)) as Quarter AutoGenerate 1;</pre>	<p>This example finds the current quarter. It is displayed as Q1 when the <b>Now()</b> function is run in the first three months of the year, Q2 for the second three months, and so on. However, when used in sorting, the field Quarter will behave as its numerical value: 1 to 4.</p>
<pre>Dual('Q' &amp; Ceil(Month (Date)/3), Ceil(Month (Date)/3)) as Quarter</pre>	<p>As in the previous example, the field Quarter is created with the text values 'Q1' to 'Q4', and assigned the numeric values 1 to 4. In order to use this in the script the values for Date must be loaded.</p>
<pre>Dual(WeekYear(Date) &amp; '-w' &amp; Week(Date), WeekStart(Date)) as YearWeek</pre>	<p>This example create sa field YearWeek with text values of the form '2012-W22' and at the same time, assigns a numeric value corresponding to the date number of the first day of the week, for example: 41057. In order to use this in the script the values for Date must be loaded.</p>

## Interval

**Interval()** formats a number as a time interval using the format in the system variables in the data load script, or the operating system, or a format string, if supplied.

Intervals may be formatted as a time, as days or as a combination of days, hours, minutes, seconds and fractions of seconds.

### Syntax:

```
Interval (number [, format])
```

**Return data type:** dual

**Arguments:**

Arguments

Argument	Description
number	The number to be formatted.
format	String describing how the resulting interval string is to be formatted. If omitted, the short date format, time format, and decimal separator set in the operating system are used.

Examples and results:

The examples below assume the following default settings:

- Date format setting 1: YY-MM-DD
- Date format setting 2: hh:mm:ss
- Number decimal separator: .

Results table

Example	String	Number
Interval( A ) where A=0.375	09:00:00	0.375
Interval( A ) where A=1.375	33:00:00	1.375
Interval( A, 'D hh:mm' ) where A=1.375	1 09:00	1.375
Interval( A-B, 'D hh:mm' ) where A=97-08-06 09:00:00 and B=96-08-06 00:00:00	365 09:00	365.375

## Money

**Money()** formats an expression numerically as a money value, in the format set in the system variables set in the data load script, or in the operating system, unless a format string is supplied, and optional decimal and thousands separators.

**Syntax:**

```
Money(number[, format[, dec_sep[, thou_sep]])
```

**Return data type:** dual

**Arguments:**

Arguments

Argument	Description
number	The number to be formatted.
format	String describing how the resulting money string is to be formatted.
dec_sep	String specifying the decimal number separator.
thou_sep	String specifying the thousands number separator.

If arguments 2-4 are omitted, the currency format set in the operating system is used.

Examples and results:

The examples below assume the following default settings:

- MoneyFormat setting 1: kr ##0,00, MoneyThousandSep'
- MoneyFormat setting 2: \$ #,##0.00, MoneyThousandSep','

**Example:**

Money( A )  
where A=35648

Results table

Results	Setting 1	Setting 2
String:	kr 35 648,00	\$ 35,648.00
Number:	35648.00	35648.00

**Example:**

Money( A, '#,##0 ¥', '.' , ',' )  
where A=3564800

Results table

Results	Setting 1	Setting 2
String:	3,564,800 ¥	3,564,800 ¥
Number:	3564800	3564800

## Num

**Num()** formats a number, that is it converts the numeric value of the input to display text using the format specified in the second parameter. If the second parameter is omitted, it uses the decimal and thousand separators set in the data load script. Custom decimal and thousand separator symbols are optional parameters.

### Syntax:

```
Num(number[, format[, dec_sep [, thou_sep]])
```

**Return data type:** dual

The Num function returns a dual value with both the string and the numeric value. The function takes the numeric value of the input expression and generates a string representing the number.

### Arguments:

Arguments

Argument	Description
number	The number to be formatted.
format	String specifying how the resulting string is to be formatted. If omitted, the decimal and thousand separators that are set in the data load script are used.
dec_sep	String specifying the decimal number separator. If omitted, the value of the variable DecimalSep that is set in the data load script is used.
thou_sep	String specifying the thousands number separator. If omitted, the value of the variable ThousandSep that is set in the data load script is used.

Example: Chart expression

### Example:

The following table shows the results when field A equals 35648.312.

Results

A	Result
Num(A)	35648.312 (depends on environment variables in script)
Num(A, '0.0', ',')	35648.3
Num(A, '0,00', ',')	35648,31
Num(A, '#,###0.0', ',', ',')	35,648.3
Num(A, '# ##0', ',', ',')	35 648

Example: Load script

### Load script

*Num* can be used in load script to format a number, even if the thousand and decimal separators are already set in the script. The load script below includes specific thousand and decimal separators but then uses *Num* to format data in different ways.

In the **Data load editor**, create a new section, and then add the example script and run it. Then add, at least, the fields listed in the results column to a sheet in your app to see the result.

```
SET ThousandSep=',';
SET DecimalSep='.';
Transactions:
Load
*,
Num(transaction_amount) as [No formatting],
Num(transaction_amount,'0') as [0],
Num(transaction_amount,'#,#0') as [#,#0],
Num(transaction_amount,'# ###,00') as [# ###,00],
Num(transaction_amount,'# ###,00',' ',' ') as [# ###,00 , ' ', ' '],
Num(transaction_amount,'#,###.00','.',',') as [#,###.00 , '.', ','],
Num(transaction_amount,'$#,###.00') as [$#,###.00],
;
Load * Inline [
transaction_id, transaction_date, transaction_amount, transaction_quantity, discount,
customer_id, size, color_code
3750, 20180830, 12423.56, 23, 0,2038593, L, Red
3751, 20180907, 5356.31, 6, 0.1, 203521, m, orange
3752, 20180916, 15.75, 1, 0.22, 5646471, s, blue
3753, 20180922, 1251, 7, 0, 3036491, l, black
3754, 20180922, 21484.21, 1356, 75, 049681, xs, Red
3756, 20180922, -59.18, 2, 0.3333333333333333, 2038593, M, Blue
3757, 20180923, 3177.4, 21, .14, 203521, xL, black
];
```

Qlik Sense table showing the results from different uses of the *Num* function in the load script. The fourth column of the table contains incorrect formatting use, for example purposes.

No formatting	0	#,#0	# ###,00	# ###,00 ,',',''	#,###.00, '',''	\$#,###.00
-59.18	-59	-59	-59###,00	-59,18	-59.18	\$-59,18
15.75	16	16	16###,00	15,75	15.75	\$15,75
1251	1251	1,251	1251###,00	1 251,00	1,251.00	\$1,251.00
3177.4	3177	3,177	3177###,00	3 177,40	3,177.40	\$3,177.40
5356.31	5356	5,356	5356###,00	5 356,31	5,356.31	\$5,356.31
12423.56	12424	12,424	12424###,00	12 423,56	12,423.56	\$12,423.56
21484.21	21484	21,484	21484###,00	21 484,21	21,484.21	\$21,484.21



Example: Load script

### Load script

*Num* can be used in a load script to format a number as a percentage.

In the **Data load editor**, create a new section, and then add the example script and run it. Then add, at least, the fields listed in the results column to a sheet in your app to see the result.

```
SET ThousandSep=',';
SET DecimalSep='.';
Transactions:
Load
*,
Num(discount,'####0%') as [Discount #,##0%]
;
Load * Inline [
transaction_id, transaction_date, transaction_amount, transaction_quantity, discount,
customer_id, size, color_code
3750, 20180830, 12423.56, 23, 0,2038593, L, Red
3751, 20180907, 5356.31, 6, 0.1, 203521, m, orange
3752, 20180916, 15.75, 1, 0.22, 5646471, s, blue
3753, 20180922, 1251, 7, 0, 3036491, l, black
3754, 20180922, 21484.21, 1356, 75, 049681, xs, Red
3756, 20180922, -59.18, 2, 0.3333333333333333, 2038593, M, Blue
3757, 20180923, 3177.4, 21, .14, 203521, XL, black
];
```

Qlik Sense table showing the results of the *Num* function being used in the load script to format percentages.

Discount	Discount #,##0%
0.3333333333333333	33%
0.22	22%
0	0%
.14	14%
0.1	10%
0	0%
75	7,500%

## Time

**Time()** formats an expression as a time value, in the time format set in the system variables in the data load script, or in the operating system, unless a format string is supplied.

### Syntax:

```
Time (number [, format])
```

**Return data type:** dual

**Arguments:**

Arguments

Argument	Description
number	The number to be formatted.
format	String describing how the resulting time string is to be formatted. If omitted, the short date format, time format, and decimal separator set in the operating system is used.

Examples and results:

The examples below assume the following default settings:

- Time format setting 1: hh:mm:ss
- Time format setting 2: hh.mm.ss

**Example:**

Time( A )  
where A=0.375

Results table

Results	Setting 1	Setting 2
String:	09:00:00	09.00.00
Number:	0.375	0.375

**Example:**

Time( A )  
where A=35648.375

Results table

Results	Setting 1	Setting 2
String:	09:00:00	09.00.00
Number:	35648.375	35648.375

**Example:**

Time( A, 'hh-mm' )  
where A=0.99999

Results table

Results	Setting 1	Setting 2
String:	23-59	23-59
Number:	0.99999	0.99999

## Timestamp

**TimeStamp()** formats an expression as a date and time value, in the timestamp format set in the system variables in the data load script, or in the operating system, unless a format string is supplied.

### Syntax:

```
TimeStamp(number[, format])
```

**Return data type:** dual

### Arguments:

Arguments

Argument	Description
number	The number to be formatted.
format	String describing how the resulting timestamp string is to be formatted. If omitted, the short date format, time format, and decimal separator set in the operating system is used.

Examples and results:

The examples below assume the following default settings:

- TimeStampFormat setting 1: YY-MM-DD hh:mm:ss
- TimeStampFormat setting 2: M/D/YY hh:mm:ss

### Example:

```
TimeStamp( A )
where A=35648.375
```

Results table

Results	Setting 1	Setting 2
String:	97-08-06 09:00:00	8/6/97 09:00:00
Number:	35648.375	35648.375

**Example:**

Timestamp( A, 'YYYY-MM-DD hh.mm')  
 where A=35648

Results table

Results	Setting 1	Setting 2
String:	1997-08-06 00.00	1997-08-06 00.00
Number:	35648	35648

## 8.13 General numeric functions

In these general numeric functions, the arguments are expressions where **x** should be interpreted as a real valued number. All functions can be used in both data load scripts and chart expressions.

### General numeric functions overview

Each function is described further after the overview. You can also click the function name in the syntax to immediately access the details for that specific function.

bitcount

**BitCount()** returns how many bits in the binary equivalent of a decimal number are set to 1. That is, the function returns the number of set bits in **integer\_number**, where **integer\_number** is interpreted as a signed 32-bit integer.

**BitCount**(integer\_number)

div

**Div()** returns the integer part of the arithmetic division of the first argument by the second argument. Both parameters are interpreted as real numbers, that is, they do not have to be integers.

**Div**(integer\_number1, integer\_number2)

fabs

**Fabs()** returns the absolute value of **x**. The result is a positive number.

**Fabs**(x)

fact

**Fact()** returns the factorial of a positive integer **x**.

**Fact**(x)

frac

**Frac()** returns the fraction part of **x**.

**Frac**(x)

sign

**Sign()** returns 1, 0 or -1 depending on whether **x** is a positive number, 0, or a negative number.

**Sign(x)**

### Combination and permutation functions

combin

**Combin()** returns the number of combinations of **q** elements that can be picked from a set of **p** items. As represented by the formula:  $\text{combin}(p, q) = p! / q!(p-q)!$  The order in which the items are selected is insignificant.

**Combin(p, q)**

permut

**Permut()** returns the number of permutations of **q** elements that can be selected from a set of **p** items. As represented by the formula:  $\text{Permut}(p, q) = (p)! / (p - q)!$  The order in which the items are selected is significant.

**Permut(p, q)**

### Modulo functions

fmod

**fmod()** is a generalized modulo function that returns the remainder part of the integer division of the first argument (the dividend) by the second argument (the divisor). The result is a real number. Both arguments are interpreted as real numbers, that is, they do not have to be integers.

**Fmod(a, b)**

mod

**Mod()** is a mathematical modulo function that returns the non-negative remainder of an integer division. The first argument is the dividend, the second argument is the divisor, Both arguments must be integer values.

**Mod(integer\_number1, integer\_number2)**

### Parity functions

even

**Even()** returns True (-1), if **integer\_number** is an even integer or zero. It returns False (0), if **integer\_number** is an odd integer, and NULL if **integer\_number** is not an integer.

**Even(integer\_number)**

odd

**Odd()** returns True (-1), if **integer\_number** is an odd integer or zero. It returns False (0), if **integer\_number** is an even integer, and NULL if **integer\_number** is not an integer.

**Odd(integer\_number)**

## Rounding functions

ceil

**Ceil()** rounds up a number to the nearest multiple of the **step** shifted by the **offset** number.

```
Ceil(x[, step[, offset]])
```

floor

**Floor()** rounds down a number to the nearest multiple of the **step** shifted by the **offset** number.

```
Floor(x[, step[, offset]])
```

round

**Round()** returns the result of rounding a number up or down to the nearest multiple of **step** shifted by the **offset** number.

```
Round( x [ , step [ , offset ] ] )
```

## BitCount

**BitCount()** returns how many bits in the binary equivalent of a decimal number are set to 1. That is, the function returns the number of set bits in **integer\_number**, where **integer\_number** is interpreted as a signed 32-bit integer.

**Syntax:**

```
BitCount(integer_number)
```

**Return data type:** integer

**Examples and results:**

Examples and results

Examples	Results
BitCount ( 3 )	3 is binary 11, therefore this returns 2
BitCount ( -1 )	-1 is 64 ones in binary, therefore this returns 64

## Ceil

**Ceil()** rounds up a number to the nearest multiple of the **step** shifted by the **offset** number.

Compare with the **floor** function, which rounds input numbers down.

**Syntax:**

```
Ceil(x[, step[, offset]])
```

**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
<b>x</b>	Input number.
<b>step</b>	Interval increment. The default value is 1.
<b>offset</b>	Defines the base of the step interval. The default value is 0.

**Examples and results:**

Examples and results

Examples	Results
<code>ceil(2.4 )</code>	Returns 3  In this example, the size of the step is 1 and the base of the step interval is 0.  The intervals are ... $0 < x \leq 1$ , $1 < x \leq 2$ , <b><math>2 &lt; x \leq 3</math></b> , $3 < x \leq 4$ ...
<code>ceil(4.2 )</code>	Returns 5
<code>ceil(3.88 ,0.1)</code>	Returns 3.9  In this example, the size of the interval is 0.1 and the base of the interval is 0.  The intervals are ... $3.7 < x \leq 3.8$ , <b><math>3.8 &lt; x \leq 3.9</math></b> , $3.9 < x \leq 4.0$ ...
<code>ceil(3.88 ,5)</code>	Returns 5
<code>ceil(1.1 ,1)</code>	Returns 2
<code>ceil(1.1 ,1,0.5)</code>	Returns 1.5  In this example, the size of the step is 1 and the offset is 0.5. It means that the base of the step interval is 0.5 and not 0.  The intervals are ... <b><math>0.5 &lt; x \leq 1.5</math></b> , $1.5 < x \leq 2.5$ , $2.5 < x \leq 3.5$ , $3.5 < x \leq 4.5$ ...
<code>ceil(1.1 ,1,-0.01)</code>	Returns 1.99  The intervals are ... $-0.01 < x \leq 0.99$ , <b><math>0.99 &lt; x \leq 1.99</math></b> , $1.99 < x \leq 2.99$ ...

## Combin

**Combin()** returns the number of combinations of **q** elements that can be picked from a set of **p** items. As represented by the formula:  $\text{combin}(p,q) = \frac{p!}{q!(p-q)!}$ . The order in which the items are selected is insignificant.

### Syntax:

```
Combin(p, q)
```

**Return data type:** integer

### Limitations:

Non-integer items will be truncated.

### Examples and results:

Examples and results

Examples	Results
How many combinations of 7 numbers can be picked from a total of 35 lottery numbers?  combin( 35,7 )	Returns 6,724,520

## Div

**Div()** returns the integer part of the arithmetic division of the first argument by the second argument. Both parameters are interpreted as real numbers, that is, they do not have to be integers.

### Syntax:

```
Div(integer_number1, integer_number2)
```

**Return data type:** integer

### Examples and results:

Examples and results

Examples	Results
Div( 7,2 )	Returns 3
Div( 7.1,2.3 )	Returns 3
Div( 9,3 )	Returns 3
Div( -4,3 )	Returns -1
Div( 4,-3 )	Returns -1
Div( -4,-3 )	Returns 1



## Even

**Even()** returns True (-1), if **integer\_number** is an even integer or zero. It returns False (0), if **integer\_number** is an odd integer, and NULL if **integer\_number** is not an integer.

### Syntax:

```
Even(integer_number)
```

**Return data type:** Boolean

### Examples and results:

Examples and results

Examples	Results
Even( 3 )	Returns 0, False
Even( 2 * 10 )	Returns -1, True
Even( 3.14 )	Returns NULL

## Fabs

**Fabs()** returns the absolute value of **x**. The result is a positive number.

### Syntax:

```
fabs(x)
```

**Return data type:** numeric

### Examples and results:

Examples and results

Examples	Results
fabs( 2.4 )	Returns 2.4
fabs( -3.8 )	Returns 3.8

## Fact

**Fact()** returns the factorial of a positive integer **x**.

### Syntax:

```
Fact(x)
```

**Return data type:** integer

### Limitations:

If the number **x** is not an integer, it will be truncated. Non-positive numbers will return NULL.

**Examples and results:**

Examples and results

Examples	Results
Fact( 1 )	Returns 1
Fact( 5 )	Returns 120 ( 1 * 2 * 3 * 4 * 5 = 120 )
Fact( -5 )	Returns NULL

## Floor

**Floor()** rounds down a number to the nearest multiple of the **step** shifted by the **offset** number.

Compare with the **ceil** function, which rounds input numbers up.

**Syntax:**

```
Floor(x[, step[, offset]])
```

**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
<b>x</b>	Input number.
<b>step</b>	Interval increment. The default value is 1.
<b>offset</b>	Defines the base of the step interval. The default value is 0.

**Examples and results:**

Examples and results

Examples	Results
Floor(2.4)	Returns 2  In this example, the size of the step is 1 and the base of the step interval is 0.  The intervals are ...0 <= x <1, 1 <= x < 2, <b>2&lt;= x &lt;3</b> , 3<= x <4....
Floor(4.2)	Returns 4

Examples	Results
Floor(3.88 ,0.1)	Returns 3.8  In this example, the size of the interval is 0.1 and the base of the interval is 0.  The intervals are ... 3.7 <= x < 3.8, <b>3.8 &lt;= x &lt; 3.9</b> , 3.9 <= x < 4.0...
Floor(3.88 ,5)	Returns 0
Floor(1.1 ,1)	Returns 1
Floor(1.1 ,1,0.5)	Returns 0.5  In this example, the size of the step is 1 and the offset is 0.5. It means that the base of the step interval is 0.5 and not 0.  The intervals are ... <b>0.5 &lt;= x &lt;1.5</b> , 1.5 <= x < 2.5, 2.5<= x <3.5,...

## Fmod

**fmod()** is a generalized modulo function that returns the remainder part of the integer division of the first argument (the dividend) by the second argument (the divisor). The result is a real number. Both arguments are interpreted as real numbers, that is, they do not have to be integers.

### Syntax:

```
fmod( a, b)
```

**Return data type:** numeric

### Arguments:

#### Arguments

Argument	Description
<b>a</b>	Dividend
<b>b</b>	Divisor

### Examples and results:

#### Examples and results

Examples	Results
fmod( 7,2 )	Returns 1
fmod( 7.5,2 )	Returns 1.5
fmod( 9,3 )	Returns 0
fmod( -4,3 )	Returns -1

Examples	Results
<code>fmod( 4, -3 )</code>	Returns 1
<code>fmod( -4, -3 )</code>	Returns -1

## Frac

**Frac()** returns the fraction part of **x**.

The fraction is defined in such a way that  $\text{Frac}(x) + \text{Floor}(x) = x$ . In simple terms, this means that the fractional part of a positive number is the difference between the number (x) and the integer that precedes the fractional part.

For example: The fractional part of 11.43 =  $11.43 - 11 = 0.43$

For a negative number, say -1.4,  $\text{Floor}(-1.4) = -2$ , which produces the following result:

The fractional part of -1.4 =  $-1.4 - (-2) = -1.4 + 2 = 0.6$

### Syntax:

```
Frac(x)
```

**Return data type:** numeric

### Arguments:

#### Arguments

Argument	Description
<b>x</b>	Number to return fraction for.

### Examples and results:

#### Examples and results

Examples	Results
<code>Frac( 11.43 )</code>	Returns 0.43
<code>Frac( -1.4 )</code>	Returns 0.6
Extract the time component from the numeric representation of a timestamp, thus omitting the date.  <code>Time(Frac(44518.663888889))</code>	Returns 3:56:00 PM

## Mod

**Mod()** is a mathematical modulo function that returns the non-negative remainder of an integer division. The first argument is the dividend, the second argument is the divisor, Both arguments must be integer values.

### Syntax:

```
Mod(integer_number1, integer_number2)
```

**Return data type:** integer

### Limitations:

**integer\_number2** must be greater than 0.

### Examples and results:

Examples and results

Examples	Results
Mod( 7,2 )	Returns 1
Mod( 7.5,2 )	Returns NULL
Mod( 9,3 )	Returns 0
Mod( -4,3 )	Returns 2
Mod( 4,-3 )	Returns NULL
Mod( -4,-3 )	Returns NULL

## Odd

**Odd()** returns True (-1), if **integer\_number** is an odd integer or zero. It returns False (0), if **integer\_number** is an even integer, and NULL if **integer\_number** is not an integer.

### Syntax:

```
Odd(integer_number)
```

**Return data type:** Boolean

### Examples and results:

Examples and results

Examples	Results
odd( 3 )	Returns -1, True
odd( 2 * 10 )	Returns 0, False
odd( 3.14 )	Returns NULL

## Permut

**Permut()** returns the number of permutations of **q** elements that can be selected from a set of **p** items. As represented by the formula:  $\text{Permut}(p,q) = (p)! / (p - q)!$  The order in which the items are selected is significant.

### Syntax:

```
Permut (p, q)
```

**Return data type:** integer

### Limitations:

Non-integer arguments will be truncated.

### Examples and results:

Examples and results

Examples	Results
In how many ways could the gold, silver and bronze medals be distributed after a 100 m final with 8 participants?  Permut( 8,3 )	Returns 336

## Round

**Round()** returns the result of rounding a number up or down to the nearest multiple of **step** shifted by the **offset** number.

If the number to round is exactly in the middle of an interval, it is rounded upwards.

### Syntax:

```
Round (x[, step[, offset]])
```

**Return data type:** numeric



*If you are rounding a floating point number you may observe erroneous results. These rounding errors occur because floating point numbers are represented by a finite number of binary digits. Therefore, results are calculated using a number that is already rounded. If these rounding errors will affect your work, multiply the numbers to convert them to integers before rounding.*

### Arguments:

Arguments

Argument	Description
<b>x</b>	Input number.
<b>step</b>	Interval increment. The default value is 1.
<b>offset</b>	Defines the base of the step interval. The default value is 0.

### Examples and results:

Examples and results

Examples	Results
Round(3.8 )	Returns 4  In this example, the size of the step is 1 and the base of the step interval is 0.  The intervals are ...0 <= x <1, 1 <= x < 2, 2<= x <3, <b>3&lt;= x &lt;4</b> ...
Round(3.8,4 )	Returns 4
Round(2.5 )	Returns 3.  In this example, the size of the step is 1 and the base of the step interval is 0.  The intervals are ...0 <= x <1, 1 <= x <2, <b>2&lt;= x &lt;3</b> ...
Round(2,4 )	Returns 4. Rounded up because 2 is exactly half of the step interval of 4.  In this example, the size of the step is 4 and the base of the step interval is 0.  The intervals are ... <b>0 &lt;= x &lt;4</b> , 4 <= x <8, 8<= x <12...
Round(2,6 )	Returns 0. Rounded down because 2 is less than half of the step interval of 6.  In this example, the size of the step is 6 and the base of the step interval is 0.  The intervals are ... <b>0 &lt;= x &lt;6</b> , 6 <= x <12, 12<= x <18...

Examples	Results
Round(3.88 ,0.1)	Returns 3.9  In this example, the size of the step is 0.1 and the base of the step interval is 0.  The intervals are ... 3.7 <= x <3.8, <b>3.8 &lt;= x &lt;3.9</b> , 3.9 <= x < 4.0...
Round(3.88875,1/1000)	Returns 3.889  In this example, the size of the step is 0.001, which rounds the number up and limits it to three decimal places.
Round(3.88 ,5)	Returns 5
Round(1.1 ,1,0.5)	Returns 1.5  In this example, the size of the step is 1 and the base of the step interval is 0.5.  The intervals are ... <b>0.5 &lt;= x &lt;1.5</b> , 1.5 <= x <2.5, 2.5<= x <3.5...

### Sign

**Sign()** returns 1, 0 or -1 depending on whether **x** is a positive number, 0, or a negative number.

#### Syntax:

**Sign(x)**

**Return data type:** numeric

#### Limitations:

If no numeric value is found, NULL is returned.

#### Examples and results:

Examples and results

Examples	Results
sign( 66 )	Returns 1
sign( 0 )	Returns 0
sign( - 234 )	Returns -1

## 8.14 Geospatial functions

These functions are used to handle geospatial data in map visualizations. Qlik Sense follows GeoJSON specifications for geospatial data and supports the following:



- Point
- Linestring
- Polygon
- Multipolygon

For more information on GeoJSON specifications, see:

 [GeoJSON.org](https://geojson.org)

### Geospatial functions overview

Each function is described further after the overview. You can also click the function name in the syntax to immediately access the details for that specific function.

There are two categories of geospatial functions: aggregation and non-aggregation.

Aggregation functions take a geometry set (points or areas) as input, and return a single geometry. For example, multiple areas can be merged together, and a single boundary for the aggregation can be drawn on the map.

Non-aggregation function take a single geometry and return one geometry. For example, for the function `GeoGetPolygonCenter()`, if the boundary geometry of one area is set as input, the point geometry (longitude and latitude) for the center of that area is returned.

The following are aggregation functions:

#### **GeoAggrGeometry**

**GeoAggrGeometry()** is used to aggregate a number of areas into a larger area, for example aggregating a number of sub-regions to a region.

```
GeoAggrGeometry (field_name)
```

#### **GeoBoundingBox**

**GeoBoundingBox()** is used to aggregate a geometry into an area and calculate the smallest bounding box that contains all coordinates.

```
GeoBoundingBox (field_name)
```

#### **GeoCountVertex**

**GeoCountVertex()** is used to find the number of vertices a polygon geometry contains.

```
GeoCountVertex (field_name)
```

#### **GeoInvProjectGeometry**

**GeoInvProjectGeometry()** is used to aggregate a geometry into an area and apply the inverse of a projection.

```
GeoInvProjectGeometry (type, field_name)
```

#### **GeoProjectGeometry**

**GeoProjectGeometry()** is used to aggregate a geometry into an area and apply a projection.

```
GeoProjectGeometry (type, field_name)
```

### GeoReduceGeometry

**GeoReduceGeometry()** is used to reduce the number of vertices of a geometry, and to aggregate a number of areas into one area, but still displaying the boundary lines from the individual areas.

```
GeoReduceGeometry (geometry)
```

The following are non-aggregation functions:

### GeoGetBoundingBox

**GeoGetBoundingBox()** is used in scripts and chart expressions to calculate the smallest geospatial bounding box that contains all coordinates of a geometry.

```
GeoGetBoundingBox (geometry)
```

### GeoGetPolygonCenter

**GeoGetPolygonCenter()** is used in scripts and chart expressions to calculate and return the center point of a geometry.

```
GeoGetPolygonCenter (geometry)
```

### GeoMakePoint

**GeoMakePoint()** is used in scripts and chart expressions to create and tag a point with latitude and longitude.

```
GeoMakePoint (lat_field_name, lon_field_name)
```

### GeoProject

**GeoProject()** is used in scripts and chart expressions to apply a projection to a geometry.

```
GeoProject (type, field_name)
```

## GeoAggrGeometry

**GeoAggrGeometry()** is used to aggregate a number of areas into a larger area, for example aggregating a number of sub-regions to a region.

### Syntax:

```
GeoAggrGeometry (field_name)
```

**Return data type:** string

### Arguments:

#### Arguments

Argument	Description
field_name	A field or expression referring to a field containing the geometry to be represented. This could be either a point (or set of points) giving longitude and latitude, or an area.

Typically, **GeoAggrGeometry()** can be used to combine geospatial boundary data. For example, you might have postcode areas for suburbs in a city and sales revenues for each area. If a sales person's territory covers several postcode areas, it might be useful to present total sales by sales territory, rather than individual areas, and show the results on a color-filled map.

**GeoAggrGeometry()** can calculate the aggregation of the individual suburb geometries and generate the merged territory geometry in the data model. If then, the sales territory boundaries are adjusted, when the data is reloaded the new merged boundaries and revenues are reflected in the map.

As **GeoAggrGeometry()** is an aggregating function, if you use it in the script a **LOAD** statement with a **Group by** clause is required.



*The boundary lines of maps created using **GeoAggrGeometry()** are those of the merged areas. If you want to display the individual boundary lines of the pre-aggregated areas, use **GeoReduceGeometry()**.*

Examples:

This example loads a KML file with area data, and then loads a table with the aggregated area data.

```
[MapSource]:
LOAD [world.Name],
     [world.Point],
     [world.Area]
FROM [lib://Downloads/world.kml]
(kml, Table is [world.shp/Features]);
```

```
Map:
LOAD world.Name,
     GeoAggrGeometry(world.Area) as [AggrArea]
resident MapSource Group By world.Name;
```

```
Drop Table MapSource;
```

### GeoBoundingBox

**GeoBoundingBox()** is used to aggregate a geometry into an area and calculate the smallest bounding box that contains all coordinates.

A GeoBoundingBox is represented as a list of four values: left, right, top, bottom.

**Syntax:**

```
GeoBoundingBox (field_name)
```

**Return data type:** string

**Arguments:**

Arguments

Argument	Description
field_name	A field or expression referring to a field containing the geometry to be represented. This could be either a point (or set of points) giving longitude and latitude, or an area.

GeoBoundingBox() aggregates a set of geometries and returns four coordinates for the smallest rectangle that contains all the coordinates of that aggregated geometry.

To visualize the result on a map, transfer the resulting string of four coordinates into a polygon format, tag the transferred field with a geopolygon format, and drag and drop that field into the map object. The rectangular boxes will then be displayed in the map visualization.

### GeoCountVertex

**GeoCountVertex()** is used to find the number of vertices a polygon geometry contains.

**Syntax:**

```
GeoCountVertex (field_name)
```

**Return data type:** integer

**Arguments:**

Arguments

Argument	Description
field_name	A field or expression referring to a field containing the geometry to be represented. This could be either a point (or set of points) giving longitude and latitude, or an area.

### GeoGetBoundingBox

**GeoGetBoundingBox()** is used in scripts and chart expressions to calculate the smallest geospatial bounding box that contains all coordinates of a geometry.

A geospatial bounding box, created by the function GeoBoundingBox() is represented as a list of four values: left, right, top, bottom.

**Syntax:**

```
GeoGetBoundingBox (field_name)
```

**Return data type:** string

**Arguments:**

Arguments

Argument	Description
field_name	A field or expression referring to a field containing the geometry to be represented. This could be either a point (or set of points) giving longitude and latitude, or an area.



*Do not use the **Group by** clause in the data load editor with this and other non-aggregating geospatial functions, because this will cause an error on load.*

## GeoGetPolygonCenter

**GeoGetPolygonCenter()** is used in scripts and chart expressions to calculate and return the center point of a geometry.

In some cases, the requirement is to plot a dot instead of color fill on a map. If the existing geospatial data is only available in the form of area geometry (for example, a boundary), use

**GeoGetPolygonCenter()** to retrieve a pair of longitude and latitude for the center of area.

**Syntax:**

```
GeoGetPolygonCenter (field_name)
```

**Return data type:** string

**Arguments:**

Arguments

Argument	Description
field_name	A field or expression referring to a field containing the geometry to be represented. This could be either a point (or set of points) giving longitude and latitude, or an area.



*Do not use the **Group by** clause in the data load editor with this and other non-aggregating geospatial functions, because this will cause an error on load.*

## GeoInvProjectGeometry

**GeoInvProjectGeometry()** is used to aggregate a geometry into an area and apply the inverse of a projection.

### Syntax:

```
GeoInvProjectGeometry(type, field_name)
```

**Return data type:** string

### Arguments:

#### Arguments

Argument	Description
type	Projection type used in transforming the geometry of the map. This can take one of two values: 'unit', (default), which results in a 1:1 projection, or 'mercator', which uses the standard Mercator projection.
field_name	A field or expression referring to a field containing the geometry to be represented. This could be either a point (or set of points) giving longitude and latitude, or an area.

Example:

#### Scripting example

Example	Result
In a Load statement: GeoInvProjectGeometry ( 'mercator', AreaPolygon) as InvProjectGeometry	The geometry loaded as <b>AreaPolygon</b> is transformed using the inverse transformation of the Mercator projection and stored as <b>InvProjectGeometry</b> for use in visualizations.

## GeoMakePoint

**GeoMakePoint()** is used in scripts and chart expressions to create and tag a point with latitude and longitude. GeoMakePoint returns points in the order of longitude and latitude.

### Syntax:

```
GeoMakePoint(lat_field_name, lon_field_name)
```

**Return data type:** string, formatted [longitude, latitude]

### Arguments:

#### Arguments

Argument	Description
lat_field_name	A field or expression referring to a field representing the latitude of the point.
lon_field_name	A field or expression referring to a field representing the longitude of the point.



Do not use the **Group by** clause in the data load editor with this and other non-aggregating geospatial functions, because this will cause an error on load.

## GeoProject

**GeoProject()** is used in scripts and chart expressions to apply a projection to a geometry.

### Syntax:

```
GeoProject (type, field_name)
```

**Return data type:** string

### Arguments:

#### Arguments

Argument	Description
type	Projection type used in transforming the geometry of the map. This can take one of two values: 'unit', (default), which results in a 1:1 projection, or 'mercator', which uses the web Mercator projection.
field_name	A field or expression referring to a field containing the geometry to be represented. This could be either a point (or set of points) giving longitude and latitude, or an area.



Do not use the **Group by** clause in the data load editor with this and other non-aggregating geospatial functions, because this will cause an error on load.

Example:

#### Script examples

Example	Result
In a Load statement: GeoProject ( 'mercator', Area) as GetProject	The Mercator projection is applied to the geometry loaded as <b>Area</b> , and the result is stored as <b>GetProject</b> .

## GeoProjectGeometry

**GeoProjectGeometry()** is used to aggregate a geometry into an area and apply a projection.

### Syntax:

```
GeoProjectGeometry (type, field_name)
```

**Return data type:** string

**Arguments:**

Arguments

Argument	Description
type	Projection type used in transforming the geometry of the map. This can take one of two values: 'unit', (default), which results in a 1:1 projection, or 'mercator', which uses the web Mercator projection.
field_name	A field or expression referring to a field containing the geometry to be represented. This could be either a point (or set of points) giving longitude and latitude, or an area.

Example:

Example	Result
In a Load statement: GeoProjectGeometry ( 'mercator', AreaPolygon ) as ProjectGeometry	The geometry loaded as <b>AreaPolygon</b> is transformed using the Mercator projection and stored as <b>ProjectGeometry</b> for use in visualizations.

## GeoReduceGeometry

**GeoReduceGeometry()** is used to reduce the number of vertices of a geometry, and to aggregate a number of areas into one area, but still displaying the boundary lines from the individual areas.

**Syntax:**

```
GeoReduceGeometry (field_name[, value])
```


**Return data type:** string

**Arguments:**

Arguments

Argument	Description
field_name	A field or expression referring to a field containing the geometry to be represented. This could be either a point (or set of points) giving longitude and latitude, or an area.



Argument	Description
value	<p>The amount of reduction to apply to the geometry. The range is from 0 to 1, with 0 representing no reduction and 1 representing maximal reduction of vertices.</p> <div style="border: 1px solid #ccc; padding: 10px; margin-top: 10px;">  <p><i>Using a value of 0.9 or higher with a complex data set can reduce the number of vertices to a level where the visual representation is inaccurate.</i></p> </div>

**GeoReduceGeometry()** also performs a similar function to **GeoAggrGeometry()** in that it aggregates a number of areas into one area. The difference being that individual boundary lines from the pre-aggregation data are displayed on the map if you use **GeoReduceGeometry()**.

As **GeoReduceGeometry()** is an aggregating function, if you use it in the script a **LOAD** statement with a **Group by** clause is required.

Examples:

This example loads a KML file with area data, and then loads a table with the reduced and aggregated area data.

```
[MapSource]:
LOAD [world.Name],
      [world.Point],
      [world.Area]
FROM [lib://Downloads/world.kml]
(kml, Table is [world.shp/Features]);
```

```
Map:
LOAD world.Name,
      GeoReduceGeometry(world.Area,0.5) as [ReducedArea]
resident MapSource Group By world.Name;
```

```
Drop Table MapSource;
```

## 8.15 Interpretation functions

The interpretation functions evaluate the contents of input text fields or expressions, and impose a specified data format on the resulting numeric value. With these functions, you can specify the format of the number, in accordance with its data type, including attributes such as: decimal separator, thousands separator, and date format.

The interpretation functions all return a dual value with both the string and the number value, but can be thought of as performing a string-to-number conversion. The functions take the text value of the input expression and generate a number representing the string.

In contrast, the formatting functions do the opposite: they take numeric expressions and evaluate them as strings, specifying the display format of the resulting text.

If no interpretation functions are used, Qlik Sense interprets the data as a mix of numbers, dates, times, time stamps and strings, using the default settings for number format, date format, and time format, defined by script variables and by the operating system.

All interpretation functions can be used in both data load scripts and chart expressions.



*All number representations are given with a decimal point as the decimal separator.*

### Interpretation functions overview

Each function is described further after the overview. You can also click the function name in the syntax to immediately access the details for that specific function.

#### **Date#**

**Date#** evaluates an expression as a date in the format specified in the second argument, if supplied. If the format code is omitted, the default date format set in the operating system is used.

```
Date# (page 1267) (text[, format])
```

#### **Interval#**

**Interval#()** evaluates a text expression as a time interval in the format set in the operating system, by default, or in the format specified in the second argument, if supplied.

```
Interval# (page 1268) (text[, format])
```

#### **Money#**

**Money#()** converts a text string to a money value, in the format set in the load script or the operating system, unless a format string is supplied. Custom decimal and thousand separator symbols are optional parameters.

```
Money# (page 1269) (text[, format[, dec_sep[, thou_sep ] ] ])
```

#### **Num#**

**Num#()** interprets a text string as a numerical value, that is it converts the input string to a number using the format specified in the second parameter. If the second parameter is omitted, it uses the decimal and thousand separators set in the data load script. Custom decimal and thousand separator symbols are optional parameters.

```
Num# (page 1270) (text[ , format[, dec_sep[ , thou_sep]]])
```

#### **Text**

**Text()** forces the expression to be treated as text, even if a numeric interpretation is possible.

```
Text (expr)
```

#### **Time#**

**Time#()** evaluates an expression as a time value, in the time format set in the data load script or the operating system, unless a format string is supplied..

`Time# (page 1271) (text[, format])`

### Timestamp#

**Timestamp#()** evaluates an expression as a date and time value, in the timestamp format set in the data load script or the operating system, unless a format string is supplied.

`Timestamp# (page 1272) (text[, format])`

### See also:

[Formatting functions \(page 1231\)](#)

### Date#

**Date#** evaluates an expression as a date in the format specified in the second argument, if supplied.

### Syntax:

`Date# (text[, format])`

**Return data type:** dual

### Arguments:

#### Arguments

Argument	Description
text	The text string to be evaluated.
format	String describing the format of the text string to be evaluated. If omitted, the date format set in the system variables in the data load script or the operating system is used.

Examples and results:

The following example uses the date format **M/D/YYYY**. The date format is specified in the **SET DateFormat** statement at the top of the data load script.

Add this example script to your app and run it.

```
Load *,
Num(Date#(StringDate)) as Date;
LOAD * INLINE [
StringDate
8/7/97
8/6/1997
]
```

If you create a table with **StringDate** and **Date** as dimensions, the results are as follows:

Results

StringDate	Date
8/7/97	35649
8/6/1997	35648

## Interval#

**Interval#()** evaluates a text expression as a time interval in the format set in the operating system, by default, or in the format specified in the second argument, if supplied.

### Syntax:

```
Interval#(text[, format])
```

**Return data type:** dual

### Arguments:

Arguments

Argument	Description
text	The text string to be evaluated.
format	String describing the expected input format to use when converting the string to a numeric interval.  If omitted, the short date format, time format, and decimal separator set in the operating system are used.

The **interval#** function converts a text time interval to a numeric equivalent.

Examples and results:

The examples below assume the following operating system settings:

- Short date format: YY-MM-DD
- Time format: M/D/YY
- Number decimal separator: .

Results

Example	Result
Interval#( A, 'D hh:mm' ) where A='1 09:00'	1.375

## Money#

**Money#()** converts a text string to a money value, in the format set in the load script or the operating system, unless a format string is supplied. Custom decimal and thousand separator symbols are optional parameters.

### Syntax:

```
Money#(text[, format[, dec_sep [, thou_sep ] ] ])
```

**Return data type:** dual

### Arguments:

#### Arguments

Argument	Description
text	The text string to be evaluated.
format	String describing the expected input format to use when converting the string to a numeric interval.  If omitted, the money format set in the operating system is used.
dec_sep	String specifying the decimal number separator. If omitted, the MoneyDecimalSep value set in the data load script is used.
thou_sep	String specifying the thousands number separator. If omitted, the MoneyThousandSep value set in the data load script is used.

The **money#** function generally behaves just like the **num#** function but takes its default values for decimal and thousand separator from the script variables for money format or the system settings for currency.

Examples and results:

The examples below assume the two following operating system settings:

- Money format default setting 1: kr # ##0,00
- Money format default setting 2: \$ #,##0.00

```
Money#(A , '# ##0,00 kr' )
```

where A=35 648,37 kr

#### Results

Results	Setting 1	Setting 2
<b>String</b>	35 648.37 kr	35 648.37 kr
<b>Number</b>	35648.37	3564837

Money#( A, ' \$#', '.', ',' )  
 where A= \$35,648.37

Results

Results	Setting 1	Setting 2
<b>String</b>	\$35,648.37	\$35,648.37
<b>Number</b>	35648.37	35648.37

### Num#

**Num#()** interprets a text string as a numerical value, that is it converts the input string to a number using the format specified in the second parameter. If the second parameter is omitted, it uses the decimal and thousand separators set in the data load script. Custom decimal and thousand separator symbols are optional parameters.

#### Syntax:

```
Num#(text[, format[, dec_sep [, thou_sep ] ] ])
```

**Return data type:** dual

The **Num#()** function returns a dual value with both the string and the numeric value. The function takes the textual representation of the input expression and generates a number. It does not change the format of the number: the output is formatted in the same way as the input.

#### Arguments:

Arguments

Argument	Description
text	The text string to be evaluated.
format	String specifying the number format used in the first parameter. If omitted, the decimal and thousand separators that are set in the data load script are used.
dec_sep	String specifying the decimal number separator. If omitted, the value of the variable DecimalSep that is set in the data load script is used.
thou_sep	String specifying the thousands number separator. If omitted, the value of the variable ThousandSep that is set in the data load script is used.

Examples and results:

The following table shows the result of *Num#(A, '#', '.', ',')* for different values of A.

Results

A	String representation	Numeric value (here displayed with decimal point)
35,648.31	35,648.31	35648.31

A	String representation	Numeric value (here displayed with decimal point)
35 648.312	35 648.312	35648.312
35.648,3123	35.648,3123	-
35 648,31234	35 648,31234	-

### Text

**Text()** forces the expression to be treated as text, even if a numeric interpretation is possible.

**Syntax:**

**Text** (expr)

**Return data type:** dual

**Example:**

Text( A )  
where A=1234

Results	
String	Number
1234	-

**Example:**

Text( pi( ) )

Results	
String	Number
3.1415926535898	-

### Time#

**Time#()** evaluates an expression as a time value, in the time format set in the data load script or the operating system, unless a format string is supplied..

**Syntax:**

**time#**(text[, format])

**Return data type:** dual

**Arguments:**

Arguments

Argument	Description
text	The text string to be evaluated.
format	String describing the format of the text string to be evaluated. If omitted, the short date format, time format, and decimal separator set in the operating system is used.

**Example:**

- Time format default setting 1: hh:mm:ss
- Time format default setting 2: hh.mm.ss

`time#( A )`  
 where A=09:00:00

Results

Results	Setting 1	Setting 2
String:	09:00:00	09:00:00
Number:	0.375	-

**Example:**

- Time format default setting 1: hh:mm:ss
- Time format default setting 2: hh.mm.ss

`time#( A, 'hh.mm' )`  
 where A=09.00

Results

Results	Setting 1	Setting 2
String:	09.00	09.00
Number:	0.375	0.375

### Timestamp#

**Timestamp#()** evaluates an expression as a date and time value, in the timestamp format set in the data load script or the operating system, unless a format string is supplied.



### Syntax:

```
timestamp#(text[, format])
```

**Return data type:** dual

### Arguments:

Arguments

Argument	Description
text	The text string to be evaluated.
format	String describing the format of the text string to be evaluated. If omitted, the short date format, time format, and decimal separator set in the operating system is used. ISO 8601 is supported for timestamps.

### Example:

The following example uses the date format **M/D/YYYY**. The date format is specified in the **SET DateFormat** statement at the top of the data load script

Add this example script to your app and run it.

```
Load *,
Timestamp(Timestamp#(String)) as TS;
LOAD * INLINE [
String
2015-09-15T12:13:14
1952-10-16T13:14:00+0200
1109-03-01T14:15
];
```

If you create a table with **String** and **TS** as dimensions, the results are as follows:

Results

String	TS
2015-09-15T12:13:14	9/15/2015 12:13:14 PM
1952-10-16T13:14:00+0200	10/16/1952 11:14:00 AM
1109-03-01T14:15	3/1/1109 2:15:00 PM

## 8.16 Inter-record functions

Inter-record functions are used:

- In the data load script, when a value from previously loaded records of data is needed for the evaluation of the current record.
- In a chart expression, when another value from the data set of a visualization is needed.



Sorting on y-values in charts or sorting by expression columns in tables is not allowed when an inter-record chart function is used in any of the chart's expressions. These sort alternatives are therefore automatically disabled. When you use an inter-record chart function in a visualization or table, the sorting of the visualization will revert back to the sorted input to the inter-record function. This limitation does not apply to the equivalent script function, if there is one.



Self-referencing expression definitions can only reliably be made in tables with fewer than 100 rows, but this may vary depending on the hardware that the Qlik engine is running on.

### Row functions

These functions can only be used in chart expressions.

Above

**Above()** evaluates an expression at a row above the current row within a column segment in a table. The row for which it is calculated depends on the value of **offset**, if present, the default being the row directly above. For charts other than tables, **Above()** evaluates for the row above the current row in the chart's straight table equivalent.

```
Above - chart function([TOTAL [<fld{,fld}>]] expr [ , offset [,count]])
```

Below

**Below()** evaluates an expression at a row below the current row within a column segment in a table. The row for which it is calculated depends on the value of **offset**, if present, the default being the row directly below. For charts other than tables, **Below()** evaluates for the row below the current column in the chart's straight table equivalent.

```
Below - chart function([TOTAL [<fld{,fld}>]] expression [ , offset [,count ]])
```

Bottom

**Bottom()** evaluates an expression at the last (bottom) row of a column segment in a table. The row for which it is calculated depends on the value of **offset**, if present, the default being the bottom row. For charts other than tables, the evaluation is made on the last row of the current column in the chart's straight table equivalent.

```
Bottom - chart function([TOTAL [<fld{,fld}>]] expr [ , offset [,count ]])
```

Top

**Top()** evaluates an expression at the first (top) row of a column segment in a table. The row for which it is calculated depends on the value of **offset**, if present, the default being the top row. For charts other than tables, the **Top()** evaluation is made on the first row of the current column in the chart's straight table equivalent.

```
Top - chart function([TOTAL [<fld{,fld}>]] expr [ , offset [,count ]])
```

NoOfRows

**NoOfRows()** returns the number of rows in the current column segment in a table. For bitmap charts, **NoOfRows()** returns the number of rows in the chart's straight table equivalent.

```
NoOfRows - chart function ([TOTAL])
```

### Column functions

These functions can only be used in chart expressions.

Column

**Column()** returns the value found in the column corresponding to **ColumnNo** in a straight table, disregarding dimensions. For example **Column(2)** returns the value of the second measure column.

```
Column - chart function (ColumnNo)
```

Dimensionality

**Dimensionality()** returns the number of dimensions for the current row. In the case of pivot tables, the function returns the total number of dimension columns that have non-aggregation content, that is, do not contain partial sums or collapsed aggregates.

```
Dimensionality - chart function ( )
```

Secondarydimensionality

**SecondaryDimensionality()** returns the number of dimension pivot table rows that have non-aggregation content, that is, do not contain partial sums or collapsed aggregates. This function is the equivalent of the **dimensionality()** function for horizontal pivot table dimensions.

```
SecondaryDimensionality - chart function ( )
```

### Field functions

FieldIndex

**FieldIndex()** returns the position of the field value **value** in the field **field\_name** (by load order).

```
FieldIndex (field_name , value)
```

FieldValue

**FieldValue()** returns the value found in position **elem\_no** of the field **field\_name** (by load order).

```
FieldValue (field_name , elem_no)
```

FieldValueCount

**FieldValueCount()** is an **integer** function that returns the number of distinct values in a field.

```
FieldValueCount (field_name)
```

### Pivot table functions

These functions can only be used in chart expressions.

After

**After()** returns the value of an expression evaluated with a pivot table's dimension values as they appear in the column after the current column within a row segment in the pivot table.

```
After - chart function([TOTAL] expression [ , offset [,n]])
```

Before

**Before()** returns the value of an expression evaluated with a pivot table's dimension values as they appear in the column before the current column within a row segment in the pivot table.

```
Before - chart function([TOTAL] expression [ , offset [,n]])
```

First

**First()** returns the value of an expression evaluated with a pivot table's dimension values as they appear in the first column of the current row segment in the pivot table. This function returns NULL in all chart types except pivot tables.

```
First - chart function([TOTAL] expression [ , offset [,n]])
```

Last

**Last()** returns the value of an expression evaluated with a pivot table's dimension values as they appear in the last column of the current row segment in the pivot table. This function returns NULL in all chart types except pivot tables.

```
Last - chart function([TOTAL] expression [ , offset [,n]])
```

ColumnNo

**ColumnNo()** returns the number of the current column within the current row segment in a pivot table. The first column is number 1.

```
ColumnNo - chart function([TOTAL])
```

NoOfColumns

**NoOfColumns()** returns the number of columns in the current row segment in a pivot table.

```
NoOfColumns - chart function([TOTAL])
```

### Inter-record functions in the data load script

**Exists**

**Exists()** determines whether a specific field value has already been loaded into the field in the data load script. The function returns TRUE or FALSE, so can be used in the **where** clause of a **LOAD** statement or an **IF** statement.

```
Exists (field_name [, expr])
```

**LookUp**

**LookUp()** looks into a table that is already loaded and returns the value of **field\_name** corresponding to the first occurrence of the value **match\_field\_value** in the field **match\_field\_name**. The table can be the current table or another table previously loaded.

```
LookUp (field_name, match_field_name, match_field_value [, table_name])
```

### Peek

**Peek()** returns the value of a field in a table for a row that has already been loaded. The row number can be specified, as can the table. If no row number is specified, the last previously loaded record will be used.


```
Peek (field_name[, row_no[, table_name ] ])
```

### Previous

**Previous()** finds the value of the **expr** expression using data from the previous input record that has not been discarded because of a **where** clause. In the first record of an internal table, the function will return NULL.

```
Previous (page 1313) (expr)
```

### See also:

 [Range functions \(page 1334\)](#)

## Above - chart function

**Above()** evaluates an expression at a row above the current row within a column segment in a table. The row for which it is calculated depends on the value of **offset**, if present, the default being the row directly above. For charts other than tables, **Above()** evaluates for the row above the current row in the chart's straight table equivalent.

### Syntax:

```
Above ([TOTAL] expr [ , offset [,count]])
```

**Return data type:** dual

### Arguments:

Arguments

Argument	Description
expr	The expression or field containing the data to be measured.
offset	Specifying an offsetn, greater than 0, moves the evaluation of the expression n rows further up from the current row.  Specifying an offset of 0 will evaluate the expression on the current row.  Specifying a negative offset number makes the Above function work like the Below function with the corresponding positive offset number.

Argument	Description
count	By specifying a third argument <b>count</b> greater than 1, the function will return a range of <b>count</b> values, one for each of <b>count</b> table rows counting upwards from the original cell.  In this form, the function can be used as an argument to any of the special range functions. <i>Range functions (page 1334)</i>
TOTAL	If the table is one-dimensional or if the qualifier <b>TOTAL</b> is used as argument, the current column segment is always equal to the entire column.

On the first row of a column segment, a NULL value is returned, as there is no row above it.



*A column segment is defined as a consecutive subset of cells having the same values for the dimensions in the current sort order. Inter-record chart functions are computed in the column segment excluding the right-most dimension in the equivalent straight table chart. If there is only one dimension in the chart, or if the TOTAL qualifier is specified, the expression evaluates across full table.*



*If the table or table equivalent has multiple vertical dimensions, the current column segment will include only rows with the same values as the current row in all dimension columns, except for the column showing the last dimension in the inter-field sort order.*

### Limitations:

- Recursive calls will return NULL.
- Sorting on y-values in charts or sorting by expression columns in tables is not allowed when this chart function is used in any of the chart's expressions. These sort alternatives are therefore automatically disabled. When you use this chart function in a visualization or table, the sorting of the visualization will revert back to the sorted input to this function.

### Examples and results:

#### Example 1:

Table visualization for Example 1

Customer	Sum([Sales])	Above(Sum(Sales))	Sum(Sales)+Above(Sum(Sales))	Above offset 3	Higher?
	2566	-	-	-	-
Astrida	587	-	-	-	-
Betacab	539	587	1126	-	-
Canutility	683	539	1222	-	Higher
Divadip	757	683	1440	1344	Higher

## 8 Script and chart functions

---

In the screenshot of the table shown in this example, the table visualization is created from the dimension **Customer** and the measures `sum(Sales)` and `Above(Sum(Sales))`.

The column `Above(Sum(Sales))` returns NULL for the **Customer** row containing **Astrida**, because there is no row above it. The result for the row **Betacab** shows the value of `Sum(Sales)` for **Astrida**, the result for **Canutility** shows the value for `Sum(Sales)` for **Betacab**, and so on.

For the column labeled `Sum(Sales)+Above(Sum(Sales))`, the row for **Betacab** shows the result of the addition of the `Sum(Sales)` values for the rows **Betacab + Astrida** (539+587). The result for the row **Canutility** shows the result of the addition of `Sum(Sales)` values for **Canutility + Betacab** (683+539).

The measure labeled `Above offset 3` created using the expression `sum(Sales)+Above(Sum(Sales), 3)` has the argument **offset**, set to 3, and has the effect of taking the value in the row three rows above the current row. It adds the `Sum(Sales)` value for the current **Customer** to the value for the **Customer** three rows above. The values returned for the first three **Customer** rows are null.

The table also shows more complex measures: one created from `sum(Sales)+Above(Sum(Sales))` and one labeled **Higher?**, which is created from `IF(Sum(Sales)>Above(Sum(Sales)), 'Higher')`.



*This function can also be used in charts other than tables, for example bar charts.*



*For other chart types, convert the chart to the straight table equivalent so you can easily interpret which row the function relates to.*

### Example 2:

In the screenshots of tables shown in this example, more dimensions have been added to the visualizations: **Month** and **Product**. For charts with more than one dimension, the results of expressions containing the **Above**, **Below**, **Top**, and **Bottom** functions depend on the order in which the column dimensions are sorted by Qlik Sense. Qlik Sense evaluates the functions based on the column segments that result from the dimension that is sorted last. The column sort order is controlled in the properties panel under **Sorting** and is not necessarily the order in which the columns appear in a table.

In the following screenshot of table visualization for Example 2, the last-sorted dimension is **Month**, so the **Above** function evaluates based on months. There is a series of results for each **Product** value for each month (**Jan** to **Aug**) - a column segment. This is followed by a series for the next column segment: for each **Month** for the next **Product**. There will be a column segment for each **Customer** value for each **Product**.

*Table visualization for Example 2*

Customer	Product	Month	Sum([Sales])	Above(Sum(Sales))
			<b>2566</b>	-
Astrida	AA	Jan	46	-
Astrida	AA	Feb	60	46
Astrida	AA	Mar	70	60
Astrida	AA	Apr	13	70
Astrida	AA	May	78	13
Astrida	AA	Jun	20	78
Astrida	AA	Jul	45	20
Astrida	AA	Aug	65	45

**Example 3:**

In the screenshot of table visualization for Example 3, the last sorted dimension is **Product**. This is done by moving the dimension Product to position 3 in the Sorting tab in the properties panel. The **Above** function is evaluated for each **Product**, and because there are only two products, **AA** and **BB**, there is only one non-null result in each series. In row **BB** for the month **Jan**, the value for **Above (Sum(Sales))**, is 46. For row **AA**, the value is null. The value in each row **AA** for any month will always be null, as there is no value of **Product** above AA. The second series is evaluated on **AA** and **BB** for the month **Feb**, for the **Customer** value, **Astrida**. When all the months have been evaluated for **Astrida**, the sequence is repeated for the second **Customer** Betacab, and so on.

*Table visualization for Example 3*

Customer	Product	Month	Sum([Sales])	Above(Sum(Sales))
			<b>2566</b>	-
Astrida	AA	Jan	46	-
Astrida	BB	Jan	46	46
Astrida	AA	Feb	60	-
Astrida	BB	Feb	60	60
Astrida	AA	Mar	70	-
Astrida	BB	Mar	70	70
Astrida	AA	Apr	13	-
Astrida	BB	Apr	13	13



Example 4

Example 4:	Result								
<p>The Above function can be used as input to the range functions. For example:  <code>RangeAvg (Above(Sum(Sales),1,3))</code>.</p>	<p>In the arguments for the Above() function, offset is set to 1 and count is set to 3. The function finds the results of the expression <code>Sum(Sales)</code> on the three rows immediately above the current row in the column segment (where there is a row). These three values are used as input to the <code>RangeAvg()</code> function, which finds the average of the values in the supplied range of numbers.</p> <p>A table with Customer as dimension gives the following results for the <code>RangeAvg()</code> expression.</p> <table data-bbox="746 779 1043 999"> <tbody> <tr> <td>Astrida</td> <td>-</td> </tr> <tr> <td>Betacab</td> <td>587</td> </tr> <tr> <td>Canutility</td> <td>563</td> </tr> <tr> <td>Divadip:</td> <td>603</td> </tr> </tbody> </table>	Astrida	-	Betacab	587	Canutility	563	Divadip:	603
Astrida	-								
Betacab	587								
Canutility	563								
Divadip:	603								

Data used in examples:





Monthnames:

```
LOAD *, Dual(MonthText,MonthNumber) as Month INLINE [
MonthText, MonthNumber
Jan, 1
Feb, 2
Mar, 3
Apr, 4
May, 5
Jun, 6
Jul, 7
Aug, 8
Sep, 9
Oct, 10
Nov, 11
Dec, 12
];
```

Sales2013:

```
Crosstable (MonthText, Sales) LOAD * inline [
Customer|Jan|Feb|Mar|Apr|May|Jun|Jul|Aug|Sep|Oct|Nov|Dec
Astrida|46|60|70|13|78|20|45|65|78|12|78|22
Betacab|65|56|22|79|12|56|45|24|32|78|55|15
Canutility|77|68|34|91|24|68|57|36|44|90|67|27
Divadip|57|36|44|90|67|27|57|68|47|90|80|94
] (delimiter is '|');
```

**See also:**

-  [Below - chart function \(page 1282\)](#)
-  [Bottom - chart function \(page 1285\)](#)
-  [Top - chart function \(page 1315\)](#)
-  [RangeAvg \(page 1337\)](#)

## Below - chart function

**Below()** evaluates an expression at a row below the current row within a column segment in a table. The row for which it is calculated depends on the value of **offset**, if present, the default being the row directly below. For charts other than tables, **Below()** evaluates for the row below the current column in the chart's straight table equivalent.

**Syntax:**

```
Below([TOTAL] expr [ , offset [,count ]])
```

**Return data type:** dual

**Arguments:**

## Arguments

Argument	Description
expr	The expression or field containing the data to be measured.
offset	Specifying an <b>offset</b> <i>n</i> , greater than 1 moves the evaluation of the expression <i>n</i> rows further down from the current row.  Specifying an offset of 0 will evaluate the expression on the current row.  Specifying a negative offset number makes the <b>Below</b> function work like the <b>Above</b> function with the corresponding positive offset number.
count	By specifying a third parameter <b>count</b> greater than 1, the function will return a range of <b>count</b> values, one for each of <b>count</b> table rows counting downwards from the original cell. In this form, the function can be used as an argument to any of the special range functions. <i>Range functions (page 1334)</i>
TOTAL	If the table is one-dimensional or if the qualifier <b>TOTAL</b> is used as argument, the current column segment is always equal to the entire column.

On the last row of a column segment, a NULL value is returned, as there is no row below it.



A column segment is defined as a consecutive subset of cells having the same values for the dimensions in the current sort order. Inter-record chart functions are computed in the column segment excluding the right-most dimension in the equivalent straight table chart. If there is only one dimension in the chart, or if the TOTAL qualifier is specified, the expression evaluates across full table.



If the table or table equivalent has multiple vertical dimensions, the current column segment will include only rows with the same values as the current row in all dimension columns, except for the column showing the last dimension in the inter-field sort order.

### Limitations:

- Recursive calls will return NULL.
- Sorting on y-values in charts or sorting by expression columns in tables is not allowed when this chart function is used in any of the chart's expressions. These sort alternatives are therefore automatically disabled. When you use this chart function in a visualization or table, the sorting of the visualization will revert back to the sorted input to this function.

### Examples and results:

#### Example 1:

Table visualization for Example 1

Customer	Sum(Sales)	Below(Sum(Sales))	Sum(Sales)+Below(Sum(Sales))	Below + Offset 3	Higher
	2566	-	-	-	-
Astrida	587	539	1126	1344	Higher
Betacab	539	683	1222	-	-
Canutility	683	757	1440	-	-
Divadip	757	-	-	-	-

In the table shown in screenshot for Example 1, the table visualization is created from the dimension **Customer** and the measures `sum(Sales)` and `Below(Sum(Sales))`.

The column **Below(Sum(Sales))** returns NULL for the **Customer** row containing **Divadip**, because there is no row below it. The result for the row **Canutility** shows the value of `Sum(Sales)` for **Divadip**, the result for **Betacab** shows the value for `Sum(Sales)` for **Canutility**, and so on.

The table also shows more complex measures, which you can see in the columns labeled: `sum(Sales)+Below(Sum(Sales))`, **Below +Offset 3**, and **Higher?**. These expressions work as described in the following paragraphs.

For the column labeled **Sum(Sales)+Below(Sum(Sales))**, the row for **Astrida** shows the result of the addition of the **Sum(Sales)** values for the rows **Betacab + Astrida** (539+587). The result for the row **Betacab** shows the result of the addition of **Sum(Sales)** values for **Canutility + Betacab** (539+683).

The measure labeled **Below +Offset 3** created using the expression `sum(Sales)+Below(Sum(Sales), 3)` has the argument **offset**, set to 3, and has the effect of taking the value in the row three rows below the current row. It adds the **Sum(Sales)** value for the current **Customer** to the value from the **Customer** three rows below. The values for the lowest three **Customer** rows are null.

The measure labeled **Higher?** is created from the expression: `IF(Sum(Sales)>Below(Sum(Sales)), 'Higher')`. This compares the values of the current row in the measure **Sum(Sales)** with the row below it. If the current row is a greater value, the text "Higher" is output.



*This function can also be used in charts other than tables, for example bar charts.*



*For other chart types, convert the chart to the straight table equivalent so you can easily interpret which row the function relates to.*

For charts with more than one dimension, the results of expressions containing the **Above**, **Below**, **Top**, and **Bottom** functions depend on the order in which the column dimensions are sorted by Qlik Sense. Qlik Sense evaluates the functions based on the column segments that result from the dimension that is sorted last. The column sort order is controlled in the properties panel under **Sorting** and is not necessarily the order in which the columns appear in a table. Please refer to Example: 2 in the **Above** function for further details.

Example 2

Example 2:	Result
The <b>Below</b> function can be used as input to the range functions. For example: <code>RangeAvg (Below (Sum(Sales) , 1, 3))</code> .	<p>In the arguments for the <b>Below()</b> function, offset is set to 1 and count is set to 3. The function finds the results of the expression <b>Sum (Sales)</b> on the three rows immediately below the current row in the column segment (where there is a row). These three values are used as input to the <code>RangeAvg()</code> function, which finds the average of the values in the supplied range of numbers.</p> <p>A table with <b>Customer</b> as dimension gives the following results for the <code>RangeAvg()</code> expression.</p>

Example 2:	Result
	Astrida 659.67
	Betacab 720
	Canutility 757
	Divadip: -

Data used in examples:





Monthnames:

```
LOAD *, Dual(MonthText,MonthNumber) as Month INLINE [
MonthText, MonthNumber
Jan, 1
Feb, 2
Mar, 3
Apr, 4
May, 5
Jun, 6
Jul, 7
Aug, 8
Sep, 9
Oct, 10
Nov, 11
Dec, 12
];
```

Sales2013:

```
Crosstable (MonthText, Sales) LOAD * inline [
Customer|Jan|Feb|Mar|Apr|May|Jun|Jul|Aug|Sep|Oct|Nov|Dec
Astrida|46|60|70|13|78|20|45|65|78|12|78|22
Betacab|65|56|22|79|12|56|45|24|32|78|55|15
Canutility|77|68|34|91|24|68|57|36|44|90|67|27
Divadip|57|36|44|90|67|27|57|68|47|90|80|94
] (delimiter is '|');
```

**See also:**

-  [Above - chart function \(page 1277\)](#)
-  [Bottom - chart function \(page 1285\)](#)
-  [Top - chart function \(page 1315\)](#)
-  [RangeAvg \(page 1337\)](#)

## Bottom - chart function

**Bottom()** evaluates an expression at the last (bottom) row of a column segment in a table. The row for which it is calculated depends on the value of **offset**, if present, the default being the bottom row. For charts other than tables, the evaluation is made on the last row of the current column in the chart's straight table equivalent.

### Syntax:

```
Bottom([TOTAL] expr [ , offset [,count ]])
```

**Return data type:** dual

### Arguments:

#### Arguments

Argument	Description
expr	The expression or field containing the data to be measured.
offset	Specifying an <b>offset</b> n greater than 1 moves the evaluation of the expression up n rows above the bottom row.  Specifying a negative offset number makes the <b>Bottom</b> function work like the <b>Top</b> function with the corresponding positive offset number.
count	By specifying a third parameter <b>count</b> greater than 1, the function will return not one but a range of <b>count</b> values, one for each of the last <b>count</b> rows of the current column segment. In this form, the function can be used as an argument to any of the special range functions. <i>Range functions (page 1334)</i>
TOTAL	If the table is one-dimensional or if the qualifier <b>TOTAL</b> is used as argument, the current column segment is always equal to the entire column.



*A column segment is defined as a consecutive subset of cells having the same values for the dimensions in the current sort order. Inter-record chart functions are computed in the column segment excluding the right-most dimension in the equivalent straight table chart. If there is only one dimension in the chart, or if the TOTAL qualifier is specified, the expression evaluates across full table.*



*If the table or table equivalent has multiple vertical dimensions, the current column segment will include only rows with the same values as the current row in all dimension columns, except for the column showing the last dimension in the inter-field sort order.*

### Limitations:

- Recursive calls will return NULL.
- Sorting on y-values in charts or sorting by expression columns in tables is not allowed when this chart function is used in any of the chart's expressions. These sort alternatives are therefore automatically disabled. When you use this chart function in a visualization or table, the sorting of the visualization will revert back to the sorted input to this function.

### Examples and results:

Table visualization for Example 1

Customer	Sum(Sales)	Bottom(Sum(Sales))	Sum(Sales)+Bottom(Sum(Sales))	Bottom offset 3
	<b>2566</b>	<b>757</b>	<b>3323</b>	<b>3105</b>
Astrida	587	757	1344	1126
Betacab	539	757	1296	1078
Canutility	683	757	1440	1222
Divadip	757	757	1514	1296

In the screenshot of the table shown in this example, the table visualization is created from the dimension **Customer** and the measures `sum(Sales)` and `Bottom(Sum(Sales))`.

The column **Bottom(Sum(Sales))** returns 757 for all rows because this is the value of the bottom row: **Divadip**.

The table also shows more complex measures: one created from `sum(Sales)+Bottom(Sum(Sales))` and one labeled **Bottom offset 3**, which is created using the expression `sum(Sales)+Bottom(Sum(Sales), 3)` and has the argument **offset** set to 3. It adds the **Sum(Sales)** value for the current row to the value from the third row from the bottom row, that is, the current row plus the value for **Betacab**.

### Example: 2

In the screenshots of tables shown in this example, more dimensions have been added to the visualizations: **Month** and **Product**. For charts with more than one dimension, the results of expressions containing the **Above**, **Below**, **Top**, and **Bottom** functions depend on the order in which the column dimensions are sorted by Qlik Sense. Qlik Sense evaluates the functions based on the column segments that result from the dimension that is sorted last. The column sort order is controlled in the properties panel under **Sorting** and is not necessarily the order in which the columns appear in a table.

In the first table, the expression is evaluated based on **Month**, and in the second table it is evaluated based on **Product**. The measure **End value** contains the expression `Bottom(Sum(Sales))`. The bottom row for **Month** is Dec, and the value for Dec both the values of **Product** shown in the screenshot is 22. (Some rows have been edited out of the screenshot to save space.)

*First table for Example 2. The value of Bottom for the End value measure based on Month (Dec).*

## 8 Script and chart functions

Customer	Product	Month	Sum(Sales)	End value
			<b>2566</b>	-
Astrida	AA	Jan	46	22
Astrida	AA	Feb	60	22
Astrida	AA	Mar	70	22
Astrida	AA	Sep	78	22
Astrida	AA	Oct	12	22
Astrida	AA	Nov	78	22
Astrida	AA	Dec	22	22
Astrida	BB	Jan	46	22

Second table for Example 2. The value of Bottom for the End value measure based on Product (BB for Astrida).

Customer	Product	Month	Sum(Sales)	End value
			<b>2566</b>	-
Astrida	AA	Jan	46	46
Astrida	BB	Jan	46	46
Astrida	AA	Feb	60	60
Astrida	BB	Feb	60	60
Astrida	AA	Mar	70	70
Astrida	BB	Mar	70	70
Astrida	AA	Apr	13	13
Astrida	BB	Apr	13	13

Please refer to Example: 2 in the **Above** function for further details.



Example 3

Example: 3	Result								
<p>The <b>Bottom</b> function can be used as input to the range functions. For example: <code>RangeAvg (Bottom(Sum(Sales),1,3))</code>.</p>	<p>In the arguments for the <b>Bottom()</b> function, offset is set to 1 and count is set to 3. The function finds the results of the expression <b>Sum (Sales)</b> on the three rows starting with the row above the bottom row in the column segment (because offset=1), and the two rows above that (where there is a row). These three values are used as input to the <code>RangeAvg()</code> function, which finds the average of the values in the supplied range of numbers.</p> <p>A table with <b>Customer</b> as dimension gives the following results for the <code>RangeAvg()</code> expression.</p>								
	<table style="width: 100%; border-collapse: collapse;"> <tbody> <tr> <td style="padding: 5px;">Astrida</td> <td style="text-align: right; padding: 5px;">659.67</td> </tr> <tr> <td style="padding: 5px;">Betacab</td> <td style="text-align: right; padding: 5px;">659.67</td> </tr> <tr> <td style="padding: 5px;">Canutility</td> <td style="text-align: right; padding: 5px;">659.67</td> </tr> <tr> <td style="padding: 5px;">Divadip:</td> <td style="text-align: right; padding: 5px;">659.67</td> </tr> </tbody> </table>	Astrida	659.67	Betacab	659.67	Canutility	659.67	Divadip:	659.67
Astrida	659.67								
Betacab	659.67								
Canutility	659.67								
Divadip:	659.67								

Monthnames:

```
LOAD *, Dual(MonthText,MonthNumber) as Month INLINE [
MonthText, MonthNumber
Jan, 1
Feb, 2
Mar, 3
Apr, 4
May, 5
Jun, 6
Jul, 7
Aug, 8
Sep, 9
Oct, 10
Nov, 11
Dec, 12
];
```

Sales2013:

```
Crosstable (MonthText, Sales) LOAD * inline [
Customer|Jan|Feb|Mar|Apr|May|Jun|Jul|Aug|Sep|Oct|Nov|Dec
Astrida|46|60|70|13|78|20|45|65|78|12|78|22
Betacab|65|56|22|79|12|56|45|24|32|78|55|15
Canutility|77|68|34|91|24|68|57|36|44|90|67|27
Divadip|57|36|44|90|67|27|57|68|47|90|80|94
] (delimiter is '|');
```

**See also:**

 [Top - chart function \(page 1315\)](#)

## Column - chart function

**Column()** returns the value found in the column corresponding to **ColumnNo** in a straight table, disregarding dimensions. For example **Column(2)** returns the value of the second measure column.


**Syntax:**

```
Column(ColumnNo)
```

**Return data type:** dual

**Arguments:**

## Arguments

Argument	Description
ColumnNo	Column number of a column in the table containing a measure.  <div style="border: 1px solid #ccc; padding: 5px; margin-top: 10px;">  <i>The Column() function disregards dimension columns.</i> </div>

**Limitations:**

- Recursive calls will return NULL.
- If **ColumnNo** references a column for which there is no measure, a NULL value is returned.
- Sorting on y-values in charts or sorting by expression columns in tables is not allowed when this chart function is used in any of the chart's expressions. These sort alternatives are therefore automatically disabled. When you use this chart function in a visualization or table, the sorting of the visualization will revert back to the sorted input to this function.

**Examples and results:****Example: Percentage total sales**

Customer	Product	UnitPrice	UnitSales	Order Value	Total Sales Value	% Sales
A	AA	15	10	150	505	29.70
A	AA	16	4	64	505	12.67
A	BB	9	9	81	505	16.04

## 8 Script and chart functions

Customer	Product	UnitPrice	UnitSales	Order Value	Total Sales Value	% Sales
B	BB	10	5	50	505	9.90
B	CC	20	2	40	505	7.92
B	DD	25	-	0	505	0.00
C	AA	15	8	120	505	23.76
C	CC	19	-	0	505	0.00

### Example: Percentage of sales for selected customer

Customer	Product	UnitPrice	UnitSales	Order Value	Total Sales Value	% Sales
A	AA	15	10	150	295	50.85
A	AA	16	4	64	295	21.69
A	BB	9	9	81	295	27.46

### Examples and results

Examples	Results
<p>Order Value is added to the table as a measure with the expression: <code>sum (UnitPrice*Unitsales)</code>.</p> <p>Total Sales Value is added as a measure with the expression: <code>sum (TOTAL unitPrice*Unitsales)</code></p> <p>% Sales is added as a measure with the expression <code>100*column(1)/column (2)</code></p>	<p>The result of Column(1) is taken from the column Order Value, because this is the first measure column.</p> <p>The result of Column(2) is taken from Total Sales Value, because this is the second measure column.</p> <p>See the results in the column % Sales in the example <i>Percentage total sales (page 1290)</i>.</p>
<p>Make the selection Customer A.</p>	<p>The selection changes the Total Sales Value, and therefore the %Sales. See the example <i>Percentage of sales for selected customer (page 1291)</i>.</p>

### Data used in examples:

```
ProductData:
LOAD * inline [
Customer|Product|Unitsales|UnitPrice
Astrida|AA|4|16
Astrida|AA|10|15
Astrida|BB|9|9
Betacab|BB|5|10
```

```
Betacab|CC|2|20
Betacab|DD||25
Canutility|AA|8|15
Canutility|CC||19
] (delimiter is '|');
```

### Dimensionality - chart function

**Dimensionality()** returns the number of dimensions for the current row. In the case of pivot tables, the function returns the total number of dimension columns that have non-aggregation content, that is, do not contain partial sums or collapsed aggregates.

#### Syntax:

```
Dimensionality ( )
```

**Return data type:** integer

#### Limitations:

This function is only available in charts. For all chart types, except pivot table, it will return the number of dimensions in all rows except the total, which will be 0.

Sorting on y-values in charts or sorting by expression columns in tables is not allowed when this chart function is used in any of the chart's expressions. These sort alternatives are therefore automatically disabled. When you use this chart function in a visualization or table, the sorting of the visualization will revert back to the sorted input to this function.

### Example: Chart expression using Dimensionality

Example: Chart expression

The **Dimensionality()** function can be used with a pivot table as a chart expression where you want to apply different cell formatting depending on the number of dimensions in a row that has non-aggregated data. This example uses the Dimensionality() function to apply a background color to table cells that match a given condition.

#### Load script

Load the following data as an inline load in the data load editor to create the chart expression example below.

ProductSales:

```
Load * inline [
Country,Product,Sales,Budget
Sweden,AA,100000,50000
Germany,AA,125000,175000
Canada,AA,105000,98000
Norway,AA,74850,68500
Ireland,AA,49000,48000
Sweden,BB,98000,99000
Germany,BB,115000,175000
Norway,BB,71850,68500
```

## 8 Script and chart functions

```
Ireland, BB, 31000, 48000  
] (delimiter is ',');
```

### Chart expression

Create a pivot table visualization in a Qlik Sense sheet with **Country** and **Product** as dimensions. Add **Sum(Sales)**, **Sum(Budget)**, and **Dimensionality()** as measures.

In the **Properties** panel, enter the following expression as the **Background color expression** for the **Sum(Sales)** measure.

```
If(Dimensionality()=1 and Sum(Sales)<Sum(Budget), RGB(255,156,156),  
If(Dimensionality()=2 and Sum(Sales)<Sum(Budget), RGB(178,29,29)  
)
```

### Result:

Country		Values		
Product		Sum(Sales)	Sum([Budget])	Dimensionality()
Canada		105000	98000	1
	AA	105000	98000	2
Germany		240000	350000	1
Ireland		80000	96000	1
	AA	49000	48000	2
	BB	31000	48000	2
Norway		146700	137000	1
	AA	74850	68500	2
	BB	71850	68500	2
Sweden		198000	149000	1

### Explanation

The expression `If(Dimensionality()=1 and Sum(Sales)<Sum(Budget), RGB(255,156,156), If(Dimensionality()=2 and Sum(Sales)<Sum(Budget), RGB(178,29,29)))` contains conditional statements that check the dimensionality value and the `Sum(Sales)` and `Sum(Budget)` for each product. If the conditions are met, a background color is applied to the `Sum(Sales)` value.

### Exists

**Exists()** determines whether a specific field value has already been loaded into the field in the data load script. The function returns `TRUE` or `FALSE`, so can be used in the **where** clause of a **LOAD** statement or an **IF** statement.



You can also use **Not Exists()** to determine if a field value has not been loaded, but caution is recommended if you use **Not Exists()** in a where clause. The **Exists()** function tests both previously loaded tables and previously loaded values in the current table. So, only the first occurrence will be loaded. When the second occurrence is encountered, the value is already loaded. See the examples for more information.

### Syntax:

```
Exists(field_name [, expr])
```

**Return data type:** Boolean

### Arguments:

#### Arguments

Argument	Description
field_name	<p>The name of the field where you want to search for a value. You can use an explicit field name without quotes.</p> <p>The field must already be loaded by the script. That means, you cannot refer to a field that is loaded in a clause further down in the script.</p>
expr	<p>The value that you want to check if it exists. You can use an explicit value or an expression that refers to one or several fields in the current load statement.</p> <div data-bbox="411 1182 475 1252" data-label="Image"> </div> <p><i>You cannot refer to fields that are not included in the current load statement.</i></p> <p>This argument is optional. If you omit it, the function will check if the value of <b>field_name</b> in the current record already exists.</p>

Examples and results:

#### Example 1

```
Exists (Employee)
```

Returns -1 (True) if the value of the field **Employee** in the current record already exists in any previously read record containing that field.

The statements `Exists (Employee, Employee)` and `Exists (Employee)` are equivalent.

#### Example 2

```
Exists(Employee, 'Bill')
```

Returns -1 (True) if the field value **'Bill'** is found in the current content of the field **Employee**.

### Example 3

```
Employees:
LOAD * inline [
Employee|ID|Salary
Bill|001|20000
John|002|30000
Steve|003|35000
] (delimiter is '|');

Citizens:
Load * inline [
Employee|Address
Bill|New York
Mary|London
Steve|Chicago
Lucy|Madrid
Lucy|Paris
John|Miami
] (delimiter is '|') where Exists (Employee);

Drop Tables Employees;
```

This results in a table that you can use in a table visualization using the dimensions Employee and Address.

The where clause, where `Exists (Employee)`, means only the names from the table Citizens that are also in Employees are loaded into the new table. The Drop statement removes the table Employees to avoid confusion.

Results

Employee	Address
Bill	New York
John	Miami
Steve	Chicago

### Example 4

```
Employees:
Load * inline [
Employee|ID|Salary
Bill|001|20000
John|002|30000
Steve|003|35000
] (delimiter is '|');

Citizens:
Load * inline [
```

```
Employee|Address  
Bill|New York  
Mary|London  
Steve|Chicago  
Lucy|Madrid  
Lucy|Paris  
John|Miami  
] (delimiter is '|') where not Exists (Employee);
```

```
Drop Tables Employees;
```

The where clause includes not: where not Exists (Employee).

This means that only the names from the table Citizens that are not in Employees are loaded into the new table.

Note that there are two values for Lucy in the Citizens table, but only one is included in the result table. When you load the first row with the value Lucy, it is included in the Employee field. Hence, when the second line is checked, the value already exists.

Results

Employee	Address
Mary	London
Lucy	Madrid

### Example 5

This example shows how to load all values.

```
Employees:  
Load Employee AS Name;  
LOAD * inline [  
Employee|ID|Salary  
Bill|001|20000  
John|002|30000  
Steve|003|35000  
] (delimiter is '|');
```

```
Citizens:  
Load * inline [  
Employee|Address  
Bill|New York  
Mary|London  
Steve|Chicago  
Lucy|Madrid  
Lucy|Paris  
John|Miami  
] (delimiter is '|') where not Exists (Name, Employee);
```

```
Drop Tables Employees;
```



To be able to get all values for Lucy, two things were changed:

- A preceding load to the Employees table was inserted where Employee was renamed to Name.  
Load Employee As Name;
- The Where condition in Citizens was changed to:  
not Exists (Name, Employee).

This creates fields for Name and Employee. When the second row with Lucy is checked, it still does not exist in Name.

Results

Employee	Address
Mary	London
Lucy	Madrid
Lucy	Paris

### FieldIndex

**FieldIndex()** returns the position of the field value **value** in the field **field\_name** (by load order).

#### Syntax:

```
FieldIndex(field_name , value)
```

**Return data type:** integer

#### Arguments:

Arguments

Argument	Description
field_name	Name of the field for which the index is required. For example, the column in a table. Must be given as a string value. This means that the field name must be enclosed by single quotes.
value	The value of the field <b>field_name</b> .

#### Limitations:

- If **value** cannot be found among the field values of the field **field\_name**, 0 is returned.
- Sorting on y-values in charts or sorting by expression columns in tables is not allowed when this chart function is used in any of the chart's expressions. These sort alternatives are therefore automatically disabled. When you use this chart function in a visualization or table, the sorting of the visualization will revert back to the sorted input to this function. This limitation does not apply to the equivalent script function.

### Examples and results:

The following examples use the field: **First name** from the table **Names**.

Examples and results

Examples	Results
Add the example data to your app and run it.	The table <b>Names</b> is loaded, as in the sample data.
Chart function: In a table containing the dimension First name, add as a measure.	
FieldIndex ('First name','John')	1, because 'John' appears first in the load order of the <b>First name</b> field. Note that in a filter pane <b>John</b> would appear as number 2 from the top as it's sorted alphabetically and not as in the load order.
FieldIndex ('First name','Peter')	4, because <b>FieldIndex()</b> returns only one value, that is the first occurrence in the load order.
Script function: Given the table <b>Names</b> is loaded, as in the example data:	
John1: Load FieldIndex('First name','John') as MyJohnPos Resident Names;	MyJohnPos=1, because 'John' appears first in the load order of the <b>First name</b> field. Note that in a filter pane <b>John</b> would appear as number 2 from the top as it's sorted alphabetically and not as in the load order.
Peter1: Load FieldIndex('First name','Peter') as MyPeterPos Resident Names;	MyPeterPos=4, because <b>FieldIndex()</b> returns only one value, that is the first occurrence in the load order.

### Data used in example:

Names:

```
LOAD * inline [
First name|Last name|Initials|Has cellphone
John|Anderson|JA|Yes
Sue|Brown|SB|Yes
Mark|Carr|MC|No
Peter|Devonshire|PD|No
Jane|Elliot|JE|Yes
Peter|Franc|PF|Yes ] (delimiter is '|');
```

John1:

```
Load FieldIndex('First name','John') as MyJohnPos
Resident Names;
```

Peter1:

```
Load FieldIndex('First name','Peter') as MyPeterPos
Resident Names;
```

### FieldValue

**FieldValue()** returns the value found in position **elem\_no** of the field **field\_name** (by load order).

#### Syntax:

```
FieldValue(field_name , elem_no)
```

**Return data type:** dual

#### Arguments:

##### Arguments

Argument	Description
field_name	Name of the field for which the value is required. For example, the column in a table. Must be given as a string value. This means that the field name must be enclosed by single quotes.
elem_no	The position (element) number of the field following the load order, that the value is returned for. This could correspond to the row in a table, but it depends on the order in which the elements (rows) are loaded.

#### Limitations:

- If **elem\_no** is larger than the number of field values, NULL is returned.
- Sorting on y-values in charts or sorting by expression columns in tables is not allowed when this chart function is used in any of the chart's expressions. These sort alternatives are therefore automatically disabled. When you use this chart function in a visualization or table, the sorting of the visualization will revert back to the sorted input to this function. This limitation does not apply to the equivalent script function.

#### Example

##### Load script

Load the following data as an inline load in the data load editor to create the example below.

Names:

```
LOAD * inline [
First name|Last name|Initials|Has cellphone
John|Anderson|JA|Yes
Sue|Brown|SB|Yes
Mark|Carr|MC |No
Peter|Devonshire|PD|No
Jane|Elliot|JE|Yes
Peter|Franc|PF|Yes ] (delimiter is '|');
```

John1:

```
Load FieldValue('First name',1) as MyPos1  
Resident Names;
```

Peter1:

```
Load FieldValue('First name',5) as MyPos2  
Resident Names;
```

### Create a visualization

Create a table visualization in a Qlik Sense sheet. Add fields **First name**, **MyPos1**, and **MyPos2** to the table.

### Result

First name	MyPos1	MyPos2
Jane	John	Jane
John	John	Jane
Mark	John	Jane
Peter	John	Jane
Sue	John	Jane

### Explanation

**FieldValue('First name','1')** results in John as the value for **MyPos1** for all first names because John appears first in the load order of the **First name** field. Note that in a filter pane John would appear as number 2 from the top, after Jane, as it's sorted alphabetically and not as in the load order.

**FieldValue('First name','5')** results in Jane as the value for **MyPos2** for all first names because Jane appears fifth in the load order of the **First name** field.

## FieldValueCount

**FieldValueCount()** is an **integer** function that returns the number of distinct values in a field.

A partial reload can remove values from the data, which will not be reflected in the number returned. The returned number will correspond to all distinct values that were loaded in either the initial reload or any subsequent partial reload.



*Sorting on y-values in charts or sorting by expression columns in tables is not allowed when this chart function is used in any of the chart's expressions. These sort alternatives are therefore automatically disabled. When you use this chart function in a visualization or table, the sorting of the visualization will revert back to the sorted input to this function. This limitation does not apply to the equivalent script function.*

### Syntax:

```
FieldValueCount(field_name)
```

**Return data type:** integer

### Arguments:

#### Arguments

Argument	Description
field_name	Name of the field for which the value is required. For example, the column in a table. Must be given as a string value. This means that the field name must be enclosed by single quotes.

### Examples and results:

The following examples use the field **First name** from the table **Names**.

#### Examples and results

Examples	Results
Add the example data to your app and run it.	The table <b>Names</b> is loaded, as in the sample data.
Chart function: In a table containing the dimension First name, add as a measure.	
FieldValueCount('First name')	5 as <b>Peter</b> appears twice.
FieldValueCount('Initials')	6 as <b>Initials</b> only has distinct values.
Script function: Given the table <b>Names</b> is loaded, as in the example data:	
FieldCount1: Load FieldValueCount('First name') as MyFieldCount1 Resident Names;	MyFieldCount1=5, because 'Peter' appears twice.
FieldCount2: Load FieldValueCount('Initials') as MyInitialsCount1 Resident Names;	MyFieldCount1=6, because 'Initials' only has distinct values.

Data used in examples:

Names:

```
LOAD * inline [
First name|Last name|Initials|Has cellphone
John|Anderson|JA|Yes
Sue|Brown|SB|Yes
Mark|Carr|MC|No
Peter|Devonshire|PD|No
Jane|Elliot|JE|Yes
Peter|Franc|PF|Yes ] (delimiter is '|');
```

FieldCount1:

```
Load FieldValueCount('First name') as MyFieldCount1
```

```
Resident Names;
```

```
FieldCount2:
Load FieldValueCount('Initials') as MyInitialsCount1
Resident Names;
```

## LookUp

**Lookup()** looks into a table that is already loaded and returns the value of **field\_name** corresponding to the first occurrence of the value **match\_field\_value** in the field **match\_field\_name**. The table can be the current table or another table previously loaded.

### Syntax:

```
lookup(field_name, match_field_name, match_field_value [, table_name])
```

**Return data type:** dual

### Arguments:

#### Arguments

Argument	Description
field_name	Name of the field for which the return value is required. Input value must be given as a string (for example, quoted literals).
match_field_name	Name of the field to look up <b>match_field_value</b> in. Input value must be given as a string (for example, quoted literals).
match_field_value	Value to look up in <b>match_field_name</b> field.
table_name	Name of the table in which to look up the value. Input value must be given as a string (for example quoted literals).  If <b>table_name</b> is omitted the current table is assumed.



*Arguments without quotes refer to the current table. To refer to other tables, enclose an argument in single quotes.*

### Limitations:

The order in which the search is made is the load order, unless the table is the result of complex operations such as joins, in which case, the order is not well defined. Both **field\_name** and **match\_field\_name** must be fields in the same table, specified by **table\_name**.

If no match is found, NULL is returned.

### Example

#### Load script

Load the following data as an inline load in the data load editor to create the example below.

```
ProductList:
Load * Inline [
ProductID|Product|Category|Price
1|AA|1|1
2|BB|1|3
3|CC|2|8
4|DD|3|2
] (delimiter is '|');

OrderData:
Load *, Lookup('Category', 'ProductID', ProductID, 'ProductList') as CategoryID
Inline [
InvoiceID|CustomerID|ProductID|Units
1|Astrida|1|8
1|Astrida|2|6
2|Betacab|3|10
3|Divadip|3|5
4|Divadip|4|10
] (delimiter is '|');

Drop Table ProductList;
```

#### Create a visualization

Create a table visualization in a Qlik Sense sheet. Add fields **ProductID**, **InvoiceID**, **CustomerID**, **Units**, and **CategoryID** to the table.

#### Result

Resulting table

ProductID	InvoiceID	CustomerID	Units	CategoryID
1	1	Astrida	8	1
2	1	Astrida	6	1
3	2	Betacab	10	2
3	3	Divadip	5	2
4	4	Divadip	10	3

#### Explanation

The sample data uses the **Lookup()** function in the following form:

```
Lookup('Category', 'ProductID', ProductID, 'ProductList')
```

The **ProductList** table is loaded first.

The **Lookup()** function is used to build the **OrderData** table. It specifies the third argument as **ProductID**. This is the field for which the value is to be looked up in the second argument '**ProductID**' in the **ProductList**, as denoted by the enclosing single quotes.

The function returns the value for '**Category**' (in the **ProductList** table), loaded as **CategoryID**.

The **drop** statement deletes the **ProductList** table from the data model because it is not required, which leaves the resulting **OrderData** table.



*The Lookup() function is flexible and can access any previously loaded table. However, it is slow compared with the Applymap() function.*

### See also:

[ApplyMap \(page 1326\)](#)

## NoOfRows - chart function

**NoOfRows()** returns the number of rows in the current column segment in a table. For bitmap charts, **NoOfRows()** returns the number of rows in the chart's straight table equivalent.

If the table or table equivalent has multiple vertical dimensions, the current column segment will include only rows with the same values as the current row in all dimension columns, except for the column showing the last dimension in the inter-field sort order.



*Sorting on y-values in charts or sorting by expression columns in tables is not allowed when this chart function is used in any of the chart's expressions. These sort alternatives are therefore automatically disabled. When you use this chart function in a visualization or table, the sorting of the visualization will revert back to the sorted input to this function.*

### Syntax:

```
NoOfRows ( [TOTAL] )
```

**Return data type:** integer

### Arguments:

#### Arguments

Argument	Description
TOTAL	If the table is one-dimensional or if the qualifier <b>TOTAL</b> is used as argument, the current column segment is always equal to the entire column.



## Example: Chart expression using NoOfRows

Example - chart expression

### Load script

Load the following data as an inline load in the data load editor to create the chart expression examples below.

```
Temp:
LOAD * inline [
Region|SubRegion|RowNo()|NoOfRows()
Africa|Eastern
Africa|Western
Americas|Central
Americas|Northern
Asia|Eastern
Europe|Eastern
Europe|Northern
Europe|Western
Oceania|Australia
] (delimiter is '|');
```

### Chart expression

Create a table visualization in a Qlik Sense sheet with **Region** and **SubRegion** as dimensions. Add `RowNo()`, `NoOfRows()`, and `NoOfRows(Total)` as measures.

### Result

Region	SubRegion	RowNo()	NoOfRows()	NoOfRows (Total)
Africa	Eastern	1	2	9
Africa	Western	2	2	9
Americas	Central	1	2	9
Americas	Northern	2	2	9
Asia	Eastern	1	1	9
Europe	Eastern	1	3	9
Europe	Northern	2	3	9
Europe	Western	3	3	9
Oceania	Australia	1	1	9

### Explanation

In this example, the sort order is by the first dimension Region. As a result, each column segment is made up of a group of regions that has the same value, for example, Africa.

The **RowNo()** column shows the row numbers for each column segment, for example, there are two rows for the Africa region. The row numbering then begins at 1 again for the next column segment, which is Americas.


The **NoOfRows()** column counts the number of rows in each column segment, for example, Europe has three rows in the column segment.

The **NoOfRows(Total)** column disregards the dimensions because of the `TOTAL` argument for `NoOfRows()` and counts the rows in the table.

If the table was sorted on the second dimension, SubRegion, the column segments would be based on that dimension so the row numbering would change for each SubRegion.

---

### See also:

 [RowNo - chart function \(page 592\)](#)

### Peek

**Peek()** returns the value of a field in a table for a row that has already been loaded. The row number can be specified, as can the table. If no row number is specified, the last previously loaded record will be used.

The `peek()` function is most often used to find the relevant boundaries in a previously loaded table, that is, the first value or last value of a specific field. In most cases, this value is stored in a variable for later use, for example, as a condition in a do-while loop.

### Syntax:

```
Peek (  
field_name  
[, row_no[, table_name ] ])
```

**Return data type:** dual

### Arguments:

#### Arguments

Argument	Description
field_name	Name of the field for which the return value is required. Input value must be given as a string (for example, quoted literals).

Argument	Description
row_no	The row in the table that specifies the field required. Can be an expression, but must resolve to an integer. 0 denotes the first record, 1 the second, and so on. Negative numbers indicate order from the end of the table. -1 denotes the last record read.  If no <b>row_no</b> is stated, -1 is assumed.
table_name	A table label without the ending colon. If no <b>table_name</b> is stated, the current table is assumed. If used outside the <b>LOAD</b> statement or referring to another table, the <b>table_name</b> must be included.

### Limitations:

The function can only return values from already loaded records. This means that in the first record of a table, a call using -1 as row\_no will return NULL.

Examples and results:

### Example 1

Add the example script to your app and run it. To see the result, add the fields listed in the results column to a sheet in your app.

```
EmployeeDates:
Load * Inline [
EmployeeCode|StartDate|EndDate
101|02/11/2010|23/06/2012
102|01/11/2011|30/11/2013
103|02/01/2012|
104|02/01/2012|31/03/2012
105|01/04/2012|31/01/2013
106|02/11/2013|
] (delimiter is '|');

First_Last_Employee:
Load
EmployeeCode,
Peek('EmployeeCode',0,'EmployeeDates') As FirstCode,
Peek('EmployeeCode',-1,'EmployeeDates') As LastCode
Resident EmployeeDates;
```

Resulting table

Employee code	StartDate	EndDate	FirstCode	LastCode
101	02/11/2010	23/06/2012	101	106
102	01/11/2011	30/11/2013	101	106
103	02/01/2012		101	106
104	02/01/2012	31/03/2012	101	106

Employee code	StartDate	EndDate	FirstCode	LastCode
105	01/04/2012	31/01/2013	101	106
106	02/11/2013		101	106

FirstCode = 101 because `Peek('EmployeeCode', 0, 'EmployeeDates')` returns the first value of EmployeeCode in the table EmployeeDates.

LastCode = 106 because `Peek('EmployeeCode', -1, 'EmployeeDates')` returns the last value of EmployeeCode in the table EmployeeDates.

Substituting the value of the argument **row\_no** returns the values of other rows in the table, as follows:

`Peek('EmployeeCode', 2, 'EmployeeDates')` returns the third value, 103, in the table as the FirstCode.

However, note that without specifying the table as the third argument **table\_name** in these examples, the function references the current (in this case, internal) table.

### Example 2

If you want to access data further down in a table, you need to do it in two steps: first, load the entire table into a temporary table, and then re-sort it when using **Peek()**.

Add the example script to your app and run it. To see the result, add the fields listed in the results column to a sheet in your app.

```
T1:
LOAD * inline [
ID|value
1|3
1|4
1|6
3|7
3|8
2|1
2|11
5|2
5|78
5|13
] (delimiter is '|');
```

T2:

```
LOAD *,
IF(ID=Peek('ID'), Peek('List')&','&value,value) AS List
RESIDENT T1
ORDER BY ID ASC;
DROP TABLE T1;
```

Create a table in a sheet in your app with **ID**, **List**, and **Value** as the dimensions.

Resulting table

ID	List	Value
1	3,4	4
1	3,4,6	6
1	3	3
2	1,11	11
2	1	1
3	7,8	8
3	7	7
5	2,78	78
5	2,78,13	13
5	2	2

The **IF()** statement is built from the temporary table T1.

`Peek('ID')` references the field ID in the previous row in the current table T2.

`Peek('List')` references the field List in the previous row in the table T2, currently being built as the expression is evaluated.

The statement is evaluated as follows:

If the current value of ID is the same as the previous value of ID, then write the value of `Peek('List')` concatenated with the current value of Value. Otherwise, write the current value of Value only.

If `Peek('List')` already contains a concatenated result, the new result of `Peek('List')` will be concatenated to it.



*Note the **Order by** clause. This specifies how the table is ordered (by ID in ascending order). Without this, the `Peek()` function will use whatever arbitrary ordering the internal table has, which can lead to unpredictable results.*

### Example 3

Add the example script to your app and run it. To see the result, add the fields listed in the results column to a sheet in your app.

```
Amounts:
Load
Date#(Month, 'YYYY-MM') as Month,
Amount,
Peek(Amount) as AmountMonthBefore
Inline
[Month, Amount
2022-01, 2
2022-02, 3
2022-03, 7
```

```
2022-04,9  
2022-05,4  
2022-06,1];
```

Resulting table

Amount	AmountMonthBefore	Month
1	4	2022-06
2	-	2022-01
3	2	2022-02
4	9	2022-05
7	3	2022-03
9	7	2022-04

The field AmountMonthBefore will hold the amount from the previous month.

Here, the row\_no and table\_name parameters are omitted, so the default values are used. In this example, the following three function calls are equivalent:

- Peek(Amount)
- Peek(Amount,-1)
- Peek(Amount,-1,'Amounts')

Using -1 as row\_no means that the value from previous row will be used. By substituting this value, values of other rows in the table can be fetched:

Peek(Amount,2) returns the third value in the table: 7.

### Example 4

Data needs to be correctly sorted in order to get the correct results but, unfortunately, this is not always the case. Furthermore, the Peek() function cannot be used to reference data that has not yet been loaded. By using temporary tables and running multiple passes through the data, such problems can be avoided.

Add the example script to your app and run it. To see the result, add the fields listed in the results column to a sheet in your app.

```
tmp1Amounts:  
Load * Inline  
[Month,Product,Amount  
2022-01,B,3  
2022-01,A,8  
2022-02,B,4  
2022-02,A,6  
2022-03,B,1  
2022-03,A,6  
2022-04,A,5  
2022-04,B,5
```

```
2022-05,B,6  
2022-05,A,7  
2022-06,A,4  
2022-06,B,8];
```

```
tmp2Amounts:  
Load *,  
If(Product=Peek(Product),Peek(Amount)) as AmountMonthBefore  
Resident tmp1Amounts  
Order By Product, Month Asc;  
Drop Table tmp1Amounts;
```

```
Amounts:  
Load *,  
If(Product=Peek(Product),Peek(Amount)) as AmountMonthAfter  
Resident tmp2Amounts  
Order By Product, Month Desc;  
Drop Table tmp2Amounts;
```

### Explanation

The initial table is sorted according to month, which means that the peek() function would in many cases return the amount for the wrong product. Hence, this table needs to be re-sorted. This is done by running a second pass through the data creating a new table tmp2Amounts. Note the Order By clause. It orders the records first by product, then by month in ascending order.

The If() function is needed since the AmountMonthBefore only should be calculated if the previous row contains the data for the same product but for the previous month. By comparing the product on the current row with the product on the previous row, this condition can be validated.

When the second table is created, the first table tmp1Amounts is dropped using a Drop Table statement.

Finally, a third pass is made through the data, but now with the months sorted in reverse order. This way, AmountMonthAfter can also be calculated.



*Order by clauses specify how the table is ordered; without these, the Peek() function will use whatever arbitrary ordering the internal table has, which can lead to unpredictable results.*

### Result

Resulting table

Month	Product	Amount	AmountMonthBefore	AmountMonthAfter
2022-01	A	8	-	6
2022-02	B	3	-	4

Month	Product	Amount	AmountMonthBefore	AmountMonthAfter
2022-03	A	6	8	6
2022-04	B	4	3	1
2022-05	A	6	6	5
2022-06	B	1	4	5
2022-01	A	5	6	7
2022-02	B	5	1	6
2022-03	A	7	5	4
2022-04	B	6	5	8
2022-05	A	4	7	-
2022-06	B	8	6	-

### Example 5

Add the example script to your app and run it. To see the result, add the fields listed in the results column to a sheet in your app.

T1:

```
Load * inline [
Quarter, value
2003q1, 10000
2003q1, 25000
2003q1, 30000
2003q2, 1250
2003q2, 55000
2003q2, 76200
2003q3, 9240
2003q3, 33150
2003q3, 89450
2003q4, 1000
2003q4, 3000
2003q4, 5000
2004q1, 1000
2004q1, 1250
2004q1, 3000
2004q2, 5000
2004q2, 9240
2004q2, 10000
2004q3, 25000
2004q3, 30000
2004q3, 33150
2004q4, 55000
2004q4, 76200
2004q4, 89450 ];
```

T2:



```
Load *, rangesum(SumVal,peek('AccSumVal')) as AccSumVal;  
Load Quarter, sum(Value) as SumVal resident T1 group by Quarter;
```

### Result

Resulting table

Quarter	SumVal	AccSumVal
2003q1	65000	65000
2003q2	132450	197450
2003q3	131840	329290
2003q4	9000	338290
2004q1	5250	343540
2004q2	24240	367780
2004q3	88150	455930
2004q4	220650	676580

### Explanation

The load statement **Load \*, rangesum(SumVal,peek('AccSumVal')) as AccSumVal** includes a recursive call where the previous values are added to the current value. This operation is used to calculate an accumulation of values in the script.

---

### See also:

## Previous

**Previous()** finds the value of the **expr** expression using data from the previous input record that has not been discarded because of a **where** clause. In the first record of an internal table, the function will return NULL.

### Syntax:

```
Previous(expr)
```

**Return data type:** dual

**Arguments:**

Arguments

Argument	Description
expr	The expression or field containing the data to be measured. The expression can contain nested <b>previous()</b> functions in order to access records further back. Data are fetched directly from the input source, making it possible to refer also to fields that have not been loaded into Qlik Sense, that is, even if they have not been stored in its associative database.

**Limitations:**

In the first record of an internal table, the function returns NULL.

**Example:**

Input the following into your load script:

```
sales2013:
Load *, (Sales - Previous(Sales) )as Increase Inline [
Month|Sales
1|12
2|13
3|15
4|17
5|21
6|21
7|22
8|23
9|32
10|35
11|40
12|41
] (delimiter is '|');
```

By using the **Previous()** function in the **Load** statement, we can compare the current value of Sales with the preceding value, and use it in a third field Increase.

Resulting table

Month	Sales	Increase
1	12	-
2	13	1
3	15	2
4	17	2

Month	Sales	Increase
5	21	4
6	21	0
7	22	1
8	23	1
9	32	9
10	35	3
11	40	5
12	41	1

## Top - chart function

**Top()** evaluates an expression at the first (top) row of a column segment in a table. The row for which it is calculated depends on the value of **offset**, if present, the default being the top row. For charts other than tables, the **Top()** evaluation is made on the first row of the current column in the chart's straight table equivalent.

### Syntax:

```
Top([TOTAL] expr [ , offset [,count ]])
```

**Return data type:** dual

### Arguments:

#### Arguments

Argument	Description
expr	The expression or field containing the data to be measured.
offset	Specifying an <b>offset</b> of n, greater than 1, moves the evaluation of the expression down n rows below the top row.  Specifying a negative offset number makes the <b>Top</b> function work like the <b>Bottom</b> function with the corresponding positive offset number.
count	By specifying a third parameter <b>count</b> greater than 1, the function will return a range of <b>count</b> values, one for each of the last <b>count</b> rows of the current column segment. In this form, the function can be used as an argument to any of the special range functions. <i>Range functions (page 1334)</i>
TOTAL	If the table is one-dimensional or if the qualifier <b>TOTAL</b> is used as argument, the current column segment is always equal to the entire column.



A column segment is defined as a consecutive subset of cells having the same values for the dimensions in the current sort order. Inter-record chart functions are computed in the column segment excluding the right-most dimension in the equivalent straight table chart. If there is only one dimension in the chart, or if the TOTAL qualifier is specified, the expression evaluates across full table.



If the table or table equivalent has multiple vertical dimensions, the current column segment will include only rows with the same values as the current row in all dimension columns, except for the column showing the last dimension in the inter-field sort order.

### Limitations:

- Recursive calls will return NULL.
- Sorting on y-values in charts or sorting by expression columns in tables is not allowed when this chart function is used in any of the chart's expressions. These sort alternatives are therefore automatically disabled. When you use this chart function in a visualization or table, the sorting of the visualization will revert back to the sorted input to this function.

### Examples and results:

#### Example: 1

In the screenshot of the table shown in this example, the table visualization is created from the dimension **Customer** and the measures `sum(Sales)` and `Top(Sum(Sales))`.

The column **Top(Sum(Sales))** returns 587 for all rows because this is the value of the top row: **Astrida**.

The table also shows more complex measures: one created from `sum(Sales)+Top(Sum(Sales))` and one labeled **Top offset 3**, which is created using the expression `sum(Sales)+Top(Sum(Sales), 3)` and has the argument **offset** set to 3. It adds the **Sum(Sales)** value for the current row to the value from the third row from the top row, that is, the current row plus the value for **Canutility**.

Example 1

Top and Bottom					
Customer	Q	Sum(Sales)	Top(Sum(Sales))	Sum(Sales)+Top(Sum(Sales))	Top offset 3
Totals		2566	587	3153	3249
Astrida		587	587	1174	1270
Betacab		539	587	1126	1222
Canutility		683	587	1270	1366
Divadip		757	587	1344	1440

### Example: 2

In the screenshots of tables shown in this example, more dimensions have been added to the visualizations: **Month** and **Product**. For charts with more than one dimension, the results of expressions containing the **Above**, **Below**, **Top**, and **Bottom** functions depend on the order in which the column dimensions are sorted by Qlik Sense. Qlik Sense evaluates the functions based on the column segments that result from the dimension that is sorted last. The column sort order is controlled in the properties panel under **Sorting** and is not necessarily the order in which the columns appear in a table.

*First table for Example 2. The value of Top for the First value measure based on Month (Jan).*

Customer	Product	Month	Sum(Sales)	First value
			<b>2566</b>	-
Astrida	AA	Jan	46	46
Astrida	AA	Feb	60	46
Astrida	AA	Mar	70	46
Astrida	AA	Apr	13	46
Astrida	AA	May	78	46
Astrida	AA	Jun	20	46
Astrida	AA	Jul	45	46
Astrida	AA	Aug	65	46
Astrida	AA	Sep	78	46
Astrida	AA	Oct	12	46
Astrida	AA	Nov	78	46
Astrida	AA	Dec	22	46

*Second table for Example 2. The value of Top for the First value measure based on Product (AA for Astrida).*

Customer	Product	Month	Sum(Sales)	First value
			<b>2566</b>	-
Astrida	AA	Jan	46	46
Astrida	BB	Jan	46	46
Astrida	AA	Feb	60	60
Astrida	BB	Feb	60	60
Astrida	AA	Mar	70	70
Astrida	BB	Mar	70	70
Astrida	AA	Apr	13	13
Astrida	BB	Apr	13	13

Please refer to Example: 2 in the **Above** function for further details.

Example 3

Example: 3	Result								
<p>The <b>Top</b> function can be used as input to the range functions. For example: <code>RangeAvg (Top (Sum(Sales), 1, 3))</code>.</p>	<p>In the arguments for the <b>Top()</b> function, offset is set to 1 and count is set to 3. The function finds the results of the expression <b>Sum(Sales)</b> on the three rows starting with the row below the bottom row in the column segment (because the offset=1), and the two rows below that (where there is a row). These three values are used as input to the <code>RangeAvg()</code> function, which finds the average of the values in the supplied range of numbers.</p> <p>A table with <b>Customer</b> as dimension gives the following results for the <code>RangeAvg()</code> expression.</p>								
	<table> <tbody> <tr> <td>Astrida</td> <td>603</td> </tr> <tr> <td>Betacab</td> <td>603</td> </tr> <tr> <td>Canutility</td> <td>603</td> </tr> <tr> <td>Divadip:</td> <td>603</td> </tr> </tbody> </table>	Astrida	603	Betacab	603	Canutility	603	Divadip:	603
Astrida	603								
Betacab	603								
Canutility	603								
Divadip:	603								






Monthnames:

```
LOAD *, Dual(MonthText,MonthNumber) as Month INLINE [
MonthText, MonthNumber
Jan, 1
Feb, 2
Mar, 3
Apr, 4
May, 5
Jun, 6
Jul, 7
Aug, 8
Sep, 9
Oct, 10
Nov, 11
Dec, 12
];
```

Sales2013:

```
Crosstable (MonthText, Sales) LOAD * inline [
Customer|Jan|Feb|Mar|Apr|May|Jun|Jul|Aug|Sep|Oct|Nov|Dec
Astrida|46|60|70|13|78|20|45|65|78|12|78|22
Betacab|65|56|22|79|12|56|45|24|32|78|55|15
Canutility|77|68|34|91|24|68|57|36|44|90|67|27
Divadip|57|36|44|90|67|27|57|68|47|90|80|94
] (delimiter is '|');
```

### See also:

-  [Bottom - chart function \(page 1285\)](#)
-  [Above - chart function \(page 1277\)](#)
-  [Sum - chart function \(page 353\)](#)
-  [RangeAvg \(page 1337\)](#)
-  [Range functions \(page 1334\)](#)

## SecondaryDimensionality - chart function

**SecondaryDimensionality()** returns the number of dimension pivot table rows that have non-aggregation content, that is, do not contain partial sums or collapsed aggregates. This function is the equivalent of the **dimensionality()** function for horizontal pivot table dimensions.

### Syntax:

```
SecondaryDimensionality( )
```

**Return data type:** integer

### Limitations:

- Unless used in pivot tables, the **SecondaryDimensionality** function always returns 0.
- Sorting on y-values in charts or sorting by expression columns in tables is not allowed when this chart function is used in any of the chart's expressions. These sort alternatives are therefore automatically disabled. When you use this chart function in a visualization or table, the sorting of the visualization will revert back to the sorted input to this function.

## After - chart function

**After()** returns the value of an expression evaluated with a pivot table's dimension values as they appear in the column after the current column within a row segment in the pivot table.

### Syntax:

```
after([TOTAL] expr [, offset [, count ]])
```



*Sorting on y-values in charts or sorting by expression columns in tables is not allowed when this chart function is used in any of the chart's expressions. These sort alternatives are therefore automatically disabled. When you use this chart function in a visualization or table, the sorting of the visualization will revert back to the sorted input to this function.*



*This function returns NULL in all chart types except pivot tables.*

**Arguments:**

Argument	Description
expr	The expression or field containing the data to be measured.
offset	Specifying an <b>offset</b> n, greater than 1 moves the evaluation of the expression n rows further to the right from the current row.  Specifying an offset of 0 will evaluate the expression on the current row.  Specifying a negative offset number makes the <b>After</b> function work like the <b>Before</b> function with the corresponding positive offset number.
count	By specifying a third parameter <b>count</b> greater than 1, the function will return a range of values, one for each of the table rows up to the value of <b>count</b> , counting to the right from the original cell.
TOTAL	If the table is one-dimensional or if the qualifier <b>TOTAL</b> is used as argument, the current column segment is always equal to the entire column.

On the last column of a row segment a NULL value will be returned, as there is no column after this one.

If the pivot table has multiple horizontal dimensions, the current row segment will include only columns with the same values as the current column in all dimension rows except for the row showing the last horizontal dimension of the inter-field sort order. The inter-field sort order for horizontal dimensions in pivot tables is defined simply by the order of the dimensions from top to bottom.

**Example:**

```
after( sum( Sales ))
after( sum( Sales ), 2 )
after( total sum( Sales ))
```

rangeavg (after(sum(x),1,3)) returns an average of the three results of the **sum(x)** function evaluated in the three columns immediately to the right of the current column.

**Before - chart function**

**Before()** returns the value of an expression evaluated with a pivot table's dimension values as they appear in the column before the current column within a row segment in the pivot table.

**Syntax:**

```
before ([TOTAL] expr [, offset [, count]])
```



*This function returns NULL in all chart types except pivot tables.*





Sorting on y-values in charts or sorting by expression columns in tables is not allowed when this chart function is used in any of the chart's expressions. These sort alternatives are therefore automatically disabled. When you use this chart function in a visualization or table, the sorting of the visualization will revert back to the sorted input to this function.

### Arguments:

#### Arguments

Argument	Description
expr	The expression or field containing the data to be measured.
offset	<p>Specifying an <b>offset</b> n, greater than 1 moves the evaluation of the expression n rows further to the left from the current row.</p> <p>Specifying an offset of 0 will evaluate the expression on the current row.</p> <p>Specifying a negative offset number makes the <b>Before</b> function work like the <b>After</b> function with the corresponding positive offset number.</p>
count	By specifying a third parameter <b>count</b> greater than 1, the function will return a range of values, one for each of the table rows up to the value of <b>count</b> , counting to the left from the original cell.
TOTAL	If the table is one-dimensional or if the qualifier <b>TOTAL</b> is used as argument, the current column segment is always equal to the entire column.

On the first column of a row segment a NULL value will be returned, as there is no column before this one.

If the pivot table has multiple horizontal dimensions, the current row segment will include only columns with the same values as the current column in all dimension rows except for the row showing the last horizontal dimension of the inter-field sort order. The inter-field sort order for horizontal dimensions in pivot tables is defined simply by the order of the dimensions from top to bottom.

### Examples:

```
before( sum( Sales ))
```

```
before( sum( Sales ), 2 )
```

```
before( total sum( Sales ))
```

rangeavg (before(sum(x), 1, 3)) returns an average of the three results of the **sum(x)** function evaluated in the three columns immediately to the left of the current column.

## First - chart function

**First()** returns the value of an expression evaluated with a pivot table's dimension values as they appear in the first column of the current row segment in the pivot table. This function returns NULL in all chart types except pivot tables.



*Sorting on y-values in charts or sorting by expression columns in tables is not allowed when this chart function is used in any of the chart's expressions. These sort alternatives are therefore automatically disabled. When you use this chart function in a visualization or table, the sorting of the visualization will revert back to the sorted input to this function.*

### Syntax:

```
first([TOTAL] expr [, offset [, count]])
```

### Arguments:

#### Arguments

Argument	Description
expression	The expression or field containing the data to be measured.
offset	Specifying an <b>offset</b> n, greater than 1 moves the evaluation of the expression n rows further to the right from the current row.  Specifying an offset of 0 will evaluate the expression on the current row.  Specifying a negative offset number makes the <b>First</b> function work like the <b>Last</b> function with the corresponding positive offset number.
count	By specifying a third parameter <b>count</b> greater than 1, the function will return a range of values, one for each of the table rows up to the value of <b>count</b> , counting to the right from the original cell.
TOTAL	If the table is one-dimensional or if the qualifier <b>TOTAL</b> is used as argument, the current column segment is always equal to the entire column.

If the pivot table has multiple horizontal dimensions, the current row segment will include only columns with the same values as the current column in all dimension rows except for the row showing the last horizontal dimension of the inter-field sort order. The inter-field sort order for horizontal dimensions in pivot tables is defined simply by the order of the dimensions from top to bottom.

### Examples:

```
first( sum( Sales ) )
first( sum( Sales ), 2 )
first( total sum( Sales ) )
```

`rangeavg (first(sum(x),1,5))` returns an average of the results of the **sum(x)** function evaluated on the five leftmost columns of the current row segment.

### Last - chart function

**Last()** returns the value of an expression evaluated with a pivot table's dimension values as they appear in the last column of the current row segment in the pivot table. This function returns NULL in all chart types except pivot tables.



*Sorting on y-values in charts or sorting by expression columns in tables is not allowed when this chart function is used in any of the chart's expressions. These sort alternatives are therefore automatically disabled. When you use this chart function in a visualization or table, the sorting of the visualization will revert back to the sorted input to this function.*

#### Syntax:

```
last([TOTAL] expr [, offset [, count]])
```

#### Arguments:

##### Arguments

Argument	Description
expr	The expression or field containing the data to be measured.
offset	Specifying an <b>offset</b> n, greater than 1 moves the evaluation of the expression n rows further to the left from the current row.  Specifying an offset of 0 will evaluate the expression on the current row.  Specifying a negative offset number makes the <b>First</b> function work like the <b>Last</b> function with the corresponding positive offset number.
count	By specifying a third parameter <b>count</b> greater than 1, the function will return a range of values, one for each of the table rows up to the value of <b>count</b> , counting to the left from the original cell.
TOTAL	If the table is one-dimensional or if the qualifier <b>TOTAL</b> is used as argument, the current column segment is always equal to the entire column.

If the pivot table has multiple horizontal dimensions, the current row segment will include only columns with the same values as the current column in all dimension rows except for the row showing the last horizontal dimension of the inter-field sort order. The inter-field sort order for horizontal dimensions in pivot tables is defined simply by the order of the dimensions from top to bottom.

#### Example:

```
last( sum( sales ) )
last( sum( sales ), 2 )
```

`last( total sum( Sales )`

`rangeavg (last(sum(x),1,5))` returns an average of the results of the **sum(x)** function evaluated on the five rightmost columns of the current row segment.

### ColumnNo - chart function

**ColumnNo()** returns the number of the current column within the current row segment in a pivot table. The first column is number 1.

#### Syntax:

```
ColumnNo([total])
```

#### Arguments:

##### Arguments

Argument	Description
TOTAL	If the table is one-dimensional or if the qualifier <b>TOTAL</b> is used as argument, the current column segment is always equal to the entire column.

If the pivot table has multiple horizontal dimensions, the current row segment will include only columns with the same values as the current column in all dimension rows except for the row showing the last horizontal dimension of the inter-field sort order. The inter-field sort order for horizontal dimensions in pivot tables is defined simply by the order of the dimensions from top to bottom.



*Sorting on y-values in charts or sorting by expression columns in tables is not allowed when this chart function is used in any of the chart's expressions. These sort alternatives are therefore automatically disabled. When you use this chart function in a visualization or table, the sorting of the visualization will revert back to the sorted input to this function.*

#### Example:

```
if( ColumnNo()=1, 0, sum( Sales ) / before( sum( sales )))
```

### NoOfColumns - chart function

**NoOfColumns()** returns the number of columns in the current row segment in a pivot table.



*Sorting on y-values in charts or sorting by expression columns in tables is not allowed when this chart function is used in any of the chart's expressions. These sort alternatives are therefore automatically disabled. When you use this chart function in a visualization or table, the sorting of the visualization will revert back to the sorted input to this function.*

**Syntax:**

```
NoOfColumns ([total])
```

**Arguments:**

## Arguments

Argument	Description
TOTAL	If the table is one-dimensional or if the qualifier <b>TOTAL</b> is used as argument, the current column segment is always equal to the entire column.

If the pivot table has multiple horizontal dimensions, the current row segment will include only columns with the same values as the current column in all dimension rows except for the row showing the last dimension in the inter-field sort order. The inter-field sort order for horizontal dimensions in pivot tables is defined simply by the order of the dimensions from top to bottom.

**Example:**

```
if( columnNo( )=NoOfColumns( ), 0, after( sum( Sales )))
```

## 8.17 Logical functions

This section describes functions handling logical operations. All functions can be used in both the data load script and in chart expressions.

**IsNum**

Returns -1 (True) if the expression can be interpreted as a number, otherwise 0 (False).

```
IsNum( expr )
```

**IsText**

Returns -1 (True) if the expression has a text representation, otherwise 0 (False).

```
IsText( expr )
```



*Both **IsNum** and **IsText** return 0 if the expression is NULL.*

**Example:**

The following example loads an inline table with mixed text and numerical values, and adds two fields to check if the value is a numerical value, respectively a text value.

```
Load *, IsNum(Value), IsText(Value)
Inline [
Value
23
Green
Blue
```

12  
33Red];

The resulting table looks like this:

Resulting table

Value	IsNum(Value)	IsText(Value)
23	-1	0
Green	0	-1
Blue	0	-1
12	-1	0
33Red	0	-1

### 8.18 Mapping functions

This section describes functions for handling mapping tables. A mapping table can be used to replace field values or field names during script execution.

Mapping functions can only be used in the data load script

#### Mapping functions overview

Each function is described further after the overview. You can also click the function name in the syntax to immediately access the details for that specific function.

##### ApplyMap

The **ApplyMap** script function is used for mapping the output of an expression to a previously loaded mapping table.

```
ApplyMap ('mapname', expr [ , defaultexpr ] )
```

##### MapSubstring

The **MapSubstring** script function is used to map parts of any expression to a previously loaded mapping table. The mapping is case sensitive and non-iterative, and substrings are mapped from left to right.

```
MapSubstring ('mapname', expr)
```

#### ApplyMap

The **ApplyMap** script function is used for mapping the output of an expression to a previously loaded mapping table.


##### Syntax:

```
ApplyMap('map_name', expression [ , default_mapping ] )
```

**Return data type:** dual

**Arguments:**

### Arguments

Argument	Description
map_name	<p>The name of a mapping table that has previously been created through the <b>mapping load</b> or the <b>mapping select</b> statement. Its name must be enclosed by single, straight quotation marks.</p> <div style="border: 1px solid gray; padding: 5px; margin-top: 10px;">  <i>If you use this function in a macro expanded variable and refer to a mapping table that does not exist, the function call fails and a field is not created.</i> </div>
expression	The expression, the result of which should be mapped.
default_mapping	If stated, this value will be used as a default value if the mapping table does not contain a matching value for expression. If not stated, the value of expression will be returned as is.



*The output field of ApplyMap should not have the same name as one of its input fields. This may cause unexpected results. Example not to use: `ApplyMap('Map', A) as A`.*

**Example:**

In this example we load a list of salespersons with a country code representing their country of residence. We use a table mapping a country code to a country to replace the country code with the country name. Only three countries are defined in the mapping table, other country codes are mapped to 'Rest of the world'.

```
// Load mapping table of country codes:
map1:
mapping LOAD *
inline [
CCode, Country
Sw, Sweden
Dk, Denmark
No, Norway
] ;

// Load list of salesmen, mapping country code to country
// If the country code is not in the mapping table, put Rest of the world
Salespersons:
LOAD *,
ApplyMap('map1', CCode,'Rest of the world') As Country
inline [
CCode, Salesperson
```

```
Sw, John  
Sw, Mary  
Sw, Per  
Dk, Preben  
Dk, Olle  
No, Ole  
Sf, Risttu  
];
```

```
// We don't need the CCode anymore  
Drop Field 'CCode';
```

The resulting table (Salespersons) looks like this:

Resulting table

Salesperson	Country
John	Sweden
Mary	Sweden
Per	Sweden
Preben	Denmark
Olle	Denmark
Ole	Norway
Risttu	Rest of the world

### MapSubstring

The **MapSubstring** script function is used to map parts of any expression to a previously loaded mapping table. The mapping is case sensitive and non-iterative, and substrings are mapped from left to right.

**Syntax:**


```
MapSubstring('map_name', expression)
```



**Return data type:** string

**Arguments:**

Arguments

Argument	Description
map_name	<p>The name of a mapping table previously read by a <b>mapping load</b> or a <b>mapping select</b> statement. The name must be enclosed by single straight quotation marks.</p> <div style="border: 1px solid gray; padding: 5px; margin-top: 10px;">  <p><i>If you use this function in a macro expanded variable and refer to a mapping table that does not exist, the function call fails and a field is not created.</i></p> </div>
expression	The expression whose result is to be mapped by substrings.

**Example:**

In this example we load a list of product models. Each model has a set of attributes that are described by a composite code. Using the mapping table with MapSubstring, we can expand the attribute codes to a description.

```
map2:
mapping LOAD *
inline [
AttCode, Attribute
R, Red
Y, Yellow
B, Blue
C, Cotton
P, Polyester
S, Small
M, Medium
L, Large
] ;

Productmodels:
LOAD *,
MapSubString('map2', AttCode) as Description
inline [
Model, AttCode
Twixie, R C S
Boomer, B P L
Raven, Y P M
Seedling, R C L
SeedlingPlus, R C L with hood
Younger, B C with patch
MultiStripe, R Y B C S/M/L
] ;
```

```
// We don't need the AttCode anymore  
Drop Field 'AttCode';
```

The resulting table looks like this:

Resulting table

<b>Model</b>	<b>Description</b>
Twixie	Red Cotton Small
Boomer	Blue Polyester Large
Raven	Yellow Polyester Medium
Seedling	Red Cotton Large
SeedlingPlus	Red Cotton Large with hood
Younger	Blue Cotton with patch
MultiStripe	Red Yellow Blue Cotton Small/Medium/Large

### 8.19 Mathematical functions

This section describes functions for mathematical constants and Boolean values. These functions do not have any parameters, but the parentheses are still required.

All functions can be used in both the data load script and in chart expressions.

#### **e**

The function returns the base of the natural logarithms, **e** ( 2.71828...).

```
e( )
```

#### **false**

The function returns a dual value with text value 'False' and numeric value 0, which can be used as logical false in expressions.

```
false( )
```

#### **pi**

The function returns the value of  $\pi$  (3.14159...).

```
pi( )
```

#### **rand**

The function returns a random number between 0 and 1. This can be used to create sample data.

```
rand( )
```

### Example:

This example script creates a table of 1000 records with randomly selected upper case characters, that is, characters in the range 65 to 91 (65+26).

```
Load
  Chr( Floor(rand() * 26) + 65) as UCaseChar,
  RecNo() as ID
Autogenerate 1000;
```

### true

The function returns a dual value with text value 'True' and numeric value -1, which can be used as logical true in expressions.

```
true( )
```

## 8.20 NULL functions

This section describes functions for returning or detecting NULL values.

All functions can be used in both the data load script and in chart expressions.

### NULL functions overview

Each function is described further after the overview. You can also click the function name in the syntax to immediately access the details for that specific function.

#### EmptyIsNull

The **EmptyIsNull** function converts empty strings to NULL. Hence, it returns NULL if the parameter is an empty string, otherwise it returns the parameter.

```
EmptyIsNull (expr )
```

#### IsNull

The **IsNull** function tests if the value of an expression is NULL and if so, returns -1 (True), otherwise 0 (False).

```
IsNull (expr )
```

#### Null

The **Null** function returns a NULL value.

```
NULL( )
```

### EmptyIsNull

The **EmptyIsNull** function converts empty strings to NULL. Hence, it returns NULL if the parameter is an empty string, otherwise it returns the parameter.

#### Syntax:

```
EmptyIsNull (exp )
```

Examples and results:

### Scripting examples

Example	Result
<code>EmptyIsNull(AdditionalComments)</code>	This expression will return as null any empty string values of the <i>AdditionalComments</i> field instead of empty strings. Non-empty strings and numbers are returned.
<code>EmptyIsNull(PurgeChar(PhoneNumber, ' -()'))</code>	This expression will strip any dashes, spaces and parentheses from the <i>PhoneNumber</i> field. If there are no characters left, the EmptyIsNull function returns the empty string as null; an empty phone number is the same as no phone number.

## IsNull

The **IsNull** function tests if the value of an expression is NULL and if so, returns -1 (True), otherwise 0 (False).

### Syntax:

```
IsNull (expr )
```



*A string with length zero is not considered as a NULL and will cause **IsNull** to return False.*

### Example: Data load script

In this example, an inline table with four rows is loaded, where the first three lines contain either nothing, - or 'NULL' in the Value column. We convert these values to true NULL value representations with the middle preceding **LOAD** using the **Null** function.

The first preceding **LOAD** adds a field checking if the value is NULL, using the **IsNull** function.

NullsDetectedAndConverted:

```
LOAD *,
If(IsNull(ValueNullConv), 'T', 'F') as IsItNull;

LOAD *,
If(len(trim(Value))= 0 or Value='NULL' or Value='-', Null(), value ) as valueNullConv;

LOAD * Inline
[ID, Value
0,
1, NULL
2, -
3, value];
```

This is the resulting table. In the ValueNullConv column, the NULL values are represented by -.

Resulting table

ID	Value	ValueNullConv	IsItNull
0		-	T
1	NULL	-	T
2	-	-	T
3	Value	Value	F

### NULL

The **Null** function returns a NULL value.

#### Syntax:

```
Null ( )
```

#### Example: Data load script

In this example, an inline table with four rows is loaded, where the first three lines contain either nothing, - or 'NULL' in the Value column. We want to convert these values to true NULL value representations.

The middle preceding **LOAD** performs the conversion using the **Null** function.

The first preceding **LOAD** adds a field checking if the value is NULL, just for illustration purposes in this example.

NullsDetectedAndConverted:

```
LOAD *,
If(IsNull(ValueNullConv), 'T', 'F') as IsItNull;

LOAD *,
If(len(trim(Value))= 0 or Value='NULL' or Value='- ', Null(), value ) as ValueNullConv;

LOAD * Inline
[ID, Value
0,
1,NULL
2,-
3,Value];
```

This is the resulting table. In the ValueNullConv column, the NULL values are represented by -.

Resulting table

ID	Value	ValueNullConv	IsItNull
0		-	T
1	NULL	-	T
2	-	-	T
3	Value	Value	F

## 8.21 Range functions

The range functions are functions that take an array of values and produce a single value as a result. All range functions can be used in both the data load script and in chart expressions.

For example, in a visualization, a range function can calculate a single value from an inter-record array. In the data load script, a range function can calculate a single value from an array of values in an internal table.



*Range functions replace the following general numeric functions: **numsum**, **numavg**, **numcount**, **nummin** and **nummax**, which should now be regarded as obsolete.*

### Basic range functions

RangeMax

**RangeMax()** returns the highest numeric values found within the expression or field.

```
RangeMax(first_expr[, Expression])
```

RangeMaxString

**RangeMaxString()** returns the last value in the text sort order that it finds in the expression or field.

```
RangeMaxString(first_expr[, Expression])
```

RangeMin

**RangeMin()** returns the lowest numeric values found within the expression or field.

```
RangeMin(first_expr[, Expression])
```

RangeMinString

**RangeMinString()** returns the first value in the text sort order that it finds in the expression or field.

```
RangeMinString(first_expr[, Expression])
```

RangeMode

**RangeMode()** finds the most commonly occurring value (mode value) in the expression or field.

```
RangeMode(first_expr[, Expression])
```

RangeOnly

**RangeOnly()** is a dual function that returns a value if the expression evaluates to one unique value. If this is not the case then **NULL** is returned.

```
RangeOnly(first_expr[, Expression])
```

RangeSum

**RangeSum()** returns the sum of a range of values. All non-numeric values are treated as 0.

```
RangeSum (first_expr[, Expression])
```

### Counter range functions

RangeCount

**RangeCount()** returns the number of values, both text and numeric, in the expression or field.

```
RangeCount (first_expr[, Expression])
```

RangeMissingCount

**RangeMissingCount()** returns the number of non-numeric values (including NULL) in the expression or field.

```
RangeMissingCount (first_expr[, Expression])
```

RangeNullCount

**RangeNullCount()** finds the number of NULL values in the expression or field.

```
RangeNullCount (first_expr[, Expression])
```

RangeNumericCount

**RangeNumericCount()** finds the number of numeric values in an expression or field.

```
RangeNumericCount (first_expr[, Expression])
```

RangeTextCount

**RangeTextCount()** returns the number of text values in an expression or field.

```
RangeTextCount (first_expr[, Expression])
```

### Statistical range functions

RangeAvg

**RangeAvg()** returns the average of a range. Input to the function can be either a range of values or an expression.

```
RangeAvg (first_expr[, Expression])
```

RangeCorrel

**RangeCorrel()** returns the correlation coefficient for two sets of data. The correlation coefficient is a measure of the relationship between the data sets.

```
RangeCorrel (x_values , y_values[, Expression])
```

RangeFractile

**RangeFractile()** returns the value that corresponds to the n-th **fractile** (quantile) of a range of numbers.

```
RangeFractile (fractile, first_expr[ ,Expression])
```

RangeKurtosis

**RangeKurtosis()** returns the value that corresponds to the kurtosis of a range of numbers.

```
RangeKurtosis (first_expr[, Expression])
```

RangeSkew

**RangeSkew()** returns the value corresponding to the skewness of a range of numbers.

```
RangeSkew (first_expr[, Expression])
```

RangeStdev

**RangeStdev()** finds the standard deviation of a range of numbers.

```
RangeStdev (expr1[, Expression])
```

## Financial range functions

**RangeIRR**

**RangeIRR()** returns the internal rate of return for a series of cash flows represented by the input values.

```
RangeIRR (value[, value][, Expression])
```

**RangeNPV**

**RangeNPV()** returns the net present value of an investment based on a discount rate and a series of future periodic payments (negative values) and incomes (positive values). The result has a default number format of **money**.

```
RangeNPV (discount_rate, value[, value][, Expression])
```

**RangeXIRR**

**RangeXIRR()** returns the internal rate of return (yearly) for a schedule of cash flows that is not necessarily periodic. To calculate the internal rate of return for a series of periodic cash flows, use the **RangeIRR** function.

```
RangeXIRR (values, dates[, Expression])
```

**RangeXNPV**

**RangeXNPV()** returns the net present value for a schedule of cash flows (not necessarily periodic) represented by paired numbers in the expressions given by **pmt** and **date**. All payments are discounted based on a 365-day year.

```
RangeXNPV (discount_rate, values, dates[, Expression])
```

---

**See also:**

 [Inter-record functions \(page 1273\)](#)



## RangeAvg

**RangeAvg()** returns the average of a range. Input to the function can be either a range of values or an expression.

### Syntax:

```
RangeAvg (first_expr[, Expression])
```

**Return data type:** numeric

### Arguments:

The arguments of this function may contain inter-record functions which in themselves return a list of values.

Arguments

Argument	Description
first_expr	The expression or field containing the data to be measured.
Expression	Optional expressions or fields containing the range of data to be measured.

### Limitations:

If no numeric value is found, NULL is returned.

### Examples and results:

Scripting examples

Examples	Results
RangeAvg (1,2,4)	Returns 2.33333333
RangeAvg (1, 'xyz')	Returns 1
RangeAvg (null( ), 'abc')	Returns NULL

### Example:

Add the example script to your app and run it. To see the result, add the fields listed in the results column to a sheet in your app.

```
RangeTab3:
LOAD recno() as RangeID, RangeAvg(Field1,Field2,Field3) as MyRangeAvg INLINE [
Field1, Field2, Field3
10,5,6
2,3,7
8,2,8
18,11,9
5,5,9
9,4,2
];
```

## 8 Script and chart functions

The resulting table shows the returned values of MyRangeAvg for each of the records in the table.

Resulting table

RangeID	MyRangeAvg
1	7
2	4
3	6
4	12.666
5	6.333
6	5

Example with expression:

```
RangeAvg (Above(MyField),0,3))
```

Returns a sliding average of the result of the range of three values of **MyField** calculated on the current row and two rows above the current row. By specifying the third argument as 3, the **Above ()** function returns three values, where there are sufficient rows above, which are taken as input to the **RangeAvg()** function.

Data used in examples:



*Disable sorting of **MyField** to ensure that the example works as expected.*



Sample data

MyField	RangeAvg (Above (MyField,0,3))	Comments
10	10	Because this is the top row, the range consists of one value only.
2	6	There is only one row above this row, so the range is: 10,2.
8	6.6666666667	The equivalent to RangeAvg(10,2,8)
18	9.3333333333	-
5	10.3333333333	-
9	10.6666666667	-

```
RangeTab:
LOAD * INLINE [
MyField
10
2
8
18
```

```
5
9
] ;
```

**See also:**

-  [Avg - chart function \(page 407\)](#)
-  [Count - chart function \(page 357\)](#)

## RangeCorrel

**RangeCorrel()** returns the correlation coefficient for two sets of data. The correlation coefficient is a measure of the relationship between the data sets.

**Syntax:**

```
RangeCorrel (x_value , y_value[, Expression])
```

**Return data type:** numeric

Data series should be entered as (x,y) pairs. For example, to evaluate two series of data, array 1 and array 2, where the array 1 = 2,6,9 and array 2 = 3,8,4 you would write `RangeCorrel (2,3,6,8,9,4)` which returns 0.269.

**Arguments:**

## Arguments

Argument	Description
x-value, y-value	Each value represents a single value or a range of values as returned by an inter-record functions with a third optional parameter. Each value or range of values must correspond to an <b>x-value</b> or a range of <b>y-values</b> .
Expression	Optional expressions or fields containing the range of data to be measured.

**Limitations:**

The function needs at least two pairs of coordinates to be calculated.

Text values, NULL values and missing values return NULL.

**Examples and results:**

## Function examples

Examples	Results
<code>RangeCorrel (2,3,6,8,9,4,8,5)</code>	Returns 0.2492. This function can be loaded in the script or added into a visualization in the expression editor.

### Example:

Add the example script to your app and run it. To see the result, add the fields listed in the results column to a sheet in your app.

```
RangeList:
Load * Inline [
ID1|x1|y1|x2|y2|x3|y3|x4|y4|x5|y5|x6|y6
01|46|60|70|13|78|20|45|65|78|12|78|22
02|65|56|22|79|12|56|45|24|32|78|55|15
03|77|68|34|91|24|68|57|36|44|90|67|27
04|57|36|44|90|67|27|57|68|47|90|80|94
](delimiter is '|');
```

```
XY:
LOAD recno() as RangeID, * Inline [
X|Y
2|3
6|8
9|4
8|5
](delimiter is '|');
```

In a table with ID1 as a dimension and the measure RangeCorrel (x1,y1,x2,y2,x3,y3,x4,y4,x5,y5,x6,y6), the **RangeCorrel()** function finds the value of **Correl** over the range of six x,y pairs, for each of the ID1 values.

Resulting table

ID1	MyRangeCorrel
01	-0.9517
02	-0.5209
03	-0.5209
04	-0.1599

### Example:

```
XY:
LOAD recno() as RangeID, * Inline [
X|Y
2|3
6|8
9|4
8|5
](delimiter is '|');
```

In a table with RangeID as a dimension and the measure: RangeCorrel(Below(X,0,4,BelowY,0,4)), the **RangeCorrel()** function uses the results of the **Below()** functions, which because of the third argument (count) set to 4, produce a range of four x-y values from the loaded table XY.


Resulting table

RangeID	MyRangeCorrel2
01	0.2492
02	-0.9959
03	-1.0000
04	-

The value for RangeID 01 is the same as manually entering RangeCorrel(2,3,6,8,9,4,8,5). For the other values of RangeID, the series produced by the Below() function are: (6,8,9,4,8,5), (9,4,8,5), and (8,5), the last of which produces a null result.

---

**See also:**

 [Correl - chart function \(page 411\)](#)

## RangeCount

**RangeCount()** returns the number of values, both text and numeric, in the expression or field.

**Syntax:**

```
RangeCount (first_expr[, Expression])
```

**Return data type:** integer

**Arguments:**

The arguments of this function may contain inter-record functions which in themselves return a list of values.

Arguments

Argument	Description
first_expr	The expression or field containing the data to be counted.
Expression	Optional expressions or fields containing the range of data to be counted.

**Limitations:**

NULL values are not counted.

### Examples and results:

Function examples

Examples	Results
RangeCount (1,2,4)	Returns 3
RangeCount (2,'xyz')	Returns 2
RangeCount (null( ))	Returns 0
RangeCount (2,'xyz', null())	Returns 2

### Example:

Add the example script to your app and run it. To see the result, add the fields listed in the results column to a sheet in your app.

```
RangeTab3:
LOAD recno() as RangeID, RangeCount(Field1,Field2,Field3) as MyRangeCount INLINE [
Field1, Field2, Field3
10,5,6
2,3,7
8,2,8
18,11,9
5,5,9
9,4,2
];
```

The resulting table shows the returned values of MyRangeCount for each of the records in the table.

Results table

RangeID	MyRangeCount
1	3
2	3
3	3
4	3
5	3
6	3

### Example with expression:

```
RangeCount (Above(MyField,1,3))
```

Returns the number of values contained in the three results of **MyField**. By specifying the first argument of the **Above()** function as 1 and second argument as 3, it returns the values from the first three fields above the current row, where there are sufficient rows, which are taken as input to the **RangeCount()** function.

Data used in examples:

Sample data


MyField	RangeCount(Above(MyField,1,3))
10	0
2	1
8	2
18	3
5	3
9	3

Data used in examples:

```
RangeTab:
LOAD * INLINE [
MyField
10
2
8
18
5
9
] ;
```

---

### See also:

 [Count - chart function \(page 357\)](#)

## RangeFractile

**RangeFractile()** returns the value that corresponds to the n-th **fractile** (quantile) of a range of numbers.



*RangeFractile() uses linear interpolation between closest ranks when calculating the fractile.*

### Syntax:

```
RangeFractile(fractile, first_expr[, Expression])
```

**Return data type:** numeric

### Arguments:

The arguments of this function may contain inter-record functions which in themselves return a list of values.

### Arguments

Argument	Description
fractile	A number between 0 and 1 corresponding to the fractile (quantile expressed as a fraction) to be calculated.
first_expr	The expression or field containing the data to be measured.
Expression	Optional expressions or fields containing the range of data to be measured.

### Examples and results:

#### Function examples

Examples	Results
RangeFractile (0.24,1,2,4,6)	Returns 1.72
RangeFractile(0.5,1,2,3,4,6)	Returns 3
RangeFractile (0.5,1,2,5,6)	Returns 3.5

### Example:

Add the example script to your app and run it. To see the result, add the fields listed in the results column to a sheet in your app.

RangeTab:

```
LOAD recno() as RangeID, RangeFractile(0.5,Field1,Field2,Field3) as MyRangeFrac INLINE [
Field1, Field2, Field3
10,5,6
2,3,7
8,2,8
18,11,9
5,5,9
9,4,2
];
```

The resulting table shows the returned values of MyRangeFrac for each of the records in the table.

#### Resulting table

RangeID	MyRangeFrac
1	6
2	3
3	8
4	11
5	5
6	4



Example with expression:

```
RangeFractile (0.5, Above(Sum(MyField),0,3))
```

In this example, the inter-record function **Above()** contains the optional offset and count arguments. This produces a range of results that can be used as input to the any of the range functions. In this case, `Above(Sum(MyField),0,3)` returns the values of `MyField` for the current row and the two rows above. These values provide the input to the **RangeFractile()** function. So, for the bottom row in the table below, this is the equivalent of `RangeFractile(0.5, 3,4,6)`, that is, calculating the 0.5 fractile for the series 3, 4, and 6. The first two rows in the table below, the number of values in the range is reduced accordingly, where there no rows above the current row. Similar results are produced for other inter-record functions.

Sample data



MyField	RangeFractile(0.5, Above(Sum(MyField),0,3))
1	1
2	1.5
3	2
4	3
5	4
6	5

Data used in examples:

```
RangeTab:
LOAD * INLINE [
MyField
1
2
3
4
5
6
] ;
```

---

**See also:**

-  [Above - chart function \(page 1277\)](#)
-  [Fractile - chart function \(page 414\)](#)

## RangeIRR

**RangeIRR()** returns the internal rate of return for a series of cash flows represented by the input values.

The internal rate of return is the interest rate received for an investment consisting of payments (negative values) and income (positive values) that occur at regular periods.

This function uses a simplified version of the Newton method for calculating the internal rate of return (IRR).

### Syntax:

```
RangeIRR (value[, value][, Expression])
```

**Return data type:** numeric

### Arguments

Argument	Description
value	A single value or a range of values as returned by an inter record function with a third optional parameter. The function needs at least one positive and one negative value to be calculated.
Expression	Optional expressions or fields containing the range of data to be measured.

### Limitations:

Text values, NULL values and missing values are disregarded.

### Example table

Examples	Results														
RangeIRR(-70000,12000,15000,18000,21000,26000)	Returns 0.0866														
<p>Add the example script to your app and run it. To see the result, add the fields listed in the results column to a sheet in your app.</p> <pre> RangeTab3: LOAD *, recno() as RangeID, RangeIRR(Field1,Field2,Field3) as RangeIRR; LOAD * INLINE [ Field1 Field2 Field3 -10000 5000 6000 -2000 NULL 7000 -8000 'abc' 8000 -1800 11000 9000 -5000 5000 9000 -9000 4000 2000 ] (delimiter is ' '); </pre>	<p>The resulting table shows the returned values of RangeIRR for each of the records in the table.</p> <table border="1"> <thead> <tr> <th>RangeID</th> <th>RangeIRR</th> </tr> </thead> <tbody> <tr> <td>1</td> <td>0.0639</td> </tr> <tr> <td>2</td> <td>0.8708</td> </tr> <tr> <td>3</td> <td>-</td> </tr> <tr> <td>4</td> <td>5.8419</td> </tr> <tr> <td>5</td> <td>0.9318</td> </tr> <tr> <td>6</td> <td>-0.2566</td> </tr> </tbody> </table>	RangeID	RangeIRR	1	0.0639	2	0.8708	3	-	4	5.8419	5	0.9318	6	-0.2566
RangeID	RangeIRR														
1	0.0639														
2	0.8708														
3	-														
4	5.8419														
5	0.9318														
6	-0.2566														

### See also:

[Inter-record functions \(page 1273\)](#)

## RangeKurtosis

**RangeKurtosis()** returns the value that corresponds to the kurtosis of a range of numbers.

**Syntax:**

```
RangeKurtosis (first_expr[, Expression])
```

**Return data type:** numeric

**Arguments:**

The arguments of this function may contain inter-record functions which in themselves return a list of values.

Arguments

Argument	Description
first_expr	The expression or field containing the data to be measured.
Expression	Optional expressions or fields containing the range of data to be measured.

**Limitations:**

If no numeric value is found, NULL is returned.

**Examples and results:**

Function examples

Examples	Results
RangeKurtosis (1,2,4,7)	Returns -0.28571428571429

**See also:**

 [Kurtosis - chart function \(page 422\)](#)

## RangeMax

**RangeMax()** returns the highest numeric values found within the expression or field.

**Syntax:**

```
RangeMax (first_expr[, Expression])
```

**Return data type:** numeric

**Arguments:**

Arguments

Argument	Description
first_expr	The expression or field containing the data to be measured.
Expression	Optional expressions or fields containing the range of data to be measured.

### Limitations:

If no numeric value is found, NULL is returned.

### Examples and results:

Function examples

Examples	Results
RangeMax (1,2,4)	Returns 4
RangeMax (1,'xyz')	Returns 1
RangeMax (null( ), 'abc')	Returns NULL

### Example:

Add the example script to your app and run it. To see the result, add the fields listed in the results column to a sheet in your app.

```
RangeTab3:
LOAD recno() as RangeID, RangeMax(Field1,Field2,Field3) as MyRangeMax INLINE [
Field1, Field2, Field3
10,5,6
2,3,7
8,2,8
18,11,9
5,5,9
9,4,2
];
```

The resulting table shows the returned values of MyRangeMax for each of the records in the table.

Resulting table

RangeID	MyRangeMax
1	10
2	7
3	8
4	18
5	9
6	9

### Example with expression:

```
RangeMax (Above(MyField,0,3))
```

Returns the maximum value in the range of three values of **MyField** calculated on the current row and two rows above the current row. By specifying the third argument as 3, the **Above()** function returns three values, where there are sufficient rows above, which are taken as input to the **RangeMax()** function.

Data used in examples:



*Disable sorting of **MyField** to ensure that the example works as expected.*

Sample data

<b>MyField</b>	<b>RangeMax (Above(Sum(MyField),1,3))</b>
10	10
2	10
8	10
18	18
5	18
9	18

Data used in examples:

```
RangeTab:
LOAD * INLINE [
MyField
10
2
8
18
5
9
] ;
```

### RangeMaxString

**RangeMaxString()** returns the last value in the text sort order that it finds in the expression or field.

**Syntax:**

```
RangeMaxString(first_expr[, Expression])
```

**Return data type:** string

**Arguments:**

The arguments of this function may contain inter-record functions which in themselves return a list of values.

### Arguments

Argument	Description
first_expr	The expression or field containing the data to be measured.
Expression	Optional expressions or fields containing the range of data to be measured.

### Examples and results:

#### Function examples

Examples	Results
RangeMaxString (1,2,4)	Returns 4
RangeMaxString ('xyz','abc')	Returns 'xyz'
RangeMaxString (5,'abc')	Returns 'abc'
RangeMaxString (null( ))	Returns NULL

Example with expression:

```
RangeMaxString (Above(MaxString(MyField),0,3))
```

Returns the last (in text sort order) of the three results of the **MaxString(MyField)** function evaluated on the current row and two rows above the current row.

Data used in examples:



*Disable sorting of **MyField** to ensure that the example works as expected.*

#### Sample data

MyField	RangeMaxString(Above(MaxString(MyField),0,3))
10	10
abc	abc
8	abc
def	def
xyz	xyz
9	xyz

Data used in examples:

```
RangeTab:
LOAD * INLINE [
MyField
10
'abc'
8
'def'
```

```
'xyz'
9
] ;
```

**See also:**

[MaxString - chart function \(page 541\)](#)

## RangeMin

**RangeMin()** returns the lowest numeric values found within the expression or field.

**Syntax:**

```
RangeMin (first_expr[, Expression])
```

**Return data type:** numeric

**Arguments:**

## Arguments

Argument	Description
first_expr	The expression or field containing the data to be measured.
Expression	Optional expressions or fields containing the range of data to be measured.

**Limitations:**

If no numeric value is found, NULL is returned.

**Examples and results:**

## Function examples

Examples	Results
RangeMin (1,2,4)	Returns 1
RangeMin (1,'xyz')	Returns 1
RangeMin (null( ), 'abc')	Returns NULL

**Example:**

Add the example script to your app and run it. To see the result, add the fields listed in the results column to a sheet in your app.

```
RangeTab3:
LOAD recno() as RangeID, RangeMin(Field1,Field2,Field3) as MyRangeMin INLINE [
Field1, Field2, Field3
10,5,6
2,3,7
8,2,8
18,11,9
```

```
5,5,9  
9,4,2  
];
```

The resulting table shows the returned values of MyRangeMin for each of the records in the table.

Resulting table

RangeID	MyRangeMin
1	5
2	2
3	2
4	9
5	5
6	2

Example with expression:

```
RangeMin (Above(MyField,0,3))
```

Returns the minimum value in the range of three values of **MyField** calculated on the current row and two rows above the current row. By specifying the third argument as 3, the **Above()** function returns three values, where there are sufficient rows above, which are taken as input to the **RangeMin()** function.

Data used in examples:

Sample data

MyField	RangeMin(Above(MyField,0,3))
10	10
2	2
8	2
18	2
5	5
9	5


Data used in examples:

```
RangeTab:  
LOAD * INLINE [  
MyField  
10  
2  
8  
18  
5  
9
```



] ;

**See also:**

 [Min - chart function \(page 344\)](#)

## RangeMinString

**RangeMinString()** returns the first value in the text sort order that it finds in the expression or field.

**Syntax:**

```
RangeMinString (first_expr[, Expression])
```

**Return data type:** string

**Arguments:**

The arguments of this function may contain inter-record functions which in themselves return a list of values.

## Arguments

Argument	Description
first_expr	The expression or field containing the data to be measured.
Expression	Optional expressions or fields containing the range of data to be measured.

**Examples and results:**

## Function examples

Examples	Results
RangeMinString (1,2,4)	Returns 1
RangeMinString ('xyz', 'abc')	Returns 'abc'
RangeMinString (5, 'abc')	Returns 5
RangeMinString (null( ))	Returns NULL

Example with expression:

```
RangeMinString (Above(MinString(MyField),0,3))
```

Returns the first (in text sort order) of the three results of the **MinString(MyField)** function evaluated on the current row and two rows above the current row.

Data used in examples:



*Disable sorting of **MyField** to ensure that the example works as expected.*

Sample data

MyField	RangeMinString(Above(MinString(MyField),0,3))
10	10
abc	10
8	8
def	8
xyz	8
9	9

Data used in examples:

```
RangeTab:
LOAD * INLINE [
MyField
10
'abc'
8
'def'
'xyz'
9
] ;
```

### See also:

[MinString - chart function \(page 544\)](#)

## RangeMissingCount

**RangeMissingCount()** returns the number of non-numeric values (including NULL) in the expression or field.

### Syntax:

```
RangeMissingCount(first_expr[, Expression])
```

**Return data type:** integer

### Arguments:

The arguments of this function may contain inter-record functions which in themselves return a list of values.

Arguments

Argument	Description
first_expr	The expression or field containing the data to be counted.
Expression	Optional expressions or fields containing the range of data to be counted.

### Examples and results:

#### Function examples

Examples	Results
<code>RangeMissingCount (1,2,4)</code>	Returns 0
<code>RangeMissingCount (5,'abc')</code>	Returns 1
<code>RangeMissingCount (null( ))</code>	Returns 1

### Example with expression:

```
RangeMissingCount (Above(MinString(MyField),0,3))
```

Returns the number of non-numeric values in the three results of the **MinString(MyField)** function evaluated on the current row and two rows above the current row.



*Disable sorting of **MyField** to ensure that the example works as expected.*

#### Sample data


MyField	RangeMissingCount (Above(MinString(MyField),0,3))	Explanation
10	2	Returns 2 because there are no rows above this row so 2 of the 3 values are missing.
abc	2	Returns 2 because there is only 1 row above the current row and the current row is non-numeric ('abc').
8	1	Returns 1 because 1 of the 3 rows includes a non-numeric ('abc').
def	2	Returns 2 because 2 of the 3 rows include non-numeric values ('def' and 'abc').
xyz	2	Returns 2 because 2 of the 3 rows include non-numeric values (' xyz' and 'def').
9	2	Returns 2 because 2 of the 3 rows include non-numeric values (' xyz' and 'def').

### Data used in examples:

```
RangeTab:
LOAD * INLINE [
MyField
10
'abc'
8
```

```
'def'
'xyz'
9
] ;
```

**See also:**

 [MissingCount - chart function \(page 361\)](#)

## RangeMode

**RangeMode()** finds the most commonly occurring value (mode value) in the expression or field.

**Syntax:**

```
RangeMode (first_expr {, Expression})
```

**Return data type:** numeric

**Arguments:**

The arguments of this function may contain inter-record functions which in themselves return a list of values.

Arguments

Argument	Description
first_expr	The expression or field containing the data to be measured.
Expression	Optional expressions or fields containing the range of data to be measured.

**Limitations:**

If more than one value shares the highest frequency, NULL is returned.

**Examples and results:**

Function examples

Examples	Results
RangeMode (1,2,9,2,4)	Returns 2
RangeMode ('a',4,'a',4)	Returns NULL
RangeMode (null( ))	Returns NULL

**Example:**

Add the example script to your app and run it. To see the result, add the fields listed in the results column to a sheet in your app.

```
RangeTab3:
LOAD recno() as RangeID, RangeMode(Field1,Field2,Field3) as MyRangeMode INLINE [
```

```
Field1, Field2, Field3
10,5,6
2,3,7
8,2,8
18,11,9
5,5,9
9,4,2
];
```

The resulting table shows the returned values of **MyRangeMode** for each of the records in the table.

Results table

RangeID	MyRangMode
1	-
2	-
3	8
4	-
5	5
6	-

Example with expression:

```
RangeMode (Above(MyField,0,3))
```

Returns the most commonly occurring value in the three results of **MyField** evaluated on the current row and two rows above the current row. By specifying the third argument as 3, the **Above()** function returns three values, where there are sufficient rows above, which are taken as input to the **RangeMode()** function.

Data used in example:

```
RangeTab:
LOAD * INLINE [
MyField
10
2
8
18
5
9
] ;
```




*Disable sorting of **MyField** to ensure that the example works as expected.*

Sample data

MyField	RangeMode(Above(MyField,0,3))
10	Returns 10 because there are no rows above so the single value is the most commonly occurring.
2	-
8	-
18	-
5	-
9	-

**See also:**

 [Mode - chart function \(page 347\)](#)

### RangeNPV

**RangeNPV()** returns the net present value of an investment based on a discount rate and a series of future periodic payments (negative values) and incomes (positive values). The result has a default number format of **money**.

For cash flows that are not necessarily periodic, see *RangeXNPV (page 1371)*.

**Syntax:**

```
RangeNPV (discount_rate, value[,value][, Expression])
```

**Return data type:** numeric

Arguments


Argument	Description
discount_rate	The interest rate per period.
value	A payment or income occurring at the end of each period. Each value may be a single value or a range of values as returned by an inter-record function with a third optional parameter.
Expression	Optional expressions or fields containing the range of data to be measured.

**Limitations:**

Text values, NULL values and missing values are disregarded.

Examples	Results														
<code>RangeNPV(0.1, -10000, 3000, 4200, 6800)</code>	Returns 1188.44														
<p>Add the example script to your app and run it. To see the result, add the fields listed in the results column to a sheet in your app.</p> <pre> RangeTab3: LOAD *, recno() as RangeID, RangeNPV(Field1,Field2,Field3) as RangeNPV; LOAD * INLINE [ Field1 Field2 Field3 10 5 -6000 2 NULL 7000 8 'abc' 8000 18 11 9000 5 5 9000 9 4 2000 ] (delimiter is ' '); </pre>	<p>The resulting table shows the returned values of RangeNPV for each of the records in the table.</p> <table border="1"> <thead> <tr> <th>RangeID</th> <th>RangeNPV</th> </tr> </thead> <tbody> <tr> <td>1</td> <td>\$-49.13</td> </tr> <tr> <td>2</td> <td>\$777.78</td> </tr> <tr> <td>3</td> <td>\$98.77</td> </tr> <tr> <td>4</td> <td>\$25.51</td> </tr> <tr> <td>5</td> <td>\$250.83</td> </tr> <tr> <td>6</td> <td>\$20.40</td> </tr> </tbody> </table>	RangeID	RangeNPV	1	\$-49.13	2	\$777.78	3	\$98.77	4	\$25.51	5	\$250.83	6	\$20.40
RangeID	RangeNPV														
1	\$-49.13														
2	\$777.78														
3	\$98.77														
4	\$25.51														
5	\$250.83														
6	\$20.40														

**See also:**

 [Inter-record functions \(page 1273\)](#)

## RangeNullCount

**RangeNullCount()** finds the number of NULL values in the expression or field.

**Syntax:**

```
RangeNullCount (first_expr [, Expression])
```

**Return data type:** integer

**Arguments:**

The arguments of this function may contain inter-record functions which in themselves return a list of values.

Arguments

Argument	Description
first_expr	The expression or field containing the data to be measured.
Expression	Optional expressions or fields containing the range of data to be measured.

**Examples and results:**

## Function examples

Examples	Results
<code>RangeNullCount (1,2,4)</code>	Returns 0
<code>RangeNullCount (5, 'abc')</code>	Returns 0
<code>RangeNullCount (null( ), null( ))</code>	Returns 2

## Example with expression:

```
RangeNullCount (Above(Sum(MyField),0,3))
```

Returns the number of NULL values in the three results of the **Sum(MyField)** function evaluated on the current row and two rows above the current row.



*Copying **MyField** in example below will not result in NULL value.*

## Sample data

MyField	RangeNullCount(Above(Sum(MyField),0,3))
10	Returns 2 because there are no rows above this row so 2 of the 3 values are missing (=NULL).
'abc'	Returns 1 because there is only one row above the current row, so one of the three values is missing (=NULL).
8	Returns 0 because none of the three rows is a NULL value.

## Data used in examples:

```
RangeTab:
LOAD * INLINE [
MyField
10
'abc'
8
] ;
```

**See also:**

[NullCount - chart function \(page 363\)](#)

## RangeNumericCount

**RangeNumericCount()** finds the number of numeric values in an expression or field.

**Syntax:**

```
RangeNumericCount(first_expr[, Expression])
```



**Return data type:** integer

**Arguments:**

The arguments of this function may contain inter-record functions which in themselves return a list of values.

Arguments

Argument	Description
first_expr	The expression or field containing the data to be measured.
Expression	Optional expressions or fields containing the range of data to be measured.

**Examples and results:**

Function examples

Examples	Results
RangeNumericCount (1,2,4)	Returns 3
RangeNumericCount (5,'abc')	Returns 1
RangeNumericCount (null( ))	Returns 0

Example with expression:

RangeNumericCount (Above(MaxString(MyField),0,3))

Returns the number of numeric values in the three results of the **MaxString(MyField)** function evaluated on the current row and two rows above the current row.



*Disable sorting of **MyField** to ensure that the example works as expected.*

Sample data


MyField	RangeNumericCount(Above(MaxString(MyField),0,3))
10	1
abc	1
8	2
def	1
xyz	1
9	1

Data used in examples:

RangeTab:

```
LOAD * INLINE [
MyField
10
'abc'
8
def
xyz
9
] ;
```

**See also:**

 [NumericCount - chart function \(page 366\)](#)

## RangeOnly

**RangeOnly()** is a dual function that returns a value if the expression evaluates to one unique value. If this is not the case then **NULL** is returned.

**Syntax:**

```
RangeOnly (first_expr[, Expression])
```

**Return data type:** dual

**Arguments:**


The arguments of this function may contain inter-record functions which in themselves return a list of values.

Argument	Description
first_expr	The expression or field containing the data to be measured.
Expression	Optional expressions or fields containing the range of data to be measured.

**Examples and results:**

Examples	Results
RangeOnly (1,2,4)	Returns NULL
RangeOnly (5, 'abc')	Returns NULL
RangeOnly (null( ), 'abc')	Returns 'abc'
RangeOnly(10,10,10)	Returns 10

**See also:**

 [Only - chart function \(page 350\)](#)

## RangeSkew

**RangeSkew()** returns the value corresponding to the skewness of a range of numbers.

### Syntax:

```
RangeSkew(first_expr[, Expression])
```

**Return data type:** numeric

### Arguments:

The arguments of this function may contain inter-record functions which in themselves return a list of values.

Arguments

Argument	Description
first_expr	The expression or field containing the data to be measured.
Expression	Optional expressions or fields containing the range of data to be measured.

### Limitations:

If no numeric value is found, NULL is returned.

### Examples and results:

Function examples

Examples	Results
rangeskew (1,2,4)	Returns 0.93521952958283
rangeskew (above (SalesValue,0,3))	Returns a sliding skewness of the range of three values returned from the above() function calculated on the current row and the two rows above the current row.

Data used in example:

Sample data

CustID	RangeSkew(Above(SalesValue,0,3))
1-20	-, -, 0.5676, 0.8455, 1.0127, -0.8741, 1.7243, -1.7186, 1.5518, 1.4332, 0, 1.1066, 1.3458, 1.5636, 1.5439, 0.6952, -0.3766


SalesTable:

```
LOAD recno() as CustID, * inline [
SalesValue
101
163
126
```

139  
167  
86  
83  
22  
32  
70  
108  
124  
176  
113  
95  
32  
42  
92  
61  
21  
] ;

---

**See also:**

 [Skew - chart function \(page 453\)](#)

### RangeStdev

**RangeStdev()** finds the standard deviation of a range of numbers.

**Syntax:**

```
RangeStdev(first_expr[, Expression])
```

**Return data type:** numeric

**Arguments:**

The arguments of this function may contain inter-record functions which in themselves return a list of values.

#### Arguments

Argument	Description
first_expr	The expression or field containing the data to be measured.
Expression	Optional expressions or fields containing the range of data to be measured.

**Limitations:**

If no numeric value is found, NULL is returned.

**Examples and results:**

Function examples

Examples	Results
RangeStdev (1,2,4)	Returns 1.5275252316519
RangeStdev (null ( ))	Returns NULL
RangeStdev (above (SalesValue),0,3))	Returns a sliding standard of the range of three values returned from the above() function calculated on the current row and the two rows above the current row.

Data used in example:


Sample data

CustID	RangeStdev(SalesValue, 0,3)
1-20	-,43.841, 34.192, 18.771, 20.953, 41.138, 47.655, 36.116, 32.716, 25.325, 38,000, 27.737, 35.553, 33.650, 42.532, 33.858, 32.146, 25.239, 35.595

SalesTable:

```
LOAD recno() as CustID, * inline [
SalesValue
101
163
126
139
167
86
83
22
32
70
108
124
176
113
95
32
42
92
61
21
] ;
```

**See also:**

 [Stdev - chart function \(page 456\)](#)

## RangeSum

**RangeSum()** returns the sum of a range of values. All non-numeric values are treated as 0.

**Syntax:**

```
RangeSum (first_expr[, Expression])
```

**Return data type:** numeric

**Arguments:**

The arguments of this function may contain inter-record functions which in themselves return a list of values.

Arguments

Argument	Description
first_expr	The expression or field containing the data to be measured.
Expression	Optional expressions or fields containing the range of data to be measured.

**Limitations:**

The **RangeSum** function treats all non-numeric values as 0.

**Examples and results:**

Examples

Examples	Results
RangeSum (1,2,4)	Returns 7
RangeSum (5, 'abc')	Returns 5
RangeSum (null( ))	Returns 0

**Example:**

Add the example script to your app and run it. To see the result, add the fields listed in the results column to a sheet in your app.

```
RangeTab3:
LOAD recno() as RangeID, Rangesum(Field1,Field2,Field3) as MyRangeSum INLINE [
Field1, Field2, Field3
10,5,6
2,3,7
8,2,8
18,11,9
5,5,9
9,4,2
];
```

The resulting table shows the returned values of MyRangeSum for each of the records in the table.

Resulting table

RangeID	MyRangeSum
1	21
2	12
3	18
4	38
5	19
6	15

Example with expression:

```
RangeSum (Above(MyField,0,3))
```

Returns the sum of the three values of **MyField**: from the current row and two rows above the current row. By specifying the third argument as 3, the **Above()** function returns three values, where there are sufficient rows above, which are taken as input to the **RangeSum()** function.

Data used in examples:



*Disable sorting of **MyField** to ensure that the example works as expected.*



Sample data

MyField	RangeSum(Above(MyField,0,3))
10	10
2	12
8	20
18	28
5	31
9	32

Data used in examples:

```
RangeTab:
LOAD * INLINE [
MyField
10
2
8
18
5
9
] ;
```

**See also:**

-  [Sum - chart function \(page 353\)](#)
-  [Above - chart function \(page 1277\)](#)

## RangeTextCount

**RangeTextCount()** returns the number of text values in an expression or field.

**Syntax:**

```
RangeTextCount (first_expr[, Expression])
```

**Return data type:** integer

**Arguments:**

The arguments of this function may contain inter-record functions which in themselves return a list of values.

## Argument

Argument	Description
first_expr	The expression or field containing the data to be measured.
Expression	Optional expressions or fields containing the range of data to be measured.

**Examples and results:**

## Function examples

Examples	Results
RangeTextCount (1,2,4)	Returns 0
RangeTextCount (5,'abc')	Returns 1
RangeTextCount (null( ))	Returns 0

Example with expression:

```
RangeTextCount (Above(MaxString(MyField),0,3))
```

Returns the number of text values within the three results of the **MaxString(MyField)** function evaluated over the current row and two rows above the current row.

Data used in examples:



Disable sorting of **MyField** to ensure that the example works as expected.



Example data

MyField	MaxString(MyField)	RangeTextCount(Above(Sum(MyField),0,3))
10	10	0
abc	abc	1
8	8	1
def	def	2
xyz	xyz	2
9	9	2

Data used in examples:

```
RangeTab:
LOAD * INLINE [
MyField
10
'abc'
8
null()
'xyz'
9
] ;
```

#### See also:

 [TextCount - chart function \(page 370\)](#)

## RangeXIRR

**RangeXIRR()** returns the internal rate of return (yearly) for a schedule of cash flows that is not necessarily periodic. To calculate the internal rate of return for a series of periodic cash flows, use the **RangeIRR** function.

Qlik's XIRR functionality (**XIRR()** and **RangeXIRR()** functions) uses the following equation, solving for the rate value, to determine the correct XIRR value:

$$XNPV(\text{Rate}, \text{pmt}, \text{date}) = 0$$

The equation is solved using a simplified version of the Newton method.

#### Syntax:

```
RangeXIRR(value, date{, value, date})
```

**Return data type:** numeric

### Arguments

Argument	Description
value	A cash flow or a series of cash flows that correspond to a schedule of payments in dates. The series of values must contain at least one positive and one negative value.
date	A payment date or a schedule of payment dates that corresponds to the cash flow payments.

When working with this function, the following limitations apply:

- Text values, NULL values and missing values are disregarded.
- All payments are discounted based on a 365-day year.
- This function requires at least one valid negative and at least one valid positive payment (with corresponding valid dates). If these payments are not provided, a NULL value is returned.

The following topics might help you work with this function:

- *RangeXNPV (page 1371)*: Use this function calculate the net present value for a schedule of cash flows that is not necessarily periodic.
- *XIRR (page 384)*: The **XIRR()** function calculates the aggregated internal rate of return (yearly) for a schedule of cash flows (that is not necessarily periodic).



Across different versions of Qlik Sense Client-Managed, there are variations in the underlying algorithm used by this function. For more information about recent updates to the algorithm, see support article [XIRR function Fix and Update](#).

### Examples and results:

#### Examples and results

Examples	Results
RangeXIRR(-2500, '2008-01-01', 2750, '2008-09-01')	Returns 0.1532

### See also:

- [RangeIRR \(page 1345\)](#)
- [RangeXNPV \(page 1371\)](#)
- [XIRR \(page 384\)](#)
- [XIRR function Fix and Update](#)

## RangeXNPV

**RangeXNPV()** returns the net present value for a schedule of cash flows (not necessarily periodic) represented by paired numbers in the expressions given by **pmt** and **date**. All payments are discounted based on a 365-day year.

### Syntax:

```
RangeXNPV(discount_rate, value, date{, value, date})
```

**Return data type:** numeric

### Arguments

Argument	Description
discount_rate	<b>discount_rate</b> is the yearly rate that the payments should be discounted by.
value	A cash flow or a series of cash flows that corresponds to a schedule of payments in dates. Each value may be a single value or a range of values as returned by an inter-record function with a third optional parameter. The series of values must contain at least one positive and one negative value.
date	A payment date or a schedule of payment dates that corresponds to the cash flow payments.

When working with this function, the following limitations apply:

- Text values, NULL values and missing values are disregarded.
- All payments are discounted based on a 365-day year.

## Example - script

Load script and results

### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- Financial data contained in a table called RangeTab3.
- The use of the **RangeXNPV()** function to compute net present value.

### Load script

```
RangeTab3:
LOAD *,
recno() as RangeID,
RangeXNPV(DiscountRate,Value1,Date1,Value2,Date2) as RangeXNPV;
LOAD * INLINE [
```

```
DiscountRate|Value1|Date1|Value2|Date2
0.1|-100|2021-01-01|100|2022-01-01|
0.1|-100|2021-01-01|110|2022-01-01|
0.1|-100|2021-01-01|125|2022-01-01|
] (delimiter is '|');
```

### Results

Load the data and open a sheet. Create a new table and add these fields as dimensions:

- RangeID
- RangeXNPV

Results table

RangeID	RangeXNPV
1	-\$9.09
2	-\$0.00
3	\$13.64

### Example - chart expression

Load script and chart expression

#### Overview

Open the Data load editor and add the load script below to a new tab.

The load script contains:

- Financial data contained in a table called RangeTab3.
- The use of the **RangeXNPV()** function to compute net present value.

#### Load script

```
RangeTab3:
LOAD *,
recno() as RangeID,
RangeXNPV(DiscountRate,Value1,Date1,Value2,Date2) as RangeXNPV;
LOAD * INLINE [
DiscountRate|Value1|Date1|Value2|Date2
0.1|-100|2021-01-01|100|2022-01-01|
0.1|-100|2021-01-01|110|2022-01-01|
0.1|-100|2021-01-01|125|2022-01-01|
] (delimiter is '|');
```

**Results****Do the following:**


Load the data and open a sheet. Create a new table and add the following calculation as a measure.

```
=RangeXNPV(0.1, -2500, '2008-01-01', 2750, '2008-09-01')
```

Results table

<b>=XIRR(Payments, Date)</b>
\$80.25

**See also:**

 [XNPV \(page 390\)](#)

## 8.22 Relational functions

This is a group of functions that calculate properties of individual dimensional values in a chart, using already aggregated numbers.

The functions are relational in the sense that the function output depends not only on the value of the data point itself, but also on the value's relation to other data points. For example, a rank cannot be calculated without a comparison with other dimensional values.

These functions can only be used in chart expressions. They cannot be used in the load script.

A dimension is needed in the chart, since this defines the other data points needed for the comparison. Consequently, a relational function is not meaningful in a dimensionless chart (for example, a KPI object).

### Ranking functions



*Suppression of zero values is automatically disabled when these functions are used. NULL values are disregarded.*

Rank

**Rank()** evaluates the rows of the chart in the expression, and for each row, displays the relative position of the value of the dimension evaluated in the expression. When evaluating the expression, the function compares the result with the result of the other rows containing the current column segment and returns the ranking of the current row within the segment.

```
Rank - chart function([TOTAL [<fld {, fld}>]] expr[, mode[, fmt]])
```

HRank

**HRank()** evaluates the expression, and compares the result with the result of the other columns containing the current row segment of a pivot table. The function then returns the ranking of the current column within the segment.

```
HRank - chart function([TOTAL] expr[, mode[, fmt]])
```

### Clustering functions

KMeans2D

The property group **Site license** contains properties related to the license for the Qlik Sense system. All fields are mandatory and must not be empty.

Site licence properties

Property name	Description
<b>Owner name</b>	The user name of the Qlik Sense product owner.
<b>Owner organization</b>	The name of the organization that the Qlik Sense product owner is a member of.
<b>Serial number</b>	The serial number assigned to the Qlik Sense software.
<b>Control number</b>	The control number assigned to the Qlik Sense software.
<b>LEF access</b>	The License Enabler File (LEF) assigned to the Qlik Sense software.

**KMeans2D()** evaluates the rows of the chart by applying k-means clustering, and for each chart row displays the cluster id of the cluster this data point has been assigned to. The columns that are used by the clustering algorithm are determined by the parameters `coordinate_1`, and `coordinate_2`, respectively. These are both aggregations. The number of clusters that are created is determined by the `num_clusters` parameter. Data can be optionally normalized by the `norm` parameter.

```
KMeans2D - chart function(num_clusters, coordinate_1, coordinate_2 [, norm])
```

KMeansND

**KMeansND()** evaluates the rows of the chart by applying k-means clustering, and for each chart row displays the cluster id of the cluster this data point has been assigned to. The columns that are used by the clustering algorithm are determined by the parameters `coordinate_1`, and `coordinate_2`, etc., up to n columns. These are all aggregations. The number of clusters that are created is determined by the `num_clusters` parameter.

```
KMeansND - chart function(num_clusters, num_iter, coordinate_1, coordinate_2 [,coordinate_3 [, ...]])
```

KMeansCentroid2D

**KMeansCentroid2D()** evaluates the rows of the chart by applying k-means clustering, and for each chart row displays the desired coordinate of the cluster this data point has been assigned to. The columns that are used by the clustering algorithm are determined by the parameters `coordinate_1`, and `coordinate_2`, respectively. These are both aggregations. The number of clusters that are

created is determined by the `num_clusters` parameter. Data can be optionally normalized by the `norm` parameter.

```
KMeansCentroid2D - chart function(num_clusters, coordinate_no, coordinate_1, coordinate_2 [, norm])
```

**KMeansCentroidND**

**KMeansCentroidND()** evaluates the rows of the chart by applying k-means clustering, and for each chart row displays the desired coordinate of the cluster this data point has been assigned to. The columns that are used by the clustering algorithm are determined by the parameters `coordinate_1`, `coordinate_2`, etc., up to `n` columns. These are all aggregations. The number of clusters that are created is determined by the `num_clusters` parameter.

```
KMeansCentroidND - chart function(num_clusters, num_iter, coordinate_no, coordinate_1, coordinate_2 [,coordinate_3 [, ...]])
```

### Time series decomposition functions

**STL\_Trend**

**STL\_Trend** is a time series decomposition function. Along with **STL\_Seasonal** and **STL\_Residual**, this function is used to decompose a time series into seasonal, trend, and residual components. In the context of the STL algorithm, time series decomposition is used to identify both a recurring seasonal pattern and a general trend, given an input metric and other parameters. The **STL\_Trend** function will identify a general trend, independent of seasonal patterns or cycles, from time series data.

```
STL_Trend - chart function(target_measure, period_int [,seasonal_smoother [,trend_smoother]])
```

**STL\_Seasonal**

**STL\_Seasonal** is a time series decomposition function. Along with **STL\_Trend** and **STL\_Residual**, this function is used to decompose a time series into seasonal, trend, and residual components. In the context of the STL algorithm, time series decomposition is used to identify both a recurring seasonal pattern and a general trend, given an input metric and other parameters. The **STL\_Seasonal** function can identify a seasonal pattern within a time series, separating this from the general trend displayed by the data.

```
STL_Seasonal - chart function(target_measure, period_int [,seasonal_smoother [,trend_smoother]])
```

**STL\_Residual**

**STL\_Residual** is a time series decomposition function. Along with **STL\_Seasonal** and **STL\_Trend**, this function is used to decompose a time series into seasonal, trend, and residual components. In the context of the STL algorithm, time series decomposition is used to identify both a recurring seasonal pattern and a general trend, given an input metric and other parameters. In performing this operation, part of the variation in the input metric will neither fit within the seasonal nor the trend component, and will be defined as the residual component. The **STL\_Residual** chart function captures this portion of the calculation.

**STL\_Residual - chart function**(target\_measure, period\_int [,seasonal\_smoother [,trend\_smoother]])

### Rank - chart function

**Rank()** evaluates the rows of the chart in the expression, and for each row, displays the relative position of the value of the dimension evaluated in the expression. When evaluating the expression, the function compares the result with the result of the other rows containing the current column segment and returns the ranking of the current row within the segment.

Rank	Product Group	Region	Sales
			194852674.81
1	Alcoholic Beverages	Japan	1142137
2	Alcoholic Beverages	USA	713322.4
3	Alcoholic Beverages	Nordic	177377.82
4	Alcoholic Beverages	UK	151711.81
5	Alcoholic Beverages	Spain	52544.88
6	Alcoholic Beverages	Germany	36235.98
1	Baked Goods	USA	128998.04
2	Baked Goods	UK	108020.84
3	Baked Goods	Japan	83352.00
4	Baked Goods	Nordic	69138.31
5	Baked Goods	Germany	54671.04
6	Baked Goods	Spain	22792.64
1	Baking Goods	UK	4513028.52
2	Baking Goods	USA	1178465.7
3	Baking Goods	Japan	594918.88
4	Baking Goods	Nordic	199728.35
5	Baking Goods	Germany	127127.80
6	Baking Goods	Spain	118308.58
1	Beverages	USA	2526718.15
2	Beverages	UK	2136698.97
3	Beverages	Japan	785487.64
4	Beverages	Nordic	368966.76
5	Beverages	Spain	286216.7
6	Beverages	Germany	223035.31
1	Breakfast Foods	UK	453951.21
2	Breakfast Foods	USA	143791.85
3	Breakfast Foods	Japan	36264.1
4	Breakfast Foods	Nordic	21278.12
5	Breakfast Foods	Germany	15978.15
6	Breakfast Foods	Spain	8997.63
1	Canned Products	USA	15548186.8
2	Canned Products	UK	1683884.48
3	Canned Products	Japan	1350468.37
4	Canned Products	Nordic	1265241.85
5	Canned Products	Germany	439338.98
6	Canned Products	Spain	387552.75
1	Dairy	USA	15219223.2

### Column segments

	Region	Country	Population	Rank(Population)
Column segment #1	Americas	Mexico	128,932,753	2
	Americas	Canada	37,742,154	3
	Americas	United States of America	331,002,651	1
Column segment #2	Europe	Sweden	10,099,265	4
	Europe	United Kingdom	67,886,011	2
	Europe	France	65,273,511	3
	Europe	Germany	83,783,942	1

For charts other than tables, the current column segment is defined as it appears in the charts straight table equivalent.

### Syntax:

**Rank** ([TOTAL] expr [, mode [, fmt]])



**Return data type:** dual

**Arguments:**

Arguments

Argument	Description
expr	The expression or field containing the data to be measured.
mode	Specifies the number representation of the function result.
fmt	Specifies the text representation of the function result.
TOTAL	If the chart is one-dimensional, or if the expression is preceded by the <b>TOTAL</b> qualifier, the function is evaluated along the entire column. If the table or table equivalent has multiple vertical dimensions, the current column segment will include only rows with the same values as the current row in all dimension columns except for the column showing the last dimension in the inter-field sort order.

The ranking is returned as a dual value, which in the case when each row has a unique ranking, is an integer between 1 and the number of rows in the current column segment.

In the case where several rows share the same ranking, the text and number representation can be controlled with the **mode** and **fmt** parameters.

**mode**

The second argument, **mode**, can take the following values:

**mode** examples

Value	Description
0 (default)	<p>If all ranks within the sharing group fall on the low side of the middle value of the entire ranking, all rows get the lowest rank within the sharing group.</p> <p>If all ranks within the sharing group fall on the high side of the middle value of the entire ranking, all rows get the highest rank within the sharing group.</p> <p>If ranks within the sharing group span over the middle value of the entire ranking, all rows get the value corresponding to the average of the top and bottom ranking in the entire column segment.</p>
1	Lowest rank on all rows.
2	Average rank on all rows.
3	Highest rank on all rows.
4	Lowest rank on first row, then incremented by one for each row.

### fmt

The third argument, **fmt**, can take the following values:

#### fmtexamples

Value	Description
0 (default)	Low value - high value on all rows (for example 3 - 4).
1	Low value on all rows.
2	Low value on first row, blank on the following rows.

The order of rows for **mode** 4 and **fmt** 2 is determined by the sort order of the chart dimensions.

### Examples and results:

Create two visualizations from the dimensions Product and Sales and another from Product and UnitSales. Add measures as shown in the following table.

#### Rank examples

Examples	Results
Example 1. Create a table with the dimensions customer and sales and the measure Rank(sales)	<p>The result depends on the sort order of the dimensions. If the table is sorted on Customer, the table lists all the values of Sales for Astrida, then Betacab, and so on. The results for Rank(Sales) will show 10 for the Sales value 12, 9 for the Sales value 13, and so on, with the rank value of 1 returned for the Sales value 78. The next column segment begins with Betacab, for which the first value of Sales in the segment is 12. The rank value of Rank(Sales) for this is given as 11.</p> <p>If the table is sorted on Sales, the column segments consist of the values of Sales and the corresponding Customer. Because there are two Sales values of 12 (for Astrida and Betacab), the value of Rank(Sales) for that column segment is 1-2, for each value of Customer. This is because there are two values of Customer for the Sales value 12. If there had been 4 values, the result would be 1-4, for all rows. This shows what the result looks like for the default value (0) of the argument fmt.</p>
Example 2. Replace the dimension Customer with Product and add the measure Rank(sales, 1, 2)	This returns 1 on the first row on each column segment and leaves all other rows blank, because arguments <b>mode</b> and <b>fmt</b> are set to 1 and 2 respectively.

Results for example 1, with table sorted on Customer:

Results table

Customer	Sales	Rank(Sales)
Astrida	12	10
Astrida	13	9
Astrida	20	8
Astrida	22	7
Astrida	45	6
Astrida	46	5
Astrida	60	4
Astrida	65	3
Astrida	70	2
Astrida	78	1
Betcab	12	11

Results for example 1, with table sorted on Sales:

Results table

Customer	Sales	Rank(Sales)
Astrida	12	1-2
Betacab	12	1-2
Astrida	13	1
Betacab	15	1
Astrida	20	1
Astrida	22	1-2
Betacab	22	1-2
Betacab	24	1-2
Canutility	24	1-2


Data used in examples:

```
ProductData:
Load * inline [
Customer|Product|UnitsSales|UnitPrice
Astrida|AA|4|16
Astrida|AA|10|15
Astrida|BB|9|9
Betacab|BB|5|10
Betacab|CC|2|20
Betacab|DD|0|25
```

```
Canutility|AA|8|15
Canutility|CC|0|19
] (delimiter is '|');
```

```
Sales2013:
crosstable (Month, Sales) LOAD * inline [
Customer|Jan|Feb|Mar|Apr|May|Jun|Jul|Aug|Sep|Oct|Nov|Dec
Astrida|46|60|70|13|78|20|45|65|78|12|78|22
Betacab|65|56|22|79|12|56|45|24|32|78|55|15
Canutility|77|68|34|91|24|68|57|36|44|90|67|27
Divadip|57|36|44|90|67|27|57|68|47|90|80|94
] (delimiter is '|');
```

### See also:

 [Sum - chart function \(page 353\)](#)

## HRank - chart function

**HRank()** evaluates the expression, and compares the result with the result of the other columns containing the current row segment of a pivot table. The function then returns the ranking of the current column within the segment.

### Syntax:

```
HRank ( [ TOTAL ] expr [ , mode [ , fmt ] ] )
```

**Return data type:** dual



*This function only works in pivot tables. In all other chart types it returns NULL.*

### Arguments:

#### Arguments

Argument	Description
expr	The expression or field containing the data to be measured.
mode	Specifies the number representation of the function result.
fmt	Specifies the text representation of the function result.
TOTAL	If the chart is one-dimensional, or if the expression is preceded by the <b>TOTAL</b> qualifier, the function is evaluated along the entire column. If the table or table equivalent has multiple vertical dimensions, the current column segment will include only rows with the same values as the current row in all dimension columns except for the column showing the last dimension in the inter-field sort order.

## 8 Script and chart functions

---

If the pivot table is one-dimensional or if the expression is preceded by the **total** qualifier, the current row segment is always equal to the entire row. If the pivot table has multiple horizontal dimensions, the current row segment will include only columns with the same values as the current column in all dimension rows except for the row showing the last horizontal dimension of the inter-field sort order.

The ranking is returned as a dual value, which in the case when each column has a unique ranking will be an integer between 1 and the number of columns in the current row segment.

In the case where several columns share the same ranking, the text and number representation can be controlled with the **mode** and **format** arguments.

The second argument, **mode**, specifies the number representation of the function result:

### mode examples

Value	Description
0 (default)	If all ranks within the sharing group fall on the low side of the middle value of the entire ranking, all columns get the lowest rank within the sharing group.  If all ranks within the sharing group fall on the high side of the middle value of the entire ranking, all columns get the highest rank within the sharing group.  If ranks within the sharing group span over the middle value of the entire ranking, all rows get the value corresponding to the average of the top and bottom ranking in the entire column segment.
1	Lowest rank on all columns in the group.
2	Average rank on all columns in the group.
3	Highest rank on all columns in the group.
4	Lowest rank on first column, then incremented by one for each column in the group.

The third argument, **format**, specifies the text representation of the function result:

### format examples

Value	Description
0 (default)	Low value&' - '&high value on all columns in the group (for example 3 - 4).
1	Low value on all columns in the group.
2	Low value on first column, blank on the following columns in the group.

The order of columns for **mode 4** and **format 2** is determined by the sort order of the chart dimensions.

### Examples:

```
HRank( sum( Sales ) )  
HRank( sum( Sales ), 2 )  
HRank( sum( Sales ), 0, 1 )
```

## Optimizing with k-means: A real-world example

The following example illustrates a real world use case where the KMeans clustering and Centroid functions are applied to a dataset. The KMeans function segregates data points into clusters that share similarities. The clusters become more compact and differentiated as the KMeans algorithm is applied over a configurable number of iterations.

KMeans is used across many fields in a wide variety of use cases; some examples of clustering use cases include customer segmentation, fraud detection, predicting account attrition, targeting client incentives, cybercrime identification, and delivery route optimization. The KMeans clustering algorithm is increasingly being used where enterprises are trying to infer patterns and optimize service offerings.

### Qlik Sense KMeans and Centroid functions

Qlik Sense provides two KMeans functions that group data points into clusters based on similarity. See *KMeans2D - chart function (page 1391)* and *KMeansND - chart function (page 1406)*. The **KMeans2D** function accepts two dimensions and works well for visualizing results through a **scatter plot** chart. The **KMeansND** function accepts more than two dimensions. As it is easy to conceptualize a 2D outcome on standard charts, the following demonstration applies KMeans on a **scatter plot** chart using two dimensions. KMeans clustering can be visualized through coloring by expression; or by dimension as described in this example.

Qlik Sense centroid functions determine the arithmetic mean position of all the data points in the cluster and identify a central point, or centroid for that cluster. For each chart row (or record), the centroid function displays the coordinate of the cluster this data point has been assigned to. See *KMeansCentroid2D - chart function (page 1421)* and *KMeansCentroidND - chart function (page 1422)*.

### Use case and example overview

The following example stages through a simulated real world scenario. A textile company in New York state, USA, must decrease expenses by minimizing delivery costs. One way to do that is to relocate warehouses closer to their distributors. The company employs 118 distributors across the state of New York. The following demonstration simulates how an operations manager could segment distributors into five clustered geographies using the KMeans function and then identify five optimal warehouse locations central to those clusters using the centroid function. The objective is to discover mapping coordinates that can be used to identify five central warehouse locations.

### The dataset

The dataset is based on randomly generated names and addresses in New York state with real latitude and longitude coordinates. The dataset contains the following ten columns: `id`, `first_name`, `last_name`, `telephone`, `address`, `city`, `state`, `zip`, `latitude`, `longitude`. The dataset is available below as a file you can download locally and then upload to Qlik Sense or inline for data load editor. The app being created is named *Distributors KMeans and Centroid* and the first sheet in the app is named *Distribution cluster analysis*.

Select the following link to download the sample data file: [DistributorData.csv](#)

*Distributor dataset: Inline load for data load editor in Qlik Sense (page 1389)*

Title: DistributorData

Total number of records: 118

### Applying the KMeans2D function


In this example, configuration of a **scatter plot** chart is demonstrated using the *DistributorData* dataset, the **KMeans2D** function is applied, and the chart is colored by dimension.

Note that Qlik Sense KMeans functions support auto-clustering using a method called depth difference (DeD). When a user sets 0 for the number of clusters, the optimal number of clusters for that dataset is determined. For this example however, a variable is created for the **num\_clusters** argument (refer to *KMeans2D - chart function (page 1391)* for syntax). Therefore, the desired number of clusters (k=5) is specified by a variable.

1. A **scatter plot** chart is dragged onto the sheet and named *Distributors (by dimension)*.
2. A **variable** is created to specify the number of clusters. The **variable** is named *vDistClusters*. For the variable **Definition**, 5 is entered.
3. **Data** configuration for the chart:
  - a. Under **Dimensions**, *id* field is selected for **Bubble**. *Cluster id* is entered for the **Label**.
  - b. Under **Measures**, *Avg([latitude])* is the expression for **X-axis**.
  - c. Under **Measures**, *Avg([longitude])* is the expression for **Y-axis**.
4. **Appearance** configuration:
  - a. Under **Colors and legend**, **Custom** is chosen for **Colors**.
  - b. **By dimension** is selected for coloring the chart.
  - c. The following expression is entered: `=pick(aggr(KMeans2D(vDistClusters,only(latitude),only(longitude)),id)+1, 'Cluster 1', 'Cluster 2', 'Cluster 3', 'Cluster 4', 'Cluster 5')`
  - d. The checkbox for **Persistent colors** is selected.


Scatter plot before KMeans coloring by dimension is applied

Distribution cluster analysis



Scatter plot after KMeans coloring by dimension is applied

Distribution cluster analysis



### Adding a **table**: *Distributors*

It can be helpful to have a table handy for quick access to relevant data. The **scatter plot** chart shows *ids* though a table with corresponding distributor names is added for reference.

1. A **table** named *Distributors* is dragged onto the sheet with the following **Columns** (Dimensions) added: *id*, *first\_name*, and *last\_name*.



Table: Distributor names

Distributors		
id	first_name	last_name
1	Kaiya	Snow
2	Dean	Roy
3	Eden	Paul
4	Bryanna	Higgins
5	Elisabeth	Lee
6	Skylar	Robinson
7	Cody	Bailey
8	Dario	Sims
9	Deacon	Hood


### Adding a **bar chart**: # observations per cluster

For the warehouse distribution scenario, it is helpful to know how many distributors will be served by each warehouse. Therefore, a **bar chart** is created that measures how many distributors are assigned to each cluster.

1. A **bar chart** is dragged onto the sheet. The chart is named: *# observations per cluster*.
2. **Data** configuration for the **bar chart**:
  - a. A **Dimension** labeled *Clusters* is added (the label can be added after the expression is applied). The following expression is entered: `=pick(aggr(KMeans2D(vDistClusters,only(latitude),only(longitude)),id)+1, 'Cluster 1', 'Cluster 2', 'Cluster 3', 'Cluster 4', 'Cluster 5')`
  - b. A **Measure** labeled *# of observations* is added. The following expression is entered: `=count(aggr(KMeans2D(vDistClusters,only(latitude),only(longitude)),id))`
3. **Appearance** configuration:
  - a. Under **Colors and legend**, **Custom** is chosen for **Colors**.
  - b. **By dimension** is selected for coloring the chart.
  - c. The following expression is entered: `=pick(aggr(KMeans2D(vDistClusters,only(latitude),only(longitude)),id)+1, 'Cluster 1', 'Cluster 2', 'Cluster 3', 'Cluster 4', 'Cluster 5')`
  - d. The checkbox for **Persistent colors** is selected.
  - e. **Show legend** is turned off.
  - f. Under **Presentation**, **Value labels** is toggled to **Auto**.
  - g. Under **X-axis: Clusters**, **Labels only** is selected.

Bar chart: # observations per cluster

### # observations per cluster



### Applying the **Centroid2D** function

A second table is added for the **Centroid2D** function that will identify the coordinates for potential warehouse locations. This table shows the central location (centroid values) for the five identified distributor groups.

1. A **Table** is dragged onto the sheet and named *Cluster centroids* with the following columns added::
  - a. A **Dimension** labeled *Clusters* is added. The following expression is entered: `=pick (aggr(KMeans2D(vDistClusters,only(latitude),only(longitude)),id)+1,'Warehouse 1','Warehouse 2','Warehouse 3','Warehouse 4','Warehouse 5')`
  - b. A **Measure** labeled *latitude (D1)* is added. The following expression is entered: `=only (aggr(KMeansCentroid2D(vDistClusters,0,only(latitude),only(longitude)),id))`  
Note the parameter **coordinate\_no** corresponds to the first dimension(0). In this case the dimension *latitude* is plotted against the x-axis. If we were working with the **CentroidND** function and there were up to six dimensions, these parameter entries could be any of six values: 0,1,2,3,4, or 5.
  - c. A **Measure** labeled *longitude (D2)* is added. The following expression is entered: `=only (aggr(KMeansCentroid2D(vDistClusters,1,only(latitude),only(longitude)),id))`  
The parameter **coordinate\_no** in this expression corresponds to the second dimension(1). The dimension *longitude* is plotted against the y-axis.

Table: Cluster centroid calculations

Cluster centroids			
Clusters	Q	latitude (D1)	longitude (D2)
<b>Totals</b>		-	-
Warehouse 1		40.945422240426	-73.719966482979
Warehouse 2		42.590538729412	-79.067889217647
Warehouse 3		42.805089516667	-75.901621883333
Warehouse 4		42.8581692625	-77.6800485875
Warehouse 5		43.436770771429	-73.734622635714

## Centroid mapping

The next step is to map the centroids. It is up to the app developer if they prefer to place the visualization on separate sheets.


1. A **map** named *Centroid mapping* is dragged onto the sheet.
2. In the **Layers** section, **Add layer** is selected, then **Point layer** is selected.
  - a. The **Field** *id* is selected and *Dist ids Label* is added.
  - b. In the **Location** section, the checkbox for **Latitude and Longitude fields** is selected.
  - c. For **Latitude**, the *latitude* field is selected.
  - d. For **Longitude**, the *longitude* field is selected.
  - e. In the **Size & Shape** section, **Bubble** is selected for **Shape**, and the **Size** is decreased to preference on the slider.
  - f. In the **Colors** section, **Single color** is selected and blue is selected for the **Color** and grey for the **Outline** color (these choices are also a matter of preference).
3. In the **Layers** section, a second **Point layer** is added by selecting **Add layer** and then selecting **Point layer**.
  - a. The following expression is entered: `=aggr(KMeans2D(vDistClusters,only(latitude),only(longitude)),id)`
  - b. The **Label** *Clusters* is added.
  - c. In the **Location** section, the checkbox for **Latitude and Longitude fields** is selected.
  - d. For **Latitude** which in this case is plotted along the x-axis, the following expression is added: `=aggr(KMeansCentroid2D(vDistClusters,0,only(latitude),only(longitude)),id)`
  - e. For **Longitude** which in this case is plotted along the y-axis, the following expression is added: `=aggr(KMeansCentroid2D(vDistClusters,1,only(latitude),only(longitude)),id)`
  - f. In the **Size & Shape** section, **Triangle** is selected for **Shape**, and the **Size** is decreased on the slider to preference.
  - g. Under **Colors and legend**, **Custom** is selected for **Colors**.

h. **By dimension** is selected for coloring the chart. The following expression is entered:  
`=pick(aggr(KMeans2D(vDistClusters,only(latitude),only(longitude)),id)+1,'Cluster 1','Cluster 2','Cluster 3','Cluster 4','Cluster 5')`

i. The dimension is labeled *Clusters*.

4. In **Map settings**, **Adaptive** is selected for **Projection**. **Metric** is selected for **Units of measurement**.


Map: Centroids mapped by cluster



## Conclusion

Using the KMeans function for this real-world scenario, distributors have been segmented into similar groups or clusters based on similarity; in this case, proximity to one another. The Centroid function was applied to those clusters to identify five mapping coordinates. Those coordinates provide an initial central location at which to build or locate warehouses. The centroid function is applied to the **map** chart, so that app users can visualize where the centroids are located relative to surrounding cluster data points. The resulting coordinates represent potential warehouse locations that could minimize delivery costs to distributors in New York state.

## App: KMeans and centroid analysis example



### Distributor dataset: Inline load for data load editor in Qlik Sense

DistributorData:

Load \* Inline [

id,first\_name,last\_name,telephone,address,city,state,zip,latitude,longitude

1,Kaiya,Snow,(716) 201-1212,6231 Tonawanda Creek Rd #APT 308,Lockport,NY,14094,43.08926,-78.69313

2,Dean,Roy,(716) 201-1588,6884 E High St,Lockport,NY,14094,43.16245,-78.65036

3,Eden,Paul,(716) 202-4596,4647 Southwestern Blvd #APT 350,Hamburg,NY,14075,42.76003,-78.83194

4,Bryanna,Higgins,(716) 203-7041,418 Park Ave,Dunkirk,NY,14048,42.48279,-79.33088

5,Elisabeth,Lee,(716) 203-7043,36 E Courtney St,Dunkirk,NY,14048,42.48299,-79.31928

6,Skylar,Robinson,(716) 203-7166,26 Greco Ln,Dunkirk,NY,14048,42.4612095,-79.3317925

7,Cody,Bailey,(716) 203-7201,114 Lincoln Ave,Dunkirk,NY,14048,42.4801269,-79.322232

8,Dario,Sims,(408) 927-1606,N Castle Dr,Armonk,NY,10504,41.11979,-73.714864

9,Deacon,Hood,(410) 244-6221,4856 44th St,Woodside,NY,11377,40.748372,-73.905445

10,Zackery,Levy,(410) 363-8874,61 Executive Blvd,Farmingdale,NY,11735,40.7197457,-73.430239

11,Rey,Hawkins,(412) 344-8687,4585 Shimerville Rd,Clarence,NY,14031,42.972075,-78.6592452

12,Phillip,Howard,(413) 269-4049,464 Main St #101,Port Washington,NY,11050,40.8273756,-73.7009971

13,Shirley,Tyler,(434) 985-8943,114 Glann Rd,Apalachin,NY,13732,42.0482515,-76.1229725

14,Aniyah,Jarvis,(440) 244-1808,87 N Middletown Rd,Pearl River,NY,10965,41.0629,-74.0159

15,Alayna,Woodard,(478) 335-3704,70 W Red Oak Ln,West Harrison,NY,10604,41.0162722,-73.7234926

16,Jermaine,Lambert,(508) 561-9836,24 Kellogg Rd,New Hartford,NY,13413,43.0555739,-75.2793197

17,Harper,Gibbs,(239) 466-0238,Po Box 33,cottekill,NY,12419,41.853392,-74.106082

18,Osvaldo,Graham,(252) 246-0816,6878 Sand Hill Rd,East Syracuse,NY,13057,43.073215,-76.081448

19,Roberto,Wade,(270) 469-1211,3936 Holley Rd,Moravia,NY,13118,42.713044,-76.481227

20,Kate,Mcguire,(270) 788-3080,6451 State 64 Rte #3,Naples,NY,14512,42.707366,-77.380489

21,Dale,Andersen,(281) 480-5690,205 W Service Rd,Champlain,NY,12919,44.9645392,-73.4470831

22,Lorelai,Burch,(302) 644-2133,1 Brewster St,Glen Cove,NY,11542,40.865177,-73.633019

23,Amiyah,Flowers,(303) 223-0055,46600 Us Interstate 81 Rte,Alexandria Bay,NY,13607,44.309626,-75.988365

## 8 Script and chart functions

---

24, Mckinley, Clements, (303) 918-3230, 200 Summit Lake Dr, Valhalla, NY, 10595, 41.101145, -73.778298  
25, Marc, Gibson, (607) 203-1233, 25 Robinson St, Binghamton, NY, 13901, 42.107416, -75.901614  
26, Kali, Norman, (607) 203-1400, 1 Ely Park Blvd #APT 15, Binghamton, NY, 13905, 42.125866, -75.925026  
27, Laci, Cain, (607) 203-1437, 16 Zimmer Road, Kirkwood, NY, 13795, 42.066516, -75.792627  
28, Mohammad, Perez, (607) 203-1652, 71 Endicott Ave #APT 12, Johnson City, NY, 13790, 42.111894, -75.952187  
29, Izabelle, Pham, (607) 204-0392, 434 State 369 Rte, Port Crane, NY, 13833, 42.185838, -75.823074  
30, Kiley, Mays, (607) 204-0870, 244 Ballyhack Rd #14, Port Crane, NY, 13833, 42.175612, -75.814917  
31, Peter, Trevino, (607) 205-1374, 125 Melbourne St., Vestal, NY, 13850, 42.080254, -76.051124  
32, Ani, Francis, (607) 208-4067, 48 Caswell St, Afton, NY, 13730, 42.232065, -75.525674  
33, Jared, Sheppard, (716) 386-3002, 4709 430th Rte, Bemus Point, NY, 14712, 42.162175, -79.39176  
34, Dulce, Atkinson, (914) 576-2266, 501 Pelham Rd, New Rochelle, NY, 10805, 40.895449, -73.782602  
35, Jayla, Beasley, (716) 526-1054, 5010 474th Rte, Ashville, NY, 14710, 42.096859, -79.375561  
36, Dane, Donovan, (718) 545-3732, 5014 31st Ave, Woodside, NY, 11377, 40.756967, -73.909506  
37, Brendon, Clay, (585) 322-7780, 133 Cummings Ave, Gainesville, NY, 14066, 42.664309, -78.085651  
38, Asia, Nunez, (718) 426-1472, 2407 Gilmore, East Elmhurst, NY, 11369, 40.766662, -73.869185  
39, Dawson, Odonnell, (718) 342-2179, 5019 H Ave, Brooklyn, NY, 11234, 40.633245, -73.927591  
40, Kyle, Collins, (315) 733-7078, 502 Rockhaven Rd, Utica, NY, 13502, 43.129184, -75.226726  
41, Eliza, Hardin, (315) 331-8072, 502 Sladen Place, West Point, NY, 10996, 41.3993, -73.973003  
42, Kasen, Klein, (518) 298-4581, 2407 Lake Shore Rd, Chazy, NY, 12921, 44.925561, -73.387373  
43, Reuben, Bradford, (518) 298-4581, 33 Lake Flats Dr, Champlain, NY, 12919, 44.928092, -73.387884  
44, Henry, Grimes, (518) 523-3990, 2407 Main St, Lake Placid, NY, 12946, 44.291487, -73.98474  
45, Kyan, Livingston, (518) 585-7364, 241 Alexandria Ave, Ticonderoga, NY, 12883, 43.836553, -73.43155  
46, Kaitlyn, Short, (516) 678-3189, 241 Chance Dr, Oceanside, NY, 11572, 40.638534, -73.63079  
47, Damaris, Jacobs, (914) 664-5331, 241 Claremont Ave, Mount Vernon, NY, 10552, 40.919852, -73.827848  
48, Alivia, Schroeder, (315) 469-4473, 241 Lafayette Rd, Syracuse, NY, 13205, 42.996446, -76.12957  
49, Bridget, Strong, (315) 298-4355, 241 Maltby Rd, Pulaski, NY, 13142, 43.584966, -76.136317  
50, Francis, Lee, (585) 201-7021, 166 Ross St, Batavia, NY, 14020, 43.0031502, -78.17487  
51, Makaila, Phelps, (585) 201-7422, 58 S Main St, Batavia, NY, 14020, 42.99941, -78.1939285  
52, Jazlynn, Stephens, (585) 203-1087, 1 Sinclair Dr, Pittsford, NY, 14534, 43.084157, -77.545452  
53, Ryann, Randolph, (585) 203-1519, 331 Eaglehead Rd, East Rochester, NY, 14445, 43.10785, -77.475552  
54, Rosa, Baker, (585) 204-4011, 42 Ossian St, Dansville, NY, 14437, 42.560761, -77.70088  
55, Marcel, Barry, (585) 204-4013, 42 Jefferson St, Dansville, NY, 14437, 42.557735, -77.702983  
56, Dennis, Schmitt, (585) 204-4061, 750 Dansville Mount Morris Rd, Dansville, NY, 14437, 42.584458, -77.741648  
57, Cassandra, Kim, (585) 204-4138, 3 Perine Ave APT1, Dansville, NY, 14437, 42.562865, -77.69661  
58, Kolton, Jacobson, (585) 206-5047, 4925 Upper Holly Rd, Holley, NY, 14470, 43.175957, -78.074465  
59, Nathanael, Donovan, (718) 393-3501, 9604 57th Ave, Corona, NY, 11373, 40.736077, -73.864858  
60, Robert, Frazier, (718) 271-3067, 300 56th Ave, Corona, NY, 11373, 40.735304, -73.873997  
61, Jessie, Mora, (315) 405-8991, 9607 Forsyth Loop, Watertown, NY, 13603, 44.036466, -75.833437  
62, Martha, Rollins, (347) 242-2642, 22 Main St, Corona, NY, 11373, 40.757727, -73.829331  
63, Emely, Townsend, (718) 699-0751, 60 Sanford Ave, Corona, NY, 11373, 40.755466, -73.831029  
64, Kylie, Cooley, (347) 561-7149, 9608 95th Ave, Ozone Park, NY, 11416, 40.687564, -73.845715  
65, Wendy, Cameron, (585) 571-4185, 9608 Union St, Scottsville, NY, 14546, 43.013327, -77.7907839  
66, Kayley, Peterson, (718) 654-5027, 961 E 230th St, Bronx, NY, 10466, 40.889275, -73.850555  
67, Camden, Ochoa, (718) 760-8699, 59 Vark St, Yonkers, NY, 10701, 40.929322, -73.89957  
68, Priscilla, Castillo, (910) 326-7233, 9359 Elm St, Chadwicks, NY, 13319, 43.024902, -75.26886  
69, Dana, Schultz, (913) 322-4580, 99 Washington Ave, Hastings on Hudson, NY, 10706, 40.99265, -73.879748  
70, Blaze, Medina, (914) 207-0015, 60 Elliott Ave, Yonkers, NY, 10705, 40.921498, -73.896682  
71, Finnegan, Tucker, (914) 207-0015, 90 Hillside Drive, Yonkers, NY, 10705, 40.922514, -73.892911  
72, Pranav, Palmer, (914) 214-8376, 5 Bruce Ave, Harrison, NY, 10528, 40.970916, -73.711493  
73, Kolten, Wong, (914) 218-8268, 70 Barker St, Mount Kisco, NY, 10549, 41.211993, -73.723202  
74, Jasiah, Vazquez, (914) 231-5199, 30 Broadway, Dobbs Ferry, NY, 10522, 41.004629, -73.879825  
75, Lamar, Pierce, (914) 232-0380, 68 Ridge Rd, Katonah, NY, 10536, 41.256662, -73.707964  
76, Carla, Coffey, (914) 232-0469, 197 Beaver Dam Rd, Katonah, NY, 10536, 41.247934, -73.664363

77, Brooklyn, Harmon, (716) 595-3227, 8084 Glasgow Rd, Cassadega, NY, 14718, 42.353861, -79.329558  
78, Raquel, Hodges, (585) 398-8125, 809 County Road, Victor, NY, 14564, 43.011745, -77.398806  
79, Jerimiah, Gardner, (585) 787-9127, 809 Houston Rd, Webster, NY, 14580, 43.224204, -77.491353  
80, Clarence, Hammond, (720) 746-1619, 809 Pierpont Ave, Piermont, NY, 10968, 41.0491181, -73.918622  
81, Rhys, Gill, (518) 427-7887, 81 Columbia St, Albany, NY, 12210, 42.652824, -73.752096  
82, Edith, Parrish, (845) 452-7621, 81 Glenwood Ave, Poughkeepsie, NY, 12603, 41.691058, -73.910829  
83, Kobe, Mcintosh, (845) 371-1101, 81 Heitman Dr, Spring Valley, NY, 10977, 41.103227, -74.054396  
84, Ayden, Waters, (516) 796-2722, 81 Kingfisher Rd, Levittown, NY, 11756, 40.738939, -73.52826  
85, Francis, Rogers, (631) 427-7728, 81 Knollwood Ave, Huntington, NY, 11743, 40.864905, -73.426107  
86, Jaden, Landry, (716) 496-4038, 12839 39th Rte, Chaffee, NY, 14030, 43.527396, -73.462786  
87, Giancarlo, Campos, (518) 885-5717, 1284 Saratoga Rd, Ballston Spa, NY, 12020, 42.968594, -73.862847  
88, Eduardo, Contreras, (716) 285-8987, 1285 Saunders Sett Rd, Niagara Falls, NY, 14305, 43.122963, -79.029274  
89, Gabriela, Davidson, (716) 267-3195, 1286 Mee Rd, Falconer, NY, 14733, 42.147339, -79.137976  
90, Evangeline, Case, (518) 272-9435, 1287 2nd Ave, Watervliet, NY, 12189, 42.723132, -73.703818  
91, Tyrone, Ellison, (518) 843-4691, 1287 Midline Rd, Amsterdam, NY, 12010, 42.9730876, -74.1700608  
92, Bryce, Bass, (518) 943-9549, 1288 Leeds Athens Rd, Athens, NY, 12015, 42.259381, -73.876897  
93, Londyn, Butler, (518) 922-7095, 129 Argersinger Rd, Fultonville, NY, 12072, 42.910969, -74.441917  
94, Graham, Becker, (607) 655-1318, 129 Baker Rd, Windsor, NY, 13865, 42.107271, -75.66408  
95, Rolando, Fitzgerald, (315) 465-4166, 17164 County 90 Rte, Mannsville, NY, 13661, 43.713443, -76.06232  
96, Grant, Hoover, (518) 692-8363, 1718 County 113 Rte, Schaghticote, NY, 12154, 42.900648, -73.585036  
97, Mark, Goodwin, (631) 584-6761, 172 Cambon Ave, Saint James, NY, 11780, 40.871152, -73.146032  
98, Deacon, Cantu, (845) 221-7940, 172 Carpenter Rd, Hopewell Junction, NY, 12533, 41.57388, -73.77609  
99, Tristian, Walsh, (516) 997-4750, 172 E Cabot Ln, Westbury, NY, 11590, 40.7480397, -73.54819  
100, Abram, Alexander, (631) 588-3817, 172 Lorenzo Cir, Ronkonkoma, NY, 11779, 40.837123, -73.09367  
101, Lesly, Bush, (516) 489-3791, 172 Nassau Blvd, Garden City, NY, 11530, 40.71147, -73.660753  
102, Pamela, Espinoza, (716) 201-1520, 172 Niagara St, Lockport, NY, 14094, 43.169871, -78.70093  
103, Bryanna, Newton, (914) 328-4332, 172 Warren Ave, White Plains, NY, 10603, 41.047207, -73.79572  
104, Marcelo, Schmitt, (315) 393-4432, 319 Mansion Ave, Ogdensburg, NY, 13669, 44.690246, -75.49992  
105, Layton, Valenzuela, (631) 676-2113, 319 Singingwood Dr, Holbrook, NY, 11741, 40.801391, -73.058993  
106, Roderick, Rocha, (518) 671-6037, 319 Warren St, Hudson, NY, 12534, 42.252527, -73.790629  
107, Camryn, Terrell, (315) 635-1680, 3192 Olive Dr, Baldinsville, NY, 13027, 43.136843, -76.260303  
108, Summer, Callahan, (585) 394-4195, 3192 Smith Road, Canandaigua, NY, 14424, 42.875457, -77.228039  
109, Pierre, Novak, (716) 665-2524, 3194 Falconer Kimball Stand Rd, Falconer, NY, 14733, 42.138439, -79.211091  
110, Kennedy, Fry, (315) 543-2301, 32 College Rd, Selden, NY, 11784, 40.861624, -73.04757  
111, Wyatt, Pruitt, (716) 681-4042, 277 Ransom Rd, Lancaster, NY, 14086, 42.87702, -78.591302  
112, Lilly, Jensen, (631) 841-0859, 2772 Schliegel Blvd, Amityville, NY, 11701, 40.708021, -73.413015  
113, Tristin, Hardin, (631) 920-0927, 278 Fulton Street, West Babylon, NY, 11704, 40.733578, -73.357321  
114, Tanya, Stafford, (716) 484-0771, 278 Sampson St, Jamestown, NY, 14701, 42.0797, -79.247805  
115, Paris, Cordova, (607) 589-4857, 278 Washburn Rd, Spencer, NY, 14883, 42.225046, -76.510257  
116, Alfonso, Morse, (718) 359-5582, 200 Colden St, Flushing, NY, 11355, 40.750403, -73.822752  
117, Maurice, Hooper, (315) 595-6694, 4435 Italy Hill Rd, Branchport, NY, 14418, 42.597957, -77.199267  
118, Iris, Wolf, (607) 539-7288, 444 Harford Rd, Brooktondale, NY, 14817, 42.392164, -76.30756  
];

### KMeans2D - chart function

**KMeans2D()** evaluates the rows of the chart by applying k-means clustering, and for each chart row displays the cluster id of the cluster this data point has been assigned to. The columns that are used by the clustering algorithm are determined by the parameters `coordinate_1`, and `coordinate_2`, respectively. These are both aggregations. The number of clusters that are created is determined by the `num_clusters` parameter. Data can be optionally normalized by the `norm` parameter.

**KMeans2D** returns one value per data point. The returned value is a dual and is the integer value corresponding to the cluster each data point has been assigned to.

**Syntax:**

```
KMeans2D(num_clusters, coordinate_1, coordinate_2 [, norm])
```

**Return data type:** dual

**Arguments:**

Arguments

Argument	Description
num_clusters	Integer that specifies the number of clusters.
coordinate_1	The aggregation that calculates the first coordinate, usually the x-axis of the scatter chart that can be made from the chart. The additional parameter, coordinate_2, calculates the second coordinate.
norm	<p>The optional normalization method applied to datasets before KMeans clustering.</p> <p>Possible values:</p> <ul style="list-style-type: none"><li>0 or 'none' for no normalization</li><li>1 or 'zscore' for z-score normalization</li><li>2 or 'minmax' for min-max normalization</li></ul> <p>If no parameter is supplied or if the supplied parameter is incorrect, no normalization is applied.</p> <p>Z-score normalizes data based on feature mean and standard deviation. Z-score does not ensure each feature has the same scale but it is a better approach than min-max when dealing with outliers.</p> <p>Min-max normalization ensures that the features have the same scale by taking the minimum and maximum values of each and recalculating each datapoint.</p>

Example: Chart expression

In this example, we create a scatter plot chart using the *Iris* dataset, and then use KMeans to color the data by expression.

We also create a variable for the *num\_clusters* argument, and then use a variable input box to change the number of clusters.



## 8 Script and chart functions

The *Iris* data set is publicly available in a variety of formats. We have provided the data as an inline table to load using the data load editor in Qlik Sense. Note that we added an *Id* column to the data table for this example.

After loading the data in Qlik Sense, we do the following:

1. Drag a **Scatter plot** chart onto a new sheet. Name the chart *Petal (color by expression)*.
2. Create a variable to specify the number of clusters. For the variable **Name**, enter *KmeansPetalClusters*. For the variable **Definition**, enter *=2*.
3. Configure **Data** for the chart:
  - i. Under **Dimensions**, choose *id* for the field for **Bubble**. Enter Cluster Id for the Label.
  - ii. Under **Measures**, choose *Sum([petal.length])* for the expression for **X-axis**.
  - iii. Under **Measures**, choose *Sum([petal.width])* for the expression for **Y-axis**.


*Data settings for Petal (color by expression) chart*

The screenshot shows the configuration panel for a chart in Qlik Sense. The panel is titled "Data" and is divided into three main sections: "Dimensions", "Alternative dimensions", and "Measures".

- Dimensions:** The "Bubble" field is set to "Id".
- Alternative dimensions:** There is a button labeled "Add alternative".
- Measures:** The "X-axis" is set to "Sum [petal.length]" and the "Y-axis" is set to "Sum [petal.width]".

The data points are plotted on the chart.

Data points on Petal (color by expression) chart

4. Configure **Appearance** for the chart:

- i. Under **Colors and legend**, choose **Custom** for **Colors**.
- ii. Choose to color the chart **By expression**.
- iii. Enter the following for **Expression**: `kmeans2d($(KmeansPetalClusters), Sum([petal.length]), Sum([petal.width]))`  
 Note that `KmeansPetalClusters` is the variable that we set to 2.  
 Alternatively, enter the following: `kmeans2d(2, Sum([petal.length]), Sum([petal.width]))`
- iv. Deselect the check box for **The expression is a color code**.

v. Enter the following for **Label**: *Cluster Id*

*Appearance settings for Petal (color by expression) chart*

Appearance

▼ Colors and legend

Colors

Custom

By expression ▼

Expression

kmeans2d(\$(KmeansPetalC *fx*)

The expression is a color code

Label

Cluster Id

Color scheme

Sequential gradient

Sequential classes

Diverging gradient

Diverging classes

Reverse colors

Range

Auto

Show legend


Auto

Legend position

Show legend title

## 8 Script and chart functions

The two clusters on the chart are colored by the KMeans expression.  
*Clusters colored by expression on Petal (color by expression) chart*



5. Add a **Variable input** box for the number of clusters.
  - i. Under **Custom objects** in the **Assets** panel, choose **Qlik Dashboard bundle**. If we did not have access to the dashboard bundle, we could still change the number of clusters using the variable that we created, or directly as an integer in the expression.
  - ii. Drag a **Variable input** box onto the sheet.
  - iii. Under **Appearance**, click **General**.
  - iv. Enter the following for **Title**: *Clusters*
  - v. Click **Variable**.
  - vi. Choose the following variable for **Name**: *KmeansPetalClusters*.
  - vii. Choose **Slider** for **Show as**.

viii. Choose **Values**, and configure the settings as required,

*Appearance for Clusters variable input box*



▼ General

Show titles  On

Title

Clusters	<i>fx</i>
----------	-----------

Subtitle

	<i>fx</i>
--	-----------

Footnote

	<i>fx</i>
--	-----------

Disable hover menu

▼ Variable

Name

KmeansPetalClusters	▼
---------------------	---

Show as

Slider	▼
--------	---

Update on drag

▼ Values

Min

2	<i>fx</i>
---	-----------

Max

10	<i>fx</i>
----	-----------


Step

1	<i>fx</i>
---	-----------

Slider label

When we are done editing, we can change the number of clusters using the slider in the *Clusters* variable input box.

*Clusters colored by expression on Petal (color by expression) chart*




### Auto-clustering

**KMeans** functions support auto-clustering using a method called depth difference (DeD). When a user sets 0 for the number of clusters, an optimal number of clusters for that dataset is determined. Note that while an integer for the number of clusters ( $k$ ) is not explicitly returned, it is calculated within the KMeans algorithm. For example, if 0 is specified in the function for the value of *KmeansPetalClusters* or set through a variable input box, cluster assignments are automatically calculated for the dataset based on an optimal number of clusters.

## 8 Script and chart functions

*KMeans depth difference method determines optimal number of clusters when (k) is set to 0*



### Iris data set: Inline load for data load editor in Qlik Sense

IrisData:

Load \* Inline [

sepal.length, sepal.width, petal.length, petal.width, variety, id

```
5.1, 3.5, 1.4, 0.2, Setosa, 1
4.9, 3, 1.4, 0.2, Setosa, 2
4.7, 3.2, 1.3, 0.2, Setosa, 3
4.6, 3.1, 1.5, 0.2, Setosa, 4
5, 3.6, 1.4, 0.2, Setosa, 5
5.4, 3.9, 1.7, 0.4, Setosa, 6
4.6, 3.4, 1.4, 0.3, Setosa, 7
5, 3.4, 1.5, 0.2, Setosa, 8
4.4, 2.9, 1.4, 0.2, Setosa, 9
4.9, 3.1, 1.5, 0.1, Setosa, 10
5.4, 3.7, 1.5, 0.2, Setosa, 11
4.8, 3.4, 1.6, 0.2, Setosa, 12
4.8, 3, 1.4, 0.1, Setosa, 13
4.3, 3, 1.1, 0.1, Setosa, 14
5.8, 4, 1.2, 0.2, Setosa, 15
5.7, 4.4, 1.5, 0.4, Setosa, 16
5.4, 3.9, 1.3, 0.4, Setosa, 17
5.1, 3.5, 1.4, 0.3, Setosa, 18
5.7, 3.8, 1.7, 0.3, Setosa, 19
5.1, 3.8, 1.5, 0.3, Setosa, 20
5.4, 3.4, 1.7, 0.2, Setosa, 21
```

5.1, 3.7, 1.5, 0.4, Setosa, 22  
4.6, 3.6, 1, 0.2, Setosa, 23  
5.1, 3.3, 1.7, 0.5, Setosa, 24  
4.8, 3.4, 1.9, 0.2, Setosa, 25  
5, 3, 1.6, 0.2, Setosa, 26  
5, 3.4, 1.6, 0.4, Setosa, 27  
5.2, 3.5, 1.5, 0.2, Setosa, 28  
5.2, 3.4, 1.4, 0.2, Setosa, 29  
4.7, 3.2, 1.6, 0.2, Setosa, 30  
4.8, 3.1, 1.6, 0.2, Setosa, 31  
5.4, 3.4, 1.5, 0.4, Setosa, 32  
5.2, 4.1, 1.5, 0.1, Setosa, 33  
5.5, 4.2, 1.4, 0.2, Setosa, 34  
4.9, 3.1, 1.5, 0.1, Setosa, 35  
5, 3.2, 1.2, 0.2, Setosa, 36  
5.5, 3.5, 1.3, 0.2, Setosa, 37  
4.9, 3.1, 1.5, 0.1, Setosa, 38  
4.4, 3, 1.3, 0.2, Setosa, 39  
5.1, 3.4, 1.5, 0.2, Setosa, 40  
5, 3.5, 1.3, 0.3, Setosa, 41  
4.5, 2.3, 1.3, 0.3, Setosa, 42  
4.4, 3.2, 1.3, 0.2, Setosa, 43  
5, 3.5, 1.6, 0.6, Setosa, 44  
5.1, 3.8, 1.9, 0.4, Setosa, 45  
4.8, 3, 1.4, 0.3, Setosa, 46  
5.1, 3.8, 1.6, 0.2, Setosa, 47  
4.6, 3.2, 1.4, 0.2, Setosa, 48  
5.3, 3.7, 1.5, 0.2, Setosa, 49  
5, 3.3, 1.4, 0.2, Setosa, 50  
7, 3.2, 4.7, 1.4, versicolor, 51  
6.4, 3.2, 4.5, 1.5, versicolor, 52  
6.9, 3.1, 4.9, 1.5, versicolor, 53  
5.5, 2.3, 4, 1.3, versicolor, 54  
6.5, 2.8, 4.6, 1.5, versicolor, 55  
5.7, 2.8, 4.5, 1.3, versicolor, 56  
6.3, 3.3, 4.7, 1.6, versicolor, 57  
4.9, 2.4, 3.3, 1, versicolor, 58  
6.6, 2.9, 4.6, 1.3, versicolor, 59  
5.2, 2.7, 3.9, 1.4, versicolor, 60  
5, 2, 3.5, 1, versicolor, 61  
5.9, 3, 4.2, 1.5, versicolor, 62  
6, 2.2, 4, 1, versicolor, 63  
6.1, 2.9, 4.7, 1.4, versicolor, 64  
5.6, 2.9, 3.6, 1.3, versicolor, 65  
6.7, 3.1, 4.4, 1.4, versicolor, 66  
5.6, 3, 4.5, 1.5, versicolor, 67  
5.8, 2.7, 4.1, 1, versicolor, 68  
6.2, 2.2, 4.5, 1.5, versicolor, 69  
5.6, 2.5, 3.9, 1.1, versicolor, 70  
5.9, 3.2, 4.8, 1.8, versicolor, 71  
6.1, 2.8, 4, 1.3, versicolor, 72  
6.3, 2.5, 4.9, 1.5, versicolor, 73  
6.1, 2.8, 4.7, 1.2, versicolor, 74  
6.4, 2.9, 4.3, 1.3, versicolor, 75  
6.6, 3, 4.4, 1.4, versicolor, 76

6.8, 2.8, 4.8, 1.4, Versicolor, 77  
6.7, 3, 5, 1.7, Versicolor, 78  
6, 2.9, 4.5, 1.5, Versicolor, 79  
5.7, 2.6, 3.5, 1, Versicolor, 80  
5.5, 2.4, 3.8, 1.1, Versicolor, 81  
5.5, 2.4, 3.7, 1, Versicolor, 82  
5.8, 2.7, 3.9, 1.2, Versicolor, 83  
6, 2.7, 5.1, 1.6, Versicolor, 84  
5.4, 3, 4.5, 1.5, Versicolor, 85  
6, 3.4, 4.5, 1.6, Versicolor, 86  
6.7, 3.1, 4.7, 1.5, Versicolor, 87  
6.3, 2.3, 4.4, 1.3, Versicolor, 88  
5.6, 3, 4.1, 1.3, Versicolor, 89  
5.5, 2.5, 4, 1.3, Versicolor, 90  
5.5, 2.6, 4.4, 1.2, Versicolor, 91  
6.1, 3, 4.6, 1.4, Versicolor, 92  
5.8, 2.6, 4, 1.2, Versicolor, 93  
5, 2.3, 3.3, 1, Versicolor, 94  
5.6, 2.7, 4.2, 1.3, Versicolor, 95  
5.7, 3, 4.2, 1.2, Versicolor, 96  
5.7, 2.9, 4.2, 1.3, Versicolor, 97  
6.2, 2.9, 4.3, 1.3, Versicolor, 98  
5.1, 2.5, 3, 1.1, Versicolor, 99  
5.7, 2.8, 4.1, 1.3, Versicolor, 100  
6.3, 3.3, 6, 2.5, virginica, 101  
5.8, 2.7, 5.1, 1.9, virginica, 102  
7.1, 3, 5.9, 2.1, virginica, 103  
6.3, 2.9, 5.6, 1.8, virginica, 104  
6.5, 3, 5.8, 2.2, virginica, 105  
7.6, 3, 6.6, 2.1, virginica, 106  
4.9, 2.5, 4.5, 1.7, virginica, 107  
7.3, 2.9, 6.3, 1.8, virginica, 108  
6.7, 2.5, 5.8, 1.8, virginica, 109  
7.2, 3.6, 6.1, 2.5, virginica, 110  
6.5, 3.2, 5.1, 2, virginica, 111  
6.4, 2.7, 5.3, 1.9, virginica, 112  
6.8, 3, 5.5, 2.1, virginica, 113  
5.7, 2.5, 5, 2, virginica, 114  
5.8, 2.8, 5.1, 2.4, virginica, 115  
6.4, 3.2, 5.3, 2.3, virginica, 116  
6.5, 3, 5.5, 1.8, virginica, 117  
7.7, 3.8, 6.7, 2.2, virginica, 118  
7.7, 2.6, 6.9, 2.3, virginica, 119  
6, 2.2, 5, 1.5, virginica, 120  
6.9, 3.2, 5.7, 2.3, virginica, 121  
5.6, 2.8, 4.9, 2, virginica, 122  
7.7, 2.8, 6.7, 2, virginica, 123  
6.3, 2.7, 4.9, 1.8, virginica, 124  
6.7, 3.3, 5.7, 2.1, virginica, 125  
7.2, 3.2, 6, 1.8, virginica, 126  
6.2, 2.8, 4.8, 1.8, virginica, 127  
6.1, 3, 4.9, 1.8, virginica, 128  
6.4, 2.8, 5.6, 2.1, virginica, 129  
7.2, 3, 5.8, 1.6, virginica, 130  
7.4, 2.8, 6.1, 1.9, virginica, 131

7.9, 3.8, 6.4, 2, virginica, 132  
 6.4, 2.8, 5.6, 2.2, virginica, 133  
 6.3, 2.8, 5.1, 1.5, virginica, 134  
 6.1, 2.6, 5.6, 1.4, virginica, 135  
 7.7, 3, 6.1, 2.3, virginica, 136  
 6.3, 3.4, 5.6, 2.4, virginica, 137  
 6.4, 3.1, 5.5, 1.8, virginica, 138  
 6, 3, 4.8, 1.8, virginica, 139  
 6.9, 3.1, 5.4, 2.1, virginica, 140  
 6.7, 3.1, 5.6, 2.4, virginica, 141  
 6.9, 3.1, 5.1, 2.3, virginica, 142  
 5.8, 2.7, 5.1, 1.9, virginica, 143  
 6.8, 3.2, 5.9, 2.3, virginica, 144  
 6.7, 3.3, 5.7, 2.5, virginica, 145  
 6.7, 3, 5.2, 2.3, virginica, 146  
 6.3, 2.5, 5, 1.9, virginica, 147  
 6.5, 3, 5.2, 2, virginica, 148  
 6.2, 3.4, 5.4, 2.3, virginica, 149  
 5.9, 3, 5.1, 1.8, virginica, 150  
 ];

### KMeansND - chart function

**KMeansND()** evaluates the rows of the chart by applying k-means clustering, and for each chart row displays the cluster id of the cluster this data point has been assigned to. The columns that are used by the clustering algorithm are determined by the parameters `coordinate_1`, and `coordinate_2`, etc., up to `n` columns. These are all aggregations. The number of clusters that are created is determined by the `num_clusters` parameter.

**KMeansND** returns one value per data point. The returned value is a dual and is the integer value corresponding to the cluster each data point has been assigned to.

#### Syntax:

```
KMeansND (num_clusters, num_iter, coordinate_1, coordinate_2 [,coordinate_3 [,
...]])
```

**Return data type:** dual

#### Arguments:

##### Arguments

Argument	Description
<code>num_clusters</code>	Integer that specifies the number of clusters.
<code>num_iter</code>	The number of iterations of clustering with reinitialized cluster centers.
<code>coordinate_1</code>	The aggregation that calculates the first coordinate, usually the x-axis (of a scatter chart that can be made from the chart). The additional parameters calculate the second, third, and fourth coordinates, etc.

Example: Chart expression

In this example, we create a scatter plot chart using the *Iris* dataset, and then use KMeans to color the data by expression.

We also create a variable for the *num\_clusters* argument, and then use a variable input box to change the number of clusters.

Additionally, we create a variable for the *num\_iter* argument, and then use a second variable input box to change the number of iterations.

The *Iris* data set is publicly available in a variety of formats. We have provided the data as an inline table to load using the data load editor in Qlik Sense. Note that we added an *Id* column to the data table for this example.

After loading the data in Qlik Sense, we do the following:

1. Drag a **Scatter plot** chart onto a new sheet. Name the chart *Petal (color by expression)*.
2. Create a variable to specify the number of clusters. For the variable **Name**, enter *KmeansPetalClusters*. For the variable **Definition**, enter *=2*.
3. Create a variable to specify the number of iterations. For the variable **Name**, enter *KmeansNumberIterations*. For the variable **Definition**, enter *=1*.
4. Configure **Data** for the chart:
  - i. Under **Dimensions**, choose *id* for the field for **Bubble**. Enter Cluster Id for the Label.
  - ii. Under **Measures**, choose *Sum([petal.length])* for the expression for **X-axis**.
  - iii. Under **Measures**, choose *Sum([petal.width])* for the expression for **Y-axis**.

Data settings for Petal (color by expression) chart

**Data**

**Dimensions**  
Bubble

Id > [grid icon]

Alternative dimensions

Add alternative

**Measures**

X-axis

Sum [petal.length] > [grid icon]

Y-axis


Sum [petal.width] > [grid icon]

The data points are plotted on the chart.



## 8 Script and chart functions

Data points on Petal (color by expression) chart



5. Configure **Appearance** for the chart:

- i. Under **Colors and legend**, choose **Custom** for **Colors**.
- ii. Choose to color the chart **By expression**.
- iii. Enter the following for **Expression**: `kmeansnd`  
`$(KmeansPetalClusters),$(KmeansNumberIterations), Sum([petal.length]), Sum([petal.width]),Sum([sepal.length]), Sum([sepal.width])`  
Note that `KmeansPetalClusters` is the variable that we set to 2.  
`KmeansNumberIterations` is the variable that we set to 1.  
Alternatively, enter the following: `kmeansnd(2, 2, Sum([petal.length]), Sum([petal.width]),Sum([sepal.length]), Sum([sepal.width]))`
- iv. Deselect the check box for **The expression is a color code**.

v. Enter the following for **Label**: *Cluster Id*

*Appearance settings for Petal (color by expression) chart*

Appearance

▼ Colors and legend

Colors

Custom

By expression ▼

Expression

kmeansnd(\$(KmeansPetal( *fx*

The expression is a color code

Label

Cluster Id

Color scheme

Sequential gradient

Sequential classes

Diverging gradient

Diverging classes

Reverse colors

Range

Auto


Show legend

Auto

Legend position

## 8 Script and chart functions

The two clusters on the chart are colored by the KMeans expression.  
*Clusters colored by expression on Petal (color by expression) chart*



6. Add a **Variable input** box for the number of clusters.
  - i. Under **Custom objects** in the **Assets** panel, choose **Qlik Dashboard bundle**. If we did not have access to the dashboard bundle, we could still change the number of clusters using the variable that we created, or directly as an integer in the expression.
  - ii. Drag a **Variable input** box onto the sheet.
  - iii. Under **Appearance**, click **General**.
  - iv. Enter the following for **Title**: *Clusters*
  - v. Click **Variable**.
  - vi. Choose the following variable for **Name**: *KmeansPetalClusters*.
  - vii. Choose **Slider** for **Show as**.

viii. Choose **Values**, and configure the settings as required,

*Appearance for Clusters variable input box*

▼ General

Show titles  On

Title

Clusters	<i>fx</i>
----------	-----------

Subtitle

	<i>fx</i>
--	-----------

Footnote

	<i>fx</i>
--	-----------

Disable hover menu

▼ Variable

Name

KmeansPetalClusters	▼
---------------------	---

Show as

Slider	▼
--------	---

Update on drag

▼ Values

Min

2	<i>fx</i>
---	-----------

Max

10	<i>fx</i>
----	-----------

Step

1	<i>fx</i>
---	-----------


Slider label



7. Add a **Variable input** box for the number of iterations.
  - i. Drag a **Variable input** box onto the sheet.
  - ii. Under **Appearance**, choose **General**.
  - iii. Enter the following for **Title**: *Iterations*
  - iv. Under **Appearance**, choose **Variable**.
  - v. Choose the following variable under **Name**: *KmeansNumberIterations*.
  - vi. Configure the additional settings as required,

We can now change the number of clusters and iterations using the sliders in the variable input boxes.

*Clusters colored by expression on Petal (color by expression) chart*




### Auto-clustering

**KMeans** functions support auto-clustering using a method called depth difference (DeD). When a user sets 0 for the number of clusters, an optimal number of clusters for that dataset is determined. Note that while an integer for the number of clusters ( $k$ ) is not explicitly returned, it is calculated within the KMeans algorithm. For example, if 0 is specified in the function for the value of *KmeansPetalClusters* or set through a variable input box, cluster assignments are automatically

## 8 Script and chart functions

calculated for the dataset based on an optimal number of clusters. Given the Iris dataset, if 0 is selected for the number of clusters, the algorithm will determine (auto-cluster) an optimal number of clusters (3) for this dataset.

*KMeans depth difference method determines optimal number of clusters when (k) is set to 0.*



### Iris data set: Inline load for data load editor in Qlik Sense

IrisData:

Load \* Inline [

sepal.length, sepal.width, petal.length, petal.width, variety, id

5.1, 3.5, 1.4, 0.2, Setosa, 1

4.9, 3, 1.4, 0.2, setosa, 2

4.7, 3.2, 1.3, 0.2, Setosa, 3

4.6, 3.1, 1.5, 0.2, Setosa, 4

5, 3.6, 1.4, 0.2, setosa, 5

5.4, 3.9, 1.7, 0.4, Setosa, 6

4.6, 3.4, 1.4, 0.3, Setosa, 7

5, 3.4, 1.5, 0.2, setosa, 8

4.4, 2.9, 1.4, 0.2, Setosa, 9

4.9, 3.1, 1.5, 0.1, Setosa, 10

5.4, 3.7, 1.5, 0.2, Setosa, 11

4.8, 3.4, 1.6, 0.2, Setosa, 12

4.8, 3, 1.4, 0.1, setosa, 13

4.3, 3, 1.1, 0.1, setosa, 14

5.8, 4, 1.2, 0.2, setosa, 15

5.7, 4.4, 1.5, 0.4, Setosa, 16

5.4, 3.9, 1.3, 0.4, Setosa, 17  
5.1, 3.5, 1.4, 0.3, Setosa, 18  
5.7, 3.8, 1.7, 0.3, Setosa, 19  
5.1, 3.8, 1.5, 0.3, Setosa, 20  
5.4, 3.4, 1.7, 0.2, Setosa, 21  
5.1, 3.7, 1.5, 0.4, Setosa, 22  
4.6, 3.6, 1, 0.2, Setosa, 23  
5.1, 3.3, 1.7, 0.5, Setosa, 24  
4.8, 3.4, 1.9, 0.2, Setosa, 25  
5, 3, 1.6, 0.2, Setosa, 26  
5, 3.4, 1.6, 0.4, Setosa, 27  
5.2, 3.5, 1.5, 0.2, Setosa, 28  
5.2, 3.4, 1.4, 0.2, Setosa, 29  
4.7, 3.2, 1.6, 0.2, Setosa, 30  
4.8, 3.1, 1.6, 0.2, Setosa, 31  
5.4, 3.4, 1.5, 0.4, Setosa, 32  
5.2, 4.1, 1.5, 0.1, Setosa, 33  
5.5, 4.2, 1.4, 0.2, Setosa, 34  
4.9, 3.1, 1.5, 0.1, Setosa, 35  
5, 3.2, 1.2, 0.2, Setosa, 36  
5.5, 3.5, 1.3, 0.2, Setosa, 37  
4.9, 3.1, 1.5, 0.1, Setosa, 38  
4.4, 3, 1.3, 0.2, Setosa, 39  
5.1, 3.4, 1.5, 0.2, Setosa, 40  
5, 3.5, 1.3, 0.3, Setosa, 41  
4.5, 2.3, 1.3, 0.3, Setosa, 42  
4.4, 3.2, 1.3, 0.2, Setosa, 43  
5, 3.5, 1.6, 0.6, Setosa, 44  
5.1, 3.8, 1.9, 0.4, Setosa, 45  
4.8, 3, 1.4, 0.3, Setosa, 46  
5.1, 3.8, 1.6, 0.2, Setosa, 47  
4.6, 3.2, 1.4, 0.2, Setosa, 48  
5.3, 3.7, 1.5, 0.2, Setosa, 49  
5, 3.3, 1.4, 0.2, Setosa, 50  
7, 3.2, 4.7, 1.4, versicolor, 51  
6.4, 3.2, 4.5, 1.5, versicolor, 52  
6.9, 3.1, 4.9, 1.5, versicolor, 53  
5.5, 2.3, 4, 1.3, versicolor, 54  
6.5, 2.8, 4.6, 1.5, versicolor, 55  
5.7, 2.8, 4.5, 1.3, versicolor, 56  
6.3, 3.3, 4.7, 1.6, versicolor, 57  
4.9, 2.4, 3.3, 1, versicolor, 58  
6.6, 2.9, 4.6, 1.3, versicolor, 59  
5.2, 2.7, 3.9, 1.4, versicolor, 60  
5, 2, 3.5, 1, versicolor, 61  
5.9, 3, 4.2, 1.5, versicolor, 62  
6, 2.2, 4, 1, versicolor, 63  
6.1, 2.9, 4.7, 1.4, versicolor, 64  
5.6, 2.9, 3.6, 1.3, versicolor, 65  
6.7, 3.1, 4.4, 1.4, versicolor, 66  
5.6, 3, 4.5, 1.5, versicolor, 67  
5.8, 2.7, 4.1, 1, versicolor, 68  
6.2, 2.2, 4.5, 1.5, versicolor, 69  
5.6, 2.5, 3.9, 1.1, versicolor, 70  
5.9, 3.2, 4.8, 1.8, versicolor, 71

6.1, 2.8, 4, 1.3, Versicolor, 72  
6.3, 2.5, 4.9, 1.5, Versicolor, 73  
6.1, 2.8, 4.7, 1.2, Versicolor, 74  
6.4, 2.9, 4.3, 1.3, Versicolor, 75  
6.6, 3, 4.4, 1.4, Versicolor, 76  
6.8, 2.8, 4.8, 1.4, Versicolor, 77  
6.7, 3, 5, 1.7, Versicolor, 78  
6, 2.9, 4.5, 1.5, Versicolor, 79  
5.7, 2.6, 3.5, 1, Versicolor, 80  
5.5, 2.4, 3.8, 1.1, Versicolor, 81  
5.5, 2.4, 3.7, 1, Versicolor, 82  
5.8, 2.7, 3.9, 1.2, Versicolor, 83  
6, 2.7, 5.1, 1.6, Versicolor, 84  
5.4, 3, 4.5, 1.5, Versicolor, 85  
6, 3.4, 4.5, 1.6, Versicolor, 86  
6.7, 3.1, 4.7, 1.5, Versicolor, 87  
6.3, 2.3, 4.4, 1.3, Versicolor, 88  
5.6, 3, 4.1, 1.3, Versicolor, 89  
5.5, 2.5, 4, 1.3, Versicolor, 90  
5.5, 2.6, 4.4, 1.2, Versicolor, 91  
6.1, 3, 4.6, 1.4, Versicolor, 92  
5.8, 2.6, 4, 1.2, Versicolor, 93  
5, 2.3, 3.3, 1, Versicolor, 94  
5.6, 2.7, 4.2, 1.3, Versicolor, 95  
5.7, 3, 4.2, 1.2, Versicolor, 96  
5.7, 2.9, 4.2, 1.3, Versicolor, 97  
6.2, 2.9, 4.3, 1.3, Versicolor, 98  
5.1, 2.5, 3, 1.1, Versicolor, 99  
5.7, 2.8, 4.1, 1.3, Versicolor, 100  
6.3, 3.3, 6, 2.5, virginica, 101  
5.8, 2.7, 5.1, 1.9, virginica, 102  
7.1, 3, 5.9, 2.1, virginica, 103  
6.3, 2.9, 5.6, 1.8, virginica, 104  
6.5, 3, 5.8, 2.2, virginica, 105  
7.6, 3, 6.6, 2.1, virginica, 106  
4.9, 2.5, 4.5, 1.7, virginica, 107  
7.3, 2.9, 6.3, 1.8, virginica, 108  
6.7, 2.5, 5.8, 1.8, virginica, 109  
7.2, 3.6, 6.1, 2.5, virginica, 110  
6.5, 3.2, 5.1, 2, virginica, 111  
6.4, 2.7, 5.3, 1.9, virginica, 112  
6.8, 3, 5.5, 2.1, virginica, 113  
5.7, 2.5, 5, 2, virginica, 114  
5.8, 2.8, 5.1, 2.4, virginica, 115  
6.4, 3.2, 5.3, 2.3, virginica, 116  
6.5, 3, 5.5, 1.8, virginica, 117  
7.7, 3.8, 6.7, 2.2, virginica, 118  
7.7, 2.6, 6.9, 2.3, virginica, 119  
6, 2.2, 5, 1.5, virginica, 120  
6.9, 3.2, 5.7, 2.3, virginica, 121  
5.6, 2.8, 4.9, 2, virginica, 122  
7.7, 2.8, 6.7, 2, virginica, 123  
6.3, 2.7, 4.9, 1.8, virginica, 124  
6.7, 3.3, 5.7, 2.1, virginica, 125  
7.2, 3.2, 6, 1.8, virginica, 126

6.2, 2.8, 4.8, 1.8, virginica, 127  
6.1, 3, 4.9, 1.8, virginica, 128  
6.4, 2.8, 5.6, 2.1, virginica, 129  
7.2, 3, 5.8, 1.6, virginica, 130  
7.4, 2.8, 6.1, 1.9, virginica, 131  
7.9, 3.8, 6.4, 2, virginica, 132  
6.4, 2.8, 5.6, 2.2, virginica, 133  
6.3, 2.8, 5.1, 1.5, virginica, 134  
6.1, 2.6, 5.6, 1.4, virginica, 135  
7.7, 3, 6.1, 2.3, virginica, 136  
6.3, 3.4, 5.6, 2.4, virginica, 137  
6.4, 3.1, 5.5, 1.8, virginica, 138  
6, 3, 4.8, 1.8, virginica, 139  
6.9, 3.1, 5.4, 2.1, virginica, 140  
6.7, 3.1, 5.6, 2.4, virginica, 141  
6.9, 3.1, 5.1, 2.3, virginica, 142  
5.8, 2.7, 5.1, 1.9, virginica, 143  
6.8, 3.2, 5.9, 2.3, virginica, 144  
6.7, 3.3, 5.7, 2.5, virginica, 145  
6.7, 3, 5.2, 2.3, virginica, 146  
6.3, 2.5, 5, 1.9, virginica, 147  
6.5, 3, 5.2, 2, virginica, 148  
6.2, 3.4, 5.4, 2.3, virginica, 149  
5.9, 3, 5.1, 1.8, virginica, 150  
];

### KMeansCentroid2D - chart function

**KMeansCentroid2D()** evaluates the rows of the chart by applying k-means clustering, and for each chart row displays the desired coordinate of the cluster this data point has been assigned to. The columns that are used by the clustering algorithm are determined by the parameters `coordinate_1`, and `coordinate_2`, respectively. These are both aggregations. The number of clusters that are created is determined by the `num_clusters` parameter. Data can be optionally normalized by the `norm` parameter.

**KMeansCentroid2D** returns one value per data point. The returned value is a dual and is one of the coordinates of the position corresponding to the cluster center the data point has been assigned to.

#### Syntax:

```
KMeansCentroid2D(num_clusters, coordinate_no, coordinate_1, coordinate_2 [, norm])
```

**Return data type:** dual

#### Arguments:

##### Arguments

Argument	Description
<code>num_clusters</code>	Integer that specifies the number of clusters.

Argument	Description
coordinate_no	The desired coordinate number of the centroids (corresponding, for example, to the x, y, or z axis).
coordinate_1	The aggregation that calculates the first coordinate, usually the x-axis of the scatter chart that can be made from the chart. The additional parameter, coordinate_2, calculates the second coordinate.
norm	<p>The optional normalization method applied to datasets before KMeans clustering.</p> <p>Possible values:</p> <p>0 or 'none' for no normalization</p> <p>1 or 'zscore' for z-score normalization</p> <p>2 or 'minmax' for min-max normalization</p> <p>If no parameter is supplied or if the supplied parameter is incorrect, no normalization is applied.</p> <p>Z-score normalizes data based on feature mean and standard deviation. Z-score does not ensure each feature has the same scale but it is a better approach than min-max when dealing with outliers.</p> <p>Min-max normalization ensures that the features have the same scale by taking the minimum and maximum values of each and recalculating each datapoint.</p>

## Auto-clustering

**KMeans** functions support auto-clustering using a method called depth difference (DeD). When a user sets 0 for the number of clusters, an optimal number of clusters for that dataset is determined. Note that while an integer for the number of clusters ( $k$ ) is not explicitly returned, it is calculated within the KMeans algorithm. For example, if 0 is specified in the function for the value of *KmeansPetalClusters* or set through a variable input box, cluster assignments are automatically calculated for the dataset based on an optimal number of clusters.

## KMeansCentroidND - chart function

**KMeansCentroidND()** evaluates the rows of the chart by applying k-means clustering, and for each chart row displays the desired coordinate of the cluster this data point has been assigned to. The columns that are used by the clustering algorithm are determined by the parameters coordinate\_1, coordinate\_2, etc., up to n columns. These are all aggregations. The number of clusters that are created is determined by the num\_clusters parameter.

**KMeansCentroidND** returns one value per row. The returned value is a dual and is one of the coordinates of the position corresponding to the cluster center the data point has been assigned to.

### Syntax:

```
KMeansCentroidND(num_clusters, num_iter, coordinate_no, coordinate_1,
coordinate_2 [,coordinate_3 [, ...]])
```

**Return data type:** dual

### Arguments:

#### Arguments

Argument	Description
num_clusters	Integer that specifies the number of clusters.
num_iter	The number of iterations of clustering with reinitialized cluster centers.
coordinate_no	The desired coordinate number of the centroids (corresponding, for example, to the x, y, or z axis).
coordinate_1	The aggregation that calculates the first coordinate, usually the x-axis (of a scatter chart that can be made from the chart). The additional parameters calculate the second, third, and fourth coordinates, etc.

### Auto-clustering

**KMeans** functions support auto-clustering using a method called depth difference (DeD). When a user sets 0 for the number of clusters, an optimal number of clusters for that dataset is determined. Note that while an integer for the number of clusters ( $k$ ) is not explicitly returned, it is calculated within the KMeans algorithm. For example, if 0 is specified in the function for the value of *KmeansPetalClusters* or set through a variable input box, cluster assignments are automatically calculated for the dataset based on an optimal number of clusters.

### STL\_Trend - chart function

**STL\_Trend** is a time series decomposition function. Along with **STL\_Seasonal** and **STL\_Residual**, this function is used to decompose a time series into seasonal, trend, and residual components. In the context of the STL algorithm, time series decomposition is used to identify both a recurring seasonal pattern and a general trend, given an input metric and other parameters. The **STL\_Trend** function will identify a general trend, independent of seasonal patterns or cycles, from time series data.

The three STL functions are related to the input metric through a simple sum:

**STL\_Trend + STL\_Seasonal + STL\_Residual = Input metric**

STL (seasonal and trend decomposition using Loess) employs data smoothing techniques, and through its input parameters, allows the user to adjust the periodicity of the calculations it performs. This periodicity determines how the time dimension of the input metric (a measure) is segmented in the analysis.

At minimum, **STL\_Trend** takes an input metric (`target_measure`) and an integer value for its `period_int`, returning a floating-point value. The input metric will be in the form of an aggregation that varies along the time dimension. Optionally, you can include values for the `seasonal_smoother` and `trend_smoother` to adjust the smoothing algorithm.

You can work with this function by entering it directly into the expression editor for a chart.

### Syntax:

```
STL_Trend(target_measure, period_int [,seasonal_smoother [,trend_smoother]])
```

**Return data type:** dual

### Arguments

Argument	Description
<b>target_measure</b>	<p>The measure to decompose into Seasonal and Trend components. This should be a measure such as Sum(Sales) or Sum(Passengers) that varies along the time dimension.</p> <p>This must not be a constant value.</p>
<b>period_int</b>	<p>The periodicity of the dataset. This parameter is an integer value representing the number of discrete steps that make up one period, or seasonal cycle, of the signal.</p> <p>For instance, if the time series is segmented into one section for each quarter of the year, you must set the <b>period_int</b> to a value of 4 to define the periodicity as Year.</p>
<b>seasonal_smoother</b>	<p>Length of the seasonal smoother. This must be an odd integer. The seasonal smoother uses data for a particular phase in the seasonal variation, over a number of periods. One discrete step of the time dimension is used from each period. The seasonal smoother indicates the number of periods used for smoothing.</p> <p>For example, if the time dimension is segmented by month and the period is Year (12), the seasonal component will be computed so that each particular month of each year is calculated from data for the same month, both in that year and in adjacent years. The <b>seasonal_smoother</b> value is the number of years used for smoothing.</p>
<b>trend_smoother</b>	<p>Length of the trend smoother. This must be an odd integer. The trend smoother uses the same time scale as the <b>period_int</b> parameter, and its value is the number of granules used for smoothing.</p> <p>For example, if a time series is segmented by month, the trend smoother will be the number of months used for smoothing.</p>

The **STL\_Trend** chart function is often used in combination with the following functions:



## Related functions

Function	Interaction
<i>STL_Seasonal</i> - chart function (page 1425)	This is the function used to compute the seasonal component of a time series.
<i>STL_Residual</i> - chart function (page 1427)	When breaking down an input metric into seasonal and trend component, part of the measures variation will not fit within either of the two main components. The <b>STL_Residual</b> function computes this portion of the decomposition.

For a tutorial with a full example showing how to use this function, see *Tutorial - Time series decomposition in Qlik Sense* (page 1429).

## STL\_Seasonal - chart function

**STL\_Seasonal** is a time series decomposition function. Along with **STL\_Trend** and **STL\_Residual**, this function is used to decompose a time series into seasonal, trend, and residual components. In the context of the STL algorithm, time series decomposition is used to identify both a recurring seasonal pattern and a general trend, given an input metric and other parameters. The **STL\_Seasonal** function can identify a seasonal pattern within a time series, separating this from the general trend displayed by the data.

The three STL functions are related to the input metric through a simple sum:

**STL\_Trend + STL\_Seasonal + STL\_Residual = Input metric**

STL (seasonal and trend decomposition using Loess) employs data smoothing techniques, and through its input parameters, allows the user to adjust the periodicity of the calculations it performs. This periodicity determines how the time dimension of the input metric (a measure) is segmented in the analysis.

At minimum, **STL\_Seasonal** takes an input metric (`target_measure`) and an integer value for its `period_int`, returning a floating-point value. The input metric will be in the form of an aggregation that varies along the time dimension. Optionally, you can include values for the `seasonal_smoother` and `trend_smoother` to adjust the smoothing algorithm.

You can work with this function by entering it directly into the expression editor for a chart.

### Syntax:

```
STL_Seasonal(target_measure, period_int [,seasonal_smoother [,trend_smoother]])
```

**Return data type:** dual

### Arguments

Argument	Description
<b>target_measure</b>	<p>The measure to decompose into Seasonal and Trend components. This should be a measure such as Sum(Sales) or Sum(Passengers) that varies along the time dimension.</p> <p>This must not be a constant value.</p>
<b>period_int</b>	<p>The periodicity of the dataset. This parameter is an integer value representing the number of discrete steps that make up one period, or seasonal cycle, of the signal.</p> <p>For instance, if the time series is segmented into one section for each quarter of the year, you must set the <b>period_int</b> to a value of 4 to define the periodicity as Year.</p>
<b>seasonal_smoother</b>	<p>Length of the seasonal smoother. This must be an odd integer. The seasonal smoother uses data for a particular phase in the seasonal variation, over a number of periods. One discrete step of the time dimension is used from each period. The seasonal smoother indicates the number of periods used for smoothing.</p> <p>For example, if the time dimension is segmented by month and the period is Year (12), the seasonal component will be computed so that each particular month of each year is calculated from data for the same month, both in that year and in adjacent years. The <b>seasonal_smoother</b> value is the number of years used for smoothing.</p>

Argument	Description
<b>trend_smoother</b>	<p>Length of the trend smoother. This must be an odd integer. The trend smoother uses the same time scale as the <b>period_int</b> parameter, and its value is the number of granules used for smoothing.</p> <p>For example, if a time series is segmented by month, the trend smoother will be the number of months used for smoothing.</p>

The **STL\_Seasonal** chart function is often used in combination with the following functions:

### Related functions

Function	Interaction
<i>STL_Trend - chart function (page 1423)</i>	This is the function used to compute the trend component of a time series.
<i>STL_Residual - chart function (page 1427)</i>	When breaking down an input metric into seasonal and trend component, part of the measures variation will not fit within either of the two main components. The <b>STL_Residual</b> function computes this portion of the decomposition.

For a tutorial with a full example showing how to use this function, see *Tutorial - Time series decomposition in Qlik Sense (page 1429)*.

## STL\_Residual - chart function

**STL\_Residual** is a time series decomposition function. Along with **STL\_Seasonal** and **STL\_Trend**, this function is used to decompose a time series into seasonal, trend, and residual components. In the context of the STL algorithm, time series decomposition is used to identify both a recurring seasonal pattern and a general trend, given an input metric and other parameters. In performing this operation, part of the variation in the

input metric will neither fit within the seasonal nor the trend component, and will be defined as the residual component. The **STL\_Residual** chart function captures this portion of the calculation.

The three STL functions are related to the input metric through a simple sum:

**STL\_Trend + STL\_Seasonal + STL\_Residual = Input metric**

STL (seasonal and trend decomposition using Loess) employs data smoothing techniques, and through its input parameters, allows the user to adjust the periodicity of the calculations it performs. This periodicity determines how the time dimension of the input metric (a measure) is segmented in the analysis.

Since time series decomposition primarily looks for seasonality and general variations in data, the information in the residual is considered the least significant of the three components. However, a skewed or periodic residual component can help identify issues in the calculation, such as incorrect periodicity settings.

At minimum, **STL\_Residual** takes an input metric (`target_measure`) and an integer value for its `period_int`, returning a floating-point value. The input metric will be in the form of an aggregation that varies along the time dimension. Optionally, you can include values for the `seasonal_smoother` and `trend_smoother` to adjust the smoothing algorithm.

You can work with this function by entering it directly into the expression editor for a chart.

### Syntax:

```
STL_Residual(target_measure, period_int [,seasonal_smoother [,trend_smoother]])
```

**Return data type:** dual

### Arguments

Argument	Description
<b>target_measure</b>	The measure to decompose into Seasonal and Trend components. This should be a measure such as Sum(Sales) or Sum(Passengers) that varies along the time dimension.  This must not be a constant value.
<b>period_int</b>	The periodicity of the dataset. This parameter is an integer value representing the number of discrete steps that make up one period, or seasonal cycle, of the signal.  For instance, if the time series is segmented into one section for each quarter of the year, you must set the <b>period_int</b> to a value of 4 to define the periodicity as Year.

Argument	Description
<b>seasonal_smoother</b>	<p>Length of the seasonal smoother. This must be an odd integer. The seasonal smoother uses data for a particular phase in the seasonal variation, over a number of periods. One discrete step of the time dimension is used from each period. The seasonal smoother indicates the number of periods used for smoothing.</p> <p>For example, if the time dimension is segmented by month and the period is Year (12), the seasonal component will be computed so that each particular month of each year is calculated from data for the same month, both in that year and in adjacent years. The <b>seasonal_smoother</b> value is the number of years used for smoothing.</p>
<b>trend_smoother</b>	<p>Length of the trend smoother. This must be an odd integer. The trend smoother uses the same time scale as the <b>period_int</b> parameter, and its value is the number of granules used for smoothing.</p> <p>For example, if a time series is segmented by month, the trend smoother will be the number of months used for smoothing.</p>

The **STL\_Residual** chart function is often used in combination with the following functions:

### Related functions

Function	Interaction
<i>STL_Seasonal - chart function (page 1425)</i>	This is the function used to compute the seasonal component of a time series.
<i>STL_Trend - chart function (page 1423)</i>	This is the function used to compute the trend component of a time series.

For a tutorial with a full example showing how to use this function, see *Tutorial - Time series decomposition in Qlik Sense (page 1429)*.

## Tutorial - Time series decomposition in Qlik Sense

This tutorial demonstrates using three chart functions to decompose a time series using the STL algorithm.

This tutorial uses time series data for the number of passengers using an airline per month to demonstrate the functionality of the STL algorithm. The **STL\_Trend**, **STL\_Seasonal**, and **STL\_Residual** chart functions will be used to create the visualizations. For more information about time series decomposition in Qlik Sense, see *Time series decomposition functions (page 1375)*.

### Create an app

Start by creating a new app and importing the dataset into it.

Download this dataset:

[Tutorial - Time series decomposition](#)



This file contains data regarding an airline's number of passengers per month.

#### Do the following:

1. From the hub click **Create new app**.
2. Open the app and drop the *Tutorial - Time series decomposition.csv* file into it.

### Prepare and load the data

In order for Qlik Sense to interpret the *YearMonth* field correctly, you might need to use Data manager to recognize the field as a date field, not a field with string values. Typically this step is handled automatically, but in this case the dates are presented in the slightly uncommon *YYYY-MM* format.

1. In Data manager, select the table and click .
2. With the *YearMonth* field selected, click  and set the **Field type** to **Date**.
3. Under **Input format**, enter *YYYY-MM*.
4. Under **Display format**, enter *YYYY-MM* and click **OK**.  
The field should now show the calendar icon.
5. Click **Load data**.

Now you are ready to start using the STL functions to visually represent your data.


### Create the visualizations

Next, you will create two line charts to demonstrate the functionality of the **STL\_Trend**, **STL\_Seasonal**, and **STL\_Residual** chart functions.

Open a new sheet and give it a title.

Add two line charts to the sheet. Resize and reposition the charts to match the following image.

### Qlik Sense grid outline of blank app sheet



### First line chart: Trend and seasonal components

#### Do the following:

1. Add the title *Seasonal and Trend* to the first line chart.
2. Add *YearMonth* as a dimension and label it *Date*.
3. Add the following measure and label it *Passengers per month*:  
 $=\text{Sum}(\text{Passengers})$
4. Under **Data**, expand the *Passengers per month* measure and click **Add trend line**.
5. Set the **Type** to **Linear**.  
 You will compare this trend line to the smoothed output of the trend component.
6. Add the following measure to plot the trend component and label it *Trend*:  
 $=\text{STL\_Trend}(\text{SUM}(\text{Passengers}), 12)$
7. Next, add the following measure to plot the seasonal component and label it *Seasonal*:  
 $=\text{STL\_Seasonal}(\text{SUM}(\text{Passengers}), 12)$
8. Under **Appearance** > **Presentation**, set **Scroll bar** to **None**.
9. Keep the default colors, or change them to fit your preferences.

## Second line chart: Residual component


Next, configure the second line chart. This visualization will display the residual component of the time series.

### Do the following:

1. Drag a line chart onto the sheet. Add the title *Residual*.
2. Add *Date* as a dimension.
3. Add the following measure and label it *Residual*:  
 $=STL\_Residual(SUM(Passengers), 12)$
4. Under **Appearance** > **Presentation**, set **Scroll bar** to **None**.

Your sheet should now look like the one below.

*Qlik Sense sheet for airline passenger analysis*



## Interpreting and explaining the data

With the STL chart functions, we can gain a number of insights from our time series data.

### Trend component

The statistical information in the trend component is deseasonalized. This makes it easier to see general, non-repeating fluctuations over time. Compared to the straight, linear trend line for *Passengers per month*, the STL trend component does capture changing trends. It displays some clear deviations while still presenting the information in a readable fashion. The smoothing behaviors in the STL algorithm helped to capture this.

The drops in number of airline passengers that are visible in the STL trend graph can be explained as part of the economic impact of recessions that occurred during the 1950s.



### Seasonal component

The detrended seasonal component isolated recurring fluctuations throughout the time series, and removed general trend information from that part of the analysis. We started with a dataset consisting of year-month aggregations. With this data, it is implicit that we are segmenting the data into one-month granules. By defining a period value of 12, we set the chart to model seasonal patterns over the course of one-year (twelve-month) cycles.

In the data, there is a repeated seasonal pattern of surges in airline passengers in the summer months, followed by declines for the winter months. This is aligned with the idea that summer is typically a popular time to take vacations and travel. We also see that over the course of the time series, these seasonal cycles increase drastically in amplitude.

### Residual component

The chart for the residual component shows all the information that was not captured in the trend and seasonal decomposition. The residual component includes statistical noise, but it can also indicate an incorrect setting of the STL trend and seasonal function arguments. Generally, if there are periodic oscillations in the residual component of the signal, or the information displayed is clearly not random, it is usually a sign that there is information in the time series not currently captured in the seasonal or trend components. In this case, you need to revisit your definitions of each function argument and possibly change the periodicity.

### Smoother values

Since we did not specify any values for the trend and seasonal smoothers, the function will use the default values for these parameters. In Qlik Sense, the default smoother values in the STL algorithm produce effective results. As a result, in most cases, these arguments can be left out of the expressions.



*Setting the seasonal or trend smoother arguments as 0 in either of the three STL functions makes the algorithm use default values, rather than values of 0.*

The trend smoother value uses the dimension that is specified in the chart. Since the *YearMonth* field presents data by months, the trend smoother value will be the number of months. The seasonal smoother will reflect the periodicity defined. In this case, since we defined one period as lasting twelve months (one year), the seasonal smoother value is the number of years. This may sound confusing, but it really means that to find the seasonality, we need to look across a number of seasons. This number is the seasonal smoother.

### Other useful information

Given that the seasonal cycles increase in amplitude over time, a more advanced analytics approach could make use of logarithmic functions to create a multiplicative decomposition. In practice, a simple measure of relative amplitude can be created in Qlik Sense by dividing the seasonal by the trend component. When this is done, we notice that over time, the summer peaks of each cycle grow larger in relative amplitude. The amplitude of the winter low points, however, do not increase over time.

### 8.23 Statistical distribution functions

Statistical distribution functions return the probabilities of occurrence of different possible outcomes for a given input variable. You can use these functions to calculate the potential values of your data points.

The three groups of statistical distribution functions described below are all implemented in Qlik Sense using the Cephys function library. For references and details on algorithms used, accuracy, and so on, see: [Cephys library](#). The Cephys function library is used by permission.

- The probability functions calculate the probability at the point in the distribution given by the supplied value.
  - The Frequency functions are used for discrete distributions.
  - The Density functions are used for continuous functions.
- The Dist functions calculate the accumulated probability of the distribution at the point in the distribution given by the supplied value.
- The Inv functions calculate the inverse value, given the accumulated probability of the distribution.

All functions can be used in both the data load script and in chart expressions.

#### Statistical distribution functions overview

Each function is described further after the overview. You can also click the function name in the syntax to immediately access the details for that specific function.

##### BetaDensity

`BetaDensity()` returns the probability of the Beta distribution.

```
BetaDensity (value, alpha, beta)
```

##### BetaDist

`BetaDist()` returns the accumulated probability of the Beta distribution.

```
BetaDist (value, alpha, beta)
```

##### BetaInv

`BetaINV()` returns the inverse of the accumulated probability of the Beta distribution.

```
BetaInv (prob, alpha, beta)
```

##### BinomDist

`BinomDist()` returns the accumulated probability of the Binomial distribution.

```
BinomDist (value, trials, trial_probability)
```

##### BinomFrequency

`BinomFrequency()` returns the Binomial probability distribution.

**BinomFrequency** (value, trials, trial\_probability)

BinomInv

BinomInv() returns the inverse of the accumulated probability of the Binomial distribution.

**BinomInv** (prob, trials, trial\_probability)

ChiDensity

ChiDensity() returns the one-tailed probability of the  $\chi^2$  distribution. The  $\chi^2$  density function is associated with a  $\chi^2$  test.

**ChiDensity** (value, degrees\_freedom)

**ChiDist**

ChiDist() returns the one-tailed probability of the  $\chi^2$  distribution. The  $\chi^2$  distribution is associated with a  $\chi^2$  test.

**ChiDist** (value, degrees\_freedom)

**ChiInv**

ChiInv() returns the inverse of the one-tailed probability of the  $\chi^2$  distribution.

**ChiInv** (prob, degrees\_freedom)

FDensity

FDensity() returns the probability of the F distribution.

**FDensity** (value, degrees\_freedom1, degrees\_freedom2)

**FDist**

FDist() returns the accumulated probability of the F distribution.

**FDist** (value, degrees\_freedom1, degrees\_freedom2)

**FInv**

FInv() returns the inverse of the accumulated probability of the F distribution.

**FInv** (prob, degrees\_freedom1, degrees\_freedom2)

GammaDensity

GammaDensity() returns the probability of the Gamma distribution.

**GammaDensity** (value, k,  $\theta$ )

GammaDist

GammaDist() returns the accumulated probability of the Gamma distribution.

**GammaDist** (value, k,  $\theta$ )

GammaInv

GammaInv() returns the inverse of the accumulated probability of the Gamma distribution.

**GammaInv** (prob, k,  $\theta$ )

### NormDist

NormDist() returns the cumulative normal distribution for the specified mean and standard deviation. If mean = 0 and standard\_dev = 1, the function returns the standard normal distribution.

```
NormDist (value, mean, standard_dev)
```

### NormInv

NormInv() returns the inverse of the normal cumulative distribution for the specified mean and standard deviation.

```
NormInv (prob, mean, standard_dev)
```

### PoissonDist

PoissonDist() returns the accumulated probability of the Poisson distribution.

```
PoissonDist (value, mean)
```

### PoissonFrequency

PoissonFrequency() returns the Poisson probability distribution.

```
PoissonFrequency (value, mean)
```

### PoissonInv

PoissonInv() returns the inverse of the accumulated probability of the Poisson distribution.

```
PoissonInv (prob, mean)
```

### TDensity

TDensity() returns the value for the student's  $t$  density function where a numeric value is a calculated value of  $t$  for which the probability is to be computed.

```
TDensity (value, degrees_freedom, tails)
```

### TDist

TDist() returns the probability for the student's  $t$  distribution where a numeric value is a calculated value of  $t$  for which the probability is to be computed.

```
TDist (value, degrees_freedom, tails)
```

### TInv

TInv() returns the  $t$  value of the student's  $t$  distribution as a function of the probability and the degrees of freedom.

```
TInv (prob, degrees_freedom)
```

---

### See also:

 [Statistical aggregation functions \(page 400\)](#)

## BetaDensity

`BetaDensity()` returns the probability of the Beta distribution.

### Syntax:

```
BetaDensity(value, alpha, beta)
```

**Return data type:** number

#### Arguments

Argument	Description
value	The value at which you want to evaluate the distribution. The value must be between 0 and 1.
alpha	A positive number defining the first shape parameter. It is the exponent of the random variable
beta	A positive number defining the second shape parameter. It states the number of denominator degrees of freedom.

## BetaDist

`BetaDist()` returns the accumulated probability of the Beta distribution.

### Syntax:

```
BetaDist(value, alpha, beta)
```

**Return data type:** number

#### Arguments

Argument	Description
value	The value at which you want to evaluate the distribution. The value must be between 0 and 1.
alpha	A positive number defining the first shape parameter. It is the exponent of the random variable
beta	A positive number defining the second shape parameter. It is the exponent that controls the shape of the distribution.

This function is related to the `BetaInv` function in the following way:

If  $prob = \text{BetaDist}(value, alpha, beta)$ , then  $\text{BetaInv}(prob, alpha, beta) = value$

## BetaInv

`BetaInv()` returns the inverse of the accumulated probability of the Beta distribution.

**Syntax:**

```
BetaInv(prob, alpha, beta)
```

**Return data type:** number

Arguments

Argument	Description
prob	A probability associated with the Beta-probability distribution. It must be a number between 0 and 1.
alpha	A positive number defining the first shape parameter. It is the exponent of the random variable
beta	A positive number defining the second shape parameter. It is the exponent that controls the shape of the distribution.

This function is related to the `betaDist` function in the following way:

If `prob = BetaDist(value, alpha, beta)`, then `BetaInv(prob, alpha, beta) = value`

## BinomDist

`BinomDist()` returns the accumulated probability of the Binomial distribution.

**Syntax:**

```
BinomDist(value, trials, trial_probability)
```

**Return data type:** number

Arguments

Argument	Description
value	The value at which you want to evaluate the distribution. The value must be an integer not smaller than zero and not greater than the number of trials.
trials	A positive integer that states the number of trials.
trial_probability	The success probability for each trial. It is always a number between 0 and 1.

This function is related to the `binomInv` function in the following way:

If `prob = BinomDIST(value, trials, trial_probability)`, then `BinomInv(prob, trials, trial_probability) = value`

## BinomFrequency

`BinomFrequency()` returns the Binomial probability distribution.

**Syntax:**

```
BinomFrequency(value, trials, trial_probability)
```

**Return data type:** number

### Arguments

Argument	Description
value	The value at which you want to evaluate the distribution. The value must be an integer not smaller than zero and not greater than the number of trials.
trials	A positive integer that states the number of trials
trial_probability	The success probability for each trial. It is always a number between 0 and 1.

## BinomInv

`BinomInv()` returns the inverse of the accumulated probability of the Binomial distribution.

**Syntax:**

```
BinomInv(prob, trials, trial_probability)
```

**Return data type:** number

### Arguments

Argument	Description
prob	A probability associated with the Binomial-probability distribution. It must be a number between 0 and 1.
trials	A positive integer that states the number of trials.
trial_probability	The success probability for each trial. It is always a number between 0 and 1.

This function is related to the `BinomDist` function in the following way:

If `prob = BinomDist(value, trials, trial_probability)`, then `BinomInv(prob, trials, trial_probability) = value`

## ChiDensity

`ChiDensity()` returns the one-tailed probability of the  $\chi^2$  distribution. The  $\chi^2$  density function is associated with a  $\chi^2$  test.

**Syntax:**

```
ChiDensity(value, degrees_freedom)
```

**Return data type:** number

#### Arguments

Argument	Description
value	The value at which you want to evaluate the distribution. The value must not be negative.
degrees_freedom	A positive integer stating the number of numerator degrees of freedom.

## ChiDist

`chiDist()` returns the one-tailed probability of the  $\chi^2$  distribution. The  $\chi^2$  distribution is associated with a  $\chi^2$  test.

### Syntax:

```
CHIDIST(value, degrees_freedom)
```

**Return data type:** number

### Arguments:

#### Arguments

Argument	Description
value	The value at which you want to evaluate the distribution. The value must not be negative.
degrees_freedom	A positive integer stating the number of degrees of freedom.

This function is related to the **ChiInv** function in the following way:

If `prob = CHIDIST(value,df)`, then `CHIINV(prob, df) = value`

### Limitations:

All arguments must be numeric, else NULL will be returned.

Examples and results:

Example	Result
<code>CHIDIST( 8, 15)</code>	Returns 0.9238

## ChiInv

`chiInv()` returns the inverse of the one-tailed probability of the  $\chi^2$  distribution.

### Syntax:

```
CHIINV(prob, degrees_freedom)
```



**Return data type:** number

**Arguments:**

Arguments

Argument	Description
prob	A probability associated with the $\chi^2$ distribution. It must be a number between 0 and 1.
degrees_freedom	An integer stating the number of degrees of freedom.

This function is related to the **ChiDist** function in the following way:

If  $\text{prob} = \text{CHIDIST}(\text{value}, \text{df})$ , then  $\text{CHIINV}(\text{prob}, \text{df}) = \text{value}$

**Limitations:**

All arguments must be numeric, else NULL will be returned.

Examples and results:

Example	Result
$\text{CHIINV}(0.9237827, 15)$	Returns 8.0000

## FDensity

$\text{FDensity}()$  returns the probability of the  $F$  distribution.

**Syntax:**

```
 $\text{FDensity}(\text{value}, \text{degrees\_freedom1}, \text{degrees\_freedom2})$ 
```

**Return data type:** number

Arguments

Argument	Description
value	The value at which you want to evaluate the distribution. The value must not be negative.
degrees_freedom1	A positive integer stating the number of numerator degrees of freedom.
degrees_freedom2	A positive integer stating the number of denominator degrees of freedom.

## FDist

$\text{FDist}()$  returns the accumulated probability of the  $F$  distribution.

**Syntax:**

```
FDist(value, degrees_freedom1, degrees_freedom2)
```

**Return data type:** number

**Arguments:**

Arguments

Argument	Description
value	The value at which you want to evaluate the distribution. The value must not be negative.
degrees_freedom1	A positive integer stating the number of numerator degrees of freedom.
degrees_freedom2	A positive integer stating the number of denominator degrees of freedom.

This function is related to the **FInv** function in the following way:  
 If  $\text{prob} = \text{FDIST}(\text{value}, \text{df1}, \text{df2})$ , then  $\text{FINV}(\text{prob}, \text{df1}, \text{df2}) = \text{value}$

**Limitations:**

All arguments must be numeric, else NULL will be returned.

Examples and results:

Example	Result
FDIST(15, 8, 6)	Returns 0.0019

## FInv

**FInv()** returns the inverse of the accumulated probability of the F distribution.

**Syntax:**

```
FInv(prob, degrees_freedom1, degrees_freedom2)
```

**Return data type:** number

**Arguments:**

Arguments

Argument	Description
prob	A probability associated with the F-probability distribution and must be a number between 0 and 1.
degrees_freedom	An integer stating the number of degrees of freedom.

This function is related to the **FDist** function in the following way:

If  $\text{prob} = \text{FDIST}(\text{value}, \text{df1}, \text{df2})$ , then  $\text{FINV}(\text{prob}, \text{df1}, \text{df2}) = \text{value}$

### Limitations:

All arguments must be numeric, else NULL will be returned.

Examples and results:

Example	Result
<code>FINV( 0.0019369, 8, 6)</code>	Returns 15.0000

## GammaDensity

`GammaDensity()` returns the probability of the Gamma distribution.

### Syntax:

```
GammaDensity(value, k,  $\theta$ )
```

**Return data type:** number

#### Arguments

Argument	Description
<code>value</code>	The value at which you want to evaluate the distribution. The value must not be negative.
<code>k</code>	A positive number defining the shape parameter.
<code><math>\theta</math></code>	A positive number defining the scale parameter.

## GammaDist

`GammaDist()` returns the accumulated probability of the Gamma distribution.

### Syntax:

```
GammaDist(value, k,  $\theta$ )
```

**Return data type:** number

#### Arguments

Argument	Description
<code>value</code>	The value at which you want to evaluate the distribution. The value must not be negative.
<code>k</code>	A positive number defining the shape parameter.
<code><math>\theta</math></code>	A positive number defining the scale parameter.

This function is related to the `GammaInv` function in the following way:  
If `prob = GammaDist(value, k,  $\theta$ )`, then `GammaInv(prob, k,  $\theta$ ) = value`

### GammaInv

`GammaInv()` returns the inverse of the accumulated probability of the Gamma distribution.

#### Syntax:

```
GammaInv(prob, k,  $\theta$ )
```

**Return data type:** number

#### Arguments

Argument	Description
prob	A probability associated with the Gamma-probability distribution. It must be a number between 0 and 1.
k	A positive number defining the shape parameter.
$\theta$	A positive number defining the scale parameter.

This function is related to the `GammaDist` function in the following way:  
If `prob = GammaDist(value, k,  $\theta$ )`, then `GammaInv(prob, k,  $\theta$ ) = value`

### NormDist

`NormDist()` returns the cumulative normal distribution for the specified mean and standard deviation. If `mean = 0` and `standard_dev = 1`, the function returns the standard normal distribution.

#### Syntax:

```
NORMDIST(value, [mean], [standard_dev], [cumulative])
```

**Return data type:** number

#### Arguments:

#### Arguments

Argument	Description
value	The value at which you want to evaluate the distribution.
mean	Optional value stating the arithmetic mean for the distribution. If you do not state this argument, the default value is 0.

Argument	Description
standard_dev	Optional positive value stating the standard deviation of the distribution. If you do not state this argument, the default value is 1.
cumulative	You can optionally select to use a standard normal distribution or a cumulative distribution.  0 = standard normal distribution  1 = cumulative distribution (default)

This function is related to the **NormInv** function in the following way:  
If  $\text{prob} = \text{NORMDIST}(\text{value}, m, \text{sd})$ , then  $\text{NORMINV}(\text{prob}, m, \text{sd}) = \text{value}$

#### Limitations:

All arguments must be numeric, else NULL will be returned.

Examples and results:

Example	Result
<code>NORMDIST(0.5, 0, 1)</code>	Returns 0.6915

## NormInv

`NORMINV()` returns the inverse of the normal cumulative distribution for the specified mean and standard deviation.

#### Syntax:

```
NORMINV(prob, mean, standard_dev)
```

**Return data type:** number

#### Arguments:

##### Arguments

Argument	Description
prob	A probability associated with the normal distribution. It must be a number between 0 and 1.
mean	A value stating the arithmetic mean for the distribution.
standard_dev	A positive value stating the standard deviation of the distribution.

This function is related to the **NormDist** function in the following way:  
If  $\text{prob} = \text{NORMDIST}(\text{value}, m, \text{sd})$ , then  $\text{NORMINV}(\text{prob}, m, \text{sd}) = \text{value}$

**Limitations:**

All arguments must be numeric, else NULL will be returned.

Examples and results:

Example	Result
NORMINV( 0.6914625, 0, 1 )	Returns 0.5000

## PoissonDist

PoissonDist() returns the accumulated probability of the Poisson distribution.

**Syntax:**

```
PoissonDist (value, mean)
```

**Return data type:** number

## Arguments

Argument	Description
value	The value at which you want to evaluate the distribution. The value must not be negative.
mean	A positive number defining the average outcome.

This function is related to the poissonInv function in the following way:

If  $prob = \text{PoissonDist}(value, mean)$ , then  $\text{PoissonInv}(prob, mean) = value$

## PoissonFrequency

PoissonFrequency() returns the Poisson probability distribution.

**Syntax:**

```
PoissonFrequency (value, mean)
```

**Return data type:** number

## Arguments

Argument	Description
value	The value at which you want to evaluate the distribution. The value must not be negative.
mean	A positive number defining the average outcome.

## PoissonInv

`PoissonInv()` returns the inverse of the accumulated probability of the Poisson distribution.

### Syntax:

```
PoissonInv(prob, mean)
```

**Return data type:** number

#### Arguments

Argument	Description
prob	A probability associated with the Poisson-probability distribution. It must be a number between 0 and 1.
mean	A positive number defining the average outcome.

This function is related to the `POISSONDIST` function in the following way:

If `prob = PoissonDist(value, mean)`, then `PoissonInv(prob, mean) = value`

## TDensity

`TDensity()` returns the value for the student's  $t$  density function where a numeric value is a calculated value of  $t$  for which the probability is to be computed.

### Syntax:

```
TDensity(value, degrees_freedom)
```

**Return data type:** number

#### Arguments

Argument	Description
value	The value at which you want to evaluate the distribution. The value must not be negative.
degrees_freedom	A positive integer stating the number of degrees of freedom.

## TDist

`TDist()` returns the probability for the student's  $t$  distribution where a numeric value is a calculated value of  $t$  for which the probability is to be computed.

### Syntax:

```
TDist(value, degrees_freedom, tails)
```

**Return data type:** number

**Arguments:**

Arguments

Argument	Description
value	The value at which you want to evaluate the distribution. The value must not be negative.
degrees_freedom	A positive integer stating the number of degrees of freedom.
tails	Must be either 1 (one-tailed distribution) or 2 (two-tailed distribution).

This function is related to the **TInv** function in the following way:  
If  $\text{prob} = \text{TDIST}(\text{value}, \text{df}, 2)$ , then  $\text{TINV}(\text{prob}, \text{df}) = \text{value}$

**Limitations:**

All arguments must be numeric, else NULL will be returned.

Examples and results:

Example	Result
$\text{TDIST}(1, 30, 2)$	Returns 0.3253

### TInv

$\text{TINV}()$  returns the  $t$  value of the student's  $t$  distribution as a function of the probability and the degrees of freedom.

**Syntax:**

```
TINV(prob, degrees_freedom)
```

**Return data type:** number

**Arguments:**

Arguments

Argument	Description
prob	A two-tailed probability associated with the t-distribution. It must be a number between 0 and 1.
degrees_freedom	An integer stating the number of degrees of freedom.



### Limitations:

All arguments must be numeric, else NULL will be returned.

This function is related to the **TDist** function in the following way:

If  $\text{prob} = \text{TDIST}(\text{value}, \text{df}, 2)$ , then  $\text{TINV}(\text{prob}, \text{df}) = \text{value}$ .

Examples and results:

Example	Result
<code>TINV(0.3253086, 30)</code>	Returns 1.0000

## 8.24 String functions

This section describes functions for handling and manipulating strings.

All functions can be used in both the data load script and in chart expressions, except for **Evaluate** which can only be used in the data load script.

### String functions overview

Each function is described further after the overview. You can also click the function name in the syntax to immediately access the details for that specific function.

#### Capitalize

**Capitalize()** returns the string with all words in initial uppercase letters.

```
Capitalize (text)
```

#### Chr

**Chr()** returns the Unicode character corresponding to the input integer.

```
Chr (int)
```

#### Evaluate

**Evaluate()** finds if the input text string can be evaluated as a valid Qlik Sense expression, and if so, returns the value of the expression as a string. If the input string is not a valid expression, NULL is returned.

```
Evaluate (expression_text)
```

#### FindOneOf

**FindOneOf()** searches a string to find the position of the occurrence of any character from a set of provided characters. The position of the first occurrence of any character from the search set is returned unless a third argument (with a value greater than 1) is supplied. If no match is found, **0** is returned.

```
FindOneOf (text, char_set[, count])
```

### Hash128

**Hash128()** returns a 128-bit hash of the combined input expression values. The result is a 22-character string.

```
Hash128 (expr{, expression})
```

### Hash160

**Hash160()** returns a 160-bit hash of the combined input expression values. The result is a 27-character string.

```
Hash160 (expr{, expression})
```

### Hash256

**Hash256()** returns a 256-bit hash of the combined input expression values. The result is a 43-character string.

```
Hash256 (expr{, expression})
```

### Index

**Index()** searches a string to find the starting position of the nth occurrence of a provided substring. An optional third argument provides the value of n, which is 1 if omitted. A negative value searches from the end of the string. The positions in the string are numbered from 1 and up.

```
Index (text, substring[, count])
```

### IsJson

**IsJson()** tests whether a specified string contains valid JSON (JavaScript Object Notation) data. You can also validate a specific JSON data type.

```
IsJson (json [, type])
```

### JsonGet

**JsonGet()** returns the path of a JSON (JavaScript Object Notation) data string. The data must be valid JSON but can contain extra spaces or newlines.

```
JsonGet (json, path)
```

### JsonSet

**JsonSet()** modifies a string containing JSON (JavaScript Object Notation) data. It can set or insert a JSON value with the new location specified by the path. The data must be valid JSON but can contain extra spaces or newlines.

```
JsonSet(json, path, value)
```

### KeepChar

**KeepChar()** returns a string consisting of the first string, 'text', less any of the characters NOT contained in the second string, "keep\_chars".

```
KeepChar (text, keep_chars)
```

### Left

**Left()** returns a string consisting of the first (leftmost) characters of the input string, where the number of characters is determined by the second argument.

```
Left (text, count)
```

### Len

**Len()** returns the length of the input string.

```
Len (text)
```

### LevenshteinDist

**LevenshteinDist()** returns the Levenshtein distance between two strings. It is defined as the minimum number of single-character edits (insertions, deletions, or substitutions) required to change one string into the other. The function is useful for fuzzy string comparisons.

```
LevenshteinDist (text1, text2)
```

### Lower

**Lower()** converts all the characters in the input string to lower case.

```
Lower (text)
```

### LTrim

**LTrim()** returns the input string trimmed of any leading spaces.

```
LTrim (text)
```

### Mid

**Mid()** returns the part of the input string starting at the position of the character defined by the second argument, 'start', and returning the number of characters defined by the third argument, 'count'. If 'count' is omitted, the rest of the input string is returned. The first character in the input string is numbered 1.

```
Mid (text, start[, count])
```

### Ord

**Ord()** returns the Unicode code point number of the first character of the input string.

```
Ord (text)
```

### PurgeChar

**PurgeChar()** returns a string consisting of the characters contained in the input string ('text'), excluding any that appear in the second argument ('remove\_chars').

```
PurgeChar (text, remove_chars)
```

### Repeat

**Repeat()** forms a string consisting of the input string repeated the number of times defined by the second argument.

```
Repeat (text[, repeat_count])
```

### Replace

**Replace()** returns a string after replacing all occurrences of a given substring within the input string with another substring. The function is non-recursive and works from left to right.

```
Replace (text, from_str, to_str)
```

### Right

**Right()** returns a string consisting of the last (rightmost) characters of the input string, where the number of characters is determined by the second argument.

```
Right (text, count)
```

### RTrim

**RTrim()** returns the input string trimmed of any trailing spaces.

```
RTrim (text)
```

### SubField

**SubField()** is used to extract substring components from a parent string field, where the original record fields consist of two or more parts separated by a delimiter.

```
SubField (text, delimiter[, field_no ])
```

### SubStringCount

**SubStringCount()** returns the number of occurrences of the specified substring in the input string text. If there is no match, 0 is returned.

```
SubStringCount (text, substring)
```

### TextBetween

**TextBetween()** returns the text in the input string that occurs between the characters specified as delimiters.

```
TextBetween (text, delimiter1, delimiter2[, n])
```

### Trim

**Trim()** returns the input string trimmed of any leading and trailing spaces.

```
Trim (text)
```

### Upper

**Upper()** converts all the characters in the input string to upper case for all text characters in the expression. Numbers and symbols are ignored.

```
Upper (text)
```

## Capitalize

**Capitalize()** returns the string with all words in initial uppercase letters.

### Syntax:

```
Capitalize (text)
```

**Return data type:** string

Example: Chart expressions

Example	Result
Capitalize ( 'star trek' )	Returns 'Star Trek'
Capitalize ( 'AA bb cc Dd' )	Returns 'Aa Bb Cc Dd'

Example: Load script

```
Load
String,
Capitalize(String)
Inline
[String
rHode iSland
washingTon d.C.
new york];
```

**Result**

String	Capitalize(String)
rHode iSland	Rhode Island
washingTon d.C.	Washington D.C.
new york	New York

## Chr

**Chr()** returns the Unicode character corresponding to the input integer.

**Syntax:**

**Chr** (int)

**Return data type:** string

Examples and results:

Example	Result
Chr(65)	Returns the string 'A'
Chr(163)	Returns the string '£'
Chr(35)	Returns the string '#'

## Evaluate

**Evaluate()** finds if the input text string can be evaluated as a valid Qlik Sense expression, and if so, returns the value of the expression as a string. If the input string is not a valid expression, NULL is returned.

### Syntax:

```
Evaluate(expression_text)
```

**Return data type:** dual



*This string function cannot be used in chart expressions.*

Examples and results:

Function example	Result
Evaluate ( 5 * 8 )	Returns '40'

### Load script example

```
Load
Evaluate(String) as Evaluated,
String
Inline
[String
4
5+3
0123456789012345678
Today()
];
```

### Result

String	Evaluated
4	4
5+3	8
0123456789012345678	0123456789012345678
Today()	2022-02-02

## FindOneOf

**FindOneOf()** searches a string to find the position of the occurrence of any character from a set of provided characters. The position of the first occurrence of any character from the search set is returned unless a third argument (with a value greater than 1) is

supplied. If no match is found, **0** is returned.

**Syntax:**

```
FindOneOf(text, char_set[, count])
```

**Return data type:** integer

**Arguments:**

Arguments

Argument	Description
text	The original string.
char_set	A set of characters to search for in text.
count	Defines which occurrence of any of the character to search for. For example, a value of 2 searches for the second occurrence.

Example: Chart expressions

Example	Result
FindOneOf( 'my example text string', 'et%s')	Returns '4' because 'e' is the fourth character in the example string.
FindOneOf( 'my example text string', 'et%s', 3)	Returns '12' because the search is for any of the characters e, t, % or s, and "t" is the third occurrence in position 12 of the example string.
FindOneOf( 'my example text string', 'α%&')	Returns '0' because none of the characters α, %, or & exist in the example string.

Example: Load script

```
Load *
Inline
[SearchFor, Occurrence
et%s,1
et%s,3
α%&,1]
```

**Result**

SearchFor	Occurrence	FindOneOf('my example text string', SearchFor, Occurrence)
et%s	1	4
et%s	3	12
α%&	1	0

## Hash128

**Hash128()** returns a 128-bit hash of the combined input expression values. The result is a 22-character string.

### Syntax:

```
Hash128 (expr{, expression})
```

**Return data type:** string

Example: Chart expressions

Example	Result
Hash128 ('abc', 'xyz', '123')	Returns 'MA&5]6+3=:>:>G%S<U*S2+'.
Hash128 ( Region, Year, Month )	Returns 'G7*=6GKPJ(Z+)^KM?<\$'A+'.
Note: Region, Year, and Month are table fields.	

Example: Load script

```
Hash_128:
Load *,
Hash128(Region, Year, Month) as Hash128;
Load * inline [
Region, Year, Month
abc, xyz, 123
EU, 2022, 01
UK, 2022, 02
US, 2022, 02 ];
```

### Result

Region	Year	Month	Hash128
abc	xyz	123	MA&5]6+3=:>:>G%S<U*S2+
EU	2022	01	B40^K&[T@!;VB'XR]<5=/\$
UK	2022	02	O5T;+1?[B&"F&1//MA[MN!
US	2022	02	C6@#]4#_G-(]J7EQY#KRW0

## Hash160

**Hash160()** returns a 160-bit hash of the combined input expression values. The result is a 27-character string.

### Syntax:

```
Hash160 (expr{, expression})
```



**Return data type:** string

Example: Chart expressions

Example	Result
Hash160 ('abc', 'xyz', '123')	Returns 'MA&5]6+3=:=>;>G%S<U*S2l:`=X*'
Hash160 ( Region, Year, Month ) Note: Region, Year, and Month are table fields.	Returns 'G7*=6GKPJ (Z+)^KM?<\$'Al.)?U\$'

Example: Load script

```
Hash_160:
Load *,
Hash160(Region, Year, Month) as Hash160;
Load * inline [
Region, Year, Month
abc, xyz, 123
EU, 2022, 01
UK, 2022, 02
US, 2022, 02 ];
```

**Result**

Region	Year	Month	Hash160
abc	xyz	123	MA&5]6+3=:=>;>G%S<U*S2l:`=X*
EU	2022	01	B40^K&[T@!;VB'XR]<5=//_F853
UK	2022	02	O5T;+1?[B&"F&1//MA[MN!T"FWZ
US	2022	02	C6@#]4#_G-(]J7EQY#KRW`@KF+W

## Hash256

**Hash256()** returns a 256-bit hash of the combined input expression values. The result is a 43-character string.

**Syntax:**

```
Hash256(expr{, expression})
```

**Return data type:** string

Example: Chart expressions

Example	Result
Hash256 ( 'abc', 'xyz', '123' )	Returns 'MA&5]6+3=:>:>G%S<U*S2I:`=X*A.IO*8N\%Y7Q;YEJ'.
Hash256 ( Region, Year, Month ) Note: Region, Year, and Month are table fields.	Returns 'G7*=6GKPJ(Z+)^KM?<\$'AI.)?U\$#X2RB [:0ZP=+Z`F:'.

Example: Load script

```
Hash_256:
Load *,
Hash256(Region, Year, Month) as Hash256;
Load * inline [
Region, Year, Month
abc, xyz, 123
EU, 2022, 01
UK, 2022, 02
US, 2022, 02 ];
```

**Result**

Region	Year	Month	Hash256
abc	xyz	123	MA&5]6+3=:>:>G%S<U*S2I:`=X*A.IO*8N\%Y7Q;YEJ
EU	2022	01	B40^K&[T@!;VB'XR]<5=//_F853?BE6'G&,YH*T'MF)
UK	2022	02	O5T;+1?[B&"F&1//MA[MN!T"FWZT=4\#V`M%6_\0C>4
US	2022	02	C6@#]4#_G-(]J7EQY#KRW`@KF+W-0]'[Z8R+#'"')=+0

## Index

**Index()** searches a string to find the starting position of the nth occurrence of a provided substring. An optional third argument provides the value of n, which is 1 if omitted. A negative value searches from the end of the string. The positions in the string are numbered from **1** and up.


**Syntax:**

```
Index (text, substring[, count])
```

**Return data type:** integer

**Arguments:**

### Arguments

Argument	Description
text	The original string.
substring	A string of characters to search for in text.  <div style="border: 1px solid #ccc; padding: 5px; margin: 5px 0;">  <i>If the substring does not exist in the text, <b>Index</b> returns 0.</i> </div>
count	Defines which occurrence of <b>substring</b> to search for. For example, a value of 2 searches for the second occurrence.

Examples and results:

Example	Result
Index( 'abcdefg', 'cd' )	Returns 3
Index( 'abcdabcd', 'b', 2)	Returns 6 (the second occurrence of 'b')
Index( 'abcdabcd', 'b', -2)	Returns 2 (the second occurrence of 'b' starting from the end)
Left( Date, Index( Date, '-' ) -1 ) where <b>Date</b> = 1997-07-14	Returns 1997
Mid( Date, Index( Date, '-', 2 ) -2, 2 ) where <b>Date</b> = 1997-07-14	Returns 07
Index('abc', 'x')	Returns 0 ('x' does not exist in the string 'abc')
Index('abc', 'a', 2)	Returns 0 (there is no 2nd occurrence of 'a')

**Example: Script**

```
T1:
Load
*,
index(String, 'cd') as Index_CD,           // returns 3 in Index_CD
index(String, 'b') as Index_B,           // returns 2 in Index_B
index(String, 'b', -1) as Index_B2;      // returns 2 or 6 in Index_B2
Load * inline [
String
abcdefg
abcdabcd ];
```

## IsJson

**IsJson()** tests whether a specified string contains valid JSON (JavaScript Object Notation) data. You can also validate a specific JSON data type.

### Syntax:

```
value IsJson(json [, type])
```

**Return data type:** dual

### Arguments

Argument	Description
json	String to test. It can contain extra spaces or newlines.
type	Optional argument that specifies the JSON data type to test for. <ul style="list-style-type: none"> <li>'value' (default)</li> <li>'object'</li> <li>'array'</li> <li>'string'</li> <li>'number'</li> <li>'Boolean'</li> <li>'null'</li> </ul>

Example: Valid JSON and type

Example	Result
IsJson('null')	Returns -1 (true)
IsJson('"abc"', 'value')	Returns -1 (true)
IsJson('"abc"', 'string')	Returns -1 (true)
IsJson(123, 'number')	Returns -1 (true)

Example: Invalid JSON or type

Example	Result	Description
IsJson('text')	Returns 0 (false)	'text' is not a valid JSON value
IsJson('"text"', 'number')	Returns 0 (false)	""text"" is not a valid JSON number
IsJson('"text"', 'text')	Returns 0 (false)	'text' is not a valid JSON type

## JsonGet

**JsonGet()** returns the path of a JSON (JavaScript Object Notation) data string. The data must be valid JSON but can contain extra spaces or newlines.

### Syntax:

```
value JsonGet(json, path)
```

**Return data type:** dual

### Arguments

Argument	Description
json	String containing JSON data.
path	The path must be specified according to <a href="#">RFC 6901</a> . This will allow lookup of properties inside JSON data without using complex substring or index functions.

Example: Valid JSON and path

Example	Result
JsonGet('{"a":{"foo":"bar"},"b": [123,"abc","ABC"]}', '')	Returns '{"a":{"foo":"bar"},"b": [123,"abc","ABC"]}'
JsonGet('{"a":{"foo":"bar"},"b": [123,"abc","ABC"]}', '/a')	Returns '{"foo":"bar}"
JsonGet('{"a":{"foo":"bar"},"b": [123,"abc","ABC"]}', '/a/foo')	Returns 'bar'
JsonGet('{"a":{"foo":"bar"},"b": [123,"abc","ABC"]}', '/b')	Returns '[123,"abc","ABC"]'
JsonGet('{"a":{"foo":"bar"},"b": [123,"abc","ABC"]}', '/b/0')	Returns '123'
JsonGet('{"a":{"foo":"bar"},"b": [123,"abc","ABC"]}', '/b/1')	Returns 'abc'
JsonGet('{"a":{"foo":"bar"},"b": [123,"abc","ABC"]}', '/b/2')	Returns 'ABC'

Example: Invalid JSON or path

Example	Result	Description
JsonGet('{"a":"b"}', '/b')	Returns null	The path does not point to a valid part of the JSON data.
JsonGet('{"a"}', '/a')	Returns null	The JSON data is not valid JSON (member "a" does not have a value).

## JsonSet

**JsonSet()** modifies a string containing JSON (JavaScript Object Notation) data. It can set or insert a JSON value with the new location specified by the path. The data must be valid JSON but can contain extra spaces or newlines.

### Syntax:

```
value JsonSet(json, path, value)
```

**Return data type:** dual

### Arguments

Argument	Description
json	String containing JSON data.
path	The path must be specified according to <a href="#">RFC 6901</a> . This allows buildup of properties inside JSON data without using complex substring or index functions and concatenation.
value	The new string value in JSON format.

Example: Valid JSON, path, and value

Example	Result
JsonSet('{ }', '/a', '"b"')	Returns '{"a": "b"}'
JsonSet('[ ]', '/0', '"x"')	Returns '['x']'
JsonSet('"abc"', '/', '123')	Returns 123

Example: Invalid JSON, path, or value

Example	Result	Description
JsonSet('"abc"', '/x', '123')	Returns null	The path does not point to a valid part of the JSON data.
JsonSet('{ "a": {"b": "c"} }', 'a/b', '"x"')	Returns null	The path is invalid.
JsonSet('{ "a": "b" }', '/a', 'abc')	Returns null	The value is not valid JSON. A string must be enclosed in quotes.

## KeepChar

**KeepChar()** returns a string consisting of the first string, 'text', less any of the characters NOT contained in the second string, "keep\_chars".

**Syntax:**

```
KeepChar (text, keep_chars)
```

**Return data type:** string**Arguments:**

## Arguments

Argument	Description
text	The original string.
keep_chars	A string containing the characters in text to be kept.

Example: Chart expressions

Example	Result
KeepChar ( 'a1b2c3', '123' )	Returns '123'.
KeepChar ( 'a1b2c3', '1234' )	Returns '123'.
KeepChar ( 'a1b22c3', '1234' )	Returns '1223'.
KeepChar ( 'a1b2c3', '312' )	Returns '123'.

Example: Load script

```
T1:  
Load  
*,  
keepchar(String1, String2) as KeepChar;  
Load * inline [  
String1, String2  
'a1b2c3', '123'  
];
```

**Results**Qlik Sense table showing the output from using the *KeepChar* function in the load script.

String1	String2	KeepChar
a1b2c3	123	123

**See also:**[📄 PurgeChar \(page 1471\)](#)

## Left

**Left()** returns a string consisting of the first (leftmost) characters of the input string, where the number of characters is determined by the second argument.

### Syntax:

```
Left(text, count)
```

**Return data type:** string

### Arguments:

Argument	Description
text	The original string.
count	Defines the number of characters to included from the left-hand part of the string <b>text</b> .

Example: Chart expression

Example	Result
Left('abcdef', 3)	Returns 'abc'

Example: Load script

```
T1:
Load
*,
left(Text,Start) as Left;
Load * inline [
Text, Start
'abcdef', 3
'2021-07-14', 4
'2021-07-14', 2
];
```

### Result

Qlik Sense table showing the output from using the *Left* function in the load script.

Text	Start	Left
abcdef	3	abc
2021-07-14	4	2021
2021-07-14	2	20

☐ See also *Index (page 1458)*, which allows more complex string analysis.

## Len

**Len()** returns the length of the input string.



**Syntax:****Len**(text)**Return data type:** integer

Example: Chart expression

Example	Result
Len('Peter')	Returns '5'

Example: Load script

```
T1:
Load String, First&Second as NewString;
Load *, mid(String,len(First)+1) as Second;
Load *, upper(left(String,1)) as First;
Load * inline [
String
this is a sample text string
capitalize first letter only ];
```

**Result**

String	NewString
this is a sample text string	This is a sample text string
capitalize first letter only	Capitalize first letter only

**LevenshteinDist**

**LevenshteinDist()** returns the Levenshtein distance between two strings. It is defined as the minimum number of single-character edits (insertions, deletions, or substitutions) required to change one string into the other. The function is useful for fuzzy string comparisons.

**Syntax:****LevenshteinDist**(text1, text2)**Return data type:** integer

Example: Chart expression

Example	Result
LevenshteinDist('Kitten','Sitting')	Returns '3'

Example: Load script

### Load script

```
T1:
Load *, recno() as ID;
Load 'Silver' as String_1,* inline [
String_2
Sliver
SSiver
SSiveer ];
```

```
T1:
Load *, recno()+3 as ID;
Load 'Gold' as String_1,* inline [
String_2
Bold
Boo1
Bond ];
```

```
T1:
Load *, recno()+6 as ID;
Load 'Ove' as String_1,* inline [
String_2
Ove
Uve
Üve ];
```

```
T1:
Load *, recno()+9 as ID;
Load 'ABC' as String_1,* inline [
String_2
DEFG
abc
୧୧୧ ];
```

```
set nullinterpret = '<NULL>';
T1:
Load *, recno()+12 as ID;
Load 'X' as String_1,* inline [
String_2
''
<NULL>
1 ];
```

```
R1:
Load
ID,
String_1,
String_2,
LevenshteinDist(String_1, String_2) as LevenshteinDistance
resident T1;
```

```
Drop table T1;
```

**Result**

ID	String_1	String_2	LevenshteinDistance
1	Silver	Sliver	2
2	Silver	SSiver	2
3	Silver	SSiveer	3
4	Gold	Bold	1
5	Gold	Bool	3
6	Gold	Bond	2
7	Ove	Ove	0
8	Ove	Uve	1
9	Ove	Üve	1
10	ABC	DEFG	4
11	ABC	abc	3
12	ABC	ピピピ	3
13	X		1
14	X	-	1
15	X	1	1

**Lower**

**Lower()** converts all the characters in the input string to lower case.

**Syntax:**

**Lower** (text)

**Return data type:** string

Example: Chart expression

Example	Result
Lower('abcd')	Returns 'abcd'

Example: Load script

```
Load
String,
Lower(String)
Inline
[String
rHode iSland
```

```
washingTon d.c.
new york];
```

**Result**

String	Lower(String)
rHode iSland	rhode island
washingTon d.C.	washington d.c.
new york	new york

**LTrim**

**LTrim()** returns the input string trimmed of any leading spaces.

**Syntax:**

```
LTrim(text)
```

**Return data type:** string

Example: Chart expressions

Example	Result
LTrim( ' abc' )	Returns 'abc'
LTrim( 'abc ' )	Returns 'abc '

Example: Load script

```
set verbatim=1;
T1:

Load *,
len(LtrimString) as LtrimStringLength;
Load *,
ltrim(String) as LtrimString;
Load *,
len(String) as StringLength;
Load * Inline [
String
' abc '
' def '];
```




The "Set verbatim=1" statement is included in the example to ensure that the spaces are not automatically trimmed before the demonstration of the ltrim function. See Verbatim (page 209) for more information.

**Result**

String	StringLength	LtrimStringLength
def	6	5
abc	10	7

**See also:**

 [RTrim \(page 1474\)](#)

**Mid**

**Mid()** returns the part of the input string starting at the position of the character defined by the second argument, 'start', and returning the number of characters defined by the third argument, 'count'. If 'count' is omitted, the rest of the input string is returned. The first character in the input string is numbered 1.

**Syntax:**

```
Mid(text, start[, count])
```

**Return data type:** string

**Arguments:**

## Arguments

Argument	Description
text	The original string.
start	Integer defining the position of the first character in text to include.
count	Defines the string length of the output string. If omitted, all characters from the position defined by <b>start</b> are included.

Example: Chart expressions

Example	Result
<code>Mid('abcdef', 3 )</code>	Returns 'cdef'
<code>Mid('abcdef', 3, 2 )</code>	Returns 'cd'

Example: Load script

```
T1:
Load *,
mid(Text,start) as Mid1,
mid(Text,start,Count) as Mid2;
Load * inline [
```

```
Text, Start, Count
'abcdef', 3, 2
'abcdef', 2, 3
'210714', 3, 2
'210714', 2, 3
];
```

### Result

Qlik Sense table showing the output from using the *Mid* function in the load script.

Text	Start	Mid1	Count	Mid2
abcdef	2	bcdef	3	bcd
abcdef	3	cdef	2	cd
210714	2	10714	3	107
210714	3	0714	2	07

### See also:

[Index \(page 1458\)](#)

## Ord

**Ord()** returns the Unicode code point number of the first character of the input string.

### Syntax:

```
Ord(text)
```

**Return data type:** integer

Examples and results:

### Example: Chart expression

Example	Result
ord('A')	Returns the integer 65.
ord('Ab')	Returns the integer 65.

### Example: Load script

```
//Guqin (Chinese: 古琴) - 7-stringed zithers
T2:
Load *,
ord(Chinese) as OrdUnicode,
ord(Western) as OrdASCII;
Load * inline [
Chinese, western
```

古琴, Guqin ];

Result:

Chinese	Western	OrdASCII	OrdUnicode
古琴	Guqin	71	21476

## PurgeChar

**PurgeChar()** returns a string consisting of the characters contained in the input string ('text'), excluding any that appear in the second argument ('remove\_chars').

### Syntax:

```
PurgeChar (text, remove_chars)
```

**Return data type:** string

### Arguments:

#### Arguments

Argument	Description
text	The original string.
remove_chars	A string containing the characters in text to be removed.

**Return data type:** string

Example: Chart expressions

Example	Result
PurgeChar ( 'a1b2c3', '123' )	Returns 'abc'.
PurgeChar ( 'a1b2c3', '312' )	Returns 'abc'.

Example: Load script

```
T1:
Load
*,
purgechar(String1, String2) as PurgeChar;
Load * inline [
String1, String2
'a1b2c3', '123'
];
```

**Results**

Qlik Sense table showing the output from using the *PurgeChar* function in the load script.

String1	String2	PurgeChar
a1b2c3	123	abc

**See also:**

[KeepChar \(page 1462\)](#)

## Repeat

**Repeat()** forms a string consisting of the input string repeated the number of times defined by the second argument.

**Syntax:**

```
Repeat (text [, repeat_count])
```

**Return data type:** string

**Arguments:**

## Arguments

Argument	Description
text	The original string.
repeat_count	Defines the number of times the characters in the string <b>text</b> are to be repeated in the output string.

Example: Chart expression

Example	Result
Repeat( ' * ', rating ) when <b>rating</b> = 4	Returns '****'

Example: Load script

```
T1:
Load *,
repeat(String,2) as Repeat;
Load * inline [
String
hello world!
hOw aRE you? ];
```



**Result**

String	Repeat
hello world!	hello world!hello world!
hOw aRe you?	hOw aRe you?hOw aRe you?

## Replace

**Replace()** returns a string after replacing all occurrences of a given substring within the input string with another substring. The function is non-recursive and works from left to right.

**Syntax:**

```
Replace(text, from_str, to_str)
```

**Return data type:** string

**Arguments:**

## Arguments

Argument	Description
text	The original string.
from_str	A string that may occur one or more times within the input string <b>text</b> .
to_str	The string that will replace all occurrences of <b>from_str</b> within the string <b>text</b> .

Examples and results:

Example	Result
Replace('abccde', 'cc', 'xyz')	Returns 'abxyzde'

**See also:**

## Right

**Right()** returns a string consisting of the last (rightmost) characters of the input string, where the number of characters is determined by the second argument.

**Syntax:**

```
Right(text, count)
```

**Return data type:** string

**Arguments:**

Arguments

Argument	Description
text	The original string.
count	Defines the number of characters to be included from the rightmost part of the string <b>text</b> .

Example: Chart expression

Example	Result
Right('abcdef', 3)	Returns 'def'

Example: Load script

```
T1:
Load
*,
right(Text,Start) as Right;
Load * inline [
Text, Start
'abcdef', 3
'2021-07-14', 4
'2021-07-14', 2
];
```

**Result**

Qlik Sense table showing the output from using the *Right* function in the load script.

Text	Start	Right
abcdef	3	def
2021-07-14	4	7-14
2021-07-14	2	14

## RTrim

**RTrim()** returns the input string trimmed of any trailing spaces.

**Syntax:**

**RTrim**(text)

**Return data type:** string

Example: Chart expressions

Example	Result
<code>RTrim( ' abc' )</code>	Returns 'abc'
<code>RTrim( 'abc ' )</code>	Returns 'abc'

Example: Load script

```
set verbatim=1;
```

T1:

```
Load *, len(RtrimString) as RtrimStringLength;
Load *, rtrim(String) as RtrimString;
Load *, len(String) as StringLength;
Load * Inline [
String
' abc '
' def '];
```



*The "Set verbatim=1" statement is included in the example to ensure that the spaces are not automatically trimmed before the demonstration of the rtrim function. See Verbatim (page 209) for more information.*

### Result

String	StringLength	RtrimStringLength
def	6	4
abc	10	6

### See also:

[LTrim \(page 1468\)](#)

## SubField

**SubField()** is used to extract substring components from a parent string field, where the original record fields consist of two or more parts separated by a delimiter.

The **Subfield()** function can be used, for example, to extract first name and surname from a list of records consisting of full names, the component parts of a path name, or for extracting data from comma-separated tables.

If you use the **Subfield()** function in a **LOAD** statement with the optional `field_no` parameter left out, one full record will be generated for each substring. If several fields are loaded using **Subfield()** the Cartesian products of all combinations are created.

### Syntax:

```
SubField(text, delimiter[, field_no ])
```

**Return data type:** string

### Arguments:

#### Arguments

Argument	Description
text	The original string. This can be a hard-coded text, a variable, a dollar-sign expansion, or another expression.
delimiter	A character within the input <b>text</b> that divides the string into component parts.
field_no	The optional third argument is an integer that specifies which of the substrings of the parent string <b>text</b> is to be returned. Use the value 1 to return the first substring, 2 to return the second substring, and so on. <ul style="list-style-type: none"> <li>• If <b>field_no</b> is a positive value, substrings are extracted from left to right.</li> <li>• If <b>field_no</b> is a negative value, substrings are extracted from right to left.</li> </ul>



*SubField() can be used instead of using complex combinations of functions such as Len(), Right(), Left(), Mid(), and other string functions.*

### Examples: Script and chart expressions using SubField

Examples - script and chart expressions

#### Basic examples

Example	Result
<code>SubField(S, ';' ,2)</code>	Returns 'cde' if <b>S</b> is 'abc;cde;efg'.
<code>SubField(S, ';' ,1)</code>	Returns an empty string if <b>S</b> is an empty string.
<code>SubField(S, ';' ,1)</code>	Returns an empty string if <b>S</b> is ';'.

Example	Result
<p>Suppose you have a variable that holds a path name vMyPath,</p> <pre>set vMyPath=\Users\ext_ jrb\Documents\Qlik\Sense\Apps;.</pre>	<p>In a text &amp; image chart, you can add a measure such as: <code>subField(vMyPath, '\', -3)</code>, which results in 'Qlik', because it is the substring third from the right-hand end of the variable vMyPath.</p>

### Script example 1

#### Load script

Load the following script expressions and data in the data load editor.

FullName:

```
LOAD * inline [
Name
'Dave Owen'
'Joe Tem'
];
```

SepNames:

```
Load Name,
SubField(Name, ' ',1) as FirstName,
SubField(Name, ' ',-1) as SurName
Resident FullName;
Drop Table FullName;
```

#### Create a visualization

Create a table visualization in a Qlik Sense sheet with **Name**, **FirstName**, and **SurName** as dimensions.

#### Result

Name	FirstName	SurName
Dave Owen	Dave	Owen
Joe Tem	Joe	Tem

#### Explanation

The **SubField()** function extracts the first substring of **Name** by setting the **field\_no** argument to 1. Since the value of **field\_no** is positive, a left to right order is followed for extracting the substring. A second function call extracts the second substring by setting the **field\_no** argument to -1, which extracts the substring following a right to left order.

### Script example 2

#### Load script

Load the following script expressions and data in the data load editor.

```
LOAD DISTINCT
Instrument,
SubField(Player,',') as Player,
SubField(Project,',') as Project;
```

```
Load * inline [
Instrument|Player|Project
Guitar|Neil, Mike|Music, Video
Guitar|Neil|Music, OST
Synth|Neil, Jen|Music, Video, OST
Synth|Jo|Music
Guitar|Neil, Mike|Music, OST
] (delimiter is '|');
```

#### Create a visualization

Create a table visualization in a Qlik Sense sheet with **Instrument**, **Player**, and **Project** as dimensions.

#### Result

Instrument	Player	Project
Guitar	Mike	Music
Guitar	Mike	Video
Guitar	Mike	OST
Guitar	Neil	Music
Guitar	Neil	Video
Guitar	Neil	OST
Synth	Jen	Music
Synth	Jen	Video
Synth	Jen	OST
Synth	Jo	Music
Synth	Neil	Music
Synth	Neil	Video
Synth	Neil	OST

### Explanation

This example shows how using multiple instances of the **Subfield()** function, each with the `field_no` parameter left out, from within the same **LOAD** statement creates Cartesian products of all combinations. The **DISTINCT** option is used to avoid creating duplicate records.

### SubStringCount

**SubStringCount()** returns the number of occurrences of the specified substring in the input string `text`. If there is no match, 0 is returned.

#### Syntax:

```
SubStringCount(text, sub_string)
```

**Return data type:** integer

#### Arguments:

Argument	Description
text	The original string.
sub_string	A string which may occur one or more times within the input string <b>text</b> .

Example: Chart expressions

Example	Result
<code>SubStringCount ( 'abcdefgdcxyz', 'cd' )</code>	Returns '2'
<code>SubStringCount ( 'abcdefgdcxyz', 'dc' )</code>	Returns '0'

Example: Load script

```
T1:
Load *,
substringcount(upper(Strings),'AB') as SubStringCount_AB;
Load * inline [
Strings
ABC:DEF:GHI:AB:CD:EF:GH
aB/cd/ef/gh/Abc/abandoned ];
```

#### Result

Strings	SubStringCount_AB
aB/cd/ef/gh/Abc/abandoned	3
ABC:DEF:GHI:AB:CD:EF:GH	2

## TextBetween

**TextBetween()** returns the text in the input string that occurs between the characters specified as delimiters.

### Syntax:

```
TextBetween(text, delimiter1, delimiter2[, n])
```

**Return data type:** string

### Arguments:

Argument	Description
text	The original string.
delimiter1	Specifies the first delimiting character (or string) to search for in <b>text</b> .
delimiter2	Specifies the second delimiting character (or string) to search for in <b>text</b> .
n	Defines which occurrence of the delimiter pair to search between. For example, a value of 2 returns the characters between the second occurrence of delimiter1 and the second occurrence of delimiter2.

Example: Chart expressions

Example	Result
<code>TextBetween('&lt;abc&gt;', '&lt;', '&gt;')</code>	Returns 'abc'
<code>TextBetween('&lt;abc&gt;&lt;de&gt;', '&lt;', '&gt;', 2)</code>	Returns 'de'
<code>TextBetween('abc', '&lt;', '&gt;')</code> <code>TextBetween('&lt;a&lt;b', '&lt;', '&gt;')</code>	Both examples return NULL.  If any of the delimiter is not found in the string, NULL is returned.
<code>TextBetween('&lt;&gt;', '&lt;', '&gt;')</code>	Returns a zero-length string.
<code>TextBetween('&lt;abc&gt;', '&lt;', '&gt;', 2)</code>	Returns NULL, as n is greater than the number of occurrences of the delimiters.

Example: Load script

```
Load *,
textbetween(Text, '<', '>') as TextBetween,
textbetween(Text, '<', '>', 2) as SecondTextBetween;
Load * inline [
Text
<abc><de>
<def><ghi><jkl> ];
```



**Result**

Text	TextBetween	SecondTextBetween
<abc><de>	abc	de
<def><ghi><jkl>	def	ghi

**Trim**

**Trim()** returns the input string trimmed of any leading and trailing spaces.

**Syntax:**

```
Trim(text)
```

**Return data type:** string

Examples and results:

**Example: Chart expression**

Example	Result
Trim( ' abc' )	Returns 'abc'
Trim( 'abc ' )	Returns 'abc'
Trim( ' abc ' )	Returns 'abc'

**Example: Load script**

```
set verbatim=1;

T1:
Load *, len(TrimString) as TrimStringLength;
Load *, trim(String) as TrimString;
Load *, len(String) as StringLength;
Load * inline [
String
' abc '
' def '](delimiter is '\t');
```



The "Set verbatim=1" statement is included in the example to ensure that the spaces are not automatically trimmed before the demonstration of the trim function. See *Verbatim* (page 209) for more information.

Result:

String	StringLength	TrimStringLength
def	6	3
abc	10	3

## Upper

**Upper()** converts all the characters in the input string to upper case for all text characters in the expression. Numbers and symbols are ignored.

### Syntax:

**Upper** (text)

**Return data type:** string

Example: Chart expression

Example	Result
Upper(' abcD')	Returns 'ABCD'

Example: Load script

```
Load
String,Upper(String)
Inline
[String
rHode iSland
washingTon d.C.
new york];
```

### Result

String	Upper(String)
rHode iSland	RHODE ISLAND
washingTon d.C.	WASHINGTON D.C.
new york	NEW YORK

## 8.25 System functions

System functions provide functions for accessing system, device and Qlik Sense app properties.

### System functions overview

Some of the functions are described further after the overview. For those functions, you can click the function name in the syntax to immediately access the details for that specific function.

### Author()

This function returns a string containing the author property of the current app. It can be used in both the data load script and in a chart expression.



*Author property can not be set in the current version of Qlik Sense. If you migrate a QlikView document, the author property will be retained.*

### ClientPlatform()

This function returns the user agent string of the client browser. It can be used in both the data load script and in a chart expression.

### Example:

```
Mozilla/5.0 (Windows NT 6.1; WOW64) AppleWebKit/537.36 (KHTML, like Gecko)
Chrome/35.0.1916.114 Safari/537.36
```

### ComputerName

This function returns a string containing the name of the computer as returned by the operating system. It can be used in both the data load script and in a chart expression.



*If the name of the computer has more than 15 characters, the string will only contain the first 15 characters.*

### ComputerName ( )

### DocumentName

This function returns a string containing the name of the current Qlik Sense app, without path but with extension. It can be used in both the data load script and in a chart expression.

### DocumentName ( )

### DocumentPath

This function returns a string containing the full path to the current Qlik Sense app. It can be used in both the data load script and in a chart expression.

### DocumentPath ( )



*This function is not supported in standard mode. .*

### DocumentTitle

This function returns a string containing the title of the current Qlik Sense app. It can be used in both the data load script and in a chart expression.

### DocumentTitle ( )

### EngineVersion

This function returns the full Qlik Sense engine version as a string.

**EngineVersion** ( )

### GetCollationLocale

This script function returns the culture name of the collation locale that is used. If the variable CollationLocale has not been set, the actual user machine locale is returned.

**GetCollationLocale** ( )

### GetObjectField

**GetObjectField()** returns the name of the dimension. **Index** is an optional integer denoting the dimension that should be returned.

**GetObjectField - chart function**([index])

### GetRegistryString

This function returns the value of a key in the Windows registry. It can be used in both the data load script and in a chart expression.

**GetRegistryString**(path, key)



*This function is not supported in standard mode. .*

### GetSysAttr

This function returns the tenant and space domain attributes for a selected app. It can be used in both the data load script and in a chart expression.

**GetSysAttr** (name)



*If you use this function in Qlik Sense Client-Managed, it only returns empty data values.*

### GroupDimensionIndex

This function returns the index of the active field for the specified cyclic dimension. The first field has index value of 1. Enter the name of the cyclic dimension in single quotes. It can only be used in a chart expression.

**GroupDimensionIndex**(dim\_name Expression)

### GroupDimensionLabel

This function returns the field label of current step in the specified cyclic dimension. Enter the name of the cyclic dimension in single quotes. It can only be used in a chart expression.

**GroupDimensionLabel**(dim\_name Expression)

### IsPartialReload

This function returns - 1 (True) if the current reload is partial, otherwise 0 (False).

**IsPartialReload** ( )

### InObject

The **InObject()** chart function evaluates whether or not the current object is contained inside another object with the ID specified in the function argument. The object can be a sheet or a visualization.

```
InObject - chart function(id_str)
```

### ObjectId

The **ObjectId()** chart function returns the ID of the object in which the expression is evaluated. The function takes an optional argument specifying which type of object the function concerns. The object can be a sheet or a visualization. This function is only available in chart expressions.

```
ObjectId - chart function([object_type_str])
```

### OSUser

This function returns a string containing the name of the user that is currently connected. It can be used in both the data load script and in a chart expression.

```
OSUser ( )
```



*In Qlik Sense Desktop and Qlik Sense Client-Managed Mobile, this function always returns 'Personal\Me'.*

### ProductVersion

This function returns the full Qlik Sense version and build number as a string.

This function is deprecated and replaced by **EngineVersion()**.

```
ProductVersion ( )
```

### ReloadTime

This function returns a timestamp for when the last data load finished. It can be used in both the data load script and in a chart expression.

```
ReloadTime ( )
```

### StateName

**StateName()** returns the name of the alternate state of the visualization in which it is used.

StateName can be used, for example, to create visualizations with dynamic text and colors to reflect when the state of a visualization is changed. This function can be used in chart expressions, but cannot be used to determine the state that the expression refers to.

```
StateName - chart function()
```

## EngineVersion

This function returns the full Qlik Sense engine version as a string.

### Syntax:

```
EngineVersion()
```

### GetSysAttr

This function returns the tenant and space domain attributes for a selected app. It can be used in both the data load script and in a chart expression.

If you use this function in Qlik Sense Client-Managed, it returns empty data values. Therefore, you can use the function to develop load scripts in Qlik Sense Client-Managed without encountering errors, to later upload the apps to Qlik Cloud.

To access the full documentation for the Qlik Cloud function, see [GetSysAttr - script and chart function](#).

### InObject - chart function

The **InObject()** chart function evaluates whether or not the current object is contained inside another object with the ID specified in the function argument. The object can be a sheet or a visualization.

This function can be used to show the hierarchy of objects in a sheet, from the top-level sheet object to visualizations nested within other visualizations. This function can be used alongside the **if** and **ObjectId** functions to create custom navigation in your apps.

#### Syntax:

```
InObject(id_str)
```

**Return data type:** Boolean


In Qlik Sense, the Boolean true value is represented by -1, and the false value is represented by 0.

#### Arguments

Argument	Description
id_str	A string value representing the ID of the object being evaluated.

The sheet ID can be obtained from the app URL. For visualizations, use the **Developer** options to identify the object ID and the text string of the object type.

#### Do the following:

1. In analysis mode, add the following text to your URL:  
*/options/developer*
2. Right-click a visualization and click  **Developer**.
3. Under **Properties**, obtain the object ID from the dialog header, and the object type from the **"qType"** property.

**Limitations:**

This function can give unexpected results when invoked in an object (for example, a button) inside a container which is a master item. This limitation also applies to filter pane master items, which are containers for a number of listboxes. This is because of how master items use the object hierarchy.

**InObject()** is often used in combination with the following functions:

Related functions

Function	Interaction
<i>if (page 567)</i>	The <b>if</b> and <b>ObjectId</b> functions can be used together to create conditional expressions. For example, visualizations might achieve conditional coloring through expressions using these functions.
<i>ObjectId - chart function (page 1490)</i>	Similar to <b>if</b> , <b>ObjectId</b> is also used with <b>InObject</b> to create conditional expressions.

### Example 1 – Basic functionality

Chart expression and results

The following basic example demonstrates how to determine whether an object is contained inside another object. In this case, we will be checking if a **Text & image** object resides in a sheet object using the ID of the sheet as an argument.

### Do the following:

1. Open a new sheet and drag a **Text & image** chart onto the sheet.
2. In the properties panel, click **Add measure**.
3. Click  $f^x$  to open the expression editor.
4. Paste the following expression into the dialog:  
`=Inobject()`
5. Modify the expression to include the ID of your sheet as a string between the parentheses.  
For example, for a sheet with ID 1234-5678, you would use the following:  
`=Inobject('1234-5678')`
6. Click **Apply**.

The value -1 is displayed in the chart, indicating that the expression was evaluated to be true.

### Example 2 – Objects with conditional colors

Chart expression and results

#### Overview

The following example demonstrates how to create custom navigation buttons showing different coloring to indicate the sheet that is currently open.

Start by creating a new app and opening the Data load editor. Paste the following load script into a new tab. Note that the data itself is a placeholder and will not be used in the example content.

#### Load script

Transactions:

```
Load
*
Inline
[
id,date,amount
8188,'1/19/2022',37.23
8189,'1/7/2022',17.17
8190,'2/28/2022',88.27
8191,'2/5/2022',57.42
8192,'3/16/2022',53.80
8193,'4/1/2022',82.06
8194,'4/7/2022',40.39
8195,'5/16/2022',87.21
8196,'6/15/2022',95.93
8197,'7/26/2022',45.89
8198,'8/9/2022',36.23
8199,'9/22/2022',25.66
8200,'11/23/2022',82.77
8201,'12/27/2022',69.98
8202,'1/1/2023',76.11
```



```
8203, '2/8/2022', 25.12
8204, '3/19/2022', 46.23
8205, '6/26/2022', 84.21
8206, '9/14/2022', 96.24
8207, '11/29/2022', 67.67
];
```


### Creating the visualizations


Load the data and create two new sheets. Title them *Sales 2022* and *Sales 2023* respectively.

Next, build two button objects that will be used to navigate between the two sheets.

#### Do the following:

1. Add two **Button** objects to the sheet.
2. Under **Appearance > General**, set the **Label** of each button to *Sales 2022* and *Sales 2023*, respectively.
3. Arrange the buttons to match the following image.  
*Sales 2022 sheet arrangement with two navigation buttons*



4. Select the *Sales 2022* button, and expand **Actions and navigation** in the properties panel.
5. Click **Add action** and under **Navigation**, select **Go to a sheet**.
6. Under **Sheet**, select *Sales 2022*.
7. Repeat this button action setup to link the **Sales 2023** button to the *Sales 2023* sheet.
8. Convert the buttons to master items by right-clicking them and selecting  **Add to master items**.

You can now copy each button and paste it in the *Sales 2023* sheet, using the same size and arrangement on the sheet.

### Creating conditional colors

Next, configure the buttons so that they will be blue if they are linked to the currently open sheet, and light gray if linked to the sheet that is not open.

#### Do the following:


1. Open the *Sales 2022* sheet and obtain the sheet ID from the URL. Keep the *Sales 2022* sheet open.
2. Click the **Sales 2022** button master item and select **Edit** in the properties panel.
3. Under **Appearance > Background**, select to color the button **By expression**.
4. In **Expression**, paste the following text:  
`=if(InObject(""), Blue(), LightGray())`
5. Between the parentheses in the above expression, paste the sheet ID for the *Sales 2022* sheet.

The button is now configured to turn blue when the *Sales 2022* sheet is open, and light gray when it is not open.

Repeat the above instructions for the *Sales 2023* sheet, linking the **Sales 2023** button master item to the *Sales 2023* sheet ID.

Each sheet should now have two buttons indicating the currently open sheet with the color blue.

*Sales 2022 sheet with blue coloring to indicate that Sales 2022 is currently displayed*



### IsPartialReload

This function returns - 1 (True) if the current reload is partial, otherwise 0 (False).

#### Syntax:

```
IsPartialReload()
```

### ObjectId - chart function

The **ObjectId()** chart function returns the ID of the object in which the expression is evaluated. The function takes an optional argument specifying which type of object the function concerns. The object can be a sheet or a visualization. This function is only available in chart expressions.

#### Syntax:

```
ObjectId([object_type_str])
```

**Return data type:** string

The function's only argument, **object\_type\_str**, is optional and refers to a string value representing the type of the object.


Arguments

Argument	Description
<b>object_type_str</b>	A string value representing the type of the object being evaluated.

If no argument is specified in the function expression, **ObjectId()** returns the ID of the object in which the expression is used. To return the ID of the sheet object within which the visualization appears, use *ObjectId('sheet')*.

In the case of visualization objects nested within other visualization objects, specify the desired object type in the function argument for different results. For example, for a **Text & image** chart within a container, use *'text-image'* to return the **Text & image** object and *'container'* to return the ID of the container.

### Do the following:

1. In analysis mode, add the following text to your URL:  
*/options/developer*
2. Right-click a visualization and click  **Developer**.
3. Under **Properties**, obtain the object ID from the dialog header, and the object type from the **"qType"** property.

### Limitations:

This function can give unexpected results when invoked in an object (for example, a button) inside a container which is a master item. This limitation also applies to filter pane master items, which are containers for a number of listboxes. This is because of how master items use the object hierarchy.

The chart expression *ObjectId('sheet')* will return an empty string in those cases, whereas *ObjectId('masterobject')* will show the identifier of the owning master item.

**ObjectId()** is often used in combination with the following functions:

## Related functions

Function	Interaction
<i>if</i> (page 567)	The <b>if</b> and <b>ObjectId</b> functions can be used together to create conditional expressions. For example, visualizations might achieve conditional coloring through expressions using these functions.
<i>InObject - chart function</i> (page 1486)	Similar to <b>if</b> , <b>InObject</b> is also used with <b>ObjectId</b> to create conditional expressions.

## Example 1 – Return chart object ID

Chart expression and results

The following basic example demonstrates how to return the ID of a visualization.

**Do the following:**

1. Open a new sheet and drag a **Text & image** chart onto the sheet.
2. In the properties panel, click **Add measure**.
3. Click  $f^x$  to open the expression editor.
4. Paste the following expression into the dialog:  
=ObjectId()
5. Click **Apply**.

The ID of the **Text & image** object is displayed in the visualization.

The same result can be achieved with the following expression:

```
=ObjectId('text-image')
```

### Example 2 – Return sheet ID

Chart expression and results

The following basic example demonstrates how to return the ID of the sheet in which a visualization appears.

#### Do the following:

1. Open a new sheet and drag a **Text & image** chart onto the sheet.
2. In the properties panel, click **Add measure**.
3. Click  $f^x$  to open the expression editor.
4. Paste the following expression into the dialog:  
`=ObjectId('sheet')`
5. Click **Apply**.

The ID of the sheet is displayed in the visualization.

### Example 3 – Nested expression

Chart expression and results

The following example shows how the **ObjectId()** function can be nested inside other expressions.

#### Do the following:

1. Open a new sheet and drag a **Text & image** chart onto the sheet.
2. In the properties panel, click **Add measure**.
3. Click  $f^x$  to open the expression editor.
4. Paste the following expression into the dialog:  
`=if(InObject(ObjectId('text-image')), 'In Text & image', 'Not in Text & image')`
5. Click **Apply**.

The text *In Text & image* appears in the chart, indicating that the object referenced in the expression is a **Text & image** chart.

For a more detailed example using conditional coloring, see the example on *InObject - chart function* (page 1486).

## ProductVersion

This function returns the full Qlik Sense version and build number as a string. This function is deprecated and replaced by **EngineVersion()**.

#### Syntax:

```
ProductVersion()
```

### StateName - chart function

**StateName()** returns the name of the alternate state of the visualization in which it is used. StateName can be used, for example, to create visualizations with dynamic text and colors to reflect when the state of a visualization is changed. This function can be used in chart expressions, but cannot be used to determine the state that the expression refers to.

#### Syntax:

```
StateName ()
```

#### Example 1:

```
Dynamic Text
='Region - ' & if(StateName() = '$', 'Default', StateName())
```

#### Example 2:

```
Dynamic Colors
if(StateName() = 'Group 1', rgb(152, 171, 206),
  if(StateName() = 'Group 2', rgb(187, 200, 179),
    rgb(210, 210, 210)
  )
)
```

## 8.26 Table functions

The table functions return information about the data table which is currently being read. If no table name is specified and the function is used within a **LOAD** statement, the current table is assumed.

All functions can be used in the data load script, while only **NoOfRows** can be used in a chart expression.

### Table functions overview

Some of the functions are described further after the overview. For those functions, you can click the function name in the syntax to immediately access the details for that specific function.

#### FieldName

The **FieldName** script function returns the name of the field with the specified number within a previously loaded table. If the function is used within a **LOAD** statement, it must not reference the table currently being loaded.

```
FieldName (field_number ,table_name)
```

### FieldNumber

The **FieldNumber** script function returns the number of a specified field within a previously loaded table. If the function is used within a **LOAD** statement, it must not reference the table currently being loaded.

```
FieldNumber (field_name ,table_name)
```

### NoOfFields

The **NoOfFields** script function returns the number of fields in a previously loaded table. If the function is used within a **LOAD** statement, it must not reference the table currently being loaded.

```
NoOfFields (table_name)
```

### NoOfRows

The **NoOfRows** function returns the number of rows (records) in a previously loaded table. If the function is used within a **LOAD** statement, it must not reference the table currently being loaded.

```
NoOfRows (table_name)
```

### NoOfTables

This script function returns the number of tables previously loaded.

```
NoOfTables ()
```

### TableName

This script function returns the name of the table with the specified number.

```
TableName (table_number)
```

### TableNumber

This script function returns the number of the specified table. The first table has number 0.

If table\_name does not exist, NULL is returned.

```
TableNumber (table_name)
```

### Example:

In this example, we want to create a table with information about the tables and fields that have been loaded.

First we load some sample data. This creates the two tables that will be used to illustrate the table functions described in this section.

Characters:

```
Load Chr(RecNo()+Ord('A')-1) as Alpha, RecNo() as Num autogenerate 26;
```

ASCII:

```
Load  
  if(RecNo()>=65 and RecNo()<=90,RecNo()-64) as Num,  
  Chr(RecNo()) as AsciiAlpha,  
  RecNo() as AsciiNum
```

```
autogenerate 255
where (RecNo())>=32 and RecNo()<=126) or RecNo()>=160 ;
```

Next, we iterate through the tables that have been loaded, using the **NoOfTables** function, and then through the fields of each table, using the **NoOfFields** function, and load information using the table functions.

```
//Iterate through the loaded tables
For t = 0 to NoOfTables() - 1

//Iterate through the fields of table
For f = 1 to NoOfFields(TableName$(t))
  Tables:
  Load
  TableName$(t) as Table,
  TableNumber(TableName$(t)) as TableNo,
  NoOfRows(TableName$(t)) as TableRows,
  FieldName$(f),TableName$(t) as Field,
  FieldNumber(FieldName$(f),TableName$(t)),TableName$(t) as FieldNo
  Autogenerate 1;
Next f
Next t;
```

The resulting table Tables will look like this:

Load table

Table	TableNo	TableRows	Field	FieldNo
Characters	0	26	Alpha	1
Characters	0	26	Num	2
ASCII	1	191	Num	1
ASCII	1	191	AsciiAlpha	2
ASCII	1	191	AsciiNum	3

### FieldName

The **FieldName** script function returns the name of the field with the specified number within a previously loaded table. If the function is used within a **LOAD** statement, it must not reference the table currently being loaded.

#### Syntax:

```
FieldName(field_number ,table_name)
```

#### Arguments:

Arguments

Argument	Description
field_number	The field number of the field you want to reference.
table_name	The table containing the field you want to reference.



**Example:**

```
LET a = FieldName(4,'tab1');
```

## FieldNumber

The **FieldNumber** script function returns the number of a specified field within a previously loaded table. If the function is used within a **LOAD** statement, it must not reference the table currently being loaded.

**Syntax:**

```
FieldNumber(field_name , table_name)
```

**Arguments:**

## Arguments

Argument	Description
field_name	The name of the field.
table_name	The name of the table containing the field.

If the field field\_name does not exist in table\_name, or table\_name does not exist, the function returns 0.

**Example:**

```
LET a = FieldNumber('Customer','tab1');
```

## NoOfFields

The **NoOfFields** script function returns the number of fields in a previously loaded table. If the function is used within a **LOAD** statement, it must not reference the table currently being loaded.

**Syntax:**

```
NoOfFields(table_name)
```

**Arguments:**

## Arguments

Argument	Description
table_name	The name of the table.

**Example:**

```
LET a = NoOfFields('tab1');
```

## NoOfRows

The **NoOfRows** function returns the number of rows (records) in a previously loaded table. If the function is used within a **LOAD** statement, it must not reference the table currently being loaded.

### Syntax:

```
NoOfRows (table_name)
```

### Arguments:

Arguments	
Argument	Description
table_name	The name of the table.

### Example:

```
LET a = NoOfRows('tab1');
```

## 8.27 Trigonometric and hyperbolic functions

This section describes functions for performing trigonometric and hyperbolic operations. In all of the functions, the arguments are expressions resolving to angles measured in radians, where **x** should be interpreted as a real number.

All angles are measured in radians.

All functions can be used in both the data load script and in chart expressions.

### cos

Cosine of **x**. The result is a number between -1 and 1.

```
cos ( x )
```

### acos

Inverse cosine of **x**. The function is only defined if  $-1 \leq x \leq 1$ . The result is a number between 0 and  $\pi$ .

```
acos ( x )
```

### sin

Sine of **x**. The result is a number between -1 and 1.

```
sin ( x )
```

### asin

Inverse sine of **x**. The function is only defined if  $-1 \leq x \leq 1$ . The result is a number between  $-\pi/2$  and  $\pi/2$ .

```
asin( x )
```

### **tan**

Tangent of **x**. The result is a real number.

```
tan( x )
```

### **atan**

Inverse tangent of **x**. The result is a number between  $-\pi/2$  and  $\pi/2$ .

```
atan( x )
```

### **atan2**

Two-dimensional generalization of the inverse tangent function. Returns the angle between the origin and the point represented by the coordinates **x** and **y**. The result is a number between  $-\pi$  and  $+\pi$ .

```
atan2( y, x )
```

### **cosh**

Hyperbolic cosine of **x**. The result is a positive real number.

```
cosh( x )
```

### **sinh**

Hyperbolic sine of **x**. The result is a real number.

```
sinh( x )
```

### **tanh**

Hyperbolic tangent of **x**. The result is a real number.

```
tanh( x )
```

### **acosh**

Inverse hyperbolic cosine of **x**. The result is a positive real number.

```
acosh( x )
```

### **asinh**

Inverse hyperbolic sine of **x**. The result is a real number.

```
asinh( x )
```

### **atanh**

Inverse hyperbolic tangent of **x**. The result is a real number.

```
atanh( x )
```

### **Examples:**

The following script code loads a sample table, and then loads a table containing the calculated trigonometric and hyperbolic operations on the values.

```
SampleData:
LOAD * Inline
[Value
-1
0
1];
```

```
Results:
Load *,
cos(Value),
acos(Value),
sin(Value),
asin(Value),
tan(Value),
atan(Value),
atan2(Value, Value),
cosh(Value),
sinh(Value),
tanh(Value)
RESIDENT SampleData;
```

```
Drop Table SampleData;
```

### 8.28 Window functions

Window functions perform calculations using values from multiple rows to produce a value for each row separately. Window functions can only be calculated once the entire table is read.

You can use window functions to perform operations such as:

- Comparing an individual number value in a row with the average, maximum, or minimum within the column.
- Calculating the rank of an individual value, either within the column or within the entire table.

Window functions do not change the number of records in the table but can perform similar tasks as aggregation functions or relational functions and range functions.

Each function is described further after the overview. You can also click the function name in the syntax to immediately access the details for that specific function.

#### **Window**

The **Window** function performs calculations from multiple rows, producing a value for each row separately.

```
Window - script function(input_expr, [partition1, partition2, ...], [sort_type, [sort_expr]], [filter_expr], [start_expr, end_expr]) [row_window_size]
```

#### **WRank**

The **WRank** function performs ranking calculations inside **Window**.

```
WRank - script function([TOTAL] expr[, mode[, fmt]])
```

### Window - script function

**Window()** performs calculations from multiple rows, producing a value for each row separately.

You can use the **Window** functions to perform operations such as:

- Comparing an individual number value in a row with the average, maximum, or minimum within the column.
- Calculating the rank of an individual value, either within the column or within the entire table.

The **Window** function does not change the number of records in the table but it can still perform similar tasks as aggregation, relational, and range functions.

The **Window** function must have a cache within the LOAD statement of the table you are working with to add to the table. For example:

```
[Transactions]:
Load
    *,
    window(avg(Expression1),[Num]);
LOAD
    TransLineID,
    TransID,
    "Num",
    Dim1,
    Dim2,
    Dim3,
    Expression1,
    Expression2,
    Expression3
FROM [lib://AttachedFiles/transactions.qvd] (qvd);
```

Window supports general functions, such as rounding or basic numerical operations. For example:

```
Load *, Round(window(Sum(Salary),Department)) as Sumsalary
Load *, window(Sum(Salary),Department) + 5 as SumSalary
```

You can define a sliding window for the **Window** function. This sets the number of rows used when applying the **Window** function on the current row. For example, you could set the window to be the 3 previous rows and the 3 subsequent rows.

#### Syntax:


```
Window (input_expr, [partition1, partition2, ...], [sort_type, [sort_expr]],
[filter_expr], [start_expr,end_expr])
```

Return data type: A new field added to the resulting table created by the LOAD statement.

### Arguments:

#### Arguments

Argument	Description
input_expr	<p>The input expression calculated and returned by the function. It must be any expression based on an aggregation, such as <code>Median(Salary)</code>. For example:</p> <pre>Window(Median(Salary)) as MedianSalary</pre> <p>The input can also be a field name with no aggregation applied. In this case, <b>Window</b> treats it like the <b>Only()</b> function is applied to that field. For example:</p> <pre>Window(Salary,Department) as wSalary</pre> <p>Optionally, you can define partitioning with the input expression. Partitioning is the same as the grouping achieved by the <b>group by</b> clause, with the difference that the result is added as a new column to the input table. Partitioning does not reduce the number of records of the input table. Multiple partition fields can be defined.</p> <p>Example:</p> <pre>LOAD Window(Max(Sales), City, 'ASC', OrderDate, Sales &gt; 300) + AddMonths(OrderDate,-6) as MAX_Sales_City_Last_6_Mos, Window(Avg(Sales), City, 'ASC', OrderDate, City = 'Portland') + AddMonths(OrderDate,-6) as Avg_Sales_Portland_Last_6_Mos, Window(Max(Sales), City, 'ASC', OrderDate, Sales &gt; 300) + AddMonths(OrderDate,-12) as MAX_Sales_City_Last_12_Mos; LOAD     City,     Sales,     OrderDate FROM [lib://AttachedFiles/Sales Data.xlsx] (ooxml, embedded labels, table is [Sales Data]);</pre>
partition1, partition2	<p>After <code>input_expr</code>, you can define any number of partitions. Partitions are fields that define which combinations to apply the aggregations with. The aggregation is applied separately with each partition. For example:</p> <pre>Window(Avg(Salary), Unit, Department, Country) as AvgSalary</pre> <p>In the above, the partitions are <i>Unit</i>, <i>Department</i>, and <i>Country</i>.</p> <p>Partitions are not mandatory, but are required for proper windowing of fields.</p>

Argument	Description
sort_type, [sort_expr]]	<p>Optionally, specify the sort type and the sort expression. sort_type can have one of two values:</p> <ul style="list-style-type: none"> <li>• ASC: Ascending sorting.</li> <li>• DESC: Descending sort.</li> </ul> <p>If you define sort_type, you need to define a sorting expression. This is an expression that decides the order of the rows within a partition.</p> <p>For example:</p> <pre>Window(RecNo(), Department, 'ASC', Year)</pre> <p>In the above example, the results within the partition of sorted ascendingly by the Yearfield.</p> <div data-bbox="384 786 1386 920" style="border: 1px solid #ccc; padding: 10px; margin-top: 10px;">  <p><i>The sort type and sort expression are primarily only required with the <b>RecNo</b> and <b>WRank</b> functions.</i></p> </div>
filter_expr	<p>Optionally, add a filter expression. This is a Boolean expression that decides whether the record should be included in the calculation or not.</p> <p>This parameter can be omitted completely, and the result should be that there is no filter.</p> <p>For example:</p> <pre>Window(avg(Salary), Department, 'ASC', Age, EmployeeID=3 Or EmployeeID=7) as wAvgSalary) as wAvgSalaryIfEmpIs3or7</pre>

Argument	Description
[start_Expr,end_Expr]	<p>Optionally, set the argument for sliding window functionality. A sliding window requires two arguments:</p> <ul style="list-style-type: none"> <li>• Start expression: The number of rows prior to the current row to include in the window.</li> <li>• End expression: The number of rows after the current row to include in the window.</li> </ul> <p>For example, if you wanted to include the 3 preceding rows, the current row, and the next following row:</p> <pre>Window(concat(Text(Salary),'-'), Department, 'ASC', Age, Year&gt;0, -3, 1) as wSalaryDepartment</pre> <p>To indicate all preceding rows or all subsequent rows, you can use the <b>Unbounded()</b> function. For example, to include all preceding rows, the current row, and the following row:</p> <pre>Window(concat(Text(Salary),'-'), Department, 'ASC', Age, Year&gt;0, UNBOUNDED(), 1) as wSlidingSalaryDepartment</pre> <p>For example, to include the third row from the current row and all subsequent rows:</p> <pre>Window(concat(Text(Salary),'-'), Department, 'ASC', Age, Year&gt;0, 3, UNBOUNDED()) as wSlidingSalaryDepartment</pre>

### Example - Adding a field containing an aggregation

Example: Adding a field containing an aggregation

#### Load script

Create a new tab in the data load editor, and then load the following data as an inline load. Create the table below in Qlik Sense to see the results.

Transactions:

Load

\*,

```
Window(Avg(transaction_amount),customer_id) as AvgCustTransaction;
```

Load \* Inline [

```
transaction_id, transaction_date, transaction_amount, transaction_quantity, customer_id, size, color_code
```

```
3750, 20180830, 23.56, 2, 2038593, L, Red
```

```
3751, 20180907, 556.31, 6, 203521, M, Orange
```

```
3752, 20180916, 5.75, 1, 5646471, S, Blue
```

```
3753, 20180922, 125.00, 7, 3036491, L, Black
```



## 8 Script and chart functions

```
3754, 20180922, 484.21, 13, 049681, XS, Red
3756, 20180922, 59.18, 2, 2038593, M, Blue
3757, 20180923, 177.42, 21, 203521, XL, Black
3758, 20180924, 153.42, 14, 2038593, L, Red
3759, 20180925, 7.42, 5, 203521, M, Orange
3760, 20180925, 80.12, 18, 5646471, M, Blue
3761, 20180926, 3.42, 7, 3036491, XS, Black
3763, 20180926, 63.55, 12, 049681, S, Red
3763, 20180927, 177.56, 10, 2038593, L, Blue
3764, 20180927, 325.95, 8, 203521, XL, Black
];
```

### Results

Results for adding a field containing an aggregation

transacti on_id	transacti on_date	transacti on_ amount	transacti on_ quantity	custom er_id	size	color_ code	AvgCustTransa ction
3750	20180830	23.56	2	203859 3	L	Red	103.43
3751	20180907	556.31	6	203521	M	Orang e	266.775
3752	20180916	5.75	1	5646471	S	Blue	42.935
3753	20180922	125.00	7	3036491	L	Black	64.21
3754	20180922	484.21	13	049681	XS	Red	273.88
3756	20180922	59.18	2	203859 3	M	Blue	103.43
3757	20180923	177.42	21	203521	XL	Black	266.775
3758	20180924	153.42	14	203859 3	L	Red	103.43
3759	20180925	7.42	5	203521	M	Orang e	266.775
3760	20180925	80.12	18	5646471	M	Blue	42.935
3761	20180926	3.42	7	3036491	XS	Black	64.21
3763	20180926	63.55	12	049681	S	Red	273.88
3763	20180927	177.56	10	203859 3	L	Blue	103.43
3764	20180927	325.95	8	203521	XL	Black	266.775

### Example - Adding a field containing an aggregation filtered for specific values

Example: Adding a field containing an aggregation filtered for specific values

#### Load script

Create a new tab in the data load editor, and then load the following data as an inline load. Create the table below in Qlik Sense to see the results.

Transactions:

Load

\*,

window(Avg(transaction\_amount),customer\_id, color\_code = 'Blue') as AvgCustTransaction;

Load \* Inline [

transaction\_id, transaction\_date, transaction\_amount, transaction\_quantity, customer\_id, size, color\_code

```
3750, 20180830, 23.56, 2, 2038593, L, Red
3751, 20180907, 556.31, 6, 203521, M, Orange
3752, 20180916, 5.75, 1, 5646471, S, Blue
3753, 20180922, 125.00, 7, 3036491, L, Black
3754, 20180922, 484.21, 13, 049681, XS, Red
3756, 20180922, 59.18, 2, 2038593, M, Blue
3757, 20180923, 177.42, 21, 203521, XL, Black
3758, 20180924, 153.42, 14, 2038593, L, Red
3759, 20180925, 7.42, 5, 203521, M, Orange
3760, 20180925, 80.12, 18, 5646471, M, Blue
3761, 20180926, 3.42, 7, 3036491, XS, Black
3763, 20180926, 63.55, 12, 049681, S, Red
3763, 20180927, 177.56, 10, 2038593, L, Blue
3764, 20180927, 325.95, 8, 203521, XL, Black
];
```

#### Results

Results for adding ad field containing an aggregation filtered for specific values

transacti on_id	transacti on_date	transacti on_ amount	transacti on_ quantity	custom er_id	size	color_ code	AvgCustTransa ction
3750	20180830	23.56	2	203859 3	L	Red	-
3751	20180907	556.31	6	203521	M	Orang e	-
3752	20180916	5.75	1	5646471	S	Blue	42.94

transacti on_id	transacti on_date	transacti on_ amount	transacti on_ quantity	custom er_id	size	color_ code	AvgCustTransa ction
3753	20180922	125.00	7	3036491	L	Black	-
3754	20180922	484.21	13	049681	XS	Red	-
3756	20180922	59.18	2	203859 3	M	Blue	118.4
3757	20180923	177.42	21	203521	XL	Black	-
3758	20180924	153.42	14	203859 3	L	Red	-
3759	20180925	7.42	5	203521	M	Orang e	-
3760	20180925	80.12	18	5646471	M	Blue	42.94
3761	20180926	3.42	7	3036491	XS	Black	-
3763	20180926	63.55	12	049681	S	Red	-
3763	20180927	177.56	10	203859 3	L	Blue	118.4
3764	20180927	325.95	8	203521	XL	Black	-

### Example - Adding a field with a sliding window

Example: Adding a field with a sliding window

#### Load script

Create a new tab in the data load editor, and then load the following data as an inline load. Create the table below in Qlik Sense to see the results.

Transactions:

Load

\*,

Window(Avg(transaction\_amount),customer\_id, 'ASC', -1, 1, 0, 1) as AvgCustTransaction;

Load \* Inline [

transaction\_id, transaction\_date, transaction\_amount, transaction\_quantity, customer\_id, size, color\_code

3750, 20180830, 23.56, 2, 2038593, L, Red

3751, 20180907, 556.31, 6, 203521, M, Orange

3752, 20180916, 5.75, 1, 5646471, S, Blue

3753, 20180922, 125.00, 7, 3036491, L, Black

3754, 20180922, 484.21, 13, 049681, XS, Red

3756, 20180922, 59.18, 2, 2038593, M, Blue

3757, 20180923, 177.42, 21, 203521, XL, Black

3758, 20180924, 153.42, 14, 2038593, L, Red

```
3759, 20180925, 7.42, 5, 203521, M, Orange
3760, 20180925, 80.12, 18, 5646471, M, Blue
3761, 20180926, 3.42, 7, 3036491, XS, Black
3763, 20180926, 63.55, 12, 049681, S, Red
3763, 20180927, 177.56, 10, 2038593, L, Blue
3764, 20180927, 325.95, 8, 203521, XL, Black
];
```

### Results

Results for adding ad field containing an aggregation filtered for specific values

transacti on_id	transacti on_date	transacti on_ amount	transacti on_ quantity	custom er_id	size	color_ code	AvgCustTransa ction
3750	20180830	23.56	2	203859 3	L	Red	41.37
3751	20180907	556.31	6	203521	M	Orang e	366.865
3752	20180916	5.75	1	5646471	S	Blue	42.935
3753	20180922	125.00	7	3036491	L	Black	64.21
3754	20180922	484.21	13	049681	XS	Red	273.88
3756	20180922	59.18	2	203859 3	M	Blue	106.3
3757	20180923	177.42	21	203521	XL	Black	92.42
3758	20180924	153.42	14	203859 3	L	Red	165.49
3759	20180925	7.42	5	203521	M	Orang e	166.685
3760	20180925	80.12	18	5646471	M	Blue	80.12
3761	20180926	3.42	7	3036491	XS	Black	3.42
3763	20180926	63.55	12	049681	S	Red	177.56
3763	20180927	177.56	10	203859 3	L	Blue	63.55
3764	20180927	325.95	8	203521	XL	Black	325.95

### Limitations

**Window** has the following limitations:

- **Window** is a resource intensive function, particularly in terms of memory consumption.
- **Window** is not supported in Qlik Sense Mobile.

- Chart expressions do not support **Window**.
- You cannot nest **Window** functions inside other **Window** functions.
- **Window** cannot be used inside an aggregation function.
- **Window** needs to be able to scan the whole table.
- **WRank()**, **RecNo()**, and **RowNo()** cannot be used with **Window** when using the sliding window functionality.

### WRank - script function

**WRank()** evaluates the rows of a table in the load script, and for each row, displays the relative position of the value of the field evaluated in the load script. When evaluating the table, the function compares the result with the result of the other rows containing the current partition and returns the ranking of the current row within the segment.

#### Partitions in a table

	Region	Country	Population	Rank(Population)
Column segment #1	Americas	Mexico	128,932,753	2
	Americas	Canada	37,742,154	3
	Americas	United States of America	333,092,651	1
Column segment #2	Europe	Sweden	10,099,265	4
	Europe	United Kingdom	67,886,011	2
	Europe	France	65,273,511	3
	Europe	Germany	83,783,942	1

**WRank** can only be used in a **Window** function. The **Window** function must include a sorting type and sorting expression. The ranking is applied on the sorting expression.

#### Syntax:

```
WRank ([mode [, fmt ] ] )
```

**Return data type:** dual

#### Arguments:

##### Arguments

Argument	Description
mode	Optionally, specifies the number representation of the function result.
fmt	Optionally, specifies the text representation of the function result.
TOTAL	If the table is one-dimensional, or if the script is preceded by the <b>TOTAL</b> qualifier, the function is evaluated along the entire column. If the table or table equivalent has multiple vertical dimensions, the current partition will include only rows with the same values as the current row in all dimension columns except for the column showing the last dimension in the inter-field sort order.

The ranking is returned as a dual value, which in the case when each row has a unique ranking, is an integer between 1 and the number of rows in the current partition.

In the case where several rows share the same ranking, the text and number representation can be controlled with the **mode** and **fmt** parameters.

### mode

The first argument, **mode**, can take the following values:

**mode** values

Value	Description
0 (default)	<p>If all ranks within the sharing group fall on the low side of the middle value of the entire ranking, all rows get the lowest rank within the sharing group.</p> <p>If all ranks within the sharing group fall on the high side of the middle value of the entire ranking, all rows get the highest rank within the sharing group.</p> <p>If ranks within the sharing group span over the middle value of the entire ranking, all rows get the value corresponding to the average of the top and bottom ranking in the entire partition.</p>
1	Lowest rank on all rows.
2	Average rank on all rows.
3	Highest rank on all rows.
4	Lowest rank on first row, then incremented by one for each row.

### fmt

The second argument, **fmt**, can take the following values:

**fmt** values

Value	Description
0 (default)	Low value - high value on all rows (for example 3 - 4).
1	Low value on all rows.
2	Low value on first row, blank on the following rows.

The order of rows for **mode** 4 and **fmt** 2 is determined by the load order of the table fields.

### Example - Adding a ranked field

Example: Adding a ranked field

#### Load script

Create a new tab in the data load editor, and then load the following data as an inline load. Create the table below in Qlik Sense to see the results.

Transactions:

Load

\*,

## 8 Script and chart functions

```
Window(WRank(0),customer_id, 'Desc', transaction_amount) as TransactionRanking;
```

```
Load * Inline [  
transaction_id, transaction_date, transaction_amount, transaction_quantity, customer_id, size,  
color_code  
3750, 20180830, 23.56, 2, 2038593, L, Red  
3751, 20180907, 556.31, 6, 203521, M, Orange  
3752, 20180916, 5.75, 1, 5646471, S, Blue  
3753, 20180922, 125.00, 7, 3036491, L, Black  
3754, 20180922, 484.21, 13, 049681, XS, Red  
3756, 20180922, 59.18, 2, 2038593, M, Blue  
3757, 20180923, 177.42, 21, 203521, XL, Black  
3758, 20180924, 153.42, 14, 2038593, L, Red  
3759, 20180925, 7.42, 5, 203521, M, Orange  
3760, 20180925, 80.12, 18, 5646471, M, Blue  
3761, 20180926, 3.42, 7, 3036491, XS, Black  
3763, 20180926, 63.55, 12, 049681, S, Red  
3763, 20180927, 177.56, 10, 2038593, L, Blue  
3764, 20180927, 325.95, 8, 203521, XL, Black  
];
```

### Results

Results for adding a ranked field

transacti on_id	transacti on_date	transacti on_ amount	transacti on_ quantity	custom er_id	size	color_ code	TransactionRa nking
3750	20180830	23.56	2	203859 3	L	Red	4-4
3751	20180907	556.31	6	203521	M	Orange	1-1
3752	20180916	5.75	1	5646471	S	Blue	2-2
3754	20180922	484.21	13	049681	XS	Red	1-1
3756	20180922	59.18	2	203859 3	M	Blue	3-3
3753	20180922	125.00	7	3036491	L	Black	1-1
3757	20180923	177.42	21	203521	XL	Black	3-3
3758	20180924	153.42	14	203859 3	L	Red	2-2
3759	20180925	7.42	5	203521	M	Orange	4-4
3760	20180925	80.12	18	5646471	M	Blue	1-1
3763	20180926	63.55	12	049681	S	Red	2-2

transacti on_id	transacti on_date	transacti on_ amount	transacti on_ quantity	custom er_id	size	color_ code	TransactionRa nking
3761	20180926	3.42	7	3036491	XS	Black	2-2
3764	20180927	325.95	8	203521	XL	Black	2-2
3763	20180927	177.56	10	203859	L	Blue	1-1

### Example - Adding a ranked field using fmt for a single digit result

Example: Adding a ranked field using fmt for a single digit result

#### Load script

Create a new tab in the data load editor, and then load the following data as an inline load. Create the table below in Qlik Sense to see the results.

Transactions:

Load

```
*,window(WRank(0,1),customer_id, 'Desc', transaction_amount) as TransactionRanking;
```

Load \* Inline [

```
transaction_id, transaction_date, transaction_amount, transaction_quantity, customer_id, size, color_code
```

```
3750, 20180830, 23.56, 2, 2038593, L, Red
3751, 20180907, 556.31, 6, 203521, M, Orange
3752, 20180916, 5.75, 1, 5646471, S, Blue
3753, 20180922, 125.00, 7, 3036491, L, Black
3754, 20180922, 484.21, 13, 049681, XS, Red
3756, 20180922, 59.18, 2, 2038593, M, Blue
3757, 20180923, 177.42, 21, 203521, XL, Black
3758, 20180924, 153.42, 14, 2038593, L, Red
3759, 20180925, 7.42, 5, 203521, M, Orange
3760, 20180925, 80.12, 18, 5646471, M, Blue
3761, 20180926, 3.42, 7, 3036491, XS, Black
3763, 20180926, 63.55, 12, 049681, S, Red
3763, 20180927, 177.56, 10, 2038593, L, Blue
3764, 20180927, 325.95, 8, 203521, XL, Black
];
```

#### Results

Results for adding a ranked field using fmt for a single digit result

transacti on_id	transacti on_date	transacti on_ amount	transacti on_ quantity	custom er_id	size	color_ code	TransactionRa nking
3750	20180830	23.56	2	203859	L	Red	4



transacti on_id	transacti on_date	transacti on_ amount	transacti on_ quantity	custom er_id	size	color_ code	TransactionRa nking
				3			
3751	20180907	556.31	6	203521	M	Orang e	1
3752	20180916	5.75	1	5646471	S	Blue	2
3754	20180922	484.21	13	049681	XS	Red	1
3756	20180922	59.18	2	203859	M	Blue	3
				3			
3753	20180922	125.00	7	3036491	L	Black	1
3757	20180923	177.42	21	203521	XL	Black	3
3758	20180924	153.42	14	203859	L	Red	2
				3			
3759	20180925	7.42	5	203521	M	Orang e	4
3760	20180925	80.12	18	5646471	M	Blue	1
3763	20180926	63.55	12	049681	S	Red	2
3761	20180926	3.42	7	3036491	XS	Black	2
3764	20180927	325.95	8	203521	XL	Black	2
3763	20180927	177.56	10	203859	L	Blue	1
				3			

### Example - Adding a ranked field with multiple partitions

Example: Adding a ranked field with multiple partitions

#### Load script

Create a new tab in the data load editor, and then load the following data as an inline load. Create the table below in Qlik Sense to see the results.

Transactions:

Load

```
*,window(wRank(0,1),customer_id, size, color_code, 'Desc', transaction_amount) as  
TransactionRanking;
```

Load \* Inline [

```
transaction_id, transaction_date, transaction_amount, transaction_quantity, customer_id, size,  
color_code
```

```
3750, 20180830, 23.56, 2, 2038593, L, Red
```

```
3751, 20180907, 556.31, 6, 203521, M, Orange
```

```
3752, 20180916, 5.75, 1, 5646471, S, Blue
```

```

3753, 20180922, 125.00, 7, 3036491, L, Black
3754, 20180922, 484.21, 13, 049681, XS, Red
3756, 20180922, 59.18, 2, 2038593, M, Blue
3757, 20180923, 177.42, 21, 203521, XL, Black
3758, 20180924, 153.42, 14, 2038593, L, Red
3759, 20180925, 7.42, 5, 203521, M, Orange
3760, 20180925, 80.12, 18, 5646471, M, Blue
3761, 20180926, 3.42, 7, 3036491, XS, Black
3763, 20180926, 63.55, 12, 049681, S, Red
3763, 20180927, 177.56, 10, 2038593, L, Blue
3764, 20180927, 325.95, 8, 203521, XL, Black
];

```

### Results

Results for adding a ranked field using fmt for a single digit result

transacti on_id	transacti on_date	transacti on_ amount	transacti on_ quantity	custom er_id	size	color_ code	TransactionRa nking
3750	20180830	23.56	2	203859 3	L	Red	2
3751	20180907	556.31	6	203521	M	Orang e	1
3752	20180916	5.75	1	5646471	S	Blue	1
3754	20180922	484.21	13	049681	XS	Red	1
3756	20180922	59.18	2	203859 3	M	Blue	1
3753	20180922	125.00	7	3036491	L	Black	1
3757	20180923	177.42	21	203521	XL	Black	2
3758	20180924	153.42	14	203859 3	L	Red	1
3759	20180925	7.42	5	203521	M	Orang e	2
3760	20180925	80.12	18	5646471	M	Blue	1
3763	20180926	63.55	12	049681	S	Red	1
3761	20180926	3.42	7	3036491	XS	Black	1
3764	20180927	325.95	8	203521	XL	Black	1
3763	20180927	177.56	10	203859 3	L	Blue	1

### Limitations

WRank has the following limitations:

- If your fmt value is 0 and you want to use the text part of the dual result for **WRank**, you must use **Text()** with **Window(WRank)**. For example: `Text(window(WRank(0), unit, 'DESC', Age))` as `UnitWRankedByAgeText`.

## 9 File system access restriction

For security reasons, Qlik Sense in standard mode does not support paths in the data load script or functions and variables that expose the file system.

However, since file system paths were supported in QlikView, it is possible to disable standard mode and use legacy mode in order to reuse QlikView load scripts.



*Disabling standard mode can create a security risk by exposing the file system.*

*Disabling standard mode (page 1522)*

### 9.1 Security aspects when connecting to file based ODBC and OLE DB data connections

ODBC and OLE DB data connections using file-based drivers will expose the path to the connected data file in the connection string. The path can be exposed when the connection is edited, in the data selection dialog, or in certain SQL queries. This is the case both in standard mode and legacy mode.



*If exposing the path to the data file is a concern, it is recommended to connect to the data file using a folder data connection if it is possible.*

### 9.2 Limitations in standard mode

Several statements, variables and functions cannot be used or have limitations in standard mode. Using unsupported statements in the data load script produces an error when the load script runs. Error messages can be found in the script log file. Using unsupported variables and functions does not produce error messages or log file entries. Instead, the function returns NULL.

There is no indication that a variable, statement or function is unsupported when you are editing the data load script.

#### System variables

System variables

Variable	Standard mode	Legacy mode	Definition
Floppy	Not supported	Supported	Returns the drive letter of the first floppy drive found, normally a:.

## 9 File system access restriction

Variable	Standard mode	Legacy mode	Definition
CD	Not supported	Supported	Returns the drive letter of the first CD-ROM drive found. If no CD-ROM is found, then c: is returned.
QvPath	Not supported	Supported	Returns the browse string to the Qlik Sense executable.
QvRoot	Not supported	Supported	Returns the root directory of the Qlik Sense executable.
QvWorkPath	Not supported	Supported	Returns the browse string to the current Qlik Sense app.
QvWorkRoot	Not supported	Supported	Returns the root directory of the current Qlik Sense app.
WinPath	Not supported	Supported	Returns the browse string to Windows.
WinRoot	Not supported	Supported	Returns the root directory of Windows.
\$(include=...)	Supported input: Path using library connection	Supported input: Path using library connection or file system	The <b>Include/Must_Include</b> variable specifies a file that contains text that should be included in the script and evaluated as script code. It is not used to add data. You can store parts of your script code in a separate text file and reuse it in several apps. This is a user-defined variable.

### Regular script statements

Regular script statements

Statement	Standard mode	Legacy mode	Definition
Binary	Supported input: Path using library connection	Supported input: Path using library connection or file system	The <b>binary</b> statement is used for loading data from another app.
Connect	Supported input: Path using library connection	Supported input: Path using library connection or file system	The <b>CONNECT</b> statement is used to define Qlik Sense access to a general database through the OLE DB/ODBC interface. For ODBC, the data source first needs to be specified using the ODBC administrator.
Directory	Supported input: Path using library connection	Supported input: Path using library connection or file system	The <b>Directory</b> statement defines which directory to look in for data files in subsequent <b>LOAD</b> statements, until a new <b>Directory</b> statement is made.
Execute	Not supported	Supported input: Path using library connection or file system	The <b>Execute</b> statement is used to run other programs while Qlik Sense is loading data. For example, to make conversions that are necessary.

## 9 File system access restriction

Statement	Standard mode	Legacy mode	Definition
LOAD from ...	Supported input: Path using library connection	Supported input: Path using library connection or file system	The <b>LOAD</b> statement loads fields from a file, from data defined in the script, from a previously loaded table, from a web page, from the result of a subsequent <b>SELECT</b> statement or by generating data automatically.
Store into ...	Supported input: Path using library connection	Supported input: Path using library connection or file system	The <b>Store</b> statement creates a QVD, Parquet, CSV, or TXT file.

### Script control statements

#### Script control statements

Statement	Standard mode	Legacy mode	Definition
For each... filelist mask/dirlist mask	Supported input: Path using library connection  Returned output: Library connection	Supported input: Path using library connection or file system  Returned output: Library connection or file system path, depending on input	The filelist mask syntax produces a comma separated list of all files in the current directory matching the <b>filelist mask</b> . The <b>dirlist mask</b> syntax produces a comma separated list of all directories in the current directory matching the directory name mask.

### File functions

File functions

Function	Standard mode	Legacy mode	Definition
Attribute()	Supported input: Path using library connection	Supported input: Path using library connection or file system	Returns the value of the meta tags of different media files as text.
ConnectionString()	Returned output: Library connection name	Library connection name or actual connection, depending on input	Returns the active connect string for ODBC or OLE DB connections.
FileDir()	Returned output: Library connection	Returned output: Library connection or file system path, depending on input	The <b>FileDir</b> function returns a string containing the path to the directory of the table file currently being read.
FilePath()	Returned output: Library connection	Returned output: Library connection or file system path, depending on input	The <b>FilePath</b> function returns a string containing the full path to the table file currently being read.
FileSize()	Supported input: Path using library connection	Supported input: Path using library connection or file system	The <b>FileSize</b> function returns an integer containing the size in bytes of the file filename or, if no filename is specified, of the table file currently being read.
FileTime()	Supported input: Path using library connection	Supported input: Path using library connection or file system	The <b>FileTime</b> function returns a timestamp in UTC format of the last modification of a specified file. If a file is not specified, the function returns a timestamp in UTC of the last modification of the currently read table file.



## 9 File system access restriction

Function	Standard mode	Legacy mode	Definition
GetFolderPath()	Not supported	Returned output: Absolute path	The <b>GetFolderPath</b> function returns the value of the Microsoft Windows <i>SHGetFolderPath</i> function. This function takes as input the name of a Microsoft Windows folder and returns the full path of the folder.
QvdCreateTime()	Supported input: Path using library connection	Supported input: Path using library connection or file system	This script function returns the XML-header timestamp from a QVD file, if any is present, otherwise it returns NULL. In the timestamp, time is provided in UTC.
QvdFieldName()	Supported input: Path using library connection	Supported input: Path using library connection or file system	This script function returns the name of field number <b>fieldno</b> in a QVD file. If the field does not exist NULL is returned.
QvdNoOfFields()	Supported input: Path using library connection	Supported input: Path using library connection or file system	This script function returns the number of fields in a QVD file.
QvdNoOfRecords()	Supported input: Path using library connection	Supported input: Path using library connection or file system	This script function returns the number of records currently in a QVD file.
QvdTableName()	Supported input: Path using library connection	Supported input: Path using library connection or file system	This script function returns the name of the table stored in a QVD file.

## System functions

System functions

Function	Standard mode	Legacy mode	Definition
DocumentPath()	Not supported	Returned output: Absolute path	This function returns a string containing the full path to the current Qlik Sense app.
GetRegistryString()	Not supported	Supported	Returns the value of a named registry key with a given registry path. This function can be used in chart and script alike.

### 9.3 Disabling standard mode

You can disable standard mode, or in other words, set legacy mode, in order to reuse QlikView load scripts that refer to absolute or relative file paths as well as library connections.



*Disabling standard mode can create a security risk by exposing the file system.*

## Qlik Sense

For Qlik Sense, standard mode can be disabled in QMC using the **Standard mode** property.

## Qlik Sense Desktop

In Qlik Sense Desktop, you can set standard/legacy mode in *Settings.ini*.

If you installed Qlik Sense Desktop using the default installation location, *Settings.ini* is located in *C:\Users\{user}\Documents\Qlik\Sense\Settings.ini*. If you installed Qlik Sense Desktop to a folder that you selected, *Settings.ini* is located in the *Engine* folder of the installation path.

### Do the following:

1. Open *Settings.ini* in a text editor.
2. Change *StandardReload=1* to *StandardReload=0*.
3. Save the file and start Qlik Sense Desktop.

Qlik Sense Desktop now runs in legacy mode.

## Settings

The available settings for StandardReload are:

- 1 (standard mode)
- 0 (legacy mode)

## 10 Chart level scripting

When modifying chart data, you use a sub-set of the Qlik Sense script which consists of a number of statements. A statement can be either a regular script statement or a script control statement. Certain statements can be preceded by prefixes.

Regular statements are typically used for manipulating data in one way or another. These statements may be written over any number of lines in the script and must always be terminated by a semicolon, ";".

Control statements are typically used for controlling the flow of the script execution. Each clause of a control statement must be kept inside one script line and may be terminated by a semicolon or the end-of-line.

Prefixes may be applied to applicable regular statements but never to control statements.

All script keywords can be typed with any combination of lower case and upper case characters. Field and variable names used in the statements are however case sensitive.

In this section you can find an alphabetical listing of all script statements, control statements and prefixes available in the sub-set of the script used when modifying chart data.

### 10.1 Control statements

When modifying chart data, you use a sub-set of the Qlik Sense script which consists of a number of statements. A statement can be either a regular script statement or a script control statement.

Control statements are typically used for controlling the flow of the script execution. Each clause of a control statement must be kept inside one script line and may be terminated by semicolon or end-of-line.

Prefixes are never applied to control statements.

All script keywords can be typed with any combination of lower case and upper case characters.

#### Chart modifier control statements overview

Each function is described further after the overview. You can also click the function name in the syntax to immediately access the details for that specific function.

##### **Call**

The **call** control statement calls a subroutine which must be defined by a previous **sub** statement.

```
Call name ( [ paramlist ] )
```

##### **Do..loop**

The **do..loop** control statement is a script iteration construct which executes one or several statements until a logical condition is met.

```
Do..loop [ ( while | until ) condition ] [statements]
[exit do [ ( when | unless ) condition ] [statements]
loop [ ( while | until ) condition ]
```

### End

The **End** script keyword is used to close **If**, **Sub** and **Switch** clauses.

### Exit

The **Exit** script keyword is part of the **Exit Script** statement, but can also be used to exit **Do**, **For** or **Sub** clauses.

### Exit script

This control statement stops script execution. It may be inserted anywhere in the script.

```
Exit script[ (when | unless) condition ]
```

### For..next

The **for..next** control statement is a script iteration construct with a counter. The statements inside the loop enclosed by **for** and **next** will be executed for each value of the counter variable between specified low and high limits.

```
For..next counter = expr1 to expr2 [ stepexpr3 ]
[statements]
[exit for [ ( when | unless ) condition ]
[statements]
Next [counter]
```

### For each ..next

The **for each..next** control statement is a script iteration construct which executes one or several statements for each value in a comma separated list. The statements inside the loop enclosed by **for** and **next** will be executed for each value of the list.

```
For each..next var in list
[statements]
[exit for [ ( when | unless ) condition ]
[statements]
next [var]
```

### If..then

The **if..then** control statement is a script selection construct forcing the script execution to follow different paths depending on one or several logical conditions.



Since the **if..then** statement is a control statement and as such is ended with either a semicolon or end-of-line, each of its four possible clauses (**if..then**, **elseif..then**, **else** and **end if**) must not cross a line boundary.

```
If..then..elseif..else..end if condition then
[ statements ]
{ elseif condition then
```

```
[ statements ] }
[ else
  [ statements ] ]
end if
```

### Next

The **Next** script keyword is used to close **For** loops.

### Sub

The **sub..end sub** control statement defines a subroutine which can be called upon from a **call** statement.

```
Sub..end sub name [ ( paramlist )] statements end sub
```

### Switch

The **switch** control statement is a script selection construct forcing the script execution to follow different paths, depending on the value of an expression.

```
Switch..case..default..end switch expression {case valuelist [ statements ]}
[default statements] end switch
```

### To

The **To** script keyword is used in several script statements.

## Call

The **call** control statement calls a subroutine which must be defined by a previous **sub** statement.

### Syntax:

```
Call name ( [ paramlist ])
```

### Arguments:

Arguments

Argument	Description
name	The name of the subroutine.
paramlist	A comma separated list of the actual parameters to be sent to the subroutine. Each item in the list may be a field name, a variable or an arbitrary expression.

The subroutine called by a **call** statement must be defined by a **sub** encountered earlier during script execution.

Parameters are copied into the subroutine and, if the parameter in the **call** statement is a variable and not an expression, copied back out again upon exiting the subroutine.

### Limitations:

- Since the **call** statement is a control statement and as such is ended with either a semicolon or end-of-line, it must not cross a line boundary.
- When you define a subroutine with `sub . . end sub` inside a control statement, for example `if . . then`, you can only call the subroutine from within the same control statement.

### Do..loop

The **do..loop** control statement is a script iteration construct which executes one or several statements until a logical condition is met.

### Syntax:

```
Do [ ( while | until ) condition ] [statements]
[exit do [ ( when | unless ) condition ] [statements]
loop[ ( while | until ) condition ]
```



Since the **do..loop** statement is a control statement and as such is ended with either a semicolon or end-of-line, each of its three possible clauses (**do**, **exit do** and **loop**) must not cross a line boundary.

### Arguments:

#### Arguments

Argument	Description
condition	A logical expression evaluating to True or False.
statements	Any group of one or more Qlik Sense script statements.
while / until	The <b>while</b> or <b>until</b> conditional clause must only appear once in any <b>do..loop</b> statement, i.e. either after <b>do</b> or after <b>loop</b> . Each condition is interpreted only the first time it is encountered but is evaluated for every time it encountered in the loop.
exit do	If an <b>exit do</b> clause is encountered inside the loop, the execution of the script will be transferred to the first statement after the <b>loop</b> clause denoting the end of the loop. An <b>exit do</b> clause can be made conditional by the optional use of a <b>when</b> or <b>unless</b> suffix.

### End

The **End** script keyword is used to close **If**, **Sub** and **Switch** clauses.

## Exit

The **Exit** script keyword is part of the **Exit Script** statement, but can also be used to exit **Do**, **For** or **Sub** clauses.

## Exit script

This control statement stops script execution. It may be inserted anywhere in the script.

### Syntax:

```
Exit Script [ (when | unless) condition ]
```

Since the **exit script** statement is a control statement and as such is ended with either a semicolon or end-of-line, it must not cross a line boundary.

### Arguments:

Arguments

Argument	Description
condition	A logical expression evaluating to True or False.
when / unless	An <b>exit script</b> statement can be made conditional by the optional use of <b>when</b> or <b>unless</b> clause.

### Examples:

```
//Exit script
Exit Script;
```

```
//Exit script when a condition is fulfilled
Exit Script when a=1
```

## For..next

The **for..next** control statement is a script iteration construct with a counter. The statements inside the loop enclosed by **for** and **next** will be executed for each value of the counter variable between specified low and high limits.

### Syntax:

```
For counter = expr1 to expr2 [ step expr3 ]
[statements]
[exit for [ ( when | unless ) condition ]
[statements]
Next [counter]
```



The expressions *expr1*, *expr2* and *expr3* are only evaluated the first time the loop is entered. The value of the counter variable may be changed by statements inside the loop, but this is not good programming practice.

If an **exit for** clause is encountered inside the loop, the execution of the script will be transferred to the first statement after the **next** clause denoting the end of the loop. An **exit for** clause can be made conditional by the optional use of a **when** or **unless** suffix.



Since the **for..next** statement is a control statement and as such is ended with either a semicolon or end-of-line, each of its three possible clauses (**for..to..step**, **exit for** and **next**) must not cross a line boundary.

### Arguments:

Arguments

Argument	Description
counter	A variable name. If <i>counter</i> is specified after <b>next</b> it must be the same variable name as the one found after the corresponding <b>for</b> .
expr1	An expression which determines the first value of the <i>counter</i> variable for which the loop should be executed.
expr2	An expression which determines the last value of the <i>counter</i> variable for which the loop should be executed.
expr3	An expression which determines the value indicating the increment of the <i>counter</i> variable each time the loop has been executed.
condition	a logical expression evaluating to True or False.
statements	Any group of one or more Qlik Sense script statements.

### For each..next

The **for each..next** control statement is a script iteration construct which executes one or several statements for each value in a comma separated list. The statements inside the loop enclosed by **for** and **next** will be executed for each value of the list.

#### Syntax:

Special syntax makes it possible to generate lists with file and directory names in the current directory.

```
for each var in list
[statements]
[exit for [ ( when | unless ) condition ]
[statements]
next [var]
```

**Arguments:**

## Arguments

Argument	Description
var	A script variable name which will acquire a new value from list for each loop execution. If <b>var</b> is specified after <b>next</b> it must be the same variable name as the one found after the corresponding <b>for each</b> .

The value of the **var** variable may be changed by statements inside the loop, but this is not good programming practice.

If an **exit for** clause is encountered inside the loop, the execution of the script will be transferred to the first statement after the **next** clause denoting the end of the loop. An **exit for** clause can be made conditional by the optional use of a **when** or **unless** suffix.





Since the **for each..next** statement is a control statement and as such is ended with either a semicolon or end-of-line, each of its three possible clauses (**for each**, **exit for** and **next**) must not cross a line boundary.

**Syntax:**

```
list := item { , item }
item := constant | (expression) | filelist mask | dirlist mask |
fieldvaluelist mask
```

## Arguments

Argument	Description
constant	Any number or string. Note that a string written directly in the script must be enclosed by single quotes. A string without single quotes will be interpreted as a variable, and the value of the variable will be used. Numbers do not need to be enclosed by single quotes.
expression	An arbitrary expression.
mask	A filename or folder name mask which may include any valid filename characters as well as the standard wildcard characters, * and ?.  You can use absolute file paths or lib:// paths.
condition	A logical expression evaluating to True or False.
statements	Any group of one or more Qlik Sense script statements.

Argument	Description
filelist mask	This syntax produces a comma separated list of all files in the current directory matching the filename mask.   <i>This argument supports only library connections in standard mode.</i>
dirlist mask	This syntax produces a comma separated list of all folders in the current folder matching the folder name mask.   <i>This argument supports only library connections in standard mode.</i>
fieldvaluelist mask	This syntax iterates through the values of a field already loaded into Qlik Sense.



*The Qlik Web Storage Provider Connectors and other DataFiles connections do not support filter masks that use wildcard (\* and ?) characters.*

### Example 1: Loading a list of files

```
// LOAD the files 1.csv, 3.csv, 7.csv and xyz.csv
for each a in 1,3,7,'xyz'
  LOAD * from file$(a).csv;
next
```

### Example 2: Creating a list of files on disk

This example loads a list of all Qlik Sense related files in a folder.

```
sub DoDir (Root)
  for each Ext in 'qvw', 'qva', 'qvo', 'qvs', 'qvc', 'qvf', 'qvd'

    for each File in filelist (Root&'/*.' &Ext)

      LOAD
        '$(File)' as Name,
        FileSize( '$(File)' ) as Size,
        FileTime( '$(File)' ) as FileTime
      autogenerate 1;

    next File

  next Ext
  for each Dir in dirlist (Root&'/*' )

    call DoDir (Dir)

  next Dir
```

```
end sub
```

```
call DoDir ('lib://DataFiles')
```

### Example 3: Iterating through a the values of a field

This example iterates through the list of loaded values of FIELD and generates a new field, NEWFIELD. For each value of FIELD, two NEWFIELD records will be created.

```
Load * inline [
FIELD
one
two
three
];
```

```
FOR Each a in FieldValueList('FIELD')
LOAD '$(a)' &'-'&RecNo() as NEWFIELD AutoGenerate 2;
NEXT a
```

The resulting table looks like this:

Example table

NEWFIELD
one-1
one-2
two-1
two-2
three-1
three-2

## If..then..elseif..else..end if

The **if..then** control statement is a script selection construct forcing the script execution to follow different paths depending on one or several logical conditions.

Control statements are typically used to control the flow of the script execution. In a chart expression, use the **if** conditional function instead.

### Syntax:

```
If condition then
  [ statements ]
{ elseif condition then
  [ statements ] }
[ else
  [ statements ] ]
end if
```

Since the **if..then** statement is a control statement and as such is ended with either a semicolon or end-of-line, each of its four possible clauses (**if..then**, **elseif..then**, **else** and **end if**) must not cross a line boundary.

### Arguments:

#### Arguments

Argument	Description
condition	A logical expression which can be evaluated as True or False.
statements	Any group of one or more Qlik Sense script statements.

### Example 1:

```
if a=1 then
    LOAD * from abc.csv;
    SQL SELECT e, f, g from tab1;
end if
```

### Example 2:

```
if a=1 then; drop table xyz; end if;
```

### Example 3:

```
if x>0 then
    LOAD * from pos.csv;
elseif x<0 then
    LOAD * from neg.csv;
else
    LOAD * from zero.txt;
end if
```

## Next

The **Next** script keyword is used to close **For** loops.

## Sub..end sub

The **sub..end sub** control statement defines a subroutine which can be called upon from a **call** statement.

### Syntax:

```
Sub name [ ( paramlist ) ] statements end sub
```

Arguments are copied into the subroutine and, if the corresponding actual parameter in the **call** statement is a variable name, copied back out again upon exiting the subroutine.

If a subroutine has more formal parameters than actual parameters passed by a **call** statement, the extra parameters will be initialized to NULL and can be used as local variables within the subroutine.

### Arguments:

Arguments

Argument	Description
name	The name of the subroutine.
paramlist	A comma separated list of variable names for the formal parameters of the subroutine. These can be used as any variable inside the subroutine.
statements	Any group of one or more Qlik Sense script statements.

### Limitations:

- Since the **sub** statement is a control statement and as such is ended with either a semicolon or end-of-line, each of its two clauses (**sub** and **end sub**) must not cross a line boundary.
- When you define a subroutine with `sub..end sub` inside a control statement, for example `if..then`, you can only call the subroutine from within the same control statement.

### Example 1:

```
Sub INCR (I,J)
I = I + 1
Exit Sub when I < 10
J = J + 1
End Sub
Call INCR (X,Y)
```

### Example 2: - parameter transfer

```
Sub ParTrans (A,B,C)
A=A+1
B=B+1
C=C+1
End Sub
A=1
X=1
C=1
Call ParTrans (A, (X+1)*2)
```

The result of the above will be that locally, inside the subroutine, A will be initialized to 1, B will be initialized to 4 and C will be initialized to NULL.

When exiting the subroutine, the global variable A will get 2 as value (copied back from subroutine). The second actual parameter "(X+1)\*2" will not be copied back since it is not a variable. Finally, the global variable C will not be affected by the subroutine call.

## Switch..case..default..end switch

The **switch** control statement is a script selection construct forcing the script execution to follow different paths, depending on the value of an expression.

### Syntax:

```
Switch expression {case valuelist [ statements ]} [default statements] end
switch
```



Since the **switch** statement is a control statement and as such is ended with either a semicolon or end-of-line, each of its four possible clauses (**switch**, **case**, **default** and **end switch**) must not cross a line boundary.

### Arguments:

#### Arguments

Argument	Description
expression	An arbitrary expression.
valuelist	A comma separated list of values with which the value of expression will be compared. Execution of the script will continue with the statements in the first group encountered with a value in valuelist equal to the value in expression. Each value in valuelist may be an arbitrary expression. If no match is found in any <b>case</b> clause, the statements under the <b>default</b> clause, if specified, will be executed.
statements	Any group of one or more Qlik Sense script statements.

### Example:

```
Switch I
Case 1
LOAD '$(I): CASE 1' as case autogenerate 1;
Case 2
LOAD '$(I): CASE 2' as case autogenerate 1;
Default
LOAD '$(I): DEFAULT' as case autogenerate 1;
End Switch
```

## To

The **To** script keyword is used in several script statements.

## 10.2 Prefixes

Prefixes may be applied to applicable regular statements but never to control statements.

All script keywords can be typed with any combination of lower case and upper case characters. Field and variable names used in the statements are however case sensitive.

## Chart modifier prefixes overview

Each function is described further after the overview. You can also click the function name in the syntax to immediately access the details for that specific function.

### Add

The **Add** prefix can be added to any **LOAD** or **SELECT** statement in the script to specify that it should add records to another table. It also specifies that this statement should be run in a partial reload. The **Add** prefix can also be used in a **Map** statement.

```
Add [only] [Concatenate[(tablename)]] (loadstatement | selectstatement)
Add [ Only ] mapstatement
```

### Replace

The **Replace** prefix can be added to any **LOAD** or **SELECT** statement in the script to specify that the loaded table should replace another table. It also specifies that this statement should be run in a partial reload. The **Replace** prefix can also be used in a **Map** statement.

```
Replace [only] [Concatenate[(tablename)]] (loadstatement | selectstatement)
Replace [only] mapstatement
```

## Add

In a chart modifying context, the **Add** prefix is used with **LOAD** to append values to the *HC1* table, representing the hypercube computed by the Qlik associative engine. You can specify one or several columns. Missing values are automatically filled by the Qlik associative engine.

### Syntax:

```
Add loadstatement
```

### Example:

This example adds two rows to the columns *Dates* and *Sales* from the inline statement

```
Add Load
x as Dates,
y as Sales
Inline
[
Dates,Sales
2001/09/1,1000
2001/09/10,-300
]
```

## Replace

In a chart modifying context, the **Replace** prefix changes all values of the *HC1* table with a computed value defined by the script.

### Syntax:

```
Replace loadstatement
```



**Example:**

This example overwrites all values in column *z* with the sum of *x* and *y*.

```
Replace Load
x+y as z
Resident HC1;
```

## 10.3 Regular statements

Regular statements are typically used for manipulating data in one way or another. These statements may be written over any number of lines in the script and must always be terminated by a semicolon, ";".

All script keywords can be typed with any combination of lower case and upper case characters. Field and variable names used in the statements are however case sensitive.

### Chart modifier regular statements overview

Each function is described further after the overview. You can also click the function name in the syntax to immediately access the details for that specific function.

**LOAD**

In a chart modifying context, the **LOAD** statement loads additional data to the hypercube from data defined in the script, or from a previously loaded table. It is also possible to load data from analytic connections.



*The **LOAD** statement must have either **Replace** or **Add** prefix, or it will be rejected.*

```
Add | Replace Load [ distinct ] fieldlist
(
inline data [ format-spec ] |
resident table-label
) | extension pluginname.functionname([script] tabledescription)
[ where criterion | while criterion ]
[ group by groupbyfieldlist ]
[order by orderbyfieldlist ]
```

**Let**

The **let** statement is a complement to the **set** statement, used for defining script variables. The **let** statement, in opposition to the **set** statement, evaluates the expression on the right side of the '=' at script run time before it is assigned to the variable.

```
Let variablename=expression
```

### Set

The **set** statement is used for defining script variables. These can be used for substituting strings, paths, drives, and so on.

```
Set variablename=string
```

### Put

The **Put** statement is used to set some numeric value in the hypercube.

### HCValue

The **HCValue** statement is used to retrieve values in a row of a specified column.

## Load

In a chart modifying context, the **LOAD** statement loads additional data to the hypercube from data defined in the script, or from a previously loaded table. It is also possible to load data from analytic connections.



*The **LOAD** statement must have either **Replace** or **Add** prefix, or it will be rejected.*

### Syntax:

```
Add | Replace LOAD fieldlist
(
inline data [ format-spec ] |
resident table-label
) | extension pluginname.functionname([script] tabledescription)
[ where criterion | while criterion ]
[ group by groupbyfieldlist ]
[ order by orderbyfieldlist ]
```

**Arguments:**

## Arguments

Argument	Description
fieldlist	<p><i>fieldlist</i> ::= ( *   <i>field</i>{, *   <i>field</i> } )</p> <p>A list of the fields to be loaded. Using * as a field list indicates all fields in the table.</p> <p><i>field</i> ::= ( <i>fieldref</i>   <i>expression</i> ) [<b>as</b> <i>aliasname</i> ]</p> <p>The field definition must always contain a literal, a reference to an existing field, or an expression.</p> <p><i>fieldref</i> ::= ( <i>fieldname</i>   @<i>fieldnumber</i>   @<i>startpos:endpos</i> [ <b>I</b>   <b>U</b>   <b>R</b>   <b>B</b>   <b>T</b> ] )</p> <p><i>fieldname</i> is a text that is identical to a field name in the table. Note that the field name must be enclosed by straight double quotation marks or square brackets if it contains e.g. spaces. Sometimes field names are not explicitly available. Then a different notation is used:</p> <p>@<i>fieldnumber</i> represents the field number in a delimited table file. It must be a positive integer preceded by "@". The numbering is always made from 1 and up to the number of fields.</p> <p>@<i>startpos:endpos</i> represents the start and end positions of a field in a file with fixed length records. The positions must both be positive integers. The two numbers must be preceded by "@" and separated by a colon. The numbering is always made from 1 and up to the number of positions. In the last field, <b>n</b> is used as end position.</p> <ul style="list-style-type: none"> <li>• If @<i>startpos:endpos</i> is immediately followed by the characters <b>I</b> or <b>U</b>, the bytes read will be interpreted as a binary signed (<b>I</b>) or unsigned (<b>U</b>) integer (Intel byte order). The number of positions read must be 1, 2 or 4.</li> <li>• If @<i>startpos:endpos</i> is immediately followed by the character <b>R</b>, the bytes read will be interpreted as a binary real number (IEEE 32-bit or 64 bit floating point). The number of positions read must be 4 or 8.</li> <li>• If @<i>startpos:endpos</i> is immediately followed by the character <b>B</b>, the bytes read will be interpreted as a BCD (Binary Coded Decimal) numbers according to the COMP-3 standard. Any number of bytes may be specified.</li> </ul> <p><i>expression</i> can be a numeric function or a string function based on one or several other fields in the same table. For further information, see the syntax of expressions.</p> <p><b>as</b> is used for assigning a new name to the field.</p>

Argument	Description
inline	<p><b>inline</b> is used if data should be typed within the script, and not loaded from a file.</p> <p><i>data ::= [ text ]</i></p> <p>Data entered through an <b>inline</b> clause must be enclosed by double quotation marks or by square brackets. The text between these is interpreted in the same way as the content of a file. Hence, where you would insert a new line in a text file, you should also do it in the text of an <b>inline</b> clause, i.e. by pressing the Enter key when typing the script. The number of columns are defined by the first line.</p> <p><i>format-spec ::= ( fspec-item {, fspec-item } )</i></p> <p>The format specification consists of a list of several format specification items, within brackets. For more information, see <i>Format specification items</i> (page 165).</p>
resident	<p><b>resident</b> is used if data should be loaded from a previously loaded table. <i>table label</i> is a label preceding the <b>LOAD</b> statement that created the original table. The label should be given with a colon at the end.</p>

Argument	Description
extension	<p>You can load data from analytic connections. You need to use the <b>extension</b> clause to call a function defined in the server-side extension (SSE) plugin, or evaluate a script.</p> <p>You can send a single table to the SSE plugin, and a single data table is returned. If the plugin does not specify the names of the fields that are returned, the fields will be named Field1, Field2, and so on.</p> <pre data-bbox="475 566 1390 600">Extension pluginname.functionname( tabledescription );</pre> <ul data-bbox="528 611 1369 797" style="list-style-type: none"> <li>• Loading data using a function in an SSE plugin <i>tabledescription ::= (table { ,tablefield} )</i> If you do not state table fields, the fields will be used in load order.</li> <li>• Loading data by evaluating a script in an SSE plugin <i>tabledescription ::= ( script, table { ,tablefield} )</i></li> </ul> <p><b>Data type handling in the table field definition</b></p> <p>Data types are automatically detected in analytic connections. If the data has no numeric values and at least one non-NULL text string, the field is considered as text. In any other case it is considered as numeric.</p> <p>You can force the data type by wrapping a field name with <b>String()</b> or <b>Mixed()</b>.</p> <ul data-bbox="528 1137 1353 1290" style="list-style-type: none"> <li>• <b>String()</b> forces the field to be text. If the field is numeric, the text part of the dual value is extracted, there is no conversion performed.</li> <li>• <b>Mixed()</b> forces the field to be dual.</li> </ul> <p><b>String()</b> or <b>Mixed()</b> cannot be used outside <b>extension</b> table field definitions, and you cannot use other Qlik Sense functions in a table field definition.</p>
where	<p><b>where</b> is a clause used for stating whether a record should be included in the selection or not. The selection is included if <i>criterion</i> is True. <i>criterion</i> is a logical expression.</p>
while	<p><b>while</b> is a clause used for stating whether a record should be repeatedly read. The same record is read as long as <i>criterion</i> is True. In order to be useful, a <b>while</b> clause must typically include the <b>IterNo( )</b> function. <i>criterion</i> is a logical expression.</p>

Argument	Description
group by	<p><b>group by</b> is a clause used for defining over which fields the data should be aggregated (grouped). The aggregation fields should be included in some way in the expressions loaded. No other fields than the aggregation fields may be used outside aggregation functions in the loaded expressions.</p> <p><i>groupbyfieldlist ::= (fieldname { ,fieldname } )</i></p>
order by	<p><b>order by</b> is a clause used for sorting the records of a resident table before they are processed by the <b>load</b> statement. The resident table can be sorted by one or more fields in ascending or descending order. The sorting is made primarily by numeric value and secondarily by national collation order. This clause may only be used when the data source is a resident table.</p> <p>The ordering fields specify which field the resident table is sorted by. The field can be specified by its name or by its number in the resident table (the first field is number 1).</p> <p><i>orderbyfieldlist ::= fieldname [ sortorder ] { , fieldname [ sortorder ] }</i></p> <p><i>sortorder</i> is either <i>asc</i> for ascending or <i>desc</i> for descending. If no <i>sortorder</i> is specified, <i>asc</i> is assumed.</p> <p><i>fieldname, path, filename</i> and <i>aliasname</i> are text strings representing what the respective names imply. Any field in the source table can be used as <i>fieldname</i>. However, fields created through the <i>as</i> clause (<i>aliasname</i>) are out of scope and cannot be used inside the same <b>load</b> statement.</p>

## Let

The **let** statement is a complement to the **set** statement, used for defining script variables. The **let** statement, in opposition to the **set** statement, evaluates the expression on the right side of the '=' at script run time before it is assigned to the variable.

### Syntax:

```
Let variablename=expression
```

Examples and results:

Example	Result
<pre>Set x=3+4; Let y=3+4; z=\$(y)+1;</pre>	<p>\$(x) will be evaluated as ' 3+4 '</p> <p>\$(y) will be evaluated as ' 7 '</p> <p>\$(z) will be evaluated as ' 8 '</p> <p>Note the difference between the <b>Set</b> and <b>Let</b> statements. The <b>Set</b> statement assigns the string '3+4' to the variable whereas the <b>Let</b> statement evaluates the string and assigns 7 to the variable.</p>
<pre>Let T=now();</pre>	<p>\$(T) will be given the value of the current time.</p>

## Set

The **set** statement is used for defining script variables. These can be used for substituting strings, paths, drives, and so on.

### Syntax:

```
Set variablename=string
```

#### Example 1:

```
Set FileToUse=Data1.csv;
```

#### Example 2:

```
Set Constant="My string";
```

#### Example 3:

```
Set BudgetYear=2012;
```

## Put

The **put** statement is used to set some numeric value in the hypercube.

Access to the columns can be done by labels. You can also access columns and rows by declaration order. See the examples below for more details.

### Syntax:

```
put column(position)=value
```

#### Example 1:

Access to the columns can be done by labels.

This example will set a value of 1 in the first position of the column labeled *Sales*.

```
Put sales(1) = 1;
```

### Example 2:

You can access measure columns by declaration order using the `#hc1.measure` format for measures.

This example will set the value 1000 in the tenth position of the final sorted hypercube.

```
Put #hc1.measure.2(10) = 1000;
```

### Example 3:

You can access the dimension rows by declaration order using the `#hc1.dimension` format for dimensions.

This example puts the value of the constant Pi in the fifth row of the third declared dimension.

```
Put #hc1.dimension.3(5) = Pi();
```



*If there are no such dimensions or expressions, in value or labels, an error is returned indicating that the column was not found. If the index for the column is out of bounds, no error is displayed.*

## HCValue

The **HCValue** function is used to retrieve values in a row of a specified column.

### Syntax:

```
HCValue(column, position)
```

### Example 1:

This example returns the value at the first position of the column with label 'Sales'.

```
HCValue(Sales,1)
```

### Example 2:

This example returns the value at the tenth position of the sorted hypercube.

```
HCValue(#hc1.measure2,10)
```

### Example 3:

This example returns the value at the fifth row in the third dimension.

```
HCValue(#hc1.dimension.3,5)
```





*If there are no such dimensions or expressions, in value or labels, an error is returned indicating that the column was not found. If the index for the column is out of bounds, NULL is returned.*

# 11 QlikView functions and statements not supported in Qlik Sense

Most functions and statements that can be used in QlikView load scripts and chart expressions are also supported in Qlik Sense, but there are some exceptions, as described here.

## 11.1 Script statements not supported in Qlik Sense

QlikView script statements that are not supported in Qlik Sense

Statement	Comments
Command	Use <b>SQL</b> instead.
InputField	

## 11.2 Functions not supported in Qlik Sense

This list describes QlikView script and chart functions that are not supported in Qlik Sense.

- **GetCurrentField**
- **GetExtendedProperty**
- **Input**
- **InputAvg**
- **InputSum**
- **MsgBox**
- **NoOfReports**
- **ReportComment**
- **ReportId**
- **ReportName**
- **ReportNumber**

## 11.3 Prefixes not supported in Qlik Sense

This list describes QlikView prefixes that are not supported in Qlik Sense.

- **Bundle**
- **Image\_Size**
- **Info**

# 12 Functions and statements not recommended in Qlik Sense

Most functions and statements that can be used in QlikView load scripts and chart expressions are also supported in Qlik Sense, but some of them are not recommended for use in Qlik Sense. There are also functions and statements available in previous versions of Qlik Sense that have been deprecated.

For compatibility reasons they will still work as intended, but it is advisable to update the code according to the recommendations in this section, as they may be removed in coming versions.

## 12.1 Script statements not recommended in Qlik Sense

This table contains script statements that are not recommended for use in Qlik Sense.

Script statements that are not recommended

Statement	Recommendation
Command	Use <b>SQL</b> instead.
CustomConnect	Use <b>Custom Connect</b> instead.

## 12.2 Script statement parameters not recommended in Qlik Sense

This table describes script statement parameters that are not recommended for use in Qlik Sense.

Script statement parameters that are not recommended

Statement	Parameters
Buffer	Use <b>Incremental</b> instead of: <ul style="list-style-type: none"><li>• <b>Inc</b> (not recommended)</li><li>• <b>Incr</b> (not recommended)</li></ul>

## 12 Functions and statements not recommended in Qlik Sense

---

Statement	Parameters
<b>LOAD</b>	<p>The following parameter keywords are generated by QlikView file transformation wizards. Functionality is retained when data is reloaded, but Qlik Sense does not provide guided support/wizards for generating the statement with these parameters:</p> <ul style="list-style-type: none"><li>• <b>Bottom</b></li><li>• <b>Cellvalue</b></li><li>• <b>Col</b></li><li>• <b>Colmatch</b></li><li>• <b>Colsplit</b></li><li>• <b>Colxtr</b></li><li>• <b>Compound</b></li><li>• <b>Contain</b></li><li>• <b>Equal</b></li><li>• <b>Every</b></li><li>• <b>Expand</b></li><li>• <b>Filters</b></li><li>• <b>Intarray</b></li><li>• <b>Interpret</b></li><li>• <b>Length</b></li><li>• <b>Longer</b></li><li>• <b>Numerical</b></li><li>• <b>Pos</b></li><li>• <b>Remove</b></li><li>• <b>Rotate</b></li><li>• <b>Row</b></li><li>• <b>Rowcnd</b></li><li>• <b>Shorter</b></li><li>• <b>Start</b></li><li>• <b>Strcnd</b></li><li>• <b>Top</b></li><li>• <b>Transpose</b></li><li>• <b>Unwrap</b></li><li>• <b>XML: XMLSAX and Pattern is Path</b></li></ul>

### 12.3 Functions not recommended in Qlik Sense

This table describes script and chart functions that are not recommended for use in Qlik Sense.

## 12 Functions and statements not recommended in Qlik Sense

---

### Functions that are not recommended

Function	Recommendation
<b>NumAvg</b>	Use Range functions instead.
<b>NumCount</b>	<i>Range functions (page 1334)</i>
<b>NumMax</b>	
<b>NumMin</b>	
<b>NumSum</b>	
<b>Color()</b>	Use other color functions instead. <b>QliktechBlue()</b> can be replaced by <b>RGB(8, 18, 90)</b> and <b>QliktechGray</b> can be replaced by <b>RGB(158, 148, 137)</b> to get the same colors.
<b>QliktechBlue</b>	
<b>QliktechGray</b>	<i>Color functions (page 555)</i>
<b>QlikViewVersion</b>	Use <b>EngineVersion</b> instead. <i>EngineVersion (page 1485)</i>
<b>ProductVersion</b>	Use <b>EngineVersion</b> instead. <i>EngineVersion (page 1485)</i>
<b>QVUser</b>	
<b>Year2Date</b>	Use <b>YearToDate</b> instead.
<b>Vrank</b>	Use <b>Rank</b> instead.
<b>WildMatch5</b>	Use <b>WildMatch</b> instead.

### ALL qualifier

In QlikView, the **ALL** qualifier may occur before an expression. This is equivalent to using **{1}** **TOTAL**. In such a case the calculation will be made over all the values of the field in the document, disregarding the chart dimensions and current selections. The same value is always returned regardless of the logical state in the document. If the **ALL** qualifier is used, a set expression cannot be used, since the **ALL** qualifier defines a set by itself. For legacy reasons, the **ALL** qualifier will still work in this version of Qlik Sense, but may be removed in coming versions.